### HISTORY OF ISLAM III

## VOLUME 3

The Eastern Islamic World Eleventh to Eighteenth Centuries

Edited by

DAVID O. MORGAN

and

ANTHONY REID

m

Cambridge

**UNIVERSITY PRESS** 

Cambridge Histories Online © Cambridge University Press, 201 1

THE NEW CAMBRIDGE HISTORY OF

**ISLAM** 

VOLUME 3

The Eastern Islamic World Eleventh to Eighteenth Centuries

Volume 3 of The New Cambridge History of Islam traces the second great expansion of the Islamic world eastwards from the eleventh century to the eighteenth. As the faith crossed new cultural boun daries, the trader and the mystic assumed as great an importance as the soldier and the administrator. Distinctive Islamic idioms began

to emerge from other great linguistic traditions apart from Arabic, especially in Turkish, Persian, Urdu, Swahili, Malay and Chinese. The Islamic world transformed and absorbed new, vital influences. As the essays in this collection demonstrate, three major features distinguish the time and place both from the earlier experience of Islam and from the universal modernity of the nineteenth and twentieth centuries. First, the steppe tribal peoples of Central Asia, many Turkic, had a decisive impact on the Islamic lands. Second, Islam expanded along the trade routes of the Indian Ocean and the South China Sea, in a quite different manner from the conquests of the heroic age. And, third, Islam interacted with Asian spirituality, including forms we today label Hinduism, Jainism, Sikhism, Buddhism, Taoism and Shamanism. It was during this period, and through exploration across land and sea, that Islam became a truly world religion.

David O. Morgan is Professor Emeritus of History and Religious Studies in the Department of History, University of Wisconsin Madison. He is the author of The Mongols (2nd edition, 2007) and Medieval Persia 1040 1797 (1988), and is General Editor of Cambridge Studies in Islamic Civilization.

Anthony Reid, formerly Director, Asia Research Institute and Professor in the Department of History at the National University of Singapore, is currently Professor Emeritus at the Australian National University, Canberra. His recent books include Southeast Asia in the Age of Commerce (2 vols., 1988 93), Charting the Shape of Early Modern Southeast Asia (1999), An Indonesian Frontier: Acehnese and Other Histories of Sumatra (2004) and Imperial Alchemy: Nationalism

and Political Identity in Southeast Asia (2010).

Cambridge Histories Online © Cambridge University Press, 201 1

THE NEW CAMBRIDGE HISTORY OF

**ISLAM** 

The New Cambridge History of Islam, offers a comprehensive history of Islamic civilisation, tracing its development from its beginnings in seventh century Arabia to its wide and varied presence in the globalised world of today. Under the leadership of the Prophet Muhammad, the Muslim community coalesced from a scattered, desert population and, following his death, emerged from Arabia

to conquer an empire which, by the early eighth century, stretched from India in the east to Spain in the west. By the eighteenth century, despite political fragmentation, the Muslim world extended from West Africa to South East Asia. Today, Muslims are also found in significant numbers in Europe and the Americas, and make up about one fifth of the world's population.

To reflect this geographical distribution and the cultural, social and religious diversity of the peoples of the Muslim world, The New Cambridge History of Islam is divided into six volumes. Four cover historical developments, and two are devoted to themes that cut across geographical and chronological divisions themes ranging from social, political and economic relations to the arts, literature and learning. Each volume begins with a panoramic introduction setting the scene for the ensuing chapters and exam ining relationships with adjacent civilisations. Two of the volumes one historical, the other thematic are dedicated to the developments of the last two centuries, and show how Muslims, united for so many years in their allegiance to an overarching and distinct tradition, have sought to come to terms with the emer gence of Western hegemony and the transition to modernity.

The time is right for this new synthesis reflecting develop ments in scholarship over the past generation. The New Cambridge History of Islam is an ambitious enterprise directed and written by a team combining established authorities and innovative younger scholars. It will be the standard reference for students, scholars and all those with enquiring minds for years to come.

Cambridge Histories Online © Cambridge University Press, 201 1

General editor

MICHAEL COOK, CLASS OF 1943 UNIVERSITY PROFESSOR OF NEAR EASTERN STUDIES, PRINCETON UNIVERSITY

VOLUME I

The Formation of the Islamic World Sixth to Eleventh Centuries

EDITED BY CHASE F. ROBINSON VOLUME 2

The Western Islamic World

Eleventh to Eighteenth Centuries

EDITED BY MARIBEL FIERRO VOLUME 3

The Eastern Islamic World Eleventh to Eighteenth Centuries

EDITED BY DAVID O. MORGAN AND ANTHONY REID VOLUME 4

Islamic Cultures and Societies to the End of the Eighteenth Century

EDITED BY ROBERT IRWIN VOLUME 5

The Islamic World in the Age of Western Dominance

EDITED BY FRANCIS ROBINSON VOLUME 6

Muslims and Modernity Culture and Society since 1800

EDITED BY ROBERT W. HEFNER

Grants made from an award to the General Editor by the Andrew W. Mellon Foundation, and from the National Endowment for the Humanities RZ -50616-06, contributed to the development of The New Cambridge History of Islam. In particular the grants funded the salary of William M. Blair who served as Editorial Assistant from 2004 to 2008.

Cambridge Histories Online © Cambridge University Press, 201 1

CAMBRIDGE UNIVERSITY PRESS

Cambridge, New York, Melbourne, Madrid, Cape Town, Singapore,

Sao Paulo, Delhi, Dubai, Tokyo, Mexico City

Cambridge University Press
The Edinburgh Building, Cambridge CB2 8ru, UK

Published in the United States of America by Cambridge University Press, New York

www.cambridge . org Information on this title: www.cambridge.org/9780521850315

© Cambridge University Press 2010

This publication is in copyright. Subject to statutory exception and to the provisions of relevant collective licensing agreements, no reproduction of any part may take place without the written permission of Cambridge University Press.

First published 2010

Printed in the United Kingdom at the University Press, Cambridge

A catalogue record for this publication is available from the British Library

isbn 978-0-521-85031-5 Volume 3 Hardback isbn 978-0-521-51536-8 Set of 6 Hardback Volumes

Cambridge University Press has no responsibility for the persistence or accuracy of URLs for external or third-party Internet websites referred to in

this publication, and does not guarantee that any content on such websites is,

or will remain, accurate or appropriate.

Cambridge Histories Online © Cambridge University Press, 201 1

Contents

List of illustrations page x

List of maps xi

List of contributors xii

Note on transliteration xv

Chronology xvi

List of abbreviations xxi

Maps xxii

Introduction: Islam in a plural Asia 1

DAVID O. MORGAN AND ANTHONY REID PART I

THE IMPACT OF THE STEPPE PEOPLES i • The steppe peoples in the Islamic world 21

EDMUND BOSWORTH

2 • The early expansion of Islam in India j8

ANDRE WINK

3 • Muslim India: the Delhi sultanate 100

PETER JACKSON

4 • The rule of the infidels: the Mongols and the Islamic world 12S

BEATRICE FORBES MANZ

5 • Tamerlane and his descendants: from paladins to patrons 169

MARIA E. SUBTELNY

Cambridge Histories Online © Cambridge University Press, 201 1

Contents

### PART II

# THE GUNPOWDER EMPIRES

6 • Iran under Safavid rule 203

# SHOLEH A. QUINN

7 • Islamic culture and the Chinggisid restoration: Central Asia in the sixteenth and seventeenth centuries 239

# R. D. McCHESNEY

8 • India under Mughal rule 266

STEPHEN DALE PART III

### THE MARITIME OECUMENE

 $9\, \bullet \, \text{Islamic trade, shipping, port states}$  and merchant communities in the Indian

Ocean, seventh to sixteenth centuries 317

### MICHAEL PEARSON

10 • Early Muslim expansion in South East Asia, eighth to fifteenth centuries 366

## **GEOFF WADE**

11 • Follow the white camel: Islam in China to 1800 409

### ZVI BEN DOR BENITE

12 • Islam in South East Asia and the Indian Ocean littoral, 1500 1800: expansion, polarisation, synthesis 427

## ANTHONY REID

 $13\, \bullet$  South East Asian localisations of Islam and participation within a global umma, c. 1500 1800 470

## R. MICHAEL FEENER

14 • Transition: the end of the old order Iran in the eighteenth century 504

## G. R. GARTHWAITE

Cambridge Histories	Online © Camb	oridge Universit	y Press, 201 1

Contents PART IV

**THEMES** 

15 • Conversion to Islam 529

RICHARD W. BULLIET

16 • Armies and their economic basis in Iran and the surrounding lands, c. 1000 1500 539

**REUVEN AMITAI** 

17 • Commercial structures 561

SCOTT C LEVI

 $18\, \bullet \, \text{Transmitters}$  of authority and ideas across cultural boundaries, eleventh to eighteenth centuries 5S2

MUHAMMAD QASIM ZAMAN

Glossary 611

Bibliography 620

Index 6S1

Cambridge Histories Online © Cambridge University Press, 201 1

Illustrations

i Mould for jewellery, bearing inscription 'Al mulk li llahi / al wahid / page 371

al qahhar'

- 2 A tasbih recovered from a mid fourth/ tenth century shipwreck in the 372 Java Sea
- 3 Mainstream South East Asian mosque type before the twentieth century, 442 exemplified in the multi tiered roof of the seventeenth century Indrapuri mosque in Aceh
- 4 The entrance to the tomb of Sunan Bonang, outside Tuban 451
- 5 Evidence of Shafi'i penalties for theft being applied in Aceh, as sketched 461 by Thomas Bowrey in the 1660s
- 6 The artificial mountain (Gunongan) of Aceh 491

Cambridge Histories Online © Cambridge University Press, 201 1

## Maps

- i Western Asia in the Saljuq period page xxii
- 2 The Mongol empire xxiv
- 3 The empire of Tamerlane xxvi
- 4 India and the Delhi sultanate xxviii
- 5 Iran under the Safavids xxix
- 6 Mughal India xxx
- 7 The Indian Ocean as Islamic oecumene xxxi
- 8 South East Asia and southern China xxxii
- 9 South East Asia in the fifteenth to eighteenth centuries xxxiii io Java in the fifteenth to seventeenth centuries xxxiv

## Contributors

Reuven Amitai is Eliyahu Elath Professor of Muslim History at the Hebrew University

of Jerusalem. Among his works are Mongols and Mamluks: The Mamluk Rkhanid War 1260

1281 (Cambridge, 1995) and The Mongols in the Islamic lands: Studies in the history of the Ilkhanate (2007).

Zvi Ben Dor Benite specialises in Chinese Islam and teaches in the Department of

Middle Eastern and Islamic Studies and the Department of History at New York University.

He is the author of The Dao of Muhammad: A cultural history of Muslims in late imperial China

(2005) and The ten lost tribes: A world history (2009). He is currently working on a book

entitled Crescent China: Islam and the nation after empire.

C.Edmund Bosworth is Emeritus Professor of Arabic Studies at Manchester

University and a Fellow of the British Academy. He was the British Editor of the second

edition of The encyclopaedia of Islam (i960 2005), and is the author of several books on Arabic

literature and on Islamic history and culture.

Richard W.Bulliet is Professor of Middle Eastern History at Columbia University in

New York City. He is the author of The patricians of Nishapur (1972), The camel and the wheel

(1975), Conversion to Islam in the medieval period (1979), Islam: The view from the edge (1994), The

case for Islamo Christian civilization (2004), Hunters, herders, and hamburgers (2005) and Cotton,

climate, and camels in early Islamic Iran (2009).

Stephen Dale is Professor of South Asian and Islamic History at Ohio State University,

specialising in the eastern Islamic world: South Asia, Afghanistan, Iran and Central Asia.

His publications include Islamic society on the South Asian frontier: The Mappilas of Malabar,

1498 1922 (1980), Indian merchants and Eurasian trade, 1600 17JO (Cambridge, 1994), The

garden of the eight paradises: Babur and the culture of empire in Central Asia, Afghanistan and

India, 1483 1530 (2004) and The Muslim empires: Ottoman, Safavid, Mughal, 1300 1923 (Cambridge, 2010).

R.Michael Feener is Associate Professor in the Department of History and the Asia

Research Institute, at the National University of Singapore. His books include Muslim legal

thought in modern Indonesia (Cambridge, 2007); and as co editor, Islamic law in contemporary

Cambridge Histories Online © Cambridge University Press, 201 1

### List of contributors

Indonesia: Ideas and institutions (2007), with Mark Cammack, and Islamic connections: Muslim societies of South and South East Asia (2009) with Terenjit Sevea.

G. R. Garthwaite is the Jane and Raphael Bernstein Professor of Asian Studies and

Professor of History at Dartmouth College. He is the author of Khans and shahs: A

documentary analysis of the Bakhtiyari in Iran (Cambridge, 1983) and The Persians (2005).

Peter Jackson is Professor of Medieval History at Keele University. His previous

publications include The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods

(as editor, 1986), The mission of Friar William of Rubruch His journey to the court of the Great

Khan Mongke, 12% 1255 (trans, and ed., with D. O. Morgan, Hakluyt Society, 2nd series, 173:

1990), The Delhi Sultanate: A political and military history (Cambridge, 1999), The Mongols and

the West, 1221 1410 (2005), The Seventh Crusade, 1244 1254: Sources and documents (trans, and ed., 2007).

Scott C. Levi is Associate Professor of History at Ohio State University. He is the

author of The Indian diaspora in Central Asia and its trade, 1550 1900 (2002) and the editor of

India and Central Asia: Commerce and culture, yoo 1S00 (2007).

R.D. McChesney is Emeritus Professor of Middle Eastern and Islamic Studies and

History at New York University . He is the author of Waqf in Central Asia (1991), Central Asia:

Foundations of change (1996) and Kabul under siege (1999) as well as numerous articles on the

social history of the greater Persianate world in the sixteenth to nineteenth centuries.

Beatrice Forbes Manz is Professor of History at Tufts University and the author of

two books: The rise and rule of Tamerlane (Cambridge, 1989) and Power, politics and religion in

Timurid Iran (Cambridge, 2007) and one edited collection, Central Asia in historical

perspective (1994).

David O. Morgan has been Professor of History and Religious Studies at the University

of Wisconsin Madison since 1999. Previously he taught the history of the Middle East and

Central Asia at the School of Oriental and African Studies, University of London. He is the

author of The Mongols (2nd edition, 2007) and Medieval Persia 1040 1797 (1988), and is General

Editor of Cambridge Studies in Islamic Civilization.

Michael Pearson is Emeritus Professor of History at the University of New South

Wales, Sydney, Australia and Adjunct Professor of Humanities at the University of

Technology, Sydney. Among his recent publications are Port cities and intruders: The

Swahili coast, India, and Portugal in the early modern era (1998 and paperback edn 2003),

(ed.) Spices in the Indian Ocean world (1996), The Indian Ocean (2003 and paperback edn 2007),

The world of the Indian Ocean, you 1800: Studies in economic, social and cultural history (2005).

Sholeh A. Quinn is Associate Professor in the School of Social Sciences, Humanities

and Arts at the University of California, Merced. She is the author of Historical writing during

the reign of Shah Abbas (2000) and co editor of History and historiography of post Mongol

Central Asia and the Middle East: Studies in honor of John E. Woods (2006).

Cambridge Histories Online © Cambridge University Press, 201 1

### List of contributors

Anthony Reid is a Southeast Asian Historian, currently Emeritus Professor and Visiting

Fellow at the Research School of Pacific & Asian Studies at the Australian National

University, where he was also employed 1970 99. In between he was founding Director

(2002 7) of the Asia Research Institute of the National University of Singapore, and

Professor of History and founding Director of the Center for SE Asian Studies at UCLA

(1999 2002). He is a Corresponding Fellow of the British Academy and the Royal Historical

Society. His more recent books include Southeast Asia in the age of commerce,  $1450\ 1680$ 

(2 vols., 1988 93), Charting the shape of early modern Southeast Asia (1999), An Indonesian

frontier: Acehnese and other histories of Sumatra (2004), Imperial alchemy: Nationalism and

political identity in Southeast Asia (Cambridge, 2009) and (as editor or co editor) Verandah of

violence: The historical background of the Aceh problem (2006), Viet Nam: Borderless histories

(2006), Islamic legitimacy in a plural Asia (2007), Chinese diaspora in the Pacific (2008) and

Negotiating asymmetry: China's place in Asia (2009).

Maria E. Subtelny (Ph.D., Harvard University, 1979) is Professor of Persian and Islamic

Studies in the Department of Near and Middle Eastern Civilizations at the University of

Toronto. Her related publications include Timurids in transition: Turko Persian politics and

acculturation in medieval Iran (2007) and Le monde est unjardin: Aspects de l'histoire culturelle de

Vlran medieval (2002).

Geoff Wade is a Senior Research Fellow at the Institute of Southeast Asian Studies,

Singapore. He researches diverse aspects of pre modern and early modern intra Asian

interactions and comparative historiography. Key works include a database of Ming

imperial references to South East Asia (www.epress.nus.edu.sg/msl/) and the six

volume collection China and Southeast Asia (2008).

Andre Wink is Professor of History at the University of Wisconsin Madison. He is the

author of Al Hind: The making of the Indo Islamic world, 5 vols. (1990, 1997, 2004 and

forthcoming) and Akbar (2008).

Muhammad Qasim Zaman is Niehaus Professor of Near Eastern Studies and Religion at

Princeton University. He is the author of Religion and politics under the early 'Abbasids (1997),

Tlie ulama in contemporary Islam: Custodians of change (2002) and Ashraf 'Ali Thanawi: Islam in modern South Asia (2008).

Cambridge Histories Online © Cambridge University Press, 201 1

Note on transliteration

The transliteration of Arabic and Persian words is based on the conventions

used by The Encyclopaedia of Islam, second edition, with the following mod

ifications. For the Arabic letter jim,j is used (not dj). For the Arabic letter qaf, q

is used (not fe). Digraphs such as th, dh, kh and sh are not underlined.

Words and terms in other languages are transliterated by chapter contributors according to systems which are standard for those languages.

Place names that are Arabic in origin have diacritical points, except in some

well known instances (e.g. Baghdad, not Baghdad), or where there are stand ard Anglicised versions (e.g. Cairo).

Cambridge Histories Online © Cambridge University Press, 201 1

Chronology

334/945 Buyids occupy Baghdad

376 / 986 Cham Muslims flee Vietnamese pressure to Hainan, south China

388/998 Mahmud of Ghazna takes power there

400/1010 Ashab mosque founded in Quanzhou, south east China

411/1020 Death of Firdawsi, author of the Shah nama

415/1024 Hindu Cola attacks disrupt Muslim maritime network in

## southern Asia

421 / 1031 Accession of Mas c ud of Ghazna

431/1040 Ghazna vids defeated by Saljugs at Dandangan

447/1055 Saljugs under Toghnl Beg occupy Baghdad: fall of Buyids

455/1063 Death of Toghnl Beg; accession of Alp Arslan

459/1067 Foundation of the Nizamiyya madrasa in Baghdad

463/1071 Saljugs defeat Byzantines at Manzikert

464/1072 Death of Alp Arslan; accession of Malik Shah

475/1082 Earliest dated Muslim gravestone in Indonesia, in Leran, east

### **Tava**

483/1090 Nizari Isma'ilis under Hasan i Sabbah take Alamut

485/1092 Death of Malik Shah and his Persian vizier Nizam al Mulk

505/1111 Death of al Ghazali

536/1141 Saljuq sultan Sanjar defeated on the Qatwan steppe by the

### Qara Khitay

552/1157 Death of Sanjar: effective end of Great Saljuq sultanate 602/1206 Quriltai in Mongolia acclaims Chinggis Khan. Foundation of

the Delhi sultanate by Qutb al Din Aybak 604/1208 Ala' al Din Muhammad Khwarazm Shah takes Transoxania

from Qara Khitay 616/1219 Mongols under Chinggis Khan invade the Khwarazm Shah's empire

Cambridge Histories Online © Cambridge University Press, 201 1

# Chronology

617/1220 Balkh and Nishapur fall to the Mongols

618/1221 Death of 'Ala' al Dm Khwarazm Shah

624/1227 Death of Chinggis Khan

654/1256 Hiilegii, first Mongol Ilkhan, takes Alamut

656/1258 Hiilegii takes Baghdad and executes the last 'Abbasid caliph

658/1260 Ilkhanid Mongols defeated at c Ayn Jalut by Mamliiks

662/1264 Qubilai becomes Great Khan of the Mongol empire after a

four year civil war 663/1265 Death of Hiilegii

672/1273 Death of Jalal al Dm Riimi, Sufi master and poet 672f. /1274 Muslim Pu Shougeng becomes maritime trade supervisor in

## Quanzhou

673/1274 Death of Nasir al Dm Tiisi

693/1294 Wijaya establishes Majapahit kingdom in Java, following

## Mongol invasion

694/1295 Accession of Ghazan Khan, first of the line of Muslim Ilkhans 695/1296 Accession of [ Ala ] al Din Khalji, sultan of Delhi

696/12.97 Death of Sultan Malik al Salih of Pasai (north Sumatra),

earliest authenticated Muslim ruler in South East Asia

703/1304 Death of Ghazan; accession of Olieitii

718/1318 Rashid al Dm, Ilkhanid minister and historian, executed

724/1324 Accession of Muhammad Tughlug, sultan of Delhi

731/1331 Ibn Battuta describes flourishing Muslim port states of Kilwa

and Mogadishu, in East Africa

734/1334 Death of Shaykh Safi al Din Ardabili, founder of the Safavid

order

736/1335 Death of Abu Sa'id, last Ilkhan of the line of Hiilegii. Birth of

Tamerlane

738/1338 Independence of Muslim Bengal

744/1343 Ibn Battuta visits flourishing sultanates of Maldives and Pasai,

respectively Malik! and Shafi'i.

751/1350 Accession of Hayam Wuruk brings Majapahit to peak;

conquest of Muslim Pasai

758/1357 Muslim 'Isfahan' rebellion in Quanzhou region; Muslim

traders flee violence by sea to South East Asia

769 1 1368 Chinese Ming dynasty replaces Mongol Yuan dynasty in China

791/1389 Death of Muhammad Baha' al Dm Nagshbandi, after whom

the Naqshbandi Sufi order was named

Cambridge Histories Online © Cambridge University Press, 201 1

# Chronology

801/1398 Tamerlane sacks Delhi

804/1402 Tamerlane defeats Ottomans at Ankara

805/1403 Independence of Muslim Gujarat

807/1405 Death of Tamerlane

807/1405 Voyages into Indian Ocean by China's Muslim admiral Zheng

He begin, extending until 838/1435 and following Muslim

trade routes to Hormuz and Aden

850/1447 Death of Shah Rukh, Tamerlane's son and ultimate successor

871/1466 Accession of Uzun Hasan Aq Qoyunlu

872/1467 Uzun Hasan defeats Jahanshah Qara Qoyunlu

873/1469 Accession of Sultan Husayn Baygara, last Timurid ruler in

#### Herat

876/1471 Vietnamese capture of Cham capital Vijaya creates Muslim

## diaspora

878/1473 Uzun Hasan defeated by Ottomans at Tirjan

882/1477 Death of Sultan Mansur, Melaka's strongest ruler

885/1480 Dated inscription in mosque of Calicut (Kerala, India)

903/1498 Vasco da Gama reaches Calicut (Kerala); Portuguese Muslim

# trade competition in Indian Ocean

907/1501 Shah Isma'il, first shah of the Safavid dynasty, takes Tabriz

910/1504 Babur occupies Kabul

913 / 1507 Uzbeks occupy Herat after death of Sultan Husayn Bayqara in

# previous year

916/1510 Shah Isma'il defeats the Uzbeks at Marv: Muhammad Shibani

## Khan killed

917/1511 Albuquerque conquers Melaka; Malay capital moves to Johor

920/1514 Ottomans defeat Shah Isma'il at Chaldiran

921/1515 Portuguese capture Hormuz

930/1524 Death of Shah Isma'il: succeeded by Tahmasp I

932/1526 Babur defeats Ibrahim Lodi at Panipat, occupies Delhi,

# founds Mughal empire

933/1527 End of Majapahit kingdom; Muslims dominate Java

936/1530 Death of Sultan Ali Mughayat, unifier of Aceh (Sumatra)

937/1530 Death of Babur; succeeded by Humayun

945 / 1538 Ottoman naval expedition into Indian Ocean against Portuguese

963/1556 Death of Humayun; succeeded by Akbar

972/1565 Alliance of four sultanates destroys Hindu Vijayanagara,

south India

Cambridge Histories Online © Cambridge University Press, 201 1

# Chronology

975/1567 Aceh Ottoman alliance against Portuguese

978/1570 Portuguese murder of Sultan Hairun ensures rise of Muslim

expansionist Sultan Baabullah in Ternate (east Indonesia) 984/1576 Death of Tahmasp

987/1579 Muslim Banten crushes Hindu Pajajaran in west Java 996/1588 Accession of Shah 'Abbas I

1007/1598 Safavid capital transferred from Qazvin to Isfahan

1014/1605 Conversion of Makassar (Sulawesi) to Islam

1014/1605 Death of Akbar; succeeded by Jahangir

1028/1619 Dutch East India Company (VOC) establishes Asian

# headquarters in Batavia (Jakarta)

1034/1625 Sultan Agung of Mataram conquers Surabaya, unifies

Javanese on syncretic Muslim programme

1037/1628 Death of Jahangir; succeeded by Shah Jahan

1038/1629 Death of Shah 'Abbas I

1038/1629 Military setbacks of Aceh against Portuguese Melaka, and

# Mataram against Batavia

1046/1636 Death of Sultan Iskandar Muda of Aceh; succeeded by son in

law Iskandar Thani, patron of Nur al Din al Raniri

1049/1639 Definitive peace between Safavids and Ottomans

1051/1641 Death of Sultan Iskandar Thani; accession of his widow

# Safiyyat al Din as first of four Aceh queens

1056 / 1646 Death of Sultan Agung of Mataram; succession of

### Amangkurat I

1067/1658 Shah Jahan imprisoned by his son Aurungzeb

1080/1669 VOC with Bugis allies conquers Makassar

1082 /1671 Khoja Afag spreads Nagshbandi Sufi order in north west

### China

1090/1679 VOC crushes Islamic Trunajaya rebellion in Java, in alliance

## with weakened Mataram

1093/1682 VOC conquers Banten, and thereafter controls sultanate

## indirectly

1105/1693 Death of Abd al Ra'uf al Singkili, scholar saint of Aceh

1105/1694 Accession of Sultan Husayn, last Safavid shah

1111/1699 Female rule ended in Aceh with help offatwa from Mecca;

## Arab dynasty

1118/1707 Death of Aurungzeb

1134/1722 Afghans occupy Isfahan: effective end of Safavid rule

Cambridge Histories Online © Cambridge University Press, 201 1
--

Chronology

1148/1736 Nadir Khan declares himself Shah of Iran

1152/1739 Nadir Shah takes Delhi

1160/1747 Assassination of Nadir Shah; foundation of kingdom of

Afghanistan by Ahmad Shah Durrani 1164/1751 Karim Khan Zand becomes ruler in Shiraz 1209/1795 Agha Muhammad Khan, founder of the Qajar dynasty, establishes the capital of Iran at Tehran

Cambridge Histories Online © Cambridge University Press, 201 1

Abbreviations

Ef The encyclopaedia of Islam, 2nd edn (Leiden, i960 2003)

Ef The encyclopaedia of Islam, 3rd edn (Leiden, 2007)

EIr Encyclopaedia Iranica

VOC Verenigde Geoctroyeerde Oost Indische Compagnie (Dutch) United Chartered East India Company

Cambridge Histories Online © Cambridge University Press, 201 1

Map i: Western Asia in the Saljug period

Cambridge Histories Online © Cambridge University Press, 201 1

Cambridge Histories Online © Cambridge University Press, 201 1

Map n: The Mongol empire

Cambridge Histories Online © Cambridge University Press, 201 1

Cambridge Histories Online © Cambridge University Press, 201 1

Map y. The empire of Tamerlane

Cambridge Histories Online © Cambridge University Press, 201 1

Cambridge Histories Online © Cambridge University Press, 201 1

Cola state at its maximum extent, c. 1 1 00 Eastern border of Ghaznavid emirate, c. 1150 Empire of Muhammad of Gh.ur, c. 1206 Vijayanagara at its maximum extent, c 14S5

ihmapHtra \* Temtir 's inTls ™ '139S ~ 9

ot ana Kangra Major religious sites c. 1 100-1400

Y (^ o Buddhist shrine

o Hindu shrine

Map 4: India and the Delhi sultanate

Cambridge Histories Online © Cambridge University Press, 201 1

low lzrplm

Empire of Shah Ismail c 1512 Area contested wiuiMughals in the 17th century | | Ottoman empire

Area and date conquered by Ottomans fieo3) Date of reconquest by Safavids 
☐ Safavid capital o Shi 'a shrine

Map 5: Iran under the Safavids

Cambridge Histories Online © Cambridge University Press, 201 1

Map 6: Mugjial India

Cambridge Histories Online  ${\hbox{\tt @}}$  Cambridge University Press, 201 1

Map 7: The Indian Ocean as Islamic oecumene

Cambridge Histories Online © Cambridge University Press, 201 1

Map 8: South East Asia and southern China

Cambridge Histories Online © Cambridge University Press, 201 1

Map 9: South East Asia in the fifteenth to eighteenth centuries

Cambridge Histories Online © Cambridge University Press, 201 1

Map 10: Java in the fifteenth to seventeenth centuries

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

DAVID O. MORGAN AND ANTHONY REID

In writing the history of the Islamic world, there are two expedients which,

sooner or later, become impossible to avoid: periodisation and geographical

subdivision. These are bound to be, to a greater or lesser extent, arbitrary, but

that does not imply that they are necessarily meaningless. It is possible to tell

the story of early Islam, the mission of the Prophet Muhammad, the first Arab

Muslim expansion and the Umayyad and 'Abbasid caliphates as a single,

integrated narrative. There is an essential unity to the historical evolution of

the Muslim community, in its first four centuries, which lends itself to such an

integrated treatment. From the eleventh century, and increasingly thereafter,

this is no longer the case. The political unity represented by the early caliph

ates is no more. Though caliphs remained important for a time as local rulers.

whether in Baghdad, Cairo or al Andalus, and even more as instruments of

legitimisation for Islamic regimes far and wide, real power passed to a multi

plicity of sultans, amirs, maliks and so on. There is nothing very surprising

about this. At the point at which this volume commences, the Islamic world

stretched uninterruptedly from Spain to Central Asia and northern India. Over

the next few centuries it was to spread much further, deeper into India and to

western China, and by oceanic routes to East Africa, coastal South Asia, South

East Asia and southern China. Not only does such an expanse defy central rule

or co ordination of any kind, the spread of Islam across such cultural and political diversity would also have been impossible if the Islamic lands had

remained politically unified. The trader and the mystical order (tarxqa) became

as important as the soldier and administrator in the further spread of Islam. As

the faith crossed numerous cultural boundaries, distinctive Islamic idioms

emerged in other great linguistic traditions beyond the Arabic including Turkish, Persian, Swahili, Malay and Chinese.

That is some justification for commencing a volume of this history in the eleventh century, and for dividing the Islamic world into a western and an

eastern half. It is convenient, and it is necessary. And as we shall see, the

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

historical experience of the eastern Islamic world, from the time of the Saljuq

incursions, is in many ways different from that of the western half. But there is

a price to be paid, in that crudely severing the lands of Islam into two can easily generate the impression of much greater divergence than was in reality

the case. We might mention just two examples. The Saljuqs, who ushered in

the new era which, it will be argued, began in the mid eleventh century, incontestably belong on the eastern side of the divide. Yet they ruled for a time

in Syria, and for centuries in Anatolia, both of which fall on the western side of

our divide, and therefore cannot be dealt with in this volume. Similarly, the

'Abbasid caliphs lived in Baghdad, within our geographical area. But whatever

the limitations of their 'secular' power in this period, they were still acknowl

edged as the titular heads of the Muslim community, until the destruction of

the caliphate by the Mongols in 1258, throughout much of the western Islamic

world.

A terminal date at the end of the eighteenth century finds its justification in

the relationship between Islam and modernity, as understood in both European and Islamic terms. The conventional periodisation of European history makes a crucial break, the division between 'medieval' and 'modern',

somewhere around 1450 1500: the time of the Renaissance and the Reformation. There were changes in the Islamic world, too, around 1500: some of these will be discussed later. But they hardly match in their radical

significance the changes that overcame Western Europe. By contrast 1800, or

the century of which it marks the centre, sees the beginnings of the impact on

the world's Muslims of the full weight of modernity in the guise of Western

economic and military success in the nineteenth and twentieth centuries. Islamic modernism, though in most respects a quite different phenomenon

from its European counterpart, had its origins in the same watershed, and can

be considered a development (however internally varied) of the nineteenth and twentieth centuries.

There remains an argument for suggesting that for the older established eastern lands of Islam, the period between the eleventh and eighteenth centuries the period treated in this volume has sufficient unity of character

to be justly termed a 'middle' age. What sets it apart from the earlier and later

periods, however, cannot be equated with what characterised the European

Middle Ages. And in any case, for most of the Asian peoples who form the majority of contemporary Muslims, our period is not a 'middle' at all, but rather the foundational period of their Islam. This volume will therefore emphasise three major features which distinguish the time and place from

both the earlier experience of Islam, and the universal modernity of the

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

nineteenth and twentieth centuries. One with far reaching consequences still

not wholly exhausted was the impact on the Islamic lands of the steppe tribal

peoples of Central Asia, especially though not exclusively the Turks. A second

was the maritime expansion of Islam along the trade routes of the Indian Ocean and the South China Sea, which had a quite different character from the

conquests of the heroic age. Related to both phenomena was a third, broader

one. Until the eleventh century, Islam had expanded and developed in interaction primarily with Christianity and its Greco Roman heritage, and with Judaism and Zoroastrianism. In the eastern lands thereafter, interactions

became extensive with Asian spirituality, including what we today label Hinduism, Jainism, Sikhism, Buddhism, Taoism and Shamanism, as well as

with Asian political and cultural forms.

### Central Asia and the Turks

The Islamic lands had had relations, friendly and otherwise, with Turks beyond

the borders for much of the period covered by volume i of this history. The at

least partly Judaised Khazar empire had for long been an effective barrier to the

spread both of Islam as a religion and of Muslim political rule north of the

Caucasus. As the Central Asian frontiers of the dar al islam were pushed forward

into and beyond Transoxania, individual Turks were captured in batde or purchased as slaves. The c Abbasid caliphs most famously al Mu'tasim, though

the process was under way before his reign came to value such slaves particularly for their martial qualities: a trained military force of Turks, newly

converted to Islam and loyal to their caliphal master, looked an attractive,

efficient and trustworthy alternative to reliance on the fractious Khurasani

armies which had first brought the 'Abbasid dynasty to power. It is true that

that loyalty did not last very long: not many years were to elapse before political

power in Baghdad became a prize to be fought for between the Turkish generals, with the caliph becoming little more than a conveniently tame, if

necessarily legitimising, figurehead. But Turkish slave soldiers (mamluks or

ghulams) had come to stay. Even the Buyids, Persians from the Caspian provinces who ruled in western Iran and in Baghdad itself for a century from

945, had a substantial Turkish element in their army. The notable dynasty to the

east which was for a time the Buyids' contemporary, the Persian Samanids of

Bukhara, were famed for their efforts not only in encouraging the spreading of

the faith of Islam further into Turk dominated Central Asia but also in trading

extensively in Turkish slaves at the frontier markets. And it was one of their

# The New Cambridge History of Islam

own dissident Turkish generals who set up the Ghaznavid empire in what is

now Afghanistan and northern India.

But all of these developments, important though they certainly were, were

changes internal to the Mr al islam. Whatever the power ultimately wielded

by Turkish military slaves, they had all been brought into Islam, in both its

religious and its secular aspects, as individuals. That, indeed, had been part of

their appeal to their early masters: they had no local or family loyalties such

ties had been left behind in their Central Asian homeland and thus it was supposed, initially with some justification, that their allegiance would be exclusively to their new Muslim owners. In the eleventh century, as this volume commences, all this was to change. Mamluk soldiers were to remain

crucially important in many Muslim states right to the end of our period. But

many of the Turks who entered the Mr al islam from now on were not to be

warriors acquired as individuals, but tribal hordes coming in en masse, their

tribal organisation, social structure and nomadic way of life still intact, and

their tribal leaders still very much in charge. It has sometimes been suggested,

with a degree of exaggeration, that for much of the Middle East the period

from the eleventh to the nineteenth centuries was one in which military, and

hence political, power throughout most of the region was held either by Turks

or by the descendants of Turks. Even at the beginning of the twentieth century, the two major independent Muslim powers in the Middle East were still ruled by Turkish dynasties: the Ottomans, of course, but the Qajars of Iran were also, in origin, of Turkish descent. Indeed, it may be said that apart from the Zand interlude of the eighteenth century in part of the

country, Iran as a whole had no ethnically Persian rulers from the arrival of the

Saljuqs until the accession of Reza Shah in 1925 very nearly 900 years.

In northern India, the first Muslim rulers (discounting the early Arab incur

sions into Sind), the Ghaznavids, had been of Turkish stock. The sultanate of

Delhi, under whose rule the first real advances of Islam as a religion in India

were made, was established by Turkish generals of the Ghurids in what is now

Afghanistan. The last and greatest Muslim dynasty, that of the Mughals, which

ultimately if briefly reigned over almost the whole of the subcontinent and

which did not finally disappear until the mid nineteenth century, was of Turko Mongol stock, the founder, Babur, rejoicing in his descent from both

Tamerlane (Temiir) and Chinggis Khan.

What impact these incursions had has been much debated. From a strictly

religious point of view, things could have been worse in that most of the nomads from the east were already converts to Islam by the time they entered

the Mr al islam. This was true of the first such incursion, that of the

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

Qarakhanids, though in any case their arrival was of comparatively limited

effect, in that they progressed no further westwards than Transoxania. Much

more important, the Saljuqs had become Muslims before they crossed the frontier: though precisely what kind of Muslims is not as obvious as is sometimes assumed. What is usually said about the conversion to Islam of

the tribal peoples of Central Asia is that it was the work of wandering Sufi

missionaries wild, wonder working figures who were so similar to the shamans of traditional tribal society that the Turks and others were hardly

able to tell the difference. There is sometimes, but not always, evidence that

something of the sort occurred, but as a general explanation this should be

viewed with a degree of scepticism. The Saljuqs are a classic example. If they

had in fact been converted to a syncretic, Shamanism like form of Sufi Islam,

it is not immediately obvious why they should have become, once in power

in Iran and Iraq, fervent champions of hardline Sunni orthodoxy. The possibility remains that lurking in the pre Islamic background may be the influence not so much of Shamanism as of either Nestorian Christianity, which was long to remain influential and widespread on the steppes, or, more probably, the Judaism of the Khazars. 1 That Judaism, it is thought, was

probably rabbinic, and the step from rabbinic Judaism to Sunni orthodoxy is

perhaps smaller than one from wonder working Sufism would have been. Evidence is lacking, but the names allegedly given to the four sons of the Muslim convert Saljuq, though respectably Islamic, have without exception

a suggestively Old Testament look to them.

Still, there was no doubting the Saljuqs' Muslim credentials, by whatever route they may have arrived at them. The bigger problem was the Mongols,

who ruled large parts of the Islamic world for many decades while still infidels.

Chinggis Khan arrived in 1219, and it was not until 1295 that the Mongol rulers

of Iran definitively went over to Islam. It was a basic presumption of Islamic

political thought that the Mr al islam should expand, inexorably, at the expense of the Mr al harb, until the whole world was under Muslim rule (though not necessarily entirely converted to Islam). There was no provision

for the process to go into reverse, for Muslim lands to come under the rule of

non Muslims. There had already been some losses, notably in al Andalus and

in the Mediterranean. But the loss to the infidel of Iran and Iraq was a far more

serious blow. The Mongols were unique in this respect until, in the modern

period, large parts of the Islamic world came under the political domination of

1 Peter B. Golden, An introduction to the history of the Turkic peoples (Wiesbaden, 1992), p. 218.

# Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

European powers and Manchu China; but at least the Mongols, unlike those

later powers, did come ultimately to acknowledge the truth of Islam.

The effect of the Turkish incursions on the fortunes of Islam as a religion was not, then, in any way catastrophic, except perhaps from the point of view of the Shl'I communities. What was significant was the boost the Saljuqs gave to the Sunni form of Islam. Prior to their arrival, much of

the Middle East had been under Shi'ite rule, most notably but not only the

Fatimids in Egypt and the Buyids in Iran and Iraq. Of the major Muslim powers of the region around iooo, only the Ghaznavids were Sunni. It was the Saljuqs who restored Sunni supremacy in the areas they came to rule;

and the ultimate abolition of the Fatimid caliphate in Egypt by Saladin may

be regarded as another long term effect, since, as Claude Cahen once observed, Nur al Dm and Saladin are not explicable without reference to the achievement of Toghril Beg, the first Saljuq sultan, and Nizam al Mulk,

the Saljugs' great Persian administrator.

In other ways, too, the advent of the Saljuqs was epoch making. They may

not precisely have caused, but they certainly initiated, a marked change in the

ethnic make up of the region. Put simply, from the eleventh century onwards.

there were a great many more Turks. This is, of course, most conspicuously

the case in Turkey, a country the Saljuqs invented, albeit inadvertently. The

collapse of the Byzantine eastern frontier after the emperor Romanus IV Diogenes's defeat at the hands of Sultan Alp Arslan, at Manzikert in 1071,

allowed Turks to flood into Anatolia. Although some of the territories then

lost were later recovered for a time by the Byzantines, the battle of Manzikert created the potential for Turkey, a potential which ultimately

produced what has been called the last and greatest of the Muslim empires,

that of the Ottomans. That, however, is not the concern of this volume. But the influx of Turks did not affect only Anatolia. It had permanent consequences for the ethnic population balance of much of the eastern Islamic world, especially Iran. To this day, a large proportion of the Iranian

population is Turkish speaking, and much of that, presumably, is of Turkish

ethnic origin. Whether or not that means that their ancestors entered Iran in

the wake of the Saljuq invasion or during the Saljuq period is, however, another question: one about which there has been a good deal of discussion.

The likelihood is that while the process of Turkish immigration did indeed begin, to a very significant degree, under the Saljuqs, the bulk of the Turks

arrived later, particularly during the Mongol period and even after. The numbers quoted by historians of the Saljuq period for the sizes of tribal hordes

are not enormous, unlike those routinely ascribed to the Mongol armies by

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

those historians' later successors (which may perhaps suggest caution about

assuming that medieval chroniclers invariably tend to exaggerate).

In terms, too, of the way of life of the peoples of the eastern Islamic world,

the arrival of the Saljuqs and other Turks from Central Asia caused a major

shift: in the balance of the population between sedentary and nomad. This was

of permanent significance: the nomadic element in the population remained,

from then on, of much greater importance, culturally and politically, than was

the case in much of the rest of the Mr al islam. It was only in the twentieth

century that a more or less successful attempt was made to curb the power

and comparative independence of the nomadic tribes of Iran and even then,

the last major tribal revolt occurred as recently as 1963. The Saljuqs' followers

in their migration across the Oxus were tribally organised nomads, and their

military force, therefore, was essentially a classic tribal horde of cavalry archers, not dissimilar in most major respects from the better known Mongols of the thirteenth century, though certainly not so disciplined and

regulated as the armies of Chinggis Khan were to be. Indeed, the tribal Turkish hordes soon came to be something of an embarrassment to the newly respectable Saljuq sultans. Traditionally, a tribal khan was very far from possessing despotic powers in time of peace, though he was expected to

command, and to command effectively, in warfare. Not all of the Turks who

followed Toghril Beg and Chaghn Beg into Iran and Iraq took kindly to their

transformation into, potentially, the subjects of much more powerful Muslim

sovereigns. Hence many of them, seen increasingly as disorderly and disrup

tive by their leaders, voted with their feet. The Turkomans whose incursions

into Byzantine eastern Anatolia precipitated the crisis that led to the battle of

Manzikert in 1071 are one example. Similarly, the lifelong preoccupation of the

last Saljuq sultan of the east, Sanjar (d. 1157), was the containment of the Ghuzz

Turkish hordes who were endangering the stability of Khurasan. It was not

long before the Saljuqs found it necessary to provide themselves with a permanent, if fairly small, standing army to reduce reliance on the tribal contingents that had first brought them to power. Their great Persian vizier,

Nizam al Mulk, in his handbook of government, the Siydsat noma, recom mended the recruitment of mamluks as a reliable buttress for the state: he was

clearly worried about the ungovernability of the Turkish tribes.

In military terms, the advent of the Turks marked the supremacy, for centuries to come, of the steppe cavalry archer. The Mongols are the most

conspicuous example of this, but in principle the same factors, to a greater or

lesser extent, worked to the advantage of other conquerors from Central Asia.

In the field, in pre modern times, an army composed of such warriors could

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

expect to have a decisive advantage over the armies of the sedentary states

they faced, richer and more populous though those states generally may have

been (though when it came to siege warfare it was a different story, and nomadic invaders frequency had to avail themselves of the expertise of engineers from the sedentary world). Because of the close approximation between ordinary nomadic life, with its herding and hunting, and warfare, the

tribesmen were in effect a permanently available mounted force, trained constantly in appropriate techniques since childhood. What is more, they were all available: no sedentary state could possibly mobilise so large a proportion of its manpower. And in the composite bow of the steppes, the nomads had a battlefield weapon which in terms of accuracy, rate of fire, range

and power of penetration had no equal until long after the first appearance of

firearms: it was centuries before a handgun existed which could hope to match

the composite bow in effectiveness. We should not assume that with the invention of gunpowder, the traditional style of steppe warfare and its composite bow were immediately rendered obsolete.

# Maritime expansion and cultural diversity

The second major theme of this volume will be the maritime expansion of Islam, accompanying the vessels that criss crossed the Indian Ocean and travelled as far as the south eastern coast of China. This pattern had very little

in common with the advancing military and administrative frontiers of the

heartlands of Islam and the steppes of Eurasia.

The forested tropical regions around the Indian Ocean were not favourable

to the empires of marching armies or cavalry charges. Communication was

much easier by water than by land. But the oceans of Asia also offered few

examples of military expansion by sea until the advent of European naval power in 1498. Those few examples the Tamil Cholas in the eleventh century, the Javanese of Majapahit in the fourteenth or the huge Chinese fleets of the early fifteenth were not Islamic, except in so far as individual Muslims took leadership roles, as the Yunnan eunuch and admiral Zheng He

(Cheng Ho) did in commanding the Chinese expeditions. The only explicit uses of central Islamic power in the Indian Ocean that of the Ottomans in response to Portuguese naval attacks in the 1530s and again in the 1560s were

failures, even if significant ones.

Nevertheless, Muslims held certain advantages in navigation and maritime

trade which gave them commercial dominance in the Indian Ocean from roughly the twelfth century to the sixteenth. Arabs, commanding the

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

favoured Red Sea and Persian Gulf routes between the Mediterranean and

Indian Oceans, had been sailing their dhows to India and beyond since pre

Islamic times. The egalitarian, commercial and legal ethos of Islam appeared

well suited to the establishment of Islamic commercial communities in all the

ports of that immensely diverse littoral. By the eighth century the Arab and

Persian Muslim traders residing in Canton were rich and numerous enough to

stage a revolt (758) which briefly took control of the city. By the end of the

Tang dynasty in 907 Sinicised Muslims, the Hui, had become a permanent part

of several coastal Chinese cities. From the ninth century we have the accounts

of Arab geographers, describing the trading routes and ports between the Red

Sea and China.

The major ports along this route were in south India and Sri Lanka, northern Sumatra, the isthmian ports of the Malayan peninsula, the north coast of Java and the Cham ports of what is now the central Vietnamese coast.

In all these places, as in the Chinese ports themselves, a few Islamic tomb

stones bear witness to the beginnings of Islamic communities in the eleventh

to fourteenth centuries. All began as enclaves and minorities, Islamic quarters

in larger trading cities. Islamic law and the Arabic language made it easier for

traders to move from one of the quarters to another, creating a kind of Muslim

commercial oecumene even before the rise of Islamic political power.

The first Islamic states in South East Asia which can be clearly documented

from tombstones and travel accounts occurred on the northern coast of Sumatra in the 1290s. The most prominent of these was Samudera, later called

Pasai, where Ibn Battuta in 1345 found a flourishing Sunrii polity following the

Shafi'i school of law, as virtually all of South East Asia does today. As Muslim

merchants became more and more important a factor in the prosperity of the

host of small river ports in the archipelago, many of their rulers became Muslim in the following century, through conviction, force, marriage or a judicious choice of alliances.

An intriguing, still unresolved, issue is the extent of northern influences from

China and Champa in this phase of Islamisation. The Mongol conquest of China

in the late thirteenth century had brought a variety of Central Asian Muslims

into the official and military service of China. They were particularly strong in

Yunnan, which the Mongols added to the Chinese empire and placed under a

Muslim governor. When the Mongols in turn were overthrown by the Ming

dynasty in 1368, those Muslims who remained were Sinicised in language and

much of their culture, but many remained in privileged positions. The great

expeditions sent to South East Asia and the Indian Ocean under the emperor

Yongle were commanded by the Yunnan Muslim Zheng He, and many of his

Cambridge Histories Online © Cambridge University Press, 201 1

#### The New Cambridge History of Islam

soldiers were also Muslim. Some traditions of Java attribute to these fleets an

injection of Chinese Muslims into the affairs of the Java Sea, and the rise of

Muslim port states such as Gresik, Tuban, Japara, Demak and Cirebon, along

the north coast of Java. Melaka on the peninsula, which replaced Pasai as the

most important Malay Muslim trading state in the late fourteenth century, also

got its start by cultivating these imperial Chinese fleets.

Once Javanese port states had become predominantly Muslim, their superior arms, wealth and motivation came into play in the conquest of the Hindu

Buddhist kingdoms of the interior. The fall of Majapahit to Muslim arms is

conventionally dated 1478, but was in any case complete by about 1527. But the

hegemony of the Islamic coast was brief. Around 1600 a new Javanese king

dom arose at Mataram, centred near modern Yogyakarta. The great king of

Mataram, usually known as Sultan Agung (1613 46), though he carried many

titles both Hindu and Muslim, achieved what Akbar attempted in India, a synthesis of old and new religions. From his reign stems the idea that Java is a

special case within Islam, a stable amalgam of Hindu Buddhist mystical ideas,

animist popular practices and Islamic externals. The controversy this idea has

engendered will engage particular attention below.

As Islam became established so far from its roots, translations became necessary into a variety of languages. In the sixteenth century this process

began with Malay and Javanese, and the fullest flower of Islamic literature in

Malay occurred in the seventeenth century. Most of the most influential writers and teachers known to us in these traditions were Sufis, and many

had studied in Mecca or Medina and become members of the Khadiriyya or

Shattariyya tafiqa. As they were throughout the Muslim world in this period,

these Sufis were followed in life and revered in death, often more than they

were read. They gave substance and life to the traditions of life and law the

traders had brought.

The century from about 1540 to 1640 is a particularly interesting one in maritime Asia, because the reaction against Portuguese attacks on Islam pro

duced a high point of rallying around the banner of political Islam. The Portuguese directed their attacks particularly against the Arab, Gujarati, south

Indian and Malay traders who had dominated the pepper and spice trade from

South East Asia to the Red Sea. After severe initial disruption and the loss of

many ports, a Muslim trading network was re established in mid century, link

ing Aceh in Sumatra to the Red Sea by way of the Maldives. In the 1560s Aceh

envoys were taking their pepper to the Ottoman court and pleading for military

assistance against the Portuguese. Military help was sent, but it was especially

the idea of a unified counter crusade in the name of Islam that was influential.

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

In Sumatra, the Peninsula, Maluku (the Spice Islands of eastern Indonesia),

Sulawesi and even Siam and Cambodia, the sharp opposition between Muslim

and Christian was at its peak in the following sixty years. We also see attempts at

the literal application of shaifa law, including the amputation of hands and feet

for theft, in several centres of South East Asia in this period.

The direct Muslim trade link to the Arab ports of the Red Sea was cut in the

first decades of the seventeenth century by more efficient Dutch and English

shipping around the Cape of Good Hope. Pilgrimage to, and study in, the holy

places became much more difficult. The antagonism between Muslim and Christian was also complicated by the ferocious competition between Dutch

and Portuguese, Protestant and Catholic. The great Islamic trading states such

as Aceh, Banten and Makassar were either conquered by the Dutch Company

in the seventeenth century or lost their most profitable trade to it. One might

see the period that followed in the late seventeenth and eighteenth centuries

as one of localisation and the deepening of roots, with much less evidence of

literalist applications of scriptural norms. The interplay between local and

exotic models, syncretism and literalism, compromise and reform, will be the

stuff of the chapters that follow.

#### Islam and Asian religions

The fact that Islamic dispersion in maritime Asia was often the work of traders

and Sufi scholars rather than armies and administrators was not the only respect

in which this Asian 'middle' period differed from its Middle Eastern analogue. In

that Middle Eastern and Mediterranean world Islam had largely taken shape in

interaction with Christianity and Judaism, sharing the scriptural emphasis and

doctrinal exclusiveness of the Abrahamic faiths. But from the eleventh century

its Asian expansion was largely in interaction with Asian spirituality, including

the widespread acceptance of the idea that the ultimate inner reality could have

many outer forms. Here the preoccupation of the Abrahamic monotheisms

with guarding and enforcing orthodoxy was a very minor strain. The first great

Islamic scholar to comment on the Indie world, Abu Rayhan al Birurii (973 1048), noted how radically it differed from Islamic (or Christian) civilisa

tions: 'On the whole there is very little disputing about theological topics among

themselves: at the utmost, they fight with words, but they will never stake their

soul or body or their property on religious controversy.' 2 The inherent plural

ism of Indie religious experience derived from this root, and made it seem

2 Alberuni's India, trans. E. Sachau; abridged edn, ed. A. T. Embree (New York, 1971), p. 19.

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

natural that different peoples would have different cults. A Thai king who presided over a particularly cosmopolitan seventeenth century space expressed

his surprise that King Louis XIV of France, in requesting him to become a Catholic Christian (following hard upon a Persian embassy urging him to become a ShTi Muslim), appeared to believe that his God required all his creatures to approach him in the same way. Since the Creator had made his

creatures so very different, should we not rather assume, he asked, that He takes

pleasure in being honoured by different rituals?

Religious architecture was one tangible area in which the influence of Asian

ideas of the sacred was influential throughout our period. Much of the Indie

tradition valued religious buildings as sacred sites rather than as places of

assembly for the faithful. Many of the earliest places of Muslim devotion in

Asia were also at holy tombs, or places of meditation and study, which had

older roots of sacredness, gradually Islamised by the practice of Sufi masters.

We naturally find the earliest Muslim buildings in China and in Java looking

very much like pre Islamic sacred sites, with pagoda like minarets and cool

courtyards, much as church architecture had influenced Islamic building in the

Mediterranean area. The very prominent role throughout Asia of saints, walls

and shaykhs, renowned for their meditation and consequent miraculous powers, predated the formal organisation of Sufi tarlqas in most areas. Their

tombs became centres of pilgrimage and meditation. As Muslim political empires weakened in the late seventeenth and eighteenth centuries, however,

the Sufi orders became an important alternative model of social organisation,

extending their reach throughout India, China and South East Asia, and frequently operating in areas ruled by Hindus, Buddhists, Confucians or Christians.

There is plenty of evidence of Muslim communities drawing sharp boun daries to protect themselves from the dangers they saw in the other religious

communities with which they coexisted in Asia. As subsequent generations of

scholars combined an Islamic with an indigenous high civilisation, however,

there were also remarkable works of synthesis, showing the truths of Islam to

be compatible with Confucian morality, on the one hand, or Indian and Javanese ideas of non duality, on the other.

In much of Asia this middle period is marked by great internal diversity, since non Muslim rulers whether Thai Buddhist, Malabari Hindu, Chinese Confucian or European port rulers had neither the legitimacy to impose uniformity on their Muslim subjects, nor any interest in doing so. Sunni and

Shi c a and various schools of law coexisted and contended over much of the

continent. In Malay speaking South East Asia, on the other hand, a remarkable

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

uniformity of Sunni Islam and Shaft 1! law prevailed by the end of our period.

One explanation of this may have to do with the prominence of these features

in the Hadramawt and the Hijaz, the two major sources of learning and legitimacy for South East Asia since the eighteenth century. Another may be

the prominence of rulers 'below the winds' in setting the pattern for Islamic

observance.

#### The Persian moment

Nizam al Mulk (d. 1092), chief minister for several decades to the early Saljuq

sultans Alp Arslan and Malik Shah, has already been referred to. He is an appropriate symbol for the beginnings of another critical development of the

period covered in this volume: Persianisation, in both administration and culture. The Saljuqs were canny enough to realise that although they might

have become the rulers of a substantial part of the central Islamic lands, and

while they might well possess awesome military superiority over any likely

rivals, they would not be well advised to try to run their empire as if it was

merely an extension of their steppe tribal dominion. They had lived for some

time on the borders of the dar al islam before entering it the time during which

they had themselves become Muslims. They knew something about Islamic

civilisation, agriculture and the life of cities. They knew enough, at any rate. to

appreciate that they needed expert help in running their new empire. That help

was available in the shape of the old Persian bureaucracy (of which Nizam al

Mulk was a representative if exceptional member), which consciously drew on

the administrative traditions of pre Islamic Iran, the 'Abbasid caliphate, the

Samanids and the Ghaznavids. There were, then, strong Islamic elements in

the tradition, but it was in essence a Persian tradition of government. It has been

argued for Iran at least, and not without justification, that the governmental

pattern established by the Saljuqs, or by the Saljuqs' Persian servants, was the

pattern that prevailed there, with changes in detail and terminology, till the

nineteenth century. Such traditions were transplanted into India, and there, too,

Persian became the language of government so ineradicably that even in the

nineteenth century it was still thought necessary to teach Persian to young

British recruits to the service of the East India Company.

Culturally, Persian influence was even more pronounced. In a celebrated exchange of letters at the beginning of the sixteenth century, Shah Isma'il I.

founder of Iran's great Safavid dynasty, wrote to the Ottoman sultan Selim I in

Turkish, but received the sultan's reply in Persian: even in Ottoman Istanbul, the

language of a cultured and educated gentleman was Persian, not Turkish let

13

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

alone Arabic. This is not to say that Arabic lost its prestige: as the language of the

Qur'an, of law and of theology, its position was unassailable. But for literature,

for poetry, for history, for civilised discourse generally, Persian became the

language of choice over a vast geographical range, enormously larger than

anything that might be considered to be Iran in a political or ethnic sense. This

was, perhaps, only beginning during the Saljuq period. The historian of that

epoch will still find that more of the sources are written in Arabic than in Persian.

The decisive shift, it would seem, occurred under the Mongols. Not a people

who were strikingly literate in any language, for them there was certainly no

reason to have any truck with Arabic, since for the first seventy years or so of

their rule in the dar al islam they were not themselves Muslims. Arabic had no

special status, whereas Persian was the language of the people they, like the

Saljuqs, employed to help them run their empire. They were not as quick as the

Saljuqs had been to appreciate the character and virtues of civilised life away

from the steppes. They had arrived in vastly greater numbers, with no educa

tional preparatory period on the borders. This may be part of the explanation for

the ferocity of the first Mongol invasions: they had not yet understood that

allowing agriculture and cities to continue in existence could be to their advant

age as the new owners. But they soon caught on, took large numbers of experienced Persian bureaucrats into their service, and facilitated the further

spread of Persian, which became something of a lingua franca throughout their

empire even in China.

This shift in a Persian direction throughout so great a proportion of the Islamic world has profound implications for how we see its overall history.

It is not so long since it was still thought self evident to depict Islamic history

as a pattern of rise (early Islam and the first expansion; the Umayyad and early 'Abbasid caliphates), decline (the later Abbasids, the coming of the Turks, the final blow to civilisation inflicted by the perfidious Mongols) and

revival (the beneficial effects of the impact of the West, from the beginning

of the nineteenth century). Any such pattern, which seems to underlie even

the first edition of this History, was definitively blown out of the water by Marshall Hodgson in his (regrettably posthumous) three volume survey The

Venture of Islam, published in 1974, a deservedly influential book which might

have had even greater repercussions had its author commanded an acces sible English style.

What Hodgson showed, among much else, was that the old rise and decline

story only made sense if the historian's gaze was firmly fixed on a kind of Baghdad Damascus Cairo triangle. That there was a decline after the early

Islamic centuries, in some sense, was undeniable, but it was an Arab and

14

Cambridge Histories Online © Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

Arabic, not a general Islamic, decline. The young Albert Hourani asked Philip

Hitti why his celebrated History of the Arabs of 1937 contained so little on the

period between the Ottoman conquest and the nineteenth century. 'There was

no Arab history then,' was the reply. 3 The centre of the Islamic world had

shifted out of the old Arab heartlands, and so likewise should the attention of the

historian. The centre shifted, in fact, to the Persian world. Hence the sixteenth

and seventeenth centuries may not have been periods of triumph in terms of

Arab culture and politics; but in the wider Islamic world, these two centuries

could easily be seen as the apogee, in which the Mr al islam was dominated by

three great and powerful empires, the Ottoman, the Safavid and the Mughal

all of them very much part of the Persian cultural area. This did not imply peace

and unity: far from it. The Ottomans were bastions of Sunni Islam, at constant

loggerheads with the Safavids (though not solely for religious reasons), until

some way into the seventeenth century. In Iran, Shah Isma'il and his successors

had set up Twelver Shi'ism as the approved indeed, compulsory form of Islam, in contradistinction and opposition to their Sunni neighbours, Ottomans

to the west and Uzbeks to the east. The religious situation in Mughal India was

more complex, but there too the approved variety of Islam was Sunnism; and

there were other causes of Mughal Safavid friction, notably the line of demar

cation between the two empires in what is now Afghanistan.

By now, it would seem, most Muslims, not just lawyers and theologians, could tell the difference between Sunni and Shi'i Islam at a glance. This had not

always necessarily been the case. Many Sunnis in the fifteenth century had been

sufficiency fervent in their devotion to 'Ali and the Shi'ite imams to cause modern historians considerable confusion. It was not helpful, for example, that

the Qara Qoyunlu sultan Jahanshah should have minted coins which were Sunni

on one side and no less clearly Shi c i on the other. The disappearance of the

caliphate after the Mongols killed the last 'Abbasid of Baghdad in 1258 may have

added to the prevailing religious turmoil. The tame 'Abbasid caliphate main

tained by the Mamluk regime in Cairo received little acknowledgement outside

its own domains: most Sunni Muslims found that they had to do without whatever stability and authority the caliphate, however politically weak it may

have become, had still provided. Whether for this or for other reasons, the

allegiance of enormous numbers of Muslims came in this period to reside not

with the official machinery of the faith but in the increasingly organised and

regularised Sufi brotherhoods: and there it has remained to this day. Sufism was,

3 A. Hourani, 'How should we write the history of the Middle East?', International journal of

15

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

and is, much more a SunnI than a ShTi phenomenon, which may be connected

with the fact that the Twelver ShTism of Iran does have a kind of hierarchy, and it

is a hierarchy which, as much in the twenty first century as in the eighteenth, is

by no means favourably disposed towards Sufism.

What was different after 1500?

As we have seen, the dominant powers in the Muslim world after 1500 were

the Ottoman, Safavid and Mughal empires. These states were distinguished

not only by their size, but also by their longevity. Since the decline in the central authority of the 'Abbasid caliphate, ruling dynasties, even formidable

ones like the Saljuqs, the Mongols and the Timurids, rarely lasted for much

more than a century, and often less. By 1500, the Ottoman dynasty, however,

was already two centuries old (though hardly a major power for some time

after its still mysterious appearance around 1300); and it was to last for a further 400 years. The other two great empires did not enjoy comparable longevity. Both were founded in the early sixteenth century, and they may be

said to have survived as holders of effective power for a little over two centuries. This did not remotely approach the Ottoman record, but it was still twice what had been the norm before 1500.

What is the explanation for this? The most obvious point is that they were 'gunpowder empires'. The argument is that, with the increasing sophistication

and expense of gunpowder weaponry, only large states could afford to keep

up to date, which endowed such states with a decisive political and military

advantage. By contrast, in the era of the dominance of the composite bow,

which every nomad cavalryman possessed, any ambitious chieftain could attempt to put together a force which, when it reached a sufficient size, could hope to be the equal of any other. Hence in part, perhaps, the comparatively ephemeral nature of many pre 1500 states.

Whether or not a 'modern' army had such an inherent advantage depended

to some extent on the type of warfare being waged. At Chaldiran in 1514, the

Ottoman victory over the Safavids seems to a large extent to have been due to

firearms; but what really counted was that the Ottoman Janissary musketeers

were sheltered behind a wagon laager, and the cannons were chained together. This all provided an effective obstacle to the Safavid cavalry charge.

But the Safavids learned their lesson. While they did use firearms to a degree,

they kept clear of wagon laagers and relied on speed and manoeuvrability,

which the Ottomans had inevitably sacrificed in their increasing reliance on gunpowder technology. Safavid Iran, it has been argued, 'succeeded in

16

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

Introduction: Islam in a plural Asia

remaining independent because it did not allow itself to get drawn into the

kind of war that only the Ottomans could win. Its reliance on cavalry instead

of firearms was the secret to its survival.' 4

Still, there can be little doubt that the efficient use of gunpowder technol

ogy did, ultimately, change things decisively. There were to be no more steppe empires after Tamerlane's, and the vast area that had produced the

Turks and the Mongols was eventually divided between the sedentary empires of Russia and China. The most spectacularly successful post Tamerlane conqueror in the region was Nadir Shah (d. 1747): but his ephem

eral conquests were the achievement of a thoroughly modern and up to date

army, not a force made up of steppe cavalry archers.

Many other factors religious, political, administrative, economic, cul tural distinguished the three great empires from their predecessors. 5 For

example, Bernard Lewis argued that the introduction into the Muslim world

by the Turks and Mongols of the steppe notion of family sovereignty and 'a workable principle of dynastic succession' made long term political stability

much easier to achieve. Certainly much had changed, and in 1500 Muslim

imperial 'decline' was a very distant prospect.

The period covered in this volume is one of great creativity and vitality in the Islamic world. It also had its share of disaster and suffering: whatever may

be said about the positive impact of Mongol rule, for example and there is

now a great deal that can and should be said, not least with respect to the

unprecedented opportunities for advancement with which Mongol rule across

Asia provided Muslims there is very little that can be done to rehabilitate the

human rights records of Chinggis Khan or Tamerlane. Yet even so, it is a mistake to portray the centuries from the eleventh to the eighteenth as centuries of steady and unremitting decline, as has too often been the tendency of historians. Rather, we should see the period as one in which Islam became truly a world religion, dressed in the civilisational colours of

Uzbeks, Uighurs, Bengalis, Gujaratis, Tamils, Malays, Javanese and Chinese.

In its breadth and depth in the eighteenth century it bore little resemblance to

the Arabic and Greek world of the eleventh. In looking to the classic or formative age of the Islamic experience of the Asians who dominate contem

porary Islam, we must look to this fascinating era of plurality and expansion.

4 Kenneth Chase, Firearms: A global history to lyoo (Cambridge, 2003), p. 127.

5 These elements are illuminatingly discussed in John Darwin, After Tamerlane: The global history of empire since 140s (New York, 2008), pp. 73 87.

6 'The Mongols, the Turks and the Muslim polity', in B. Lewis, Islam in history: Ideas, people and events in the Middle East (Chicago and La Salle, 1993), p. 205.

17

Cambridge Histories Online © Cambridge University Press, 201 1

PART I

THE IMPACT OF THE STEPPE PEOPLES

Cambridge Histories Online © Cambridge University Press, 201 1

:i

The steppe peoples in the Islamic world

**EDMUND BOSWORTH** 

Ι

Until the opening of the eleventh century CE, the eastern frontiers of the

Islamic world had been fairly stable. The frontier region between what is now

eastern Afghanistan and north western India, essentially the Indus Valley, still

remained fluid, and was now to form the springboard for Muslim expansion

further into India under the Ghaznavids and Ghurids. To the north east, the

ancient Iranian kingdom of Khwarazm on the lower Oxus and, above all, the

equally Iranian Samanid emirate in Khurasan and Transoxania, which flour

ished for almost two centuries, constituted bastions of Islamic faith and society

against the peoples of the Eurasian steppes. See Map i for this chapter.

However, the years after c. iooo CE witnessed for this region an irruption of

peoples from the steppe and forest lands beyond these Islamic outposts of

Khwarazm and Transoxania, first of Turks and then, in the second half of the

twelfth century, of Mongols and Turco Mongols in the shape of the Qara Khitay and then, after 12.17, of Chinggis Khan's hordes. New ethnic elements

were thus injected into the eastern Islamic world, hitherto dominated ethni

cally mainly by Iranians, and politically and culturally by a symbiosis of the

Persian and Arabic literary and governmental traditions. These incursions

from Inner Asia had effects on the older Islamic lands in the case of the Mongol invasions, cataclysmic ones but in the longer term, the perdurable,

absorptive powers of Islamic religion and culture exercised their effects on the

incomers.

Many of the Turks were recent converts to Islam when they arrived on the

north eastern margins of the Islamic world, and the pagan elements among

them gradually followed suit. The Mongol Western Liao or Khitan, who arrived in Transoxania and eastern Turkistan in the middle decades of the

twelfth century and became known to the Muslims as the Qara Khitay, retained their own animist and Buddhist beliefs but were content to leave

## The New Cambridge History of Islam

their Muslim vassal rulers and subjects with the free and unimpeded exercise

of their own cult (see below, p. 70). The Mongols of Chinggis and his family

were initially hostile, at times strongly so, towards their Muslim subjects, but

by c. 1300 the Mongol Ilkhanids of Persia had become Muslim and the process

was repeated, rather more slowly, among the Chaghadayids of western and

eastern Turkistan and the Golden Horde of the western Inner Asian steppes in

the course of the fourteenth century.

In the religio cultural sphere, Islamic society probably absorbed without difficulty a certain amount of extraneous influences; and certain syncretistic,

even heterodox, elements have been discerned in the activities of certain Sufi

orders in Transoxania and the adjacent steppelands, and in those of the dervish

orders which came to flourish in the lands of the Rum Saljuqs and those of the

tribal chiefs, the beyliks, in Anatolia (see below, pp. 54 5). The Perso Islamic

governmental tradition, in which older Iranian ideas of kingship had been grafted on to Islamic concepts of authority, elevated the sovereign to a high

position above his subjects, with his power buttressed by the support of a professional army, often a standing one and multiethnic in composition. This

became speedily attractive to the Turkish and Mongol princes who installed

themselves south of the Oxus river, if not to their tribal followers. Over the

course of time, such rulers, above all the Turkish ones, began to assume a role

of near universal providers of military leaders and princes for virtually all the

central and eastern Islamic lands, so that Turks could eventually be found

ruling from Algiers through Syria and Yemen to Bengal: a phenomenon which

waned only in the twentieth century with the bloodless disappearance of the

Qajars in Persia in 1925 and the line of Muhammad All in Egypt in 1953.

Turkish rulers thus fitted neatly into existing political and administrative structures, skilfully moulded by the Arab and Persian bureaucrats who had

been responsible for the day to day running of the lands to which these Turks

had recently fallen heir and whose services the Turks now eagerly sought.

Only in parts of Central Asia and eastern Turkistan did the older tribal ways of

life and tradition persist, explicable by the fact that the Turkish Oarakhanids

and the Qara Khitay, who largely dominated these regions in the eleventh and

twelfth centuries, remained resistant to the more authoritarian and hierarch

ical trends that came to dominate the lands south of the Oxus. The domination

after c. 1040 of the Saljuq Turks, the line of Great Saljuqs in Persia and Iraq

(with minor branches in regions like Anatolia, Syria and Kirman), of their epigoni the atabegs, and then, after the Mongol interlude, of the various Turkmen lines controlling lands stretching from Anatolia to Afghanistan, had lasting effects, over the centuries, in the domains of demography,

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

language and land utilisation, though these were not immediately felt (see below).

Within the lands which came to be dominated by the Saljuqs (i.e. the northern tier running from western Afghanistan through Khurasan and north western Persia to al Jazira, Syria, Armenia and Anatolia), the incoming

Turkmens, above all composed of the various tribes of the Oghuz/Ghuzz, found that upland regions like northern Khurasan, Azerbaijan, Arran and the

regions of the Zagros chain extending through Fars towards the Persian Gulf

shores, furnished especially attractive pasture lands for their herds of sheep

and goats. These movements, and the resultant patterns of territorial occupa

tion, set in train changes in land utilisation, demography and linguistic usage

which were eventually wide ranging. Lambton has noted that the initial effects of the influx of nomads were probably not extensive during the early

Saljuq period, since their numbers were limited and their effects on the economy of Khurasan, for instance, no worse than those of the Ghaznavid armies which had been trampling across it, to the distress of the local population. Given that the pastoralists now injected into the economies and

industries of the towns dairy products, and wool and hides, their effects may

even have been beneficial. 1 Bregel has attempted to estimate, from the sparse

figures given in the sources, the numbers of Turkmens entering the Persian

lands under the Saljuqs, and has agreed that these were comparatively modest. 2 It was most likely in post Saljuq times, those of the Mongols and

of the Timurids and the Turkmen dynasties which succeeded them, that the

momentum of immigration into the Persian lands increased, with fresh waves

of Turks involving continuing bands of Oghuz but also other tribal groups like

the Qipchaqs. The whole process had in fact already been set in train, for western Persia in particular, during the preceding Buyid times, by the system

of iqta L s, grants of land by rulers for the support of their troops and civilian

officials, which were theoretically revocable by the monarch. At first, these

grants were made by the central administration from a position of strength, a

means of reducing administrative expenses; but in practice, they could often

not be reclaimed from over mighty  $\colongraph{\circ} 0$  holders, the muqta's, and thus became

i Ef 'flat' (A. K. S. Lambton), vol. Ill, pp. 1098 9, and her chapter 'The iqta' system and the

Seljuqs', in A. K. S. Lambton, Landlord and peasant in Persia: A study of land tenure and land

revenue administration (London, 1953), pp. 53 76; and Lambton, Aspects of Saljuq Ghuzz

setdements in Persia', in D. S. Richards (ed.), Islamic civilisation 950 1150 (Oxford, 1973), pp. 105 25.

2. Yuri Bregel, Turko Mongol influences in Central Asia', in Robert L. Canfield (ed.),

Turko Persia in historical perspective (Cambridge, 1991), p. 58.

23

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

virtually hereditary. 3 All these trends probably amounted to a long term process of pastoralisation, although it is not clear whether existing agricultural

lands, especially those in areas where dry farming was possible, were trans

formed into grassland or whether the nomads took over for their flocks lands

which were marginal or until then underused, in which case the nomads were

actually contributing to the economic development of these regions.

Whatever may have been the case here, in such areas as Arran in eastern Transcaucasia; Azerbaijan; parts of Jibal or north western Persia such as the

region of Khalajistan south west of Tehran and west of Sava; and the southern

Zagros mountain region, later occupied by Turkmen tribes like the Qashqal

and the three Turkish tribes within the ethnically mixed Khamsa confeder ation, the concentration of Turkish elements, not least including the ruling

elite there, was such that forms of the Turkish language took over in these

areas and have largely prevailed there until the present day. In south western

Persia, a limited form of the nomadic way of life, or at least transhumance,

persisted for the Qashqal and other Turkish groups well into the twentieth century.

#### Π

There had never been a completely hard and fast boundary between the Turkish peoples of Inner Asia on the one hand, and the lands of ancient Iranian civilisation such as Khwarazm, Sogdia and Farghana on the other. The

local princes of Sogdia had in the early second /eighth century allied with Turkish elements under their chiefs, the yabghus (jabbuyas of the Arabic sources), in the upper Oxus lands in order to oppose the advancing Arabs. 4

A century later, the ruler of the eastern provinces of the 'Abbasid caliphate, al

Ma'mun, faced with a coming struggle for power with his brother, the caliph

alAmm (r. 193 8/809 13), had to conciliate various potentates on the far eastern fringes of his governorate, described as the Yabghu, the Khaqan, the

ruler of Tibet and the king of Kabul, some of whom at least must have been

Among a large literature on the iqtd' at this time, see CI. Cahen, 'L'evolution de l'iqta' du

IX e au XIII e siecle', Annates: Economies, Societes, Civilisations, 8 (1953), pp. 25 52; A. K. S.

Lambton, 'Reflections on the iqtd'', in G. Makdisi (ed.), Arabic and Islamic studies in honor

of Hamilton A. R. Gibb (Leiden, 1965), pp. 358 76; Ef 'Ikta'' (Cahen); and a useful summary

in D. O. Morgan, Medieval Persia 1040 1797 (London, 1988), pp. 37 40.

H. A. R. Gibb, The Arab conquests in Central Asia (London, 1923), pp. 8 9; R. Grousset, The

empire of the steppes: A history of Central Asia (New Brunswick, NJ, 1970), pp. 116 20; EIr

'Jabbuya. ii. In Islamic sources' (C. E. Bosworth).

# Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

themselves Turks or rulers over Turkish peoples. 5 From the caliphate of al

Ma'mun (r. 198 218/813 33) and that of his brother and successor al Mu'tasim

(r. 218 27/833 42), Turks from the steppes formed an increasing element of

slave soldiers (ghilman, matnalik) at the side of the remnants of the old Arab

free muqatila and the Khurasanian guards of the first Abbasids. The Samanid

emirate grew rich on the slave trade from the steppes, with markets at places

like Isfijab, Nakhshab and Bukhara, and the amirs exacted transit dues at the

Oxus crossings for slaves forwarded to the caliphal heartland for military or

domestic purposes. 7 The Arab geographers and compilers of 'road books'

from the later third /ninth century onwards now began to differentiate between various tribes of the Turks; Ibn Khurradadhbih (wrote in the later

third/ninth century) mentions Kimek, Tiirgesh, Qarluq, Toghuz Oghuz, Kirghiz, Qipchaq and Khazars. By c. 1050, the detailed account of Turkish

peoples given by the Ghaznavid author Gardizi in his history shows that Muslim knowledge of these peoples of the deep steppes, and even of Finno

Ugrian and Mongol peoples of the forest zone to their north, was quite extensive.

Hence the coming of the Qarakhanids into the settled lands of Samanid Transoxania at the end of the tenth century CE may not have appeared to local

Muslims of say Samarqand or Bukhara as a cataclysmic event, an irruption of

savage barbarians from beyond the imagined Inner Asian defensive wall against the Qur'anic Gog and Magog. The precise ethnic origins of the Qarakhanids (a name coined, together with that of 'Ilek/Ilig Khans', by Western scholars in the nineteenth century; the contemporary Islamic sources

simply call them 'the Khans', al Khaqaniyya, Khaniyan or the Al i Afrasiyab,

with a reference to the ruler of Turan, the foe of the Iranians, in Firdawsi's

5 alTabari, Ta'nkh alRusul wa 'Imuluk, ed. M.J. de Goeje et al., 15 vols. (Leiden,

1879 1901), vol. Ill, pp. 815 16, Eng. trans. M. Fishbein, The History of al Tahari, vol.

XXXI: The war hetween brothers (Albany, 1992), pp. 71 2. The question whether there

was any substantial infiltration of Turks into the borderlands of what became the

Samanid emirate during the first three or four centuries of Islam has been much

discussed but without any conclusive results; cf Bregel, 'Turko Mongol influences',

pp. 54 8.

6 Among an extensive literature on this very important trend of medieval Islamic military

history, see the works of David Ayalon, Patricia Crone, Daniel Pipes, etc., surveyed in

Matthew S. Gordon, The breaking of a thousand swords: A history of the Turkish military of

Samarra (AH zoo 275/815 889 CE) (Albany, 2001), pp. 6 8 and passim; also Ef. 'Ghulam.

i. The caliphate, ii. Persia' (D. Sourdel and C. E. Bosworth).

7 See the geographers Ibn Hawqal and al MaqdisI, cited in C. E. Bosworth, The Ghaznavids:

Their empire in Afghanistan and eastern Iran, 904 1040 (Edinburgh, 1963), pp. 208 9.

8 See the information on specific tribes in Peter B. Golden, An introduction to the history of tfte Turkic peoples (Wiesbaden, 1992), pp. 1898".

25

## The New Cambridge History of Islam

Shah noma) and their early history are shrouded in mystery, and various suggestions have been put forward. We can put aside the old view, recently

revived by certain modern Chinese historians, that they stemmed from the

Uighurs, who were originally located in what is now Mongolia and after 840 in

eastern Turkistan. Much more feasible is the hypothesis of Omeljan Pritsak,

that the Qarakhanid ruling house came from the tribal group of the Qarlug,

which included associated tribes like the Chigil, Yaghma, Arghu and Tukhsi; it

seems likely that, in the later eighth century, the Qarluq, under their chief who

had the title of Yabghu, were forced westwards by the Uighurs into the Semirechye or Yeti Su, 'the land of the seven rivers' in the Chu and Hi river

valleys Issik Kol lake region (what is now the northern part of the Kirghiz Republic and the south easternmost part of the Kazakh Republic). They thus

acquired neighbours on their west in the shape of another great tribal group

which was to have a great future in the eastern and central lands of Islam, the

Oghuz (in Arabic sources, Ghuzz). By the mid ninth century the Qarluq lands

stretched from the territory of the Oghuz in the west to the confines of Tibet

in the east, and from the lands of the Kimek on the Irtysh river in the north to

the northern frontiers of the Samanid emirate. 9

It is the transition from this Qarluq grouping to that of the Qarakhanids of the

later tenth century that is obscure. But on the evidence of Islamic sources, it

does seem that the Qarluq chiefs had assumed the exalted title of qaghan/khan

and by c. 950 had become Muslim, an event crystallised in what is perhaps a

semi legendary tale of the conversion of a Qarluq chief who later became supreme qaghan/khan of his people, Satuq Bughra Khan, who assumed on

his conversion the Muslim name of 'Abd al Karim. 10 The Islamisation of the

western part at least of the Qarluq seems to have followed, although this was

probably a slow and piecemeal process, one probably reflected in the story

given in the sources (but with what must have been gross exaggeration) that in

9 Omeljan Pritsak, "Von den Karluk zu den Karachaniden', Zeitschrif der Deutschen

Morgenldndischen Gesellschaji, 101 (1951), pp. 270 87; Pritsak, 'Die Karachaniden', Der

Islam, 31 (1953), pp. 21 2; Peter B. Golden, 'The Karakhanids and early Islam', in Denis

Sinor (ed.), Tfie Cambridge history of early Inner Asia (Cambridge, 1990), pp. 354 7; Golden,

An introduction, pp. 196, 214 15.

10 A prime source here is the Mongol period writer on the 'ulamS and scholars of Central

Asia, Jamal Qarshi (fl. later seventh/ thirteenth century), used by F. Grenard, 'La

legende de Satok Boghra Khan et l'histoire', Journal Asiatique, ser. 9, 14 (1900), pp. 5

79; W. Barthold, Zwolf Vorlesungen iiber die Geschiehte der Tiirken Mittelasiens (Berlin,

1935), PP- 73 8; Pritsak, 'Von den Karluk zu den Karachaniden', pp. 291 3; Jiirgen Paul,

'Nouvelles pistes pour les etudes karakhanides', in Vincent Fourniau (ed.), Etudes

karakhanides, Cahiers d'Asie centrale 9 (Tashkent and Aix en Provence, 2001), pp. 19 22.

26

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

349/960, about 200,000 tents of Turkish tribesmen became Muslim. 11 Over the

ensuing decades, the Qarluq, despite their status as new Muslims, made

depredations into the northern borders of the Samanid emirate, now increas

ingly enfeebled by dynastic quarrels, financial crises and the indiscipline and

rebelliousness of the army commanders.

In 382/992 Bughra Khan Harun or Hasan, the grandson of Satuq Bughra Khan, temporarily occupied the Samanid capital of Bukhara, without the sources mentioning any serious show of resistance by the populace, no doubt by now war weary and willing to give a trial to anyone who promised

a degree of peace and order. 12 The definitive takeover of Bukhara came a few

years later, in 389/999, when another member of the Qarakhanid family, the

Ilig (Tkish. ellig/elig 'holder of a territory', i.e. one subordinate to the supreme

Khan) Nasr b. 'All of Ozkend in the Farghana valley marched into it unop posed. A last member of the Samanid family was to fight on bravely for a few

more years, but the political map of the north eastern Iranian lands was now

changed decisively. Nasr divided up the Samanid dominions with one of the

dynasty's former Turkish commanders, Mahmud, whose father Sebiiktegin

had established himself some twenty years previously at Ghazna in what is

now eastern Afghanistan, laying the foundation of what was to become under

Mahmud (r. 388 421/998 1030) the mighty Ghaznavid empire. 13 The Oxus

became in effect the boundary between the two new powers, although at the

outset the Qarakhanids coveted the rich province of Khurasan, while Mahmud was later, in 408/1017, to add the ancient kingdom of Khwarazm

on the lower Oxus to his extensive dominions. 14 Both these empires, directed

by Turks, were to persist, with varying fortunes, for some two centuries, but

evolved into very different types of state. The Ghaznavid sultans developed to

a high degree the Perso Islamic ideal of a despotic monarch elevated far above

his subjects, with a sharp division in society of the ruler and his supporting military and bureaucratic apparatus over against a docile, tax paying

11 Miskawayh, Tajdrib al umam, ed. and trans. H. F. Amedroz and D. S. Margoliouth, The

eclipse of the 'Abhasid caliphate, 7 vols. (Oxford, 1920 1), vol. II, p. 181, trans, vol. V, p. 196;

Ibn al Athir, al Kdmilfi 'I ta'rikh, 13 vols. (Beirut, 1385 7/1965 7), vol. VIII, p. 532.

12 For the attitude of the Bukharan people and the religious leaders at this time, see Hilal

al Sabi', cited in W. Barthold, Turkestan down to the Mongol invasion (London, 1928),

pp. 258 9, 267; Richard N. Frye, Bukhara, the medieval achievement, 2nd edn. (Costa Mesa,

CA, 1997), pp. 1478.

13 Barthold, Turkestan, pp. 257 67; Muhammad Nazim, The life and times of Sultan Mahmud

of Ghazna (Cambridge, 1931), pp. 30 2, 42 8; Frye, ch. 'The Samanids', in R. N. Frye (ed.),

The Cambridge history of Iran, vol. IV: Tfte period from the Arab invasion to the Saljugs

(Cambridge, 1975), pp. 157 60; Frye, Bukhara, pp. 142 9.

14 Barthold, Turkestan, pp. 275 9; Nazim, Sultan Mahmud, pp. 56 60.

27

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

populace. 15 Such a trend towards autocracy was to become the norm in much

of the Persian and Indo Muslim lands south of the Oxus over the next centuries, a process from which the Saljuq tribal leaders were not, as we shall see below, to be immune.

For the Qarakhanid khans in Transoxania, the Semirechye and the western

part of eastern Turkistan as far as the Tarim basin, development was to be

otherwise. The khans never attempted to build up the lands they controlled

into a unitary state of any kind, far less into a hierarchical state directed by a

Turkish military elite, as did their Ghaznavid rivals. Rather, the Qarakhanids

remained a tribal confederation, with various members of the family, often at

odds with each other, possessing winter seats in established urban centres like

Balasaghun, Ozkend, Bukhara and Kashghar. The assemblage of lands that

they came to control was regarded by the Qarakhanids as a family possession,

rather than that of a single, individual ruler. There was a complex network of

subordinate princes and chiefs under the great khan or khans, for after c. 1040

the united khanate split into a western one, controlling Sogdia with its cities of

Bukhara and Samarqand, and an eastern one, controlling the Semirechye and

Eastern Turkistan with two capitals, Balasaghun (until the entry of the Oara

Khitay into Sogdia in 536/1141) and Kashghar, with Kashghar latterly the sole

capital. For a few decades, which cannot be closely delimited but which extended up to c. 609/1212L and the expansionism of the Khwarazm Shahs,

there was a further line of khans in the Farghana valley. Throughout Qarakhanid history, family members often held appanages, some quite limited in extent. Turkish names (many of animals or birds, perhaps reflecting

an original totemistic significance of these) and titles (held side by side with

Islamic ones) usually changed as people moved up the hierarchy of ruling power, creating great problems for anyone trying to construct a genealogical

stemma of the dynasty or lists of individual rulers and their regnal dates. Given

the very limited range of Islamic historical and literary sources, the legends on

the numerous coin emissions of the Qarakhanids are of prime importance, and

recent advances in our knowledge here have mainly stemmed from this type

of evidence, adduced mainly by such Russian scholars as E. A. Davidovich,

B. D. Kochnev and M. Fedorov, utilising coin hoards that have come on the

market since the break up of the Soviet Union in 1991. 1

15 Barthold, Turkestan, pp. 291 2; Bosworth, The Ghaznavids, pp. 48 97; Frye, Bukhara, pp. 156 7.

16 On the territorial extent of the Qarakhanid lands, see B. D. Kochnev, 'Les frontieres du

royaume des Karakhanides', in Fourniau (ed.), Etudes karakhanides, pp. 41 8. On the

28

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

Within the towns and cities controlled by the Qarakhanids, we know of a certain amount of court life and of the existence of cultural circles, out of which arose significant monuments of early Turkish Islamic literature. The

didactic poem, the Qutadgu bilig, 'Knowledge that brings happiness', was written by Yusuf Khass Hajib, an author who stemmed from Balasaghun but

who in 462/1069L completed his work at Kashghar for the khan of the eastern branch there; and although Mahmud Kashghari compiled his great

dictionary of the Turkish language at Baghdad (begun in 464/1072), he came

from the Semirechye and had connections with the Qarakhanid ruling house. 17 The khans were clearly not gross barbarians. One of the rulers of

the western branch, Shams al Mulk Nasr b. Ibrahim (d. 472/1080), built extensively at his capital Bukhara, reconstructing the great mosque there after it had been burnt down and building a palace for his line outside the

citadel of Bukhara which he called Shamsabad and which had gardens and an

enclosed parkland (quruq) for game and wild beasts. His brother Khidr Khan

(r. 472 7479/1080 ?io86) added to the complex of Shamsabad; the latter's son

Ahmad (r. 7479 88/?io86 95) built a new palace (sardy) at Juybar with elaborate gardens and a water supply for them, which a continuator of Narshakhfs local history of Bukhara says was the centre of government at

Bukhara for thirty years; and Arslan Khan Muhammad b. Sulayman (r. 495 524/1102 30) had new palaces and baths constructed and built a new great mosque. 18

Nevertheless, it seems that the Qarakhanids spent much of their time outside these urban centres, remaining in close touch with their tribal followers and aiming to stay attuned to their needs and aspirations, hence

nomadising with them during the spring and summer months. Such contact

was a necessity for them, since they apparently chose not to employ a professional army built up round a military slave nucleus but to utilise their

fellow tribesmen when military necessity arose. A corollary of not having an

complexity of Qarakhanid onomastics and titulature, see Pritsak, 'Die Karachaniden',

pp. 23 4. The present rapid evolution of our knowledge of their titulature and geneal

ogy means that the section on the dynasty in C. E. Bosworth, The New Islamic dynasties:

A chronological and genealogical manual (Edinburgh, 1996), pp. 181 4 no. 90, already needs

correcting and updating; see Kochnev, 'La chronologie et la genealogie des

Karakhanides du point de vue de la numismatique', in Fourniau (ed.), Etudes karakha nides, pp. 49 75.

17 See Ef~. 'Al Kashghari, Mahmud b. al Husayn b. Muhammad' (G. Hazai), 'Kutadghu

bilig' (A.J. E. Bodroligeti) and 'Yusuf Khass Hadjib' (R. Dankoff).

18 Narshakhi, Tdrikh i Bukhara, ed. Mudarris Ridawi (Tehran, n.d. [1939]), pp. 35 6, 60 1,

Eng. trans. R. N. Frye, Tfie history of Bukhara (Cambridge, MA., 1954), pp. 29 30, 50 2; cf.

Barthold, Turkestan, pp. 100, 103, 319 20.

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

expensive standing army was that the expenses of running the state were low.

Life in the urban centres went on little changed from Samanid times, with the

religious classes retaining their power, so that influential hereditary lines like

the sadrs or supreme Hanafi religious leaders in Bukhara of the Al i Burhan

could flourish under Qarakhanid and then Qara Khitay overall political

trol during the sixth/twelfth and early seventh/thirteenth centuries. 19 The

local Iranian landed classses, the dihqdns, probably enjoyed a resurgence of

power in Transoxania under the light yoke of the Qarakhanids. Narshakhi's

continuator says that taxes were everywhere lightened when the Turks supplanted the Samanids; the fragmented authority that the Qarakhanids were content to exercise now reversed the trends under the Samanids towards

state centralisation. 20

When they first came into the Islamic lands, the number of Qarluq and other tribesmen in the Qarakhanids' following was probably not large, but

elements, such as the Qipchaq and Qanghh, who had moved into the west ern Inner Asian steppes when first the Qarluq and then the Saljuqs had moved southwards into the Islamic lands, were gradually attracted into the

Qarakhanid lands. The influx of Qipchaq certainly accelerated under the Anushteginid Khwarazm Shahs (see below, p. 59), who recruited them extensively for their armies. In the absence of specific information, we can

only assume that many of these newcomers to the major sedentary regions

of Central Asia, that is, Khwarazm, Transoxania and Farghana, remained

nomadic in lifestyle, but some process of sedentarisation must gradually have taken place, contributing to an ethnic and linguistic turcisisation process in what had been originally the outer Iranian lands, I'Iran exterieur

(the process in eastern Turkistan must have begun much earlier, in the period of Uighur domination there). 21 Persian was to retain its prestige as the

media for cultural, intellectual and religious life, as it has done in the Central

Asian cities almost till the present day, but the general population became

more and more ethnically mixed, a trend accelerated by the great Turco Mongol population movements of the thirteenth century onwards. Turkish

ethnicity and language thus became preponderant; the indigenous Middle

Iranian language of Khwarazm died out completely by the end of the four teenth century, and Sogdian and other Iranian tongues of the eastern

19 See on these sudur, Pritsak, 'Al i Burhan,' Der Islam, 30 (1952), pp. 81 96; EIr Al e Borhan' (C. E. Bosworth).

20 Tdnkh i Bukhara, p. 39 (with the text here corrected by Frye), trans. Frye, p. 33 and n.

21 Bregel, 'Turko Mongol influences', pp. 56, 59 60.

30

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

Transoxanian fringes and Pamirs region survive today only as small, vestig ial remnants. 22

The history of the Qarakhanids' two centuries of existence is bound up, in the eyes of the Muslim historians, with their relations to neighbouring powers, and, especially, with those two that controlled the adjacent province

of Khurasan, the Ghaznavids and then the Saljuqs, and, in the sixth/eleventh

century, especially with the Anushteginid Khwarazm Shahs and the Qara Khitay, until their demise on the eve of the Mongol invasions. Accordingly,

the history of the western branch of the Qarakhanids is better known than that

of the eastern one. 23 The sources have little to say on the internal political and

social history of the khanates beyond adverting to internal dynastic disputes

and tensions between the khans and the religious classes. In the course of

these dissensions, an exemplar of Muslim rulers, Tamghach Khan Ibrahim

(on whom see below, p. 32), executed an imam, Abu'l Qasim Samarqandi; and

as result of family disputes and intrigues of the 'ulama' against him, Shams

al Mulk Nasr's nephew Ahmad b. Khidr, was eventually judicially murdered at

Samarqand in 488/1095. 24 The sources also record various military forays of

the khans northwards into the steppes, as far as the Manghishlaq peninsula to

the east of the Caspian Sea, in order to subdue recalcitrant tribesmen. Thus

Arslan Khan Muhammad b. Sulayman led regular campaigns into the steppes,

presumably against pagan Qipchaqs, and brought back numerous slave cap

tives, gaining the tide of Ghazt. 25

The Ghaznavids' relations with the western Qarakhanids were not in general harmonious. Despite the formal division of the Samanid territories

01389/999, the khans coveted the rich province of Khurasan, and in 396/1006

the Ilig Nasr's forces invaded and occupied NTshapur before retreating on

22 See EIr 'Chorasmia. iii. The Chorasmian language' (D. N. MacKenzie); Ef Suppl. 'Iran,

iii. Languages (d) Kh w arazmian, (e) Sogdian and Bactrian in the early Islamic period'

(MacKenzie and N. Sims Williams); J. R. Payne, 'Pamir languages', in R. Schmitt,

Compendium linguarum iranicarum (Wiesbaden, 1989), pp. 417 44.

23 There is as yet no detailed monograph on the Qarakhanids, and the materials for this hardly

exist. Hence one must have recourse to the relevant sections in Barthold, Turkestan,

pp. 268ff.,305 22,353 5,364 6; Pritsak, 'Die Karachaniden' (political and dynastic framework

only); Resat Gene, Karahank devlet teskildh (XL ytizyil) (Turk hdkimiyet anhyisi ve Karahanlilar

(Istanbul, 1981) (internal structure and administration of the khanates); Ef llek Khans or

Karakhanids' (C. E. Bosworth); Golden, 'The Karakhanids and early Islam', pp. 343 70;

E. A. Davidovich, 'The Karakhanids', in M. S. Asimov and C. E. Bosworth (eds.), History of

civilizations of Central Asia, vol. IV: The age of achievement: AD y;o to the end of the fifteenth

century, part 1: The historical, social and economic setting (Paris, 1998), pp. 119 43.

24 Mu'in al Fuqara' Ahmad b. Muhammad, Kitah i Mullazada, cited in Barthold, Turkestan,

p. 313, and Ibn al Athir, vol. X, pp. 243 4, cited in Turkistan, pp. 316 18.

25 Bundari, Zubdat al nusra, ed. M. T. Houtsma, in Recueil de textes relatifs a l'histoire des Seljoucides, vol. II (Leiden, 1889), p. 264.

31

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Sultan Mahmud's return from India in 398/1008. 26 It became Mahmud's

policy to encourage internal rivalries and dissidence within the Qarakhanid

house. His acquisition of Khwarazm in 407/1017, bringing to an end the line

of Ma'munid shahs there, enabled him to turn the flank of the khans. A particular thorn in the sultan's flesh was the ruler in Bukhara and

Samarqand, 'All b. Bughra Khan Harun or Hasan called 'Alitegin (d. 425/1034), hence Mahmud allied with his more distant brother and rival, Oadir

Khan Yusuf of Kashghar and Khotan, whom he met personally near Samarqand in 416/1025. The sultan sent a punitive expedition into Transoxania which drove out 'Alitegin to the outer steppelands, and he negotiated marriage alliances between his children and those of Qadir Khan

Yusuf Mahmud did not, however, envisage overthrowing 'Alitegin in order

to replace him by Qadir Khan Yusuf as ruler of a much stronger, unified Qarakhanid kingdom. 'Alitegin returned, and it was left to Mahmud's son and successor Mas'ud (r. 421 32/1030 41) to send an army into Sogdia in 423/

1032 against 'Alitegin and his Turkmen auxiliaries led by members of the Saljuq family. The fighting was indecisive, and the Ghaznavid army had to

extricate itself with some difficulty. After 'Alitegin's death, his sons carried

on the struggle against Mas'ud, allying with the sultan's rebellious governor

in Khwarazm Harun b. Altuntash. 27

Mas'ud managed to secure control, exercised through rulers who were his

vassals, of the principalities north of the upper Oxus of Chaghaniyan, Wakhsh

and Khuttal. However, the Ghaznavid position here came under pressure in

the late 420s /1030s from a new Qarakhanid foe, whom the Ghaznavid histor

ians Gardizi and Bayhaqi know by his totemistic name of Boritegin 'wolf prince', but who was to have a more glorious future as Tamghach Khan Ibrahim, son of the Ilig Nasr. Ibrahim crushed the sons of 'Alitegin and secured the western khanate for himself, ruling in Transoxania for nearly thirty years till 460/1068 or shortly afterwards as a ruler distinguished, as

several anecdotes in the collection of the later literary anthologist 'Awfi relate,

for his great piety and justice and for his solicitude regarding the welfare of his

subjects (see further, below, pp. 478). 1

26 'Utbi, al Kitdb al YamTni, Gardizi, Kitdb Zayn al akhbdr, Bayhaqi, Tdnkh i Mas'udi and Ibn

al Athir, cited in Barthold, Turkestan, pp. 272 3, and Nazim, Sultan Mahmud, pp. 48 52.

27 Gardizi, Bayhaqi and Ibn al Athir, cited in Barthold, Turkestdn, pp. 275 85, 294 8, and

Nazim, Sultan Mahmud, pp. 52 60; Golden, 'The Karakhanids', pp. 362 5.

28 Barthold, Turkestan, pp. 311 13, citing Ibn al Athir and Awfi's collection of anecdotes, the Jawdmi' al hikdydt.

32

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

After the victory of the Saljuqs over the Ghaznavid army at Dandanqan in 431/1040 (see below, p. 37), the external history of the western branch of the

Qarakhanids becomes to a considerable degree intertwined with that of the Saljuqs, this linkage of fortunes including various marriage links between the two great powers, and it is to this last dynasty that we must now turn.

III

The Saljuq family sprang from the Oghuz tribal group of the Turks. 29 This was

an anciently attested people of Inner Asia, mentioned by the Byzantine historians as the Ouzoi; in the Orkhon inscriptions as a component of the tribes making up the Eastern Turk empire, the Oghuz; and in Khazarian Hebrew as the Turk and in Rus' sources like the Nestor Chronicle as Torki.

The actual name derives from a Turkish root ogh/uq denoting a kinship group.

They seem to have been a loose assemblage of related clans rather than a unified grouping, with constituents identified by numerals, such as the Uch

Oghuz Three Tribal Groupings', Toquz Oghuz 'Nine Groupings', etc. After the

disintegration of the Eastern Turk empire in 744, the Oghuz moved south

westwards from Mongolia, so that by the tenth century they were the western

neighbours of the Qarluq group in the Eurasian steppelands. 30

A prime source on their status and nature in the early tenth century, just before they began to be affected by Islam, is the caliphal envoy Ahmad b. Fad

lan's account of his journey to the court of the recently Islamised king of Bulghar on the middle Volga in 309 10/921 2. He travelled through the lands

of the Oghuz on his journey from Khwarazm, passing to the north of the Caspian Sea and crossing rivers like the Emba and the Ural. The Oghuz whom

he met were at a low cultural level, animistic shamanists, living wretchedly

and wandering 'like straying wild asses'. He met certain of their leaders, whose titles recur later in the Islamic history of the Saljuqs. Their chief was

the Yabghu, bearer of the Orkhon Turkish title which had passed to the Oghuz

when the chiefs of the Qarluq assumed the grander title of qaghan/khan (a title which the Oghuz and then the Saljuqs were never to arrogate to

29 The spelling Saljuq represents what is, linguistically, a hybrid convention. Islamic

tradition (and Syriac authors borrowing from it) writes s.l.juq, with back vowels;

Kashghari's orthography in the Diwan lughdt al turk shows, however, that he read it

with front vowels, i.e. Seljiik. See Barthold, Zwolf Vorlesungen, p. 101; Golden, An

introduction, p. 217.

30 See Golden, An introduction, pp. 205ff.

V,

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

themselves), and his deputy the Kiilerkin or Kudherkin; the army leader, the sahib

aljaysh, held the title of Sii bashi or Sii begi; there was a subordinate commander

called the Lesser Yinal; and there was another commander, the Tarkhan. 31 It is

soon after this time that we first encounter the term Turkmen to denote the south

western Turks, whereas the Turks of the more easterly Qarluq group were

simply called Turks. In c. 370/980 the geographer alMaqdisi speaks of 'two

frontier posts against the Turkmdniyyun in the region of Isfljab on the middle

Syr Darya; these had become converts to Islam 'out of fear but had clearly not

given up their old predatory habits. 32 In the next century, Turkmen comes to be

used exclusively for the Oghuz followers of the Saljuqs, as by the Ghaznavid

historians Gardizi and Bayhaqi in their accounts of the overrunning of Khurasan

and then by the Saljuq vizier Nizam al Mulk in his 'mirror for princes', the Siyasat

noma (see on this, below, pp. 50 1) for the tribal followers of the Great Saljug

sultans who had remained nomads in Persia and the lands further west.

On the evidence of the Muslim historians and geographers, the Oghuz were

already in contact with the borders of the Islamic lands in Khwarazm and Transoxania, often as raiders but also as traders and, increasingly, as auxiliary

troops in the service of various of the Muslim powers there. They were clearly

a loose, disorganised grouping, with the component clans pursuing their own

interests, as indeed they continued to do when involved in the politics and

warfare of Muslim Transoxania in the first decades of the fifth /eleventh century and as individual members of the Saljuq family did when they overran

Ghaznavid Khurasan. The Yabghu had no supreme authority over all the Oghuz, and the Yabghu of the first years of the fifth/ eleventh century,

whose winter capital was at Jand on the lower Syr Darya, became completely

sidelined by the vigorous and pushing Saljugs (see below).

It is towards the middle of the tenth century that we learn something about

the origins of the Saljuq family, who belonged to the Qimq clan or sub group

(among some twenty two to twenty five of these named by Kashghari and other sources), and together with the Qayi and Bayandur apparently one of

the leading clans of the group. 33 A prime source for Saljuq beginnings is an

31 Rihla, ed. and Ger. trans. A. Z. V. Togan, Von Fadldns Keisebericht (Leipzig, 1939), text

pp. 15 17, trans, pp. 28 31, cf. Excursus 33 6; Fr. trans. Marius Canard, 'La relation du

voyage d'Ibn Fadlan chez les Bulgares de la Volga', Annales de VInstitut d'Etudes Orientates

de Id Faculte des Lettres d'Alger, 14 (1956), pp. 76 9.

32 Ahsan al taqdsim, ed. M.J. de Goeje (Leiden, 1906), p. 274; cf. Bosworth, The Ghaznavids, p. 214.

33 CI. Cahen, 'Les tribus turques d'Asie occidentale pendant la periode seljukide', Wiener

Zeitsehriftfiir die Kunde des Morgenlandes , 51 (1948 52), pp. 179 80; Golden, An introduction, pp. 207 9.

34

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

anonymous Malik natna (so called in imitation of the Shah namaY), probably

written for the prince Alp Arslan b. Chaghn Beg just after 451/1059, now lost

but known from extracts in later historians such as Sadr al Dm al Husayni, Ibn

al Athir, Barhebraeus and Mirkhwand. The ancestor of the family, Dugag,

known as Temiir Yaligh 'Iron bow' (bows and arrows being symbols of power

among the Oghuz) from his courage and strength, and his son Saljuq were

both in the service of the Oghuz Yabghu, with the latter holding the office of

Sii bashi, but relations became strained, with the ambitious Saljuq and his

family challenging the Yabghu's authority. 34

According to al Husayni, Duqaq had opposed the Yabghu's plans to raid the

Islamic lands, but this is clearly an attempt to push back in time the family's

adoption of Islam and show them as motivated by the true light of faith. 35 It

was more likely towards 382/992 that the family became Muslim, having moved from the inner steppes to Jand, whither they had expelled the Yabghu's

representative. Saljuq's sons are found with Old Testament names like Mika'il, Israel, Musa, etc., possibly the results of earlier contacts back in the

steppes with Khazar Judaism or with Nestorian or Melkite Christianity. The

hostility between the two branches of the Oghuz was to last into the 1040s

when the brothers Toghnl Beg Muhammad and Chaghri Beg Dawud b. Mika'il b. Saljuq finally got the upper hand over the Yabghu Shah Malik

(see below, p. 39). From c. 375/985 Oghuz bands served as auxiliaries of the

Samanids along the northern frontiers of the emirate, and in 382/992 Arslan

Israel b. Saljuq was aiding the amirs against Bughra Khan Harun or Hasan

when he temporarily occupied Bukhara; it seems that this Saljuq leader had at

some point arrogated to himself the ancient title of Yabghu in defiance of the

original holder of the title. 36

Over the next thirty years, the Saljuqs and their followers were found as condottieri in the service of the Qarakhanids and Ghaznavids, allying with

whoever could promise plunder and pasture for their herds; they became particularly close to 'Alitegin, ruler in Transoxania (see above, p. 32). Towards

the end of the second decade of the eleventh century a long distance raid

of Turkmens under Chaghri Beg as far as Azerbaijan and the frontiers of Rum

34 CI. Cahen, 'Le Malik Nameh et les origines seljukides', Oriens, 2 (1949), pp. 41 3;

Bosworth, The Ghaznavids, pp. 219 20.

35 Akhbar al dawla al saljuqiyya, ed. Muhammad Iqbal (Lahore, 1933), pp. 12.

36 Cahen, 'Le Malik Nameh', pp. 42 6; Bosworth, The Ghaznavids, pp. 220 3; C.E. Bosworth,

'The political and dynastic history of the Iranian world (AD 1000 1217)', in The Cambridge

history of Iran, Vol. V: The Saljuq and Mongol periods, ed. J. A. Boyle (Cambridge, 1968), pp. 17 18.

35

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

or Anatolia is reported in some sources, but this date seems rather early and the

story more probably refers to raids of some ten or more years later. 37

The Ghaznavid conquest of Khwarazm in 408/1017 brought Sultan Mahmud into immediate proximity of the Oghuz of the surrounding steppes,

at a time when movements in the eastern part of Inner Asia, on the borders of

the Khitan state in Mongolia, had initiated a series of tribal migrations which

ultimately put pressure on the Oghuz to move southwards to the fringes of

Khurasan. There now begin complaints from the people of the towns on the

northern rim of Khurasan, such as Nasa, Abivard and Farava, concerning

Oghuz depredations. Hence in 418/1027 Mahmud despatched against them a

powerful army which hurled the Turkmens back into the steppes to Dihistan

and Balkhan Kuh, and westwards into Persia, where they were enrolled as

auxiliaries by the Ghaznavid governor of Rayy and Jibal and by the Kakuyid

ruler of Isfahan, 'Ala' al Dawla Muhammad, but proved a continual source of

violence and instability there (it was these Turkmens whom the Ghaznavid

historians call the ''Iraqi' ones, from their penetration of northern Persia, 'Iraq i 'Ajam or Persian Iraq). After 'Alitegin's death in 425/1034, the Saljuqs,

now headed by Toghnl Beg, entered the service of the Khwarazm Shah Harun

b. Altuntash until Sultan Mas'ud procured the latter 1 s death, after which

Mas'ud's new ally, Shah Malik of Jand, defeated and scattered the Oghuz, driving them into Khurasan but thereby making the security system there worse.

The sultan launched punitive expeditions against these Turkmens, but a surprise defeat of his army on the road to Nasa in 426/1035 compelled him

to make formal grants of the northern Khurasanian towns to Toghnl, Chaghn and Musa Yabghu. Inevitably, these concessions only emboldened

the Saljuq leaders to demand more. They complained in 428/1036 that the

pastures allotted to them were inadequate, and sought a grant of Marv, Sarakhs and Abivard, strategic and commercial centres that the sultan could not possibly surrender. The Turkmens, disorganised though they were, gradually wore down the professional armies of the Ghaznavids, ill equipped for the highly mobile type of warfare required along the steppe

37 Cahen, 'Le Malik Nameh', pp. 50 1 (denying the historicity of an expedition at this early

date); Ibrahim Kafesoglu, 'Dogu Anadoluya Selcuklu akim (1015 21) ve tarihi ehem

miyeti', in Fuad Kopriilii armagam (Istanbul, 1953), pp. 259 74, Eng. trans. Gary Leiser, in

Mesogeios I Mediterranee (Paris), 25 6 (2005), pp. 27 47.

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

fringes; even if defeated in a pitched battle, the Turkmens could melt into the desert and re form. 38

The oasis towns of Khurasan were suffering badly from Turkmen herds trampling their crops and from disruption of the caravan trade, were frus trated at the sultan's inability to protect them and were resentful of the heavy

taxation he was requiring in order to keep his armies continuously in the field.

They began to make the best of a bad job and to conclude local agreements

with the Turkmens. Thus towards the end of 428/1037 the leading c ulama' and

notables of Marv surrendered the city to Toghril and Chaghn on condition

that the populace was not harmed. In 429/1038 the Saljuq leader Ibrahim Inal

and then Toghril entered Nishapur and made an agreement with leading clerics and secular leaders; Toghril sat down formally upon Mas'ud's throne

(the sultan subsequently had this profaned object broken up) and seems to

have been able to restrain the mass of Turkmens from plundering. Such occupations were only temporary, and the arrival of Ghaznavid troops caused

the Turkmens to withdraw. But time was running out for Mas'ud. His army,

heavily encumbered with war materiel, including elephants, but with totally

inadequate supplies of food, fodder and water, set out from Sarakhs for Marv

in spring 431/1040. At Dandanqan it was totally defeated, in one of the decisive

batdes of eastern Islamic history, by some 16,000 Turkmens. Toghril was proclaimed amir of Khurasan on the battlefield and renewed his contacts with

the caliph in Baghdad, sending an envoy to secure formal confirmation of his

territorial acquisitions, since the whole of Khurasan speedily passed under

Saljuq control. The dispirited Mas'ud fled to Ghazna, and fearing (unnecessa

rily, as it proved) that his capital would fall to the Saljuqs, withdrew in the next

year to India, where his troops, now devoid of confidence in him, mutinied

and deposed him, soon after which he was killed. The Ghaznavid empire was

to survive for over another century, but in a truncated form and now essentially oriented towards India. 39

#### IV

The Saljuqs had for long had a great fear of Sultan Mas'ud and the Ghaznavid

war machine, but this ended with the Dandanqan victory, which not only gave

38 Cahen, 'Le Malik Nameh', pp. 55 60; Bosworth, The Ghaznavids, pp. 241 3; Bosworth,

'The political and dynastic history', pp. 18 20.

39 Cahen, 'Le Malik Nameh', pp. 61 4; Bosworth, The Ghaznavids, pp. 243 68 (with a

translation of the detailed passage in Bayhaqi on the first Saljuq occupation of

Nishapur); Bosworth, 'The political and dynastic history', pp. 203.

37

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

them control of Khurasan but also laid open to them the lands further west.

Northern and western Persia were at this time in the last phase of what V. Minorsky called 'the Daylami interlude' of medieval Persian history. 40 Among the powers involved here, the Ziyarids were ruling in the lowland

Caspian provinces of Gurgan and Tabaristan. The amirs had latterly been vassals

of the Ghaznavids, but after 433/104<sup> the Saljuq became their overlords; in the</sup>

middle decades of this century, the Ziyarid ruler c Unsur al Ma'ali Kay Kawus

was the author of a celebrated 'mirror for princes', the Qabus noma, named after

his illustrious forebear Qabus b. Vushmgir. Other princes of the central Elburz

region, such as the Iranian Bavandid Ispahbadhs and the Daylami Musafirids of

the region of Daylam itself, at the south western corner of the Caspian Sea, were

too inaccessible in their mountain fastnesses to be dislodged by the Saljugs, and

in general remained as tribute paying vassals of the Great Saljuqs while these

last continued dominant in western Persia. 41 There were various lines of Kurdish chiefs in Azerbaijan and the Zagros regions of Kurdistan and Luristan, but the main powers that the Saljuqs were to come up against were

those of the Daylami Buyids and Kakuyids. The heyday of the Buyid confeder

acy had been in the later fourth/tenth century under such forceful rulers as

Fakhr al Dawla of Rayy and 'Adud al Dawla of Fars and Iraq, but when the

Saljuqs appeared in western Persia, the dynasty was in a state of some confusion

and decay. The northern emirate, based on Rayy, had already been annexed by

Mahmud of Ghazna in 420/1029, but now passed almost immediately under

Saljuq control. However, the Buyids still had extensive lands in western and

southern Persia, that is, Jibal, Fars, Kirman and Iraq; the last of these, Ialal al

Dawla (r. 416 35/1025 44), had styled himself Amir alUmara' 'Supreme Commander' and in 429/i037f assumed the ancient Sasanid tide (regarded by

strict Muslims as blasphemous) of Shahanshah 'King of Kings' 42 . Although

40 See his La domination des Dailamites, Publications de la Societe des Etudes iraniennes

(Paris, 1932), repr. in Iranica, twenty articles / Bist maqala yi Minorsky (Tehran, 1964), pp. 12 30.

41 For these petty dynasties, see Bosworth, 'The political and dynastic history', pp. 24 32,

and for their chronology, Bosworth, The New Islamic dynasties, pp. 148 9, 164 7 nos. 71, 80 1.

42 For the Buyids of Persia, see EI 1 'Buwayhids' (CI. Cahen); and Bosworth, 'The political

and dynastic history', pp. 36 7; for those of Iraq, H. Busse, Chalifund Grosskdnig. Die

Buyiden im Iraq (94; iojjJ (Beirut and Wiesbaden, 1969) and J. J. Donohue, The Buwayhid

dynasty in Iraq 334H/945 to 403H/1012: Shaping institutions for the future (Leiden and

Boston, 2003); and for the chronology of the various branches of the dynasty, see

Bosworth, The New Islamic dynasties, pp. 154 7 no. 75. For a special study of Jalal al

Dawla's act of lese majeste towards the caliph, see H. F. Amedroz, 'The assumption of

the title Shahanshah by Buwaihid rulers', Tfte Numismatic Chronicle, ser. 4, 5 (1905),

PP-3939-

38

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

theoretically a vassal of the Buyids, the able Daylami ruler in Isfahan and Hamadan, 'Ala 1 al Dawla Muhammad, called in the sources Ibn Kakuya (d.

433/1041), was able to pursue a skilful policy of self interest, making peace with

Toghril when Saljuq pressure became overwhelming, which enabled his descendants to survive modestly within the Great Saljuq empire till well into

the sixth/twelfth century. 43

The two outstanding members of the Saljuq family, Toghril Beg and Chaghn Beg, seem to have made an informal division of power regarding the lands which were falling into their hands. Khwarazm was taken over when

Toghril led a campaign into it in 433/104<sup>^</sup>. or shortly thereafter. The old enemy of the Saljuqs, and ally of Sultan Mas'ud of Ghazna, the original Yabghu Shah Malik of Jand, did not long enjoy his dominion over Khwarazm. He was now defeated and driven out of the capital Gurganj. It seems that he was unable to return to his old centre of Jand (presumably

because it was now in alien hands, those of the Oghuz or Qipchaq) and had to

flee southwards through Khurasan and eventually to Makran, where he met

his death. 44 Henceforth Chaghn was in overall charge of the eastern lands,

whose core was Khurasan and its dependencies, while other members of the

Saljuq family, Ertash and Musa Yabghu or Bighu, campaigned in adjacent parts of Afghanistan, including Sistan, which now, under its local princes, the

so called Maliks of Nimruz, became a Saljuq vassal state. 45

Toghril assumed responsibility for Saljuq expansion into the western lands, a

task which he now set about putting into practice. After Mahmud of Ghazna's

seizure of the Saljuq Arslan Israel in 418/1027 (see above, p. 36), his Turkmen

followers, the ''Iraqi' ones, had scattered westwards and had become a

lent element in the politics and society of western Persia. In the 1030s, the

Buyids, Kakuyids, Ghaznavids and various local Kurdish princes all endeav

oured to employ Turkmen bands against their opponents and rivals. As a result.

the whole region became chronically insecure. The rich cities of western Persia

were obvious targets for the Turkmen marauders, and it is around this time that

town walls were built or rebuilt as a protective measure, for example at Isfahan

43 See Bosworth, 'Daylamis in central Iran: The Kakuyids ofjibal and Yazd', Iran, Journal of

the British Institute of Persian Studies, 8 (1970), pp. 73 95, and for their chronology,

Bosworth, The New Islamic dynasties, pp. 160 1 no. 78.

44 Ibn al Athir, vol. X, p. 506, under year 434; Ibn Funduq, Tdrikh i Bayhaq, ed. Ahmad

Bahmanyar (Tehran, 1317/1938), p. 51, with the year 433 for Shah Malik's flight; Omeljan

Pritsak, 'Die Untergang des Reiches des Oguzischen Yabgu', in Fuad Koprulii armagam, p. 408.

45 C. E. Bosworth, The history of the Saffarids of Sistan and tfte Maliks of Nimruz (247/861 to

949/1542 3) (Costa Mesa and New York, 1994), pp. 376 86.

39

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

by Ibn Kakuya and at Shiraz by the Buyid amir of Fars, Khuzistan and Kirman

'Irnad al Din Abu Kalijar. 46 The lands beyond were also affected, especially after

the Saljuq leaders had imposed their control on the cities of Persia, as did

Ibrahim Inal at Rayy and then Hamadan in 1033 4 and 1041 3, driving many of

the ''Iraqi' Turkmens into northern Iraq and al Jazira and even as far as Armenia

and Diyarbakr in south eastern Anatolia. It seems that Toghril and the other

leaders were already trying to exercise some control over their more anarchic

followers, and that these last were resisting this. Later, it would become some

thing like official policy of the Great Saljuq sultans to deflect uncontrollable

elements to the farther western fringes, such as northern Syria, Armenia and

Anatolia. In particular, Azerbaijan, an area particularly fragmented, politically,

ethnically and confessionally, now became a concentration point for Turkmens

attracted inceasingly from Inner Asia once the Ghaznavid and Buyid defences in

northern Persia had crumbled. As noted above, Azerbaijan had upland pasture

grounds suitable for the nomads' herds, and there were old established tradi

tions of ghazi warfare there, aimed at such Christian powers as Armenia and

Georgia, which the Turkmens, once they became Muslims of sorts, could adopt. It is these factors which came together and set in train the process

whereby Azerbaijan became what it is today, ethnically and linguistically, Turkish (see above, p. 24). From the second half of the fifth/ eleventh century

onwards, Turkmens also infiltrated into Anatolia and founded there in the course of the following century ghazi states like those of the Shah i Armanids,

Danishmendids, Mengiijekids and Saltuqids; but before these came into being, a

member of the Saljuq family, Sulayman b. Qutlumush or Qutalmish, had already laid the foundations for the most important and longest lasting of all

of them, the Saljuq sultanate of Rum (see below, p. 45).

Toghril's immediate need, however, was gradually to establish Saljuq authority over northern and western Persia. This was facilitated by Ibn Kakuya's death. Under Saljuq suzerainty, his two sons Faramurz and Garshasp succeeded him in Isfahan and Hamadan respectively, 47 while Toghril made Rayy his own base, until in 442/io5of. the Saljuq leader took

over Isfahan from Faramurz (who had tried to keep on good terms with both

the Saljugs and the Buyids of Fars and Khuzistan), and moved his capital

46 For Shiraz, see Ibn al Balkhi, Fars noma, ed. G. Le Strange and R. A. Nicholson (London,

1921), p. 133; and for Isfahan, Mufaddal b. Sa'd Mafarrukhi, Kitdb Mahdsin Isfahan, ed. Jalal

al Din Tihranl (Tehran, 1312/1933), pp. 81, 100 1, and Nasir i Khusraw, Safarndma, ed.

Muhammad Dabir Siyaqi (Tehran, 1335/1956), pp. 122 3, Eng. trans. W. M. Thackstonjr

(New York, 1986), p. 98.

47 Bosworth, 'Daylamis in central Iran', pp. 81 2.

40

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

thither from Rayy. 48 The Buyids themselves were still powerful enough for

Toghril to treat diplomatically with 'Imad al Din Abu Kalijar in 439/1047^.

Toghril promised to restrain Ibrahim Inal and the ''Iraqi' Turkmens from raiding Buyid territory, and a marriage alliance was arranged between a young

Buyid prince and one of Chaghn Beg's daughters. 49 This did not, however,

prevent Chaghn's son Qavurd raiding through Khurasan into the Buyid province of Kirman and taking it over, the beginning of a petty Saljuq principality which was to last for over a century (see below); this was in 440/1048, the point at which Abu Kalijar died before he could take steps to

recover his lost province. Fars now fell into the hands of the Shabankaral Kurdish chief Fadluya, who in 454/1062 killed the Buyid amir there and ended

the dynasty's line there, only in turn to bring down on himself Saljuq intervention and annexation of the province. 50

The other surviving Buyid emirate, that in Iraq, was centred on Baghdad, a

city now wracked with the violence of Turkish soldiery and of rival Sunm and

Shi'ite factions. As early as 426/1035 the Saljuq chiefs crossing the Oxus into

Khurasan (see above, p. 36) had styled themselves Mawali Amir al Mifmiriin

'Clients of the Commander of the Faithful', conscious of the symbolic value of

such claimed ties, and Toghril had opened up diplomatic relations with the

'Abbasid caliphs when first he occupied Nishapur. Although the Turkmens

who later overran Anatolia were to contain within their ranks many heterodox

religious elements, including messianic Shi'ite ones, it clearly suited Toghril

now to pose as protector of the caliph and defender of Sunm orthodoxy as

against a Buyid Shi'ite Amir al Umarff there and Turkish commanders who

were in touch with the Isma'ili Fatimids, deadly enemies of the Abbasids, at

the other side of the Syrian desert. In later times, pro Saljuq historians would

attempt an ideological justification for the coming of the Turks and their rule

over so much of the Islamic world by adducing Toghnl's deliverance of the

caliph from the Buyids and the Saljuqs' subsequent leadership in the jihad or

holy war against the Byzantines in Anatolia. 51

Toghril marched into Baghdad in 447/1055, deposed the last Buyid amir there, al Malik al Rahim Khusraw Firuz, restored order in the city and had the

48 Bundati, p. 9; Ibn al Athir, vol. IX, pp. 507 8.

49 Ibn al Athir, vol. IX, p. 536.

50 H. Bowen, 'The last Buwayhids', Journal of the Royal Asiatic Society (1929), pp. 233 43;

Bosworth, 'The political and dynastic history', pp. 44 7, 49.

51 Cf. the words of Rawandl (who dedicated his history to one of the Rum Saljuq sultans),

Rahat al sudur, ed. Muhammad Iqbal (1921), pp. 17 18, cited in Bosworth, 'The political and dynastic history', p. 15.

41

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

# The New Cambridge History of Islam

khutba, with the caliph al Qa'im's permission, made for himself. 52 Whether

ToghriTs removal of the Buyids was regarded by him as a crusade to release

the caliphs from Shi'ite tutelage is unclear; in the ensuing decades, the 'Abbasids were to find that the weight of Saljuq authority was at times as heavy as that of the Buyids had been. It is undoubtedly true that Togtail's

close advisers when he appeared in Iraq were all strong Sunms, such as the

'Amid al Mulk Abu Nasr Kunduri, and convinced Hanafis in legal rite; when

Toghril gave Kunduri permission to curse the Shi'a in the khutba of Khurasan,

the latter also added cursing of the Ash'aris, who were in general Shafi'is in

legal rite. Toghril was not actually received by al Qa'im until 449/1058, when

he was awarded grandiloquent titles, including that of Malik al Mashriq wa 'I

Maghrib 'King of East and West,' robes of honour in 'Abbasid black, and two

crowns signifying rule over the Arabs and the Ajam. He seems to have glorified in his role as deliverer of the caliph, allegedly enthroning himself

wiith great pomp and majesty. 53 However, it took much browbeating on ToghnTs part, including threats of cutting off finance, before the caliph would

agree to an 'Abbasid princess, one of his own daughters, marrying a barbarian

Turk, a situation which was soon resolved anyway since Toghril died in 445/

1063 before the marriage could be consummated. 54

The appearance of Toghril in Iraq with a powerful war machine which was

clearly now going to be the dominating force in the caliphal heartlands, posed

problems for the theologians and jurists of the time. These scholars had

able to ignore on religious grounds the realities of other leading powers of the

age: for them, the Buyids had been military commanders only, and Shi'ites to

boot (probably Zaydis); the Fatimids styled themselves caliphs (and were in

reality far more glorious rulers than the feeble 'Abbasids) but as Isma'ili ShTites were beyond the religious pale. Now, as mentioned above, Toghril

vaunted his Sunni credentials, so that the theorists had somehow to accom

modate the sultan, as holder of secular power, alongside the caliph, theoret

ically the wielder of all power under God but, in practice at this time, the holder of a largely moral and religious influence only. The jurists of the later

fifth/ eleventh and sixth/twelfth centuries had reluctantly to wresde with this

52 Busse, Chalifund Grosskonig, pp. 119 21.

53 Bundari, pp. 13 14; Husayni, pp. 17 18; Pseudo Zahir al Din NTshapuri, Saljuq noma, Eng.

trans. K. A. Luther (Richmond, 2001), pp. 41, 43; Ibn alAthir, vol. IX, pp. 633 4;

Barhebraeus, Chronography, vol. I, Eng. trans. E.A. Wallis Budge (Oxford, 1932),

pp. 201 2, 211 12.

54 Bosworth, 'Political and dynastic history', pp. 45 6, 47 9; Busse, Chalifund Grosskonig, pp. 121 7.

42

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

problem of reconciling these two elements within the secular Islamic world,

seen for example in the works of Abu Hamid al Ghazali (d. 505/1111) on this

question, in particular his 'mirror for princes', the Nasihat al muluk, written in

Persian towards the end of his life. 55

Whilst Toghril was engaged in the west, Chaghn Beg, from his capital at Marv, was consolidating Saljuq rule in the east. There were for a while fears of

a Ghaznavid revanche to recover Khurasan, under the vigorous Sultan Mawdud b. Mas c ud (r. 432 7440/1041 71048), in alliance with the Oarakhanid

ruler of Transoxania, Tamghach Khan Ibrahim (see above, p. 32). But Mawdud's anti Saljuq coalition fell apart on his death, and on his accession

in 451/1059, the new Ghaznavid sultan Ibrahim b. Mas'ud negotiated a peace

settlement with Chaghri which recognised the status quo in the east, with the

upper Oxus principalities under Saljuq control but eastern Afghanistan, beyond Tirmidh and Balkh, left to the Ghaznavids. 56

Thus at the deaths of Chaghri in 452/1060 and of Toghril three years later,

there stood a vast Saljuq empire comprising Persia, Khwarazm and much of

Iraq, and this had been accomplished without undue violence and disturbance,

at least by the standards of the age, to the economies of those lands. The two

brothers had worked in harmony, but the maintenance of the empire now demanded strong, unified rule, especially as there were strong centrifugal forces

at work in the state. There had already been sporadic revolts by members of the

Saljuq family who cherished an older Turkish, patrimonial view of the assem

blage of the lands as the shared heritage of senior family members, that is, a

'collective sovereignty' rather than the view that supreme direction of the state

was the personal property of a single, forceful individual. It was usually the

eldest and most militarily prestigious member of the family who succeeded in

enforcing his claim to the throne. However, this never precluded other ambi

tious family members from putting forward their claims, and there were always

plenty of Turkmen malcontents on whom they could rely in a bid for power;

these Turkmens were in any case unenamoured of the prospect of a strong

centralised government which would entail encroachments on their personal

freedom and, above all, result in the imposition of taxation. 57 Such challenges to

55 See G. Makdisi, 'Les rapports entre Calife et Sultan a l'epoque saljuqide', International

Journal of Middle East Studies, 6 (1075), pp. 228 36; A. K. S. Lambton, State and government

in medieval Islam: An introduction to tfte study of Islamic political theory: The jurists (Oxford, 1981), pp. 103 29.

56 C. E. Bosworth, The later Ghaznavids: Splendour and decay: The dynasty in Afghanistan and northern India, 1040 1186 (Edinburgh, 1977), pp. 25 30, 51 5; Bosworth, 'The political and dynastic history', pp. 49 53.

57 See Golden, An introduction, pp. 220 1.

4i

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

the sultans' authority were to continue all through the life of the Great Saljuq

sultanate, culminating in the role of the Oghuz nomads of northern Afghanistan

and the upper Oxus region in procuring the downfall of Sanjar b. Malik Shah in

548/1153 (see below).

A succession crisis ensued at the childless Toghnl's death, but the most able

of Chaghri's sons, Alp Arslan, was raised to the throne by a combination of

several of the slave commanders of the Saljuq army, whose interests lay in the

building up of a powerful, paid, professional army, and a statesman of genius,

Alp Arslan's personal vizier, Abu 'All al Hasan Nizam al Mulk, forestalling an

attempt by Toghnl's vizier Kunduri to install a palpably less suitable candidate. 58

The Khurasanian official Nizam al Mulk, an archetypal representative of the Perso Islamic administration but also a convinced proponent of orthodox

Sunnl faith, was to guide the destinies of the Great Saljuq empire for the two

reigns which were to form its apogee, those of Alp Arslan (r. 455 65/1063 73)

and his son Malik Shah (r.  $465\ 85\ /\ 1073\ 92$ ), and it was not for nothing that Ibn al

Athir styled these thirty years al dawla al nizamiyya (see further on Nizam al

Mulk, below, pp. 49 51).

### V

Alp Arslan's decade of rule, buttressed by Nizam al Mulk's guiding hands, saw

expansion into new areas of the west, with unruly Turkmens directed into Armenia, Transcaucasia and Anatolia, and the consolidation of the sultanate in

its heartlands of Persia and Iraq. In 456/1064 the sultan, accompanied by

son Malik Shah and the vizier Nizam al Mulk, led an expedition into Arran and

Transcaucasia. He captured the old Armenian capital of Am and also Kars, and

in a second campaign of 460/1068 ravaged Georgia and occupied Tiflis, although the capable king of Georgia, Bagrat IV (r. 1027 72), managed to retrieve the situation and retain control of his realm. 59

For some time, Turkmen raiders had been operating within Byzantine Anatolia, although without any concerted plan or unified direction; at times

they were even used by the Greek emperors as auxiliary troops (foederati)

against other Turkmen bands. In the years 459 60/1067 8 Caesarea/Kayseri,

Amorium and Iconium/Konya were sacked by the Turkmens, attacks which

58 Bundan, pp. 26, 28; Ibn al Athir, vol. X, p. 29.

59 Husayni, pp. 34 8, 43 6; V. Minorsky, Studies in Caucasian history (London, 1953), pp. 64 7-

44

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

menaced Byzantine lines of communication and supply through the Taurus

mountains and Cilicia to their possessions and their armies operating in northern Syria from such centres as Malatya, Antioch and Edessa. Hence in

462/1070, despite a probable truce that he had made with Alp Arslan, the emperor Romanus Diogenes (r. 1068 71) sent an army into Anatolia and northern Syria which menaced the Muslim emirate of Aleppo. In the spring

of the next year, Romanus assembled a vast army at Erzerum and marched

into Armenia, but was confronted by Alp Arslan's forces, decisively defeated

by them at Manzikert/ Malazgird on a tributary of the upper Euphrates, and

himself captured. The sultan was preoccupied with operations in Syria aimed

at the Fatimids, and was content to release Romanus on payment of a ransom

and some slight adjustments of territory. Alp Arslan's victory made him a Muslim hero, but one can infer from his release of the emperor that the sultan

was not consciously leading a crusade and had no definite plan to overthrow

Byzantine authority in Anatolia.

Nevertheless, Alp Arslan's success here meant that most of Armenia now passed definitively into Muslim hands, with the Georgians remaining the only

significant Christian power in the region. The perceived weakness of Byzantine defences in eastern Anatolia opened the floodgates for further Turkmen raids there. It is soon after the date of the Manzikert battle that we hear of the activities of the four sons of Qutlumush/Qutalmish b. Arslan

Israel, the sultan's cousin, one of whom, Sulayman, was to found the Saljug

sultanate of Rum in central and western Anatolia. : These Turkmen raids were essentially acts of private enterprise rather than Saljuq state directed

ones. Both Alp Arslan and Malik Shah were hostile towards the family of Qutlumush, since the ambitious Qutlumush had fruitlessly rebelled against

Alp Arslan immediately after the latter's accession in 456/1064, dying then in

mysterious circumstances.

Events within the heartlands of the sultanate continued to concern Alp Arslan. Qutlumush's bid for power had been quashed, but it soon became clear that the sultan's own elder brother, Qara Arslan Qavurd, was dissatisfied

with his circumscribed dominion over the province of Kirman in south eastern

60 Bundari, pp. 38 44; Husaym, pp. 46 53; Pseudo Zahir al Din Nishapuri, trans. Luther,

pp. 48 53; Ibn al Athir, vol. X, pp. 65 7; CI. Cahen, 'La campagne de Mantzikert d'apres

les sources musulmanes', Byzantion, 9 (1934), pp. 621 5; Cahen, Pre Ottoman Turkey

(London, 1968), pp. 66 72; C. Hillenbrand, Turkish myth and Muslim symbol: The battle of

Manzikert (Edinburgh, 2007), pp. 325.

61 Cahen, Pre Ottoman Turkey, pp. 73 4.

62 Bundari, pp. 28 9; Husaym, pp. 30 2; Ibn al Athir, vol. X, pp. 36 7; Barhebraeus, pp. 226 7.

45

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

### The New Cambridge History of Islam

Persia. The origins of Saljuq rule there are rather obscure, and the opening

pages of the otherwise valuable local historian Muhammad b. Ibrahim's history of the Kirman Saljuqs are unfortunately missing. The Buyids had recovered Kirman from a short lived Ghaznavid occupation in the early 1030s, but the Ghaznavid debacle at Dandanqan allowed Oghuz raiders to

move southwards through Khurasan and harry the towns of Kirman, the capital Bardasir being attacked in 434/i042f. Kirman remained in Buyid hands for a few more years, but just before the death in 440/io48f. of the amir of Fars, Khuzistan and Kirman, Abu Kalijar, Bardasir passed into Qavurd's hands. 63 There thus began some 140 years of Saljuq rule there under a line of Qavurd's descendants until this was extinguished by the irruption into Kirman of unruly bands of Oghuz tribesmen in the later sixth/

twelfth century. Under Saljuq rule, Kirman was to enjoy a period of consid

erable prosperity. Qavurd, who reigned for thirty four years, is said to have

built caravanserais and cisterns along the trade routes, to have protected the

people of the agricultural oases by directing his tribal followers to pasture

their herds out on the steppes and granting them specific iqtd's, and to have

led a punitive expedition against the predatory Kufichi and Baluch moun taineers of south eastern Kirman and adjacent Baluchistan. 64 The province

seems to have benefited by trade from India and beyond which had entered

such Persian Gulf ports as Tiz, Siraf and Hormuz and now passed through

Kirman to Khurasan and Central Asia. Chaudhuri has remarked that the prosperity at this time of cities like Kirman (as Bardasir now becomes styled)

and Yazd is only explicable by income derived from artisanal activity and from services supplied to caravans of merchants passing through the region;

the local historian mentions communities of foreign merchants, including Rumls and Indians, in a trading colony near the town of Jiruft, in the mid sixth/twelfth century. 65

Qavurd had accepted Alp Arslan's succession in 455/1063, but three years

later rebelled against him. This required the sultan to lead an army into Kirman against him (459/1067) which subsequently penetrated into Fars,

and, in a further campaign of 461/1069, the Shabankaral chief Fadluya, who

63 Afdal al Din Kirmani, Tqd al 'ula li 'I mawqifal a'la, ed. 'AE AmM Na'ini (Tehran, 1311/1932),

pp. 68 9; Muhammad b. Ibrahim, Tdrtkh i Saljuqiyan i Kirman, ed. M. T. Houtsma, in Recueil

de textes relatifs a l'histoire des Seljoucides, vol. I (Leiden, 1886), pp. 2 3; Ibn al Athir, vol. IX,

pp. 510 11, 547; Erdogan Mercil, Kirman Selcuklart (Istanbul, 1980), pp. 11 26.

64 Muhammad b. Ibrahim, pp. 45, 68, n12; Mercil, Kirman Selcuklart, pp. 2768.

65 K. N. Chaudhuri, Trade and civilisation in the Indian Ocean: An economic history from the rise of Islam to 17<sup>0</sup> (Cambridge, 1985), p. 56; Muhammad b. Ibrahim, p. 49.

46

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

had seized control of Fars after the demise of the Buyids, was defeated and subsequently killed in 464/i07if.

Alp Arslan never visited Baghdad in person but was careful, through Nizam

al Mulk's diplomatic contacts with the 'Abbasid caliph al Qa'im's own viziers.

Ibn al Muslima and then Fakhr al Dawla Ibn Jahir, to maintain his influence in

the caliphal capital at a time when the Abbasids were beginning tentatively to

assert their political power in Iraq after the long years of subordination to the Buyid amirs, a development which was gradually to accelerate and to

form the background for Saljuq 'Abbasid relations over the next century or so.

For the moment, thanks to the skill of Nizam al Mulk (whose daughter married Ibn Jahir's son 'Amid al Dawla), relations were generally cordial. In

458/1066 the sultan secured caliphal approval for his designation of his son

Malik Shah as walial l ahd or covenanted heir, a step which placed Alp Arslan's

vision of rulership firmly within the Perso Islamic succession procedure of

primogeniture (or, at least, choice of the ruler's most capable son) and outside

the old Turkish one of succession by seni orate within the whole ruling family;

and the seal was set on these good relations when in  $464/107^{\sim}$ . Alp Arslan's

daughter was married to al Qa'im's son and heir, the later caliph al Muqtadi. 67

On the eastern fringes of the Saljuq empire were two still formidable powers, the Qarakhanids and the Ghaznavids. The Ghaznavid sultan Ibrahim was in general content to maintain the modus vivendi arrived at in

451/1059 by himself and Chaghn Beg (see above, p. 43); specific information is

totally lacking here, but it is probable that Ibrahim concerned himself mainly

with India during these years.

The Ghaznavid realm was distant, and the Saljuq sultanate had obviously reached a logical and sensible frontier, running as it did southwards through

the mountain regions of what is now Afghanistan; an army advancing beyond

it would have faced serious strategic and logistical problems. Relations with

the Qarakhanids, neighbours of the Saljuqs just across the Oxus, were more

immediate and therefore more delicate. The Qarakhanid Tamghach Khan Ibrahim had built up a powerful and flourishing kingdom in Transoxania and

Farghana, achieving a reputation during his reign as an exemplary just ruler,

careful of the interests of his subjects. He had a special care for the economic

and financial stability of his kingdom. Among other currency reforms, he introduced a mu'ayyadl dirham of a guaranteed standard against gold, thus

- 66 Bundari, pp. 30 1; Ibn al Athlr, vol. X, pp. 71 2.
- 67 Bundari, pp. 36, 45, 46 7; Ibn al Athir, vol. X, pp. 50, 70 1.
- 68 Bosworth, The later Ghaznavids, pp. 51 2, 61 2.

47

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

facilitating internal trade, and when he conquered Farghana, which had previously been part of the eastern Qarakhanid khanate, he incorporated this into the currency area of the western khanate. 9 Ibrahim had certainly

shown himself a skilful and tenacious field commander in his struggles with

rival members of the Qarakhanid family in Transoxania and against Mas'ud of

Ghazna in the upper Oxus region (see above, p. 32). Alp Arslan, still at this

time his father Chaghn Beg's deputy, was the aggressor here in 453/1061,

sending an expedition across the Oxus, and causing Ibrahim to send a delegation to the 'Abbasid caliph with protests about this unprovoked attack.

A further aspect of Alp Arslan's concern for the lands beyond the Oxus and Svr

Darya, the sources of irruptions into the empire by indisciplined Turkmens,

was a campaign in 457/1065, soon after he had become sultan, from Khwarazm

into the lower Syr Darya steppes, bringing into subjection the ruler (a Qipchaq

tribal chief?) of Jand and Sawran and visiting at Jand the tomb of his ancestor

Saljuq b. Duqaq; and a punitive expedition against the Qipchaq that took

as far as the Manghishlag peninsula is also mentioned. 70

But after these shows offeree, Alp Arslan adopted a more pacific attitude towards the Qarakhanids, and a series of marriage alliances was negotiated.

The sultan himself married the widowed daughter of Mahmud of Ghazna's

old ally, Qadir Khan Yusuf; one of his own daughters married Tamghach Khan

Ibrahim's son and successor Shams al Mulk Nasr; and his son Malik Shah. the

future sultan, married another Qarakhanid princess, who eventually, as the

formidable Terken Khatun, gave birth to the short reigned Saljuq sultan of

485 7/1092 4, Mahmud (I). Tensions nevertheless arose between Alp Arslan

and Shams al Mulk Nasr in 465/1072 towards the end of the sultan's reign. He

crossed the Oxus on a bridge of boats with an army alleged to number 200,000, but the campaign was cut short when he was assassinated by a castellan whom he had condemned to death, and Shams al Mulk Nasr was

therefore able to take the offensive by seizing Tirmidh and temporarily occupying Balkh. 71

Although he had not added any significantly increased amount of territory

to the Saljuq empire, Alp Arslan left it in a stable condition, certainly the strongest power in the central and eastern Islamic lands. When he had made

Malik Shah his heir in 458/1066, he had distributed to various members of the

Saljuq family governorships on the eastern fringes of the empire, in

69 Davidovich, 'The Karakhanids', pp. 128 9.

70 Husayni, pp. 40 1; Ibn al Athir, vol. X, p. 49; Barthold, Turkestan, pp. 311 14.

71 Husayni, pp. 53 4; Ibn al Athir, vol. X, pp. 73 4; Barthold, Turkestan, p. 314; Bosworth,

'The political and dynastic history', pp. 64 5.

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

Khwarazm, Tabaristan and eastern Khurasan, as appanages. It would appear

from this that he was still mindful of traditional obligations to his kinsmen but

also that he viewed the central and western parts of his empire, which he kept

firmly within his own hands, as the centre of gravity in the state, hence the

most deserving of his personal control.

Malik Shah's twenty years' reign is often regarded as the zenith of the Great

Saljuq empire before a 'time of troubles' ensued under his fractious and squabbling sons, one which was in turn followed by a de facto division of the

sultanate into a western part, comprising essentially Iraq and western Persia.

and an eastern part embracing Khurasan and its dependencies. Malik Shah

consolidated and in many ways surpassed the achievements of his father, and

under him, the directly administered Saljuq empire stretched from aljazira

and northern Syria to Khwarazm and the Oxus, with protectorates of varying

degrees of effectiveness over the Turkmen bands in Anatolia and the Qarakhanid lands in the extreme east; while in the south, the Fatimids were

cleared out of southern Syria and most of Palestine and successful expeditions

were undertaken within the Arabian peninsula as far as Yemen and al Ahsa'.

This was a truly impressive achievement for a monarch who died at the comparatively early age of thirty seven, but it could not have been secured

without guidance from the wise and experienced Persian vizier, Nizam al  $\operatorname{Mulk}$ 

whom Malik Shah inherited from his father, whose service to the two Saljuq

rulers amounted to some thirty years. 72 Words are attributed to him, uttered

just before his assassination in 485/1092, in which he boasted, with truth, that

the security and florescence of the realm was due as much to himself as to his

master, 73 and in effect he acted as an atabeg (Tkish. 'father commander') or

tutor to Malik Shah, although this title and the institution only came into general

use in the following century, when various young Saljuq princes were provided

with ghuldm or slave commanders as guardians and tutors. 74

Nizam al Mulk directed state policy mainly through the Great Diwdn, the DTwdn i Wazir, which might accompany the sultan's dargdh or court on his

progresses and campaignings (and Nizam al Mulk not infrequently led military campaigns himself) but often remained in the capital Isfahan.

72 Pending the appearance of a biography of this outstanding figure from Professor Carole

Hillenbrand, see A. K. S. Lambton, 'The internal structure of the Saljuq empire', in Tfte

Cambridge history of Iran, vol. V: The Saljuq and Mongol periods, pp. 2646°.; EI 2 'Nizam al

Mulk' (H. Bowen and C. E. Bosworth).

73 Words given in their fullest form in Ibn al Athir, vol. X, pp. 205 6, trans, in Bosworth,

'The political and dynastic history', p. 68.

74 See Ef 'Atabak' (CI. Cahen).

49

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Nizam al Mulk filled other government departments with his partisans and proteges. For him, as with Admiral 'Jackie' Fisher in Britain over eight

centuries later, favouritism was the secret of efficiency. During his own lifetime, his numerous sons filled many strategic posts; he even attempted

(in this instance, unsuccessfully) to impose his son, Mu'ayyid al Mulk

'Ubaydallah, as the 'Abbasid caliph al Muqtadi's vizier. After his death, the

influence of his sons and of the Nizdmiyya, the body of his supporters and partisans, remained significant almost till the end of the Great Saljuq sulta

nate, especially as it was widely believed that skills, such as administrative

ones, descended hereditarily (in regard to Nizam al Mulk's sons, this belief

was only partly justified). 75

Nizam al Mulk aimed at providing the formal administrative infrastructure

of a typical Perso Islamic state, with an array of specialised diwdns, for what

was still basically a Turkish dynasty only two or three generations away from

their steppe origins and retaining many of the customs and attitudes of Oghuz

tribal society/ 6 He also aimed at training up a corps of scholars and officials

inculcated with an orthodox Sunni Muslim education who would enable the

Saljuq state to equal the intellectual attractiveness and the material splendours

of the heretical Isma'ili Shi'ite state of the Fatimids in Cairo. The famed madrasas or colleges that he founded in the cities of aljazira, Iraq and Persia, the nizdmiyyas, were not the first of their kind, nor was he the sole

founder of such institutions in his own time, but he took especial care to recruit for them leading intellectuals of the age, such as the jurist Abu Ishaq al

Shirazi (d. 476/1083), chosen for the Baghdad nizdmiyya which opened in 459/1067, and he later brought the celebrated theologian and mystic al Ghazali to lecture there.

However, Nizam al Mulk was more than just a motivator and encourager of others. His own treatise on statecraft, the Siydsat ndma, completed in 484/1091 just before his death, really delineates an administrative and military

ideal that he had failed to achieve during his own lifetime and of whose necessity he had not succeeded in convincing his Turkish masters. The nub of

the problem was, how could the newer Perso Islamic ideal of autocratic government, with its administrative apparatus designed to overawe subjects

75 For this last body, see Ef 'Nizamiyya' (C. E. Bosworth).

76 For the Saljuq administrative structures, see Bosworth, 'The political and dynastic

history', pp. 68ff., and Lambton, 'The internal structure of the Saljuq empire',

pp. 203 82; Morgan, Medieval Persia 1040 1797, pp. 34 40; and for the vizierate specifi

cally, Carla L. Klausner, The Seljuk vezirate: A study of civil administration 1055 1194 (Cambridge, MA, 1973).

50

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

and keep them from rebelling, be grafted on to the ways of a line of Turkish

chiefs sprung from the steppes and with attitudes still going back to nomadic

life (from which Malik Shah was only two generations away), in which the chief had to cherish and respect the interests of his fellow tribesmen, his only

support? 77 Hence although Nizam al Mulk chides his Saljuq masters for not

keeping up the apparatus of repression and intelligence gathering practised by

former rulers like the Buyids and Ghaznavids, he recognises that the sultans

still needed to conciliate their still non sedentarised Turkmen kinsmen and

supporters and to satisfy their needs. For one direction in which the Saljuqs

had gone along the road of earlier rulers within the governmental mainstream

of the Islamic heartlands, was to recognise the need for a professional, paid

body of troops at the side of their tribal followers. The norm was for such an

army to be built round a nucleus of Turkish ghuldm troops, but there were also

contingents in the Saljuq armies of free troops recruited from various groups

to be found within the empire and on its fringes and regarded as warlike, such

as Arabs, Armenians and Greeks. Nizam al Mulk specially commends the use

of Daylamis, Khurasanians, Georgians and Shabankaral Kurds/ 8 It seems to

have been Toghnl who first tried to throw off exclusive dependence on his

Turkmen followers, and Alp Arslan certainly had several highly competent

slave commanders, like the eunuch Savtegin (d. 478/1085). This ghuldm cam

paigned in Arran in 460 / 1068 and again in 468 / 1075, securing that region for the

sultan and extinguishing the main line of the local dynasty, probably Kurdish in

ethnic origin, of the Shaddadids of Dvin and Ganja, and then went on to serve

Malik Shah, being temporarily appointed governor of Kirman after the suppres

sion of Qavurd's revolt in 465/1073 (see below, p. 52). In the sixth/twelfth century, as the personal power of the Saljuq sultans became enfeebled, it was

members of this corps of ghuldms who assumed power in various parts of the

realm, such as the founders of the Ahmadili and Eldigiizid lines of atabegs in

Azerbaijan and that of the Salghurids in Fars (see below, p. 73). Professional

armies were, of course, expensive, and the Saljuq ones had to be maintained

partly by land grants, iqtd% but also by taxation. The sultans welcomed the

access of personal power that such armies brought, but were conscious of the

need not to antagonise their subjects, and especially the Turkmens (totally

unused to paying taxes at all), by undue financial burdens; hence Malik Shah's

77 See for evidence of Malik Shah's concern for his Turkish tribal retainers (including, e.g.,

the giving of periodic feasts for them), Bosworth, 'The political and dynastic history',

p-79-

78 Siydsat noma, ed. Harold Darke (Tehran, 1340/1961), p. 128, Eng. trans. Darke, The book of government or rules for kings (London, i960), pp. 100 1.

51

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

periodic fits of economy, strongly opposed by Nizam al Mulk, when soldiers

were discharged from the army during periods of peace. 79

The events of Malik Shah's reign show him as an energetic warrior whose sphere of operations ranged from the Mediterranean shores of Syria to

Turkistan. 'He had first of all to crush opposition to his accession to his father's throne from members of his own family, for whom the concept of hereditary succession, which seemed now to be fixed in the descent of Chaghn

Beg, was by no means obvious or desirable. When Alp Arslan was killed on the

banks of the distant Oxus, his brother Qavurd who had proved his military and

administrative skills by governing Kirman for around a quarter of a century and

who had behaved there like an independent sovereign, with such regal attrib

utes as a ceremonial parasol (chatr), the use of the traditional tamgha or emblem

of the Saljuqs and exalted honorific titles considered that he, as the senior

capable member of the family, had the superior right. The two claimants met

outside Hamadan in 465/1073. Malik Shah emerged the victor in a closely fought

battle in which the support for Malik Shah of his gkulatn commanders and Arab

and Kurdish, that is, non Turkish, auxiliary troops was decisive. The defeated

Qavurd was strangled with a bowstring, presumably to prevent the shedding of

royal blood. Kirman was given to Savtegin to govern, but eventually restored to

Qavurd's sons. It seems that one of them, 'Imad al Dawla Turan Shah (r. 477

90/1085 97), extended his power over the neighbouring province of Fars, for,

subsequently, Malik Shah's son Berk yaruq sent a military expedition to recover

it for direct Great Saljug rule.

Another potential challenger to the succession, Malik Shah's brother Ayaz,

conveniently died at this point, so the sultan was able to grant out appanages

in eastern Khurasan, including Herat, Balkh and Walwalij, to various other

Saljuq family members. One of these, a further brother of the ruler, Shihab al

Din Tekish, was later, in 477/1084<sup> tempted to rebel in Khurasan while Malik</sup>

Shah was campaigning at the other end of the empire in al Jazira; the sultan

hastened across Persia and quelled the outbreak, blinding and imprisoning

79 Bosworth, 'The political and dynastic history', pp. 80 1.

80 An anecdote much quoted in the sources to show the geographical extent of Malik

Shah's power (see, e.g., Pseudo Zahir al Din Nishapuri, trans. Luther, p. 59) has Nizam

al Mulk writing out a financial draft for the boatmen at the Oxus crossing which will be

honoured from the finances of Antioch.

81 Muhammad b. Ibrahim, pp. 12 13, 21 5; Bundari, pp. 48 9; Husayrii, pp. 56 8; Rawandi,

pp. 126 8; Ibn al Athir, vol. X, pp. 78 9, 239; Ibrahim Kafesoglu, Sultan Mdik\$ah devrinde

Biiyiik Selguklu imparatorlugu (Istanbul, 1953), pp. 23 6; Bosworth, 'The political and

dynastic history, pp. 87 90.

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

Tekish. 82 The firmness of the sultan and Nizam al Mulk in dealing with internal opposition contrasts with the more lenient policy of Alp Arslan towards malcontents like these, but the displays of force had their required

effect, and Malik Shah faced no more challenges from within the Saljuq family

for the rest of his reign.

Malik Shah was now free to deal with the rival power of the Qarakhanids across the Oxus. As noted above (p. 48), at the time of his assassination Alp

Arslan had been engaged in hostilities with the khan of Transoxania, Shams al

Mulk Nasr. The temporary vacuum of power had allowed the khan to cross

the Oxus and invade Tukharistan. Once he was firmly on his throne, Malik Shah

came eastwards in 466/107^., drove the Qarakhanids out of Balkh, captured

Tirmidh and pushed on to the khan's capital at Samarqand. The latter was

forced to sue for peace, especially as he seems to have been involved, around

this time, with the rival, eastern branch of the Qarakhanids, the descendants of

Qadir Khan Yusuf of Kashghar and Khotan. 83 This success enabled Malik Shah

to exert considerable influence within the western Qarakhanid lands, and a

further opportunity for intervention presented itself in 482/1089. The then ruler

in Samarqand, Ahmad b. Khidr Khan, nephew of both Shams al Mulk Nasr and

Malik Shah's Qarakhanid wife Terken Khatun, was at odds with the orthodox

religious institution in his capital. The latter appealed to Malik Shah, who invaded Transoxania again, captured Bukhara and Samarqand, deposed Ahmad Khan and deported him to the Saljuq capital Isfahan. He then marched

onwards to the Semirechye, where at Ozkend he received the homage of the

Eastern Qarakhanid ruler Harun b. Sulayman, who now agreed to place Malik

Shah's name in the khutba of his lands. Internecine disputes within the Qarakhanid confederation nevertheless continued. Malik Shah had to intervene

again and play an intercessory role, and at some unknown date he returned

Ahmad Khan to Samarqand (where he was later, in 488/1095, to be deposed and

executed by the influential body of orthodox 'ulamd' there on the grounds that

the khan was showing Isma'iti sympathies). In this way, the eastern khanate for

a short period, and the western khanate for well over half a century, became

subject to the Saljuqs, with strong rulers like Malik Shah and Sanjar often

intervening to place their own candidates on the throne in Samarqand; some

82 Husaynl, pp. 58, 6i, 63 4; Ibn al Athir, vol. X, pp. 76, 92 3, 118 19, 137 8; Kafesoglu,

Sultan Meliksah, pp. 57 9; Bosworth, 'The political and dynastic history', pp. 90 1.

83 Ibn al Athir, vol. X, p. 92; Barthold, Turkestan, pp. 314 15; Pritsak, 'Die Karachaniden',

p. 46; Bosworth, 'The political and dynastic history', p. 91.

53

Cambridge Histories Online  $\ \ \,$  Cambridge University Press, 201 1

The New Cambridge History of Islam

Qarakhanid coins of this period acknowledge the Saljuq sultans, but whether

this vassal status ever involved the payment of tribute is not known. 84

Further south, but still on the eastern fringes of the empire, in Sistan the Maliks of Nimruz also remained Saljuq vassals; joint operations of the Maliks

and Saljuq commanders against the Isma'ilis of Quhistan are mentioned towards the end of Malik Shah's reign. 5 The Ghaznavid sultan Ibrahim b. Mas'ud tried unsucessfully to take advantage of the troubled events around

Malik Shah's succession and to recover his lost territories in Badakhshan and

Tukharistan, but Malik Shah had to treat on equal terms with him. There were marriage links between the two great Turkish houses; Ibrahim's son, the

future sultan Mas'ud III (r. 492 508/1099 1115), married successively daugh

ters of Alp Arslan and Malik Shah, the latter being Gawhar Khatun, famed in

Ghaznavid history as the mahd i Hrdq 'bride from western Persia'. Saljuq cultural influence seems to have been strong around this time; at some point the sultans formally adopted the Saljuq title of al Sultan al Mu c azzam

'Highly Exalted, Supreme Sultan'.

At the other end of the Saljuq empire, Azerbaijan and Arran retained their

importance as concentration points for Turkmen bands operating in the Caucasus region and in Anatolia. The line of Shaddadid amirs of Ganja and

Am was already in vassalage to the Saljuqs, but soon after Malik Shah's accession his armies extinguished this branch of the family (see above, p. 51).

The sultan campaigned personally in Georgia in 471/1078^ Kars was recap

tured from the Georgians and Turkmen commanders penetrated to the Black

Sea coast in Lazistan and threatened the Byzantine city of Trebizond (accord

ing to one report, temporarily capturing it). The whole of the Araxes Kur basin of Arran seems now to have been parcelled out as iqta's for the Turkmens and their commanders. 87

The sons of Qutlumush had arrived in Anatolia at the opening of Malik Shah's reign. Turkmen bands operating under their general leadership were

now overrunning much of Byzantine Anatolia; they were able to take advant

age of succession disputes within the imperial family at Constantinople which

84 Narshakhl, p. 34, trans. Frye, p. 29; Rawandi, pp. 128 30; Ibn al Athir, vol. X, pp. 171 5,

243 4; Barthold, Turkestan, pp. 316 18; Pritsak, 'Die Karachaniden', pp. 47 8; Kafesoglu,

Sultan Meliksah, pp. 119 23; Davidovich, 'The Karakhanids', pp. 130 1.

85 C. E. Bosworth, 'The Isma'ilis of Quhistan and the Maliks of Nimruz', in Farhad Daftary

(ed.), Medieval Isma'ili history and thought (Cambridge, 1996), p. 224.

86 Bosworth, The later Ghaznavids, pp. 52 6.

87 CI. Cahen, 'La premiere penetration turque en Asie Mineure,' Byzantion, 18 (1948),

p. 49; Minorsky, Studies in Caucasian history, pp. 67 8; Ef 'Shaddadids' (C. E. Bosworth).

54

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

continued there until Alexius Comnenus (r. 1081 1118) emerged victorious.

During these internecine struggles of the Greeks, Turkmens were recruited as

auxiliaries by the various contenders, with the result that Sulayman b. Qutlumush's raiders reached the Sea of Marmara shores by 474/1081 and

captured Nicaea/Iznik. The beginnings of the future Saljuq sultanate of Rum may be placed here, based on Konya which the sultan Mas c ud b. Qilich

Arslan (r.  $510\ 52/1116\ 56$ ) adopted as his capital. It seems unlikely, as future

Rum Saljuq historiography of the seventh/thirteenth century was to assert,

that Malik Shah formally invested Qutlumush's sons (whom he regarded with

suspicion and even hostility) with Anatolia as an appanage. Their assumption

during his reign of the title of sultan seems to have been a unilateral act and

was probably regarded by the Supreme Sultan Malik Shah as derogatory to his

own position.

Within the central lands of the Great Saljuq sultanate, Malik Shah's concern

was to secure the provinces of al Jazira and Syria as buffers against Fatimid

intervention there (although Fatimid power in these regions was waning by

this time) and to bring under control local Arab and Kurdish principalities,

some of which were ShTite in sympathy. Roving Turkmen bands were already operating there, laying the groundwork for what was to be a perma

nent Turkmen ethnic element in northern Syria and Iraq. At the opening of his

reign, Malik Shah sent his brother Tutush to hold Syria as an appanage. Tutush and the commander Artuq b. Ekseb of the Doger clan of the Oghuz

(whose progeny, the Artuqids, were to found a long enduring Turkmen emirate in Diyarbakr) secured southern Syria and northern Palestine, and

Artuq campaigned in eastern Arabia as far as al Ahsa', attacking Carmathian

sectaries there (469/1076^. 89 The Kurdish Marwanids in Diyarbakr were

extinguished by a joint campaign of the caliphal vizier Fakhr al Dawla Ibn Jahir and Saljuq commanders (477 8/1084), and the Arab 'Uqaylids of north

ern Syria and al Jazira were humbled, with the sultan campaigning there personally in 478 9/1085 6. The great cities of the region Mosul, Aleppo, Antioch and Damascus all thus came under Saljuq control. 90 Tutush's personal ambition was to end in his death in 488/1095 when he challenged

the succession of his nephew Berk yaruq (see below), but his sons Duqaq and

Ridwan managed, in the troubled decades after Malik Shah's death, to establish a short lived Saljuq sultanate of Syria, with themselves and their

88 Cahen, 'La premiere penetration turque', pp. 35 6; Cahen, Pre Ottoman Turkey, pp. 73 8.

89 Ibn al Athir, vol. X, pp. in, 183 4; Kafesoglu, Sultan Melik§ah, pp. 31 9.

90 Kafesoglu, Sultan Melik^ah, pp. 40 59; Bosworth, 'The political and dynastic history', PP- 97 9-

55

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

sons in Damascus and Aleppo repectively, as theoretical vassals of the Great

Saljug sultans further east. 91

Malik Shah's relations with the 'Abbasids were at best correct and often hostile. Since Alp Arslan's time there had been in Baghdad a Saljuq ghuldm

governor, Gawhar ayin, as shihna or military commander for the maintenance

of the sultan's authority and interests in the capital and in the wider region of

Iraq. 92 Baghdad was at this time a maelstrom of hostile factions Sunni Hanbalis, Shi'ites in their respective quarters of the city and 'ayyars, bands

of urban desperadoes, everywhere. The sultan tended to leave relations with

the caliphs to Nizam al Mulk, and only came first to Baghdad after his Syrian

campaign, that is, in the mid 1080s. Nizam al Mulk's contacts with the caliph

ate were, of course, conducted with the caliph's own viziers, which substan

tially meant with the Banu Jahir. 93 Relations oscillated between frostiness and

cordiality, the latter when Nizam al Mulk established a friendly relationship

with 'Amid al Dawla Ibn Jahir, sealed by marriage alliances between the two

families, and leading up to the events of 480/1087, when the caliph al Muqtadi

married one of Malik Shah's daughters. 94 A son was speedily born, the short

lived Abu'l Fadl Ja c far, who became the sultan's favourite. But thereafter,

relations rapidly deteriorated, and just before his death the sultan was plan

ning to make Baghdad instead of Isfahan his winter capital, and extensive

building operations were undertaken during the winter of 484 5/1091 2. When Nizam al Mulk was in 485/1092 murdered, ostensibly by Isma'ili assassins, the sultan threw off all restraint and resolved to expel the caliph

from his ancestral capital. It seems that he had the idea of setting up his infant

grandson, Ja'far, as caliph, but any such plans were aborted by Malik Shah's

own sudden illness and death only fifty three days after that of his minister. 95

The death of Nizam al Mulk at the hands of Isma'ili Jida'ts or devotees (if this was not in fact procured, as rumour had it, by the sultan himself, an act

which would have been paralleled by that three centuries before when Harun

al Rashid rid himself of the Barmakids) highlights what was being felt at this

- 91 For the Saljuqs of Syria, see 'AH Sevim, Suriye vefilistin Selftiklan tarihi (Ankara, 1983); EI 1
- 'Saldjukids. III. 4. The Saldjuks of Syria (471 511/ 1078 1117' (C. E. Bosworth).
- 92 Ibn al Athir, vol. X, pp. 70, 112.
- 93 See Ef 'Djahir, Banu' (CI. Cahen).
- 94 Bundari, pp. 72 3; Ibn al Athir, vol. X, pp. no, 120.
- 95 Bundari, p. 70; Rawandi, p. 140; Ibn al Athir, vol. X, pp. 199 200, 204 6; Barhebraeus,

Eng. trans. Budge, p. 231; Kafesoglu, Sultan Meliksah, pp. 203 13. For studies of the

somewhat mysterious death of Nizam al Mulk, see M. T. Houtsma, 'The death of the

Nizam al Mulk and its consequences', Journal of Indian History, 3 (1924), pp. 147 60;

K. Rippe, 'tjber den Sturz Nizam ul Mulks', Fuad Kopriilii armagam, pp. 423 35.

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

time as a threat to the fabric of Sunrii orthodox society by the Nizari Isma'ilis

and the descendants of the earlier Carmathians. Several centres of Nizari activity emerged around this time across the Saljuq empire, including north

ern Syria, the Elburz mountains region, Quhistan in Khurasan, and the region

around Isfahan in Fars, brought into being by da'Ts or propagandists connected

with the Nizari group in Fatimid Egypt. Hasan i Sabbah's seizure in 483/1090

of the fortress of Alamut in north western Persia, the region of Daylam, where

there were long established currents of Shi'ism and heterodoxy, gave the movement a base where a line of chiefs, the Grand Masters, who regarded

themselves as the true heirs of Nizar and the rightful Isma'ili Imams, were to

endure till the appearance in Persia of the Mongol conqueror Hiilegu in 654/1256. These Isma'ilis were dedicated enthusiasts, even fanatics, but cannot

have been all that numerous. Their chosen weapon was not so much action by

large bodies of troops (although on several occasions in the sixth/twelfth century they fielded contingents in northern Persia) as selective political assassination which, in an age when so much depended on personal leadership

and example, could have serious effects on the fortunes of states. It certainly

engendered in the minds of orthodox Muslims something approaching a psychosis, the fear that orthodox Islam was in danger of subversion from within. The Isma'ilis were never a major threat to the fabric of the Saljuq empire, although in the course of the sixth /twelfth century various military

expeditions were to be sent against their mountain strongholds. 96

The Great Saljuq sultanate now entered upon a 'time of troubles'. Three generations of leaders, culminating in Malik Shah, had provided inspired leadership and military success. They had been aided by dashing Turkish slave commanders and efficient Persian administrators, but the unity that they

had achieved, dependent as it was on personal elan plus an ability to keep the

nomadic elements either under control or with their energies directed to external expansion, was precarious. The greatest of all the Persian statesmen

who served them, Nizam al Mulk, had had a view of an ideal Islamic state and

society which he had urged his often reluctant masters to keep before their

eyes and which had made the sultanate something more than a mere

96 M. G. S. Hodgson, Tfie order of Assassins: The struggle of the early Nizari Ismd'ilis against tfie

Islamic world (The Hague, 1955), pp. 41 61; Morgan, Medieval Persia, pp. 43 6; Farhad

Daftary, The Ismd'ilis: Their history and doctrines (Cambridge, 1990), pp. 324 42.

57

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

exploitative, robber state. The centrifugal tendencies inherent in a Turkish

tribal society, with its notions of collective leadership where seniority in kinship, as well as experience in leading warfare, counted, had been kept in

check by the first sultans, at times not without difficulty, and these notions

continued in the consciousness of Saljuq family members, surfacing in times of

uncertainty and crisis. It might have been expected that, on an Ibn Khaldunian

analysis, three generations of expansion were now due to be followed by a

period of decline and collapse, and this was to some extent true for the western lands of the sultanate, although the period of decline there was protracted and the sultanate was an inordinately long time dying (the last Great Saljuq, Toghril (III) b. Arslan Shah, was not killed until almost the end of

the sixth /twelfth century).

Malik Shahs sons Berkyaruq and, especially, Muhammad managed with difficulty to establish some degree of central control, but after 511/1118 their

successors in western Persia and Iraq were embroiled in family dissensions and

rivalries. This provided an opportunity, in regions like Azerbaijan and Arran, al

Jazira and Fars, for the ambitions of Turkish slave commanders, the atabegs,

who often arrogated to themselves the powers of the young Saljuq princes they

were supposed to be nurturing and tutoring. Also, the Abbasid caliphate, after

its years in the doldrums under the Buyids, enjoyed a revival of power and

influence in the course of the sixth /twelfth century, so that the caliphs from al

Mustarshid (r. 512 29/1118 35) up to al Nasir (r. 575 622/1180 1225) became

major players in the military campaignings and power politics of Iraq and western Persia. Iraq was in effect lost to the Great Saljuqs by the early 1150s,

but the last two generations of sultans in the west managed in very difficult.

circumstances to keep the sultanate alive for over three more decades. It was

the misfortune of Arslan Shah (r.  $556\ 71/1161\ 76$ ) and his son Toghril (III)

(r. 571 90/1176 94) to be squeezed between the 'Abbasids in the west and a

new line of vigorous, expanding Khwarazm Shahs of Anushtegin's line who

established a great empire in Transoxania and eastern Persia only to be over

whelmed in the end by the Mongols of Chinggis Khan.

However, while the descendants of Muhammad b. Malik Shah were

squabbling in the western part of the sultanate, the eastern part enjoyed a

remarkable period of some sixty years' comparative stability and governmen

tal continuity under Malik Shah's son Ahmad Sanjar, who became governor of

Khurasan in 490/1097 and remained there until he died in 552/1157, being

recognised after Muhammad's death in 511/1118 as supreme head of the Saljuq

ruling family. What put an end to Sanjar's power in the east was a combina

tion of external pressures, from new political entities beyond the Oxus like the

58

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

Khwarazm Shahs and Qara Khitay, and internal ones from discontented Oghuz tribesmen within Khurasan, who were never reconciled to central control from Sanjar's capital at Marv and whose ranks were continually being

replenished by fresh influxes of nomads from Inner Asia. As well as causing

Sanjar's sultanate to end unhappily, these Oghuz were also responsible for the

demise of the Saljuq line in Kirman in c. 584/1188. Only in Anatolia did the

name endure in the shape of the Rum Saljuqs, who enjoyed a glorious existence in the sixth /twelfth century but after 641/1243 fell back into the

status of vassals of the Mongols for the last sixty years or so of their existence.

With the support of the Nizamiyya, the youth Abu'l Muzaffar Berk yaruq (Tkish. 'firm, strong brightness') was raised to the throne at Rayy on his father's death against a rival party in Isfahan of the Chief Secretary Taj al Mulk

Abu'l Ghana'im and Malik Shah's Qarakhanid queen and widow Terken Khatun, who favoured the latter's infant son Mahmud. Mahmud in fact

conveniently died soon afterwards, and Berk yaruq secured the sultanate for

himself, being recognised in 487/1094 by the caliph al Mustazhir, but was

beset by a host of rival Saljuq claimants to the throne: Isma'il b. Yaquti in Azerbaijan and, more seriously, two of his uncles, Arslan Arghun in Khurasan

(whose power there only ended with his death at the hands of his ownghuldms

in 490/1097) and Tutush in Syria. Tutush (Tkish. 'he who grasps [power]') had

a strong army at his disposal, and was soon in control of Baghdad, but Berk

yaruq met him in battle near Rayy and defeated him in 488/1095, and Tutush

was slain. The seat of Berk yaruq's power was essentially Iraq and western

Persia, that is, Fars and Jibal, and in 490/1197 he appointed his half brother

Ahmad Sanjar (Tkish. 'he who pierces, thrusts') as governor of Khurasan, providing him with an atabeg and a vizier. 97 Berk yaruq campaigned in Khurasan against Arslan Arghun, and it was at this time that he had to send

to Khwarazm his commander, the Amir i Dad ('chief justiciar') Habashi, and

who now appointed as governor there, with the title of Khwarazm Shah, Qutb al Dm Muhammad, the son of Malik Shah's governor there Anushtegin

Gharchal. This was the origin of the last and most brilliant line of Khwarazm

Shahs, who were to become in the course of the sixth/twelfth century a major

power in Turkistan and Khurasan. After this time, distractions in the west compelled Berk yaruq to leave Sanjar at Balkh substantially to govern the east

on his own with the title of malik 9

97 Bundari, pp. 82 6; Husaynl, pp. 74 6; Rawandl, pp. 140 3; Ibn al Athlr, vol. X, pp. 229,

244 5, 262 5; Bosworth, 'The political and dynastic history', pp. 102 6.

98 Ibn al Athlr, vol. X, pp. 265 8; Juwayni, Tdrikh i Jahdn gushd, Eng. trans. J. A. Boyle

(Manchester, 1958), vol. I, pp. 277 8; Barthold, Turkestan, pp. 318 19.

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

Back in the west, Berkyaruq's power remained uncertain, and outlying parts were never under his control. His half brother Muhammad Tapar (Tkish. 'he who obtains, finds') was in Arran, but soon threw off the control

of his atabeg and used north western Persia as his base for a bid for the caliphate. Hence all the years left to Berkyaruq, that is, 490 8/1097 1105, were taken up with a struggle against his rival Muhammad, who by now had

the support of most of the Nizamiyya and of his full brother Sanjar, who provided him with troops. In desperation, Berk yaruq seems at times to have

had to call on contingents of Isma'ili troops from northern Persia for help.

In 495/1102 he was compelled to cede to Muhammad the tide of malik and the provinces of Azerbaijan and Arran, aljazira, Syria and Diyarbakr, but Muhammad soon repudiated this arrangement. Berkyaruq besieged Muhammad in Isfahan and defeated his army in Azerbaijan, but worn out by illness and continual campaigning, decided to make peace, with the provisions that each of the two half brothers should have the title of sultan

in his own right, Muhammad to keep the provinces he had been allotted

Berkyaruq to retain the heartlands of the empire, Iraq, Jibal, Fars and Khuzistan. In the next years, however, Berk yaruq died at the age of only twenty five, and Muhammad succeeded by default to the whole of the lands

west of Khurasan and the title of Supreme Sultan."

During the years of internecine warfare, the lands fought over were ravaged and plundered by each side; regular taxation could not be collected,

and irregular, forced levies had to be made in order to pay armies. The Turkish ghuhxtn commanders and tribal chiefs would, for their part, sell their

services to either side, but had a vested interest in seeing that no strong, central power emerged from the struggle. Hence it is at this time that, out of

the various appanages nominally held by Saljuq princes after Malik Shah's

death but in practice often ruled by their Turkish atabegs, various lines of the

latter begin to emerge: the sons of Bursuq in Khuzistan, the Shah i Armanids

at Khilat in eastern Anatolia, the Artuqids in Diyarbakr and, slightly later, the

Zangids at Mosul.

Muhammad reigned for thirteen years as undisputed sultan (498 511 / 1105 18),

while Sanjar remained as viceroy of the east, with his court and administration

now established at Marv and with the title of malik. The sources praise Muhammad as a just and pious ruler, although he does not seem to have been

99 Bundari, pp. 87 9, 261; Husaynl, pp. 76 8; Rawandi, pp. 145 9; Ibn al Athir, vol. X,

pp. 287 8, 329 31, 333 5, 369 72, 380; Bosworth, 'The political and dynastic history',

pp. 108 11; and for a further connected account of Berk yaruq's reign, M. F. Sanaullah,

The decline of the Saljuqid empire (Calcutta, 1938), pp. 91 113.

60

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

a more capable military commander than Berk yaruq was. He did, however.

have the advantage of a period of peace. Hence he was able to give a small

amount of help to the amirs of Syria, such as the dispossessed prince of Tripoli,

Ibn 'Ammar, now challenged by the Frankish Crusaders, and he campaigned in

Daylam and in the Isfahan region against the Isma'ilis, who had been able. in the

disturbed conditions of the time, to increase their power in those regions and in

Quhistan; both lines of policy were calculated to give the sultan kudos in the eyes

of the religious classes. Within central Iraq, Muhammad strengthened his position by humbling the ShTite Arab Mazyadids of Hilla, and his good relations

with the Abbasids were sealed by the marriage in 502/no8f of Muhammad's

sister to the caliph al Mustazhir. In western Persia, his governor in Fars, Chavh

Saqa ] 6, brought prosperity to his province by curbing the predatory Shabankara'i Kurds. 100

Muhammad died in 511 / 1118, the last Great Saljuq to exercise substantial control

over the western provinces of the sultanate. As his successor, he appointed his son

Mahmud, who was to reign for fourteen years (511 25/1118 31), but there were

four other sons of Muhammad, sc. Mas'ud, Toghnl, Sulayman Shah and Saljuq

Shah, who at various times exercised power in different areas, all but the last

actually gaining the title and authority of sultan. Muhammad had held in check

the tendencies to division and disunity, but these now had full play; the succession

was permanently disputed, with up to three or four claimants at any one time.

These royal aspirants to power could only gain support from the Turkish amirs by

alienating to them more and more land as iota's, thus reducing their own fiscal

resources, and these commanders were now able to intervene even in the sultan's

own administration. Thus Anushirwan b. Khalid (whose Persian chronicle of his

times, now lost, forms, via an Arabic version by c Imad al Din al Isfahan!, the

ultimate basis of Bundari's Arabic epitome, the Zubdat al nusra) served as vizier to

the Saljuqs Mahmud and Mas'ud and to the 'Abbasid caliph al Mustarshid, and

accordingly had first hand experience of affairs. 101 He lamented the parlous state

of the realm: 'In Muhammad's reign the kingdom was united and secure from all

envious attacks; but when it passed to his son Mahmud, they split up that unity

and destroyed its cohesion. They claimed a share with him in the power and left

him only a bare subsistence.' 102

100 Ibn al Balkhi, Fars noma, pp 165, 167; Bundari, pp. 117 18; Husaym, pp. 81 2; Ibn al

Athir, vol. X, pp. 244, 452 3, 471, 527 8; Sanaullah, The decline of the Saljuqid empire,

pp. 114 32; Bosworth, 'The political and dynastic history', pp. 113 19.

101 See EIr 'Anuservan Kasani' (C. E. Bosworth).

102 Bundari, p. 134; Ibn al Athir, vol. X, pp. 525 7.

61

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

At the outset, Mahmud faced an invasion from his uncle Sanjar, who among

other things alleged that Mahmud was encouraging the Qarakhanids to attack

him in his rear. Sanjar' s powerful army was said to have included four vassal

kings with their troop contingents, and he had with him war elephants. Not

surprisingly, Mahmud was defeated near Sawa in Jibal and Sanjar advanced as

far as Baghdad; in the ensuing peace settlement, Mahmud had to cede to Sanjar territories south of the Caspian including the strategically highly important city of Rayy. Mahmud's brother Toghnl held lands in northern Jibal, from where he rebelled against Mahmud's authority; while Mas'ud, in

Mosul, al Jazira and Diyarbakr, and with support from local Turkmen bands

and Kurdish chiefs, likewise refused allegiance. Mahmud was, however, able

to maintain the Saljuq position, in part because of the Abbasids' fear of their

powerful and hostile neighbour, the Mazyadid amir Dubays b. Sadaqa. These

troubles allowed Mahmud to give only intermittent attention to the external

frontiers of the realm. In the north, the Georgians were resurgent under their

forceful king David the Restorer (r. 1089 1125), who recaptured Tiflis and Am

from the Muslims, threatened the lands of the Shirvan Shahs in eastern Transcaucasia and withheld tribute from the Saljuqs. Mahmud could do little

against these actions, despite a personal appearance in the region, and later in

his reign the Georgians were able temporarily to capture Ganja. 103

Mahmud's death in 525/1131 brought further internal crises, with his young

son Dawud proclaimed sultan in Hamadan but with parallel claims from Mas'ud in Iraq and Saljuq Shah in Fars and Khuzistan. As senior member of

the dynasty, the mediation of Sanjar was sought, but he only now pushed the

claims of his own protege Toghnl. The threat of a Qarakhanid revolt in Transoxania prevented him from giving much aid to Toghnl, and when the

latter died in 529/1134 after reigning in Azerbaijan alone as the sultan Toghnl

(II), Mas'ud managed to secure the throne in Hamadan in the face of oppo

sition from Dawud, now in Azerbaijan, and began a reign of almost twenty

years (529 47/1134 52), the longest of any sultan in the west since Malik Shah.

His authority was nevertheless largely confined to Jibal and central Iraq. Azerbaijan was the centre of Dawud's limited authority, but the province fell under the control of Turkish commanders, with Shams al Din Eldigiiz as

atabeg for the young Arslan b. Toghnl (II) in Tabriz and Aq Sonqur b. Ahmadili in Maragha; Fars was dominated by Mas'ud's enemy, the amir

103 Sources for the period and connected narrative are given in M. A. Koymen, Biiyiik

Selcuklu imparatorlugu tarihi, vol. II: Ikinci imparatorluk devri (Ankara, 1954), pp. 5 148,

164 73, and Bosworth, 'The political and dynastic history', pp. 119 24; see also W. E. D.

Allen, A history of the Georgian people (London, 1932), pp. 96 100.

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

Boz aba; and Zangi b. Aq Sonqur, son ofaghuldm commander of Malik Shah,

from a base at Mosul built up a powerful principality in al Jazira, Diyarbakr

and northern Syria. 104

During his early years, Mas'ud had been able to curb the growing power of

the 'Abbasids, capturing al Mustarshid in a battle near Hamadan, shortly after

which the caliph was murdered by Isma'irl assassins. 105 The new caliph al Rashid

was soon embroiled with the sultan over non payment of tribute due to the

Saljuqs, and Mas'ud's authority reached its peak when in 530/1136 he deposed

al Rashid after the caliph had reigned only two years (529 30/1135 6). ro But

thereafter, the capable and energetic new caliph al Muqtafi (r. 530 55/1136 60)

built up his army with Armenian and Rumi ghuldms instead of unreliable Turkish ones, strengthened the defences of Baghdad and was able on several

occasions to defy the Saljugs. 107

In the middle and later parts of his reign, Mas'ud fell more and more under

the influence of the Turkish amirs. He was beset by over mighty and ambitious

commanders. Two of these, 'Abbas of Rayy and Boz aba of Fars, who had in

their care two young sons of the former sultan Mahmud, in 54o/ii45f raised up

a rebellion, which Mas'ud managed to quell, but he was not free of the threat.

from Boz aba till the latter was killed during a further outbreak a year later. On

his western flank, Mas'ud's authority had been eclipsed by the spectacular

successes of Zangi, a Muslim hero after his capture of Edessa from the Crusaders in 539/1144; the threat from Zangi was only relieved by Zangi's

death in 541/1146. The sultan was thus able at last to break out of the encircling

grip of the Turkish atabegs and amirs. He now relied much on his favourite, the

amir Khass Beg Arslan b. Palang eri, but this excessive dependence on Khass Beg

raised up in 543/1148 a coalition of excluded and discontented amirs, who

espoused as a candidate for the sultanate one of Mahmud's sons, Malik Shah.

Mas'ud was besieged in Takrit, but the coalition then dispersed, and Mas'ud's

temporary ally the caliph al Muqtafi (both the sultan and the caliph feared

Mazyadid dominance in central Iraq) had successfully defended Baghdad. 10

Mas'ud died in 547/1152 without a direct heir. Ibn al Athir lamented that 'With him the fortunes of the Saljuq family died; after him, there was no banner

104 Bundari, pp. 156 75, 184, 219 20; Ibn al Athir, vol. X, pp. 669 70, 674 8, 686 7. For

connected narratives of the reigns of Toghnl and Mas'ud, see Koymen, Ikinci impar

atorluk devri, pp. 203 300, and Bosworth, "The political and dynastic history', pp. 124 33.

105 Bundari, pp. 176 8; Husayni, p. 107; Ibn al Athir, vol. XI, pp. 24 8.

106 Ibn al Athir, vol. XI, pp. 35, 42 3.

107 Bundari, p. 235.

108 Bosworth, 'The political and dynastic history', pp. 130 4.

### The New Cambridge History of Islam

for them to rely upon or turn to "Qays's death was not the death of a single

man, but rather the collapse of a whole tribe's foundations." 109 There were

several Saljuq princes, including a brother of Mas'ud and various nephews, with

claims to the succession. Muhammad (II) b. Mahmud (r. 548 54/1153 9) is

praised by 'Imad al Din as 'the most majestic, the most learned and the most

just of the Saljuqs', but two other ephemeral rulers were of mediocre capability.

In 551 2/1157 Muhammad had advanced on Baghdad, but after a prolonged siege

of the city, had to withdraw on receiving news of a threat to his position in Jibal

from his brother Malik Shah and Eldigiiz. 110 Thus, after Mas'ud' s death, there

was no longer a shihna of the sultan in Baghdad; al Muqtafi appropriated all

buildings and properties of the Saljuqs in the city, so that all Saljuq influence

ended there.

#### VII

In contrast to the vicissitudes and difficulties of the Great Saljuqs in Iraq and

western Persia, the eastern part of the empire, governed by Sanjar b. Malik

Shah since Berk yaruq's time, enjoyed a continuity of administration for more

than half a century, while the Saljuq amirs in Kirman, substantially untroubled

in their comparative geographical isolation, were to survive almost till the end

of the sixth/twelfth century (see below, p. 73). Constitutionally, Sanjar at first

styled himself on his coins merely as Malik or Malik al Mashriq, 'King of the

East', and recognised his brothers Berkyaruq and Muhammad as Supreme

Sultan, al Sultan al Mu'azzatn. But when Muhammad died in 511/1118, Sanjar

regarded himself, in accordance with the old Turkish principle of the senio

rate, as the senior figure in the dynasty and immediately placed on his coins

the title of Supreme Sultan, regarding his nephew Mahmud b. Muhammad

and his successors as subordinate to him. 111 His court at Marv paralleled those

of his kinsmen in western Persia and Iraq at Isfahan and Hamadan, and he had

a fully developed administration in Marv directed from a diwan i a'la and presided over by a vizier (the names of several of these are known) and with a

109 Ibn al Athir, vol. XI, pp. 160 1.

no Bundaii, p. 288; Husayni, pp. 134 9; Rawandl, pp. 266 9; Pseudo Zahir al Din

Nishapuri, trans. Luther, pp. 130 2; Ibn al Athir, vol. XI, pp. 312 55.

in Bosworth, 'The political and dynastic history', pp. 135 6; C.E. Bosworth, 'The Saljugs

and the Khwarazm Shahs. Part 3. The eastern Seljuq sultanate (1118 57) and the rise and

florescence of the Khwarazm Shahs of Anushtegin's line up to the appearance of the

Mongols (1097 1219)', in UNESCO, History of the civilizations of Central Asia, vol. IV: The

age of achievement: AD 750 to the end of the fifteenth century. Part 1, Tfte historical, social and

economic setting (Paris, 1998), pp. i6iff. Bf 'Sandjar b. Malik Shah' (C. E. Bosworth).

64

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

busy chancery under the Chief Secretary. We know quite a lot about the central and provincial administration exercised from Marv through the survival

of copies of documents issued by this chancery, several of which concern the

appointment of provincial governors. Thus an investiture document for Sanjar's nephew Mas'ud b. Muhammad as governor of Gurgan stresses the

importance of this region, at the south eastern corner of the Caspian Sea, as a

ihaghr or frontier defence region against the infidel Turks of Dihistan and Manghishlaq. He is enjoined to facilitate safe travel through his lands, to listen

to complaints of oppression, to collect taxation only at the official rate laid

down (i.e. he is not empowered to alter the official tax rates), to pay out the

official salaries of his subordinates, and to consult with the leading men and the

masses of people alike. It was recognised that the Turkmens were a special case

and that they were a chronically unruly element. Thus other documents concern the appointment of a shihna, that is, in this context the official charged

with administering tribesmen in a tribal area, in this instance, the Turkmens of

Gurgan, and with keeping order among them. 112,

Sanjar's role in the events of Mahmud's reign and his support for Toghril (II) b. Muhammad in Azerbaijan have been mentioned above (p. 62), but after

his intervention in western Persia of 526/1132 against Mas'ud b. Mahmud it

was happenings in Khurasan, Transoxania and Khwarazm which came vir tually to monopolise his attention in the seat of his power, Marv.

The considerable Saljuq cultural influence within the later Ghaznavid sulta

nate has been noted. When the Ghaznavid sultan Mas'ud (III) b. Ibrahim died in

508/1115, a succession dispute between his two sons, Bahram Shah and Malik

Arslan or Arslan Shah, ensued, carried on at both the diplomatic and military

levels. The former appealed to Sanjar for help. The Saljuq sultan led a powerful

army to Ghazna, defeated Malik Arslan and placed Bahram Shah on the throne

as his vassal. Apart from an episode in 529 30/1135 6 when Bahram Shah

stopped paying tribute to Marv, bringing down on himself a second Saljuq

attack on Ghazna which temporarily expelled him to his north west Indian

possessions, most of his four decades of rule was as Sanjar's liege, a dependence

seen in the legends on Bahram Shah's coins minted at Ghazna. 113

112 A. K. S. Lambton, 'The administration of Sanjar's empire as illustrated in the 'Atabat al

kataba', Bulletin of the School of Oriental and African Studies, 20 (1957), pp. 376 8, 380 2 (the

author of this collection of insha', official documents, was the head of Sanjar's chancery

at Marv); Heribert Horst, Die Staatsverwaltung der Grosselguqen und Horazmsahs

(Wiesbaden, 1964), pp. 43 60.

113 Ibn al Athir, vol. X, pp. 504 8; Juzjani, Tabaqat i nasirl, ed. 'Abd al Hayy Habibi (Kabul,

1342 3/1963 4), vol. I, pp. 241 2, Eng. trans. H. G. Raverty (London, 1881 99), vol. I,

p. 107; Bosworth, Tfte later Ghaznavids, pp. 89 98, 99 101.

65

Cambridge Histories Online  $\ \ \,$  Cambridge University Press, 201 1

The New Cambridge History of Islam

Ghazna was on the remote periphery of Sanjar's dominions. Much more immediately acute for him were relations with the Qarakhanids of Transoxania and with Khwarazm. At the beginning of his governorship, Sanjar had to repel an attack by a Qarakhanid originally from the eastern branch of the family and a great grandson of Qadir Khan Yusuf, Jibrall b. 'Urnar (495/1102), whose troops captured Tirmidh and penetrated into Khurasan. 114 Sanjar now took steps to place on the throne in Samarqand a

more compliant vassal, a great grandson of Tamghach Khan Ibrahim b. Nasr,

Arslan Khan Muhammad b. Sulayman, who was to enjoy a rule there of some

thirty years (495 524/1102 30). He was further attached to the Saljuq cause by

a marriage alliance with one of Sanjar's daughters, receiving military aid from

the Supreme Sultan against a challenger to his succession. He regularly led

slave raids into the steppes against pagan Qipchaqs, earning the title of Ghdzi,

and became known as one of the greatest builders of his dynasty, restoring the

walls and citadel of Bukhara, laying out palaces and an c Tdgdh or open area for

the celebration of the Muslim festivals, and erecting a splendid congregational

mosque. Only at the very end of his reign, when Arslan Khan was a sick man

and when the religious institution, which had a long history of antagonism

towards the khans, caused discord in the state, did Sanjar again appear at

Samarqand, plundering part of the city and deposing Arslan Khan (524/1130).

Sanjar now placed various short lived rulers on the throne, his choice finally in

526/1132 lighting on his own nephew (through his earlier marriage to a Qarakhanid princess) Mahmud, third son of Arslan Khan. 115

Mahmud proved a faithful ally of the Saljuqs, and his fortunes were to be closely intertwined with those of the dynasty in Khurasan. When Mahmud became at odds with unruly Qarluq tribesmen in his military following, he appealed to Sanjar for help, whereupon the Qarluq in turn called upon the

new power which had just appeared in Turkistan, that of the Qara Khitay (see

on them, below). It was this episode that provoked the Qara Khitay invasions

of Transoxania and Khwarazm and led to Sanjar's crushing defeat of 536/1141

at the Qatwan steppe in Ushrusana to the east of Samarqand, dealing a severe

blow to the sultan's prestige in the east. Mahmud fled with Sanjar to Khurasan

and remained there, while in Transoxania the Qara Khitay set up one of his

brothers, Tamghach Bughra Khan Ibrahim (r. 536 51/1141 56), who likewise

114 Barthold, Turkestan, pp. 318 19; Pritsak, 'Die Karachaniden', p. 49.

115 Ibn al Athir, vol. X, p. 350; Barthold, Turkestan, pp. 319 22; Pritsak, 'Die Karachaniden',

pp. 50 2; Davidovich, 'The Karakhanids', p. 131.

66

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

later fell out with his Qarluq troops and was in the end defeated by them in

battle and killed. 11

Mahmud later fell heir to Sanjar's position in Khurasan. One of Sanjar's perennial problems was controlling the pastoralist nomads who had become

an increasingly significant element in the countryside of Khurasan, with their

numbers frequently replenished by fresh arrivals of Oghuz, apparently forced

out of the Inner Asian steppes by pressure from the Qarluq; their increased

numbers probably meant increased pressures on the sedentary population of

Khurasan and encroachments by the nomads upon the settled agricultural

lands. Sanjar's frequent military campaignings placed a heavy financial burden

on his subjects, and his tax collectors had to resort to increasingly harsh measures. Eventually, in 548/1153, a group of Oghuz who nomadised on both sides of the upper Oxus, in Khuttal and in Tukharistan, rebelled against

these exactions. They had been accustomed to handing over an annual tribute

of 24,000 sheep for the sultan's kitchens, but this had become exacted with

increased brutality. Sanjar refused all compromise and led an expedition

against these Oghuz, but was defeated and captured by them, after which

the Oghuz swept through Khurasan and sacked cities like NTshapur, taking an

especial vengeance on the sultan's officials and on members of the religious

institition, whom they regarded as closely linked with the established order.

Although the polite fiction was maintained that Sanjar was the guest of the

Oghuz, he was in fact closely guarded (according to Juwaym, they paraded

him around on a throne during the day, but locked him up in a cage at night 117 ), and only managed to escape three years later. His prestige was totally

shattered; the leaderless army of Khurasan had become accustomed to choos

ing its own amirs as leaders, and, very soon after his liberation, Sanjar died

(552/1157). While Sanjar had been in captivity, the Qarakhanid Mahmud Khan

was recognised by the Saljuq army in Khurasan as legitimate malik of Khurasan. He had moved his own residence to Nishapur and had left his son Muhammad as regent in Transoxania; and after Sanjar's death and the

extinguishing of Saljuq rule in the east, he continued to rule from Khurasan till

his own death in 557/1162."

116 Ibn al Athir, vol. XI, p. 202; Barthold, Turkestan, p. 333; Pritsak, 'Die Karachaniden',

p. 53; Davidovich, 'The Karakhanids', p. 132.

117 Juwaym, trans. Boyle, vol. I, p. 285.

118 Bundari, pp. 277 81; Rawandi, pp. 172 4; Pseudo Zahir al Din Mshapuri, trans. Luther,

pp. 88 95; Ibn al Athir, vol. XI, pp. 81 6, 183; Juwayru, trans. Boyle, vol. I, pp. 285 6, 289;

Barthold, Turkestan, pp. 326, 329 31; M. A. Koymen, 'Biiyiik Selcuklar imparatorlugunda

Oguz isyam', Ankara Universitesi Dil ve Tank Cografya Fakultesi Dergisi, 5 (1947), pp. 159 73,

Ger. trans, at pp. 175 86; Pritsak, 'Die Karachaniden', pp. 52 4.

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

The beginnings of the Khwarazm Shahs of the line of Anushtegin during the reigns of Malik Shah and Berk yaruq go back to the appointment of Outb

al Dm Muhammad as Shah, as mentioned above (p. 59). Now, for the first and

last time in its history, Khwarazm was to become under his descendants the

centre of a military empire embracing large stretches of Central Asia and much of Persia. The basis for this success was not only the ambitions and the

military skills of the Shahs, which could come into play when the earlier great

powers that had dominated the region, the Qarakhanids and the Saljuqs, were

at best in a static if not declining state, but the fact that Khwarazm was an

agriculturally rich region. It had a highly sophisticated system of canals and

irrigation channels, and towns which flourished on trade between the Islamic

lands and the Eurasian steppes, the Khwarazmians themselves always having

been great travellers, attested by traces of their presence in the toponymy of

south Russia and even Hungary. 119 Thus with a strong financial base, the shahs

had the sinews of war at their disposal. It was to be their bad luck in the early

seventh/thirteenth century to come up against a foe whose ruthlessness and

violence were on a scale hardly known previously in the Islamic lands, the

Mongols of Chinggis Khan. 12,0

Qutb al Dm Muhammad (governor 490 52.1/1097 112,7), as a Saljuq appointee, remained Sanjar's faithful vassal, with frequent attendance at his

court in Marv and provision of troops for the Saljuq armies on various

occasions. It is unclear why the sultans departed from the principle which,

certainly in their heyday, they tried to follow elsewhere in the empire of avoiding the creation of hereditary lines of provincial governors. Sanjar was a

far stronger monarch than his kinsmen further west, who had not the prestige

or military strength to curb the formation of hereditary lines of local gover

nors and atabegs. It may be that Khwarazm was adjudged a special case; it was

almost an island of flourishing agriculture and civilised Islamic life jutting out.

into the steppes, a good number of whose tribal inhabitants were still pagan.

On this analysis, it was sensible of Sanjar to send there commanders of proven

ability who knew the local conditions and who could cope with the nomadic

pressures that surrounded much of Khwarazm, even if this meant allowing a

hereditary line to develop there, with all the attendant temptations to rebel

lion and independence.

119 A. Z. V. Togan, The Khorezmians and their civilisation, Preface to his facsimile edn. of

Zamakhshari's Muqaddimat al adab (Istanbul, 1951), pp. 2off.

120 For histories of the shahs, see Ibrahim Kafesoglu, Harezmsahlar devleti tarihi (48; 617/

1092 1229) (Ankara, 1956); Z. M. Bunyatov, Gosudstarstvo Khorezmshakhov Anushteginidov (Moscow, 1986).

68

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

The next Shah, 'Ala' al Din Atsiz (governor 521 51/1127 56), was the real founder of his family's fortunes. Though nominally subject to Sanjar almost to the end and initially respectful, sending troops for Sanjar's campaigns, he pursued a calculated policy of securing as much autonomy as possible for Khwarazm, with independence as an ultimate goal. He secured his northern borders by extending control over the Oghuz and others of Manghishlaq to the east of the Caspian and over the Qipchaqs beyond the Aral Sea, recruiting many of them into his army, irrespective of

whether they were Muslim or pagan. He intervened militarily, when occasion arose, in the affairs of his Qarakhanid neighbours, at a later date

dealt cautiously with the Qara Khitay who came to control Transoxania (see below) and took advantage of Sanjar's difficulties with the Oghuz tribesmen in Khurasan.

Atsiz had unsuccessfully rebelled against Sanjar in 533/1138, but this flooding

of the lower Oxus valley failed to Sanjar's advance; he defeated the Shah and

temporarily installed a Saljuq nominee in Gurganj. But a further expedition of

538/ii43f, provoked by Atsiz's raids into Khurasan as far as Bayhaq and NTshapur, could not establish a permanent Saljuq presence in Khwarazm;

the Shah seems to have had solid support from his Khwarazmian subjects.

Sanjar's defeat at the Qatwan steppe emboldened Atsiz further to pursue his

own ends, although during Sanjar's captivity at the hands of the Oghuz he

showed remarkable restraint; and when Sanjar managed to escape after three

years, his negotiations with the Qarakhanid ruler in Khurasan, Mahmud Khan,

for joint intervention against the Oghuz, were put on hold. Thus Atsiz was still

nominally a vassal of Sanjar when he died only a few months before the sultan

himself.

The Qara Khitay have been mentioned, and this people of Far Eastern origin now played a part in the history of Islamic Transoxania, without their

ever becoming Muslims. The Qara Khitay stemmed from the Khitan Liao, probably Mongolian in ethnos, who had been regarded by the Chinese Song

emperors as a legitimate Chinese dynasty living north of the Great Wall. In

the early twelfth century, under pressure from another people of the Siberian

fringes, the Tungusic Jiirchen of Manchuria, a part of the Liao migrated across

the Altai and Tien Shan mountains into the Semirechye, founding there an

empire based on an ordo or tented encampment near the Muslim town of Balasaghun. They then extended into eastern Turkistan, northwards into the

upper Yenesei valley and westwards into Transoxania. The Qara Khitay were

thus ostensibly one more wave of Inner Asian peoples into the settled Islamic

lands, but with a difference from, for example, the Qarluq and Oghuz, who

69

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

had taken over Turkistan and founded the Qarakhanid and Saljuq political

groupings, or from the Mongols who succeeded them, with their policies of

massacre and terror against all who opposed them. The Qara Khitay leader,

the Tianyou, 'One protected by Heaven' in the Chinese context, or the Giirkhan, a new title meaning 'Universal Khan' in the Islamic one, was content

to leave in place existing rulers, in practice the various branches of the Qarakhanids and the Khwarazm Shahs, with free exercise of their own Islamic religion provided they handed over regular tribute to the Giirkhan.

It seems that the Qara Khitay felt no attraction towards the Islamic religion

because they lived outside the towns which were centres of Muslim life and

because they regarded the Chinese Liao position, which attached them to the

Chinese religious and cultural world, as superior. 12,1

Hence the appearance of the Qara Khitay in the Islamic lands did not make a

great difference to life there. Their requirements of the local people were essentially fiscal; at least at the outset, their yoke was light, and Muslim sources

regard them, for infidels, comparatively favourably. 122. They possessed, how

ever, a powerful military machine, as they showed when in 536/1141 they humbled Sanjar (who seems deliberately to have provoked them). From the

time of II Arslan (r. 551 67/1156 72), the Khwarazm Shahs at times chafed under

Qara Khitay financial control, but the withholding of tribute usually provoked

punitive expeditions into Khwarazm. The next Shah, Tekish (r. 567 96/1172

1200), owed his succession to the throne to intervention by the Giirkhan's son

in law Fuma (Chin, fu ma 'son in law of the emperor'), but sought an early

opportunity to throw off their control. The Islamic sources state that the Qara

Khitay tax collectors, who had originally behaved in an impartial and equitable

manner, had become increasingly arrogant and oppressive. The looseness of

power relationships within the ruling family of the Qara Khitay, and lax control

over subordinates, may have contributed to this; but it may be that, latterly, the

shahs raised the banner of jihad against the Qara Khitay on any pretext that came

to hand in an attempt to pacify the orthodox religious classes aroused by the

shahs' anti c Abbasid policies.

121 See histories of the dynasty in W. Barthold, History of the Semirechye, in Four studies on

the history of Central Asia, trans. V. and T. Minorsky (Leiden, 1962), vol. I, pp. 100 7;

Barthold, ZwolfVorlesungen, pp. 120 6; Denis Sinor, 'The Khitan and the Kara Khitay', in

UNESCO, History of civilizations of Central Asia, vol. IV, part 1, pp. 227 42; Michal Biran,

The empire of the Qara Khitai in Eurasian history: Between China and tfte Islamic world

(Cambridge, 2005); Ef 'Kara Khitay' (C. E. Bosworth).

122 A contemporary, Nizami 'Arudi Samarqandi, speaks of the 'boundless justice' of the

Giirkhan in his Chahar maqdla, ed. Muhammad Qazwini and Muhammad Mu'in

(Tehran, 1333/1954), p. 38.

70

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

After Sanjar's capture by the Oghuz, Khurasan entered into an administra

tive limbo. The Oghuz were too disorganised and unsophisticated to form an

organised state there, and, after the sultan's death, power became divided out

among the former Saljuq amirs under the general overlordship of the Qarakhanid Mahmud Khan (see above, pp. 667). The most powerful of these was Sanjar's ghuldm Mu'ayyid al Din Ay Aba (d. 569/1174), who estab

lished himself at Nishapur, eventually as a vassal of Mahmud Khan, and earned a reputation for his wise and just rule.

#### VIII

The Great Saljuqs of the west had almost forty years of continued life after

Sanjar's death, but their power became more and more circumscribed. One

significant factor here was the growing political and military power of the Abbasid caliphs, increasingly inclined now to assert their secular rights. Al Muqtafi, as well as recruiting troops, excluded the Saljuq shihnas from Baghdad after the death of Sultan Mas'ud b. Muhammad (see above, p. 64),

and he was aided by a formidably energetic vizier, 'Awn al Din Yahya Ibn Hubayra (d. 560/1165), accorded by his master the title of 'Sultan of Iraq' after

the ejection of the shihna from the capital. 123 A wide ranging 'Abbasid diplo

matic policy was adopted; links were made, for example with the Sunni hero

of Syria, Nur al Din b. Zangi; and the caliphs themselves now took the field at

the head of their armies. There was a strongly Hanbali ethos at the heart of the

caliphate in Baghdad, against the Shi'ite influence centred on the great Shi'ite

shrine cities of central Iraq.

The peak of caliphal influence in Iraq and western Persia came under al Nasir (r. 575 622/1180 1225). I24 Al Nasir had a vision of a rejuvenated Islamic world and hoped to establish the caliphate once more as the spiritual and secular focus for the aspirations of all Muslims, whatever their sectarian loyalties, and certainly including the Sunnis and moderate Shi'ites. An aspect of his ethical and moral policy here was his encourage ment of a system of political alliances backed by membership of the

123 See on him Herbert Mason, Two statesmen of medieval Islam: Vizir Ibn Hubayra (499

560AH/110; 1165AD) and Caliph an Nasir li Din Allah (#3 622AH/1138 i2i;AD) (The Hague

and Paris, 1972), pp. 13 66; Angelika Hartmann, 'Ibn Hubaira und an Nasir li Dm Allah',

Der Islam, 57 (1976), pp. 87 99.

124 See the magistral study of Angelika Hartmann, An Nasir li Din Allah (1180 1225). Politik,

Religion, Kultur in der spaten 'Abbdsidenzeit (Berlin and New York, 1975); EI 2 'al Nasir li

Din Allah' (Hartmann).

71

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

chivalric orders of the futuwwa. 1 \* 5 He himself joined the Rahhasiyya order

at Baghdad in 578/n82f. and personally introduced into it other potentates,

including members of the Ayyubid family, the Rum Saljuqs and, at the other end of the Islamic world, the Ghurid sultans. Although his efforts here in the central and eastern lands of Islam did not survive the Mongol cataclysm, the ideals and practices of futuwwa did have a a clear influence

in the Anatolia of the later Saljuqs and the succeeding beyliks, in the shape

of the akhi groups in the towns there. 11 The caliph undoubtedly scored

great success in orthodox Sunni eyes by bringing back into the fold of orthodoxy the new Grand Master of the Isma'ilis of Alamut, Jalal al Din Hasan (III) b. Muhammad (acceded to power in 607/1210), who publicly proclaimed his abandonment of the doctrine of qiyama, the return of the Expected Imam just before Resurrection Day, and declared his adhesion to

Sunni Islam. On the Talisman Gate at Baghdad, which al Nasir now erected (no longer extant), the great Swiss epigraphist Max Van Berchem interpreted the decoration showing a human figure with his hands on the heads of two dragons as representing the caliph's triumph over his two great enemies, the Isma'ili Grand Master and the Khwarazm Shah 'Ala' al Din Muhammad. 127

Al Nasir's main enemy in western Persia was the remaining Great Saljuq, Toghril (III), against whom he concentrated his efforts. In 583/1187 he ordered

the old Saljuq palace in Baghdad, the symbol of tutelage by an outside regime,

to be torn down. 12 The sources are not wholly explicit, although one at least,

Ibn al Athir, does state that al Nasir egged on the Khwarazm Shah Tekish in order to dispose of Toghril, 129 even though the Khwarazm Shahs, with

their long term ambitions of conquering western Persia and pushing into Iraq, were known to be dangerous enemies of the caliphate (see below). It

was more obviously in the natural interests of the caliphate that al Nasir should

incite against the Shahs their opponents on the eastern fringes of Khurasan, the

Ghurids. This line of chiefs from Ghur, in the mountainous interior of what is

now Afghanistan, had in the mid sixth/twelfth century dealt a near death blow to the surviving Ghaznavids, and under their forceful sultan Ghiyath 125 See Ef 'Futuwwa' (CI. Cahen).

126 See Cahen, Pre Ottoman Turkey, pp. 195 200, 335 41; Ef 'Akhi' (Fr. Taeschner).

127 Hodgson, The order of Assassins, pp. 217 25; Daftary, The Ismd'ilis:Their history and

doctrines, pp. 405 7. However, Hodgson (p. 223 n. 31) suggested that the figures

depicted are simply astrological symbols.

128 Ibn al Athir, vol. XI, p. 560.

129 Ibn al Athir, vol. XII, p. 107.

72

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

al Din Muhammad (r. 558 99/1163 i202f.) were now vigorously expand ing westwards into Khurasan, inevitably coming up against the Khwarazm Shahs. 130

Another factor contributing to the demise of the Great Saljuqs was the shrinkage of their territories, hence financial resources, and their sphere of

action through the growth of powerful atabeg and other Turkish commanders.

In Azerbaijan, the Eldigiizids of Tabriz and the Ahmadilis of Maragha were all

powerful, and through Shams al Dm Eldigiiz's marriage to the widow of the

ephemeral sultan Toghnl (II) b. Muhammad, and other marriages linking his

line with the Saljuq family, this atabeg was able to set up Toghnl's son Arslan as

sultan and, inevitably, protege of the Eldigiizids in Hamadan in 556/1161. Eldigiiz's sons and successors maintained a close tutelage over the last two

Saljuqs, and Toghriil (III) b. Arslan was only able to break out of this during the

last years of his life. Fars was under the Turkmen Salghurids, from the Oghuz

tribe of the Salghur/Salur, while Khuzistan was controlled by another Turkmen, Shumla, from the Oghuz tribe of the Avshar, and his progeny. In

Khurasan, the Oghuz tribesmen remained a significant if disorganised force.

They had brought about the eventual downfall of Sanjar, and in 582/1186 the

Oghuz leader Malik Dinar put an end to the Saljuq line in Kirman. Malik Dinar

tried to legitimise his rule by marrying a Saljuq princess, and is actually praised

in the sources for his just ten years' rule and his care for the prosperity of Kirman

and its subjects, an attitude uncharacteristic of Turkmens of his background; but

after his death, his incompetent son and successor was unable to hold the Oghuz

horde together, and when he in turn died the Oghuz had to submit to the Khwarazm Shah Tekish and were incorporated into his army. 131

Thus the last two sultans, Arslan and Toghnl (III), held no more thanjibal, with their centres of power at Hamadan and Isfahan and occasionally at Ravv.

Arslan ruled only nominally under the control of Eldigiiz, who adopted the

title of Atabak alA l zam 'Supreme atabeg,' and it was his son Nusrat al Dm

Jahan Pahlawan Muhammad who in 571/1176 set up Toghnl as sultan when

Arslan died. The sources commend this last of the Saljuqs for his intellectual as

well as his martial qualities, but the odds were heavily stacked against him.

Toghnl soon became restive under Jahan Pahlawan's successor as atabeg, Qrzil Arslan, who treated him harshly, and he gathered together troops, assumed the initiative and defeated the forces of the caliph (now Qizil

130 Bosworth, 'The political and dynastic history', pp. 163 5.

131 Bosworth, 'The political and dynastic history', pp. 169 75; Mercil, Kirman SelfuMan, pp. 210 28.

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

Arslan's ally) at Day marg near Hamadan in 584/1188. He nevertheless had to

surrender to Qiziil Arslan in 586/1190, who imprisoned him and now pro claimed himself sultan, but he was mysteriously murdered so that Toghnl could obtain his freedom. He soon secured Jibal for himself, but at this point

came up against the Khwarazm Shah Tekish. Although Toghnl captured Rayy

from its unpopular Khwarazmian garrison, he was overwhelmed by the Khwarazmians' superior numbers in a battle with Tekish outside Rayy. He

was killed at the age of only twenty five, the last Saljuq to rule (590/1194), and

his head sent by the Shah to Baghdad. Western Persia was now divided up

between a commander of the Eldigizids and the caliph. 132

The latter, however, now faced a much more redoubtable and powerful foe

than the last Saljuq, especially since after 589/1193 Tekish was free of his

brother and rival for power in Khurasan, the deceased Sultan Shah.

considered himself as heir to the Saljuq empire, which involved control of western Persia, and, after his death, increased pressure was exerted on al Nasir

by Tekish's son and successor, the last Shah to reign in Khwarazm, 'Ala' al Dm

Muhammad (r. 596 617/1200 20). 'Ala 1 al Din demanded recognition of his

claim to a vast empire which now stretched from Turkistan to the Indian Ocean shores, the justification for his assumed title of 'the Second Alexander',

and required al Nasir to place his name in the Baghdad khutba.

Al Nasir could only seek to neutralise the Shahs by giving moral support to

the Ghurids in their struggle with the Shahs for possession of Khurasan. 'Ala'

al Din Muhammad knew from documents captured at Ghazna that the caliph

had earlier incited the Ghurids against him and was now using Isma'ili fidd'is

to remove his opponents. Questioning the whole legitimacy of the 'Abbasids

as excluders of the 'Alids from their rights, he secured afatwa from compliant

c ulama' declaring al Nasir deposed, and nominated in his place a Husaynid

'Alid as anti caliph, whose name he now placed in the khutba of the Khwarazmian lands and on his coins. He began to march on Baghdad in the

winter of 614/ I2i7f but was halted in the mountains of Kurdistan by unusually

heavy snowfalls; and hearing of the Mongols' appearance on the borders of

Transoxania, he turned back to Khurasan. 133

132 Bundari, pp. 301 3; Husaynl, pp. 176 93; RawandT, pp. 339 74; Pseudo Zahir al Din

Nishapuri, trans. Luther, pp. 151 3; Ibn al Athir, vol. X, pp. 24 5, 75 6; Juwayni, trans.

Boyle, vol. I, pp. 299 303; Barthold, Turkestan, pp. 366 7; Kafesoglu, Harezmsahlar devleti tarihi, 116 19, pp. 123 6.

133 Ibn al Athir, vol. XII, pp. 106 8; Juwayni, trans. Boyle, vol. II, pp.364 7,390 2; Barthold,

Turkestan, pp. 373 5; Kafesoglu, Harezmsahlar devleti tarihi, pp. 202 5, 214 20.

74

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

It is at this point that a totally new phase of Islamic history begins, with

appearance of the Mongols. Ruling houses familiar in the history of Transoxania had already disappeared. The last ruler of the western branch

of the Qarakhanids, c Uthmanb. Ibrahim (r. 600 9/1204 12), had borne gran

diose titles like Sultan al Saldtin 'Supreme Sultan' but was ill equipped to withstand the Khwarazmian onslaught. He had rebelled in Samarqand against

'Ala' al Dm Muhammad, upon which the Khwarazm Shah had come to 'Uthman's capital, sacked it and executed him. 134 The Naiman Mongol leader

Kuchliig had in autumn 1211 captured the Qara Khitay Giirkhan Chih lu ku/Zhilugu near Kashghar and in effect taken over the Qara Khitay titulature

and state apparatus for himself 135 Such radical changes in the governmental

pattern of eastern and western Turkistan facilitated the expansion to the west

shortly afterwards of Chinggis Khan's hordes. According to a Western source,

al Nasir had been negotiating with the Mongols in order to delay the advance

of the Khwarazmians, an allegation that Angelika Hartmann thought might

well contain some truth. 136 At all events, the policies of provocation pursued

by 'Ala 3 al Dm Muhammad brought down on his head the Mongols in 1217,

with fateful consequences not merely for his own dynasty but for the Islamic

lands in Asia as a whole.

#### IX

As has been seen (above, p. 21), the two centuries or so that we have covered

brought new ethnic groupings and demographic trends into the eastern Islamic lands, with consequences in the linguistic field and in that of land tenure and utilisation. The question remains, were there significant reactions

in the fields of culture and of literary and artistic expression, within the milieux

of the Qarakhanids, the Saljuqs and Khwarazm Shahs, as well as political, economic and demographic ones? It was noted (above, p. 29) that the earliest

monuments of Turkish Islamic literature emanate from the Qarakhanid milieux of western and, especially, eastern Turkistan, either composed at the courts of the khans, as with the Qutadghu bilig and the moral and didactic

treatise, the l Atabat al haqaHq, of Ahmad YiiknekT, or written by an expatriate

like Kashghari. Poetry, both of a folk nature and of a higher, court level,

134 Juwaym, trans. Boyle, vol. II, pp. 392 5; Barthold, Turkestan, pp. 365 6; Pritsak, 'Die Karachaniden', pp. 56 7.

135 Ibn al Athir, vol. XII, pp. 269 71; Biran, Tde empire of the Qara Khitai, pp. 79 80.

136 Ef 'al Nasir li Din Allah', at vol. VII, pp. 997 8.

75

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

continued to be composed, according to Kashghari. 137 There may also have

been at this time the beginnings of a Sufi mystical literature in Turkistan, but

the topic is shrouded in mystery. The shaykh Ahmad Yasawi (i.e. from Yasi in

the middle Syr Darya valley, the modern town of Turkistan in the southern

most part of the Republic of Kazakhstan; it is there that the shaykh's mauso

leum, later known as 'the Ka c ba of Turkistan' and a great goal of Central Asian

pilgrims, is situated) is often adduced as a significant figure here, but the death

date given for him of 562/1167 is probably too early and the collection of Turkish mystical poetry attributed to him, the Drwdn i hikmet, was almost

certainly put together by other hands after his death. 138 Whether the

Qarakhanid rulers ever became literate in the prestige Islamic languages of

Persian and Arabic, let alone in Turkish itself, is unknown. Their close identification with their Turkish military backing, their loose system of governance hence lack of need for a complex bureaucracy of traditional Islamic type, and their lifestyle that was at least semi nomadic, would seem

to make this problematical; Turkish must have been the language which continued to loom largest in their mode of life and for their military and administrative needs. Yet perhaps this is too facile a judgement; the career at

the Bukhara court of a poet like Am c aq (d. c. 543/1148^ shows that a poet in

Persian could secure honour and doubtless financial reward from the Qarakhanids. 139

We have more information about the situation in the Persian lands. Here the ethnically Turkish Saljuq sultans and their provincial governors and atabegs became highly dependent on the bureaucracies that they inherited

from their predecessors for running the complex administrative and fiscal

structures which had evolved over the centuries. The personnel involved were almost wholly Persian, imbued with Arabo Persian procedures and traditions of statecraft; they possessed the whole gamut of the Islamic sciences

and, especially, polite learning, adab, and all these they placed at the disposal of

their Turkish masters. Although we know that the Saljuqs' predecessors in

Khurasan, the Ghaznavids, became highly literate within one or two

### 137 Barthold, ZwdlfVorlesungen, p. 117.

138 See EI 2 . 'Yasawiyya' (Th. Zarcone). Accepted ideas about the Yasawiyya are due for a

radical reappraisal in the light of recendy discovered texts on religious life in Islamic

Central Asia which may bring the order's origins into the seventh/thirteenth century

rather than in the previous one. See the Foreword by Devin DeWeese to Gary Leiser

and Robert Dankoff (trans, and eds.), Early mystics in Turkish literature: Mehmed Fuad

Kiypriilu (London and New York, 2006), pp. viii xxvii.

139 See Alessio Bombaci, Storia della letterature turca dall'antico impero di Mongolia all'odierna

Turchia (Milan, 1956), part III, ch. VII %'eta qarakhanide (XI XII sec.)', pp. 81 106.

76

Cambridge Histories Online © Cambridge University Press, 201 1

The steppe peoples in the Islamic world

generations from their Central Asian ghulatn origins, 140 we have little firm

information about the cultural and linguistic attainments of the Saljuq sultans

themselves. BartholcTs categorical assertion that the sultans 'were strangers to

all culture' and that Sanjar was certainly illiterate requires more substantial

proof than he adduced. 141 It does not seem likely that the contemporary 'Imad

al Dm al Isfahan! would praise the dead Muhammad (II) b. Mahmud as 'the

most learned of his house' (awfarahum Hbn an ) (see above, p. 64) if the sultan

had been illiterate. Unlike the case with the Qarakhanids, no substantial body

of Turkish lore and literature emanated from the Saljuq courts, so far as we

know. The literature of their courts which is known to us is wholly in Persian

and Arabic, with Persian poets of high calibre, such as Mu'izzi, the eulogist of

Malik Shah and Sanjar (d. between 519 and 521/1125 and 112.7), and, a gener

ation or so later, such poets at Sanjar's court as Adib Sabir (d. between 538 and

542/1143 and 1148) and Anwari (585/1189 or 587/1191). Of provincial courts, we

find Khaqam (d. 595/1199) at that of the Shirvan Shahs in Transcaucasia, while

the Khwarazm Shahs Atsiz and II Arslan had the services of an outstanding

poet and epistolary stylist in Rashid al Dm Watwat (d. 578/n82f. or somewhat

earlier). 142 It seems improbable that there was not some degree of Persianisation among the Turks at the court circles here, to which there had

been some degree of predisposition, on the evidence of Mahmud Kashghari;

he states that 'when the Oghuz mixed with the Persians they forgot many Turkic words and used Persian instead'.' 143 Although the course of Islamic

history shows that rulers of Turkish origin clung much longer to their native

tongue than is often (mainly from lack of explicit information) thought, 144 and

Turkish must have remained a valuable tool for diplomacy and communica

tion with Turkish tribesmen and chiefs remaining within the steppes, the attraction of Persian ways and customs at rulers' courts and the use of Persian

governmental lore and practice in their administrations inevitably led to the

formation of a composite culture combining Turkish vitality with Persian sophistication.

140 Bosworth, The Ghaznavids, pp. 129 30.

141 Barthold, Turkestan, p. 308.

142 See J. Rypka et al., History of Iranian literature (Dordrecht, 1968), pp. 194 5, 197 9, 200, 202 8.

143 Diwan lughat al turk, trans. R. Dankoff and J. Kelly, Compendium of the Turkic dialects (Cambridge, MA, 1982 5), vol. I, p. 115.

144 See Ef Suppl. 'Turks. III. Literature. 6 (a) Turkish literature in Muslim India' (B. Peri) on the use of Turkish in Mughal India up to the nineteenth century.

77

# The early expansion of Islam in India

#### ANDRE WINK

In the wake of the Islamic conquests, trading activity between the Middle East

and India appears to have expanded dramatically. Between the Hellenistic

period and the first/ seventh century, the Arabs had lost their predominance in

this trade to the Ethiopians Byzantium's trading partners in the Indian Ocean and, to an even greater degree, to the latter's political and commercial

rivals, the Sasanid Persians. The early Islamic conquests brought Byzantine/

Sasanid rivalry to an abrupt end while bringing the Middle East into a single

monetary exchange system and linking the Mediterranean to the Indian Ocean

under the aegis of a single imperial polity. Gravitating towards Mesopotamia

and the Persian Gulf, the trade with India became the major external source of

wealth for Islam, at the same time that the overland route to China acquired

much greater significance with the accession of the Tang dynasty in 618 CE.

The Islamic trade with India was a trade in pepper (the 'black gold of India')

and spices in the broadest sense, but included an almost infinite array of other

items, from jewels to metallurgical products and ivory, to teakwood and textiles, which were exchanged against precious metals, horses and many

manufactured products such as paper, glass and the like.

#### The India trade

There is significant evidence to show that the conquests in Makran and Sind

were, at least partly, motivated by the ambition to safeguard the India trade

against the (semi )nomadic tribes of these regions, such as the Jats and Mids, whose predatory activities affected much of the western Indian Ocean, from the mouth of the Tigris up to the coasts of Sri Lanka. The early conquests in the eastern direction enhanced the power of the Azd 'Uman at the expense of the tribes of the Sindian wastes. These Azdi of Oman were a thoroughly Persianised population of Arab seafaring merchants

(Zoroastrians before the rise of Islam) which had been settled on the coasts of

78

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

Fars and Kirman Makran, and as far as Sind from the days of the first Sasanid

emperor Ardashir (r. 226 41 CE) onwards. 1 The Azdi rise to power on the

easternmost frontiers of the caliphate did not go unopposed (the notorious

governor al Hajjaj turned against them in the late first/ seventh century) but

demonstrates a strong link between the expansion of Islamic commercial interests and the conquests on the Indian frontier. This link persisted until

about 447/1055, when the Saljuq Turks occupied Baghdad, the India trade was

rerouted to the Red Sea and the Baluchi overran Makran. Until that time, in

Oman the ports of Suhar, Julfar, Daba and Masqat rose to eminence under the

Azdi trading network. Many other Persian Gulf cities became important after

the conquest of Sind and the subsequent foundation of Baghdad, including

Basra (newly founded by the Arabs), Kufa, Wasit and al Ubulla the latter city

attracting such a large part of the India trade that it came to be regarded

'part of al Hind'. The efflorescence of these cities is another strong indication

of the importance, from c Abbasid times onwards, of the Persian Gulf con nection with India, and beyond, with Malaya and China, as well as with Africa.

The Buyid dynasty (320 454/932 1062) boosted this trade still further, along

the entire littoral, by effectively keeping the Baluchi tribes of Kirman at bay.

Throughout the early centuries, the Hijaz and the Red Sea ports were completely eclipsed. Jiddah and Aden were not restored until the rise of the

Fatimids (359 567/969 1171) and the Ayyubids (567 650/1171 1250) in Egypt.

By then the intercontinental trade route through Syria and Asia Minor, via

Baghdad, to the Persian Gulf was subverted by the arrival of the Saljuq Turks,

the subsequent devastation of Fars by the Shabankara and other unhinged

tribes elsewhere in the Gulf region (including the islands), the concomitant

decline of the c Abbasids and by the beginning of the Crusades in 485/1096. To

some degree the decline of Baghdad, Shiraz and of Basra and other cities in the

Persian Gulf, was offset by the Saljuqs' policy of rerouting the India trade from

Makran to Hormuz and northwards to Jiruft and Bardasir, in Kirman, and

far as Yazd and the caravan route to Azerbaijan and Anatolia. 2, But the decline

of the Persian Gulf and the rise to pre eminence of the Red Sea and Egypt in

the India trade were sealed by the fall of Constantinople in 600/1204, during

1 A. Wink, Al Hind: The making of the Indo Islamic world, vol. I: Early medieval India and the

expansion of Islam, yth uth centuries (Leiden, 1990), pp. 45 53; G. F. Hourani, Arab seafaring

in the Indian Ocean in ancient and early medieval times (Princeton, 1951), pp. 45 6;

D. Hawley, Oman (London, 1977), pp. 17, 19.

2 J. Aubin, 'La mine de SIraf et les routes du Golfe Persique aux XIe et XIIe siecles', Cahiers

de Civilisation Medievale, X XII (1959), pp. 295 301; A. Wink, AlHind: The making of the

Indo Islamic world, vol. II: The slave kings and the Islamic conquest of India, uth rfih centuries (Leiden, 1997), pp. 17 23.

79

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

the Fourth Crusade, and the destruction of the caliphate by the Mongols in

656/1258. From the Red Sea and Egypt, links with Malabar, especially with

Calicut, and with the Coromandel were increasingly given emphasis over those with Gujarat and western India, although the latter areas were soon to

regain an important role in trade, above all that in textiles.

Outside the conquered territories of Makran and Sind, Zabul and Kabul, and parts of the Punjab, up to the eleventh century no permanent Muslim communities appear to have been founded in India beyond the coastal towns. 3

On the coasts, however, Muslim communities took root in innumerable locations, from Gujarat and the Konkan to Malabar, the Coromandel, Sri Lanka, Bengal and beyond, to the Malay Indonesian archipelago and China;

and everywhere their raison d'etre was trade. Sustaining the emerging net

works of Indian Ocean trade, we also find significant numbers of Hindus and

Jains migrating to the Persian Gulf, Oman, Socotra, to the Red Sea and its

islands, as well as to Indonesia, but in all likelihood these did not found permanent communities. If we can go by the later medieval and early modern

evidence, Hindus and Jains, beyond India, remained sojourners. 4 It was the

Muslim diasporas in the Indian Ocean that became numerically the most important and by the thirteenth century overshadowed all others, including

the Jews and Parsis, not least because they routinely gave rise to mestizo communities, originally often through mufa or 'temporary marriage' with

women of low fishing and mariner castes, while living under Hindu domi nation. Up to about the tenth century the largest settlements of Muslim trading groups of this kind, mainly originating from the Persian Gulf region

and Oman and to a lesser extent from the Hadramawt, were to be found on

the coasts of Gujarat and the Konkan, in the domain of the Rashtrakuta or

Ballahara kings. Here the Arab element gradually submerged under the Turkish conquests from as early as the eleventh century but mostly from the late thirteenth century or, in the Konkan, under the expanding Bahmani

dominion from the fourteenth century onwards. According to al Mas'udi, the

largest settlement was that of about 10,000 Muslims in Saymur (south of present day Mumbai). 5 In the tenth century, many of these were baydsira

3 M.J. De Goeje (ed.), Al a'ldg al nafisa oflbn Rusta (Leiden, 1892), p. 135.

4 Cf. C. D. Ley (ed.), Portuguese voyages, 1498 1663 (London, 1947), p. 22; S. C. Levi, The

Indian diaspora in Central Asia and its trade, yyo 1900 (Leiden, 2002), pp. 261 2; A. Wink,

Al Hind: The making of the Indo Islamic world, vol. Ill: Indo Islamic society, 14th lyth centuries (Leiden, 2004), p. 200.

5 al Mas'udi, Muruj al dhahab, 2 vols. (Cairo, 1948), vol. I, p. 170.

80

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

(sing, baysarf), that is 'Muslims born in al Hind of Muslim parents'. 6 Particularly the Caulukya king Siddharaja (1094 1143) fostered the growth of

coastal Muslim communities in Gujarat which came to include more and

more local converts and ran the gamut from wealthy traders and shipping

magnates to sailors, oilmen and other manual labourers. 7 In the popular imagination, Siddharaja later became the founder of all important Muslim

communities in Gujarat and he was reported to have been converted to their

sects by the Bohras and the Khojas Isma'ili communities which became larger in Gujarat than anywhere else in India and even by the Sunnis who entered Gujarat from the Turkish dominated areas of the north.

The Arab Muslim trading communities of south India the Navayat of the Canara coast, the Mappilas of Malabar and the Lappai or 'Labbai' (a corruption

of c ArabT) of the Coromandel retained the Shaft 1! legal orientation and assiduously fostered the Arab identity that they had brought with them from Baghdad and the Persian Gulf, as well as from Arabia, Yemen and Hadramawt, even though these same communities adopted important elements (such as the matriarchal customs of Malabar) from their Hindu host

environment. They remained closely connected, through trade and continued

migration, with the Muslims of the Middle East, and developed more impor

tant ties (also through intermarriage) with other Shafi'i Muslim societies which sprang up in the tropical ecosystems of south India, Sri Lanka and the

Indian Ocean island archipelagoes than with the 'Tartars' of continental India,

whom they affected to regard as late converts and who were Hanafi. With origins going back as far as the eighth century in some places, and some Mappilas in effect claiming to be refugees from the reign of terror of al Hajjaj

in Iraq at the end of the seventh century, the coastal Muslims of south India

were clearly dominant in maritime commerce (especially long distance) by

the thirteenth century and had grown numerous in many ports. But the position of these south Indian Muslims among the politically empowered Hindu majority in south India always remained extremely ambivalent, espe

dally in caste conscious Malabar. Here, the Mappila and even the 'Pardeshi',

or foreign Muslim element, while enjoying a privileged position among the

Hindu military upper castes of Nayars and Nambutiri Brahmans, nonetheless

6 On this term, see J. C. Wilkinson, 'Bayasirah and Bayadir', Arabian Studies, 1 (1974), pp. 75 85.

7 S. C. Misra, Muslim communities in Gujarat (Baroda, 1964), pp. 7 13.

8 Cf. S. Bayly, 'Islam in southern India: "Purist" or "syncretic"?', in C. A. Bayly and D. H. A.

Kolff(eds.), Two colonial empires: Comparative essays on the history of India and Indonesia in

tfte nineteenth century (Leiden, 1986); Wink, Al Hind, I, pp. 69 86.

81

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

remained separated from these by a ritual barrier of pollution. 9 Other groups

of Muslims of unknown provenance found employment as mercenaries in the indigenous armies of south India, serving the kings of Malabar and Sri Lanka alike. 10

The conquest of Zamindawar, Zabulistan and Kabul

By contrast, the sweeping victories in the north of the Indian subcontinent, in

the frontier regions of Zamindawar, Zabulistan or Zabul, and Kabul (all of which are now in southern and eastern Afghanistan), as well as in Makran,

Baluchistan and Sind, allowed the Muslims to assume political power over a

Hindu Buddhist population which vastly outnumbered them but could, as revenue and tribute paying subjects, be fitted into the easternmost adminis

trative divisions of the caliphate. Zamindawar was the lowland region around

Kandahar ('where people do not eat cows') and here the Zunbil kings and

their kinsmen the Kabulshahs who were probably descendants of a southern

branch of the Chionite Hephthalites or 'White Huns' had their winter residence, in the religious centre of their realm where the cult of the Shaivite god Zun was performed on a hilltop. Zabul was the mountainous zone of the upper Helmand and Kandahar rivers where the Zunbils had their

summer residence. Partly due to the inaccessibility of their realm, the resist

ance of the Zunbils was much more effective than that of other Indian kings

who took up arms against the invading Muslims. In effect, the Zunbils and the

related Kabulshahs were able to slow down the final conquest until as late as

256/870 holding out for more than a century and a half after the remnants of

Chionite Hephthalite power were erased in the upper Amu Darya valley, in

Herat and the surrounding region of Badhghis, as well as in the region of what.

is now northern Afghanistan, and for as long after the Brahman kings of Sind

had been overthrown at their first encounter with the Muslim armies.

The Zunbils' tenacious resistance thwarted an attempted Muslim advance through Zabul and Kabul to the Indus Valley as early as 22/643." Arab forces

advanced to the shrine of Zun in 32/652^ mutilating the icon (the shrine itself

survived until as late as the third/ninth century), and after that date mounted

frequent plunder and slave expeditions as far as Ghazna, Kabul and Bamiyan,

first from a base in Zarang, in Sistan, and subsequently from Bust, a town to

9 Wink, Al Hind, II, pp. 275 80.

10 Ibid., pp. 268 9. 11 Wink, Al Hind, I, pp. 119 28.

82

The early expansion of Islam in India

the east of Zarang which drew great numbers of volunteer ghdzis but never

became more than a turbulent frontier outpost. 12. The Zunbil more than once

struck back at the Arab positions in Sistan up to the end of the eighth century

this remained the 'ill omened frontier' of consolidated conquests. According

to al Mas'udi, 'the Zunbil was that king of al Hind who marched to Sistan with

the design to invade the kingdom of the Syrians'. 13 An army sent under al

Hajjaj, in 77/697?., to Zammdawar and almost as far as Kabul, was virtually

destroyed. Arab infighting in Sistan, exacerbated by Zunbil interventions, brought the Islamic conquest to a halt, and for about one and a half centuries

no lasting military gains were made in the difficult terrain of the Zunbil's dominions, although the latter, lying athwart the vital caravan route from Hind to Khurasan, were frequented by Muslim merchants, as well as by renegades, especially Kharijites persecuted by al Hajjaj, and although some

Afghans living in the area were possibly converted at this early stage. In the

first half of the eighth century, the Zunbil instead chose to pay homage to the

Tang emperor of China.

The military breakthrough in Zabul and Kabul (although not yet in moun tainous Ghur) occurred in the late ninth century CE, under the Saffarids,

dynasty of local Sagzi provenance which had an intimate knowledge of the

geographical and climatological conditions of these regions. By then the Buddhist 'Turk Shahi' dynasty of Kabul had made room for a 'Hindu Shahi'

dynasty, founded by a Brahman vizier of the old dynasty in a new capital at

Wayhind. 14 Under the Samanids, a Turkish slave general by the name of Alptigin set up his headquarters at Ghazna in 322/933, and then founded the

dynasty of the Ghaznavids, which drove the Hindu Shahi rulers further into

the Punjab, and ultimately, in the early fifth/ eleventh century, into Kashmir,

thereby giving a new impetus to Islamic expansion in Hind.

The conquest of Makran

From a military point of view, the first report received by the caliph 'Uthman

relating to the Indian borderlands of Makran revealed conditions which were

hardly more encouraging than those of the Zunbil's dominions to the north:

'the water is scanty, the dates are bad and the robbers are bold; a small army

12 C. E. Bosworth, Sistan under the Arabs: From the Islamic conquest to ike rise of the Saffarids (20 250/651 864) (Rome, 1968).

13 al Mas'udi, Muruj al Dhahab, I, p. 211.

14 Y. Mishra, The Hindu Sahis of Afghanistan and the Punjab, AD 86; 1026 (Patna, 1972).

83

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

would be lost there, and a large army would starve'. 15 This report essentially

refers to the ancient Gedrosia, the barren territory where Alexander nearly lost

his army in 325 BCE, on his march back from the Indus to Susa. Here the Greeks had been startled, after having become acquainted with the far more

civilised barbarian kingdoms of the north west frontier, by the primitive life of

the Ichthyophagoi, or what the Persians called the Maki khordn the 'fish eaters'

of which the name Makran is said to be a corruption.

It was an ancient convention to regard the satrapy of the Gedrosi (Makran),

with those of the Arachotae (Kandahar), Arii (Herat) and Parapanisidae (Kabul),

as part of India. Al Biruni, in the fifth/ eleventh century, similarly maintained

that 'the coast of al Hind begins with Tiz, the capital of Makran, and from there extends in a south eastern direction towards the region of Debal'. 16

From a physiographic point of view, Makran is an extension of the Great Desert or Dasht i Lut of Persia, and the part that was Indianised and ruled by

Indian kings lay to the east of a wholly arid tract, extending up to Tiz (the chief

commercial centre of Makran, on the Persian Gulf), and was called Kij Makran,

now constituting the south western division of the province of Kalat, Baluchistan, with a coastline of 320 kilometres. Kij Makran consisted largely

of mountain ranges with cultivable tracts with towns and villages running from east to west, with Kij being the largest inland town, on the great highway

connecting India with Persia which in the early centuries of Islam was even

more vital to the economic life of the caliphate than the route running through

the Kabul river valley.

The Arabs first invaded Makran, routing a large assembly of Indian troops

and elephants, in 23/644, towards the end of the caliphate of 'Umar, almost

three quarters of a century before Muhammad al Qasim conquered Sind and

established the first Muslim settlement on the Indus. 17 Parties of horsemen

began exploring the Makran coastal regions during the caliphate of 'Uthman (r.

23 35/644 56). Soon after, under 'All (r. 35 40/656 61) and Mu'awiya (r. 41 60/

661 80), military raids into the Makran were resumed which took the Arabs as

far inland as Qiqanan, and even beyond, as far as al Ahwar (Lahore), but these

resulted mostly in defeat. Later in the caliphate of Mu'awiya, Makran was

'conquered by force', and permanent garrisons were established which subdued

the country as far as Qandabil, obtaining more regular flows of tribute and

slaves, although not without reversals. Some of the main towns of Makran had

15 al Baladhuri, Futilh al bulddn (Cairo, 1932), pp. 420 1.

16 Pliny, Natural history, II (London, 1947), Book VI, XX.53 XXI.56, XXIII.78 9; al Biruni,

Kitdbfi Tahqiqimd li I Hind (Hyderabad, India, 1958), p. 167.

17 Wink, Al Hind, I, pp. 129 44.

84

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

to be subdued again by Muhammad al Qasim when the latter launched the

'holy war against Sind and Hind' which was authorised by the caliph Walid and

which led to the conquest of Sind by Arab forces around 96/712. 1

In Makran, in the succeeding centuries, an unknown number of Arab Muslims, living in urban enclaves, appear to have asserted authority against

largely unconverted and 'depraved' native tribes Jat dromedary men, an emerging population of Baluchis, pastoral and seafaring Mids preying on coastal traffic from Sind, and numerous other mobile groups which the Arabs had to contend with, often in violent encounters. Like Zabul, Makran

became a place of refuge for Kharijites and other extremists, following in the

wake of Persian Mazdeans fleeing from Kirman. But there was also the increasing number of Azdi Arabs, originating from Oman, which established

an important mercantile presence in Makran that lasted until the Baluchis,

under pressure from the Saljuqs, overran the province in about 447/1055 from

the west. An important conduit of long distance commerce, Makran remained

more or less under the effective control of the caliphate between 96/712 and

256/870. The authority of the Tahirid, Saffarid and Samanid dynasties of eastern Persia did not extend as far as Makran, and we find that, by 256/870,

Makran was effectively controlled by a number of ' mutaghalliba chiefs who had

'usurped' power without being appointed by Baghdad but who still used the

caliph's name in the Friday prayers in Kij, and in a place called Mashki, on the

Kirman border, as well as elsewhere, without paying tribute. Even then however the commercial traffic through Makran and along its coasts appears

to have continued undiminished.

### The conquest of Sind

Sind, the alluvial plain on both sides of the middle and lower course of the

river Indus or 'Mihran', extending from Attock and the Salt Range to the coast,

and with varying portions of the dry and hilly uplands, such as Qiqanan, adjoining Baluchistan, and of the Thar desert included, was conquered under

al Hajjaj, 'governor of 'Iraq and Hind and Sind' from 74/694 to 95/714. This

occurred at a time of great expansionist ambition, amounting to an all out

reorientation of the caliphate in the eastern direction, towards Iraq and the

Persian Gulf, towards Ma Wara ] al Nahr, and, above all, towards Hind. 19 Like

18 U. M. Daudpota (ed.), Chachndma (Hyderabad, Deccan, 1939), p. 91; al Baladhuri, Futuh al bulddn, p. 424.

19 Wink, Al Hind, I, pp. 144 218.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Makran, Sind had a mixed Hindu Buddhist population, with some Zoroastrian elements. Most of Sind also had a pastoral nomadic economy,

and much of it was still wilderness, a land of deserts, marshes and reeds. It

probably held no more than several hundred thousand people along the lower

Indus, next to perhaps 50,000 in Baluchistan. In some places, especially in the

areas around al Mansura and Multan, it was considerably more densely settled

by agriculturists, and it was generally more urbanised than Makran, commen

surate with its greater commercial importance. For the Arabs, Sind was overwhelmingly important as a thoroughfare of the India trade, both overland

and maritime.

The first Arab naval expedition to Sind was undertaken in 'Umar's reign, either in 15/636 or 23/644, but was unauthorised by the caliph, who was hesitant about naval expeditions at that time. 20 The Arab naval force came via

Bahrayn and Oman to Debal and then crossed the sea to Tanah, a port on the

west coast of India, near present day Mumbai. 21 The same caliph, having

received reports that Sind was inaccessible, 'even worse' than Makran, also

prohibited an overland expedition from Makran to Sind. c Uthman, too, prohibited his troops from invading Sind. Not until Makran was occupied and the Mids of the coast of Sind were brought to heel under Mu'awiya was

such hesitation set aside. The expeditionary force which was then, in 94/710,

sent from Shiraz in southern Persia under al Hajjaj's nephew and son in law,

the seventeen year old Muhammad al Qasim, consisted of 6,000 Syrian cav

airy and detachments from Iraq with the mawali. These were military men

who would not return to their places of origin but would settle down, with

native women, in colonies which were known as junud and amsar, usually in or

around the main towns of Sind. The conquest army that invaded Sind in 95/711

was not followed by a mass migration of Arab tribes, nomads or otherwise, as

had been the case in Iraq between 17/638 and 25/656. Reinforcements, how

ever, of camel riders were made along the way, and more troops were transferred by sea, while numberless volunteers soon began to arrive from

Syria, and local forces of Jats and Mids were swept up in the conquest army as well.

The port city of Debal was taken first, with great slaughter, and here the first mosque of the subcontinent was built. Other cities to the north of Debal

capitulated to the conquest army, which then crossed the Indus for the

20 H. M. Ishaq, 'A peep into the first Arab expeditions to India under the companions of

the Prophet', Islamic Culture, 19 (1945), pp. 109 14; B. M. B. K. As Sindi, 'The probable

date of the first Arab expeditions to India', Islamic Culture, 20 (1946), pp. 250 66.

21 al Baladhuri, Futuh al bulddn, p. 420; Daudpota, Chachnama, p. 73.

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

decisive engagement with Dahir, the Brahman king of Sind, who was killed in

battle, his head, with those of 'the chiefs of Sind' and a fifth of the booty and

slaves, sent to al Hajjaj. The governor rightly surmised that this victory practically put all of Sind in his hands and, on the occasion, delivered a sermon

in the great mosque of Kufa congratulating his people on 'the conquest of

Hind and the acquisition of immense wealth'. 22. The capital cities of Brahmanabad, Alor and Multan, with all fortresses in between, were now taken in quick succession, with, according to the sources, casualties on the

Muslim side remaining low, while the enslavement of great numbers of women and children accompanied the killing of the 'fighting men' of Sind. Few chose to convert. But more mosques were built, and Friday prayers were

held and coins were issued in the name of the caliph. The victorious Muhammad al Qasim was executed in 96/715 as part of a purge undertaken

against the relatives and proteges of al Hajjaj, upon the latter's death, after

having attempted to thwart the succession of the new caliph Sulayman.

Subsequent Umayyad governors made repeated attempts to convert Dahir's son Hullishah and other surviving members of the Sindian ruling elite, but with little lasting result. Apostasy and rebellion went hand in hand.

The Arabs remained at war in Sind, even while conducting immensely lucrative raids, both by land and by sea, as far as Cutch, Gujarat and Rajasthan. Such raids, too, went not without reverses. An inscription in Sanskrit of the Gurjara Pratihara king Bhoja I commemorates how Nagabhata, the founder of the dynasty, defeated a powerful 'Mleccha king'

who had invaded his dominion. 23 In the last decades of the Umayyad caliphate,

in fact, the position of the Arabs not only appears to have deteriorated in many

parts of Sind, but they withdrew altogether from regions to the east and south.

This was also the time, however, when the two major stronghold towns were built of al Mahfuza and al Mansura, on opposite sides of a now unknown

lake 'which borders on al Hind', and here the Arabs could secure their posi

tion. 24 Al Mansura, which appears to have been built adjacent to 'old Brahmanabad', the former capital of the Brahman rajas, became the seat of

the later governors. There are now three main masses of ruins in this area.

approximately 75 kilometres to the north east of modern Hyderabad. To none

of these the name of al Mansura is attached, the city having been destroyed, like

its predecessor Brahmanabad and so many other cities of Sind and Hind, by an

22 Wink, Al Hind, I, p. 205.

23 Indian Antiquary (Bombay, 1872 1923), 60 (1911), p. 240.

24 al Baladhuri, Futuk al buldan, pp. 430 1.

87

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

earthquake and shifts in the course of the river occurring at some time after the

fifth /eleventh century. But it was from the secure bases of these twin cities that

the early Abbasid governors, displaying varying degrees of loyalty to the caliphate, engaged in a new round of conquest activities, again both by sea

and by land, and extending Arab control beyond previous limits, even, fleet

ingly, to the coasts of Gujarat and Kathiawar. They also regained control of

Multan and the upper Punjab, subduing the Jats and Mids in a range of localities,

while at the same time building mosques of increasing size and number.

Sind, with Makran, went its own way, under hereditary governing dynas ties, by about the same time that the Tulunids in Egypt and the Saffarids in

Sistan gained practical autonomy, and the Zanj revolt occurred in Iraq. De facto renunciation of caliphal control over Sind occurred in 256/870. By

this time Sind, like Makran, was parcelled out among a number of muta ghalliba chieftains who were under the authority of hereditary governors but

sent them no revenue or tribute. Among the hereditary Arab governors of Sind the two most important ones in the fourth/tenth century were those of

Multan and al Mansura, both still mentioning the Abbasid caliph in their Friday prayers, although, as the century wore on, Multan appears to have

paid allegiance to the Shahi rulers rather than Baghdad. Multan became an

Isma'ili principality when it openly proclaimed the sovereignty of the fourth

ruler of the Fatimid dynasty of Egypt, al Mu'izz (r.  $341\ 65/953\ 76$ ), the anti

caliph who was also known as 'the western one'. Al Muqaddasi, visiting Sind

in 375/985, observed: 'In Multan the khutba is read in the name of the Fatimid (caliph) and all decisions are taken according to his commands. Envoys and presents go regularly from Multan to Egypt. Its ruler is powerful

and just.' 2,5 In Sind generally, the Fatimid da'wa of missionary Isma'ilism an

organised Shi'ite Muslim sect with roots in western India and Sind going back to the ninth century but not officially embraced by any ruling dynasty

until the Fatimids of Cairo espoused it was extraordinarily successful and appears to have been related to the developments in trade. 2 When the Fatimids

extended their control down the Arabian and African shores, the Red Sea route gained greatly in importance, eclipsing the Persian Gulf in the trade with India. By the mid fifth /eleventh century, even Baghdad was temporarily held in the Fatimids' name. In Sind, Makran and Baluchistan, Isma'ili propaganda and Fatimid trade (which was supported by military

25 M.J. De Goeje (ed.), Al Muqaddasi, Descriptio imperii moslemici (Leiden, 1906), p. 485.

26 B. Lewis, 'The Fatimids and the route to India', Revue de la Faculte des Sciences

Economiques de l'Universite d'Istanbul (Oct. 1949 July 1950), nos. 1 4, pp. 50 4; M.J. De

Goeje, Memoire sur les Carmathes du Bahrain et les Fatimides (Leiden, 1886).

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

intervention, as well as by the introduction of a Fatimid coinage) developed

side by side, indicating that Sind remained the vital commercial hinge that it

had become in the second/ eighth century. When Mahmud of Ghazna con

quered Multan in 400/1010, the Isma'ili communities suffered a severe set

back. They later revived significantly, only to be suppressed once more in 570/

1175 by Muhammad Ghuri, but never entirely.

Throughout the three centuries of Arab Muslim rule in Sind, it appears, urbanism increased. The pastoral and only lightly Indianised Jats and similar

tribes which the Arabs encountered in the waste and swamp lands throughout

lower and central Sind and which they generally described as 'highway robbers',

'thieves' and 'pirates', 27 were brought under the political authority of the

Muslim state. They were either demilitarised and domesticated, or enlisted in

protection rackets as caravaneers, dromedary men, watchmen and the like, or

directly enlisted in the armies. Significant groups of Jats were also deported as

slaves to Iraq, or settled in the swamps of the Shatt al 'Arab (a policy inherited

from the Sasanids). Throughout these centuries, there also appears to have been

a substantial, although by no means complete, shift away from the pastoral

nomadism of lower Sind to a more settled, agricultural existence in the Multan

area and the Punjab, particularly among the Jats. Even the notorious Mids, who

were especially numerous in south eastern coastal Sind, do not seem to have

engaged in large scale piracy at sea between 221/836, when Arab attacks on

them intensified, and the early fifth/ eleventh century, although they held on to

a pastoral existence. There is no evidence that conversion to Islam had pro

ceeded very far by the fifth/ eleventh and sixth/ twelfth centuries anywhere in

Sind, nor that the Buddhists converted. 2. In the early Islamic world, Arab Sind

was, above all, important as a conduit of the India trade. The conquest, the

quickened pace of commerce, and the increase of traffic between India and the

heartlands of the Umayyad and Abbasid caliphates, as well as western Asia,

Africa and Europe, also led to a noteworthy dissemination of numerous Indian

crops hard wheat, rice, sugarcane, new varieties of sorghum, banana, sour

orange, lemon, lime, mango, as well as spinach, artichoke and eggplant/aubergine among them and new agricultural techniques to parts of the

27 Daudpota, Chachndma, pp. 61, 215; al Baladhuri, FutiZfi al bulddn, p. 424.

28 As is maintained by D. N. Maclean, Religion and society in Arab Sind (Leiden, 1989).

Maclean, like others before him, argues that Buddhists collaborated with the Arabs at an

early stage and converted to Islam, lured by the prospect of being incorporated in a

'pan Islamic international trade network'. Not only is there no evidence for this theory,

but Buddhism and Hinduism occurred in blurred forms in Sind.

89

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

world far beyond India. 29 This process was relatively slow and less easily visible,

but its results revolutionised agriculture and may well have been the most

significant legacy of early Muslim rule in Sind over the long term.

The emergence of post-nomadic empires

The next, and most important, chapter in the history of the early expansion of

Islam in India begins with the Turks, a people of Central Asian origin but no

longer nomadic by the time of their arrival in the subcontinent in the late fourth/tenth and fifth/eleventh centuries. Due to the conquests of the Turks,

by the seventh/thirteenth century more people would be living under Islamic

imperial rule in India than anywhere else, even though it would be a long time

before these numbers would be reflected in the numbers of converts.

Meanwhile, the old Islamic heartlands, with only Egypt excepted,

the fifth/eleventh and seventh/ thirteenth centuries, suffered nomad invasions

on an increasingly large and devastating scale first the Saljuqs, then the Mongols (with, in Iraq, Bedouin making destructive inroads into the breaches

left open by the Mongols) followed by extensive nomadisation and a concomitant long term decline of the urban and economic infrastructure. India did not suffer from nomad devastation and already had a population at

this time of around ioo million people, which was, moreover, continually increasing. With the majority of these living in the fertile northern plains at

the time one of the richest agricultural regions which were now coming under Islamic rule, and with the Islamic heartlands in disarray but maritime

trade with Egypt expanding, the Indian subcontinent moved to a central position within the Islamic world at large.

Nomads have never been able to establish empires in the monsoon climate of

India. 30 The Turks who established their Islamic empire beyond Sind in the

fifth /eleventh century, like their pre Islamic predecessors (the Shakas, Kushanas

and Hephthalites), are better designated as post nomadic people, with origins in

the steppes but no longer active practitioners of pastoral nomadism. The successive post nomadic empires which they established were a quite specific

adaptation to the ecological conditions of India. The Indian subcontinent, from a

physiographic point of view, was a zone of transition between the nomadic

world of the deserts and steppes which stretched from North Africa to Central

29 A. Watson, Agricultural innovation in the early Islamic world: The diffusion of crops and

farming techniques, 700 1100 (Cambridge, 1983).

30 Wink, Al Hind, II, pp. 52 76 and passim; Al Hind, III, pp. 118 69; J.J. L. Gommans, 'The

silent frontier of South Asia, c. AD 1000 1800', Journal of World History, 9, 1 (1998), pp. 1 23.

90

Cambridge Histories Online © Cambridge University Press, 201 1

## The early expansion of Islam in India

and Inner Asia and the humid, equatorial parts of Asia where intensive rice

agriculture was practised in alluvial river plains enclosed by rainforests. Because

the arid zone of deserts and steppes had important extensions into India, the

subcontinent was always closely linked to the nomadic world of the arid zone

and it shared some of its features. Historically, it meant, above all, that the

Indian subcontinent was conquered repeatedly by people of nomadic back

ground and then colonised to varying degrees, but that it was never subjected to

extensive nomadisation. Another branch of the Turks, the still nomadic Saljuqs,

in the fifth/ eleventh century, sponsored a significant pastoral immigration into

Iran and Anatolia, but failed to do so in India. There are remains of Saljuq

mausoleums and minarets in Afghanistan, but not beyond. On the Indian frontier, the incidental settlements of Saljuqs that may have occurred remained

isolated, like in Baltistan (on the bank of the Indus, between Gilgit and Ladakh),

where the rajas and viziers claim descent from Saljuq Turks who arrived here

just before their fellow tribesmen pushed into Iran and Anatolia. 31 And there are

some Saljuq families in the Juggaur district of Awadh who claim to be descend

ants of the brother of Nur al Din Muhammad, the Artuqid ruler of Diyarbakr,

and to have arrived there from Anatolia as part of the Ghurid armies in 580 / 1184.

But none of these were nomads. Later, in the seventh/ thirteenth century, the

Mongol nomadic hordes in their turn failed to establish themselves in India on a

permanent basis. Only in areas like Binban and the Kuh i Jud, on the north west

frontier of the subcontinent, did Mongol occupation lead to the devastation of

agricultural land and large tracts of agricultural land being turned into pasture to

sustain the Mongol cavalry. This did not happen in the plains. India was, for

climatological and ecological reasons, unsuitable for Mongol style nomadism.

India's patchy pastoral economy of sheep, goats and cattle always stood in a

competitive relationship with sedentary agriculture, and it could not accom

modate large hordes of Turkish and Mongol nomads on account of its lack

of good pasture lands and appropriate fodder grasses, particularly for horses.

The humid climate of most of the subcontinent was detrimental to the health

of horses and did not provide good breeding conditions, outside a few areas

that were an extension of the arid zone, as in the north west, or in some parts of

the Deccan. Generally, Turko Mongol writing is pervaded by fear of India's

hot and humid climate and concomitant unhealthy conditions for horses as well

as men.

The Turkish conquest of India, then, did not significantly modify the equilibrium between nomadic and sedentary people. The Turks who

31 D. Murphy, Where the Indus is young: A winter in Baltistan (London, 1977), p. 185.

91

# The New Cambridge History of Islam

migrated to India from the steppe, like those who were in the vanguard of the

military conquest, always left their nomadism behind. But, even though their

numbers were dwarfed by the size of the domestic population of the subcon

tinent, the impact of the Turks was immensely important. For one thing, the

Turks extended the rule of Islam across the Indian plains. For another, the

Turks, straddling the arid north west frontier from Afghanistan to the mouth

of the Indus as well as the steppe lands, acquired a virtual monopoly of the

regular supply of good warhorses that the subcontinent could not provide for

itself. Most importantly, the Turkish conquest armies, consisting of regular

and irregular recruits from the nomadic steppes and built around a core of

mamluks but never accompanied by sprawling nomadic hordes with their flocks and herds of sheep, with women and children in tow, brought about

a revolution in warfare and military technique that would change the patterns

of political and resource mobilisation of the subcontinent forever.

The inhabitants of the steppes, living in conditions which were optimal for

horse breeding, in medieval times distinguished themselves by the practice of

mounted archery, and this allowed the Turks to prevail militarily over their

sedentary neighbours, in India as much as in Byzantium, Iran or China. For

this reason the Turks could bring about a horse warrior revolution in India

even though they could not bring about a pastoral nomadic one. The military

differential between the Turks and the Indians, both social and technical in

origin, was an essential factor in the early centuries of incessant conquest

activity, especially because the Turks were relatively few in numbers and

prone to be decimated by disease. While the co ordinated deployment of mounted archers was essential for Turkish military victory, it appears beyond

doubt that in India itself archery was left to infantry and a relatively small

number of elephant riders. Although horses and horsemanship had a long history here, India failed to develop mounted archery, and it was this failure

which was exposed by the Turks coming from Central Asia.

The heavy (although never exclusive) reliance on horses and mounted archery by the post nomadic Turkish empires is what set them apart not only from the Indians but also from the Muslim Arabs who preceded them in

the conquest of the north western frontier areas of the subcontinent. The batdes of the Arabs in the first centuries of Islam were mostly fought by infantry, supported by archers. However, these infantry armies of the Arabs

were not recruited from among the nomads but mostly from among the sedentary population of the towns and oases. The relatively minor nomadic

element in the Arab armies was largely put to tactical use as light cavalry,

especially in raiding excursions. What was essential in the Arab armies was

92

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

superior mobility in the campaigns in the desert and the ability to concentrate

forces over great distances by making use of the dromedary. The role of the

dromedary was decisive in the early Arab conquests and explains, at least

partly, why these conquests did not go much beyond Sind and the arid regions

of the Thar desert. But in spite of the prominent role they gave to the dromedary, the Arab conquerors were clearly not nomads, nor did they introduce mounted archery to India, nor did they bring large numbers of nomadic pastoralists along at a later stage for relocation in Sind.

Post nomadic expansion of the kind that the Turks undertook in India could

normally only be consolidated in the interstices of the sedentary world, along

India's inner frontier of arid and semi arid habitats. Hence the Islamic global

isation of the economy, concomitant with the great increase of the offensive

capabilities of mobile warfare in these centuries, followed the vagaries of the

arid zone. As a result, in this period of post nomadic empire formation, the

role of horses, dromedaries and oxen increased considerably, enlarging India's

capacity for warfare, transportation and cultivation simultaneously.

The importance of the domesticated elephant was, however, from now on gradually reduced in the new warhorse military economy. In India, elephants

were kept in forested reservations outside the cultivated realm where they

needed a transhumance circuit which included both elevated and lowland,

even swamp like, terrain. Such elephant forests, like grazing pastures for horses, stood in a competitive relationship with sedentary agriculture. Over

time, with the agricultural realm expanding, the ecological situation of ele

phants in many parts of the subcontinent had come to resemble more and more that of horses. Horse grazing, on the other hand, had the advantage that

it could be done in non contiguous areas, which were, moreover, not neces

sarily excluded from any other use, as elephant forests mostly were. The mobility of elephants was limited, while they had to be kept in a half tamed or

wild state in forest reservations, and was further impeded by the fodder problem. Horses were more mobile, being always tame, and could more easily be controlled, relocated, concentrated and deployed over long distan

ces. Beginning with the post nomadic empires of the Turks in the late fourth/

tenth and fifth/ eleventh centuries, the disadvantages of the keeping and use of

horses relative to elephants were gradually reduced to the point that elephants

were bound to become ever more obsolete in warfare. Horses proved to be

tactically much more useful in mobile warfare, while elephants could only be

deployed statically, in set battles.

In general, the evidence shows that the post nomadic empires of medieval

India were in an almost permanent state of military mobilisation, and that

93

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

they relied specifically on mounted archers, much like nomadic empires. They were almost equally fluid and indeterminate in their institutional infra

structure (lacking, notably, a clear law of succession). The major difference

was that they did not rely on pastoral nomadism but on agriculture as their

means of subsistence. Post nomadic armies were thus trimmed of their live

stock, and unlike the nomadic armies mobilised by the Saljuqs and Mongols,

did not move in conjunction with women, children and other non combatants, while they were always broken up in smaller contingents and

never moved en masse.

#### From Ghazna to Lahore

Al Biruni, in his Kitab al Hind, dates the beginning of 'the days of the Turks'

from 'the time when they seized power in Ghazna under the Samarii dynasty,

and sovereignty fell to Nasir al Dawla Sabuktigin'. 32, The dynasty of the Ghaznavids, which was then founded, was from the beginning preoccupied

with the invasion of the major river plains, first of the Indus, then the 'five

river' land of the Punjab, and finally the 'two river' land of the Ganges Yamuna Duab. It would pursue these goals until 582/1186, when the dynasty

was overthrown by the Ghurids and their Turkish slave generals who, in their

turn, would push the conquests as far as the eastern Ganges delta. Thus, for

almost two centuries, the Turkish rulers of Ghazna played an important role

in the expansion of Islam. 33 They were quick to proclaim themselves the caliphal defenders of Sunni orthodoxy against the Shi'ite Buyids and the Isma'ili principalities of Sind. Most importantly, they took it as their historic

mission to conquer 'the infidels of al Hind'.

Acutely conscious of their post nomadic status, the Ghaznavids and their Turkish slaves recast themselves as a Perso Islamic ruling elite with such zeal

(adopting even non Turkish names) that it is almost impossible to find significant reminders in the Persian historical record of their Turkishness, or

of their former paganism, let alone their former nomadism. The fact remains

that Turks from the steppes were the most important ethnic component of the

Ghaznavid armies from beginning till end, especially of the mamluk leadership

and elite troops, even though these armies were at all times rather heteroge

neous, including recruits from among the semi nomadic Arab population of

32 al Biruni, Kitab al Hind, p. 16.

33 C. E. Bosworth, The Ghaznavids: Their empire in Afghanistan and eastern Iran. 994 1040

(Edinburgh, 1963); Bosworth, The later Ghaznavids: Splendour and deeay: Tde dynasty in

Afghanistan and northern India, 1040 1186 (Edinburgh, 1977); Wink, Al Hind, II, pp. 112 35.

The early expansion of Islam in India

Khurasan (which had become 'a second Arabia'), and now also from among

the Afghans (still absent in the Arab armies), Daylami infantry and cavalry

(originally from the Caspian Sea area), Tajiks or 'Persians' from Khurasan and

various groups of Indians soon enough Indian Muslims as well. According to

contemporary sources (which are almost certainly highly exaggerating), under

Sultan Mahmud of Ghazna (r. 388 421/998 1030), these regular troops could

number over 50,000, excluding provincial garrisons. Volunteer ghazis, who

went unregistered and without salaries, living off plunder, are said to have

joined in the jihad in even greater numbers.

Up to the end of Mahmud's reign, such Ghaznavid armies remained extremely mobile, undertaking raids into Hind, after the monsoon rains had

subsided, on an almost annual basis, and then withdrawing to Ghazna with

booty and slaves. From about 404/1013<sup> garrisons</sup> were beginning to be left.

behind and forts were conquered on a more permanent basis, while more and

more petty Hindu rajas were beginning to be co opted in the conquest state.

Lahore gradually emerged as a second Ghaznavid capital in the Punjab but did

not replace Ghazna until 555/1160, when the latter city was taken over by the

Ghurids. There were practically no permanent additions to the Ghaznavid conquests beyond Sind and the Punjab at any time, so that beyond these areas

the pattern remained one of lightning raids into 'infidel' territory. Some of the

major sacred sites of the Hindus, such as Kanauj, Mathura, Thaneshwar and

Somnath, were plundered, their icons destroyed or removed, while enormous

amounts of treasure which had been accumulated over centuries (the figures

given by many texts are astronomical) were transferred to the Ghaznavid capital and brought back into monetary circulation or, in their turn, carried

off by the Saljuq armies when they temporarily seized Ghazna in 511/1118.

Scores of mosques were erected with the rubble of smashed temples, with

carefully selected fragments being remitted to Ghazna to be trampled by the

faithful.

Demographic losses resulting from the destruction and killing concomitant

with warfare, as well as from the large scale deportation of war captives and slaves, were probably severely aggravated by the outbreak of a famine,

followed by epidemic disease, in 423/1033, in the wake of several decades of

prolonged campaigning, which seemed to indicate that the great age of Ghaznavid expansion was drawing to a close. According to a later historian,

Firishta: 'This year of 423/1033 was remarkable for a great famine (qaht) in

many parts of the world. The famine was followed by a pestilence which swept away many thousands from the face of the earth. In less than one month

40,000 people died in Isfahan alone. Nor did it rage with less violence in

95

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Hindustan, where whole countries were entirely depopulated.' 34 In the Punjab, when the Hindu Shahi ruler Anandapala was forced out (causing the Isma'ili amir of Multan to flee as well), a great exodus of Brahmans appears

to have occurred from the increasingly Muslim dominated province towards

the mountain valley of Kashmir, as well as to Varanasi and other areas still

beyond the reach of the 'country conquering Turushkas'. Among the invading

Turks, the most substantial losses of manpower were probably caused by exposure to the almost entirely new disease pool comprising malaria, smallpox, cholera, bubonic plague and a host of others of the hot and humid climate of the densely settled plains of India rather than by warfare as such.

An investiture patent was sent from the caliphal office in Baghdad in 421/1030, officially recognising not only the Punjab as a Muslim domain under the

Ghaznavids but also all the areas which they had conquered to the west, as far

as Qasdar, Sibi or Walishtan, Qiqanan and Makran. The dynasty held on to its

possessions in northern and eastern Afghanistan, as well as its Indian con quests, for over a century more. Contemporary authors attached great sig

nifLcance to the establishment of Saljuq suzerainty over Ghazna in 511/1118,

consequent upon the death of Mas'ud. By that time, however, the real threat

to the Ghaznavids' survival came not from the Saljuqs but from the Shansabanis of Ghur.

# Mountains of Firuzkuh, plains of Hind

The Shansabani dynasty superseded the Ghaznavids in the second half of the

twelfth century. This dynasty was not of Turkish, nor even Afghan, but of eastern Persian or Tajik origin, speaking a distinct Persian dialect of its own,

like the rest of the inhabitants of the remote and isolated mountain region of

Ghur and its capital of Firuzkuh (in what is now central Afghanistan). Here it

presided over a mainly agricultural rather than a nomadic population a source of slaves for the Arabs whose external commercial connections were

alleged to have been in the hands of Jews since the time of Harun al Rashid. 35

As long as he remained a Malik aljibal or 'King of the Mountains', the Ghurid

ruler did not have a cavalry at his disposal but merely an army of footsoldiers

34 Ta'rikh i Firishta (Lucknow, 1864), p. 41.

35 N. Lees (ed.), Tabaqat i NasirT of Abu 'Umar aljiizjdni (Calcutta, 1894), pp. 36 7; Wink,

Al Hind, II, pp. 135 49; C. E. Bosworth, 'The early Islamic history of Ghur', Central Asiatic

Journal, 6 (1961), pp. 116, 118; for a modern account, in Dutch, of Firuzkuh, see

G. Mandersloot, Firozkohi: Een Afghaans Reisjournaal (Rotterdam, 1971).

96

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

equipped with long shields made of bullock hide and cotton cloth. When Turkish and Mongol pastoral nomads did penetrate into Firuzkuh in the early

seventh/thirteenth century they, eventually, under Ogedei, utterly destroyed

it, bringing the Jewish presence to an end as well.

Islam had come to Ghur, or at least to its capital, long before the Ghaznavids began to meddle with the Shansabanis' dynastic disputes and, in

the period leading up to the mid sixth/twelfth century, began to prop up the

dynasty against rival mountain chieftains. Gathering strength, the Shansabani

ruler acquired the title of sultan in return for tributary status. Soon after the

mid sixth/twelfth century, however, the Ghurid sultan 'Ala 3 al Dm Jahansuz

(the 'world burner') undertook to use his increased strength for the destruc

tion of the city of Ghazna itself, as well as of the palaces at Bust which had been

built by Mahmud. Now, under an agreement with the Saljuq sultan Sanjar,

effective Ghurid dominion was extended over neighbouring regions like Tukharistan, Bamiyan, Zamindawar, Bust and parts of Khurasan, or as Juzjani, the chief chronicler of the Shansabani dynasty, wrote, with some exaggeration, 'from Hindustan and the frontier of Chin and Mahachin to Iraq

and from the Jihun river in Khurasan to Hormuz'. 36 In the process, the composition and character of the Ghurid armies changed entirely.

Not only did the geographic recruitment area of the Ghurid army broaden

in the second half of the sixth/ twelfth century, but cavalry became all important. In the Ghurid cavalries that invaded India we find Afghans, Damghams from Qumis in northern Iran, Tajiks from Khurasan, Khalaj from Garmsir and Zammdawar, Saljuq amirs from Rum, and innumerable 'Ghuzz Turks' who had arrived in Khutlan and Chaghaniyan around 511/1118

and in Tukharistan, Ghazna, Kabul and Zabul after the mid sixth /twelfth century. Moreover, when in 556/1161 Sayf al Din Muhammad succeeded to

the throne of Firuzkuh, the Ghurid state evolved from a local clan based polity

into an empire led by a Turkish mamluh elite which was largely purchased in

the steppes of Central Asia, thus coming very close to the post nomadic model

of the Ghaznavids who preceded them in the conquest of Hind. Having subdued the Ghuzz Turks at Ghazna, the Ghurid Mu'izz al Din (better known as 'Muhammad Ghuri') in 569/1173 'ascended the throne of Ghazna

like Mahmud'. The Ghurid conquest of Hind then became the work of Sultan

Mu'izz al Din, the ruler of the appanage of Ghazna from 569/1173 to 599/1203

and of Firuzkuh between 599/1203 and 602/1206, and three of his Turkish

slaves, Qutb al Din Aybak, Nasir al Din Qabacha and Taj al Din Yildiz, and

36 Lees (ed.), Tabaqdt i Nasin, p. 76.

97

### The New Cambridge History of Islam

one non slave, Ikhtiyar al Dm Muhammad bin Bakhtiyar Khalaji. Without sons of his own, Mu'izz al Din arranged for his Turkish slaves to become the

heirs to his dominion after his death. Meanwhile he effectively used his prerogative to keep his own Shansabani kinsmen out of his appanage of Ghazna, and by extension out of Hind, and could monopolise its by now diminished but still considerable wealth for himself. 37 In this way, Turkish

predominance in the expanding empire was sealed.

The essential difference between the Ghurids and their Ghaznavid prede cessors did not lie in different military strategies or tactics both relied heavily

on mounted archery but probably in the logistics of supplies. By the late sixth/twelfth century we first hear of the activities in north western India of

regular supply corps or commissariats, the roving bands of grain dealers with

bullock trains which in later times were called Banjdras. These appear to have

made their appearance with the Ghurid armies at this time, some of them already converting to Islam, according to later tradition, under Muhammad

Ghuri. 38 The first nomadic Muslim caravaneers (kdrwdmydri) supplying the

Ghurid armies in the field apparently came from the Multan area athwart the route of the earliest Ghurid campaigns in India. Aiming to bypass the Ghaznavid dominion in the Punjab, Mu'izz al Din in 570/1175 had taken the

southern route through the Gomal Pass, and Multan was the first city he captured, followed by Uch, in upper Sind, leaving both in the hands of a governor. He returned in 573/1178 via the same route, proceeding through the

desert towards Nahrwala in Gujarat, still in an attempt to outflank the Ghaznavids. The defeat of his exhausted army by the Caulukya king Mularaja II induced him finally to give up the southern route. But the nomadic

caravaneers of Multan, if later tradition can be relied on, accompanied the

Ghurids in many, perhaps all, subsequent campaigns.

These subsequent campaigns during the next five years resulted in the subjugation of Sind, as far as Debal and Makran. Peshawar, Sialkot and, through strategem, Lahore were secured by 582/1186, bringing to an end

Ghaznavid rule in the Punjab. Coming into a strategic position to advance into

the plains of northern India, the Ghurids then began to engage Prthiviraja, the

Cahamana 'King of the Earth'. Prthiviraja, heading a powerful alliance of

37 S. Kumar, 'The emergence of the Delhi sultanate, 588 685/1192 1286', Ph.D. thesis,

Duke University (1992), pp. 929.

38 M. A. Sherring, Hindu tribes and castes, vol. Ill (New Delhi, 1974; first published 1881),

p. 80; H. M. Elliot, Memoirs on the history, folk lore, and distribution of the races of the north

western -provinces of India, vol. I (London, 1869), p. 52; P. Carnegy, Notes on the races, tribes

and castes, inhabiting the province of Awadh (Lucknow, 1868), p. 137.

Cambridge Histories Online © Cambridge University Press, 201 1

The early expansion of Islam in India

Indian kings, initially prevailed in the so called First Battle of Tara'in of 587/

1191, forcing the 'army of Islam' back to Lahore. In the following year, however, Prthiviraja's army was scattered and defeated in the Second Battle

of Tara'in, in which the Ghurid elite guard of 10,000 mounted archers appears

to have played a decisive role.

In the events which then unfolded, Qutb al Dm Aybak began his meteoric rise. The forts of Sarsati, Hansi, Samana and Kahram, then Ajmer, Mirath,

Baran, Delhi and Kol, were all in his hands prior to 589/1193. Officially, it was

still Mu'izz al Din who received caliphal authorisation for these conquests and

who built the first triumphal arches and Jami c Masjid in the emerging new

Indo Muslim capital of Delhi. But Aybak, the former slave, was about to ascend the throne of an independent sultanate of Delhi which was largely his

creation a watershed event that happened in 602/1206.

In the intervening years, the conquests were extended from Delhi: to Rajasthan, Varanasi and Bayana; to Gwalior, 'the pearl of the necklace of the

forts of Hind'; up to Bada'un and Katahr, in the northern Duab, and as far as

the frontier of the country of Ujjayn. The Candella forts of Kalanjar, Mahoba

and Khajuraho were taken by Aybak in 598 9/1202 3. Bada'un became the

starting point for the conquests of Awadh, Bihar and Bengal, by Muhammad

bin Bakhtiyar Khalaji, in Aybak's service. Bihar was extensively raided by his

forces. Buddhist monks took flight, or were massacred, their monasteries turned into horse stables. Muhammad bin Bakhtiyar took possession of the

capital of Nadiya in 600/1204, bringing Sena rule to an end, leaving the city in

desolation, and prompting an exodus of Brahmans to the remotest corners

of Bengal, then transferring the seat of Muslim government to Lakhnawti,

a former northern Sena capital on the Ganges, near Gaur. Here another provincial administration was set up, the khutba was read and coins were issued, still in Mu'izz al Din's name, while mosques, madrasas and khanaqas

were founded all over the area. In real terms the conquest was now completed. Well over half a millennium after the beginning of the first campaigns.

Muslim arms prevailed from the Indus to the mouths of the Ganges and Brahmaputra. The plains of Hind were no longer 'in darkness'. 39

39 See C. Defremery and B. R. Sanguinetti (eds. and trans.), Voyages d'Ibn Batoutah, 4 vols. (Paris, 1853 8), II, pp. 89 90.

99

Muslim India: the Delhi sultanate

PETER JACKSON

The emergence of an independent Muslim state in India

Following Mu'izz al Din Muhammad's assassination in 602/1206 the Muslim

conquests in the Indo Gangetic plain went their own way. While the Ghurid

heartlands, Ghur and FIruzkuh, were contested among the various princes of his

dynasty, further east the beneficiaries were the Turkish slave (ghulam; banda)

commanders to whom the sultan had largely delegated authority. 1 Two of

them Taj al Din Yildiz in Ghazna and Qutb al Din Aybak in Lahore were quick to establish their de facto autonomy. Aybak was acknowledged by the

Khalaj rulers who succeeded Muhammad b. Bakhtiyar at Lakhnawti in Bengal.

and thus became the paramount ruler in Muslim India. But Aybak, who contested Ghazna with Yildiz, in turn recognised the overlordship of Mu'izz

al Din's nephew and successor, Ghiyath al Din Mahmud; numismatic evidence

suggests that he bore no higher title than malik After Aybaks death in 607/i2iof, his heir Aram Shah was soon defeated and killed by Aybaks slave

and governor in Budaon, Iltutmish, who had been set up at Delhi. Aybaks territories were now disputed among Iltutmish, Yildiz and another former Ghurid slave lieutenant, Nasir al Din Qubacha, who held Multan and Uchch

in Sind.

If Aybak was the effective founder of an independent Muslim power in India, Shams al Din Iltutmish (607 33/1210 36), 2 was the real architect of the

Delhi sultanate. Although he was initially obliged to acknowledge Yildiz's sovereignty and to content himself with the title of malik, his fortunes

1 Irfan Habib, 'Formation of the sultanate ruling class of the thirteenth century', in Irfan

Habib (ed.), Medieval India 1: Researches in the history of India 1200 1750 (Oxford and Delhi, 1992), PP- 5 7-

2 The correct form of the name was established by Simon Digby, 'Iletmish or Iltutmish? A

reconsideration of the name of the Dehli sultan', Iran, 8 (1970), pp. 57 64.

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

improved as a consequence of events beyond the Indus. In 612/1215E, the

Khwarazm Shah Muhammad b. Tekish overwhelmed the last Ghurid princes

and seized Ghazna from Yildiz. Fleeing into the Punjab, Yildiz was defeated by

Iltutmish on the historic battlefield of Tara'in, captured and later put to death

at Budaon. Then, in 617 21/1220 4, the Khwarazmian empire in turn was destroyed by the pagan Mongols under Chinggis Khan. Muhammad's son Jalal

al Dm, defeated by the Mongols on the Indus (618/1221), spent three years in

exile in the Punjab, where he carved out for himself a short lived principality

before returning to Persia. The Mongol forces sent in pursuit were unable to

apprehend him and ravaged parts of Sind, besieging Multan for several weeks

(621/1224); they did not touch the territory of Delhi. Iltutmish had at first made peace with Jalal al Din, though he seems subsequently to have assisted

Oubacha against him. 3

Qubacha's territories had therefore borne the brunt of the Khwarazmian and Mongol attacks; and this may have weakened him in the face of Iltutmish's

assault in 625/1228, when Uchch and Multan fell and Qubacha drowned himself in the Indus to avoid capture. Within the next few years, Iltutmish expelled one of Jalal al Din's lieutenants from Kurraman and secured the

submission of another, Hasan Qarluq, who ruled in Binban. In 628/i23of. his

son Nasir al Dm Mahmud overthrew the Khalaj ruler of Lakhnawti, who had

assumed the title of sultan, and when a rebellion broke out on the prince's

death soon afterwards Iltutmish crushed it in person and brought the Muslim

held regions of Bengal under his control (630/1232^. Even prior to this, in

626/1229, he had received a patent from the 'Abbasid caliph al Mustansir,

investing him with the government of the whole of Muslim India. When he

died (633/1236), his dominions extended from the river Jhelum almost to the  $\frac{1}{2}$ 

Ganges delta.

Sultans and nobility, c. 1220-1295

The elite of the early Delhi sultanate comprised overwhelmingly first generation immigrants from Persia and Central Asia: Persians ('Tajiks'), Turks, Ghuris and also Khalaj from the hot regions (garmsif) of modern Afghanistan. Even if Fakhr i Mudabbir, writing in 602/1206, exaggerates the

improvement in their fortunes that immigrants could expect, 4 it is clear that

3 See Peter Jackson, 'Jalal al Din, the Mongols and the Khwarazmian conquest of the

Panjab and Sind', Iran, 28 (1990), pp. 45 54.

4 Fakhr i Mudabbir, Shajarat [or Bahr] al ansab, partial edn by Sir E. Denison Ross as

Ta'rikh [sic] i Fakhr al Din Mubdrakshdh (London, 1927), p. 20.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

from the time of the Ghurid campaigns northern India exerted a strong attraction upon them. Such immigration grew in the wake of the Mongol

campaigns of devastation, and Iltutmish is said to have encouraged it. 5 The

majority of the newcomers, perhaps, would have been military men, but a later writer mentions also sayyids and 'ulamd\ Among the latter class was the

historian Juzjani, a refugee from Ghur, who first entered Qubacha's service

but deserted to Iltutmish on his invasion of Sind in 625/1228, and later rose to

be three times grand qddi of the Delhi empire.

Like the Ghurids, however, Iltutmish built up a corps of Turkish slave troops, known from the sultan's own \aqab as the Shamsis. The later historian

Diya yi Barani (fl. 758/1357) refers to them by the term chihilgdriis: its signifi

cance is unclear, though the distributive form may well indicate that each commanded a group of forty ghu lams. 7 Barani characterises Iltutmish's mostly

shortlived successors as mere ciphers who watched helplessly while his Turkish ghu]dms wrested power from the free nobles who had entered Muslim India during his reign.

In some measure, this picture can be substantiated from the Tabaqat i Nasiri

which Juzjani completed in 658/1260. Under Iltutmish's son Rukn al Din Firuz

Shah (r. 633 4/1236) the Turkish household slaves massacred a great many Tajik

bureaucrats; 9 shortly afterwards they overthrew and murdered Firuz Shah in a

rising on behalf of his half sister Radiyya (r. 634 7/1236 40). She in turn was

deposed when she demonstrated signs of independence and showed excessive

favour to her African (HabashT) master of the horse; the Turks enthroned another son of Iltutmish, Mu'izz al Din Bahram Shah (r. 637 9/1240 2). A number of Turkish amirs who attempted to reinstate her as sultan were defeated, and Radiyya was killed by Hindus while in flight near Kaithal (637/1240). Following her deposition, considerable power was vested in a military officer who bore the style of ndHb ('viceroy'); Bahram Shah's own

enthronement was contingent on his acceptance of the Turkish ghiddtn Ikhtiyar

al Din Avbak in this position.™

5 Jajarmi, preface to his translation of al Ghazali's Ihya' 'ulum al din, British Library ms.

Or. 8194, fo. 3v; Nazir Ahmad, 'Benini's Kitab as Saydana and its Persian translation',

Indo Iranica, 14, part 3 (1961), p. 17; Juzjam, Tabaqat i Nasiri, ed. 'Abd al Haiy Habibi, 2nd

edn, 2 vols. (Kabul, AH solar 1342 3), vol. I, pp. 440 1.

6 'Isami (c. 1350), Futuh al saldtin, ed. A. S. Usha (Madras, 1948), pp. 114 15.

7 Peter Jackson, The Delhi sultanate: A political and military history (Cambridge, 1999), p. 66;

Gavin R. G. Hambly, 'Who were the Chihilgani, the forty slaves of Sultan Shams al Din

Iltutmish of Delhi?', Iran, 10 (1972), pp. 57 62.

8 Barani, TafOth i Firuzshahi, ed. Saiyid Ahmad Khan (Calcutta, 1861 2), pp. 27 8, 550.

9 Juzjani, vol. I, p. 456; cf. also vol. II, p. 36. 10 Juzjani, vol. I, p. 463.

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

Aybak's murder at the sultan's instigation prompted fears that he planned

the wholesale annihilation of the Turkish slave commanders, and an army sent

to defend the frontier following the Mongol sack of Lahore turned back and

besieged Delhi. Bahram Shah was put to death and replaced by FIruz Shah's

son, 'Ala' al Dm Mas'ud Shah (r. 639 44/1242 6). We know relatively little of

internal politics during Mas'ud Shah's reign, but a later writer ascribes his

downfall to resentment at his reliance upon African (HabashT) slave elements. 11

He was displaced in favour of Iltutmish's youngest son, Nasir al Dm Mahmud

Shah (r. 644 64/1246 66), a shadowy figure in our sources, who passed much

of his relatively long reign under the tutelage of his viceroy (nd'ib), Iltutmish's

former slave, Baha ] al Dm Balaban. On Mahmud Shah's death, Balaban succeeded him as Sultan Ghiyath al Dm Balaban (r. 664 85/1266 87).

Baram clearly exaggerates the incapacity of Iltutmish's progeny. Radiyya and Bahram Shah both displayed signs of energy, and all four monarchs of

Iltutmish's line appear to have tried to build up power bases of their own. The

implication, moreover, that the Turkish slaves constituted a discrete or monolithic group is simplistic. No faction comprised exclusively Turkish slave officers. They are found collaborating with amirs of Ghuri and Tajik origin as well as free Turkish nobles; 12 while the opposition to Balaban, which

included prominent Turkish ghuldm commanders, was fronted by an Indian

slave amir, 'Imad al Din Rayhan. 13 It is possible, of course, that our perspective

is distorted not only by Baram but also by Juzjani, who was writing for Balaban, himself a Turkish gkularn. Turkish slave officers may only seem to

dominate the political landscape because they are the principal focus of the

penultimate section itabaaa) of his work.

Moreover, far from eliminating immigrant notables the Turkish ghuldm element ultimately lost out to them. Fugitives from the territories conquered

by the Mongols continued to enter Muslim India during Balaban's reign, among

them the Khalaj amir and future sultan, Jalal al Dm. From 659/1261, when the

Mongol empire dissolved in civil war, even Mongol notables sought asylum in

Delhi, where they became known as 'neo Muslims' (now musulmanan), and a

whole quarter of the old city was assigned to them. 14 Balaban has been accused

11 Yahya' ibn Ahmad Sirhindi, Tarikh i Mubarakshahi, ed. S. M. Hidayat Hosain (Calcutta,

1931), P-34-

12 Peter Jackson, 'The Mamluk institution in early Muslim India', Journal of the Royal Asiatic

Society (1990), pp. 347 9, and Jackson, Delhi sultanate, pp. 68 9.

13 Jackson, Delhi sultanate, pp. 71 3.

14 Firishta, Guhhan i IbrahtmT, lithograph edn, 2 vols. (Bombay, AH 1247), vol. I, p. 131,

citing the late eighth/fourteenth century writer 'Ayn al Mulk Bijapuri; Baram, Tarikh i

Firuzshakl, p. 133.

103

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

of sapping the strength of the Turkish nobility by destroying many of his erstwhile Shams! colleagues; but like his old master Iltutmish he clearly sought

to promote his own Turkish ghuldms (known as 'Ghiyathis'), several of whom

received high military command and lucrative assignments (iqtd's).

Balaban's elder son Muhammad perished in battle with the Mongols (683/1284); and when the old sultan died, a party among the nobility ignored

the claims of both Muhammad's son Kaykhusraw and Balaban's younger son,

Bughra Khan, and installed the latter's young and pliable son, Mu'izz al Din

Kayqubad (r. 685 9/1287 90). Kaykhusraw, who made an unsuccessful bid for

Mongol support, was murdered. Bughra Khan, who governed Lakhnawti, advanced west in a bid for the throne, but was reconciled with his son and

contented himself with autonomy in Bengal. Kayqubad fell increasingly under

the control of the powerful justiciar (dddbek), Nizam al Din, who destroyed

many of Balaban's Turkish slave officers, and of the immigrant 'neo Muslim'

Mongol amirs. After Nizam al Din's own murder, a faction deposed the ailing

Kayqubad in favour of his infant son, Shams al Din Kayumarth (r. 689/1290),

but lacked the strength to resist the Khalaj commander Jalal al Din, the gover

nor of Samana, who eliminated both Kayqubad and the child ruler and himself

assumed the title of sultan as Jalal al Din Firuz Shah (r. 689 95/1290 6).

During the seventh/thirteenth century the Muslim held territories in west ern Bengal and Bihar were often in rebellion under ambitious governors; from

Kayqubad's accession (685/1287) they formed an independent sultanate until

their reconquest in 724/1324. The Delhi sultan's authority often barely extended beyond the lower and middle Indus Valley, the eastern Punjab, the towns of the Duab and parts of Awadh. Only a relatively small area, comprising Delhi and its environs (hawdlT) and perhaps one or two other strongpoints such as Gwalior, was retained as khdlisa, the 'reserved' territory,

exploited directly by the sultan's own revenue officials. The monarch could do

no more than grant out other territories to his officers as iqtd': that is, the

grantee (muqta') was responsible for extracting tribute from the local chiefs

(rdnagdn, muqaddamdn) and headmen (kh.iita.ri), maintaining himself and a body

of troops from the proceeds and, by the turn of the century, forwarding the

surplus (fawddil) to Delhi. In Balaban's reign the appointment of an accountant

(khwdja) to each iqtd' indicates the government's concern both to maximise its

revenues and to rein in the ambitions of its leading amirs. 15

15 Baram, Tdnkh i Rruzshdhi, pp. 36 7; Irfan Habib, 'Agrarian economy', in Tapan

Raychaudhuri and Irfan Habib (eds.), The Cambridge economic history of India, vol. I:

c.1200 c.ijso (Cambridge, 1982), pp. 69 70.

Muslim India: the Delhi sultanate

Warfare with the Hindu states

The struggles for power at the centre during the seventh/thirteenth century

inevitably had an impact on the expansion of the sultanate. In stark contrast

with the era of his lieutenancy on Mu'izz al Din's behalf, Aybak's reign witnessed no recorded campaigns against independent Hindu kingdoms, and Iltutmish, during the first fifteen years of his reign, is known only to have

headed one such expedition, against the Chauhan (Chahamana) kingdom of

Jalor. It is clear, moreover, that some of Aybak's conquests were lost after

his death and had to be retaken by Iltutmish, only to pass out of Muslim hands again. Two examples will suffice. The great fortress of Ranthanbor, seat of the senior line of the Chauhan dynasty, had been reduced to tributary

status in 587/1191, but must have defied Iltutmish, who took it in 623/1226.

Further east, Gwalior had yielded to Aybak in 597/i2oof, but was subse quently lost, since Iltutmish recaptured it in 630/1233. Yet both towns were

abandoned under Radiyya in 635/i237f Ranthanbor was repeatedly attacked

(in 646/1248, 657/1259 and 691/1292) before its final reduction by Ala 1 al Dm

Khalji. Gwalior's recovery at some point before 657/1259 was shortlived, and thereafter we cannot be sure that it was ever in Muslim hands prior to

the eighth/fourteenth century. Even in the 1340s the Moroccan visitor Ibn

Battuta describes this important strongpoint as 'an isolated and inaccessible

castle in the midst of the infidel Hindus' and sets its garrison at 600 horse

men, who were constantly engaged in jihad. 1

The north western districts of the Punjab, as we shall see, lay within the penumbra of Mongol sovereignty; even much of the eastern Punjab was home to imperfectly subdued tribes like the Khokhars, the Bhattis, the Jats

and the Mandahars of Kaithal. There were numerous mawasdt (sing, mawtis,

'refuge'), where the sultan's writ barely ran and could be enforced only by

painstakingly hacking down the jungle. 17 During his reign, as in his final years

as viceroy, Balaban's principal concerns appear to have been the reduction of

the hilly tracts (kuhpdya) west of the capital, the erection of forts in the Duab

16 Ibn Battuta, Tuhfat al nuzzar, ed. Ch. Defremery and B. R. Sanguinetti, 4 vols. (Paris, 1853 8), vol. Ill, pp. 188, 195, and trans. H. A. R. Gibb and C. F. Beckingham, The travels of Ibn Battuta AD 1325 1354, Hakluyt Society, 5 vols. (Cambridge and London, 1958 2000), vol. Ill, pp. 642, 645.

17 Ibn Battuta, vol. Ill, p. 389 (trans. Gibb and Beckingham, vol. Ill, pp. 741 2). For an example (Katehr), see Simon Digby, 'Before Timur came: Provincialization of the Delhi sultanate through the fourteenth century', Journal of the Economic and Social History of the Orient, 47 (2004), p. 302 and n. 5.

105

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

and punitive campaigns against the notoriously refractory Hindus of Katehr (now Rohilkhand).

Much of the campaigning by the seventh/thirteenth century monarchs or their representatives, in fact, might seem to have had no purpose and certainly no effect beyond the temporary humiliation of Hindu potentates and the guarantee of annual tribute or the acquisition of large quantities of

precious metals and impressive numbers of slaves, horses and elephants. Juzjani, it is important to note, suggests that the main purpose of warfare against Hindu kingdoms was to amass the resources which would enable the

sultans to raise larger armies to resist the Mongols. 1 Whatever the case, in the

wake of such swashbuckling and often risky campaigns, the spread of Muslim

settlement, the construction of mosques and the regular extraction of land

revenue (khardj) from local Hindu chiefs were a less spectacular and doubtless rather intermittent process.

## The Mongol threat in the thirteenth century

The reigns of Iltutmish's first successors witnessed a steady build up of Mongol pressure beyond the Indus. Generals acting on behalf of the qaghan

Ogedei (r. 1229 41) destroyed the residue of the Khwarazmian principality,

driving Hasan Qarluq from Binban into Sind, and reduced to obedience the

other local rulers in present day Afghanistan; they thereby secured the terri

tories that had acted as the springboard for Ghurid invasions of India half a

century previously. Kashmir was invaded and reduced to tributary status in

c. 632/1235. The first Mongol attack on the Delhi sultanate came in 639/1241,

when they sacked Lahore. In 643/1245 they invested Uchch, necessitating a

relief expedition under Sultan Mas'ud Shah. From this point onwards Mongol

raids upon the westernmost provinces became an annual occurrence. Nor

were they an altogether unwelcome element in the politics of the sultanate.

Sultan Mahmud Shah's brother Jalal al Dm took refuge with them in c. 1250,

and on the orders of the qaghan Mongke (r. 1251 9) an army under Sali Novan

installed him as ruler of a territory that embraced Lahore, Nandana, Kujah

(now Gujrat) and Sodra. 19 We do not know what became of the prince,

18 Juzjani, vol. II, p. 57.

19 Karl Jahn, 'Zum Problem der mongolischen Eroberungen in Indien (13. 14.

Jahrhundert)', in Akten des XXIV. intemationalen Orientalisten Kongresses Miinchen ...

1957 (Wiesbaden, 1959), pp. 617 19. I. H. Siddiqui, 'Politics and conditions in the

territories under the occupation of Central Asian rulers in north western India 13th

and 14th centuries', Central Asiatic Journal, 27 (1983), pp. 288 306.

106

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

though Kiishlii Khan, the sultan's governor of Sind, likewise accepted client

status in 653/1255; and by the time Juzjam wrote in 658/1260 there are signs of

apprehension that the Delhi sultanate would fall under Mongol overlordship.

In that very year Balaban, as Mahmud Shah's viceroy, was in diplomatic contact with the qaghan's brother Hiilegu, who was in overall command of

Mongol forces in Persia. The object and outcome of these negotiations are

alike unclear, and it is just at this juncture, regrettably, that juziam's narrative

comes to a halt.

The sultanate undoubtedly owed the reprieve it now obtained not so much

to diplomacy as to the disintegration of the Mongol empire. Following Mongke's death in 1259, civil war broke out in the Mongolian homeland. Other members of the dynasty took sides in this struggle, and a secondary

conflict erupted between Hiilegti, in Persia, and his cousin Berke, who

commanded the Mongols of the Golden Horde in the Pontic and Caspian steppes. By the time that Qubilai emerged as undisputed qaghan in the Far

East (1264), the empire had splintered into a number of rival khanates: the

Ilkhanate, under Hiilegii and his descendants in Persia; the khanate of the

Golden Horde; the Chaghadayid khanate in Central Asia; and the dominions

of Qubilai and his successors in Mongolia and China. The situation was further

complicated, first, by the flight of Berke's troops from Persia into Afghanistan

(c. 660/1262) under a commander called Negiider, who gave his name to a

new, independent Mongol grouping; and second, by the emergence in Central

Asia in 669/1271 of Ogedei's grandson Qaidu, who headed a confederacy of

Mongol princes in opposition to the qaghan until his death in 1303. The empire

did not again acknowledge a single head until Qaidu's son Chapar submitted

to the qaghan Temiir in 1304.

These upheavals enabled Balaban, early in his reign, to reassert the sultan's authority in Sind and to restore the fortifications of Lahore. Mongol pressure on the Punjab was naturally at its greatest when mounted

by a major Mongol power drawing on the resources of the whole empire or

at least of Central Asia. The Negiideri Mongols (or Qara'unas, as they were

also known) did not fall within this category. Although they continued to raid the sultanate annually, they appear to have penetrated no further than

Rupar, on the upper Sutlej, 20 or the Multan region, where they did, how ever, succeed in defeating and killing Sultan Balaban's son Muhammad in 683/1285.

20 Baram, Tankh i Firuzshahi, p. 82: for the corruption in the text here, see S. H. Hodivala,

Studies in Indo Muslim history, 2 vols. (Bombay, 1939 57), vol. II, pp. 85 6.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

From the Khaljis to the Tughluqids

The ethnic origins of the Khalaj are obscure; although early Arab geographers

class them among the Turkish tribes, by the seventh/thirteenth century they

were regarded as a separate people, distinct from the Turks. 21 Yet the signifi

cance of the so called 'Khalji revolution' does not lie so much in the transfer of

power from a Turkish ruling elite to a non Turkish one. It is true that Ialal

al Dm promoted to high office several of his numerous kinsfolk and other fellow Khalaj tribesmen, and that in 690/1291 he had to crush a rebellion by

Balaban's nephew and supporters of the old dynasty. But Ghiyathi amirs were

by no means excluded from the state apparatus. It was only after the sultan's

assassination by his nephew 'Ala' al Dm (695/1296), the muqta' of Kara, that a

marked change occurred in the composition of the ruling class.

Jalal al Din's youngest son, Rukn al Dm, was proclaimed sultan in Delhi, but

fled to Multan, where he held out with his brothers until the city fell to his

cousin's forces (696/1296). 'Ala 1 al Din Muhammad Shah (r. 695 715/1296 1316)

is said to have brought down the great majority of his uncle's amirs and those

who survived from the era of Balaban and Kayqubad. His most trusted servitors

were close kinsmen and officers who had formed his entourage at Kara. But the

example set by the new sultan was infectious, and during the early years of his

reign he was confronted with a number of bids by relatives to murder him and

seize the throne; even his brother, Ulugh Khan, was allegedly planning an

unauthorised expedition to Tilang at the time of his sudden death.

Under 'Ala' al Din Indian slave amirs first appear to have held high military

rank, and during the final stage of the reign one of these, the eunuch Kafur,

attained a position of dominance, persuading the sultan to imprison his son

Khidr Khan in Gwalior and to nominate as his successor one of his younger sons

by the daughter of the Yadava king of Deogir. When 'Ala' al Din died, this child

was duly enthroned as Shihab alDIn 'Umar (r. 715 16/1316) under Kafur's

tutelage. 'Ala' al Din's sons were blinded, with the exception of Qutb al Din,

who engineered Kafur's murder and himself ascended the throne as Qutb al Din

Mubarak Shah (r. 716 20/1316 20). Qutb alDin was in turn murdered by his

Indian favourite Hasan, on whom he had conferred the title Khusraw Khan and

who now seized the throne. During his brief reign (720/1320), Nasir al Din

Khusraw Shah the only Indian convert, in fact, ever to become Sultan of

21 Baram, Tarikh i Firuzshahi, pp. 150, 171 2; C. E. Bosworth and Sir Gerard Clauson, 'Al

Xwarazmi on the peoples of Central Asia', Journal of the Royal Asiatic Society (1965), pp. 6,

8; repr. in Bosworth, The medieval history of Iran, Afghanistan and Central Asia (London,

1977); Aziz Ahmad, 'The early Turkish nucleus in India', Turcica, 9 (1977), pp. 99 109.

108

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

Delhi had all 'Ala' al Din's sons killed. When one of Ala' al Din's officers, Tughluq, the muqta c of Deolpalpur, overthrew the usurper with the ostensible

aim of avenging his old master's dynasty, he himself was proclaimed sultan as

Ghiyath al Din Tughluq Shah (r. 720 4/1320 4). 22

Tughluq, who was in all probability an immigrant of Turco Mongol origin from the Qara'una (Negiideri) territories in Afghanistan, 2,3 came to power

with the aid of officers who had served under him on the north western frontier; and men from these regions would play a prominent role in the early

years of Tughluqid rule. In 724/1324 the sultan personally intervened in a

succession dispute in Muslim Bengal, where Balaban's line had died out earlier

in the century, 24 and occupied Sunargaon, installing his own client at Lakhnawti. He died while he was on his way back to Delhi from this campaign

later in the year, when a palace that had been erected for his reception at

Afghanpur by his son and heir Ulugh Khan collapsed on him. Ulugh Khan, who now succeeded as Sultan Muhammad b. Tughluq (r. 724 52/1324 51), is

nevertheless exonerated of the charge of parricide by the majority of contem

porary sources and of modern historians.

#### The great Mongol invasions

'Ala' al Din's reign witnessed a sharp escalation in Mongol attacks. From the

1280s the Negiideri territories had been under pressure from the Chaghadayid

Mongols of Transoxiana and Turkistan. By c. 1295 the Chaghadayid khan Du'a, who was allied with Qaidu, had established his son Qutlugh Qocha as

ruler of a large principality south of the Amu darya (Oxus). Qutlugh Oocha

and Qaidu's commanders were responsible for a series of major assaults, which penetrated more deeply into northern India than previous attacks. The most formidable occurred during 'Ala' al Din's absence from Delhi on campaigns against independent Hindu powers. In c. 699/12.99^. Qutlugh Qocha in person headed a campaign which almost reached Delhi, although

he was wounded and died during the retreat; 25 while in 703/1303 his general

Taraghai was able to subject the capital to an investment lasting several weeks.

22 For the probable date of Tughluq's death, usually placed in 725/1325, see Jackson, Delhi sultanate, pp. 330 1.

23 R. C. Jauhri, 'Ghiyafhu'd Din Tughluq his original name and descent', in Horst Kriiger

(ed.), Kunwar Mohammad Ashraf: An Indian scholar and revolutionary 190J 1962 (Berlin, 1966), pp. 62 6.

24 Abdul Majed Khan, 'The historicity of Ibn Batuta re Shamsuddin Firuz Shah, the

so called Balbani king of Bengal', Indian Historical Quarterly, 18 (1942), pp. 65 70.

25 See Jackson, Delhi sultanate, p. 222.

109

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

After this, the outbreak of civil war in Central Asia between Du'a and Chapar

seriously impaired the Mongols' ability to mount major strikes against India

for some time. Ala ] al Din's amirs, notably Tughluq at Deopalpur, were able

not only to defeat invading Mongol forces, who may in some cases have been

fugitives, but even to take the offensive and launch campaigns beyond the

Indus. 2 Ibn Battuta saw an inscription at Multan in which Tughluq laid

to twenty nine victories over the Mongols. 27

Muhammad b. Tughlug began his reign with an expedition to Peshawar,

which lay on the very border of the Mongol dominions, and may thereby have

provoked a large scale invasion by the Chaghadayid khan, Du'a's son Tarmashirin, who threatened Delhi and advanced as far as Mirat (Meerut)

before withdrawing beyond the Indus. At one time the historicity of this attack

was denied, on the grounds that the standard recension of Baram's Tarikh

makes no reference to it; but it is in fact mentioned not only by another contemporary, 'Isami, but also in an earlier recension of Barani's work and by

an author writing in the Mamluk empire, who dates it at the beginning of 730/winter of i329f 2 Tarmashirin's attack was to be the last major assault on

the sultanate prior to Temiir's invasion.

The aims behind the Mongol invasions of India are difficult to assess. Elsewhere in Mongol held territories the traditional aim of world conquest

had not been jettisoned, but it is conceivable that in India the hot season acted

as a significant deterrent to permanent occupation. For this reason the Mongols had abandoned the siege of Multan in 621/1224, 29 and those whom

Jalal al Din Khalji installed in the vicinity of Delhi in 691/1292 did not remain

long because the climate was uncongenial to them. 30 On the other hand, such

considerations do not seem to have prevented Mongol notables and their families from settling in India at other times, as during the reigns of Balaban

and Kayqubad. The invading Mongol armies in 691/1292 and in c. 1306 were

26 According to a document found in Amir Khusraw, Rasd'il al i'jdz, lithograph edn, 5 vols,

in 2 (Lucknow, 1876), vol. IV, pp. 144 56. See Jackson, Delhi sultanate, pp. 229 30.

27 Ibn Battuta, vol. Ill, p. 202 (trans. Gibb and Beckingham, vol. Ill, p. 649).

28 Shams al Din Muhammad al Jazari (d. 739/1338), Hawadith al zamdn, ed. 'Abd al Salam

Tadmuri, 3 vols. (Beirut, AH 1419), vol. Ill, p. 377; Peter Jackson, 'The Mongols and the

Delhi sultanate in the reign of Muhammad Tughluq (1325 1351)', Central Asiatic Journal,

19 (i975), PP- 118 26, and Jackson, Delhi sultanate, p. 232.

29 'Ala' al Din Ata Malik Juwaym, Tdfikh i Jahdn gushd, ed. Mirza Muhammad Qazwini,

3 vols., Gibb Memorial Series, vol. XVI (Leiden and London, 1912 37), vol. I, p. 112, and

trans. J. A. Boyle, The history of the world conqueror, 2 vols.

(Manchester, 1958, repr. in 1

vol., 1997), vol. I, p. 142.

30 Barani, Tdrikh i Rruzshdht, p. 219.

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

certainly accompanied by women and children; 31 and during Muhammad b.

Tughluq's reign Mongol commanders, with their wives and offspring, would

winter in the Punjab every year in anticipation of the sultan's largesse. 32.

Qutlugh Qocha and Taraghai, at least, were probably intent on the plunder

afforded by a wealthy city like Delhi. But other campaigns may have repre

sented simply seasonal migrations in search of winter grazing grounds.

# The conquest of India

A change of tempo is also visible during 'Ala 1 al Dm Khalji's reign in the context of relations with independent Hindu kingdoms. As muqta' of Kara under Jalal al Dm, he had led an audacious raid into the distant Yadava kingdom in the Deccan, sacking its capital, Devagiri (Deogir). Following his

accession he launched an expedition against Gujarat (698f.f12.99f.), which

sacked Somnath, Anhilvara (Patan) and Kanbhaya (Cambay); though the Chaulukyas were not finally overthrown until c. 710/1310 and even thereafter

Muslim rule was confined to the eastern parts of their kingdom. 'Ala 1 al Din

then embarked upon the reduction of Rajasthan and the far south. While the

sultan himself captured Ranthanbor (700/1301) and Chitor (703/1303), his

generals took Sevana and Jalor (708/i307f) and overthrew the Paramara kingdom of Malwa (705/1305). As a consequence, an inscription of i309fi in

the vicinity of Chanderi could describe the 'Mlecchas' as having overrun the

earth in 'Ala 1 al Din's time and strongholds such as Dhar, Mandu, Chanderi

and Erach could be granted out as tqta's. 33

The sultan's Indian slave lieutenant, Malik Kafur, was especially prominent in

campaigns further to the south. His first expedition reduced the Yadava king

Ramadeva to client status (706/1307). Ramadeva was brought to Delhi and

treated with honour by 'Ala 1 al Din, who then sent him back to the Deccan as

his subordinate. The value of this relationship was demonstrated in the consid

erable assistance that Ramadeva furnished for Kafur's subsequent campaigns;

his successor, however, would repudiate Delhi's overlordship, necessitating a

fresh campaign by Kafur against the Deccan (c. 7i4/i3i4f). 34 In further expedi

tions Kafur exacted tribute from the Kakatiya kingdom of Tilang (709/1309^)

and the Hoysala kingdom of Dvarasamudra (7io/i3iof). An assault on the

31 Ibid., pp. 219, 321 2.

32 Ibid., p. 499.

33 Michael D. Willis (ed.), Inscriptions of Gopaksetra: Materials for the history of central India

(London, 1996), p. 22; Baram, Tdrikh i FiruzshahT, p. 323.

34 Kishori Saran Lai, A history of the Khaljis AD 1290 1320, 3rd edn (Delhi, 1980), pp. 255 7.

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

Pandya kingdom of Ma'bar (710/1311) secured plunder, though not submission.

In the north, meanwhile, by stages that are largely concealed from us, the

subjugation of regions like Bundelkhand and Awadh was accelerated.

Expansion into peninsular India continued under Ala ] al Din's successors.

Qutb al Din headed a successful expedition against the rebellious Deccan (717/1317), and his favourite Khusraw Khan conducted a wide ranging cam

paign against Ma'bar; though the reduction of much of the country seems to

have been left until the reign of Ghiyath al Din Tughluq (c. 1323) or perhaps

that of Muhammad b. Tughluq (c. 1327). 35 It was Muhammad who, as Ulugh

Khan's and his father's heir apparent, had defeated the recalcitrant Kakatiya

monarch, Rudradeva II, and asserted direct rule over Tilang (c. 72i/i32if). While in pursuit of the rebel Baha' al Din Garshasp in 727/1327, Muhammad's

generals overthrew the kingdom of Kampila and annexed it to the sultanate.

The spectacular expansion of 'Ala 3 al Din's reign rested upon the successful

imposition of a system of direct taxation within northern India (see below).

But more general circumstances underlying Muslim military superiority need

to be taken into consideration. One must have been the sultans' access to a

larger supply of good warhorses via the overland route from Central Asia and from the Golden Horde territories in the steppes north of the Black Sea

and the Caspian than was available to their Hindu opponents in peninsular

India, who were dependent on the seaborne trade in horses from Fars and the

Arabian peninsula. The Delhi sultans' cavalry often outnumbered that of their

antagonists, and the readiness of Hindu princes to pay high prices for good

quality warhorses was notorious. 36

The sultans' armies may also have enjoyed an advantage in siege technol ogy. It is widely accepted that the late seventh/thirteenth century witnessed

the introduction into the subcontinent of the counterweight trebuchet (maghribi) from Muslim regions to the west. This represented a major advance

on the older type of catapult (manjariiq; 'arrada), since it was capable of throwing a projectile at least four times as heavy over a distance at least twice as great. 37 The role played by gunpowder is less clear. The Mongols had

35 N. Venkataramanyya, The early Muslim expansion in south India (Madras, 1942), pp. 70, 122 5.

36 Simon Digby , War horse and elephant in the Dehli sultanate: A study of military supplies

(Oxford and Delhi, 1971), pp. 29 32; Ranabir Chakravarti, 'Horse trade and piracy at

Tana (Thana, Maharashtra, India): Gleanings from Marco Polo', Journal of the Economic

and Social History of the Orient, 34 (1991), pp. 159 82; Andre Wink, Al Hind: The making of

tfte Indo Islamic world, vol. II: The slave kings and the Islamic conquest of India, ntft 13th

centuries (Leiden, 1997), pp. 83 7.

37 Jos Gommans, 'Warhorse and gunpowder in India c.iooo 1850', in Jeremy Black (ed.),

War in the early modern world (London, 1999), pp. 112 13.

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

been acquainted with gunpowder since their campaigns of the 1230s in China

and had apparently been using it in Persia in the 1250s; and from the very

limited evidence found in contemporary Indo Muslim sources a case has been

made for the introduction of gunpowder based devices into northern India

before 1300, perhaps through the agency of Mongol renegades. 3

Administrative developments under c Ala 5 al-Din and his successors

Both the successful resistance to major Mongol attacks during 'Ala 3 al Din's

era and the pronounced territorial expansion over which he presided were

made possible by administrative measures which, in the first place, greatly

extended the area under the sultan's direct control and subjected it to a uniform system of land tax. Unlike the kharaj previously levied, which was

simply tribute by another name, that imposed by c Ala J al Dm was a percentage

of the value of the crop or, in some regions, of the crop itself, required on the

basis of measurement and at the time of the harvest (bar sax i kisht). The rate

was 50 per cent, the maximum permitted by the Hanaf 1 school which was

dominant in the sultanate. Barani, who is our principal source for these measures, presents them at one point as an expedient designed to bring low

the rural Hindu chiefs, an aim with which he himself was stridently in sympathy. 39 But he also makes it clear that the impulse behind them was

militaristic 40 to enable the sultan to raise considerably larger armies, in order, presumably, both to repel the Mongols (see below) and to conquer the

Hindu kingdoms of central and southern India. It is a measure of the govern

ment's enhanced effectiveness that the land tax proper could be levied in both

newly conquered Jhayin (near Ranthanbor) and in Kabar (in the hitherto turbulent territory of Katehr).

The second arm of 'Ala 1 al Din's policy was the enforcement of low prices

and wages in Delhi and its environs and possibly in some other regions also.

Doubt has been expressed regarding the reliability of the data supplied by

Barani, who is our principal source for these measures; but Irfan Habib has

38 Iqtidar Alam Khan, 'The role of the Mongols in the introduction of gunpowder and

firearms in South Asia', in Brenda J. Buchanan (ed.), Gunpowder: The history of an

international technology (Bath, 1996), pp. 33 44; Khan, 'The coming of gunpowder to

the Islamic world and north India: Spotlight on the role of the Mongols', Journal of Asian

History, 30 (1996), pp. 27 45; Khan, Gunpowder and firearms: Warfare in medieval India

(Oxford and Delhi, 2004), pp. 17 40 passim.

39 Barani, Tarikh i Firuzshdhi, pp. 287 8.

40 Ibid., pp. 304, 323 4-

113

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

shown both that they were intimately linked with the taxation policy and that

Barani's material is corroborated by other authors. 41 The chief priority was

that prices for grain and other foodstuffs should be kept at a level which would

enable the sultan to pay his troops at a fixed and relatively modest rate.

We are told that 'Ala' al Din's price control measures did not survive him. 42

But the growth of centralised control at the expense of the sultan's represen

tatives in the provinces undoubtedly continued after his death. Although under Ghiyath al Din Tughluq the muqta' still had access to that portion of

the ic0 revenue which was earmarked for the stipends of his troops, a further

erosion of the mugta"s rights occurred during the reign of his son and

successor. We know from an external observer that there was now a direct

link between the revenue department and the ordinary trooper, that is, that

the allocation to the muqta' of the funds to pay his troops, and hence his capacity to bind them to his own interests, had ceased. 43 Ibn Battuta reveals

that within the province of Amroha, for instance, there was now ensconced,

alongside the military commander, a financial officer (wall al kharaj) answer

able directly to the sultan. 44 It has been plausibly suggested that this encroach

ment may have fostered the discontent among the military class that characterised the latter years of Muhammad's reign. 45

The reigns of Muhammad b. Tughluq and Firuz Shah

At the accession of Muhammad b. Tughluq (r. 724 52/1324 51), the Delhi sulta

nate embraced a larger area than at any time previously. The sultan's reputation

as a formidable holy warrior and victor over the Mongols reached Persia and

Mamluk Egypt, 46 and according to Ibn Battuta, who visited India during Muhammad's reign, even the rulers of the Maldives feared him. 47 He seems to

41 See Irfan Habib, 'The price regulations of 'Ala'uddm Khalji a defence of Zia' Baram',

Indian Economic and Social History Review, 21 (1984), pp. 393 414.

- 42 Baranl, Tdrikh i Firuzshahi, pp. 383 6.
- 43 Ibn Fadl allah al 'Umari (d. 749/1348), Masalik al absdrfimamalik al amsar, partial edn by

Otto Spies, Ibn Fadlalldh al 'Oman's Bericht iiber Indien (Leipzig, 1943), Arabic text p. 13

(German trans, pp. 378), and trans. I. H. Siddiqi and Q. M. Ahmad, A fourteenth century

Arab account of India under Sultan Muhammad bin Tughlaq (Aligarh, 1975), pp. 37 8.

44 Ibn Battuta, vol. Ill, pp. 436, 439 (trans. Gibb and Beckingham, vol. Ill, pp. 762, 763).

45 Habib, 'Agrarian economy', pp. 72 3.

46 Shabankaral, Majma' al ansdb, ed. Mir Hashim Muhaddith (Tehran, AH 1363 solar),

pp. 87 8, 287; Ibn Fadl allah al 'Umari ed. Spies, p. 29 (German trans., p. 55); trans.

Siddiqi and Ahmad, p. 54; partial edn by Klaus Lech, Das mongolische Weltreich,

Asiatische Forschungen, 22 (Wiesbaden, 1968), Arabic text p. 40 (German trans., p. 118).

47 Ibn Battuta, vol. IV, p. 158 (trans. Gibb and Beckingham, vol. IV, p. 843).

114

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

have been a man of boundless ambition. Bararii, who for seventeen years was a

member of his entourage, asserts that the sultan would not tolerate a single island

or closet remaining outside his authority. 48 The same author pays tribute to the

efficiency of the revenue department, during Muhammad's early years, in levying

the kharaj from an unprecedented number of far flung provinces. 49

The successive crises which afflicted the sultanate under Muhammad were

accordingly all the more perplexing. Here we should bear in mind two circumstances. In the first place, the recent imposition of direct rule over so

much of the south entailed both the forfeiture of plunder and new fiscal commitments in terms of maintaining garrisons and a civil administration in

formerly enemy territory. And second, in the 1330s the Ilkhanate and the Chaghadayid khanate in Central Asia entered upon a period of upheaval, while the Egyptian Mamluk sultanate underwent a series of monetary crises.

We cannot dismiss the possibility, therefore, that in Muhammad's time the

sultanate and its neighbours and major trading partners were engulfed in a

common economic turbulence.

Bararii, however, blames the upheavals on the sultan's own policies: the establishment of Dawlatabad (Deogir), in the Deccan, as the second capital;

the so called 'Khurasan project'; a sharp increase in the government's revenue

demand from the Duab cultivators; and the introduction of a 'token' cur rency. 5 ° It will be argued here that these various measures were closely linked

and that they were by no means as chimerical as Bararii claimed.

Bararii provides inconsistent definitions of the region of 'Khurasan', which

Muhammad planned to invade, and has thereby misled modern historians. It is

clear that the expedition was directed against the old enemy, the Mongol Chaghadayid khanate in Transoxiana and present day Afghanistan; indeed, at

one point Bararii specifies that Ma Wara' al Nahr (Transoxiana) was the target. A

large force set at 475,000 in an earlier recension of Barani's work and at 370,000

in the standard text was mustered specifically for the purpose, but had to be

disbanded owing to a lack of money to pay the troops in the second year. In an

attempt to keep the troops in training and doubtless also for the sake of plunder,

a part of this army was despatched into an unspecified region of the sub Himalaya (termed Qarachil in our sources), but with disastrous consequences.

From this point onward, the sultan and the Chaghadayid rulers seem to have been on amicable terms. Muhammad is said to have corresponded with

Baram, Tankh i Firuzshaht, p. 458. 49 Ibid., pp. 468 9. 50 Ibid., p. 471. Cambridge Histories Online © Cambridge University Press, 201 1

#### The New Cambridge History of Islam

Tarmashirin, whose offspring took refuge with him after their father's over

throw and death in  $735/1334^$  and subsequently played host to a fresh wave of

Mongol notables and their followers during the upheavals that convulsed the

Chaghadayid polity. He jettisoned military confrontation with the Mongols in

favour of using the vast patronage at his disposal to win over individuals and

groups. 51 By his last years, he was on friendly terms with the amir Qazaghan,

the effective ruler of the western Chaghadayid khanate in Transoxiana, who

was of Qara'una origin (as Muhammad's own dynasty may have been): Qazaghan would furnish him with a body of Mongol auxiliaries for his final

campaign in Sind in c. 751/1350.

Closely connected with the Khurasan expedition was the establishment of

second capital at Dawlatabad; and one author hints that they coincided. 52 The

broader impulse behind the choice of Deogir seems to have been twofold: to

implant Islam more securely in the newly conquered Deccan province and to

create a more suitably situated administrative centre for the greatly extended

sultanate. But the nature and timing of the project, which was launched in

727/i326f, have been obscured. The aim was not to abandon Delhi com pletely. It was the principal residents only of the old city of Delhi (the QiYa yt

RdiPithura, i.e. the city of Prthviraja, captured by Aybak in 589/1193) and their

households who were moved south. The newer 'cities' in the Delhi complex,

like Siri, Hazar Sutun and Tughluqabad, were not affected; at this very time

Muhammad was engaged in ambitious construction projects in the region,

including a new fortress, c Adilabad, near Tughluqabad, and a wall that linked

the old city of Delhi with Sir! to enclose an area henceforward known as Jahanpanah. 53 And Baram's statement that the amirs and maliks and their

troops were with the sultan in Delhi while their families were in Dawlatabad shows that Muhammad was turning the old city into a vast military encampment. 54

The increase in taxation in the Duab was also intimately linked with the needs of the enormous 'Khurasan' force. Baram, again, has helped to confuse

the question by using the phrase yaki ba dah wa yaki ba blst ('tenfold and

51 Ibid., first recension, Bodleian ms. Elliot 353, fo. 199b; Jackson, Delhi sultanate, pp. 233 5.

52 Mir i Khwurd, Siyar al awliyd', lithograph edn (Delhi, AH 1302), p. 271.

53 H. Waddington, "Adilabad: A part of the "fourth" Delhi', Ancient India, 1 (1946),

pp. 60 76; A. Welch and H. Crane, 'The Tughluqs: Master builders of the Delhi

sultanate', Muqarnas, 1 (1983), pp. 128 9.

54 Barani, Tdrikh i Firuzshdhi, p. 479; Peter Jackson, 'Delhi: The problem of a vast military

encampment', in R. E. Frykenberg (ed.), Delhi through the ages: Essays in urban history,

culture and society (Oxford and Delhi, 1986), pp. 24 6, and Jackson, Delhi sultanate,

pp. 258 60.

116

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

twenty fold') for the rise. Any enhancement in the revenue demand, following

so swiftly on Tarmashirin's devastation of the province, would have caused

unrest. But if we piece together the scraps of information in our sources, it

seems that the khardj was now demanded partly in cash, that the basis of assessment was a standard (and not the actual) yield, that the value of the crop

was calculated according to decreed (and not current) prices and that a number of other taxes were simultaneously imposed on them. 55 The culti

vators were being required to pay, as well as provision, the unprecedentedly

large army that Muhammad had amassed. That the remuneration of the troops placed a strain on the sultan's finances is also clear from other evidence:

the abandonment of 'Ala 3 al Din's system, with a partial reversion to the assignment of iqtffs to pay the troops; 56 and the issue of a low denomination

currency from 73o/i329f onwards. This latter measure, like the reduction of

the silver content of the tanga since 727/1326<sup>^</sup> was designed to remedy an

acute shortage of silver in the Delhi sultanate. 57

The reign appears to be dominated by revolts. The two earliest (727 8/i326f.) those of Kushlii Khan, governor of Sind, and Baha 1 al Dm Garshasp,

governor of Sagar in the Deccan were the work of men closely associated with Tughluq's seizure of power in 720/1320, and were seemingly sparked off

by the Dawlatabad project. Kushlii Khan was allegedly stung into rebellion by

the arrogance of an officer sent to oversee the transfer of his family to the

south, and Garshasp may have been concerned about the establishment of a

new bastion of central power so close to his own territory. Both were crushed,

as was an insurrection by Ghiyath al Dm Bahadur Bura, a scion of the former

ruling dynasty in Bengal, in 73o/i329f

The revolt of the Duab cultivators, which lasted from 732/i33if. to 734/i333f

and necessitated campaigns by Muhammad in person to suppress it, served to

ignite a series of further risings throughout the sultanate as Muslim amirs and

Hindu chiefs alike sought to profit from the sultan's embarrassments, and thus

led to the permanent loss of a number of distant territories. In the far south,

Ma'bar seceded (734/1334) under an officer who assumed the title of Sultan

Jalal al Dm Ahsan Shah. In 735 / i334f Muhammad led an army south to recover

the province, but was obliged to retreat by the outbreak of an epidemic which

severely reduced the number of troops under his command. This crisis

55 Barani, Tdrlkh i Firuzshdhi, pp. 473, 479; also first recension, Bodleian ms. Elliot 353, fo.

192b; Sirhindl, pp. 101 2; Jackson, Delhi sultanate, pp. 262 3.

56 Barani, Tdrlkh i Firuzshdhi, pp. 476 7.

57 Simon Digby, 'The currency system', in Raychaudhuri and Habib (eds.), Cambridge economic history of India, vol. I, pp. 97 8.

117

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

sparked off further revolts. Two Hindu chiefs formerly in the sultan's service

established the new state of Vijayanagara with its nucleus in Kampila, and

another Hindu warlord seized power in Tilang (c. 736/1335^). In the same year,

a rebel named Fakhr al Din ('Fakhra') seized control in Bengal following the

assassination of Muhammad's governor. When fresh troops failed to arrive

from Delhi, a loyal officer named 'All Mubarak himself assumed the title of

sultan at Lakhnawti in opposition to Fakhra. From c. 743/i342f both men were

confronted by a third claimant, Shams al Dm Ilyas Shah, who would emerge

victorious by the early 1350s. 58

The secession of these provinces prompted Muhammad to make greater demands on the territories he still controlled, and this in turn provoked further

risings by Muslim officers, probably c. 740/1339L Nizam Ma ] in and Nusrat

Khan, who had farmed the revenues at Kara and at Bidar respectively, both

rebelled when they were unable to amass the enormous sums which they had

contracted to raise. 'Ayn al Mulklbn Mahru, the governor of Awadh, rebelled

under the false impression that Muhammad planned his recall and execution.

There is also evidence that resentment against the sultan's pagan Hindu servitors underlay some insurrections, such as that in Sivistan (Sehvan) in

c. 742/i34if, when a Hindu officer whom Ibn Battuta calls Ratan was killed,

and that of All Shah Kar ('the Deaf) in Bidar slightly later, when the chief victim was a Hindu tax farmer named Bhiran. 59 These revolts were all suppressed.

The sultan, whose relations with many representatives of the religious class, especially the Chishtiyya, were strained, seems to have tried to win their support by securing confirmation of his title from the puppet 'Abbasid

caliph maintained by the Mamluk sultans at Cairo. He was the first Delhi ruler

to win caliphal recognition, in all likelihood, since Radiyya and certainly since

the sack of Baghdad in 656/1258; the arrival of an official envoy with a diploma

in 745/i344f was attended by considerable ceremony. At this point Muhammad still retained the allegiance of the great majority of the military

class, but in 7 45 / i344f new revenue raising arrangements for the Deccan and

for Gujarat met with determined opposition from the amiran i sada ('amirs of a

hundred') in the two provinces. Muhammad defeated the Gujarat rebels and

then moved to Dawlatabad, where he was again victorious. But on his

58 A. H. Dani, 'Shamsuddin Ilyas Shah, Shah i Bangalah', in H. R. Gupta et al. (eds), Essays

presented to Sir Jadunath Sarkar, 2 vols. (Hoshiarpur, 1958), vol. II, p. 55.

59 K. A. Nizami, 'Sultan Muhammad bin Tughluq (1324 51)', in M. Habib and K. A. Nizami,

A comprehensive history of India, vol. V: The Delhi sultanat AD 1206 1526 (New Delhi, 1970), p. 565.

118

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

withdrawal to deal with a fresh rising in Gujarat by his Turkish ghuldm, Taghai, insurrection flared up in the Deccan once more, and in Rabi 1 II 748 /August 1347 the province seceded under Hasan Gangu, the founder of

the Bahmani dynasty (748 933/1347 1527). The sultan died on the banks of the

Indus on 21 Muharram 752/20 March 1351 after spending his last three years in

Gujarat and Sind in a vain attempt to eliminate Taghai, who was not killed

until a few weeks later. ° The sultanate now wielded no authority south of the

Narbada river.

Muhammad's cousin Firuz Shah (r. 752 90/1351 88), who was proclaimed sultan by the army commanders in Sind, had first to deal with a mutiny by

Mongol detachments which had formed part of the late ruler's army. Then he

advanced slowly on Delhi, where a faction centred on the vizier, Khwaja

Jahan, had enthroned an alleged infant son of Muhammad. The opposition

melted away, and although Khwaja Jahan submitted he was shordy put to death at the instigation of the amirs. A later conspiracy to replace Firuz Shah

with Muhammad's sister's son came to nothing. The legitimacy of the regime

was boosted by the arrival of successive embassies from the c Abbasid caliph at

Cairo from 754/1353 onwards, bringing diplomas that recognised Firuz Shah as

the only Muslim ruler in the subcontinent and indeed over a still wider area

that included Sarandib (Sri Lanka), the Maldives, Java and Sumatra.

In military terms, Firuz Shah's reign was undistinguished. The sultan declined an invitation from elements in Ma'bar to intervene there, and the

shortlived sultanate of Ma'bar would be snuffed out by Vijayanagara in 779/i377f. Firuz Shah also abandoned a projected expedition against the Bahmani regime at Dawlatabad. Two attacks on Bengal, the first against Ilyas Shah (754/1353) and the second against his son Sikandar Shah (760/1359), achieved little more than the acquisition of elephants and other

items of tribute; Bengal would remain independent until the tenth/sixteenth

century. Of the two expeditions which the sultan headed into Sind in the late

1360s with the purpose of avenging Muhammad's humiliation, the first failed

and the second was hardly more effective. His most successful campaign, against the fortress of Nagarkot (c. 766/1365), resulted in the submission of its

raja; the region would serve as a base for his son Muhammad in the civil wars

that followed the old sultan's death.

In order to prevent a repetition of the unrest that had plagued his cousin's

reign, the new sultan made concessions to the amirs, the military class and

even the cultivators. Iqta's, including the smallest assignments made to

60 Sirat i FiruzshdhT, School of Oriental and African Studies ms. 283116, pp. 19, 27 8.

# Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

individual troopers, and administrative posts were made hereditary. In c. 759/1358

the revenue demand for the whole empire was fixed at 67,500,000 tangas for the

duration of the reign. Firuz Shah, a man of undoubted if conventional piety, also

made efforts to retain the support of the religious class, abolishing the uncanonical

taxes imposed by Muhammad and setting aside a total of 3,600,000 tangas for

'u]ama\ shaykhs and other holy men. In strictly political terms, these measures

appear to have paid off. We know of only one revolt during the reign, that of

Shams al Din Damgharii in Gujarat (782/1380<sup>^</sup>, which was put down by the local

amiran i sada. It is clear, nevertheless, that such tranquillity was achieved at a price.

The policy of hereditary iqtffs risked the creation of autonomous principalities in

an era of lesser security; and at the fiscal level, the government failed to benefit

from a general increase in agricultural production, to which, incidentally, Firuz

Shah's own measures to extend cultivation had contributed. The military

sequences of this decline in the government's resources, accentuated by a decade

of internecine strife, would become evident when Temiir attacked Delhi in

801/1398.

#### Hindu-Muslim relations within the Delhi sultanate

The era of the Delhi sultanate witnessed the first implantation of Islam within a vast region lying east and south east of the Indus Valley. The sultans' attitudes towards 'Hinduism', their treatment of their non Muslim

subjects, and the way in which those subjects viewed Islam and Muslim rulers, are accordingly matters of some moment; but discussion of these

issues has been bedevilled by preconceptions born of modern communal ism. Admittedly, literary sources such as the voluminous works of Amir Khusraw Dihlawi (d. 726/1325) furnish numerous examples of opprobrious

comment about 'Saturnian' or 'crow faced' Hindus. J Yet it is clear that beneath such polemic lay a substratum of everyday intercourse between Hindus and Muslims. Muhammad b. Tughluq, who gained a reputation for

fraternising with Hindus, 2 was possibly only the most eminent Muslim figure to take part in Hindu festivities. And against epigraphical evidence that denounces the barbarian (mleccha) Muslim invaders and celebrates their

defeat at the hands of Hindu kings must be set those Sanskrit inscriptions

which, like the Palam Baoli inscription of 1276, simply locate the Muslim

61 Annemarie Schimmel, 'Turk and Hindu: A poetical image and its application to

historical fact', in Speros J. Vryonis, Jr (ed.), Islam and cultural change in the Middle Ages

(Wiesbaden, 1975), pp. 107 26.

62 'Isami, Futuh al saldtin, p. 515.

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

sultans within a sequence of ruling dynasties and utilise the symbolism and

motifs of an earlier era to depict their rule. 63 Even in the far south, where the

sultans' faith was rejected along with their sovereignty, the culture and titulature of the court of Vijayanagara retained the imprint of several years' subjection to the Delhi sultanate. 64

The complexity of the relations between the sultans and their Hindu subjects can be illustrated with reference to two questions: the fate of Hindu religious establishments and the imposition of the jizya (the Islamic

poll tax). Muslim conquerors and rulers have often been charged with the wholesale desecration or destruction of Hindu temples, and hence with fanatical hostility towards Hinduism. Admittedly, whatever doubts attach to

the claims of the early seventh/thirteenth century author Hasan i Nizami that

Aybak uprooted 'idolatry' and destroyed idol temples in a number of centres

(including a thousand in Varanasi), architectural remains endorse his state

ment that the materials from demolished temples were incorporated in newly

constructed mosques, as for instance in the Qutb Minar at Delhi and the Arhai

Din ke Jhompra mosque at Ajmer. 65 But recent research suggests that such

actions sprang less from Muslim iconoclasm than from an awareness of Indian

political tradition. That is to say, Muslim rulers were actuated by precisely the

same considerations as were the plundering attacks by Hindu kings on temples in the territories of their Hindu rivals namely, further to undermine

the legitimacy of the defeated sovereign by severing the intimate link between

his authority and the religious complex over which he presided. Moreover.

the situation in the immediate wake of the Muslim conquest and the impact of

Muslim rule, once established, might well differ sharply. In much the same

way as Hindu kings had patronised Muslim mosques within their dominions,

63 Brajadulal Chattopadhyaya, Representing the Other? Sanskrit sources and rfte Muslims

(eighth to fourteenth century) (New Delhi, 1998), pp. 48 54. But cf. Peter Hardy, 'The

authority of mediaeval Muslim kings in South Asia', in Marc Gaborieau (ed.). Islam et

societe en Asie du Sud, Collection Purusarthe, 9 (Paris, 1986), p. 39.

64 Philip B. Wagoner, '"Sultan among Hindu kings": Dress, titles, the Islamicization of

Hindu culture at Vijayanagara', Journal of Asian Studies, 55 (1996), pp. 851 80; also

Wagoner, 'Harihara, Bukka, and the sultan: The Delhi sultanate in the political

imagination of Vijayanagara', in David Gilmartin and Bruce B. Lawrence (eds.),

Beyond Turk and Hindu: Rethinking religious identities in Islamicate South Asia

(Gainesville, FL, 2000), pp. 300 26.

65 Hasan i Nizami, Taj al ma'athir, India Office ms. 15 (Ethe, Catalogue, no. 10), fos. 53a, 74b,

134b, 185a; Robert Hillenbrand, 'Political symbolism in early Indo Islamic mosque

architecture: The case of Ajmir', Iran, 26 (1988), pp. 105 17.

66 Richard M. Eaton, 'Temple desecration and Indo Muslim states', Journal of Islamic

Studies, 11 (2000), pp. 293 302; repr. in Gilmartin and Lawrence (eds.), Beyond Turk

and Hindu, pp. 254 60.

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

and continued to do so even when under attack from Delhi, the sultans and

their officers can also be found extending their protection, and donating funds,

to Hindu (or Jain) religious establishments. 67 Of the numerous documents

conferring land and tax exemptions on Brahmans, Jains, jogis and Parsis, issued by the Mughal emperors or by the rulers of the successor states to the Delhi sultanate, some clearly represent the renewal or extension of grants

made in the sultanate period.

The Muslim legal texts which enjoyed authority throughout the wider Islamic world make no mention of Hindus among the dhimmis ('protected peoples'), those non Muslims who were liable to pay the jtzya (a graduated

poll tax); although an obscure reference in the Qur'an to a people called the

'Sabians' had enabled the early Arab conquerors to admit Zoroastrians to dhimml status. By the eighth /fourteenth century a good many Indo Muslim

authors and one legal text composed within the sultanate, the Fatawayi Ftruzshahi, were prepared to refer to the sultan's Hindu subjects as dhimmis.

Kufi's Chach nama (c. 6i3/i2i6fi), which purports to be a Persian translation

of an earlier (lost) work in Arabic, speaks of the levying of the jizya on the

conquered population of Sind at the time of the Muslim conquest in the early

second/eighth century. This is quite anachronistic, and it has been suggested

that this kind of statement was used to justify what had become standard practice in Sind by the time the Chach nama was written. 69 References to

seventh/thirteenth century conditions in India seem to show the term jtzya

(sometimes kharaj wa jizya) being used of the tribute rendered by Hindu potentates. The occasional allusion by Barani raises the slight possibility that

the poll tax was levied on the Hindu populace within Muslim held towns in

northern India. 70 But the earliest incontrovertible evidence for the imposi

tion of the jizya as a discriminatory tax on individual non Muslims dates from the reign of the Tughluqid Firuz Shah; though it is difficult, even so, to

see how the measure could have been enforced outside the principal urban centres.

67 Carl W. Ernst, Eternal garden: Mysticism, history and politics at a South Asian Sufi center

(Albany, NY, 1992), pp. 32 3, 48 50; Eaton, 'Temple desecration', pp. 302 3 (and in

Gilmartin and Lawrence, p. 261).

68 B.N. Goswamy and J. S. Grewal (eds.), The Mughals and the Jogis ofjakhhar (Simla, 1967),

pp. 20 1. For the Lodi period, see also Iqtidar Husain Siddiqi, 'Wajh i Ma'ash grants

under the Afghan kings (1451 1555)', Medieval India: A miscellany, 2 (1972), pp. 36 7.

69 Peter Hardy, 'Is the Chach nama intelligible to the historian as political theory?', in

Hamida Khuhro (ed.), Sind through the centuries (Oxford and Karachi, 1981), pp. 116 17.

70 Barani, Tdrikh i Firuzshahi, p. 217; Barani, Fatawa yi Jahdndari, ed. Afsar Saleem Khan

(Lahore, 1972), p. 167.

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

The civil wars and Temiir's invasion

During his last years Firuz Shah had associated with him first his youngest son

Muhammad Shah and then Tughluq Shah, the son of his grandson Fath

who, after enjoying quasi sovereign status in the empire in the 1350s and early

1360s, had died in 778/1376. 7I Tughluq Shah II (r. 790 1/1388 9), who duly

succeeded his great grandfather, was able to hold off Muhammad, but was

himself murdered by a cousin, Abu Bakr Shah (r. 791 2/1389 90). There now

ensued a duel for the throne between Muhammad, who commanded the support of the majority of the provincial governors, and Abu Bakr, who was

based in Firuz Shah's new residence of Firuzabad and backed by the old sultan's numerous slaves. It was only when a significant number of these slave

officers, for unknown reasons, transferred their allegiance to Muhammad that

Abu Bakr was expelled from the Delhi complex, enabling his rival to enter the

capital and to order the execution of all the Firuzshahi slaves in the opposition

party. Abu Bakr was subsequently captured (793/1390^) and died in captivity

in Meerut.

Muhammad's triumph was a hollow one. He was able to replace the rebellious governor of Gujarat (793/1391), but otherwise his brief reign was

spent endeavouring to enforce obedience on Hindu princes rather closer to

the capital, notably the muqaddams of Gwalior and Etawa, and Bahadur Nahir,

the chief of the Meos (Miwat) immediately south west of Delhi, who had been

a steady adherent of Tughluq Shah and Abu Bakr Shah. Muhammad was preparing a campaign to suppress Shaykha, the Khokhar chief, who had rebelled and occupied Lahore, when he died in 796/1394; his son and succes

sor, Humayun Shah, followed him to the grave a month later. Another son of

Muhammad, the ten year old Mahmud Shah (r. 796 815/1394 1412), was there

upon proclaimed sultan.

The new reign began auspiciously, when Sarang Khan, the newly appointed governor of Deolpalpur, dislodged Shaykha from Lahore, while the vizier Khwaja Jahan Sarwar was given the title of malik al sharq and entrusted with the government of an enormous tract extending from the Duab to Bihar, with its centre at Jawnpur. But antipathy between the principal

amirs at court, Muqarrab Khan, the sultan's deputy, and Sa'adat Khan, the

bdrbek (military chamberlain) and a former slave of Muhammad Shah, and the

71 For coins in Fath Khan's name, see H. Nelson Wright, The coinage and metrology of the

Sultans of DehlT (Delhi, 1936; repr. New Delhi, 1974), pp. 186 8; and for the precise

genealogy of these princes, Jackson, Delhi sultanate, p. 332.

123

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

intrigues of Mallu Khan, Sarang Khan's brother, paralysed the regime. Sa'adat

Khan was ousted and retaliated by proclaiming as sultan at Firuzabad Nusrat

Shah, a brother of Tughluq Shah II (797/ i394f). Sa'adat Khan shortly fled from

Firuzabad to Delhi, where Muqarrab Khan put him to death; but the oppo

sition centred on the person of Nusrat Shah continued. The forces of the two

sultans Nusrat Shah commanding the allegiance of the districts between the

Duab, Sambhal, Panipat and Rohtak, while Mahmud Shah was acknowledged

in Delhi and Sir! fought numerous engagements but were unable to dislodge

each other from their respective power bases. This was the situation when the

Central Asian conqueror Temiir 'the Lame' (Timiir i lang, Tamerlane') invaded northern India.

The turbulence that afflicted the Chaghadayid khanate from Tarmashirin's

reign onwards had lasted for over a quarter of a century, and had led to its

division into a western khanate, centred on Transoxiana, and an eastern, embracing the more nomadic lands and known as Mughulistan. Although the Punjab and Sind suffered minor forays early in the reign of Firuz Shah,

these are likely to have been the work of small groups of fugitives dislodged

from Transoxiana in the struggles that followed Qazaghan's death in 759/1358

and preceded the rise of Temiir in the late 1360s. Once he had become from

77i/i369f de facto master of the western khanate, which he ruled through a

puppet khan of Ogedei's line, Temiir embarked on a career of conquest that

pitted him against the khans of the Golden Horde, the various local princes

who had taken over the lands of the Ilkhanate in Persia, and the Delhi sultanate, so frequently invaded by Chaghadayid armies in the past.

One source alleges that Temiir and Firuz Shah had corresponded, and that

Muhammad Shah, during his struggle with Abu Bakr Shah in 792/1390, had set

out for Samarqand to seek Temiir's assistance when he was summoned to Delhi to take the throne/ 2 Temiir himself claimed that as a good Muslim he

was impelled by the duty to punish the rulers of Delhi for having allowed such

latitude to their pagan Hindu subjects; though as it transpired the victims of

his Indian campaign would be overwhelmingly Muslims. In any case, Temiir needed no pretext for attacking India. His military operations were ostensibly

designed to recreate the world empire of Chinggis Khan, who had entered

India briefly in c. 1223.

Temiir's advance forces, commanded by his grandson Pir Muhammad, who governed Kabul, took Multan in 800/1397. Temiir himself moved

72 Muhammad Bihamadkham, Tankh i Muhammadl, British Library ms. Or. 137, fos. 422b 423a,

442b; trans. M. Zaki (Aligarh, 1972), pp. 32, 59 60.

124

Cambridge Histories Online © Cambridge University Press, 201 1

Muslim India: the Delhi sultanate

through Multan and the Punjab by way of the Ghaggar river, to do battle with

Sultan Mahmud Shah and Mallu Khan in the plain outside Delhi on 7 Rabi c II

801/16 December 1398. Despite a spirited resistance, the Delhi army was routed; Mallu and the sultan fled, and the Chaghadayid forces plundered the

city for several days. The rival sultan, Nusrat Shah, abandoned Firuzabad for

the Duab, where the conqueror soon followed him. After storming Meerut.

however, Temiir began a gradual withdrawal westwards across the Indus. His

triumph can be attributed to the fact that he had welded the Chaghadayid

nomads into a formidable military machine and drew, in addition, on con tingents supplied by client rulers beyond the Chaghadayid boundaries. Nevertheless, the weakness of the opposition must also be taken into account.

Against the invaders Mallu and the sultan had been able to muster only 10,000

horse, 20,000 foot and 120 elephants, 73 a pitiful force compared with those

available to 'Ala 3 al Din Khalji, to Muhammad b. Tughluq or even to Firuz Shah.

# The truncated sultanate

While Mallu re established himself in Siri, where he was rejoined after a time by

Mahmud Shah, and brought back under control the Duab and the environs

(hawalT) of the capital, what remained of the Delhi sultanate underwent

irrevocable fragmentation. Autonomous states emerged under Khidr Khan in

Multan, Zafar Khan Wajih al Mulk in Gujarat, Amid Shah (Dilawar Khan) in

Malwa, Shams Khan Awhactl in Bhayana, Khwaja Jahan Sarwar in Jawnpur

and Mahmud Khan b. Firuz Khan in Kalpi. It should be noticed that all these

rulers except the last had been nominees and supporters of Muhammad Shah

(r. 792 6/1390 4); and even Mahmud Khan of Kalpi, whose father had been

vizier to Tughluq Shah II, had submitted to Muhammad after Abu Bakr's downfall and received an increase in his territory. All, again with one exception.

were slow to declare their independence of Delhi and appear to have done so

only after Temiir's attack. The exception was Khidr Khan, who, expelled from

Multan by Sarang Khan, had thrown in his lot with Temiir and had been reinstated in the city as his lieutenant. It was Khidr Khan who defeated and

killed Mallu Khan in 808/i405f Mahmud Shah maintained a shadowy authority

73 Ghiyath al Din 'All Yazdi, Ruz noma yi ghazawdt i Hindustan, trans. A. A. Semenov,

Dnevnik pokhoda Timura v Indiiu (Moscow, 1958), p. 115; Nizam i Shami, Zafar noma,

ed. Felix Tauer, Histoire des conquetes de Tamerlan, 2 vols., Monografie Archivu 125

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

in Delhi until his death in 815/1412; then, following the brief reign of the amir

Dawlat Khan, Khidr Khan occupied the capital (817/1414).

Under Khidr Khan's dynasty known, in view of their alleged descent from the Prophet Muhammad, as the Sayyids (817 55/1414 51) the sultanate had

shrunk to being just one of a number of competing principalities in the north.

Khidr Khan (r.  $817\ 24/1414\ 21$ ) at no point assumed the title of sultan, but

contented himself with the style ofrayat i a c ld ('exalted standard'). He, his son

Mubarak Shah (r. 824 37/1421 34) and the latter's nephew Muhammad Shah

(r.  $837\ 49/\ 1434\ 45$ ) acknowledged the sovereignty of Temiir's son, Shah Rukh

(d. 850/1447), who ruled in Herat, though this did not afford them security

against further attacks by that monarch's kinsmen and lieutenants in Kabul. 74

The Sayyid rulers' own military energies were absorbed in attempts to extract

the land revenue from the Meos, the Duab, Katehr, Etawa and Gwalior and

by the need to defend their territories against threats from the sultanates of

Malwa, Gujarat and, especially, Jawnpur. In the west, Multan, Khidr Khan's

old base, seceded under the dynasty of a local shaykh (847/1443). In the east,

Jawnpur denied the sultanate access both to important sources of elephants

and to some of the most fertile of its former territories. A historian writing in

the Mughal era immortalised a contemporary ditty that saluted the last Sayyid,

'Ala 3 al Dm Alam Shah (shah i 'alam, 'world king'), as ruler only from Delhi as

far as Palam. 75

Afghan immigrants, who had first attained prominence among the amirs during the Khalji era, formed a high proportion of the nobility and the military

officers under the Sayyids, and in 855/1451 one of their chiefs, Bahlul Lodi,

displaced the feeble 'Alam Shah and ascended the throne. Under the Lodi dynasty (855 932/1451 1526) the sultanate enjoyed something of a renaissance.

Bahlul (r. 855 94/1451 89) conquered the sultanate of Jawnpur (884/1479). His

son and successor, Sikandar (r. 894 923/1489 1517), reduced Bihar and Nagaur,

terminated Awhadi rule in Bhayana (898/1492^ and recovered territory both

from the Hindu ruler of Gwalior and from the Muslim sultan of Malwa. It is a

measure of his preoccupation with his southern frontiers that in 911/1505 he

transferred his capital from Delhi to Agra.

Afghan immigration continued apace under the Lodis, and although Bahlul

had been content to be simply primus inter pares, his successors were con

cerned to impose their will upon the Afghan chiefs. Sikandar achieved this by

74 Hafiz i Abru, Zubdat al tawdrikh, ed. Sayyid Kamal Haj Sayyid Jawadi, 2 vols. (Tehran,

AH solar 1372), vol. II, pp. 408 9, 641 2, 680 1, 755, 798 9.

75 Ahmad Yadgar, Tdnkh i Shahl, ed. M. Hidayat Hosain (Calcutta, 1939), p. 5.

126

Cambridge Histories Online © Cambridge University Press, 201 1

#### Muslim India: the Delhi sultanate

diplomatic means, but the more high handed tactics of his son Ibrahim (r. 923 32/1517 26) provoked sharp opposition. One Afghan amir rebelled in

Bihar, while another, Dawlat Khan Lodi, governor of the Punjab, made overtures to Babur, a descendant of Temiir who since 910/1504 had ruled in

Kabul and who had already invaded the Punjab three times. Babur took Lahore (930/1524), and two years later advanced on Delhi. On 8 Rajab 932/

20 April 1526, despite the numerical superiority of the Delhi forces and

in some measure to Babur's artillery, Ibrahim was defeated and killed at Panipat and Babur supplanted the Lodis.

The victory at Panipat marked the establishment of the Mughal empire. Although many historians now regard the expulsion of Babur's son Humayun

by Shir Shah, and the brief reassertion of Afghan rule in Delhi under the Sur

dynasty (947 62/1540 55), as introducing a restoration also of the Delhi sultanate, this episode is best reserved for a later chapter.

In its early stages, the Delhi sultanate survived upon raids against inde pendent Hindu kingdoms, which yielded plunder and tribute and enabled it to

withstand pressure from the Mongols in the north west. From the time of 'Ala' al Dm Khalji, a successful attempt was made to field more formidable

armies by maximising the appropriation of the agrarian surplus. At the same

time, however, the balance of military priorities changed, and the sultans followed a policy of imposing direct control over Hindu states in Rajasthan

and the south. This shift brought in its wake administrative and economic problems, with the result that the sultanate forfeited first its more distant territories in Bengal and the south and then those closer to Delhi. Temiir's

attack effectively delivered the coup de grace; but the Delhi polity still survived

for more than a century as one of a number of rival states in northern India.

Cambridge Histories Online © Cambridge University Press, 201 1

#### 4

The rule of the infidels: the Mongols and the Islamic world

BEATRICE FORBES MANZ

The formation of the Mongol empire

The Mongol period was a watershed for the Islamic world, as it was for most.

of Eurasia. The ferocity of the conquest and the confusion of early rule exacerbated an agricultural decline already deepened by decades of internal

warfare. For artisans and merchants, however, the period brought significant

new opportunities. As foreign nomads, the Mongols were not a novelty, and

eastern regions had already experienced the rule of the non Muslim Qara Khitay. However, the Mongols replaced the familiar caliphate with a new imperial ideal and administrative methods conceived and tested in Mongolia

and China. While the Chinggisid rulers were quick to adopt the bureaucratic

practices of conquered territories, they did so within a framework conceived

at the beginning of Chinggis Khan's rule; thus steppe traditions lay at the base

of Mongol administration.

The political and economic connections of the Mongolian plateau reached from northern China to western Turkistan (see Map 2). Its southern sections

were closely involved with China and the Silk Road and sometimes in contact

with powers to the west. In the northern forest region many tribes lived from

hunting and fishing or reindeer herding, while in the steppe pastoral

nomadism prevailed. There were also agricultural settlements. Two related

languages, Turkic and Mongolian, predominated, sometimes spoken within

one confederation. The most powerful populations were the pastoral nomads,

and it is probably not by chance that the Mongols set their myth of origin in

the time and place of their transition to pastoralism. 1 Their main animals were

those that predominate among the nomads of Iran and Afghanistan sheep,

goats, horses, cattle and camels. The most important political unit was the

1 Thomas T. Allsen, 'Spiritual geography and political legitimacy in the eastern steppe', in

Henri J. M. Claessen and Jarich G. Oosten (eds.), Ideology and the formation of early states (Leiden, 1996), p. 118.

128

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

tribe, usually based on a combination of real and fictive kinship. Tribes arew

or shrank according to economic and military conditions; they could break up

into small units but could also develop into confederations or states. The region had been the centre of several steppe empires, most notably the Turkic

(Tii chiieh) empire which dominated the eastern steppes from 552 to 745 CE.

The Turkic state developed an imperial ideology, a written language and a set

of administrative institutions which survived long beyond its rule.

When leaders of the Mongolian plateau lost their positions, as the more ambitious often did, they took refuge within neighbouring tribes and states. In

the twelfth century northern China was ruled by the Jurchen Chin dynasty (1115

1234), which was closely involved in the politics of the Mongolian plateau. In the

Ordos and the Gansu corridor the Tangut or Hsi Hsia state (982 1227) ruled over

a multiethnic population. From the northern Tarim river basin to the northern

Tien Shan the major power was the Uighur kingdom which had preserved the

traditions of the Turkic empire in a partly sedentary state. In about 1130, the Uighurs became vassals of a new power, the Qara Khitay state founded by

the Khitan Liao dynasty, whose realm extended from the western Tarim river

basin to Transoxiana, where its rulers competed with the Khwarazm Shahs.

The strongest steppe powers were the Naiman in the Altai and the Kerait in

the upper Orkhon. Although probably largely Mongolian in language, both

were of Turkic origin and remained attached to Turkic political traditions.

The Naiman had adopted the Uighur script for their chancellery and financial

administration. Most of the ruling lineage was Buddhist, and Nestorian Christianity had also gained a following. The Kerait rulers were Nestorian

Christians and had developed a central court with elements of state organ

isation. Their ruling lineage had the advantage of controlling the Orkhon river

valley, the sacred centre of earlier steppe empires. In the eastern region tribes

were less organised. Among them were the Mongols, part of a loose coalition

centred in the region of the Onon and Kerulen rivers. Further east were the

Tatars; both tribes had lineages which claimed the title khan, but they were

often controlled by several competing leaders. 2

Temiijin the man who became Chinggis Khan was born into the Kiyan Borjigin section of the Mongol tribe, probably about 1167. In 1147 the Tatars

2 Paul Ratchnevsky, Genghis Khan, Ms life and legacy, trans, and ed. Thomas N. Haining

(Oxford, 1992), pp. 1 8; Isenbike Togan, Flexibility and limitation in steppe formations: Tfte

Kerait khanate and Chinggis Khan (Leiden, 1998), pp. 75 7, 117 18; Thomas T. Allsen, 'The

rise of the Mongolian empire and Mongolian rule in north China', in Herbert Franke and

Denis Twitchett (eds.), Cambridge history of China, vol. VI (Cambridge, 1994), pp. 323 6,

331 2; Allsen, 'Spiritual geography', pp. 124 6; Rashid al Din Hamadani, Jami' al tawdrikh,

ed. A. A. AH zade (Moscow, 1968 80), vol. I, pp. 249 51, 289.

129

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

had defeated the Mongols, and in Temiijin's youth his tribe was in disarray.

Temiijin's father Yesiigei was killed by Tatars when Temiijin was eight or nine years old and newly betrothed to his chief wife, Borte. The histories recount Temiijin's youth as a tale of hardship: a widow with her children abandoned by the tribe. This led the young man to a classic steppe solution,

gathering a band of personal followers from outside his own tribe. In the early

1180s he collected his bride, Borte, and attached himself to the leader of the

Keraits, To'oril best known by his Chinese title Ong Khan who had been an

ally of Temiijin's father and apparently enjoyed authority over part of the Mongol tribe. As a leader attempting to centralise and enlarge his confeder

ation, Ong Khan offered Temiichin an excellent opportunity for advance ment. 3 By the mid to late 1180s, Temiijin had become well known, and he was

chosen as the head of the Borjigin. He rewarded his personal followers with

offices, creating patriarchal positions cook, falconer, equerry which also involved wider duties. Temiijin's rapid advancement and Ong Khan's asser

tion of power aroused resentment, and soon both men disappeared from sight

for almost ten years. During this time Ong Khan was with the Qara Khitay to

the west, and Temijin may have been in China. 4

In 1195 6 Ong Khan regained his throne with Temiijin's help and for the next several years the two men collaborated to defeat their rivals, using an

unusual level of violence against their enemies. The Secret History of the Mongols, written for the Chinggisid dynasty, claims that in 1203 Ong Khan

pushed out his own son, making Temiijin his adopted son and heir apparent.

However, within a short time Temiijin was at war with Ong Khan, who was

killed by the Naiman while fleeing after a defeat. Instead of massacring the

Kerait, as he did other defeated tribes, Temiijin appropriated their prestige

and presented his victory as a legitimate succession to the rule of the Kerait

confederation. For a while he recognised Ong Khan's brother as co ruler and

formed marriage alliances with him; he took one daughter himself and chose

another, Sorqaqtani Beki, for his youngest son Tolui. His new administration

incorporated the Turkic institutions of the Kerait and Naiman. He reorganised

his army on the decimal system and created a central regiment, the keshig,

recruited from his personal followers. In a campaign lasting from May 1204

into 1205 he broke the power of the Naiman and Merkid and became master of

the Mongolian plateau. 5

- 3 Togan, Flexibility, pp. 68 76.
- 4 Ratchnevsky, Genghis, pp. 45 9; Allsen, 'Rise', p. 337.
- 5 Ratchnevsky, Genghis, pp. 52 88; Allsen, 'Rise', pp. 338 42.

## Cambridge Histories Online © Cambridge University Press, 201 1

## The Mongols and the Islamic world

In 1206 Temiijin convoked a quriltai a gathering of tribal leaders at the source of the Onon river. His followers raised his white standard bearing nine.

horse or yak tails, combining the colour and number associated with good

fortune. The Turkic concept of God given fortune attached to the ruler became a central part of Mongol imperial ideology. Temiijin now received the title Chinggis Khan. The term has been translated as 'Oceanic', but Igor de

Rachewiltz recently argued for the meaning 'fierce, hard, or tough' The new

khan had a scribe from the Naiman adapt the Uighur alphabet for Mongolian

and teach it to his sons. The keshig grew to 10,000 men; its members served as

chamberlains, supervisors of households and herds, and major military commanders. Another office was that of chief judge (yeke jarghuchi), with

two tasks: to oversee the apportionment of subject peoples and to preserve

Chinggis Khan's legislative pronouncements, known as jasaghs.

Chinggis Khan seems to have adopted the centralising policy of Ong Khan,

who had asserted the power of the dynasty over tribal leaders. 7 Most tribes

were divided among contingents commanded by personal followers. 8 Another tactic that Chinggis shared with Ong Khan was the increase in violence, particularly the massacre of defeated tribesmen, and the selective

use of extreme violence remained part of his strategy throughout his career.

Chinggis now moved rapidly towards expansion. In 1209 he conquered the

Tangut and from 1211 to 1215 mounted campaigns against north China and

Manchuria. By 1216, the Mongols had taken the Chin capital.

## Western conquests

Islamic Central Asia had long been connected to the eastern steppe. The Khwarazmian cities traded with China and Mongolia, and Temiijin had several Muslim merchants among his early followers. Soon after his enthrone

ment he encouraged his eldest son Jochi to campaign on the northern and

western frontiers. In 1207 8 two commanders, Jebe and Siibetei, pursued fugitives west and they apparently clashed with the Khwarazm Shah Sultan

Muhammad (r. 596 617/1200 2of.) in Semirechye in 1209 10. 9 Circumstances

6 Igor de Rachewiltz, 'The title Cinggis Qan/Qa'an re examined', in W. Heissig and Klaus

Sagaster (eds.), Gedanke und Wirkung: Festschrift zum go. Geburtstag von Nikolaus Poppe,

Asiatische Forschungen, 108 (Wiesbaden, 1989), pp. 281 8.

7 Togan, Flexibility, pp. 86, 90 1, 102 3.

8 Allsen, 'Rise', pp. 346 7.

9 Paul D. Buell, 'Early Mongol expansion in western Siberia and Turkistan (1207 1219): A reconstruction', Central Asiatic Journal, 36, 1 2 (1992), pp. 4 16.

131

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

The New Cambridge History of Islam

favoured the Mongol advance: the Qara Khitay had recently increased their

exactions on subject people, and had alienated several vassals. The Uighur

ruler sent gifts to Chinggis Khan in 1209, then arrived in person in 1211 and was

rewarded with high status. The Qarlug chiefs of the Hi valley likewise

submitted voluntarily. 10 Meanwhile the rulers of Samarqand and Bukhara

reacted to Qara Khitay pressure by inviting in the Khwarazm Shah.

In 1208, after Chinggis Khan defeated the Naiman, their prince Guchiilug took refuge at the Qara Khitay court, where he rose quickly and then allied

with Sultan Muhammad to seize power over the kingdom in 1211. Soon, however, he was attempting to expand into the regions of Kashghar and Kulja and threatening the Khwarazm Shah. The Khwarazmians and Mongols

now shared a common enemy and Sultan Muhammad sent an embassy and

trading caravan to Chinggis Khan. However, the Mongols' western advance

soon strained relations. In 1216 Chinggis Khan sent his senior commander Jebe

against Guchiilug, and by the end of 1218 the Qara Khitay realm was under

Mongol control. In the meantime Jochi moved west to put down an uprising

of the Siberian tribes. The Khwarazm Shah now faced the Mongols directly.

A Mongol embassy arrived in Transoxiana proposing trade relations, to which

Sultan Muhammad assented, but when the caravan reached Utrar the city

governor executed its merchants and seized their goods, probably with Sultan

Muhammad's encouragement. When Chinggis Khan sent an envoy to protest,

the Khwarazm Shah had him killed. This incident provided justification for

western conquest. Chinggis Khan left a force in northern China and enlarged

the western army with foot soldiers and cavalry from the Uighurs, Qarluq and

the ruler of Almaliq. In the summer of 1219 the army gathered on the Irtysh

river. Sultan Muhammad held a large realm, but he faced serious internal political problems. 11 He therefore retreated along with his major commanders

and left the defence of Transoxania, Khwarazm and Khurasan to its cities and

their garrison troops. 12

Even if the Khwarazm Shah had stood firm, it is not clear how he could have

organised a successful defence. As usual, Chinggis Khan divided his forces so

that Transoxiana suffered attack simultaneously by four separate armies. One

contingent was sent under Jochi to take Sighnaq, Uzkand and Jand. 13 A small

10 Thomas Allsen, 'The Yuan dynasty and the Uighurs of Turfan in the thirteenth century',

in Morris Rossabi (ed.), China among equals (Berkeley, 1983), pp. 246 7.

- 11 W. Barthold, Turkestan down to the Mongol invasion (London, 1968), pp. 374 80, 393 9.
- 12 'Ala' al Din 'Ata Malik Juwaym, The history of the world conqueror, trans. John A. Boyle, 2 vols. (Manchester, 1958), pp. 373 8.
- 13 Barthold, Turkestan, p. 415; Buell, 'Early Mongol expansion', p. 27.

132

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

army went against Banakath and Khujand, while Chinggis Khan's second and

third sons, Chaghadai and Ogedei, conquered Utrar, then joined the main army

with a levy of men from the city. Chinggis and his youngest son Tolui headed

against Bukhara, where they arrived in February 1220. After three days of

fighting most of the garrison fled. The next day the population opened the

city gates but since resistance continued in the citadel the Mongols attacked

it for twelve days, during which much of the city was destroyed by fire. Once the garrison was conquered, the Mongols massacred the surviving sol diers, destroyed the city walls and took a levy of men. They then marched against Samarqand, where the civilian section of the city surrendered after

four days.

The methodology of Mongol campaigns is well known. When cities sub mitted they were subjected to a tax and assigned a Mongol official. In most

recorded cases, the garrison troops resisted, often backed up by the population

for one or two days. The population was then taken out of the town, which

the army looted. The walls were destroyed, the garrison massacred, and the

Mongols conscripted military levies and craftsmen before allowing people to

return to the city. Craftsmen were immediately put to use, either in the army

or as skilled labour in Mongol workshops. 14 Not all of these actions were

new the massacre of soldiers after battle, permitted looting and the destruc

tion of fortifications were all familiar. It was in the systematic organisation of

conquered populations that the Mongols stood out, and in the ferocity with

which they punished recalcitrant cities. In such cases the population was divided up among the soldiers to be killed, with the exception of women and children to be enslaved, young men for levies, craftsmen and the religious

classes, who were spared. The historians report figures for the dead that far

exceed the actual city populations and illustrate the horrid fascination of Mongol actions.

After taking Samarqand Chinggis Khan again divided his army, sending a contingent against Khujand and Farghana and one to Wakhsh and Talagan.

Jebe, Siibetei and Chinggis Khan's son in law Taghachar pursued the Khwarazm Shah who abandoned Nishapur in spring 617/1220. Jebe and Siibetei headed west as Sultan Muhammad fled to an island in the Caspian,

where he died in the winter of 6i7/i22of The troops chasing the sultan were

reportedly ordered not to attack cities. There was nonetheless considerable

destruction, but it appears that the contingent overlooked minor acts of

14 Thomas T. Arisen, Commodity and exchange in the Mongol empire: A cultural history of

Islamic textiles (Cambridge, 1997), pp. 31 6.

133

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

aggression in the interest of efficient pursuit. 15 Taghachar remained in Khurasan and was killed putting down an uprising in NTshapur.

Considering the consequences of resistance, it is remarkable how many cities

opposed the Mongols. Rebellions are often attributed to the lower classes, but in

many cities members of the elite were also involved, and there was often internal disagreement. 1 It is probable that the extraordinary level of destruction

in Khwarazm and Khurasan was due to the resistance of their cities, based partly

on factionalism and partly on a miscalculation of Mongol strength. In both

provinces early Mongol armies were sometimes small enough for local forces to

defeat. The fact that Chinggis Khan could send out small contingents in different

directions is a testament to the exceptional loyalty of the Mongol army; the

defeat of one army did not threaten Chinggis Khan's control over his followers.

This sort of discipline was a phenomenon unknown in the recent experience of

Iranian cities. The Mongols moreover enlarged their army through local alliances and levies some levies rebelled, but others fought efficiently and participated enthusiastically in punitive massacres. 17

In 1220 Chinggis Khan remained north of the Oxus while Jebe and Siibetei

wintered in western Iran, and in their absence the people of Khurasan and

Khwarazm lost some of their fear of the invaders. Khwarazmian amirs retook

Yangikent from Jochi's governor, and Sultan Muhammad's sons Jalal al Din

Mangubirni and Uzlaq shah returned to Khwarazm. The most active centre of

unrest was Marv, whose leaders disagreed over Mongol rule. The anti Mongol

party attacked Sarakhs for accepting a Mongol governor, then, joined by some

Turkmens and other remnants of the Khwarazm Shah's army, they defeated

a small Mongol contingent. In triumph, they paraded their prisoners through the town. 1 At the end of winter 1221, Chinggis Khan attacked Balkh and at about the same time Jebe and Siibetei defeated the Georgians

in Transcaucasia, while Jochi, Chaghadai and Ogedei besieged Urganj. Tolui

was assigned the pacification of Khurasan. His first major goal was Marv, where he arrived in Muharram 618 /February 1221. He brought a Mongol

contingent significantly enlarged by levies from Khurasanian cities, including

15 Barthold, Turkestan, pp. 421 7; Juwaym, History, pp. 143 7, 383 6.

16 Jiirgen Paul, 'L'invasion mongole comme revelateur de la societe iranienne', in D. Aigle

(ed.), L'Iran face a la domination mongole, Biblioteque Iranienne 45, (Tehran, 1997),

pp. 46 9; I, P. Petrushevskii, 'Pokhod mongol'skikh voisk v Sredniuiu Aziiu v 1219

 $1224~\rm gg.~i$ ego posledstviia', in S. L. Tikhvinskii, (ed.), Tataro Mongoly v Azii i Evrope

(Moscow, 1970), p. 114.

17 Juwayni, History, pp. 162, 168, 178.

18 ibid., pp. 150 9.

134

# The Mongols and the Islamic world

Sarakhs, and he took Marv in eight days. He then attacked NTshapur, which

suffered a massacre in revenge for the death of his brother in law Taghachar.

The new offensive did not extinguish opposition. The Khwarazm Shah's son Jalal al Din Mangubirni, who had regrouped near Ghazna, succeeded in

defeating a small Mongol force. Chinggis sent an army under his chief judge,

Shigi Qutuqu, but once again Jalal al Din was victorious, and his success ignited a number of insurrections in Khurasan. Together with Chaghadai, Ogedei and Tolui, Chinggis defeated Jalal al Dm after a fierce battle near the

Indus in autumn 618/1221. According to Persian histories, Jalal al Dm fought

bravely and then plunged into the river, watched by the admiring Mongols;

this event became a favourite subject for Persian miniatures. Jalal al Dm spent

the next three years south of the Indus and some leaders in Khurasan continued to trust in his future. Several months after Tolui took Herat in the spring of 618/1221 local people rebelled and killed the city's Mongol official. Chinggis sent out his commander Eljigidei, who took Herat after a

siege of six months and ordered a general massacre. Marv and Sarakhs also

rose against the Mongols, and the movement spread to other cities, notably

Nisa. The Mongols probably did not restore control until late summer 619/1222. 19 At the end of 1222 Chinggis Khan moved to Transoxania and in

early 1223 the main army departed for the east.

#### The successors of Chinggis Khan

Chinggis Khan died in August 1227, leaving an empire in the process of formation. He had made several grants of land and troops to relatives during

his life perhaps designed to placate people unhappy with the growth of central power but it is not clear what provisions he had made for the future

of his empire. 20 The sources which describe his division of territory, troops

and responsibility were all written considerably later and show signs of distortion. 21 As things turned out, Chinggis Khan's sons Jochi, Chaghadai,

Ogedei and Tolui, borne by his principal wife Borte, became the progenitors

of the four recognised branches of the dynasty. The larger part of the empire

19 ibid., pp. 164 8; Barthold, Turkestan, p. 448.

20 Men da Bel hi ('Polnoe opisanie Mongolo Tatar'), ed. and trans. N. Ts. Munkuev

(Moscow, 1975), pp. 55 9; Peter Jackson, 'From ulus to khanate: The making of the

Mongol states e. 1220 c. 1290', in Reuven Amitai Preiss and David O. Morgan (eds.), The

Mongol empire and its legacy (Leiden, 1999), pp. 15 20.

21 Peter Jackson, 'The dissolution of the Mongol empire', Central Asiatic Journal, 22 (1978),

pp. 188 91; Dorothea Krawulsky, Mongolen und Ilkhane Ideologic und Geschichte: 5

Studien (Beirut, 1989), pp. 65 85.

135

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

and its army fell to their descendants and although borders were frequently

disputed, the central territories are clearly described. They are designated by

the term ulus, signifying both land and its population. The north west, including the Russian steppes, was the ulus of Jochi; since he died before his

father, this region went to his sons. The Altai was Ogedei's ulus, the Semirechye and Turkistan went to Chaghadai, while as the youngest Tolui

kept the heartland of Mongolia and became regent on his father's death.

Chinggis's third son, Ogedei, was enthroned as supreme khan qaghan by the Mongol princes at a quriltai near the Kerulen river in autumn 1229.

Expansion was one of Ogedei's first concerns and an important tool in asserting power. In 1230 he sent a commander to retake Khurasan and western

Iran; this campaign will be described later. He sent an army to the Russian

steppes, an expedition which reached into Hungary and was ended by his death in 1241. These lands became part of Jochi's ulus. In the east Ogedei

mounted campaigns against Korea and northern China, where the Mongols

overthrew the Chin dynasty in 1234. The Mongols were well aware of the importance of their settled territories. Chinggis Khan had appointed gover

nors known as darughas in many cities and had created administrations in

northern China and Transoxiana. Ogedei transformed these into jointly owned branch secretariats under civilian governors, a system later extended

into Iran. Turkistan was put under the Khwarazmian Mahmud Yalavach and

northern China under the Khitan Yeh lii Ch'u ts'ai.

Centralisation was a priority for the new qaghan, but, like his father, he

to placate his relatives. The qaghan's officials in the branch secretariats were

accompanied by representatives of the Jochid, Chaghadayid and Toluid houses. In this way the qaghan maintained his claim on the settled territories

while acknowledging the interests of family members. In the armies sent on

major campaigns, the lines of the four brothers were likewise represented.

These troops were known as tamma, and since some remained as garrison

troops, each area of the empire had armies representing the four dynastic

branches. Mongol princes and princesses furthermore had holdings outside

their own ulus. Many held appanages lands whose income was to go to an

individual and retained rights to income from cities and artisans granted during conquest, usually managed by their own agents.

Ogedei attempted to increase government revenues without further damag

ing the population, who were suffering from dues levied by innumerable people

connected to the government or to the Mongol elite. In China Yeh lii Ch'u Ts'ai

abolished most irregular dues and from 1230 to 1235 introduced a tax on adults

and on households. Additional income came from government monopolies on

136

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

salt, liquor, vinegar and yeast. There was a tax on trade, the tamgha, while

Mongols and other nomads were taxed at a rate of one animal per hundred. 22 In

1234 6, the Mongols carried out a census in north China and began the military

recruitment of Chinese. There were censuses in Mazandaran, Khurasan and

Sistan in 1239 42. 23 The qaghan reorganised the official post a system of

stopping places and horses for official business throughout the empire and

in 1235 began the construction of the capital city Qaraqorum in Mongolia. 24

Towards the end of his life, Ogedei was incapacitated by alcoholism, and power went to his wife, Toregene Khatun, who became regent on his death in

December 1241. During her long regency princes and amirs expanded their

power in the settled regions at the expense of the government and the population. By this time rifts had opened within the dynasty and indeed it is

possible that Tolui's death in 1232 was at Ogedei's command. 25 Relations

between the Ogedeyid and Jochid houses were particularly strained, since

Giiyiig the son of Ogedei and Toregene had quarrelled bitterly withjochi's

son and successor Batu on the western campaign. In 1246 Toregene nonethe

less managed to arrange Giiyiig's enthronement as qaghan. Like his father,

Giiyiig began his reign with measures to increase central control, sending

armies against China, the Tangut regions and the Middle East. He cancelled all

orders and grants given since his father's death and ordered new censuses in

China and the Middle Eastern territories. 26 Giiyiig however died in the summer of 1248, possibly on his way to confront Batu. Once more the empire

was ruled by a regent, Giiyiig's widow Oghul Qaimish. In the twenty four years between Chinggis Khan's death and Mongke Khan's enthronement in

1251, the Mongol empire was without a ruler for ten years, enough to undo

much of the systematisation achieved by the qaghans.

22 Thomas Allsen, Mongol imperialism: The policies of the Grand Qan Mongke in China, Russia

and the Islamic lands, 1251 izyg (Berkeley, 1987), pp. 159 62, 169; Igor de Rachewiltz,

'Yeh lii Ch'u Ts'ai (1189 1243); Yeh lii Chu (1221 1285)', in Igor de Rachewiltz, Hok lam

Chan, Hsiao Ch'i ch'ing and Peter W. Geier, (eds.), In the service of the khan: Eminent

personalities of the early Mongol Yuan period (Wiesbaden, 1993), pp. 150 1.

23 Ann K. S. Lambton, Continuity and change in medieval Persia: Aspects of administrative,

economic and social history, nth 14th century, Columbia Lectures on Iranian Studies,

2 (Albany, NY, 1988), p. 201.

24 David O. Morgan, 'Reflections on Mongol communications in the Ilkhanate', in Carole

Hillenbrand (ed.), Studies in honour of Clifford Edmund Bosworth, vol. II: The Sultan's

turret: Studies in Persian and Turkish culture (Leiden, 2000), pp. 376 9.

25 Joseph Fletcher, 'The Mongols: Ecological and social perspectives', Harvard Journal of Asiatic Studies, 46 (1986), p. 36.

26 Ho dong Kim, 'A reappraisal of Giiyiig Khan', in Reuven Amitai and Michal Biran

(eds.), Mongols, Turks, and others: Eurasian nomads and tfte sedentary world (Leiden, 2005),

pp. 327 9; Allsen, 'Rise', p. 387.

137

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

The Islamic lands in the early Mongol empire

Until 1259, the Mongol territories of the Middle East were part of an empire

ruled from Mongolia. At this period, Transoxania was the only province directly under Mongol control and it fared better than other Islamic lands.

In the region of Samarqand and Bukhara, Chinggis Khan appointed the Khitan

Yeh lii A hai, referred to in Persian sources by his title, T'ai shih, as darugha.

Yeh lii began reconstruction, importing Chinese, Khitan and Tangut agricul

turalists to offset depopulation; the Chinese Taoist Ch'ang ch'un, who visited

Samarqand in 1221, stated that its population had been reduced to one fourth.

On Yeh lii A hai's death, c. 1223, his position went to his son, Yeh lii Mien ssu ko, who held it until about 1239. 27 Transoxania was joined with the other

regions of the Silk Road and in 1229 Ogedei appointed Mahmud Yalavach to be

in charge of the regional administration. Mahmud repaired irrigation systems

and implemented a tax reform, probably the model for that of Yeh lii Ch'u ts'ai in China, with a poll tax on adult males called qubchur and a land

tax called qalan. Other taxes were abolished, at least in theory. Mahmud had to

contend with attempts by Chaghadai, whose territory adjoined Transoxania,

to assert authority. In 636/1238<sup> the rebellion of Mahmud Tarabi in Bukhara</sup>

brought a punitive assault, but Mahmud was able to prevent a massacre by an

appeal to Ogedei. Perhaps to placate Chaghadai, Ogedei moved Mahmud to

China and replaced him by his son Mas c ud, with no change in policy. Contemporary observers and numismatic evidence suggest that by 1260 Central Asia had nearly regained its earlier prosperity. 2

The situation was very different in Iran, where Chinggis Khan made no attempt to install systematic administration. 29 Some eastern cities had Mongol

officials but most simply remained under earlier rulers: the atabegs of Fars in

southern Iran, the Khwarazm Shah's son Ghiyath al Din in Rayy, and in Azerbaijan, the Saljuqid atabegs. Kirman was seized in 6i9/i22if. by Baraq

Hajib, a former servitor of the Khwarazm Shahs, who gave allegiance to the

Mongols and founded the Qutluq Khanid dynasty. Most rulers offered sub mission to the qaghan and many travelled to the central court. Describing

27 Paul D. Buell, 'Sino Khitan administration in Mongol Bukhara', Journal of Asian History,

13, 2 (1979), pp. 122 5, 134 41; and Buell, 'Yeh lii A hai (ca. 1151 ca. 1223); Yeh lii T'u hua

(d. 1231)', in de Rachewiltz et al. (eds.), In the service, pp. 118 19.

28 Buell, 'Administration', pp. 139 47; Thomas Allsen, 'Mahmud Yalavac (? 1254); Mas'ud

Beg (? 1289); 'AH Beg (? 1280); Buir (/!. 1206 1260)', in de Rachewiltz et al. (eds.), In the service, pp. 122 7.

29 Paul D. Buell, 'Tribe, "Qan" and "ulus" in early Mongol China: Some prolegomena to

Yuan history', Ph.D. thesis, University of Washington (1977), p. 154.

138

## The Mongols and the Islamic world

Giiyiig's enthronement in 1247, Juwayni mentions rulers or their relatives from Anatolia, Georgia, Mosul and Aleppo, along with envoys from Fars, Kirman, the caliph in Baghdad and the Isma'ilis of Alamut. 3 ° The exception

was the Khwarazm Shah's sonjalal al Dm. After Chinggis Khan's departure he

left India, defeated his brother Ghiyath al Din in central Iran and set out against the caliph and the atabeg of Azerbaijan. He took Tabriz in 622/1225

and then attacked the Georgians and campaigned towards Kirman. The pillage

he allowed his army soon turned rulers and populations against him, and he

headed east to fight the Mongol forces of Khurasan.

In the summer of 627/1230 Ogedei sent an army under the commander Chormaghun to assert Mongol control over Iran. Jalal al Din retreated and was

subsequently killedby Kurds in Shawwal 628/August 1231. Chormaghun's army

subdued most of northern and central Iran including the Mughan plain, from

this time on the Mongols' regular winter pasture. The Georgians and the Armenians became faithful allies. When Chormaghun became incapacitated,

his second in command, Baiju, took over and extended Mongol power into

northern Syria and Anatolia. On 6 Muharram 641/26 June 1243, Baiju defeated

the armies of the Saljuqid sultan of Rum, Kaykhusraw II (r. 1237 46), at the battle

of Kose Dagh. Kaykhusraw retained the throne as a vassal but many of the

important posts in Anatolia went to Mongol amirs.

The allocation of command within Iran is not entirely clear. Although Chormaghun was given overall authority, he was active primarily in the west and appointed Chin Temiir, governor of Khwarazm for Jochi's son Batu, over Khurasan and Mazandaran, along with representatives from the

qaghan and the other Chinggisid houses. Chin Temiir's authority probably

covered only north western Khurasan, since Ogedei sent a separate army to

the southern region stretching from Badhghis to the Indian borderlands. 31

Mongol officials soon began to fight among themselves and to ally with competing Iranian rulers. There was no one cause for Mongol rivalries; the

presence of agents from all four uluses contributed, but regional and personal

tensions were also important. Chin Temiir came into conflict with Dayir,

commander of the southern army stationed in Badhghis. Ogedei had ordered

Dayir to pacify Nishapur, and Dayir used the directive to claim control of Khurasan with Chormaghun's backing. Chin Temiir countered by sending two regional rulers (maliks) to Ogedei's court, thus winning both imperial

30 Juwayni, History, p. 250.

31 Ibid., p. 487; Juwayni, Tdrikh i jahan gushd, ed. Mirza Muhammad Qazwini, Gibb Memorial Series XVI (Leiden, 1912 37), vol. II, p. 223; Jean Aubin, 'L'ethnogenese des Qaraunas', Turcica, 1 (1969), p. 70.

139

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

favour and local allies. His proteges received patents for their regions and

Ogedei confirmed Chin Temiir as governor of Khurasan, independent of Chormaghun. The vizier Baha' al Dm Juwayni, father of the historian 'Ata Malik, joined Chin Temiir as sahib dlwan. Dayir however remained strong in

the south along with another amir, Qara Noyan, in alliance with Rukn al Din

Marghani who held the fortress of Khaysar in Ghuristan. 32 On Chin Temiir's

death in 633/1235^ Ogedei appointed Batu's agent Nosal as governor but

Chin Temiir's ambitious chamberlain, Korgiiz, gained actual power and succeeded Nosal on his death in i239f A rival party developed around the

candidacy of Chin Temiir's son Edigii Temiir. This split combined with tensions among the maliks of Khurasan and Mazandaran and divided both

Mongols and Persians into rival camps. Ogedei sent his official Arghun Aqa to

investigate and summoned the combatants to Qaraqorum, where the Mongol

commanders and officials noyans took different sides in the dispute. Korgiiz

maintained his position and was appointed to take over from Chormaghun in

the west, but his authority was undermined by the influence of Arghun Aqa,

allied with Edigii Temiir's party.

Herat, which lay within the sphere of the southern commanders, was also affected by regional and dynastic rivalries. Ogedei entrusted its reconstruction to

the former head of the city weavers, 'Izz al Din, who arrived back in 635/i237f

He, and his son after him, worked in collaboration with a Mongol governor

appointed by Qara Noyan of the southern army. However, their power was

challenged by another Iranian, who appealed for help to Batu and Korgiiz, both

happy to use local rivalries to their own advantage. Batu's candidate took power

and showed consistent favour to the agents of Batu and Korgiiz, but after some

years he was murdered perhaps with the help of Arghun Aqa. In 643/i245f the

governorship of Herat went to the protege of Dayir and Qara Noyan, the Ghiirid Malik Shams al Din Kart, founder of the Kartid dynasty. 33

32 Juwayni, History, pp. 485 7; Sayf b. Muhammad b. Ya'qub al Harawi Sayfi, Tdrikh ndma i

Harat, ed. Muhammad Zubayr al Siddiqi (Calcutta, 1944), p. 151; Rashld al Din

Hamadam, trans. J. A. Boyle, The successors of Genghis Khan (New York, 1971), pp. 51 3;

Jean Aubin, Emirs mongols et vizirs persans dans les remous de V 'acculturation, Cahiers de

Stadia Iranica (Paris, 1995), p. 14.

33 Mu'in al Dm Zamchi Isfizan, Rawdat aljannat fi awsaf madinat Harat, ed. Sayyid

Muhammad Kazim Imam (Tehran, AH solar 1338), vol. II, pp. 107 21; Sayfi, Tdrikh

ndma, pp. 117 40; Lawrence G. Potter, 'The Kart dynasty of Herat: Religion and politics

in medieval Iran', Ph.D. thesis, Columbia University, 1992, p. 41; George Lane, Early

Mongol rule in thirteenth century Iran (London, 2003), pp. 154 8; Ahmad b. Jalal al Din

Fasih Khwafi, Mujmal i fasthi, ed. Muhammad Farrukh (Mashhad, solar 1339), vol. II, P- 314-

140

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

Shortly after Ogedei's death Korgiiz was killed by the Chaghadayids, whom

he had insulted, and Arghun Aqa took his place. Coming into office during the

interregnum, Arghun faced major difficulties but through energy, competence and frequent visits to the central court he maintained this position. 34

After Ogedei's death Batu increased his influence, particularly over western

Iran and Anatolia, and it was from his court that the official patent for Kaykhusraw arrived. During his brief reign in 1246 8, Giiyiig attempted to

assert authority, sending Arghun Aqa west to take over Georgia, but shortly

after Mongke took power in 1251 Baiju regained command. Arghun Aqa retained overall authority but had difficulty asserting his power over Baiju

in the west. 35

The restoration of agriculture in Khurasan began during Ogedei's reign. In 1239 40 Korgiiz began to restore buildings and agriculture in the region of

Tus and Radkan where he centred his administration. Arghun Aqa continued

the development of Tus and also restored Mary. However, the constant

infighting hampered progress. The qaghan controlled conflicts by summoning

those involved to the central court (yarghu). While officials and rulers were

away, their rivals often gained ground, but if they returned with a decision in

their favour, the situation was abruptly reversed. Confusion increased during

the interregnums as the princes sent their agents to demand taxes without

regard to legality. Under these conditions, orderly administration was impos

sible to maintain.

#### Mongke and the Toluid coup

The reign of Mongke marked at once the apogee and the end of unified Mongol

rule. Mongke was a man of great intelligence and will who expanded the empire

beyond earlier borders while mobilising its resources to an extent that was

extraordinary for the medieval period. However, he did not ease tensions within the dynasty. Mongke came to the throne through a coup against the

line of Ogedei. During Toregene's regency Batu had allied with Tolui's widow

Sorqaqtani Beki, the niece of the Kerait Ong Khan, a powerful woman and a

bitter enemy of Toregene. After Giiyiig's death Sorqaqtani collaborated with

Batu to arrange the election of her son Mongke at a quriltai west of Mongolia

attended primarily by Jochid and Toluid princes. The choice was confirmed in

34 George Lane, 'Arghun Aqa: Mongol bureaucrat', Iranian Studies, 32, 4 (1999), pp. 459 82;

EIr Arghun Aga' (Peter Jackson).

35 Juwayni, History, pp. 507 9.

# Cambridge Histories Online © Cambridge University Press, 201 1

#### The New Cambridge History of Islam

another quriltai in summer 1251. Shortly after his accession Mongke discovered

an assassination plot by Ogedeyid and Chaghadayid princes, and opened his

reign with a series of trials of men and women who had opposed his election.

Rulers from settled territories who had taken the wrong side suffered appro

priately. The Ogedeyid and Chaghadayid lines both endured numerous execu

tions and from this time on power lay with the Toluids and Jochids.

Mongke undertook a series of reforms to rationalise taxes and mobilise resources for the central government. In Iran the poll tax became a progres

sive one, from 7 dinars for wealthy men to 1 dinar for the poor; it was revised in

 $654\ 6/1256\ 8$ , when rates were reduced for the people of moderate means and

increased for the rich. The tax continued to be resented, in part due to its similarity to the jizya tax for non Muslims. We should remember also that it

fell most heavily on the wealthy class, which included the historians on whom

we rely. 36 In 1252 Mongke organised a new census, covering many areas not

counted before. Registration began in China in 1252; the next year marked its

beginning in Iran, and 1254 in the Caucasus. In the Golden Horde, where little

had previously been done, the census lasted from 1254 to 1259. It seems likely

that Mongke's reign also brought new taxes along with monopolies a Chinese practice in West Asia. The Armenian historian Kirakos mentions the tamgha tax on trade and taxes on fishermen, miners and craftsmen as a

recent hardship; he also relates the seizure of the salt mines of Transcaucasia. 37

The population was further liable for corvee duties, onerous for Mongols and

settled subjects alike. One purpose of the census was the mobilisation of troops. The population was divided into decimal units from 10 to 10,000, of

which some served as soldiers and others provided for the army's needs. The

system is best known in China, where auxiliary formations served also as territorial administrative units. In the Middle East, these armies were known

as cherig and contained both cavalry and footmen, conscripted from all seg

ments of the population.

In 1252 Mongke organised military expeditions under the leadership of his

younger brothers, sending Qubilai against China and Hiilegii to the Middle

East. From this time Qubilai was based in north China, though the regional

secretariat remained in existence under Mahmud Yalavach. It is clear that

Mongke allowed Qubilai only limited independence, and there was frequent

friction over his authority. In 1256 when Mongke attacked the Song dynasty of

southern China, he led the campaign in person.

36 Allsen, Mongol imperialism, pp. 166 7. 2,7 Ibid., pp. 116 43, 161 3.

142

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

The Mongols and the Islamic world

Hiilegii and the founding of the Ilkhanid dynasty

For Mongke the existing state of balanced conflict in Iran was no longer acceptable. Hiilegii was ordered to subjugate three powers seen as trouble

some: the tribes of Luristan, the Isma'ilis in Quhistan, the Caspian region and

Syria, and the caliph. These powers had previously reached an accommoda

tion with the Mongols but relations had since soured. 38 Advance forces prepared the route from western Mongolia to Azerbaijan and informed populations along the path of the supplies they must provide. The experienced

commander Ked Buqa served as advance guard. 39 He crossed the Oxus in

651/1253, and campaigned in Quhistan, Rayy and the region of Alamut before

Hiilegii arrived at Samarqand in 653/1255. By this time it was clear that the

region was to become more fully integrated into the empire, and local rulers

were ordered to provide supplies and to accompany the army. It is not surprising that some people who had previously shown obedience should balk at new conditions. Since the Isma'ili grand master Rukn al Dm Khurshah

of the Maymun Diz fortress near Qazvin was unwilling to meet Hiilegii's terms, the army took the fortress on 29 Shawwal 654 / 19 November 1256. They

destroyed many other fortresses including the centre at Alamut, from which

astronomical instruments and part of the famous library were saved. The astronomer Nasir al Din Tusi, who had been in the service of the Isma'ilis,

joined Hiilegii's camp.

For the assault on Baghdad Hiilegii called in Mongol armies under Baiju and Jochid commanders. The caliph refused Mongol conditions, so the armies

converged on the city along with local forces including Armenians, Georgians

and the atabegs of Shiraz and Mosul. The assault began on 22 Muharram 656/29 January, 1258 and the caliph surrendered on 4 Safar/10 February. Although the inhabitants laid down their arms they were systematically slaughtered and the city was sacked for seven days; the scene echoed the massacres of the first Mongol conquest, apparently at Mongke's orders. On 14

Safar/20 February the caliph was killed, probably by being rolled in a carpet

and kicked, a sign of respect since it avoided the shedding of blood.

In the autumn of 656/1258 Hiilegii invaded Syria, accompanied by the Saljuq sultans of Rum, the ruler of Mosul, King Het'um of Armenia, and Hefum's son in law, Bohemond VI of Antioch. Ked Buqa went ahead as

38 Juwaym, History, pp. 250, 256; Timothy May, 'A Mongol Isma'ili alliance?: Thoughts on

the Mongols and Assassins', Journal of the Royal Asiatic Society, ser. 3, 14, 3 (2004), pp. 231 9.

39 Juwaym, History, pp. 608 10.

143

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

advance guard. The subjugation of Syria appeared to pose little challenge,

since the Ayyubid dynasty was in disarray and most of its princes had declared

submission. In Egypt the Mamluks had not yet consolidated power and were

continually threatened by the remaining Ayyubid rulers of Syria, most notably

al Nasir Yusuf in Damascus. Aleppo capitulated after a week; the citadel surrendered about a month later, on n Rabi' I 658/25 February 1260, and the city was subjected to pillage and massacre. Hama, Horns and Damascus

submitted without a struggle. By the beginning of summer the army had reached Gaza, where Hiilegii learned of the struggle over succession to Mongke and turned back, leaving behind a small army under Ked Buqa. 4 °

For some time the campaign continued smoothly. However, the situation in Egypt had changed with the accession of the Mamluk Qutuz in late 657/1259. He came to power on an anti Mongol platform and attracted a number of important amirs, including the gifted Baybars. They gathered a

force significantly larger than that of Ked Buqa and when the armies joined

battle at 'Ayn Jalut on 3 September 1260, Ked Buqa was killed and the Mongols

fled. 41 Qutuz proceeded north to restore local rule in Damascus and Aleppo.

The battle at 'Ayn Jalut was not the first defeat of Mongol forces, though it was

an exceptionally severe one. What gave it lasting importance was lack of Mongol resolve. The Mongols undertook another campaign later that year but

after a defeat near Horns in 658/1260 they evacuated much of Syria. Most

importantly the Mamluk victories provided instant prestige to their nascent

state. In 660/1261 the new sultan Baybars welcomed a fugitive Abbasid, thus

acquiring a shadow caliph, and from this time on the Mamluks presented their

rule as a bulwark of Islam against the infidels.

# The founding of the Ilkhanate

Mongke's death on 12 August 1259 led to the establishment of independent

Mongol states in Iran and China. During his reign the increase in revenue from

agriculture and trade had changed the balance of power between the steppe

and settled regions, making central power more difficult to maintain. The struggle that developed between his brothers Ariq Boke, based in Mongolia,

and Qubilai in north China, offered Hiilegii a valuable opportunity. Although

Qubilai had himself enthroned as khan, Hiilegii was the only important ruler

 $40\ Reuven$  Amitai Preiss, Mongols and Mamluks: The Mamluk Ilkhdnid war,  $1260\ 1281$ 

(Cambridge, 1995), pp. 16 28; R. Stephen Humphreys, From Saladin to the Mongols:

The Ayyubids of Damascus, 1193 1260 (Albany, NY, 1977), pp. 330 63.

41 Amitai Preiss, Mongols, pp. 39 45.

144

Cambridge Histories Online © Cambridge University Press, 201 1

# The Mongols and the Islamic world

to recognise him. He was rewarded in 1262 when Qubilai's envoys invested

him with the title ilkhan and official power over the Mongol Middle East. The

Ilkhanate became a separate state, though not equal in prestige to the Golden

Horde, Mongol China or the Chaghadayid khanate. Formal recognition by Qubilai and his successors remained a source of legitimation up to the four

teenth century and the two khanates maintained close relations. 42 There is

continuing controversy over whether Hiilegii's assumption of power accorded with Mongke's intentions, as the historians of Iran and China assert,

or was a coup contravening the testament of Chinggis Khan, as the khans of

the Golden Horde contended. 43 It is possible that the truth is in between, and

that Hiilegii was given a position of limited independence similar to that of

Qubilai in China. During his campaign the joint regional secretariat continued

under Arghun Aqa, but the foundation of an observatory at Maragha suggests

the intention to remain. 44

Hostilities between Hiilegii and the Jochids broke out in 1261 2 over control

of north western Iran, claimed by both khanates. Berke, who had succeeded

Batu in the Golden Horde, began to advance through the Caucasus probably in

660/late 1261; in 661 2/1262, the Ilkhanids repulsed his army, though in attempt

ing to chase Berke they were defeated. 45 Berke had converted to Islam and he

now initiated an alliance with the Mamluks. The Mongols had for some time

been in contact with the pope and European rulers, and Hiilegii sent a mission

in 660/1262 to King Louis IX of France, proposing joint action against the Mamluks. 46 These two opposing alliances lasted through much of the Ilkhanid period. Hiilegii also had to cope with two attempts at independence.

One was from the new Zangid atabeg in Mosul, who allied with the Mamluks.

Ilkhanid troops took the city in 660/1262 and put an end to the dynasty. In Fars,

the death of the atabeg Abu Bakr in 658/1260 brought a succession struggle and

attacks on Mongol functionaries. Hiilegii installed Abu Bakr s young grand

daughter Abish and arranged for her marriage to his son Mongke Temiir.

42 Thomas T. Allsen, 'Changing forms of legitimation in Mongol Iran', in Gary Seaman

and Daniel Marks (eds.), Rulers from the steppe: State formation and the Eurasian periphery,

Ethnographic Monograph Series, 2 (Los Angeles, 1991), pp. 226-32; Allsen, 'Notes on

Chinese titles in Mongol Iran', Mongolian Studies, 14 (1991), pp. 27 39.

43 Jackson, 'Dissolution', pp. 208 27; Aubin, Emirs, pp. 17 19; Allsen, Mongol imperialism, pp. 46 51.

44 Juwayni, History, p. 519.

45 For variant analyses and chronology see J. A. Boyle, 'Dynastic and political history of the

II Khans', in Cambridge history of Iran, vol. V (Cambridge, 1968), p. 353; Lane, Early

Mongol, pp. 75 6; Jackson, 'Dissolution', pp. 233 4.

46 Jean Richard, 'D'Aljigidai a Gazan: La continuite d'une politique franque chez les

Mongols d'Iran', in Aigle (ed.), L'Iran, pp. 62 3.

145

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

The early Ilkhanid dynasty

Hiilegii died on 19 Rabi 1 II 663/8 February 1265. The realm he left his successors

was potentially rich but appallingly difficult to rule. Several decades of conflict

had left the region riddled with local rivalries. Many personnel from outside

Chinggisid uluses remained in Iran, and members of the other Chinggisid branches still had possessions within Ilkhanid domains. 47 The early Mongol

commanders Korgiiz, Chormaghun, Baiju and Arghun Aqa left behind offspring with inherited land, alliances and expectations of continuing power.

Mongol noyans were personally involved in administration alongside Persian

bureaucrats who were their allies or clients. 4 The role of Mongol dynastic

women added yet another complication. Royal women had their own entour

age (ordo), including armed retainers, and they had independent sources of

income in taxes, trade and workshops. In the early Ilkhanate, two of Hiilegii's

widows, Khutuy Khatun and Oljei Khatun, held very considerable political power. 49 Since so many of the elite had rights to local income, it was almost

impossible for the central government to collect the money it needed. The

inclusion of both women and noyans in state deliberations was formalised in the

accession ceremonies for new rulers. 50 In addition many local rulers were

closely involved in Mongol politics, and were familiar with Mongolian culture

and language. 51 The most powerful were the Kartids in Herat (1245 1381), the

Qutluq Khanid dynasty of Kirman (1222 1305/6) and the Salghurids of Fars

(1148 1280). The dynasties of Fars and Kirman both married princesses to the

dynasty. 52

Because so many different groups were politically active, conflicts within any one sphere pulled in people from other ones. Struggles within subordinate

dynasties, within the dlwan and, most importantly, issues of succession pro

duced factions which included local rulers, bureaucrats, amirs and members

of the dynasty. The transfer of loyalty from one ruler to the next was complicated by the institution of the keshig, which survived in Iran and

47 Thomas T. Allsen, Culture and conquest in Mongol Eurasia (Cambridge, 2001), pp. 46 9.

48 David O. Morgan, 'Mongol or Persian: The government of Ilkhanid Iran', Harvard

Middle Eastern and Islamic Review, 3, 2 (1996), pp. 62 76; Judith Pfeiffer, 'Conversion to

Islam among the Ilkhans in Muslim narrative traditions: The case of Ahmad Tegiider',

Ph.D. dissertation, University of Chicago (2003), pp. 226 7.

49 Pfeiffer, 'Conversion', pp. 224 5.

50 Rashid al Din Hamadam, Jami' al tawarikh: Compendium of chronicles: A history of the

Mongols, trans. Wheeler Thackston, Sources of Oriental Languages and Literatures,

Harvard University (Cambridge, MA, 1998 9), pp. 519, 548 9, 562 3, 580.

51 Aubin, Emirs, pp. 25 6.

52 Lane, Early Mongol, pp. 96 175.

146

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

combined a concept of service and loyalty to the individual ruler with the expectation of inheriting office. 53

Hiilegii was succeeded by his son Abaqa (r. 1265 82), apparently chosen without opposition. He was enthroned on 3 Ramadan 663/19 June 1265 and

within a month had sent an army to counter an invasion from the Golden Horde. His troops were successful, in part probably due to the death of Berke Khan. At about this time the Mamluks began a series of raids on Armenia,

which lasted several years. In 665 / 1266 Abaqa opened relations with European

kings to arrange joint campaigns against the Mamluks, but the Ilkhans offered

their Armenian allies essentially no protection, even allowing Antioch to be

taken in 666/1268. 54 The major reason for Mongol inaction in the west was the

Chaghadayid threat in the east. Baraq Khan (r. 1266 71) claimed that the region

from Badhghls to Ghazna belonged to the Chaghadayids. He pillaged from

Badakhshan to Nishapur and ordered the ruler of Herat, Malik Shams al Dm

Kart, to put the resources of the city at his disposal. Malik Shams al Dm took

refuge in the fortress of Khaysar while Abaqa led his army east and achieved a

decisive victory over Baraq's forces near Herat in 668/1270. 55 The eastern

Ilkhanate nonetheless remained insecure in part because of the Qara'unas, a

group originating from the Mongol tamma troops in the region from Badhqhis

to the borders of India. These troops had remained largely intact and con stituted a significant force. One contingent had become the personal property

(injii) of Hiilegii and had moved west, but most remained in the eastern borderlands and gradually came under Chaghadayid control. The section previously attached to the Jochid prince Negiider, known as the Negiideri,

were particularly active and constituted a constant danger to the southern

regions of Iran. 56

The greatest threat in the west came in 675/1277, when the Mamluk sultan

Baybars took over Kayseri, the capital of the Rum sultanate, and began minting coins in his own name. Baybars had support from several local officials, including the powerful Parwana Mu'in al Din Suleyman, who had

risen to prominence through the favour of Baiju. Baybars retreated to Syria as

Abaqa approached with his army. Abaqa viewed the battlefield where his forces had been defeated and punished those judged responsible; the Parwana

53 Charles Melville, 'The keshig in Iran: The survival of the royal Mongol household', in

Linda Komaroff (ed.), Beyond the legacy of Genghis Khan (Leiden, 2006), pp. 136 41, 145 50.

54 Amitai Preiss, Mongols, pp. 94 138.

55 Michal Biran, 'The battle of Herat (1270): A case of inter Mongol warfare', in Nicola Di

Cosmo (ed.), Warfare in Inner Asian history (500 1800) (Leiden, 2002), p. 190.

56 Aubin, 'L'ethnogenese', pp. 65 94.

147

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

he took back with him and executed. 57 In 680/1281 Abaqa sent an army into

Syria which was defeated by the Mamluks near Horns on 30 October; he planned to invade again, but died of delirium tremens on 20 Dhu' 1 Hijja 680/1

April 1282. In general his reign, one of the longest in the Ilkhanate, was a time

of peace and recovery.

Abaqa's brother and successor Tegiider Ahmad reigned only two years before his defeat and execution. His experience provides an illustration of the

problems facing Ilkhanid rulers attempting to keep the loyalty of members of

the dynasty, noyans, bureaucrats and vassals. Before coming to the throne

Tegiider had converted to Islam and taken the name Ahmad, and some historians have attributed his fall to his promotion of Islam. There were however many other reasons for his failure. On Abaqa's death support of royal women, princes and noyans was fairly evenly divided between Ahmad

and Abaqa's son Arghun. Arghun ceded the election but asserted his rights to

the inheritance of valuable property and troops as Abaqa's son. He collected

half the taxes of Khurasan and in addition laid claim to shares in the wealth of

Shiraz and Baghdad. 58 Ahmad's prominent diwan officials, the Juwayni broth

ers Shams al Dm and c Ata Malik, were undermined by a rival, Majd al Mulk of

Yazd, attached to Arghun. Ahmad ended fighting in the diwan by executing

Majd al Mulk, but was less successful with the Mongol elite. 59 The Jalayir

noyan Buqa, powerful under Abaqa, initially favoured Arghun, and Ahmad

was able to win his service only by giving him a level of power which alienated

other noyans. ° In Fars, already disturbed by recent moves against corruption,

local officials withheld taxes and played the noyans against each other.

Two courses of action connected to Ahmad's religion probably did con tribute to his downfall. He chose as his closest advisers two Muslim shavkhs

rather than the Mongol noyans, notably Soghunchaq and Shiktiir, who held

high positions and expected to wield primary influence. Furthermore, against

the advice of his entourage, he attempted to improve relations with the Mamluks and the Golden Horde. 2 Had the Mamluks welcomed his over tures, the policy might have succeeded, but they met his advances coldly.

57 Amitai Preiss, Mongols, pp. 157 77; Claude Cahen, The formation of Turkey: The Seljukid

Sultanate of Rum: Eleventh to fourteenth century, trans. P. M. Holt (Harlow, 2001), pp. 196 207.

- 58 Pfeiffer, 'Conversion', pp. 149 59, 204 10, 230.
- 59 Lane, Early Mongol, pp. 197 206; Pfeiffer, 'Conversion', pp. 216 18.
- 60 Pfeiffer, 'Conversion', pp. 153, 228 9; Rashid al Dm, Compendium, pp. 40, 541, 548, 554.
- 61 Denise Aigle, he Tars sous la domination mongole: Politique etfiscalite (Xllle XlVe s.) (Paris,

2005), pp. 126 32; Lane, Early Mongol, pp. 141 4.

62 Pfeiffer, 'Conversion', pp. 182 4; Peter Jackson, The Mongols and the West, 1221 1410 (Harlow, 2005), pp. 168 9.

148

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

As Ahmad tried to assert power, increasing numbers of noyans and princes

went over to Arghun, who wrote to Qubilai Khan to complain about Ahmad's

abandonment of the 'old ways'. What was meant by this phrase is not explained. When Ahmad attacked Arghun his amirs, under the leadership of

Buqa, switched sides; he was defeated in battle near Qazvin and executed on

25 Jumada I 683/9 August 1284.

Arghun was enthroned on 27 Jumada I/u August; his accession spelled the

end of the Juwayni viziers as Ata Malik died of a stroke in 1283 and Shams

al Dm was executed a few months into Arghun's reign. Buqa Jalayir, whose

help had been decisive in Arghun's victory, became the chief administrator

and sent to Qubilai Khan for official approval this arrived in early 684/1285,

and Arghun staged an official enthronement. 63 Arghun returned to the policy

of alliance with Europe and enmity to the Mamluks, but as usual no action

resulted. The Mamluk border remained relatively quiet and two invasions from the Golden Horde, in spring 1288 and 1290, were easily repelled. In Fars

Arghun ended the reign of the Salghurid princess Abish, associated with Ahmad, and instituted more direct Mongol control.

Over the course of Arghun's reign the rivalries of Mongol noyans came to dominate political life. The first problem came from Buqa Jalayir and his brother Aruq, governor (shahna) of Baghdad. Their power aroused resent ment among other senior amirs. The vizier Sadr al Din Zanjani, employed by

Amir Taghachar who commanded the Ilkhanid Qara'unas troops, accused Buqa of withholding the revenue of Fars, and there were similar accusations

about Tabriz and Baghdad. As Buqa lost power he formed a conspiracy to enthrone a different member of the dynasty; this failed, and he was executed

in 687/1289. Arghun now chose as the head of his diwan the Jewish physician

Sa'd al Dawla who had helped to investigate Buqa's brother Aruq. Over the

next years Sa'd al Dawla expanded his power and that of his family, thus becoming a target of animosity in his turn.

Buqa's execution led to an insurrection by Nawruz, the son of the earlier governor, Arghun Aqa. Nawruz had inherited great wealth in land and flocks

centred in Radkan and held the emirate of Khurasan, thus sharing control of

the region with Arghun's son Ghazan. Several princes were implicated in his

plot and executed, and Nawruz fled to the Chaghadayid regions, from which

he invaded Khurasan in 690/1291. As Arghun became seriously ill that year, a

group of noyans including Taghachar conspired to eliminate their enemies.

63 Aubin, Emirs, pp. 37 8; Allsen, 'Changing forms', p. 229.

149

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

bringing about a series of executions of rival noyans and of Sa'd al Dawla with

his family. On 7 Rabi c I 690/10 March 1291, Arghun died.

The two major candidates for the throne were Arghun's brother Geikhatu and his cousin Baidu. Geikhatu was chosen and enthroned on 24 Rajab 690/23

July 1291. Among his major supporters was Amir Choban, a great nephew of

the noyan Soghunchaq, who had died in 689 /1290. Geikhatu was persuaded to

forgive the noyans who had destroyed Sa c d al Dawla; thus Taghachar remained active and his protege Sadr al Din Zanjani became head of the fiscal

administration. Geikhatu attempted a set of fiscal reforms modelled on those

of Qubilai Khan, probably with the help of Bolad Ch'eng Hsiang, a Khitan administrator with a distinguished record of service in China, who had come

to Iran with Qubilaf s embassy in 684/1285. 64 The programme is remembered

for the experiment with paper money, known by its Chinese name, ch'ao. Its

introduction was carefully planned, proclaimed in Ramadan 693/August 1294,

and implemented a month later, but the population refused to accept it. Commerce shut down and violence erupted on the streets, so the experiment

was cancelled. Only a few months later Geikhatu's amirs conspired to install

Baidu, with Taghachar again among the leaders. Geikhatu was killed on 6 Jumada I 694/24 March 1295 and Baidu was enthroned the next month but

he ruled only until 23 Dhu '1 Qa'da/4 October when Ghazan had him put to

death. These events had a devastating effect on the dynasty in Kirman, which

was divided into two factions, one allied by marriage with Geikhatu and the

other with Baidu. In the course of their reigns the leaders of both factions took

sides in central politics and were killed, bringing the province into disorder.

Ghazan and the later Ilkhanids

Ghazan Khan is remembered primarily for his conversion to Islam and the

reforms he promulgated with the help of the famous vizier and polymath Rashid al Din Hamadani. Ghazan's reign was long seen as the crucial moment

for Mongol assimilation and adaptation to Islamic society. However, he did

not abandon his Mongol heritage and recent scholarship has brought into question the extent of actual change he achieved. 65

Ghazan had made peace with the rebellious Nawruz in late 693/1294, and

when some of Baidu's amirs defected to Ghazan, the two men prepared to

64 Allsen, Culture, pp. 72 4.

65 For example, Reuven Amitai, 'Ghazan, Islam and Mongol tradition: A view from the

Mamluk sultanate', Bulletin of the School of Oriental and African Studies, 59, 1 (1996), pp. 1 10.

150

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

make a bid for power. Nawruz, who was Muslim, suggested that Ghazan convert. Since many Mongols in the army were already Muslim, Ghazan would be attractive to them as well as to the subject population. His con version was an official one, and after Baiju's defeat, Nawruz destroyed churches,

synagogues and Buddhist monasteries in Tabriz, but Ghazan put an end to the

destruction when he returned to Tabriz a few months after his enthronement

on 23 Dhu '1 Hijja 694/3 November 1295. Ghazan did not reverse foreign policy;

he wrote inimical letters to the Mamluks and friendly ones to the European

powers. His title padishah i Islam expressed independence within the Mongol

tradition and claims to pre eminence in the Islamic world. In accord with this, he

worked to gain influence in the Holy Cities. 67 Ghazan however had little success

against the Mamluks. He undertook a series of expeditions to Syria from 1299 to

1303 but although his forces took Horns and Damascus temporarily, within a few

months the Mamluks had reoccupied Syria, and further campaigns in 700/1300

and 702/1303 were failures, though for a time in 700/1300 all Mamluk forces

were driven from Syria.

Ghazan's two predecessors had been unseated by the Mongol noyans, and

he owed his throne to Nawruz. It is not surprising therefore that his reign was

marked by purges of powerful commanders. One victim was Taghachar, who had deserted Geikhatu for Baidu, and then Baidu for Ghazan. Soon Nawruz's power also became unacceptable, and he was executed in 696/1297.

Bloodshed continued through Ghazan's reign and reached into the diwdn. In

1298 Sadr al Dm Zanjani was executed, partly due to accusations by Rashid al

Dm, who took his place as sahib diwdn with Sa'd al Din Sawaji as partner.

Rashid al Dm was born into ajewish family of doctors in 647 or 648/1249 51

and probably began his career at court quite young. He was close to Ghazan

and seems to have served him in a personal capacity as well as an admin istrative one. His enormous wealth appears to have come partly as reward for

his scholarly works and his service as administrator (mutawalli) of Ghazan

Khan's waqf. 69 In his history, the Jam? al tawdrikh, Rashid al Dm describes

Ghazan Khan's reforms and gives the texts of many decrees. Land taxes were

to be collected regularly, according to fixed rates written on plaques attached

66 Charles Melville, 'Padshah i Islam: The conversion of Sultan Mahmud Ghazan Khan',

Pembroke Papers, 1 (1990), pp. 159 77; Amitai, 'Ghazan', pp. 13.

67 Charles Melville, '"The year of the elephant": Mamluk Mongol rivalry in the Hejaz in

the reign of Abu Sa'id (1317 1335)', Studia Iranica, 21, 2 (1992), pp. 198 9.

68 Rashid al Din, Compendium, pp. 586, 625 6, 632.

69 Birgitt Hoffmann, Waqf im mongolischen Iran. RasTduddlns Sorge um Naehruhm und

Seelenheil, Freiburger Islamstudien, 20 (Stuttgart, 2000), pp. 59 72.

151

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

to the walls of buildings. Numerous extraordinary taxes were repealed and

neither envoys nor military were allowed to demand lodging at will. Other

measures promoted the restoration of abandoned land and systematised currency, weights and measures. To support the army, grants of land were

distributed to Mongol soldiers according to rank; these were to be farmed,

probably by slaves or subjects, as was the case in China. 70 Rashid al Dm claimed credit for the reforms in his history and in the correspondence attributed to him; however, the correspondence has been shown to be a later composition, and recent scholarship has questioned Rashid al Din's pre eminence in the programme. 71 Like earlier reforms, Ghazan's measures

show similarities to many of Qubilai Khan's programmes; one should note that Bolad Ch'eng Hsiang, who had served under Qubilai, was still at court. 72

Ghazan Khan died on 5 Shawwal 703/11 May 1304 and was succeeded by his

brother Kharbanda, who took the name Oljeitii when he was enthroned on

15 Dhu '1 Hijja/19 July with the traditional Mongol rites. He became disen

chanted with Sunnism, supposedly after a particularly acrimonious debate

between Hanaf 1 and Shafi'i c ulama\ and he adopted 'Ithna c ashari (Twelver)

ShTism in 1309 10, but made no effort to impose it. Oljeitii was in an unusually

comfortable position, since Ghazan had executed the most powerful amirs and

had left no male offspring. Furthermore Oljeitii lived in a rare period of harmony among the Mongol states; he wrote optimistically to Philip the Fair of France in spring 1305 that the Mongol empire had been restored.

Oljeitii faced a number of challenges from the smaller powers within his realm and on its borders. Early in 706 / 1306 he sent an expedition against Herat

whose ruler, Malik Fakhr al Din Kart, had failed to congratulate him on his

accession or send tribute, and was harbouring the Negiideri who habitually

raided Kirman and Fars. When the Kartids murdered the Ilkhanid commander

another army was sent out, which seized Herat. In 706/1307 Oljeitii undertook

a major expedition against Gilan which foundered with the defeat and death of

his chief amir Qutlugh Shah; this initiated the rise of Amir Choban, who

70 Shihab al Din Ahmad al 'Umari, Das tnongolische Weltreich. Al 'Umaris Darstdlung der

mongolischen Reiche in seinem Werk Masalik al absdr ft mamalik alamsar, ed. and trans.

K. Lech (Wiesbaden, 1968), p. 155; Ch'i ch'ing Hsiao, The military establishment of the

Yuan dynasty, Harvard East Asian Monographs, 77 (Cambridge, MA, 1978), pp. 20 2, 46.

71 A. H. Morton, 'The letters of Rashid al Dm: Ilkhanid fact or Timurid fiction?', in Amitai

Preiss and Morgan (eds.), Mongol empire, pp. 155 gg; David O. Morgan, 'Rasid al Din and

Gazan Khan', in Aigle (ed.), L'Iran, pp. 1857.

72 Thomas T. Allsen, 'Biography of a cultural broker, Bolad Ch'eng Hsiang in China and

Iran', in Julian Raby and Teresa Fitzherbert (eds.), The court of the R khans 1290 1340

(Oxford, 1996), pp. 722.

152

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

dominated the later Ilkhanate. 73 In autumn and winter 707/13071"., Oljeitii

attacked the Mamluk fortress Rabat al Sham but withdrew on meeting resist

ance. In 713/1313E the truce with the Chaghadayids broke down when the

Ilkhan annexed Negiideri territories, and a Chaghadayid army chased Ilkhanid

troops almost up to Herat. As Oljeitti set out against them they withdrew,

the Chaghadayid prince Yasa'ur defected and Oljeitti rewarded him with the

rich region of Badhghts.

Oljeitti died 1 Shawwal 716/17 December 1316 of a stomach problem probably related to drinking. His twelve year old son Abu Sa'td succeeded

him but actual power lay with Amir Choban. There was bitter rivalry within

the diwan where Rashid al Dm and his partner Taj al Dm 'All Shah had become so inimical that Oljeitii had divided the administration, with Rashid

al Dm in charge of central and southern Iran and 'All Shah in charge of the

north west, including Mesopotamia and Asia Minor. 'All Shah engineered Rashid's execution with other family members on i7jumada 1 718/17 July 1318.

Early the next year Yasa'ur attacked Mazandaran while the Jochid Uzbek Khan (r. 1313 41) invaded through the Caucasus. The Ilkhanid forces pushed

Yasa'ur to the south, where he was later killed by the Chaghadayid khan Kebeg. In the Caucasus, Abu Sa'id headed against Uzbek Khan with insuffi

cient forces and his advance guard was put to flight. A little later he reversed

the situation, aided by Choban. Choban punished the amirs who had failed to

stand against Uzbek Khan; a few months later these amirs waylaid him and he

had to flee to the court for safety. The rebellious amirs gained support from

Abu Sa'id's uncle Irenjin and marched on Tabriz, but were defeated near Miyana in 719/1319.

For some years Choban and 'All Shah worked cooperatively and it was they

who achieved peace with the Mamluks in 1320 3. However, even though Choban was married to Abu Sa'id's sister Sati Beg, from the mid 1320s he

encountered increasing hostility, due in part to the behaviour of his son Dimashq Khwaja who served as his representative at court. When Choban

failed to heed complaints, Abu Sa'id encouraged members of the court to kill

Dimashq Khwaja in 727/1327. Furthermore, Abu Sa'id had fallen in love with

Amir Choban's daughter, married to another amir, and Choban refused to

arrange her divorce. Eventually Choban began an open revolt and fled to Herat, where the Kartids, reluctant to break with the Ilkhans, killed him. 74

73 Charles Melville, 'The Ilkhan Oljeitii's conquest of Gilan (1307): Rumour and reality', in Amitai Preiss and Morgan (eds.), Mongol empire, pp. 73 125.

74 Charles Melville, The fall of Amir Chupan and the decline of the Ilkhanate 1327 1337: A decade of discord in Iran (Bloomington, IN, 1999), pp. 11 27.

153

# The New Cambridge History of Islam

There were further conspiracies in 1328 and 1329, leading to the execution of

many of the amirs involved in the fall of Dimashq Khwaja. The diwan was entrusted to Rashid al Din's son Ghiyath al Din but many noyans disliked him

and dissidents gathered around the deposed governor of Shiraz, Mahmud Shah Injii, so that the governor whom Abu Sa'id sent to Fars in 735/i334f was

unable to take over for some time. The Golden Horde again advanced, and

Abu Sa'id headed against them but died on 13 Rabi c II 736/30 November 1335.

Since he was childless and no other strong members of the dynasty survived,

his death initiated a protracted struggle.

#### Mongol patronage

The Mongol period was one of high achievement in fields which interested the

Mongol ruling class, whose familiarity with Chinese and Central Asian culture

affected the production of the artists and scholars working for them. Outside

influences initiated a period of extraordinary cultural efflorescence for Iran.

The Mongols showed a predilection for practical scientific knowledge such as

astronomy, medicine, agronomy and geography. When Chinggis Khan con

quered the Middle East he brought along Chinese astronomers, one of whom

was in charge of an observatory in Samarqand by 1222. The Khitan Yeh lit

Ch'u Ts'ai used Middle Eastern astronomical tables to revise Chinese calen

dars and produced a new calendar for the Mongol rulership. 75 Hiilegii came to

Iran with Chinese doctors and astronomers and employed Naslr al Dm Tusi

(1201 74), who became supervisor of waqf endowments, some of which he

diverted to promote his own intellectual interests. Soon after taking Baghdad

Hiilegii founded an observatory in Maragha, with Middle Eastern and Chinese

astronomers. Here Tusi composed an influential work on planetary astron omy and his team produced the Zij i Ilkhdnl star tables used for centuries thereafter. The Mongols also brought Middle Eastern scholars to China. Qubilai Khan (1215 94) established several institutes for Middle Eastern scien

ces, including the Office of Western Medicine in 1263 and a Muslim astro nomical observatory in 1271. In 1285 he commissioned a geographical compendium including information from Middle Eastern maps. 76

Textile production was among the earliest concerns of Mongols, who set up

workshops in Iran, Mongolia and China to produce luxury cloth combining

Iranian and Chinese motifs. Ceramics and metalwork also flourished with a

75 Allsen, Culture, pp. 165 6.

76 Ibid., pp. 108, 150, 166 7.

154

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

liberal admixture of Chinese decorative themes like the dragon, phoenix and

peony, which remained part of Persian art thereafter. The Ilkhans founded

their state just after the demise both of the caliphate and of a united Mongol

empire, and in crafting their legitimation they turned to Iranian traditions.

One illustration of the new ideology was Abaqa Khan's palace at Takht i Sulayman, situated on the site of a royal Sasanian city. Conspicuous among

the decorative motifs were verses and illustrations of the Persian epic, the

Shah noma; like earlier nomad dynasties, the Ilkhans were identified with the

Turanian king Afrasiyab. The palace also contained references to Chinese symbolism. 77 Production of luxury manuscripts became one of the marks of

Ilkhanid patronage, with the creation of magnificent Qur'ans, and later illustrated histories and epics. 78

Arghun Khan's major architectural undertaking was a suburb of Tabriz called Arghuniyya, completed in 690/1291. Conversion to Islam brought increased patronage of religious architecture, while the interest of Ghazan

and Rashid al Din in Mongolian and Chinese traditions introduced a period

of intense cultural borrowing. Abandoning the custom of secret burial, Ghazan built his mausoleum in a waqf complex which constituted a whole suburb near Arghuniyya, and included a mosque, madrasas, a khanaqa, observatory, library, hospital, hospice for sayyids and a kitchen to feed the

poor. 79 In 7i3/i3i3f. Oljeitii completed a mausoleum in the town of Sultaniyya which became the necropolis and second capital for the Ilkhanids. The mausoleum, still standing, is a masterpiece of Islamic archi

tecture. Rashid al Dm built a charitable foundation in Tabriz similar to Ghazan's, known as the Rab c i Rashidi. In addition to religious buildings and a hospital, he endowed a scriptorium where his works would be regularly copied to ensure their diffusion. ° In the later Ilkhanid period numerous people endowed mausoleum complexes on a smaller scale referred to by scholars as 'little cities of God', which became a standard feature of the urban landscape. The rise of Sufi organisations continued

77 Tomoko Masuya, 'Ilkhanid courtly life', in Stefano Carboni and Linda Komaroff (eds.),

The legacy of Genghis Khan: Courtly art and culture in western Asia, 1256 13%, (New York,

2002) pp. 84 5; A. S. Melikian Chirvani, 'Conscience du passe et resistance culturelle

dans l'Iran mongol', in Aigle (ed.), L'Iran, pp. 145 59.

78 Masuya, 'Ilkhanid courtly life', p. 79; Stefano Carboni, 'Synthesis: Continuity and

innovation in Ilkhanid art', in Carboni and Kamaroff (eds.), Legacy, p. 203; Robert

Hillenbrand, 'The arts of the book in Ilkhanid Iran', in Carboni and Komaroff (eds.),

Legacy, pp. 135, 143.

79 Hoffmann, Waqf, p. 112.

80 Birgitt Hoffmann, 'The gates of piety and charity: Rasid al din Fadl Allah as founder of pious endowments', in Aigle (ed.), L'Iran, p. 196.

155

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

under the Mongols and their khdnaqds became a locus for cultural activity,

including the production of fine manuscripts.

Rashid al Dm was the author at least the planner and editor of several encyclopaedic works. His treatise on agronomy was novel in its practical bent

and in the inclusion of numerous plants from outside, particularly from China.

His greatest work was the monumental world history, the fatni' al tawarikh,

begun for Ghazan Khan and completed about 710/131 of. He made use of

information from Indian and Buddhist scholars, Ghazan's knowledge of Mongol lore, and Bolad Ch'eng Hsiang's expertise in Chinese and Mongolian

history to put earlier histories of the Islamic world into a new frame encompass

ing the Mongols, Europeans, Chinese and others. The history was illustrated a

practice new with the Ilkhans and the paintings show strong Chinese and Central Asian elements. Within a few years luxury copies of the Shah noma were

being illustrated, and by the 730s /1330s, the time of the 'Great Mongol' (Demotte) Shah noma, a new Persian style of painting had begun. The new

fashions set by the Ilkhans affected their vassals and neighbours. In the four

teenth century, Shiraz became a centre for the production of illustrated manu

scripts, including several Shah nomas, and Armenian manuscripts of the period

show Chinese motifs. Even the Mamluks took inspiration from their Mongol enemies.

The economic impact of the Mongols

It is difficult to form an accurate picture of economic developments under the

Mongols. The most detailed study on agriculture is the book of I. P. Petrushevskii, who was constrained by Soviet policies which dictated a negative

assessment of Mongol rule; 82 his conclusions can no longer be accepted without.

critical examination. 3 More recent scholars vary in their opinions, but some

common revisions emerge. The decline in agriculture is no longer attributed

only to the Mongols and greater importance is given to restoration before

81 Sheila S. Blair, 'Calligraphers, illuminators, and painters in the Ilkhanid scriptorium', in Komaroff (ed.), Beyond the legacy, pp. 170 1.

82 I. P. Petrusheveskii, Zemledelie i agramye otnosheniia v Irane XIII XIV vekov (Moscow and

Leningrad, i960). Parts are summarised in 'The socio economic condition of Iran under

the Ilkhans', in Tfie Cambridge history of Iran, vol. V, pp. 483 537.

83 Lambton, Continuity, p. 219; Jean Aubin, 'Reseau pastoral et reseau caravanier: Les

grand'routes du Khurassan a l'epoque mongole', Le Monde Iranien et I'Islam, 1 (1971),

pp. 107 8; and Aubin, 'La propriete fonciere en Azerbaydjan sous les Mongols', Le

Monde Iranien et I'Islam, 4 (1976 7), p. 130.

The Mongols and the Islamic world

Ghazan Khan. 84 The Mongols entered a region where agriculture was already in

decline and their conquest precipitated a crisis. The seriousness of the situation

did not escape notice; Chinggis Khan began restoring Transoxiana before his

departure. Rebuilding continued under the Great Khans and the Ilkhanids, but

recovery was hampered by the difficulty of asserting central control.

In addition to the qubchur, qalan and tamgha, the Mongols collected numer

ous taxes for the support of specific services. However, only a portion of what

the population handed over reached the central government. Private income

sources and the stipends of princes, princesses and amirs were sometimes

collected directly from the population. Furthermore, local governors and maliks often bribed Mongol collectors, thus enriching both groups at the expense of the population. 85 The situation may have been even worse in areas ruled through local powers, where the regional dynasty provided an

additional level of consumption and corruption. Fars provides an illustration

of the difficulties facing the Ilkhanid tax administration. Under several differ

ent khans officials arrived with a reform agenda only to suffer attack and speedy demotion. The oppression of the agricultural population was not due

to preferential treatment of nomads. During the struggle preceding Ghazan's

accession to the throne, when taxes were increased and demanded in advance,

a levy of 20 per cent was raised from livestock, thus bringing the nomadic

tribes into disorder, at least in Fars. 87 In Rashid al Din's description of abuses

preceding Ghazan's reign he describes the impoverishment of common soldiers in the Mongol army, a problem that also plagued the Yuan.

Trade and production were of particular interest to the Mongols. The tamgha tax provided significant income, some perhaps going directly into

the dynasty's private treasury. 89 The leadership also engaged directly in international commerce through partnerships known as ortoq, in which money was entrusted to merchants in return for a share of profits. There

84 Aubin, 'Propriete',pp. 79 81,129 32; Lambton, Continuity, p. 144; Peter Christensen, The

decline oflranshahr: Irrigation and environment in the history of the Middle East 500 BC to AD

i}oo (Copenhagen, 1993), p. 12 and passim.

85 Thomas Allsen, 'Sharing out the empire: Apportioned lands under the Mongols', in A.

Wink and A. Khazanov (eds.), Nomads in the sedentary world (Richmond, 2001), pp. 177

81; Aubin, 'Propriete', p. 94; Aigle, Fars, pp. 152 3.

86 A. K. S. Lambton, 'Mongol fiscal administration in Persia', part II, Studia Islamica, 65

(1987), pp. 100 21; Lane, Early Mongol, pp. 133 41; Aigle, Fars, pp. 92, 104, 120, 127.

87 Lambton, 'Fiscal administration', II, pp. 109 10.

88 Rashid al Din, Compendium, pp. 232, 739 40; Hsiao, Military, pp. 29 31.

89 Philip Remler, 'New light on economic history from Ilkhanid accounting manuals',

Studia Iranica, 14, 2 (1985), pp. 170 3; Hamd Allah Mustawfi QazwinI, The geographical

part of the Nuzhat al qulub, ed. G. Le Strange, Gibb Memorial Series (London, 1915 18),

text, pp. 50, 56, 59, 78, 116.

157

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

was thus a close relationship between the Mongol government and interna

tional merchants, who benefited from significant privileges. Ortoqs existed

under the Ilkhans and provided additional income for the dynasty and elite. 90

A number of merchants served the administration, particularly as holders of

tax farms. The most notable examples were the wealthy merchants of Oavs in

the Persian Gulf, who for some time managed the taxes of Fars. 91

Tabriz and Sultaniyya were international trading centres where the land routes through Central Asia connected with those of the Golden Horde and

the sea trade of the Persian Gulf. After about 1275 the Genoese dominated

Black Sea commerce from Kaffa, the major port for the Golden Horde, and

from about 1280 into the middle of the fourteenth century they maintained a

colony in Tabriz. 91 In the south two small mercantile powers, Qays, usually

allied with Fars, and Hormuz, closer to the Qutluq Khanids of Kirman, competed in the rich trade with India and China. For the sea trade, horses

and pearls appear to have been the major exports but for other regions textiles

were more important, and it is notable that the production of silk and cotton is

said to have increased. 93 The Ilkhans were active in protecting trade routes in

both the Black Sea and the Gulf. 94 Mongol interest in trade promoted the

growth of the middle classes. Skilled craftsmen seem to have risen in status,

while practical and linguistic skills provided a path to advancement within

government. The success of people from the lower classes is a frequent lament.

of Ilkhanid bureaucrat historians, 95

# The Mongol legacy in Iran

It is hard to define the end of the Mongol period in the Middle East. Despite

strong separate identities, Mongols and Iranians intermarried and became

closely connected both culturally and politically. 96 While Mongolian

90 Thomas Allsen, 'Mongolian princes and their merchant partners, 1200 1260', Asia Major, 3rd ser., 2 (1989), pp. 94 121.

91 Lambton, 'Fiscal administration', II, pp. 105 6, 114.

92 Jacques Paviot, 'Les marchands italiens dans l'Iran mongol', in Aigle (ed.), L'Iran, pp. 73, 78.

93 Lambton, Continuity, p. 181.

94 Paviot, 'Les marchands', p. 84; Jean Aubin, 'Les princes d'Ormuz du XHIe au XVe siecle', Journal Asiatique, 241 (1953), pp. 85, 92 3.

95 Oliver Watson, 'Pottery under the Mongols', in Komaroff (ed.), Beyond the legacy,

pp. 330 3; Bernard O'Kane, 'Persian poetry on Ilkhanid art and architecture', in

Komaroff (ed.), Beyond the legacy, p. 353; Aubin, 'Propriete', p. 129.

96 al 'Umari, Mongolische Weltreich, p. 159; Tatiana Zerjal, Yali Xue, et ah, 'The genetic

legacy of the Mongols', American Journal of Human Genetics, 72 (2003), pp. 717 21.

158

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

remained the chancery language, by the fourteenth century the ruling class

spoke Turkic, like earlier steppe dynasties. Many bureaucrats and local rulers

were familiar with Mongolian culture and depended on Mongol legitimacy for

their own prestige. Thus when Abu Sa c id Khan died childless on 30 November

1335, the first reaction was to prop up Chinggisid rule. Ghiyath al Dm b. Rashid

al Dm installed a new khan within hours of Abu Sa'id's death, but was soon

defeated. In the northern regions the competing powers were families of noyans who had married into the royal family over several generations. Hasan

Beg Jalayir, a grandson of Oljeitu married to a Chinggisid woman, soon promoted his own candidate. In early 739/July August 1338, the descendants

of Choban made a bid for power, using Abu Sa'id's sister Sati Beg Choban's

widow as candidate. The Jalayirids (1336 1432) based themselves in Baghdad

and the Chobanids (1336 56) in Tabriz, with constantly shifting borders.

For several years vassal states in southern Iran continued to give nominal

allegiance to the khans of the Jalayirids or Chobanids. The Injuid dynasty in Fars

soon lost out to Mubariz al Din Muzaffar, who had begun his career under Abu

Sa c id and later allied with the Chobanids. The Muzaffarid dynasty took over

much of southern and central Iran, including Kirman and Isfahan. The eastern

centre of the Ilkhanate lay in Khurasan. Here noyans gathered with Iranian

rulers and religious figures in the summer of 737/1336 and elected as khan

Taghay Temiir, a descendant of Chinggis Khan's brother Jochi Qasar. 97 The

most powerful noyan in Khurasan was Arghunshah, who was descended from

Arghun Aqa and led the family's hereditary troops. His dynasty and that of

Taghay Temiir however soon lost territory to the Iranian Sarbadarid dynasty of

Sabzawar (1337 86), while the Kartid dynasty of Herat became the pre eminent

power of the region. For some time after Abu Sa'id's death rulers included the

name of one or another Chinggisid khan on their coinage, then in the mid 740s/

1340s a few began to issue coins anonymously. It was only in the 1350s that some

rulers looked to new sources of legitimacy. In 755/1354 Mubariz al Din Muzaffar

requested a patent from the shadow caliph in Egypt, and in 759/1358, following

the demise of the Chobanid dynasty, the Jalayirid sultan Uways claimed power

in his own name. 9

There is no sign of an exodus of Mongol population and we find Mongol tribes and populations active well into the fifteenth century. The Iranian armies (cherig) organised by the Mongols remained an important element of

97 Jean Aubin, 'Le quriltai de Sultan Maydan (1336)', Journal Asiatique, 279 (1991), pp. 175 97.

98 Steven Album, 'Power and legitimacy: The coinage of Mubariz al Din Muhammad ibn

al Muzaffar at Yazd and Kirman', Le Monde harden et Vlslam, 2 (1974), pp. 158 68.

159

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

military power for more than a century. Mongol influence continued in government structures as well. Turkic and Mongolian words entered into Persian vocabulary and several Mongol institutions, such as the military governor darugha and the imperial guard, the keshig, lasted through the Safavid dynasty." A more contentious element of Mongol tradition was the

yasa (Mongolian: jasagh), usually translated as 'law' or 'code'. Scholars dis

agree over whether or not the yasa was a specific set of laws existing as a

written document. The precepts preserved deal primarily with military and

administrative matters which were tried in the Mongol court, the yarghu.

By the fourteenth century however the term yasa was a general one, encom

passing both law and custom (yosun). There was considerable disagreement

over how much the yasa and the sharfa conflicted. For rulers who adhered to

both the Mongol and the Islamic order, like Ghazan Khan and later Tamerlane, there was apparently no contradiction, while scholars hostile to

Mongol rule considered the two systems mutually exclusive. Whatever the

reality of the yasa, as a marker of identity it remained central to Turco Mongolian government. 100 For centuries the Mongol empire continued to

set the standard of imperial power against which all dynasties had to measure

themselves, and reference to Mongol ancestry was used in Islamic lands into

the nineteenth century.

#### The Chaghadayid khanate

Transoxania and the Silk Road cities lay within the Chaghadayid khanate, about which we have distressingly little information since the area produced

almost no indigenous historical writing. Most of the settled regions were included in the satellite administration created by Ogedei in 1229, which remained in existence for some time after Qubilai's accession. 101 The families

of the early officials Mahmud Yalavach and Yeh lii A hai retained their positions for decades; that of Yalavach until after 1302. 102 Their long tenure

suggests that the Chaghadayid administration did not suffer from the vicious

bureaucratic infighting that plagued Iran. Political history presents a strong

99 Melville, 'Keshig.

100 For recent discussion see: Denise Aigle, 'Le grand jasaq de Gengis Khan, l'empire, la

culture mongole et la sharfa, Journal of the Economic and Social History of the Orient, 47, 1

(2004), pp. 31 79; David Morgan, 'The "Great yasa of Chinggis Khan" revisited', in

Amitai and Biran (eds.), Mongols, Turks and others, pp. 291-308.

101 The census conducted in Bukhara about 1265 was at his orders. (Michal Biran, Qaidu

and the rise of the independent Mongol state in Central Asia (Richmond, 1997), p. 35.)

102 Biran, Qaidu, p. 98; Allsen, 'Mahmud Yalavac', pp. 122 36.

160

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

contrast. The khanate was constantly embroiled in wider politics and succes

sion was often imposed from outside. When Giiyiig came to the throne in 1246, he replaced Chaghadai's grandson Qara Hiilegii b. Mo'etiiken (r. 1242 6)

with Chaghadai's son Yesii Mongke (r. 1246 51). Because the Chaghadayids

opposed Mongke's accession, Yesii Mongke was executed along with other

Chaghadayids. Qara Hiilegii died before he could resume the throne, but until

1260 his widow Orghina Khatun served as regent for her young son Mubarakshah. She held great prestige as a granddaughter of Chinggis Khan,

a member of the Oirat tribe and a close relation of the wives of several Mongol

khans. 103

After Mongke's death the struggle between Ariq Boke and Qubilai offered

new chance for the Chaghadayids. Ariq Boke offered the throne to Alghu (r. 1260 6), and in 1261 sent him to gather supplies. Instead, Alghu enlarged the

Chaghadayid territories and sent his own agents to Samarqand and Bukhara,

still under joint administration. His actions led to open warfare with Ariq Boke

in 661 / i262f; Alghu prevailed and cemented his position by marrying Orghina

Khatun. 104 In 664/1266, after Alghu's death, Orghina Khatun enthroned her

Muslim son Mubarakshah, who was soon deposed by his first cousin Baraq

(r. 1266 71).

The Jochids were likewise interested in Chaghadayid politics. Berke Khan allied with Qaidu, a grandson of Ogedei working to restore Ogedeyid rule in

Central Asia, and promised him the Chaghadayid throne. Qaidu's attempt to

overthrow Alghu in about 663/i264f failed, but, after Alghu's death, he managed for a while to take over the regions of Talas and Almaliq. Pushed

west by Qubilai, he defeated Baraq Khan in 1268 near Khojand. Baraq retreated to Samarqand and Bukhara and began plundering them. Qaidu proposed peace, and in 1269 organised a quriltai at which the rulers agreed

that Transoxiana would be divided two thirds to Baraq and one third to Qaidu and both would remain outside the agricultural areas. Tiring of Baraq,

Qaidu encouraged him to invade Khurasan with a number of commanders who were secretly ordered to desert. On 1 Dhu '1 Hijja 668/22 July 1270 Abaqa's army defeated Baraq outside Herat. About a year later Baraq died,

and Qaidu became khan over a combined realm.

By this time the Chaghadayids were beginning to expand control towards Ghazna, where the Qara'unas increasingly came under their command. After

103 Rashid al Dm, Compendium, pp. 55 6; Karin Quade Reutter, '... denn sie haben einen

unvoUkommenen Verstand'. Herrschaftliche Damen im Grossraum Iran in derMongolen und

Timuridenzeit (c. iyo i;oy) (Aachen, 2003), p. 316; Rashid al Din, Successors, pp. 109 10.

104 Rashid al Din, Successors, pp. 150 1; Biran, Qaidu, pp. 21 2.

161

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

the defeat of Baraq, the deposed khan Mubarakshah b. Qara Hiilegii joined

the Ilkhans, and Abaqa appointed him to the command of the Negiideri, whose allegiance soon passed to the Chaghadayids. Another contingent of

Qara'unas near Ghazna was commanded by the descendants of Chaghadai's

son Baiju. This was an important post, allowing involvement in the politics of

Khurasan and Kirman and profitable raids on the Delhi sultanate. 105

On Baraq's death Qaidu enthroned Buqa Temiir (r. 1272 82), from a differ

ent dynastic line. Over the next eleven years Transoxiana suffered uprisings

and plunder by princes of the lines now excluded the sons of Alghu and Baraq and from 1277 to 1279 Qaidu was also at odds with Buqa. The situation

improved in 1282 when Qaidu enthroned Du'a b. Baraq (r. 1282 1307). The two

men spent several years fighting the Yuan, thus giving Transoxiana a welcome

rest. With the rebellion of Amir Nawruz in 688/1289, Qaidu and Du'a turned

west and from 1290 to 1295 they again threatened Khurasan. After 1295 their

attention turned east until Oaidu's death in 701/1301. 10

Du'a Khan now emerged as the major power in the combined Ogedeyid and Chaghadayid realm, with Qaidu's son Chapar as the subordinate khan.

Du'a made peace with the Yuan but he and Chapar were almost immedi ately at war. 107 Du'a prevailed, resulting in an exodus of Chapar's troops into

the Ilkhanate in 1306. IO Chapar submitted to the Yuan in 1310 and most Ogedeyid territories were divided between the Chaghadayids and the Yuan.

Since many of the Chaghadayids' eastern migration routes now included Yuan territory, the border became a constant source of friction. 109 After Du'a's death in 706/1307 the throne rotated rapidly among his sons. 110 The

next major power was Du'a's son Kebek, who enthroned his brother Esen Buqa (r. 1310 18), keeping for himself the administration of Farghana and

Transoxania, centred in Nakhshab. Kebek took the throne himself about 1318

and ruled until 727/1327. He is famous for his currency reform; the silver dinar he minted took his name and remained the standard for currency in Transoxiana and eastern Iran for over a century.

105 Aubin, %'ethnogenese', pp. 82 4; Kazuhide Kato, 'Kebek and Yasawr: The establishment of

the Chaghatai Khanate', Memoirs of the Research Department of the Toyo Bunko, 49 (1991), p. 104.

106 For the date: Biran, Qaidu, p. 69.

107 Ibid., pp. 72 3.

108 Russell G. Kempiners, 'Vassaf's Tajziyat al amsar wa tazjiyat al a'sar as a source for the

history of the Chaghadayid khanate', Journal of Asian History, 22, 2 (1988), p. 177.

109 Biran, Qaidu, p. 77; Yingsheng Liu, 'War and peace between the Yuan dynasty and the

Chaghadaid khanate (1312 1323)', in Amitai and Biran (eds.), Mongols, Turks and others, pp. 340 41-

no Biran, Qaidu, p. 77; Michal Biran, 'The Chaghadaids and Islam: The conversion of

Tarmashirin Khan (1331 34)', Journal of the American Oriental Society, 122, 4 (2002), p. 750.

162

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

Kebek was followed on the throne by three brothers, Eljigidei (r. 1327 30), Dore

Temiir(r. 1330 1) and finally Tarmashirin (r. 731 5/1331 4). 111 It is Tarmashirin who

is credited with the Islamicisation of the western part of the Chaghadayid khanate.

He converted to Islam probably shortly before he came to the throne, and as ruler

he promoted conversion; according to Muslim sources, he abrogated the yasa in

favour of the shaft 'a. This move is seen as a reason for his fall he was blamed for

giving up the annual convocation and for failing to visit his eastern territories.

According to one source, he also attempted to push his Mongol followers into

practising agriculture. Other problems probably contributed to his downfall, most

notably the recent devastation of Transoxiana and increasing dynastic discord.

In 735/1334 Tarmashirin was deposed by a coalition including several of his

nephews, based apparently in the eastern regions. 112

Two of Tarmashirin's nephews succeeded in turn to the throne after which

the chronology of rule becomes confused. It seems likely that the realm had

begun to divide into eastern and western sections, with separate khans claiming

power in each. 113 While the khans immediately after Tarmashirin were probably

not Muslim, it is clear that Islamicisation of the nomads in Transoxiana had

begun before Tarmashirin, and his overthrow did not interrupt the process. In

747/i346f, Qazan Khan b. Yasa'ur was killed by the amir of the Qara'unas troops, who took power in the name of a puppet khan and ruled over the western section of the khanate, which came to be known as the Ulus Chaghatay.

The eastern section stayed under the rule of Chinggisid khans, and Islam was

not established there until the conversion of Tughluq Temiir Khan in 755/1354.

The two sections remained largely separate though it appears that the situation

was viewed as temporary up to the fifteenth century. 114

The expansion of Islam

Anatolia

Although the Mongol conquest put many Muslims under the rule of infidels,

Mongol rule eventually resulted in a massive expansion of the dar al islam.

in The dates of these reigns have been corrected by Biran, 'Chaghadaids', pp. 744 5.

112 Ibid., pp. 749 50; Ibn Battuta, The travels oflbn Battuta, AD 1325 1354, trans. H. A. R. Gibb, Hakluyt Society (Cambridge, 1971), vol. Ill, pp. 560 1.

113 Biran, 'Chaghadaids', p. 750; Peter Jackson, 'The Mongols and the Delhi Sultanate in the

reign of Muhammad Tughluq (1325 1351)', Central Asiatic Journal, 19, 1 2 (1975), p. 144 n.

129; Jean Aubin, 'Le khanat de Cagatai et le Khorassan (1334 1380)', Turcica, 8, 2 (1976), pp. 22 4.

114 Ho dong Kim, 'The early history of the Moghul nomads: The legacy of the Chaghatai

khanate', in Amitai Preiss and Morgan (eds.), Mongol empire, pp. 302 3.

163

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Muslims became predominant in western Anatolia and much of the western

Eurasian steppe, while large Muslim minorities formed in parts of China. In

Anatolia, the Mongols accelerated a process already under way. Oghuz Turkic

tribes had entered Asia Minor in the Saljuq period, and by the beginning of the

thirteenth century the Saljuq sultanate of Rum controlled most of central and

eastern Anatolia, though for some time much of the population probably remained Christian. From 1230 on, Mongols moved into the pastures of Azerbaijan and crowded out nomad Turks, many of whom migrated into Anatolia. In 675/1277 the sultanate of Rum was incorporated into the Ilkhanate, and as central rule weakened in the fourteenth century, Turkmen

nomads sought opportunities on the western borders, thus expanding their

territory at the expense of the remaining Christian kingdoms. By the end of

the century the population of Anatolia was largely Turkic and Muslim.

#### The Golden Horde

It was under Mongol rule that Islam began to take hold among the Turks of

the western steppes. Muslim merchants had long been active in the Volga

region and Islam had become formally established there with the conversion

of the Bulghar kingdom in the tenth century. When the Mongols set out to

incorporate the Qipchaq steppe, they began in 1231 2 with the Bulghar region

thus many of their first subjects were Muslim. The Golden Horde capital Sarai

was built on the lower Volga, important for both pasture and trade. It is not

surprising then that the second major khan of the Golden Horde, Berke (r.

1257 67), became Muslim, reportedly through the influence of the Bukharan

shaykh Sayf al Din Bukhari. 115 Berke did not impose Islam as a state religion,

and since his religious orientation aided his alliance with the Mamluks, the

importance of Islam for him and his followers may be exaggerated in histories

and correspondence. 11 However, the European friar William of Rubruck states that pork was not allowed within his court and it appears that many

of his followers converted. The khans who followed Berke adhered to other

religions, but the amir Nogay, the greatest power in government from 1267 to

his death in 1299, was Muslim.

115 Istvan Vasary, '"History and legend" in Berke Khan's conversion to Islam', in Aspects of

Altaic civilization III: Proceedings of the thirtieth meeting of tfte Permanent International

Altaistic Conference, Indiana University, Bloomington, Indiana, June 19 25, 1987

(Bloomington, IN, 1990), pp. 235 6, 239 48.

116 Vasary, 'History and legend', p. 250; Devin DeWeese, Islamization and native religion in

the Golden Horde: Baba Tukles and conversion to Islam in historical and epic tradition

(University Park, PA, 1994), pp. 83 5.

164

Cambridge Histories Online © Cambridge University Press, 201 1

## The Mongols and the Islamic world

The official Islamicisation of the Golden Horde came with Uzbek Khan (r. 1313 41). Like many other khans who promoted Islam, Uzbek attempted to

increase central power at the expense of Mongol noyans, and his early rule was

marked by resistance and widespread purges. 117 During his reign the ruler of

the eastern section of the Jochid realm, Irzan Khan (r. 720 45/i32of. i344f),

also converted and built mosques, madrasas and khdnaqds in the northern

Jaxartes region. Islamicisation was a gradual process; Ibn Battuta noted in his

travels that Christianity was still more popular than Islam among most Turkic

tribes. 11 Legends quickly grew up around the conversion of the Jochid rulers

and over time combined with native Turkic religion to form origin myths for

new communities. Thus conversion became a self perpetuating process. The

succession states which emerged in the fifteenth and sixteenth centuries were

ruled largely by Muslims, and many of their followers were likewise believers.

#### China

By the twelfth century China had a sizeable Muslim population concentrated

in port and trading cities. 119 The first immigrants in the Mongol period came as

captured artisans and military conscripts. Several workshops staffed by cap

tives became colonies in Mongolia and China. 12,0 The use of foreign soldiers

continued into the reign of Qubilai; thus Muslim troops were among the garrison armies which eventually became permanent settlements. 121 The

Mongols brought in merchants from eastern Iran and Central Asia, many of

whom entered into ortoq partnerships. To the disgust of elite bureaucrats, the

khans recruited merchants to serve in administration, particularly in financial

affairs. In 1239, when Ogedei faced a pressing need for income, the merchant

Abd al Rahman proposed tax farming and received the tax collection of north

China. For some years the taxes of northern China were often farmed out to

ortoq merchants. When peasants were unable to pay, the same men offered

them credit at exorbitant rates. Ortoq merchants continued to exploit tax collection until the reign of Mongke, who abolished the worst abuses but

- 117 G. A. Fedorov Davydov, Obshchestvennyi stroi Zolotoi Ordy (Moscow, 1973), p. 104.
- 118 Ibn Battuta, Travels (Cambridge, 1962), vol. II, p. 470; DeWeese, Islamization, p. 131.
- 119 Donald D. Leslie, Islam in traditional China: A short history to 1800 (Belconnen, 1986), PP- 53 5-
- 120 Allsen, Commodity, pp. 30 45.

History, 1, 1

121 Thomas T. Allsen, 'Ever closer encounters: The appropriation of culture and the apportionment of peoples in the Mongol empire', Journal of Early Modern

(1997), PP- 8 9; Michael Dillon, China's Muslim Hui community: Migration, settlement and sects (Richmond, 1999), pp. 21 3.

165

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

allowed merchants to continue their money lending activities, and their practices contributed to the Chinese dislike of Muslims in the Mongol period.

From Mongke's reign onwards much of China was under the oversight of Qubilai. Like Mongke, he attempted to rein in the power of the ortoq merchants, but after a rebellion in 1261 which involved Chinese officials he

turned to foreigners to staff his administration. Qubilai instituted a systematic

classification of population according to ethnicity: Mongols had the highest

status, western and Central Asians (se mu) came second, then northern Chinese. In theory, the highest offices were reserved for the Mongols and se mu, who also enjoyed tax privileges and the right to bear arms. We cannot

tell what proportion of offices were held by Muslims, but it is clear that they

remained active through the Yuan period, especially in the financial sphere.

The highest financial position, control over the Central Secretariat of north

China, went to the Muslim Ahmad, who remained in office for over twenty

years and succeeded in raising revenue at the cost of his own popularity. He was murdered in 1282 and is recorded in Chinese historiography as an evil

minister. One should note however that his non Muslim successors were equally unpopular.

Another Muslim official won the opposite reputation; this was Bukharan Sayyid Ajall (d. 1279), whom Qubilai appointed governor of the border region

Yunnan in 1274. While he is remembered for introducing Chinese culture into

Yunnan, he also presided over an influx of Muslim people, who created a sophisticated irrigation system. He was succeeded in office by his son, who

remained to 1291, and from this time on Yunnan contained a significant Muslim minority. 12,2 In 1279 Qubilai received help from the Muslims of the

southern cities in conquering the Southern Song. The Muslim official Pu Shougeng, who had gone over from the Song into Qubilai's service, was appointed supervisor of maritime trade for Kwantung and Fukien. 123

Despite the usefulness of Muslims, Qubilai was not immune to public feeling against them, particularly after 1278, when rebellions began along the

north western frontier. In 1280 he forbade circumcision and made the slaugh

ter of animals according to sharfa rites a crime punishable by death. In 1287

however he was persuaded to rescind many restrictions on the grounds that

they would discourage the western merchants needed for China's prosperity.

Swings in policy continued after his death in 1294, and the enthronement of a

122 Paul D. Buell, 'Saiyid Ajall (1211 1279)', in de Rachewiltz et al. (eds.), In the service, PP- 474 9-

123 Morris Rossabi, 'The Muslims in the early Yuan dynasty', in John D. Langlois (ed.), China under Mongol rule (Princeton, 1981), pp. 270 5.

166

Cambridge Histories Online © Cambridge University Press, 201 1

The Mongols and the Islamic world

new emperor often meant a change in the position of Muslims. By 1368, when

the Ming dynasty overthrew the Yuan, China had a sizeable Muslim popula

tion spread over several provinces. During the Ming the community contin

ued to grow and at this time many intermarried with Chinese and began to

adopt Chinese language and culture. 124 Only in the north west did most Muslims retain a separate linguistic identity.

#### Conclusion

Within the Islamic regions the Mongols brought at once devastation and new

initiatives. In their attempts to centralise administration, the khans faced determined resistance from the Mongol elite, particularly in fiscal affairs. The constant political contests after Chinggis Khan's death exacerbated similar

tendencies in the Middle East. Since neither Islamic nor Mongolian tradition

favoured primogeniture, there were frequent succession struggles, and the

Mongol period was one of particularly intense factionalism. Not many men of

power, whether bureaucrats or commanders, died of natural causes. The only

way to achieve an orderly administration was to rule for a long time, and here

Mongol rulers were handicapped by their excessive consumption of alcohol.

Leadership required constant feasting, accompanied by the drinking of both

fermented and distilled alcohol. The resulting alcoholism was a common cause of death, and both the Great Khans and the Ilkhans had unusually short reigns.

Mongol rule marks the end of what might be called the classical age of Arab

Muslim culture and Islamic societies emerged from it more diverse and more

expansive. As Mongols centred themselves in the north, trade routes changed

and new regions came to the fore. Mongol rule did not extend into Syria or

Egypt, thus creating a separation between Iran and the Arab cultural region of

the Mamluk sultanate. 125 From this time on, the Middle East remained divided

into three major cultural zones, one primarily Arab, one primarily Iranian and

one primarily Turkish. Like the Saljuqids, the Mongols entered through eastern Iran and gave a central place in their administration to Persian bureau

crats; they also adopted elements of Iranian legitimation. The promotion of

Persian traditions combined with cultural borrowing to create new Persian

124 Dillon, China's Muslim, pp. 27 9.

125 Bert Fragner, 'Ilkhanid rule and its contributions to Iranian political culture',

Komaroff(ed.), Beyond the legacy, pp. 68 80.

167

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

styles increasingly distinct from Arab culture. As the Islamic religion spread to

new areas, it was often marked by Persian as well as Mongol influence.

By destroying the central caliphate, the Mongols inaugurated a new era in

which it was possible to assert sovereign rule over one part of the Islamic world.

This act made possible the great empires of the early modern period the Ottomans, Safavids, Mughals and Uzbeks, each of which fostered a unique

cultural complex, while sharing many elements of the mixed culture that developed under the Mongols.

5

Tamerlane and his descendants: from paladins to patrons

## MARIA E. SUBTELNY

#### Introduction

The nearly simultaneous dissolution of the Mongol successor states of the Ilkhans in Iran, the Chaghadayids in Central Asia and the Golden Horde in the

Qipchaq, or Eurasian, steppe during the fourteenth century was paralleled in

the far east by the unravelling of the Mongol Yuan dynasty in China, and in the

far west by the eventual displacement of the Bahri Mamluk state in Egypt by

its Circassian counterpart. These political developments following the period

of the great pax mongolica, which under the Chinggisid dispensation had brought together east and west, Turk and Iranian, Arab and Mongol in a vast international mercantile and cultural enterprise, resulted in the creation

of what has traditionally been viewed as a political vacuum, particularly in the

eastern Islamic world, and they mark the transition between the beginning

and end of what Marshall Hodgson referred to as the Islamic Later Middle

Period (1250 1500). z See Map 3 for this chapter.

With the death of the last Ilkhanid ruler, Abu Sa'id, in 736/1335, greater Iran

and Central Asia became the arena for competing political factions, some of

which succeeded in establishing local control in the form of dynastic states.

Originally a Mongol tribe in Ilkhanid service, the Jalayirids established them

selves in north western Iran and Iraq, eventually prevailing over their rivals,

the Chopanids. The Muzaffarids, who were of Arab descent, carved out a

political niche for themselves in southern and western Iran, in the process

absorbing the short lived dynasty of the Injuids, who ruled over Fars. In western Khurasan, the revolutionary Shi'i state established by the Sarbadar

rebel movement, which was centred on Sabzavar, managed to maintain itself

for about fifty years despite a highly unstable and confused chronology. And in

1 Marshall G. S. Hodgson, The venture of Islam: Conscience and history in a world civilization,

vol. II: The expansion of Islam in the Middle Periods (Chicago, 1974), pp. 371 3.

169

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

eastern Khurasan, the Kart (or Kurt) kings ruled lavishly, albeit precariously,

from what would later become the great Timurid capital of Herat (in present

day north western Afghanistan). These independent and semi independent

polities were in constant flux, their political fortunes waxing and waning, and

even when they encroached on the territories of their neighbours they often

lacked sufficient power to sustain control over them. The prevailing climate

was thus one of political instability and social ferment, which was aggravated

by the general decline of the agrarian economy as a result of the Mongol invasions of the previous century.

The restoration of political order and the re establishment of balance in the eastern Islamic world was the result of the ruthless empire building strategies of the nomadic warlord Tamerlane (Turkic form, Temiir; Persianized form, Timur or Taymur) during a thirty five year period lasting roughly from 1370 until his death in 807/1405. All of the aforemen

tioned states would at some point towards the end of the fourteenth century be conquered or annexed by Temiir in his drive to create a neo Mongol empire in terms of both geographical extent and Chinggisid ideology. Like most so called nomadic empires, Temiir's fell apart almost immediately after his death, as he had made few provisions either for an orderly succession or for the establishment of a bureaucratic administration, having spent most of his life conducting military campaigns. Despite the initial political chaos, Temiir's descendants, referred to collectively as the Timurids, managed to rule important fragments of the empire for an entire century and their concern for fiscal administration and agricultural development, sophisticated court culture and patronage of the arts and architecture assured them pride of place in the cultural history of the eastern Islamic world.

Temur: charismatic authority and Chinggisid tradition

Temiir's authority was based on the Turko Mongolian concept of leadership

based on charisma, which according to the typology developed by Max Weber

represents one of the forms of legitimate domination in history. Extremely

adept at manipulating his own image, Temiir adopted the title sahib qirdn,

meaning one whose manifest destiny is governed by the auspicious conjunc

tion of the planets Jupiter and Venus, and he linked himself genealogically not

only to Chinggis Khan (d. 1227), the founder of the Mongol empire, but also to

'All b. Abi Talib (d. 661), the first Shi'i imam and foremost member of the

170

Cambridge Histories Online © Cambridge University Press, 201 1

Tamerlane and his descendants

family of the Prophet Muhammad. 2 A powerful psychological portrait of

Temiir was drawn by Ibn Arabshah in his polemical Arabic history, 'Aja'ib al maqdur fi nawd'ib Taymur, completed in 839/1435. 3 In an effort to portray

himself as the new avatar of the Chinggisid dispensation, Temiir fostered an

elaborate personal myth that had many similarities with the legends surround

ing the youth and early career of Chinggis Khan. Timurid historians even assigned to him a birth date designed to coincide with the year of the death of

the last Ilkhanid, Abu Sa'id, thereby suggesting an unbroken continuum of

Chinggisid rule in West Asia. 4 Temiir's marriage to a Chinggisid princess (the

daughter of Qazan Khan) gave him the right to use the title kiirgan, or imperial

son in law, which was also adopted by several of his descendants, and he attempted to revive the Chinggisid house through the elevation of puppet khans in the Ulus Chaghadai. 5

Temiir's claims to a Chinggisid connection have often been dismissed by scholars as pretensions inadequate to satisfy the requirement of Chinggisid

descent that had become the main legitimating factor in Central Asian politics.

Although he may not have been of direct Chinggisid descent, Temiir was nevertheless the scion of a prominent Mongolian tribal family the Barulas (Turkic form, Barlas) that had been closely associated with the house of Chinggis Khan's second son, Chaghadai. As recent research has demonstrated,

the Barlas had belonged to Chinggis Khan's keshig, or imperial guard corps,

which was a central institution of imperial Mongol rule, and Temiir's tribal

ancestor Qarachar Noyon, who figures prominently in Timuro Chinggisid genealogical history, had apparently been the head of the guard corps assigned

to Chaghadai, whose appanage included the region of Transoxania. In accordance with the model of the Mongol patrimonial household, whereby

2 Maria E. Subtelny, Timurids in transition: Turko Persian politics and acculturation in

medieval Iran (Leiden, 2007), pp. 11 13.

3 J. H. Sanders (trans.), Tamerlane or Timur tfte Great Amir: From the Arabic life by Ahmed Ibn

Arabshah (London, 1936); and R. D. McChesney, 'A note on the life and works of Ibn

'Arabshah', in Judith Pfeiffer and Sholeh A. Quinn (eds.), History and historiography ofpost

Mongol Central Asia and the Middle East: Studies in honor of Professor John E. Woods

(Wiesbaden, 2006), pp. 205 49.

4 Abu Sa'id died on 13 Rabi' II 736/30 November 1335, and the date of Temiir's birth is

sometimes given as 25 Sha'ban 736/8 April 1336.

5 Jean Aubin, 'Le khanat de Cagatai et le Khorassan (1334 1380)', Turcica, 8, 2 (1976), p. 54;

Beatrice Forbes Manz, The rise and rule of Tamerlane (Cambridge, 1989), pp. 14 15; and

John E. Woods, Timur's genealogy', in Michel M. Mazzaoui and Vera B. Moreen (eds.),

Intellectual studies on Islam: Essays written in honor of Martin B. Dickson (Salt Lake City, 1990), pp. 108 9.

6 S. M. Grupper, A Barulas family narrative in the Yuan Shih: Some neglected prosopo

graphical and institutional sources on Timurid origins', Archivum Eurasiae Medii Aevi, 8

(1992 4), pp. 21 38, 60 1 and 77 81; and Shiro Ando, Timuridische Emire nach dem Mu'izz

171

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

members of the imperial guard corps were appointed to the highest ranks of

government administration, Qarachar Noyon became Chaghadai Khan's chief

administrator as well as chief judge of the yarghu, or court of investigation,

through which Mongol law was enforced. 7

The Barlas tribe thus occupied an important position in Transoxiana, where

it had held the hereditary command of the tiimen of Kesh still from Qarachar

Noyon's time. This, incidentally, provides an explanation for Temiir's cus tomary title amir ('commander') or amir i buzurg ('the great commander'),

which may be interpreted as an abbreviation of amir i tiimen, referring to his

command of this former Mongol military administrative district. As the descendant of the head of Chaghadai Khan's keshig, Temiir would have remained loyal not only to the house of Chaghadai but also to the yasa, or Chinggisid customary law, of which Chaghadai had been designated official

custodian by his father and of which Qarachar Noyon had been yarghuchi, or

chief judge, in the Ulus Chaghadai.

Yasa vs shan'a: Turko-Mongolian custom and Islamic law

Transoxania belonged to that part of the Ulus Chaghadai that had been Islamicised for some time, and Temiir was himself a Muslim, if only nomi nally. Because he came to exercise control over a significant portion of the

Islamic world, Temiir's attitude towards Islam and shan'a law became a question of considerable import and even urgency. Although he did not hesitate to invoke Islamic legality whenever it was to his advantage to do so, Temiir generally favoured the yasa over the shari'a, which prompted Islamic jurists at one point to declare him an infidel. 9

Exactly what legal precepts constituted the yasa is still a matter of scholarly

debate. In its Timurid elaboration, the yasa was usually referred to as the tord

or 'the tord of the Lord of the auspicious conjunction' {tord i sahib giranT}, that

is, Temiir. In a nutshell, it represented Turko Mongolian customary law as

al ansab. Untersuchung zur Stammesaristokratie Zentralasiens im 14. und y Jahrhundert

(Berlin, 1992), pp. 68 9. For the term keshig or keshik, see Gerhard Doerfer, Tiirkische

und mongolische Elemente im Neupersischen, 4 vols. (Wiesbaden, 1963 75), vol. I, pp. 467 9.

7 For this interpretation of Qarachar's role in the Ulus Chaghadai, see Subtelny, Timurids in

transition, pp. 1824.

8 Manz, Rise and rule of Tamerlane, p. 156; and Woods, Timur's genealogy', p. 96. For the

term tilmen, which denoted a military district capable of supplying a contingent of 10,000

men, see Doerfer, Tiirkische und mongolische Elemente, vol. II, pp. 632 42.

9 Ahmad b. Muhammad Ibn 'Arabshah, 'Aja'ih al maqdur fi nawd'ih Taymur, ed. Ahmad Fa'iz al Himsi (Beirut, 1407), p. 455.

172

Cambridge Histories Online © Cambridge University Press, 201 1

#### Tamerlane and his descendants

practised by Temiir and his Chaghadai followers. The Timurids cultivated the

torti as a means of maintaining their nomadic military ethos and Chaghatay

identity as distinct from the culture of the Muslim, largely Iranian (Tajik), sedentary population over which they ruled. 10 Just as there appears to have

been no written exposition of the precepts of the Chinggisid yasa, which can

only be partially reconstructed from the sources, so too is the nature of the

Timurid torti known only through random references in the contemporary

Persian, Arabic and Turkish sources that identify specific customs and practi

ces as belonging to it, often through negative comparison with Islamic prescriptions. Probably the single most important feature of the torti that conflicted with sharl'a law was the yarghu, or Turko Mongolian court of investigation. Although it was supposedly abolished during the reign of Temiir's son Shah Rukh, the yarghu continued to exist, along with many other Turko Mongolian practices, until the end of the dynasty's rule in Iran.

Temiir's early career and conquests

Politically, the western Ulus Chaghadai where Temiir began his political career represented a confederation of old Mongolian and Turko Mongolian

tribes (such as the Suldus, Barlas, Arlat, Jalayir, Yasa'uri and Apardi), local

commanders with their own tribal armies (such as the Khuttalani amirs), and

metis Qara'unas tribes, all of whom vied with each other for power, under the

nominal rule of Chinggisid khans of the line of Chaghadai. The political turmoil of the period lent itself to the emergence of a series of strong men.

most of whom were tribal commanders of non Chinggisid background. Temiir emerged in the political arena around 761/1360 when he was appointed

head of the Barlas tribe to replace Amir Hajji Beg, who had fled the Ulus at the

time of the invasion of the eastern Chaghadayid (Mughul) khan Tughluq Temiir. When Temiir was granted control of the ancestral tiimen of Kesh, he

allied himself with the powerful Qara'unas leader Amir Husayn in his bid to

become head of the western Ulus. But when Hajji Beg Barlas returned from

exile, and the troops of the Kesh tiimen deserted Temiir, he returned his allegiance to Hajji Beg. Another invasion by the Mughuls in the following year, and the appointment of Ilyas Khwaja Khan as ruler of western Chaghadai, put an end to Hajji Beg's political ambitions. Temiir again allied

himself with Amir Husayn and even helped him gain a military victory over the

Mughuls, but the two soon found themselves in competition, and when Amir

10 For the term torn, see Doerfer, Tiirkische und mongolische Elemente, vol. I, pp. 264 7.

173

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Husayn seized control of the Ulus in 767/1366 in the name of a Chinggisid

puppet khan, Temiir was forced to seek refuge in the region around Marv where he spent the next two years freebooting, as a political vagabond.

Temiir has often been portrayed as a common brigand or horse thief before

coming to power in the Ulus, but such a characterisation does not do justice to

the importance in steppe politics of the period of qazaqliq (Persianized form,

qazaqt), or political vagabondage, during which an aspiring tribal leader assembled a loyal following and forged political alliances that were often strengthened by marriage and commercial ties." The socio political institution

of qazaqliq was informed by the patrimonial and highly personal nature of

relations in the early Timurid state, and those who supported Temiir during

his period of political vagabondage were subsequently appointed to leading

military administrative positions.

By 771/1369 Temiir had assembled a military force, which included the aristocracy of the Barlas tribe, and defeated Amir Husayn, who was later executed by Timurid amirs. After being confirmed as leader of the Ulus at a

quriltai, or tribal gathering, in the spring of 771/1370, Temiir set himself up in

the capital city of Samarqand, ruling through a Chinggisid puppet khan from

the line of Ogedei. Temiir's control over the tribes of the Ulus would remain

precarious for over a decade, however, and the campaigns of conquest which

he launched almost immediately were designed primarily to harness these

tribal energies and channel them into his evolving political enterprise.

During the 1370s Temiir asserted his authority over the eastern part of the

Ulus Chaghadai in a series of short campaigns against Mughulistan, Khwarazm and the Qipchaq steppe. By 777/1375 he annexed the Farghana

valley region and appointed his son 'Umar Shaykh governor of Andijan. After

installing a governor in Kashghar in 779/1377L, he maintained his claim to the

region by campaigning as far as the Irtysh and Yulduz rivers. Repeated campaigns were made against the Qungirat Sufi dynasty of Khwarazm in 773 4/1372 3. Temiir's first expedition to the Qipchaq steppe took place in

778 9/1376 7onbehalfofToqtamish, a pretender to the leadership of the Blue

Horde, whom Temiir had set up in 777/1376 in the region of Utrar north of the

Syr Darya river. Even after Temiir Malik, the son and successor of the Jochid

11 See Annemarie von Gabain, 'Kasakentum, eine soziologisch philologische Studie', Acta

Orientalia Academiae Scientiarum Hungaricae, 11, 1 3 (i960), p. 162; Stephen F. Dale, The

garden of the eight paradises: Babur and the culture of empire in Central Asia, Afghanistan and

India (1483 1530J (Leiden, 2004), pp. 98 100; and Subtelny, Timurids in transition, pp. 29

32. For Temiir's marriage alliances during this period, see Manz, Rise and rule of

Tamerlane, pp. 46 and 57.

174

Cambridge Histories Online © Cambridge University Press, 201 1

## Tamerlane and his descendants

khan Urus, defeated Toqtamish, the latter remained khan in Sighnaq in accordance with Temiir's wishes. In 779/1377^, Toqtamish captured leader

ship of the Blue Horde from Temiir Malik and by 784/1382 he extended his

control over the Golden Horde after defeating its ruler, Mamay, in 782/1380

and raiding the Russian principalities as far as Moscow, which he sacked in

784/1382.

Temiir's first campaigns against Iran began in 1380 1 with incursions into the

agriculturally rich, eastern province of Khurasan, and he appointed his son

Miranshah its governor in 782/1380. Although the Kart kings, who ruled from

Herat, were initially allies, Temiir occupied the city in 783/1381. Later, after a

major rebellion in Herat in 785/1383, the Kartid ruler was removed and his

territory annexed. Also in 783/1381 Temiir took over the region of Kalat and

Tus, which had been held by the Turko Mongolian Ja'un i Qurban tribe, who

eventually surrendered to him, and he accepted the submission of the Sarbadar

state of Sabzavar, whose chiefs rallied to his support. In 785/1383 he conquered

SIstan. He then turned to the western regions of Iran. In 786/1384 he took

Astarabad in Mazandaran, which he entrusted to the Ilkhanid prince Luqman b.

Togha Temiir, and he expelled the Jalayirid dynasty from Sultaniyya in Azerbaijan. The goal of this first phase of operations against Iran, which did

not result in the establishment of firm administrative control over the con quered regions, appears to have been to extract ransom money and acquire

booty for Temiir's treasury and for rewarding his troops.

Toqtamish's attack on Tabriz in 787/1385<sup> </sup>occasioned Temiir's campaign against western Iran and the Caucasus and inaugurated a decade long contest

between the two nomadic warlords, which was reminiscent of the rivalry between the Golden Horde of the Qipchaq steppe and the Ilkhanids of Iran.

This three year campaign, as it was dubbed by the Timurid historians, which

began in 788/1386, was the first of Temiir's major campaigns against Muslim

West Asia. In 788/1386, he campaigned in Luristan, wrested Tabriz from the

Jalayirids and subjugated Georgia after taking Tiflis by storm. In 789/1387, he

sent his son Miranshah to Azerbaijan to counter Toqtamish, who was defeated. Temiir then campaigned in the Lake Van region against the Qara

Qoyunlu, as well as in Kurdistan. In the same year he secured the submission

of Isfahan, which was under the rule of the Muzaffarids, but a revolt of the

population occasioned a general massacre in which 70,000 were estimated to

have been killed. News of the massacre facilitated the capture in the same year

of Shiraz, which was entrusted to a Muzaffarid vassal.

In response to the pillaging of Transoxania in 789/1387 by Toqtamish, who

had gained the support of the Qungirat Sufi dynasty and the eastern

175

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Chaghatayids, Temiir launched a series of punitive campaigns against him and

his allies during the years  $789\ 98/1387\ 96$ . In 789/1387 he seized and sacked

the city of Urganj in Khwarazm, which had been ruled by the Sufi dynasty, and

deported its population. Two campaigns were waged against Khidr Khan, the

ruler of Mughulistan. Temiir then turned to the Qipchaq steppe and in 793/1391 defeated Toqtamish north of the Samara river, installing a new khan in the Golden Horde. Toqtamish recovered control of the Golden Horde, however, and in the following year raided the region of Shirwan in

the Caucasus. Temiir finally defeated Toqtamish in 797/1395 at the Terek river. After a looting spree along the Volga river, then down to the Crimea,

then back up again along the Don, he ended up in the northern Caucasus, where he campaigned against the Circassians and Alans. In the winter of 798/1395, he sacked the Golden Horde capital of New Saray near the Volga, as

well as Hajji Tarkhan (Astrakhan). He left the Qipchaq steppe in 798/1396 and,

although he did not establish permanent control, the Golden Horde never fully recovered from his depredations.

At the same time, Temiir inaugurated the so called five year campaign against Iran, which lasted 794 8/1392 6, with attacks against Mazandaran.

while Luristan and Kurdistan were pacified by his sons. In 795/1393 he extinguished the Muzaffarid dynasty in southern Iran and appointed his son

'Umar Shaykh governor of the region. He appointed his other son Miranshah

governor of western Iran ('Iraq i Ajam) and Iraq ('Iraq i 'Arab), and having

secured the support of the Aq Qoyunlu, he proceeded to oust the Jalayirids

and Qara Qoyunlu who still held sway here. In 795/1393 he captured Baghdad

from the Jalayirids and appointed a Sarbadar chief as governor. (However,

Sultan Ahmad Jalayir recovered control of the city a year later.) In 796/1394,

Diyarbakr and al Jazira were taken. In 798 / 1396, on his way back from his final

expedition against Toqtamish, Temiir campaigned in Georgia, Azerbaijan and Fars.

Temiir's next campaign was directed against northern India and in 800/1397

he sent his grandson Pir Muhammad, who ruled in present day Afghanistan,

ahead to the Punjab. He set off himself in 800/1398 and in the winter of 801/1398 sacked Delhi, after which he campaigned along the Ganges.

After returning to Samarqand in the spring of 801/1399, Temiir decided to

swing back to the west again and in 802/1399 inaugurated the seven year campaign, which would be his longest, lasting 802 7/1399 1404. It was

sioned by Miranshah's apparent inability to deal with unrest in Azerbaijan and

his growing independence in the region. Temiir removed Miranshah, whom

he transferred to his own retinue, and restored order there himself. After

176

### Tamerlane and his descendants

wintering in Qarabagh, he again campaigned against Georgia, storming Tiflis

in 802/1400 and confirming the vassalship of the Georgian king.

On account of his involvement in Turkmen, Kurd and Arab tribal politics, Temiir came into conflict with both the Ottomans and the Mamluks. Relations with the Mamluks were already strained. They had murdered Temiir's ambassador to Cairo and given refuge to his Jalayirid and Qara Qoyunlu opponents; moreover, they had attempted to form an anti Timurid alliance with the Golden Horde. In 803/1400, Temiir attacked Aleppo, which surrendered, and later that same year (803/1401) he took Damascus, which was pillaged by his soldiers and its population massacred

or deported. It was at his camp near the city that he was supposedly visited by

the historian Ibn Khaldun, who was acting as envoy from the Mamluk sultan

al Malik al Nasir Faraj. 12 Taken by storm in 803/1401 from Sultan Ahmad

Jalayir's commander, Baghdad was destroyed and its population massacred. 13

While it has been demonstrated that Temiir's treatment of the towns he captured was generally motivated by a desire to extract booty or ransom money, there can be no doubt that his use of terror tactics, such as the wholesale slaughter of civilian populations and the erection of towers of decapitated human heads, was meant not only to deter popular resistance

but also to enhance his image as a neo Mongol conqueror. 14

As for Temiir's relations with the Ottomans, the extension of Ottoman control over the eastern Anatolian principalities, as well as Ottoman support

of both Ahmad Jalayir and Qara Yusuf, provided Temiir with enough reasons

to conduct an expedition against Anatolia. In  $802/1400\ he$  took Sivas and in the

summer of 804/1402, after wintering in Qarabagh, he defeated the Ottoman

sultan Bayezid I Yildinm at Chubuq Ovasi near Ankara, taking him prisoner.

(Bayezid died in captivity at Aqshehir in 805/1403.) Temiir's grandson Muhammad Sultan was entrusted with the capture of Bursa, which he burned

to the ground in 805/1402. Campaigning deep into Ottoman territory, Temiir

reached as far as Izmir (Smyrna) on the Aegean coast. He obtained the submission of the Byzantine emperor at Constantinople, and later on that of

Bayezid's son Siileyman. Temiir's invasion disrupted Ottoman territorial expansion and consolidation, but because no permanent administrative struc

tures had been put in place, the Ottomans soon resumed their empire building

 $12\ Walter\ J.$  Fischel, Ibn Khaldun and Tamerlane: Their historic meeting in Damascus,  $1401\ AD$ 

(803 AH): A study based on Arabic manuscripts of Ibn Khaldun's Autobiography' (Berkeley and Los Angeles, 1952).

13 Jean Aubin, 'Tamerlan a Bagdad', Arabica, 9 (1962), pp. 303 9.

14 Jean Aubin, 'Comment Tamerlan prenait les villes', Studia Islamica, 19 (1963), pp. 83 122.

177

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

strategies, eventually becoming the paramount power in the region. Turning

east again, Temiir passed through Qarabagh (where he wintered in 806/i403f.), Georgia (which he again laid waste) and Mazandaran (where he put

down a major rebellion), returning to Samargand in 807/1404.

Temiir's last and most ambitious campaign was launched against China right after the great quriltai held in Samarqand in 807/1404, which was attended by many foreign embassies, including a Spanish one headed by Ruy Gonzales de Clavijo, who left a detailed account. 15 But the project was

abandoned when Temiir died upon reaching Utrar in 807/1405.

It appears that Temiir was originally supposed to be buried at Kesh

(Shahr i sabz) in the quruq, or royal preserve, where his sons 'Umar Shaykh and Jahangir had already been buried in the funerary structures connected to the Aq Saray complex. He was eventually buried in Samarqand, however, in what came to be known as the Gur i Amir, which he had constructed in 807/1404, and which was transformed into a dynastic

mausoleum thanks largely to the efforts of Shah Rukh's son Ulugh Beg. Also

buried there, besides Temiir's sons Shah Rukh and MIranshah, his grandson

Ulugh Beg, and his favourite nephew, Muhammad Sultan, was his spiritual

adviser, Sayyid Baraka. 1

## The Timurid state and administration

The Timurid state (the term is applied loosely here) was predominantly military in character. It was based on a tribal military elite and supported by

nomadic cavalry forces. The army was characterised by the use of Turko Mongolian titles, the Chinggisid ranking of military offices, and adherence to

Mongolian battle formations. Offices and titles such as beg and noyon ('commander'), tovachi ('troop inspector'), yasavX ('sergeant at arms'), yurtchi

('quartermaster') and akhtachi ('equerry') reflected long standing Turko Mongolian practice. Besides the paramount Barlas tribe with its various branches, the main tribes represented in the Timurid army and military administration were the Arlat, Jalayir, Arghun, Qungirat, Turkmen, Tarkhan, Uzbek, Ilchikday and Uighur, among others. Whereas some of

15 [Ruy Gonzalez de] Clavijo, Embassy to Tamerlane, 1403 1406, trans. Guy Le Strange (London, 1928; repr. 2005).

16 V. V. Bartol'd, 'O pogrebenii Timura', in V. V. Bartol'd, SocMneniia, vol. II, part 2, ed. Iu.

E. Bregel' (Moscow, 1964), pp. 423 54; and Robert D. McChesney, Timur's tomb: Politics

and commemoration, Central Eurasian Studies Lectures, 3 (Bloomington, IN, 2003).

# Cambridge Histories Online © Cambridge University Press, 201 1

### Tamerlane and his descendants

these enjoyed hereditary positions, others achieved dominance under partic

ular rulers or became prominent only during the later Timurid period. 17

Like all states based on Turko Mongolian concepts of socio political organ

isation, the Timurid polity was essentially patrimonial in nature, personal service to the ruler being one of its defining features. Many official titles, such

as qorchi ('quiver bearer'), bokdviil ('taster'), suchi ('cup bearer') and qushchi

('falconer'), denoted household positions. In point of fact these were impor

tant military administrative positions that reflected an individual's trustwor

thiness and proximity to the ruler in the patrimonial household. There were

also various categories of individuals who enjoyed special privileges and

direct access to the ruler, such as the tarkhans, who were exempt from taxation

and judicial prosecution, and the ichkis ('insiders'), who were members of the

household establishment with close personal ties to the ruler, often through

the institution of foster brotherhood (kokdltashT). 1

Since the Timurid empire was established in the sedentary oases of Central

Asia and Iran, the organisation of military affairs was adapted to the existing

Arabo Persian administrative system of the dlwdn, which was concerned with

the organisation of financial and bureaucratic affairs. The resulting adminis

trative structure was a dichotomous one that distinguished between the military and civilian spheres, thereby reflecting the cultural division between

the Turkic and Tajik (Iranian) segments of society, with the former respon

sible for the conduct of military affairs and the latter in charge of bureaucratic

administration. The distinction between the military and bureaucratic branches became blurred, however, as Tajik (Iranian) bureaucrats became

increasingly powerful in the financial administration of the state and were

even granted membership in the Timurid household establishment. 19

The overarching administrative structure of the dlwdn consisted of two branches, the dlwdn i tovachi, which dealt with military affairs, and the dlwdn i

a'ld (also dlwdn i buzurg or dlwdn i mdl), which dealt with administrative and

financial matters as well as with non Islamic judicial matters, such as the yarghu court. The highest ranking personnel of both dlwdns held the title amir, although the officers of the dlwdn i tovachi traditionally had precedence

over those of the dlwdn i a'ld. An amir could be appointed concurrently to both

dlwdns. Collectively, the amirs of both dlwdns were referred to as 'the great

17 Ando, Timuridische Emire, pp. 66ff.

18 Ibid., pp. 245 52; and Subtelny, Timurids in transition, pp. 33 5.

19 H. R. Roemer, 'The successors of Timur', in Peter Jackson and Laurence Lockhart

(eds.), The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods (Cambridge,

1986), pp. 131 2; and Subtelny, Timurids in transition, pp. 68 70.

179

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

commanders' (Persian, umara yi buzurg; Turkish, ulugh begler), and their respective heads held the title of chief amir (amir al umara'). Other amirs

were appointed as provincial governors (hakim, wall, darugha).

The diwan i a'ld or diwan i mal was staffed by Iranian bureaucrats (often referred to as diwaniyan or ashab i diwan), who exhibited a remarkable con

tinuity of indigenous administrative traditions, as their positions were often

hereditary. Because of the wide scope of its financial and administrative responsibilities, the diwan i a'ld appears to have been organised into several

departments, including the diwan i insha' (chancery), diwan i amlak i khassa

(privy purse) and diwan i sadarat (or diwan i awqaf), which was presided over

by the sadr, the supervisor of pious endowments and religious appointments.

The head of the diwan i a'ld was the chief vizier, and the overseer of the viziers

was called the mushrif. Although the main language of the Timurid chancery

was Persian, the Tajik scribes, or nawisandagan i Tajik, had their Turkic counterparts in the nawisandagan i Turk, who belonged to the diwan i tovachi.

Many of these Turkish scribes, who were proficient in the use of the Uighur

script, had Uighur scribal (bakhshi) backgrounds. Other important bureau

cratic positions were the parwanachl, who was responsible for issuing financial

orders, and the muhrdar, or keeper of the seal, who had the right to authorise

various types of orders by using a particular type of seal. As had always been

the case in Persian chancery practice, the use of seals was widespread, the

most important being the royal seal (muhr i buzurg, muhr i kalan, muhr i humayun), the seal of the parwanachi (muhr i parwana) and the seal used for

tax vouchers (muhr i barat). 2 '

The struggle for succession and the emergence of Shah Rukh

Although the goal of Temiir's conquests appears to have been the restoration

of the Mongol world empire, his far flung realm fell apart soon after his death

in 807/1405. Like Chinggis Khan, Temiir had divided his empire into four parts, each governed by one of his sons or the son's descendants: the eldest,

'Umar Shaykh (d. 796/1394), and his sons held central and southern Iran; 2.1

Jahangir's (d. 777/1376) son Pir Muhammad governed Kabul in the south east;

Miranshah (d. 810/1408) held the western regions with his sons Khalil Sultan

20 See Ando, Timuridische Emire, pp. 223ff.

21 On the question of who was the eldest son of Temiir, see John E. Woods, The Timurid dynasty, Papers on Central Asia, 14 (Bloomington, IN, 1990), p. 14 n. 34.

Cambridge Histories Online © Cambridge University Press, 201 1

## Tamerlane and his descendants

(d. 814/1411) in Armenia and Georgia (later in Rayy), 'Umar (d. 809/1407) in

Azerbaijan, and Aba Bakr (d. 811/1409) in 'Iraqi Arab and Kurdistan; and the

youngest, Shah Rukh, and his sons held Khurasan and the region of Transoxiana

to the north and east. Temur did not designate any of his sons as his successor

during his lifetime, but rather his grandson Muhammad Sultan b. Jahangir, who

died in 805/1403, and then another grandson, Pir Muhammad b. Iahangir. But

even before the latter's murder in 809/1407, a succession struggle ensued that

lasted fifteen years and involved not just immediate members of Temur's family

and the Timurid amirs but also the tribal society of the Ulus Chaghadai, as well

as local dynasts and vassal rulers, some of whom took advantage of the opportunity to assert their independence. Internecine warfare among the Timurid princes, and encroachment by outside powers, including the Golden

Horde, Jalayirids and Qara Qoyunlu, resulted in significant territorial losses in

Khwarazm, 'Iraq i Arab and Azerbaijan.

Shah Rukh, who had been governor of Khurasan since 799/1396<sup>^</sup> was engaged from the time of Temiir's death in putting down rebellions by Temiir's former vassals and in countering the centrifugal tendencies of power

fill Timurid amirs who sought to reassert their authority at his expense. By 811/1409, however, he managed to extend his authority to Transoxania

where he installed his son Ulugh Beg as governor in Samarqand. In 815/1413,

his powerful amir Shah Malik recovered Khwarazm from the Golden Horde.

Campaigns against the sons of 'Umar Shaykh in Fars in  $817\ 18\ /\ 1414\ 15$  resulted

in the appointment of another son, Ibrahim, as governor in Shiraz. But despite

several successful campaigns against the Qara Qoyunlu in 'Iraq i Ajam and

Azerbaijan, these and other regions were eventually lost to the Timurid empire, which was essentially reduced to the two large regions of Khurasan,

with its capital Herat, and Transoxiana, with Temiir's former capital Samarqand. Although Transoxania was the principal site of the succession

struggles after Temiir's death, with Shah Rukh's emergence as the leading

power in 811/1409 the focus of the Timurid realm shifted south to Khurasan.

Shah Rukh was faced with the task of transforming what remained of the Timurid nomadic empire, which had been fuelled by a 'booty economy', into an

Islamic polity based on the regular taxation of revenues derived from agricul

ture and trade. This was dictated as much by fiscal necessity as it was by a desire

to legitimate Timurid rule over a predominantly sedentary Muslim population

that was becoming increasingly restive. In 813/1411 Shah Rukh officially abro

gated the tora and abolished the yarghu court of investigation in favour of a

'return' to shari'a law and Islamic practices, although the effectiveness of these

measures remained limited. The Sunni religious revival initiated by Shah Rukh

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

was supported by the Muslim religious intelligentsia, who portrayed him as the

'renewer of Islam'. Styling himself padishdh i Islam, he even had pretensions to

be recognized as caliph of the entire Muslim world, a claim that was challenged

by the Mamluk sultan. Shah Rukh's Islamicising policies included the prohib

ition of prostitution and the drinking of wine in the capital city of Herat, as well

as the promotion of Islamic missionary activity in such regions as Quhistan, a

traditional Isma'ili enclave. Notwithstanding these policies, Shah Rukh's reign

witnessed the growth of heterodox movements of socio religious opposition,

some of which espoused extremist and messianic views, often with a Shil colouring, such as the cabalistic Hurufiyya, whose adherents even made an

unsuccessful attempt on his life in 830/1427.

The chief means by which Shah Rukh sought to promote Islamic doctrinal orthodoxy were the madrasas he and his wife, Gawharshad (d. 861/1457), constructed in Herat in 8i3/i4iof. and 820 7/1417 24. The mandate of these

educational institutions, which were staffed by prominent Sunm scholars and

jurists, was to ensure the dominant position of the Hanafi and Shafi'i schools

of legal interpretation. The curriculum of Islamic higher learning established

at this time continued to be followed in madrasas in pre Safavid Iran and in

Uzbek Central Asia. 22, On the popular level, Shah Rukh tapped into the widespread practice of the visitation of tombs of Muslim saints by reviving

the burial place of the eleventh century Hanbali traditionist and patron saint of

Herat, Khwaja 'Abd Allah Ansari (d. 481/1089), known as Pir iHarat, which he

developed architecturally into a large shrine complex that became a venue for

ceremonial events of a political nature. The Ansari shrine and cult continued

to be patronised by Shah Rukh's successors, reaching a high point under the

last Timurid ruler of Herat, Sultan Husayn, who even claimed descent from

'Abd Allah Ansari and used his shrine as a dynastic burial place. 23 The tombs of

other famous Sufis and important Muslim religious figures were also accorded

attention, chief among these being the shrine of 'All b. Musa al Rida, a descendant of All b. Abi Talib and the eighth Shi'i imam, at Mashhad, which was developed and endowed principally by Gawharshad and her son

Baysunghur. 24 Timurid patronage of the Mashhad shrine, which included the

22 Maria Eva Subtelny and Anas B. Khalidov, 'The curriculum of Islamic higher learning in

Timurid Iran in the light of the Sunni revival under Shah Rukh', Journal of the American

Oriental Society, 115, 2 (1995), pp. 211 36.

23 Maria Eva Subtelny, 'The cult of 'Abdullah Ansari under the Timurids', in Alma Giese

and J. Christoph Biirgel (eds.), Gott ist schbn und Er liebt die Schdnheit/God is beautiful and

He loves beauty: Festschrift in honour of Annemarie Schimmel (Bern, 1994), pp. 388 92.

24 Lisa Golombek and Donald Wilber, The Timurid architecture of Iran and Turan, 2 vols.

(Princeton, 1988), vol. I, pp. 328ff.

182

### Tamerlane and his descendants

construction of a spectacular congregational mosque, was not motivated simply

by a desire to appease the Shi! population of the region, as has sometimes been

argued; rather, it represented a reassertion of the long standing Sunni tradition

of veneration of the ahl al bayt, or family of the Prophet, in Iran and Central Asia,

as well as an expression of the deep reverence Turko Mongolian dynasts had for

saints and holy men of all religious stripes.

An important legacy of Shah Rukh's reign was the professionalisation of the

financial administration. Under the chief vizier, Ghiyath al Din Pir Ahmad Khwafi, who headed the dlwdn from 820/1417 until Shah Rukh's death in 850/1447, standard bureaucratic procedures such as the use of accounting

notation (siyaqat) and the keeping of ledger books (daftaf) were introduced. 25

Ghiyath al Din Pir Ahmad subsequently served in the administrations of several other Timurid princes (including Abd al Lafif, 'Ala' al Dawla, Sultan Muhammad and Abul Qasim Babur) until his death in 857/1453. His

son Majd al Din Muhammad Khwafi followed in his footsteps, beginning his

career in the chancery of Sultan Abu Sa'id and eventually becoming chief executive officer in the administration of Sultan Husayn Bayqara in 876/1472,

until his dismissal in 895/1490. Thus, for roughly three quarters of a century,

two generations of the Khwafi family exerted a profound influence on the financial administration of the Timurid state, which they attempted to central

ise on the Perso Islamic model. 2

During Shah Rukh's reign, regular diplomatic and trade relations were established between the Timurid state and the Ming dynasty. The items exchanged consisted largely of silk fabrics, paper money and porcelains provided by the Chinese in return for such commodities as jade and horses.

Although Shah Rukh expressed hope that the Ming emperor would convert to

Islam, facilitating trade appears to have been the main concern on both sides. 27

Ulugh Beg: scientific achievement

Shah Rukh's death in 850 / 1447 precipitated another struggle for power among

the Timurid princes, as most of his sons had predeceased him. His only remaining son, Ulugh Beg, born Muhammad Taraghay, who had been

25 Ghiyath al Din b. Humam al Din Khwandamir, Dastiir al wuzard", ed. Sa'id Nafisi

(Tehran, 1317; repr. 2535/1976), pp. 353 7; and Sayf al Din Hajji b. Nizam 'Uqayti, Athar

al wuzard', ed. Mir Jalal al Din Husayni Urmawi 'Muhaddith' (Tehran, 1337), pp. 342 3.

26 For Majd al Din Muhammad Khwafi, see below.

27 Ralph Kauz, Politik und Handel zwischen Ming und Timuriden. China, Iran und Zentralasien im Spatmittelalter (Wiesbaden, 2005), pp. 93 143.

183

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

governor of Samarqand since 811/1409, eventually succeeded him after defeat

ing his nephews Aba Bakr b. Muhammad Juki (d. ?852/?i448) and 'Ala' al Dawla b. Baysunghur (d. 865/1460) in 852/1448 in Khurasan. However, because he preferred to remain in the original Timurid seat of power in Transoxania, Ulugh Beg failed to consolidate his victory. When he was called

to the defence of Samarqand, he left Herat in the hands of his son Abd al Latif, who was unable to hold on to it for more than a few months. Ulugh Beg thus

lost control of Khurasan, which by that time had come to be regarded as key to

Timurid hegemony.

Concentrating his political and cultural efforts on Transoxania, Ulugh Beg

ruled Samarqand in a semi independent manner until 853/1449. During the

early part of his father's reign, he had helped reaffirm Timurid authority in

such regions as Farghana and Mughulistan. In 830/1427, however, he was

defeated on the Syr Darya by the khan of the Blue Horde, and in 1435 the eastern Chaghadayids took back Kashghar. A much more significant threat

was posed by the nomadic Uzbek confederation that had been created in the

Qipchaq steppe under the leadership of the Jochid ruler Abul Khayr Khan,

who during the 1440s established himself in the northern Syr Darya region and

in 852/1448 launched a raid into Transoxania, looting and burning the region

around Samarqand. Abul Khayr Khan took advantage of the struggles among

the Timurid princes to intrude into Transoxanian politics. After two years of

fighting following the death of Shah Rukh, the already fractured Timurid empire was further divided into three principal parts: Transoxania under Ulugh Beg; 'Iraq i Ajam and Fars under Muhammad b. Baysunghur; and Khurasan under Abul Qasim Babur. In 853 / 1449 Ulugh Beg's son Abd al Latif,

who was governor of Balkh and with whom he had strained relations, rebelled

against him, and after a humiliating defeat Ulugh Beg was forced to submit. In

an act that occasioned universal disapproval, Abd al Latif had his father murdered. In 854/1450, after a brief rule in Samarqand, he was himself killed

by Ulugh Beg's amirs.

Ulugh Beg has come to be known primarily for his scientific interests and organisation of advanced scientific study at Samarqand. A competent astron

omer himself, who had been tutored in his youth by the famous astronomer

Qadizada Rumi (d. c. 840/1436) of Bursa, Ulugh Beg assembled a large group of

scientists, including the Persian mathematician Ghiyath al Din Jamshid Kashi

(d. 832/1429) and the astronomer 'Ala' al Dm AE Qushchi (d. 879/1474), at his

court. In 823/1420 he oversaw the foundation of an astronomical observatory,

probably modelled on the famous Ilkhanid observatory at Maragha, the most

conspicuous feature of which was its meridian transit instrument, which had a

Cambridge Histories Online © Cambridge University Press, 201 1

## Tamerlane and his descendants

radius of approximately 40 metres. The most celebrated and lasting achieve

ment of the Samarqand observatory was the completion (in 1437 48) of a new

set of astronomical tables (zij), which contributed greatly to knowledge in the

field of theoretical astronomy. Impressive advances were also made in the field

of computational mathematics, including the calculation of n and the application

of the decimal place value system to fractions, and in the trigonometric tables of

Ulugh Beg's zij, with their prodigiously accurate sine table. 2,

Ulugh Beg has sometimes been portrayed as ruling Transoxania more in the neo Mongol style of his grandfather, Temiir, than in accordance with the

Islamicising policies of his father, Shah Rukh. Although this is to some extent

true, it rather reflects the often uneasy coexistence of Turko Mongolian and

Perso Islamic customs that characterised the early Timurid period as a whole.

Deeply concerned with Chinggisid genealogical history, Ulugh Beg was apparently responsible for the composition of a history of the Chinggisids,

entitled TdrTkh i arba' ulus, which is an important source for the chronology of

the later Chaghadayids. In what appears to have been an attempt to assert the

primacy of Samarqand in Timurid dynastic culture, he transferred his father's

body from Herat to the Gur i Amir mausoleum in 852/1448. At the same time,

he was also the founder of important madrasas in Samarqand and Bukhara.

Despite his efforts, however, he was unable to gain the support of the religious

establishment. His difficult relationship with his sons, military defeats, as well

as the disintegrating state of Timurid politics, all contributed to his demise. 29

# Sultan-Abu Sa'id: administrative continuity

The Timurids were never able to implement a policy of the rational transfer of

power based on the principle of primogeniture because they adhered to the

concept of corporate sovereignty, which held that every male member of the

paramount clan was eligible to succeed the previous holder of power. With

four competing Timurid lines and scores of uncles, cousins and grandsons, the

Timurid polity was plunged with predictable regularity into internecine warfare. After the death of Abd al Latif in 854/1450, Sultan Abu Sa'id, a grandson of Miranshah, emerged as the next leading candidate for the con

tested Timurid throne. 30

28 E. S. Kennedy, 'The exact sciences in Timurid Iran', in The Cambridge history of Iran, vol. VI, pp. 568 80.

29 V. V. Bartol'd, 'Ulugbek i ego vremia', in Bartol'd, Sochineniia, vol. II, part 2, pp. 25 196.

30 'Sultan' is a component of this double name, not a political tide. The Timurids often used the

title mirza, an abbreviated form of amirzaAa, meaning 'descended from the amir' (i.e. Temiir).

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

Sultan Abu Sa'id, who had earlier been in the service of Ulugh Beg, succeeded in capturing Samarqand in 855/1451 with the aid of the Jochid Abu'l Khayr Khan. Another Timurid contender, Abul Qasim Babur, who was of the line of Shah Rukh, challenged him by invading Transoxania in 858/1454 from his base in Khurasan. Sultan Abu Sa'id took advantage of the

anarchic situation following Abu'l Qasim Babur's death in 861/1457 to occupy

Herat, at which time he had Shah Rukh's widow, Gawharshad, executed for

allegedly conspiring against him. After a brief Qara Qoyunlu interregnum in

862/1458, Sultan Abu Sa'id took Herat again and in 863/1458 formally occu

pied the throne for a second time. His defeat of a coalition of Timurid princes

in 863/1459 resulted in the elimination of a significant number of rivals.

Although he ruled over Khurasan, Transoxania, Mazandaran and parts of Afghanistan, Sultan Abu Sa'id's hold on these territories was precarious, as he

was pressured on the one hand by incursions on the part of the Uzbeks and the

eastern Chaghadayids, and on the other by another rising Timurid contender.

Sultan Husayn Bayqara, of the line of 'Umar Shaykh, who in 865/1461 made an

attempt to capture Herat. Because of the continual warfare, agricultural activity in Khurasan had been interrupted, and a terrible famine ensued in

Herat and its dependencies in the winter of 863/1458. As for areas to the west

of Khurasan, the Qara Qoyunlu leader Jahanshah, who had been kept in check

in Azerbaijan by Shah Rukh, extended his power over central and western

Iran, effectively putting an end to Timurid control over these regions. A modus vivendi was eventually established with the Timurids, but this came

to an abrupt end in 872/1467, when Jahanshah was killed and the Qara Qoyunlu confederation was destroyed by the Aq Qoyunlu under the leader

ship of Uzun Hasan. The need to stem the growing power of the Aq Qoyunlu

resulted in an ill fated campaign against Azerbaijan, in the course of which

Sultan Abu Sa'id was captured and handed over to yet another Timurid pretender to the throne of Herat, Yadgar Muhammad, who put him to death in 873/1469 in order to avenge the murder of Shah Rukh's widow, Gawharshad. 32 From now on, the ever shrinking Timurid realm would be

reduced to the two main provinces of Khurasan and Transoxania.

Although it began badly, Sultan Abu Sa'id's eleven year reign in Herat was

by all accounts a beneficial one. Thanks largely to the efforts of competent

administrators, in particular the vizier Qutb al Din Ta'us Simnani, who

31 Ghiyath al Din b. Humam al Din al Husayni Khwandamir, Hainb al siyarfiakhbdr afiad i

bashar, ed. Jalal al Din Huma'I, 4 vols. (Tehran, 1333; 3rd repr. 1362), vol. IV, pp. 67 77.

32 Khwandamir, Habib al siyar, vol. IV, pp. 87 93.

186

Cambridge Histories Online © Cambridge University Press, 201 1

Tamerlane and his descendants

focused his energies on the agricultural development of Khurasan and the

construction of major irrigation works, Sultan Abu Sa'id laid the foundation

for the agricultural prosperity that characterised the reign of his eventual

successor, Sultan Husayn Bayqara. 33

Sultan-Husayn Bayqara: from political vagabond to princely patron

Sultan Husayn Bayqara, a great grandson of 'Umar Shaykh, started his career

in the retinue of his cousin Abul Qasim Babur in Herat. After the latter's death

in 861/1457, he entered the service of his cousin Sanjar (d. 863/1459) in Marv.

A falling out with Sanjar forced him into the first of several periods of political

vagabondage (qazaqliq) in the region around Marv and in the deserts of Khwarazm. In 862/1458, he succeeded in taking Astarabad from the Qara Qoyunlu, but he soon clashed with Sultan Abu Sa'id, who retook it from him

in 864/1460, forcing him to flee. Sultan Husayn now began another period of

political vagabondage in Khwarazm, during which he tried to gain the support

of Mustafa Khan, the Uzbek ruler of the region. In 865/1461, he was able to

recapture Astarabad again, after which he made an ambitious bid for Herat,

to which he laid siege. But he was forced to retire to Astarabad and again fled

to Khwarazm before Sultan Abu Sa'id's approaching army. In 866/1461, he

made yet another unsuccessful attempt to conquer Khurasan but was again

forced into a long period of qazaqliq, which lasted seven and a half years. It was

not until Sultan Abu Sa'id's death in 873/1469 that Sultan Husayn was finally

able to capture Herat and proclaim himself ruler. In order to re establish order

as quickly as possible and gain the support of the religious intelligentsia, he

proclaimed his intention to govern Timurid Khurasan according to Islamic

principles. 34

Sultan Husayn's first period of rule in Herat, which lasted only about fifteen

months, was challenged by Yadgar Muhammad, a great grandson of Shah Rukh, who had been supported first by Jahanshah Qara Qoyunlu against Sultan Abu Sa'id and then, after Jahanshah's death, by the Aq Qoyunlu am.Tr

Uzun Hasan. Yadgar Muhammad managed to take the city for a short while in

875/1470 before being captured and executed by Sultan Husayn, who acceded

to the throne of Herat for a second time. 35 Sultan Husayn thus ruled Herat for

33 M. E. Subtelny, 'A medieval Persian agricultural manual in context: The Irshdd al zird'a

in late Timurid and early Safavid Khorasan', Studia Iranica, 22, 2 (1993), pp. 184 9.

34 Khwandamir, Habtb al siyar, vol. IV, pp. 115 35.

35 Ibid., pp. 146 52; and Subtelny, Timurids in transition, pp. 43 67.

187

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

roughly thirty seven years, from 873/1469 until his death in 911/1506.

A determined and gifted political leader, his long, uninterrupted rule in Herat represented a period of political and economic stability that was

ducive to the creation of the so called Timurid cultural renaissance.

At the beginning of his reign, Sultan Husayn was faced with the urgent task

of restoring fiscal stability to a region whose main tax base had become eroded

due to a decline in agricultural production. Further financial pressures were

created by the cost of rewarding old retainers and recruiting new personnel to

his fledgling state. At the time of his accession, Sultan Husayn made several

key appointments of individuals who had earlier served in the administrations

of Abul Qasim Babur and Sultan Abu Sa'id. He was soon also joined by 'Alishir (also known as Mir 'Alishir and 'Alishir NawaT), the scion of an Uighur family of bakhshis, or Turkic chancery scribes, who were connected

to the Timurid house by ties of foster brotherhood (kokaltashT). Although he

subsequently held several official appointments, such as amir of the diwan i

a'la, 'Alishir was an ichki, or member of the Timurid household establishment.

who until his death in 906/1501 served Sultan Husayn primarily as a trusted

adviser. 37

In 876/1472, Sultan Husayn appointed Majd al Din Muhammad Khwafi, the

son of Shah Rukh's chief vizier, Ghiyath al Din Pir Ahmad Khwafi, as head of

the financial administration, granting him unprecedented powers to imple

ment fiscal and bureaucratic reforms. Majd al Din's appointment turned out

to be a controversial one, and he was removed from office in 883/1478, only to

be reinstated again in 892/1487. During his second tenure in office, Majd al

Din attempted to centralise the Timurid fisc by purging the diwan of corrupt

officials and instituting a reform of the taxation system that included curtailing

the system of land grants with tax immunity, called soyurghal, whose main

beneficiaries were members of the Timurid military elite and household establishment. 3 Accustomed to a more decentralised form of government,

the Turko Mongolian amirs were particularly opposed to Majd al Din's cen

tralising policies and they conspired to have him removed from office. 39 Leading the coalition against Majd al Din were 'Alishir and his brother

36 Mu'in al Din Muhammad Zamchi Isfizari, Rawdat al jannat fi awsdf madinat Hardt, ed.

Sayyid Muhammad Kazim Imam, 2 vols. (Tehran, 1338 9), vol. II, p. 368.

37 Maria Eva Subtelny, "All Shir Nava'i: Bakhshi and beg, Harvard Ukrainian Studies, 3 4

(1979 80), part 2, pp. 799 802; and EP "All Shir Nava'i' (M. E. Subtelny).

38 For the system of landholding and taxation under the Timurids, see Bert Fragner, 'Social

and internal economic affairs', in The Cambridge history of Iran, vol. VI, pp. 491 567.

39 Maria Eva Subtelny, 'Centralizing reform and its opponents in the late Timurid period',

Iranian Studies, 21, 1 2 (1988), pp. 130 49.

Cambridge Histories Online © Cambridge University Press, 201 1

## Tamerlane and his descendants

Darwish 'All Kokaltash A wealthy landowner who enjoyed access to the Timurid dlwan, Alishir would have been hit hard by Majd al Din's reforms.

V. V. Bartol'd speculated that Alishir's extensive building activities may have

contributed to the financial difficulties the Timurid treasury was experiencing.

This appears to be borne out by the fact that 'Alishir temporarily fell out of

favour with the court and in 892/1487 was forced to leave Herat for a while to

assume the governorship of Astarabad. 40 The coalition of amirs finally pre

vailed, and Majd al Din was dismissed in 895/1490. (He died in 899/1494, most

likely having been murdered.)

Following Sultan Husayn's death in 911/1506, intractable fiscal problems

and political uncertainty due to the uneasy co regency of Sultan Husayn's sons

Badi' al Zaman Mirza and Muzaffar Husayn Mirza prompted invasion by the

Uzbeks, who under the leadership of Abul Khayr Khan's grandson Muhammad Shibani captured Herat in 913/1507, thereby bringing Timurid

rule in Khurasan to an end.

The agrarian economy

During Sultan Husayn's reign, the agriculture of the core Timurid region of

Khurasan reached a high level of development. Thanks to the construction

and reconstruction of major irrigation works and the restoration of agricul

tural production under Shah Rukh and Sultan Abu Sa'id following the dis ruption caused by Temiir's conquests, the area under cultivation in Khurasan

was expanded considerably during the second half of the fifteenth century.

Agricultural production consisted mainly of fruits (including many varieties of

grapes), garden vegetables, herbs and flowers (including roses for the produc

tion of rose water), and various types of cereal grains. A rich source of information about the intensive agriculture practised in the Herat region is

the Timurid agricultural manual, Irshdd alzira'a, composed in 921/1515 by

Oasim b. Yusuf Abu Nasri. 41

The Timurids appreciated the economic value of agriculture, which represented the chief source of tax revenues in Khurasan. Although trade and commerce were also important, long distance trade along the so called Silk

Road declined with the increasing decentralisation of the Timurid empire,

political pressure from the Turkmen dynasties in the west and the growing

power of the Uzbeks to the north east. During the fifteenth century, there was

40 V. V. Bartol'd, 'Mir AH Shir i politicheskaia zhizn", in Bartol'd, Sochineniia, vol. II, part 2, pp. 238 9.

41 Subtelny, 'Medieval Persian agricultural manual', pp. 184 9.

189

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

an increase in lands belonging to Islamic pious endowments (awqafi, partic

ularly those connected with the many shrine complexes that had been con

structed and developed throughout Khurasan by members of the Timurid elite. Besides the shrines of 'Abd Allah Ansari and 'All Rida, which were developed under Shah Rukh at Herat and Mashhad, respectively, the shrine

complex based on the purported tomb of Ali b. Abi Talib, which was miraculously 'rediscovered' in 885/i48of in a village (today Mazar i Sharif)

located on the Hazhdah Nahr ('Eighteen canal') irrigation network in the Balkh region, was agriculturally and commercially developed by Sultan Husayn and members of the Timurid elite. 42. It appears that the Timurids

systematically established and endowed such complexes and by staffing them

with professional personnel made them into efficient vehicles for managing

the intensive irrigated agriculture of Khurasan. 43 The same management

model was applied, albeit on a smaller scale, by members of prominent Sufi

orders, such as the Naqshbandiyya, to their own agricultural enterprises.

## The Timurid renaissance

The upsurge in cultural activity in Iran and Central Asia under Timurid patronage coincided roughly with the Renaissance in Europe, and even though there was no historical connection between the two cultural phenom

ena and no shared philosophical basis, historians of Timurid art and culture

dubbed it the 'Timurid renaissance', a designation that continues to be used

even as some scholars have demonstrated its inappropriateness. 45 It cannot be

denied, however, that there was something extraordinary about the way in

which a large number of artistic and literary talents came together with wealthy patrons and elaborated a culture whose impact on the subsequent development of almost every field of artistic endeavour, in both the eastern

and western Islamic world, was entirely out of proportion to the Timurid dynasty's relatively limited duration and geographical scope.

An insightful explanation for the increase in cultural patronage and the creativity it fostered is the notion of the 'military patronage state', put forward

by Marshall Hodgson, who argued that while a state ruled by a privileged

42 R. D. McChesney, Waqfin Central Asia: Four hundred years in the history of a Muslim shrine, 1480 1889 (Princeton, 1991), pp. 21 45.

43 Subtelny, Timurids in transition, pp. 198 219.

44 Jiirgen Paul, Die politische und soziale Bedeutung der Naqsbandiyya in Mittelasien im y. Jahrhundert (Berlin, 1991), pp. 89 112.

45 Jean Aubin, 'Le mecenat timouride a Chiraz', Studia Islamica, 8 (1957), p. 72.

190

Cambridge Histories Online © Cambridge University Press, 201 1

## Tamerlane and his descendants

military family did not necessarily increase the amount of patronage of high

culture, it did provide a different framework for its distribution. 46 A closer

examination of the socio economic bases of the Timurid state would appear to

support this hypothesis, as the fragmentation of political authority due to incessant dynastic and internecine struggles went hand in hand with the fiscal

decentralisation that resulted from the granting of benefices and tax immun

ities to the many Timurid princes and military commanders whose growing

power and independence only reinforced the prevailing centrifugal tenden

cies. Such a situation, often regarded by historians as signalling a period of

decadence or decline, appears in fact to have stimulated the production of

culture by creating multiple centres with competing courts and patrons. 47

#### Literature

The literary output of the Timurid period was exceedingly rich and varied,

with works composed in three languages Persian, Arabic and Chaghatay Turkish. Persian, which was spoken by the vast majority of the indigenous

Iranian population of Khurasan and Transoxania, was the main literary language, used for historical writing, chancery correspondence, and poetry

and prose. Although Arabic continued to be used for works on the religious

and exact sciences, Persian increasingly exerted its dominance in these areas as

well. Under Timurid patronage, Chaghatay, a Middle Turkic language, became a full fledged literary language used in a growing corpus of poetic

and prose works that often closely followed Persian models.

As was generally the case in classical Persian literature, poetry predomi nated over prose. Timurid biographical sources, such as Alishir NawaTs Majalis alnafa'is (completed 897/149^.), devoted largely to contemporary poets writing in Persian and /or Turkish, and Dawlatshah Samarqandi's Tadhkirat alshu'ara (completed c. 892/1487), provide an idea of the extent of

poetical activity as well as information about contemporary literary tastes.

A rare glimpse of the poetic activity of women is provided by Fakhri Harawi's

Jawahir al 'ajayib. 48 The favoured poetical forms were the ghazal, or lyric

poem in monorhyme, which was utilised for mystico erotic themes, and the

mathnawi, consisting of rhyming couplets, which was used for epic or

46 Hodgson, Venture of Islam, vol. II, pp. 404 10.

47 Maria Eva Subtelny, 'Socioeconomic bases of cultural patronage under the later

Timurids', International journal of Middle East Studies, 20, 4 (1988), pp. 479 505.

48 Maria Szuppe, 'The female intellectual milieu in Timurid and post Timurid Herat: Faxri

Heravi's biography of poetesses, Javaher al 'ajdyeb', Oriente Moderno, n.s. 15, 2 (1996), vol. I, pp. 119 37-

191

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

romantic tales, often having an ethical or mystical intent. 49 The poetry of the

period was characterised by rhetorical embellishment and stylistic intricacy,

with a penchant for the innovative imitation of earlier poetic models. Reflecting the literary tastes of the period, such verse forms as the palindrome.

the chronogram and the enigma (mu'atnma) enjoyed great popularity. 50 Music

was closely associated with poetry and the literary gathering (majlis), and in

addition to the works of musical theorists and composers like 'Abd al Oadir al

Maraghi (d. 1435), the descriptions of performances by singers and musicians in

contemporary sources attest to the vitality of the Timurid musical tradition. 51

The most important Persian poet of the period was 'Abd al Rahman Jami (d. 898/1492), who is sometimes unjustifiably referred to as the last classical

poet of Iran. A disciple of the Naqshbandi spiritual master Sa'd al Dm Kashghari and a close friend of 'Alishir Nawa\*i, Jam! is best known for his Haft awrang, a compendium of seven mathnawls composed largely in imitation

of the Khamsas ('Quintet') of Nizami and Amir Khusraw, although with a mystico ethical interpretation, and entitled Sibilat al dhahab, Saldman wa Absal, Tuhfat al ahrar, Subhat al abrar, Yusuf wa Zulaykha, Layll wa Majniin

and Iskandar nama (or Khirad nama i IskandarT). Jami was also the author of

three dlwans of poems. His interpretations were entirely in keeping with Islamic theosophical conceptions as these had been elaborated from the twelfth century, and his poetic works attest to a high level of spiritual sensibility and rhetorical sophistication. He was also the author of several

prose works, mostly on mystical and related topics, including Lawa'ih, Shawahid al nubuwwa, Baharistan and the popular Sufi hagiography Nafahat

al uns. 52

Jami's close friend and spiritual disciple Alishir Nawal (d. 906/1501) is perhaps the most imposing cultural figure of the period, as he was not only an

outstanding poet himself in both Turkish and Persian, but also the main patron and prime mover of literary and cultural activity at Sultan Husayn's

court. Although he was not the 'founder' of the Chaghatay literary language,

he was certainly its greatest representative. Despite the fact that New Persian

(FarsT) had been the literary language par excellence in Iran and Central Asia

49 For an overview, see Jan Rypka, History of Iranian literature, ed. Karljahn, trans. P. van

Popta Hope (Dordrecht, 1968), pp. 279 90; and Ehsan Yarshater, 'Persian poetry in the

Timurid and Safavid periods', in The Cambridge history of Iran, vol. VI, pp. 965 85.

 $50\ \mathrm{Maria}\ \mathrm{Eva}\ \mathrm{Subtelny},$  'A taste for the intricate: The Persian poetry of the late Timurid

period', Zeitschrift der Deutsehen Morgenldndischen Gesellschaft, 136, 1 (1986), pp. 56 79.

51 Owen Wright, 'On the concept of a "Timurid music'", Oriente Moderno, n.s. 15, 2 (1996), vol. II, pp. 665 81.

52 Evgenii Eduardovich Bertel's, Navoi i Dzhami (Moscow, 1965), pp. 209 78.

192

Cambridge Histories Online © Cambridge University Press, 201 1

#### Tamerlane and his descendants

since the tenth century, Alishir championed the cause of Turkish (TiirkT), which he argued could not only vie with Persian as a poetic language but in

some respects was superior to it. Following the lead of earlier Timurid poets

such as Lutfi, Sakkaki and Gada'i, he shaped Chaghatay Turkish into a supple

instrument of poetic expression, composing almost thirty works under the

pen name Nawal He also wrote several works in Persian under the pen name

Fani. His chief works are the Khamsa, modelled on the works of Nizami,

Khusraw and Jami, which comprise Hayrat al abrdr, Farhdd wa Shirin, Layliwa

Majniin, Sab'a i sayydr and Sadd i Iskandari. He also wrote Lisdn al tayr in

imitation of 'Attar's mystical masterpiece, Mantiq al tayr. Of great originality

and subtlety are his lyric poems, collected under the general title Khazd'in

alma' am, which in fact comprises four dlwans. His prose works include Muhakamat al lughatayn, Mahbub al quliib, Nasd'im al mahabba, MTzdn al

awzdn and Wagfiyya (which in spite of its title is in fact his apologia). 53

Another Chaghatay author who cannot escape mention is the Timurid prince Zahir al Dm Muhammad Babur (d. 937/1530), founder of the Timurid

(Mughal) state in India. His prose memoirs, known as the Babur noma, are a

masterpiece of concise and straightforward Chaghatay prose, revealing an

endearingly complex personality who lived in difficult political times. 54

But a figure who perhaps best captures the spirit of the late Timurid period is

Kamal alDm Husayn Wa'izi Kashifi (d. 910/1504<sup>^</sup>. A popular preacher by profession, Kashifi reputedly wrote forty works of a compilative nature cover

ing the entire spectrum of learning in medieval Iran at the turn of the sixteenth

century. Written mainly in Persian, they encompassed the Islamic religious

sciences, the exact sciences, literature and ethics, as well as various popular

esoteric sciences. His best known work is the Alid martyrology Rawdat al shuhadd', which achieved near canonical status under the Shi'i Safavid dynasty.

However, he was almost equally well known for Anwar i SuhaylT, which was

based on the KaUa wa Dimna animal fables; Akhldq i Muhsini, a treatise on ethics

and statecraft; and Mawdhib i 'Aliyya, a Qur an commentary popularly known as

Tafslr i Husayni. Kashifi's works on magic (Asrdr i QdsimT), chancery correspond

ence (Makhzan al inshcT), astrology {Sab'a i Kdshifiyya) and rhetorics (Baddyi' al

afkdrfisandyi' al ash'dr) are only beginning to be subjected to scholarly analysis. 55

53 E? art. "All Shir NavaT (M. E. Subtelny); and Maria Eva Subtelny, 'The Vaqfiya of Mir

'All Sir Nava'I as apologia', Journal of Turkish Studies, 15 (1991), vol. II, pp. 257 86.

54 Wheeler M. Thackston (trans, and ed.), The Baburnama: Memoirs of Babur, prince and

emperor (New York, 1996); and Dale, Garden of the eight paradises, pp. 23 66.

55 Maria E. Subtelny, 'Husayn Va'iz i Kashifi: Polymath, popularizer, and preserver',

Iranian Studies, 36, 4 (2003), pp. 463 7.

The New Cambridge History of Islam

Historical writing and chancery prose

The Timurids contributed to the further development of the eastern Iranian

tradition of historical writing, which was heavily influenced by Persian literary

conventions. Temiir had an acute sense of his historical mission and engaged

secretaries to document his utterances and conquests. The Zafar noma ('Book

of conquests'), completed by Nizam al Din 'All Shami in 806/1404, which chronicled Temiir' s early career and military conquests, formed the basis for

later Timurid histories. Under Shah Rukh, the court sponsored historiography

sought to portray Temiir in a more positive, Islamic light and by the same token legitimate Shah Rukh's claim to the Timurid heritage.

Continuations of

Shami's history included Taj al Salmani's Shams al husn, which covered the

period 807 11/1404 9, and Hafiz i Abru's Dhayli Zafar namai Shami, com posed in 814/1412. In order to situate the history of the Timurid dynasty within

the larger Islamic framework, several universal histories were composed at

this time, chief among them being Mu'in al Din Natanzi's Muntakhab al tawarikh i Mu'ini, completed 817/1414, and Hafiz i Abru's Majma' i tawarikh.

which covered the period to 830/1427. 5& Sharaf al Din 'All Yazdi's Zafar nama,

completed in 832/1424^ represented an expanded version of Shami's work,

with which it shared the same title. 57 A number of important illustrated manuscripts of this work have survived from the Timurid period. 58

The main source for the history of the period to 875/1470 is the Matla' i sa'dayn wa majma' i bahrayn by Abd al Razzaq Samarqandi, who drew on the

work of Hafiz i Abru. The most widely utilised work for the history of the Timurid dynasty as a whole, but particularly for the second half of the fifteenth

century, is Khwandamir's Habib alsiyar, which represents a continuation of

Mirkhwand's universal history, Rawdat al safa, up to the year 930/1524. 59 Other

sources containing valuable biographical information relating to the careers of

Timurid administrators are Khwandamir's Dastur alwuzara', completed c. 9i5/i509f, and Sayf al Din 'Uqayli's Athar al wuzara', completed in 883/i478f.

56 EIr art. 'Hafez e Abru' (Maria Eva Subtelny and Charles Melville).

57 John E. Woods, 'The rise of Timurid historiography', Journal of Near Eastern Studies, 46,

2 (1987), pp. 81 108; and Shiro Ando, 'Die timuridische Historiographie II. Saraf al din

'All Yazdi', Studia Iranica, 24, 2 (1995), pp. 219 46.

58 See, for example, Thomas W. Lentz and Glenn D. Lowry, Timur and the princely vision:

Persian art and culture in the fifteenth century (Los Angeles, 1989), pp. 100 5 and 264 7.

59 Khwandamir, Habihu's siyar: Tome three, trans. W. M. Thackston, 2 parts (Cambridge, MA, 1994), part 2.

60 For an overview of historical sources for the Timurid period, see Ch. A. Stori [C. A.

Storey], Persidskaia literatura: Bio bibliograficheskii ohzor, trans, and rev. Iu. E. Bregel', 3

vols. (Moscow, 1972), vol. I, pp. 339 93 and vol. II, pp. 787 843.

194

Cambridge Histories Online © Cambridge University Press, 201 1

Tamerlane and his descendants

Other sources for Timurid history are the compilations of official docu

merits and chancery correspondence, such as Mansha' al inshd', which contains

documents composed by 'Abd al Wasi' Nizami Bakharzi, and Sharafndma by

Abd Allah Marwarid, both of whom were connected with the court of Sultan

Husayn. J Makhzan al inshd', a manual for chancery scribes, was composed in

907/1501L by Husayn Wa'iz i Kashifi. 2 Mention may also be made of the correspondence of Sufi shaykhs and spiritual leaders, such asjami and 'Ubayd

Allah Ahrar, which are a rich source of information about the social and economic history of the period. 3

Painting, calligraphy and the arts of the book

The literary legacy of the Timurid period was inextricably linked with the production of book manuscripts, many of which were sumptuously illustrated

and illuminated. It is no exaggeration to state that, judged by any standards, the

arts of the book were raised under Timurid patronage to the highest levels of

artistic accomplishment. In fact, the illustrated manuscripts produced during

this period have in many respects come to represent 'Islamic' painting as

whole. It should be noted, however, that the painting of the Timurid period was

based on a long standing Iranian tradition of figural representation, which was

heavily influenced by Chinese painting during the post Mongol period. Among

the main literary works illustrated were the Persian epic, Shah ndma, and the

Khamsas of Nizami and Amir Khusraw, which included such favourites as the tales of Layli wa Majniin, Khusraw wa Shlrin and the Alexander romance.

A stunning example of what may be termed religious art is an illustrated Islamic

ascension narrative (mi'rdj ndma), which dates from the period of Shah Rukh. 64

Probably the most important contribution to the development of painting and the arts of the book under Timurid patronage was the institution of the

kitdbkhdna, which functioned as a library, scriptorium and artistic atelier, in

which an impressive array of painters, gilders, calligraphers, bookbinders and

other craftsmen worked under court sponsorship on the production of

61 For a partial translation of the latter, see Hans Robert Roemer (ed. and trans.),

Staatsschreiben der Timuridenzeit. Das Sarafnama des 'Abdalldh Marwarid in kritischer

Auswertung (Wiesbaden, 1952).

62 Colin Paul Mitchell, 'To preserve and protect: Husayn Va'iz i Kashifi and Perso Islamic chancellery culture', Iranian Studies, 36, 4 (2003), pp. 485 507.

63 A. Urunbaev (ed. and trans.), Pis'ma avtografy Abdarrakhmana

Dzhami iz AVboma NavoV (Tashkent, 1982); and Jo Ann Gross and Asom Urunbaev (eds. and trans.), The letters of

Khwdja 'Ubayd Allah Ahrar and his associates (Leiden, 2002).

64 Marie Rose Seguy (ed.), The miraculous journey of Mahomet: 'Mirdj ndmeh', Bibliotheque

Nationale, Paris (Manuscrit Supplement Turc 190), trans. Richard Pevear (New York, 1977).

195

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

illustrated manuscripts and other luxury items for use by the Timurid court

elite. Although the kitdbkhana was not a Timurid invention, a number of princely and elite patrons, notably Shah Rukh's son Baysunghur (d. 837/1434),

made it the focal point of what has been referred to as 'the Timurid cultural

complex'. 65 Baysunghur also appears to have initiated the development of the

Persian album, in which calligraphic specimens, paintings and drawings were

assembled together and used for presenting artistic collections and workshop

designs. Besides Herat, other important Timurid centres of cultural and scientific patronage in the first half of the fifteenth century were Shiraz (especially under the princes Iskandar b. 'Umar Shaykh and Ibrahim Sultan

b. Shah Rukh), Isfahan, Yazd and Samarqand. 67

The undisputed locus of cultural activity in the second half of the fifteenth

century was the court of Sultan Husayn Bayqara in Herat. The manuscripts

produced under his patronage and that of members of the Timurid elite are

among the most outstanding specimens of the arts of the book in Islamic cultural history. The painters of this period included Shah Muzaffar, Mirak

Naqqash and the extraordinarily gifted Bihzad (d. 1535). 69 As for calligraphers,

it would appear that the pinnacle of the calligraphic arts in the eastern Islamic

world was attained by the likes of Sultan 'All Mashhadi and Mir All al Harawi, both of whom were attached to the Timurid scriptorium. Among the favoured manuscripts copied and illustrated during this period were the

works of the poets 'Alishir Nawa\*i, Nizami, Jami and Amir Khusraw, Rumi's

Mathnawi and Husayn Kashiff's Anwar i Suhayll. 70

### Architecture

Temiir appreciated the legitimating function of architecture, and his architec

tural legacy reflects a taste for monumentality that was part of an ideological

65 Lentz and Lowry, Timur and the princely vision, pp. 50 and i59ff.

66 David J. Roxburgh, The Persian album, 1400 1600: From dispersal to collection (New Haven, 2005), pp. 37S.

67 Aubin, 'Le mecenat timouride', pp. 75 88; and Francis Richard, 'Un temoignage

inexploite concernant le mecenat d'Eskandar Soltan a Esfahan', Oriente moderno, n.s.

15, 2 (1996), vol. I, pp. 45 72.

68 Oleg Akimushkin et at, The arts of the book in Central Asia, 14th 16th centuries, ed. Basil

Gray (London, 1979), pp. 179 214.

69 Abolala Soudavar, Art of the Persian courts: Selections from the Art and History Trust

collection (New York, 1992), pp. 95ff.; and Michael Barry, Figurative art in medieval

Islam and the riddle of Bihzad of Herat (1465 yy) (Paris, 2004), pp. 133ft

70 Hamid Sulaimon and Fozila Sulaimonova, Alisher Navoii asarlariga ishlangan rasmlar, XV

XIX asrlar I Miniatiury k proizvedeniiam Alishera Navoi XV XIX vekov/ Miniatures illustrations of

Alisher Navoi's works of the XV XlXth centuries (Tashkent, 1982); and Soudavar, Art of the

Persian courts, pp. 85 125.

196

Cambridge Histories Online © Cambridge University Press, 201 1

### Tamerlane and his descendants

programme of self aggrandisement. Unfortunately, many buildings in this 'imperial Timurid style', such as the Bibi Khanum congregational mosque and the Aq Saray palace in Samarqand, were often erected hurriedly and either

collapsed or soon fell into ruin. Others, like the shrine of Ahmad Yasawi in

Turkistan, loom large on the horizon or are enveloped in gloomy splendour,

as in the case of the Gur i Amir mausoleum in Samarqand. In the popular imagination, Temiir's monuments were connected with the memory of his brutal conquests and the forcible transfer of architects, engineers and artisans

to Samarqand. After Temiir's death, the Iranian architect Qawam al Din Shirazi (d. 842/1438) was instrumental in creating a distinctive style which

architectural historians have labelled 'metropolitan Timurid'.

Characterised

by geometric complexity, it featured barrelled vaults (aywan), large dome chambers (gunbad) and rectangular halls with transverse tripartite vaults

articulated with plaster stalactite compositions (muqarnas). Probably the most representative building constructed by Qawam al Dm Shirazi that is still standing is the congregational mosque of Gawharshad at the shrine of

Imam Rida in Mashhad. 71

An integral feature of Timurid architecture was its decoration, including polychrome surface revetments in mosaic faience, glazed or unglazed brick,

cuerda seca and painted plaster, which utilised a wide array of geometric,

ornamental and epigraphic designs of great intricacy and abstract beauty. The

practical aspects of geometrical patterning, such as the interlocking star and

polygon patterns in two and three dimensions (called girih), have been preserved in architectural drawings and design scrolls dating from this period/ 2

Timurid architecture favoured complexes and ensembles, particularly the pairing of madrasa and khdnaqd, and funerary monuments, especially in the

form of the domed mausoleum, were constructed largely under the patronage

of elite Timurid women. 73 Another characteristic aspect of Timurid architec

ture was its close connection with garden design. Temiir constructed a large

number of garden residences in Samarqand, with names like Bagh i dilgusha

('The heart expanding garden') and Bagh i jahannuma ('The world revealing

71 For a comprehensive description of surviving Timurid architectural monuments, see

Golombek and Wilber, Timurid architecture, vol. I, pp. 187 216 and 224 457.

72 Giilru Necipoglu, The Topkapt scroll geometry and ornament in Islamic architecture (Santa Monica, 1995), pp. 29 57 and 349 59.

73 Maria Eva Subtelny, 'A Timurid educational and charitable foundation: The Ikhlasiyya complex of 'AH Shir Naval in 15th century Herat and its endowment', Journal of the

American Oriental Society, in, 1 (1991), pp. 42 6; and Subtelny, Timurids in transition, pp. 151 2.

197

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

garden'). Shah Rukh's royal garden residence in Herat was called Bagh i zaghan (The ravens' garden'), and Sultan Husayn constructed the Bagh i jahanara (The world adorning garden') to serve as his seat of government. 74

Sultan Husayn, who reputedly had a great interest in horticulture and arbor

iculture, had in his employ a master landscape architect named Mirak i Sayyid

Ghiyath (d. c. 1550), whose design of the quadripartite garden (chahdrbdgh) had

a profound influence on the architecture of Central Asia and Mughal India. 75

### The decorative and artisanal arts

As in the case of painting, the decorative and artisanal arts of the Timurid

period were greatly influenced by Chinese aesthetics. This was probably most

evident in ceramics, since large quantities of Ming porcelains had been brought to Central Asia and Iran during the many trade embassies exchanged

between the Timurids and the Ming dynasty during the first half of the fifteenth century. A taste for the signature blue and white Ming porcelain vessels resulted in the production of 'chinoiserie ceramics' during the Timurid

period. These were not mere imitations of Chinese models but imaginative

reinterpretations of such traditional Chinese design motifs as the peony or

chrysanthemum, the cloud point, the dragon motif and the classic scroll patterns, which were adapted to the Timurid penchant for repetitive arab esque patterns known as islimi/ 6 The most important ceramic workshops

operating during the Timurid period were in Nishapur, Samarqand and Mashhad; Herat does not appear to have figured as a centre of ceramic production, although it was certainly a consumer of blue and white ceramic

objects, as attested by the frequent illustrations of various kinds of porcelain

vessels, such as bowls, plates and decanters, in manuscripts produced by the

Timurid atelier. Great strides in the study of Timurid ceramics have been made in recent years thanks to the application of petrographic analysis techniques to the body fabric of ceramic wares, thereby permitting the

74 Lisa Golombek, 'The gardens of Timur: New perspectives', Muqamas, 12 (1995), pp. 137

47; and Golombek and Wilber, Timurid architecture, vol. I, pp. 174 83.

75 Maria Eva Subtelny, 'Agriculture and the Timurid chahdrbdgh: The evidence from a

medieval Persian agricultural manual', in Attilio Petruccioli (ed.), Gardens in the time of

tfie great Muslim empires: Theory and design, (Leiden, 1997), pp. 115 18; and Subtelny, he

monde est unjardin: Aspects de I'histoire culturelle de I'Iran medieval (Paris, 2002), pp. 101 25.

76 Lisa Golombek, Robert B. Mason and Gauvin A. Bailey, Tamerlane's tableware: A new

approach to the chinoiserie ceramics of fifteenth and sixteenth century Iran (Costa Mesa,

1996), PP- 58 9; and Bernard O'Kane, 'Poetry, goemetry and the arabesque: Notes on

Timurid aesthetics', Annales Islamologiques, 26 (1992), pp. 76 8.

198

Cambridge Histories Online © Cambridge University Press, 201 1

Tamerlane and his descendants

identification of centres of production. 77 Many specimens of Timurid chinoiserie

ceramics were preserved in porcelain collections, particularly the collection

formerly housed at the Safavid shrine in Ardabil. 7

The decorative arts of the Timurid period displayed great interdependence,

and architectural decoration and the design motifs featured on chinoiserie

ceramics were also found on textiles, carpets, bookbindings, wood carvings

and metalwork of the period. The few surviving fabrics and textiles produced

by Timurid workshops betray strong Chinese influence. The most desirable

fabrics were silk and silk brocade, which were used for ceremonial robes, such

as the exquisite cloud collar preserved in the Armoury Chamber of the Moscow Kremlin. 79 The elaborate tents, royal parasols and sumptuous cano

pies utilised by Temiir and the Timurids in their outdoor audiences and entertainments are frequently depicted in paintings. ° Only tiny fragments

of carpets have survived, but again representations in Timurid paintings provide an idea of their intricate designs. J Among objects that have survived

in greater quantities, mention may be made of those fashioned from jade, which was highly esteemed by the Timurids for its reputed talismanic proper

ties. Many objects, such as candlesticks, basins and ewers were made from

metals such as copper and brass, which were frequently inlaid with silver and

gold. The most spectacular example of Timurid metalwork is the huge bronze

cauldron commissioned by Temiir for the shrine of Ahmad Yasawi. 2 In general, Timurid aesthetics reflected a preoccupation with geometric sym

metry, decorative intricacy and artistic refinement that found expression in all

areas of cultural creativity.

### Conclusion

It was thanks to the rich cultural legacy of the Timurids that this Turko Mongolian dynasty, which became increasingly marginalised politically towards the end of the fifteenth century, achieved a renown in the Islamic

77 Robert B. Mason, 'The response I: Petrography and provenance of Timurid ceramics',

in Golombek, Mason and Bailey, Tamerlane's tableware, pp. 16 56.

78 T. Misugi, Chinese porcelain collections in the Near East: Topkapi and Ardebil, 3 vols. (Hong Kong, 1981).

79 See Lentz and Lowry, Timur and tfte princely vision, p. 216.

80 Bernard O'Kane, 'From tents to pavilions: Royal mobility and Persian palace design',

Ars Orientalis, 23 (1993), pp. 249 68.

81 Lentz and Lowry, Timur and tfte princely vision, pp. 220 1.

82 Linda Komaroff, The golden disk of heaven: Metalwork of Timurid Iran (Costa Mesa, 1992), pp. I7ff.

199

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

world that far exceeded its geopolitical significance. The Timurid court of Herat in particular served as a model for subsequent Islamic dynasties, including those of the Uzbeks, Safavids, Mughals and Ottomans, who aspired

to the same level of sophistication in their own court culture and patronage of

the arts. 3 In more recent times, the charismatic figure of Temiir and the Timurid cultural legacy have become of great relevance to the construction of

their national identity by the modern Uzbeks of the post Soviet republican period. 84

83 Stephen Frederic Dale, 'The legacy of the Timurids', Journal of the Royal Asiatic Society,

3rd ser., 8, 1 (1998), pp. 43 58; and Eleazar Birnbaum, 'The Ottomans and Chagatay

literature: An early 16th century manuscript of NavaTs Envan in Ottoman orthography',

Central Asiatic Journal, 20, 3 (1976), pp. 157 90.

84 Maria Eva Subtelny, 'The Timurid legacy: A reaffirmation and a reassessment', Cahiers d'Asie Centrale, 3 4 (1997), pp. 14 17.

Cambridge Histories Online © Cambridge University Press, 201 1

PART II

THE GUNPOWDER EMPIRES

Cambridge Histories Online © Cambridge University Press, 201 1

6

Iran under Safavid rule

SHOLEH A. QUINN

Safavid origins

The Safavid dynasty traces its origins to a fourteenth century Sufi order established in the northern Iranian city of Ardabil, located in the province of

Azerbaijan (see Map 5). Iran at this time was witnessing one of its not so uncommon periods of political fragmentation and decentralisation, and con

trol of Ardabil was in the hands of either the post Ilkhanid Mongol Jalayirids or

Turcoman Aq Qoyunlus. As a result of the Mongols placing increasing importance on Tabriz, and transferring the capital to Sultaniyya, both in northern Iran, Azerbaijan was increasingly becoming an important Islamic

centre. 1 In Ardabil, the eponymous founder of the Safaviyya taiiqa, Shaykh Safi

al Dm Ishaq Ardabili (650 735/1252 1334) and his followers lived what approxi

mated to a 'typical' Sufi existence. Even during his lifetime, Shaykh Safi was

highly respected and well known in Ardabil. Adepts of the Safaviyya order,

according to Ibn Bazzaz's massive hagiographical source, the Safvat al safa,

written during the lifetime of Shaykh Safi's son and successor, Shaykh Sadr

al Dm Musa, engaged in prayer, fasting, dhikr sessions and other activities. Ibn

Bazzaz narrates the many miraculous events of Shaykh Safi's life, all designed

to portray him as a devout and pious Sufi. The Safaviyya was just one of many

Sufi orders that flourished in post Mongol Iran and Anatolia. During the time

of Shaykh Safi, the order was decidedly Sunni although like many contem porary orders it may have professed special love and devotion to the family of

'All as evidenced by an anecdote from the Safvat al safa, where Ibn Bazzaz

relates on the authority of Shaykh Sadr al Din that one day, Shaykh Zahid,

who was Shaykh Safi's pir or murshid, was communicating with God. When

his followers asked him where he had been, he said that his heart had travelled

1 Michel Mazzaoui, Tfie origins of the Safawids: Si'ism, Sufism, and tfte Gulat (Wiesbaden, 1972), P- 43-

# The New Cambridge History of Islam

the entire world in order to choose an appropriate spot for a centre for Shaykh

Safi. He decided upon Ardabil, because the people were pure in their faith

(safa yi Tman) and stated that 'in this place (i.e. in Ardabil), except for the surma

and jamd c a, there has not been and there is no dispute and diversity of opinion

of the schools (madhdhib) such as the 'Ashariyya, Mu'tazila, Qadiriyya, Mushabbaha, Mujassama, Mu'attala and others'. 2

The followers of the Safavids were known pejoratively by the Ottomans as

Qizilbash, literally 'Red Heads', for the colour of their turbans. These were the

Turcoman tribal groups, most of which originated in eastern Anatolia, sup

ported the Safaviyya and became their religious followers. There were many

different Qizilbash tribes; some, such as the Afshars and the Qajars, eventually

seized power after Safavid rule came to an end. Other groups included the

Rumlus, the Ustajlus and the Dhu ] l Qadrs. The Qizilbash adhered to the same

sort of ghulat Shi'ism as their shaykhs.

The next two leaders of the Safaviyya, Shaykh Sadr al Din Musa (d. 794/1391^

and Shaykh Khvaja 'All (d. 832/1429), continued in Shaykh Safi's footsteps while

the prestige and influence of the order grew in significant ways. Under Shaykh

Sadr al Din Musa, Jalayirid officials acknowledged the influence of the Safaviyya,

and even issued firmans acknowledging the influence of the order. 3 Although

during this time the order experienced some persecution and difficulties, it.

managed to survive these and emerge even more prosperous and influential

under Shaykh Khvaja 'All. 4 At the same time, Iran's political landscape was

changing, and leaders of the Safaviyya not only married into ruling families but

also had interactions with political powers in the region. It is interesting to note

that later Safavid chroniclers highlighted and in some cases exaggerated or

reinvented these relationships. For example, although not mentioned in any

Timurid source, several Safavid chroniclers of the sixteenth and seventeenth

centuries narrate an account of either Shaykh Sadr al Din or Khvaja 'All's meet

ings with Temur (r. 771 807/1370 1405). 5 For example, according to the well

known chronicler of Shah Abbas, Iskandar Beg Munshi, in the first two of three

encounters, Shaykh Khvaja Ali first met Temur when the famous conqueror

crossed the Oxus on his way to Transoxiana. Apparently, in this meeting, a vision

2 Ibn Bazzaz Tavakkul ibn Isma'il, Sajvat al safi, ed. Ghulam Riza Tabataba'I Majd

(Ardabil, [1373] 1994), p. 178. This passage (with slight modifications) is translated in

Mazzaoui, Origins of the Safawids, p. 49.

3 Mazzaoui, Origins of the Safawids, p. 53.

4 Ibid., p. 54.

5 Woods has listed, according to the early Timurid sources, the important religious

individuals and shrines that Temur visited around this time. They number nearly thirty,

and none of them are Safavid. Personal communication from John E. Woods.

204

## Iran under Safavid rule

of Shaykh Khvaja 'All appeared to Temiir, and presented him with his whip that

had fallen into the water. Temiir interpreted this as a good omen. The dervish

told him, 'My home is Ardabil, the place where I shall appear is Dezful, and the

place where I shall be buried is Jerusalem.' In the second meeting, Temiir was

on his way from Baghdad to Khuzistan when a dervish appeared wearing a black

Sufi robe. He told Timiir that he was the dervish who had given him the whip

which had fallen into the Oxus, and stated that they would meet again in Ardabil. 7 Iskandar Begs account of the third meeting describes how Temiir

came to release Anatolian prisoners. He also adds a section on the discovery of a

waqf (endowment) document, now considered a forgery, indicating that Temiir

endowed the revenues of a parcel of land for the benefit of the Safavid family.

While it is probable that such meetings never took place, they indicate something

of the standing that the early Safavid shaykhs had for later dynastic writers. 9

The activities of the Safaviyya during the leadership of Junayd (d. 893/1460)

started to change when the order became involved in ghdzi warfare against

Byzantine Trebizond and the Georgian Caucasus. 10 By this time, too, the order had taken on many of the beliefs associated with ghuluwwism, or exag

gerated religious beliefs. The history of ghuluww expression in Islamicate history

is complex. In previous centuries, ghuluww thinkers had become known for

their ideas about the nature of the imam; this includes the idea that the imam was, if not divine, then at least of the rank of prophethood and with the

authority that accompanied that status. They also expounded ideas that sug

gested the anthropomorphism of God, resurrection, reincarnation and the

transmigration of souls. Influences from certain varieties of Zoroastrianism,

Judaism and Christianity also informed the development of ghuluww notions. 11 By the Safavid period, such beliefs had already been absorbed

into forms of Imamism, and many Sufi orders, though not necessarily Shi'i.

showed particular reverence for 'AE and displayed ghuluww tendencies. The

religious, Sufi and associated esoteric factions that shared some common characteristics with the Safaviyya in the fifteenth century included the Ahl i

Haqq, the Musha'sha', the Hurufiyya, the Baba'is and others. These groups all

6 Iskandar Beg Munshi, Tarikhi 'aUimarayi 'Ahhasi, 2nd edn, 2 vols., ed. Iraj Afshar

(Tehran, 1350 [1971]), vol. I, p. 15; trans. Roger Savory as History of Shah 'Abbas the

great (Tank e 'alamara ye 'Ahhasi), 3 vols., Persian Heritage Series, 28 (Boulder, CO,

1978), vol. I, p. 27 (hereafter cited as 'trans.').

7 Iskandar Beg Munshi, 'Alam drayi 'Ahhasi, p. 15, trans., p. 27.

8 See Heribert Horst, Timur und Hoga 'Alt Einheitragzur geschiehte der Safawiden (Mainz, 1958).

9 See ibid.

10 See Mazzaoui, Origins of the Safawids, p. 74.

11 See EF 'ghulat' (Marshall Hodgson).

205

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

shared certain similar features, including the propagation of ghuluww beliefs

through charismatic leaders, a number of whom made messianic claims or

claims of divinity for themselves, and they enjoyed widespread popular appeal. 12 The Safavid Junayd appears to have presented himself as something

of a divine incarnation. The hostile Aq Qoyunlu writer Fazl Allah b. Ruzbihan

Khunji, author of the 'Alam ara yi Amini, states that 'they openly called Shaykh

Junayd "God" and his son "Son of God'". 13 At the same time that the Safaviyya

was displaying ghuluww proclivities, Safavid leaders continued to forge marital

alliances with the ruling families of the time. For example, Junayd married the

Aq Qoyunlu ruler Uzun Hasan s sister, and Junayd's son Haydar (d. 893/1488)

married Uzun Hasan s daughter.

Shah Ismail's rise to power and subsequent reign

The Safavid family continued to involve themselves in Aq Qoyunlu politics,

including succession struggles, until Isma'il (r. 907  $30/1501\ 24$ ) took the throne

and crowned himself king. As Aq Qoyunlu power weakened, however, and in

the political confusion that ensued during this time, Ismail and his brother

Ibrahim were smuggled away to Gilan, in the Caspian Sea region. 14 Isma'il was

tutored and protected by the Shi 1! Sufis of Lahijan. Eventually, he marched out

from Lahijan with his followers, taking advantage of Aq Qoyunlu civil war and

general weakness, and started moving into Arzinjan in Anatolia, and then

towards Ardabil. He continued to gather supporters and after waging successful

campaigns in Shirvan and Baku, he finally headed for Tabriz. 15

When he reached Tabriz, Isma'il crowned himself king, or Shah, in 907/1501.

At the same time, he declared Twelver Shi'ism the official state religion. The

early Safavid chronicler Ghiyath al Din Khwandamir explains how 'a regal decree

was issued that all preachers in the realm of Azerbaijan pronounce the khutba in

the name of the Twelve Imams'. Furthermore, the muezzins were ordered to

add the phrase And I profess that 'All is the Friend of God' to the call to prayer. 16

The whole issue of Shah Isma'il's religious policies has received a great deal

of scholarly attention. Isma'il's own religious persuasion before this time was

12 For more information on this process, see Kathryn Babayan, Mystics, monarchs, and

messiahs: Cultural landscapes of early modern Iran (Cambridge, MA, 2002), pp. 245 81.

13 See Mazzaoui, Origins of the Safawids, p. 73.

14 Ibid., p. 80.

15 Ibid., pp. 81 2.

16 Ghiyath al Din ibn Humam al Dm Khvandamir, Tankh i habib al siyar, 4 vols., ed. Jalal

al Din Huma'i ([Tehran], 1333 [1954]), vol. I, p. 468; trans. Wheeler Thackston as

Habibu's siyar, 2 vols. (Cambridge, MA., 1994), vol. I, p. 576.

206

Cambridge Histories Online © Cambridge University Press, 201 1

Iran under Safavid rule

marked by significant ghuluww concepts, as his poetry attests. In his diwan,

where he refers to himself as 'KhataT, Isma'il makes numerous high proph

etological, imamological, messianic and related claims, where he suggests that

he is the Mahdi, the return of Christ, and other religious and political figures of

the past, as seen in the following poem:

Shah Isma'il is my name, I am the mystery of Truth / Of all of these Ghazis I

am the commander

Fatima is my mother, 'All is my father / Of the Twelve Imams I am the Pir Upon Yazld I revenged my father's blood / Know well that I am of Haydarian

#### essence

The living Khidr and Jesus son of Mary / The Alexander of the people of the age

Behold Yazid and the polytheists and the damned! / Quit am I of the Qibla of

the hypocrites

With me is Prophethood (nubuwat) and the secret of successorship (vilayat) I

Successor am I to Muhammad Mustafa

With my sword have I subdued the world / I am the Qanbar (menial slave) of

'All Murtada

Safi is my grandfather, Haydar is my father / Of the people of courage, truly I

am Ja'far

Husaynid am I my curse upon Yazid! / Khatal am I, a servant of the shah 17

The establishment of ShTism as the official state religion

Shah Isma'il's early religiosity raises certain questions in light of the fact that

the most significant policy change that he instituted once he crowned himself

king was the proclamation of ShTI Islam as the official state religion. The chroniclers themselves are not particularly forthcoming about the matter;

Iskandar Beg Munshi simply states the following: 'The practice of the Twelver

rite of shi'ism was made public. The pulpits in the mosques resounded with

sermons in which the exalted names of the Shi'ite Imams were commemo

rated. The dinars were stamped with the inscription, "There is no god but God; Mohammad is the Prophet of God, and 'All is the favorite friend of God",

and with the name of that chosen One of his descendants (Esma'il himself).' 1

The reason behind this decision has been the subject of some debate and

17 Shah Isma'il, 71 Canzoniere di Sah Isma'il Hatd't, ed. Tourkhan Gandje'l (Naples, 1959),

no. 16, trans. Robert Dankoffin 'Readings in Islamic civilization: From the rise of Islam

to the beginning of the ioth/i6th century', Robert Dankoff, gen. ed., unpublished ms.

Slightly modified.

18 Iskandar Beg Munshi, 'Alam drdyi 'AbbdsT, pp. 27 8; trans., p. 44.

207

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

discussion. Some have suggested that Isma'il wanted to distinguish his new

state from Sunni neighbours to the east and west, and therefore he chose to

convert Iran to Shi'ism. 19 Another possible reason could be that while ghuluww

Shi'ism was an acceptable form of religious expression for Ismail's Qizilbash

supporters, he needed something that provided more formal organisation for

ruling a state. Whatever his reasons, the changes he imposed on Iran were

successful, for today the majority of Iran's population is Shi'i, unlike the Sunni

majority in Iran at the time of Shah Isma'il.

The question of outside influences

Although Shah Isma'il used many Persians who had been administrators during

previous dynasties to run the bureaucracy of the new empire, in order to promote Shi'ism, he invited scholars and experts from Qum, a traditional Shil

centre in Iran, and southern Lebanon, in particular the Jabal 'Amil region, which

had been a centre of Shi'ism since the tenth century, to travel throughout Iran

and promote Shi'ism. 2  $^{\circ}$  He also appointed such individuals to be muezzins and

prayer leaders in mosques. There has been considerable discussion surrounding

the migration of Shi'i clerics to Iran in the Safavid period. Debate has surrounded

the question of which Shi'i scholars from outside Iran, in particular Jabal 'Amil,

came to Iran, and how many there were. The standard view was that the numbers were quite large, but it has been recently argued that individuals

such as the famous 'All ibn Abd al AE al Karaki (d. 940/1534), the first Shil

from Jabal Amil who went to Iran, were more the exception than the rule. 21 At

this point, it remains uncertain exactly how many scholars came to Iran, why

they came, how long they stayed and what their activities were once they arrived. 22 What does seem to be the case is that although most of the Shil

scholars in Iran were not from Jabal 'Amil, many of the Shi'i scholars in the

Jabal 'Amil region did in fact leave for Safavid Iran, resulting in a "brain drain' of

19 See, for example, EI 1 'Isma'il I' (Roger Savory).

20 For details on Shah Isma'U's early administration, see Jean Aubin, 'Etudes Safavides I

Sah Isma'il et les notables de l'Iraq Persan', Journal of Economic and Social History of the

Orient, 2 (1959), pp. 37 8. For the movement of scholars from Jabal 'Amil to Iran, see

Albert Hourani, 'From Jabal 'Amil to Persia', Bulletin of the School of Oriental and African

Studies, 49 (1986), pp. 133 40.

21 Andrew J. Newman, 'The myth of the clerical migration to Safawid Iran: Arab Shiite opposition to 'Ali al Karaki and Safawid Shiism', Die Welt des Islams, 33

opposition to 'Ali al Karaki and Safawid Shiism', Die Welt des Islams, 33 (1993), pp. 66 112.

22 Devin J. Stewart, 'Notes on the migration of 'Amili scholars to Safavid Iran', Journal of Near Eastern Studies, 55 (1996), p. 3.

23 Ibid., p. 4.

208

Cambridge Histories Online © Cambridge University Press, 201 1

#### Iran under Safavid rule

In terms of the impact these Shi'i experts had in Iran, it appears that they were

in fact quite influential. For example, al Karaki was the leading Shil authority in

Iran during his time, and, furthermore, the leading jurists during the first 120

years of the dynasty were from Jabal Amil. 24 Moreover, the influx was not

immediate or early, as the bulk of the migrations took place after the reign of

Shah Ismail in the second half of the sixteenth and the seventeenth centuries. 25

Once these individuals arrived in Iran, they received prestigious court positions. Al Karaki and others were instrumental in converting Iran to Imami Shilsm, as distinct from the earlier Safavid Qizilbash form of Shilsm

that was tinged with ghuldt beliefs. However, not all jurists who settled in Iran

agreed with each other over religious matters; indeed, robust debates took

place as early as the reign of Shah Tahmasp, when, for example, al Karaki and

his former student Amir NTmat Allah al Hilli the sadr debated whether or not

Friday prayers should take place in light of the absence of the twelfth imam. 2

Al Karaki was powerful and influential enough to garner opposition from sadrs and other notables as he gained increasingly important positions from the king. 27 The king sided with al Karaki, who ended up finding support

from among the Qizilbash. The Qizilbash seemed to favour the king's policies

of further establishing a Shi'i orthodoxy in Iran. 2 Al Karaki and his colleagues

gradually helped to 'invent' a new Shi'i identity for the Safavids that included

practices that helped to differentiate the Shi c i Safavids from their Ottoman

enemies. Popular expressions of religiosity included the ritual cursing of the

first three Sunni caliphs, and others developed over time.

Ismail's initial conquests resulted in his taking over most of Iran, what had

been former Aq Qoyunlu territory, part of Ottoman territory in eastern Anatolia, Baghdad and Khuzistan. 29 He later challenged the Uzbeks, killed

Muhammad Shaybani (Shibani) Khan the Uzbek leader in 916/1510, and took

over Herat the same year. Although this did not end the Uzbek threat and one

of Ismail's generals was in fact defeated by the Uzbeks in 918/1512, essentially

the Uzbeks were kept behind their border. Of all his enemies, it was the Ottomans who posed the greatest threat and danger to Safavid rule. The

24 Ibid., p. 6.

25 Ibid., p. 7.

26 Rula Jurdi Abisaab, Converting Persia: Religion and power in the Safavid empire (London, 2004), p. 17.

27 Ibid., pp. 17 18.

28 Ibid., p. 20.

29 This summary is based on the very useful overview of Ismail's conquests in Hans R.

Roemer, 'The Safavid period', in Peter Jackson and Laurence Lockhart, (eds.), The Cambridge

history of Iran, vol. VI: The Timurid and Safavid periods (Cambridge, 1986), pp. 189 350.

209

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

Ottomans were worried, of course, about the possibility of rebellion and defection on the part of eastern Anatolian Turcoman Qizilbash to the Safavid cause. This fear was well founded, for in 917/1511, a rebellion led by

a Qizilbash named Shah Qui! Khan took place in the province of Teke Hi. His

death in turn led to further rebellions within Ottoman territory, most notably

in Rum. When Sultan Selim succeeded to the sultanate after the abdication of

his father Bayezid in 918/1512, he persecuted Qizilbash in Anatolia and eventually led a campaign against Shah Isma'il in 920/1514. This was the famous battle of Chaldiran, greatly celebrated in Ottoman chronicles, where

Isma'il and his army suffered a decisive defeat.

### The vicissitudes of Tahmasp's reign and after

Although the Safavids experienced military defeat at Chaldiran, the political

outcome of the battle was a stalemate between the Ottomans and Safavids,

even though the Ottomans ultimately won some territory from the Safavids.

The stalemate was largely due to the 'scorched earth' strategy that the Safavids employed, making it impossible for the Ottomans to remain in the

region. 30 Nevertheless, the defeat was a personal setback for Isma'il, who

appears to have spent the rest of his life thereafter involved only in the internal

affairs of his state.

It was not until Isma'il's son, Tahmasp (r. 930 84/1524 76), took the throne

that the policies his father established were fully enforced and started to become integrated into Iranian society. Tahmasp was ten years old when he

came to the throne on Monday, 19 Rajab 930/23 May 1524, and therefore could

not immediately establish himself as king. A co regency was established consisting of Div Sultan Rumlu and Kapak Sultan Ustajlu. 31 The two factions

represented by these individuals came into conflict that eventually led to outright civil war between the Rumlus and their supporters and the Ustajlus

and their backers. Although the civil war kept the various Qizilbash factions at

bay, during the early years of Shah Tahmasp's reign, Qizilbash leaders still

managed to become extremely powerful and for all practical purposes ruled

the various provinces under their control independently. It took Shah Tahmasp some nine years to re establish his authority.

30 See Ef 'Caldiran' 0- R- Walsh).

31 Martin B. Dickson, 'Shah Tahmasb and the Uzbeks: The duel for Khurasan with 'Ubayd

Khan (930 946/1524 1540)', Ph.D. dissertation., Princeton University (1958), p. 52.

Cambridge Histories Online © Cambridge University Press, 201 1

Iran under Safavid rule

Externally, Shah Tahmasp had to face the Uzbek challenge coming from the east and the Ottomans to the west. The Uzbeks were first to take advantage of Tahmasp's initial weakness when he ascended the throne. The

research of Martin Dickson has shown that there were actually two distinct

Uzbek states bordering on Khurasan that the Safavid monarch had to contend

with: the Yadgarid Uzbeks of Khwarazm and the Abu'l Khayrid Uzbeks of Ma

Wara' al Nahr. It was the latter, led by 'Ubayd Khan, that posed the greatest

threat to the Safavids. 32 Although Tahmasp was successful in retaking Herat at

one stage, the Uzbeks posed a fairly constant threat to the eastern borders of

the Safavid state, invading Safavid territory a total of five times during Tahmasp's reign. 33

Tahmasp also had to deal with external threats from the Ottomans, in particular when Sultan Siileyman 'kanuni' (law giver), or 'the Magnificent' as

he is known in the West (r. 926 74/1520 66), came to power. Despite four campaigns against the Safavids, the Ottomans were never able to make significant inroads into Safavid territory, for several reasons. First of all, they

were trying to expand their empire in a westward direction as well as towards

the east, and so their resources were thinly stretched. Second, the route from

Istanbul to Iran was long and difficult. It involved crossing mountain passes

which became covered with snow and impossible to penetrate in the winter.

Furthermore, the previously mentioned 'scorched earth' strategy that the Safavids employed deprived the Ottomans of any resources that they might

have acquired from the land on the passage to Iran. Hostilities against the

Ottomans came to an end with the signing of the treaty of Amasya, which fixed the north west border of the Safavid state and divided Georgia between

the Safavids and the Ottomans. 34 Although the Safavids were successful in

keeping back the Ottomans, in 962/1555 Shah Tahmasp nevertheless trans

ferred the Safavid capital from Tabriz to Qazvin, which better protected the

Safavid capital from any future Ottoman threats.

Of all Tahmasp's neighbours during this period, the Mughals perhaps presented the least danger to the Safavid state. The Mughal emperor Humayun, facing problems both externally and internally, was forced to flee India and in 951/1544 sought refuge at Shah Tahmasp's court. In an act

of great humiliation, he was forced to acknowledge his loyalty to Shi'i Islam.

After presenting Tahmasp with handsome gifts, including a large diamond

32 Ibid., p. 23.

33 These took place in 930/1524, 930 2/1524 6, 933 5/1526 8, 935 7/1529 31, 937 41/1531 4 and 941 4/1535 8. See ibid., pp. 1 4.

34 Ef 'Tahmasp', (Roger Savory).

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

that weighed, according to the Safavid sources, approximately three quarters

of a pound, Humayun was sent on his way back to India with support troops. 35

### Shah Tahmasp's religious policies

Tahmasp was a very different character from his father. He did not want to be

regarded as a semi divine figure, and he took steps to crush any sort of religious

expression that considered him a messianic figure thereby transfiguring notions

of Safavid kingly legitimacy. This took some time to accomplish; the Italian

traveller Michele Membre, who visited Tahmasp's camp when it was near Marand, describes how Anatolian Turcomans came to join Tahmasp: 'Thus,

there were of those Turcomans, horsemen, with their arms and lances, to the

number of 600, who were stationed over against the court of the said Sophy, at a

distance, riding round and round; all together they kept crying "Allah, Allah". . .

until the Shah came forth from his apartments, at the entrance.' 36 Furthermore,

although Shah Tahmasp may have suppressed groups who proclaimed him as

the Mahdi, he continued to promote the notion that he had a special relationship

with this figure. 37 Membre describes how Shah Tahmasp would not allow one

of his sisters to marry "because, he says, he is keeping her to be the wife of the

Mahdi. This Mahdi is a descendant of Ali and Muhammad, and he says he keeps

her on the grounds that he is the court and the true place of Muhammad. Thus,

too, he has a white horse, which he keeps for the said Mahdi ... no one rides this

horse and they always put it in front of all his horses.' 38 In addition to down

playing the ghuluww tendencies exhibited during Ismail's reign and earlier,

during Tahmasp's reign, both ghuluww expressions of religiosity and Sunnism

were persecuted, leading to many individuals leaving Iran for Mughal India.

Tahmasp further solidified Iran's new Shi°i identity by formally including within

his military corps groups of tabarrffiyan. These individuals were in charge of

ensuring that the practice of ritual cursing of the first three Sunnl caliphs was

carried out throughout Iran, and they also engaged in surveillance activities in

an attempt to detect any Sunni activity. They received the direct support of

Tahmasp himself. 39

- 35 Iskandar Beg Munshi, 'Alam ardyi 'Abbdsi, p. 99; trans., p. 164.
- 36 Michele Membre, Mission to the Lord Sophy of Persia (1539 1542), trans. A. H. Morton (London, 1993), p. 18.
- 37 Moojan Momen, An introduction to Shi'i Islam (New Haven, 1985), pp. 109 10.
- 38 Membre, Mission to tfte Lord Sophy, pp. 25 6.
- 39 Rosemary Stanfield Johnson, 'The Tabarra'iyan and the early Safavids', Iranian Studies,

# Cambridge Histories Online © Cambridge University Press, 201 1

### Iran under Safavid rule

Despite this relative difference in Isma'il and Tahmasp's relationship with the

Qizilbash with regards to their messianic position, Tahmasp continued the

practice of marrying into prominent Qizilbash families. Recent scholarship on

the Safavid family has traced kinship ties with the Safavids and the Tekelu

Qizilbash tribe, and shown that the Safavids pursued this policy in order to

broaden their base of support and enjoy continued Qizilbash loyalty. 40 Although this policy changed by the end of the sixteenth century, during the

reigns of Shah Ismail and Shah Tahmasp, it brought advantages to the Qizilbash

in terms of wealth and prestige for the offspring of these alliances and Oizilbash

loyalty and an ever growing kinship network for the Safavid royal family.

Early Safavid political legitimacy, until the time of Shah Abbas, rested on three pillars: the king as the shadow of God on earth in line with pre Islamic

Persian notions of kingship; the king as the shaykh of the Safaviyya Sufi order;

and the king as the representative of the seventh imam, Musa al Kazim, from

whom the Safavids claimed descent. This ideological platform is reflected in

both Safavid historical writing and painting. During Shah Tahmasp's reign,

chroniclers rewrote the Safavid past in order to show that the Safavid Sufi

founders had always been practising Twelver Shils. For example, Amir Mahmud, son of a well known late Timurid/early Safavid chronicler Khwandamir, used his father s HaWb al siyar as a model which he rewrote in

significant ways for his own history, known as the Dhayl i halnb al siyar. For

example, in his Safvat al safa, Ibn Bazzaz describes in detail the illness, death and

burial of Shaykh Zahid, Shaykh Safi's pir/murshid (Sufi guide). Amir Mahmud

transformed the account of rituals performed before the burial, and the burial

itself, into a specifically Twelver Shi'i funeral. The following parallel passages

illustrate the process of historical revision reflecting the religious transformation

that Iran was undergoing during Shah Tahmasp's rule:

#### Safvat al safa

Shaykh Safi performed all of the religious, customary and ceremonial duties

that were necessary and if the Shaykh forgot something because of fear, the

spirit of Shaykh Zahid taught him until he did it, and he assisted and helped

him in all that he did and did not do until the necessary duties and customs

were completely finished. Then he performed a formal burial in his luminous,

fragrant sepulchre. 41

40 See Maria Szuppe, 'Kinship ties between the Safavids and the Qizilbash amirs in late

sixteenth century Iran: A case study of the political career of members of the Sharaf al

Din Oghli Tekelu family', in Charles Melville (ed.), Safavid Persia: The history and politics

of an Islamic society (London, 1996), pp. 79 104.

41 Ibn Bazzaz, Safvat al safa, p. 248.

213

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Hablb al siyar

Shaykh Safi al Din proceeded with the necessities of preparing and shrouding

[the body], and performed the customs of mourning. 42

Dhayl i hablb al siyar

Shaykh Safi al Din commanded that his pure body be washed according to the

custom of the Prophet and in conformity with Twelver practice, and shrouded him, and offered prayers at his blessed funeral; and they buried

him in a suitable place in that region, and proceeded to build a tomb for that

unique one of the age. 43

As seen in these passages, the original episode in Sajvat al saja describes how

after Shaykh Zahid died they buried him, thus completing the requisite duties

of a formal burial (dafn i sun). In Amir Mahmud's chronicle, Shaykh Safi washed the body according to the customs of the Prophet (sunnat i rasul) and in conformity with Twelver practice. 44 Historians writing during Shah

'Abbas's reign reproduced this particular version of the narrative in their accounts, and in this way they continued to propagate the notion that the early Safavids were practising Twelver Shi'is.

In 940/1533, Shah Tahmasp himself commissioned a certain Abu al Fath

Husayni to 'update' the Sajvat al saja in certain ways. Al Husaym altered the

preface which contained the genealogy, and the epilogue. This royal command to revise the Sajvat al saja reflects the Safavids' preoccupation with their

earlier history and legitimising principles. However, even before al Husaym

made his revisions, changes had been made to the Safavid genealogy which

extended Firuz Shah's ancestry back to the seventh imam of the Imami Shi'a,

Musa al Kazim, and added the title 'sayyid' to the names of the shaykhs and

their ancestors. Indeed, as Roger Savory has pointed out, reworkings of the

Safavid genealogy included the addition of four unknown individuals simply

named 'Muhammad' to extend the genealogy back to Musa al Kazim. 45

As the borders of the Safavid state expanded, and as Safavid historiography

evolved to reflect changing notions of politics, kingship and religion, so too did

Safavid artistic achievements. For example, Safavid miniature painting during

this time found its greatest expression in the form of a Shah noma completed

during the reign of Shah Tahmasp. Shah Isma'il initially commissioned the work

as a gift for his nine year old son, Prince Tahmasp. The manuscript eventually

42 Khwandamir, Hablb al siyar, p. 417.

43 Amir Mahmud ibn Khwandamir, Iran dar ruzgar i Shah Isma'il va Shah Tahmasb Safavl,

ed. Ghulam Riza Tabataba'i (Tehran, 1370 [1991]), p. 42.

44 Ibid.

45 Roger Savory, Iran under the Safavids (Cambridge and New York, 1980), p. 3.

214

Cambridge Histories Online © Cambridge University Press, 201 1

Iran under Safavid rule

found its way to the Ottoman empire, where it may have been presented to the

Ottoman sultan Murad III (r. 982 1003/1574 95) as a coronation gift from Shah

Tahmasp in 984/1576. 4 Martin Dickson and Stuart Cary Welch, in their massive

undertaking to study this important illuminated manuscript, were able to identify at least four senior painters and five younger artists who worked on

the 'Houghton Shah noma as it is sometimes called, although only two of the

paintings are actually signed. 47 In this great manuscript, often groups of artists

worked on individual paintings, although some of the finest illustrations were

executed by one artist. 48 It was probably the great artist Sultan Muhammad who

directed the project at first, assigning specific illustrations to particular artists,

depending on their abilities. 49 He was then succeeded by Mir Musawwir, who

was replaced by Aqa Mirak 50 Some artists specialised in backgrounds, others in

portraits, and still others in battle scenes or tragic events. Completed pages of

illustrations were then passed on to specialists who gilded and framed the pages

and added various ornaments to the pages. 51 This particular Shah noma contains

perhaps the greatest and certainly the most famous miniature painting in all of

Persian art: Sultan Muhammad's 'The Court of Gayumars'. According to Welch

and Dickson, the painting represents a combination of Tabriz Turcoman and

Timurid Herati artistic traditions. The painting shows the first king of Iran,

Gayumars, seated on a mountain top. On either side of him stand two lines of

individuals dressed in leopard skins. The rocks and mountains in the back ground of the painting contain hidden pictures of people and monsters, perhaps

'earth spirits'. 52. It is no coincidence that the Safavid kings would choose to direct

their royal patronage to a Shah noma; ever since the Mongols invaded Iran, the

production of illustrated Shah nomas was an important way in which kings

legitimised their rule. For the Mongols in particular, who were ruling as outsiders, producing a Shah noma helped legitimise rule over their Iranian

subjects. And the Safavids, who claimed in part to be ruling as the shadow of

God on earth in line with pre Islamic notions of kingship, were no exception.

Although some Safavid artists, namely painters, found patronage with the first two Safavid kings, others, whether out of religious conviction, or religious

46 Stuart Cary Welch, A king's book of kings: The Shah nameh of Shah Tahmasp (New York,

1972), pp. 16 17. See also M. B. Dickson and S. C. Welch, The Houghton Shahnameh (Cambridge, MA, 1981).

47 Ibid., p. 21.

48 Ibid., p. 25.

49 Ibid., p. 20.

50 Ibid.

51 Ibid., p. 21.

52 Ibid., pp. 88 91.

215

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

persecution, or the promise of higher salaries, left Iran for neighbouring Mughal India. For example, the late TimuridV early Safavid historian Khwandamir, who was a Zaydi ShTi, went to India in 935/1528 and met Babur (r. 932 7/1526 30). Babur, whom Khwandamir often accompanied on

various campaigns, mentions Khwandamir's presence in his autobiographical

memoirs, the Babur ndma. 53 Shortly after their meeting, Babur died and was

succeeded by his son Humayun, to whom Khwandamir dedicated his Humayun

ndma, also known as the Qaniin Humdyunl (940/1534). 54 Khwandamir enjoyed

great prestige under Humayun, who eventually made him the amir i muwdrrikh,

or 'chief chronicler'. 55 As a result, Khwandamir bridged the historiographical

traditions of the Safavids and the Mughals by writing for both dynasties.

During Akbar's reign (r. 963 1014/1556 1605), Mughal historians utilised, or

at least were familiar with, Mirkhwand's Rawzat al safa, a late Timurid work,

because a certain Mir Ghiyath al Din 'Ali 'Naqib Khan' had apparently committed to memory the seven volumes of Rawzat al safa, thus reflecting

the popularity that this work enjoyed in at least some Mughal circles. 56 Nagib

Khan came from a well known family that had originally served the Safavids.

His father was Mir c Abd al Latif Qazvini, one of Akbar's tutors, and his uncle

was Mirza 'Ala al Dawla 'Kami' Qazvini, author of the Nafa'is al ma'aihir, a

biographical dictionary of Persian poets. 57 Naqib Khan's grandfather was

Yahya ibn Abd al Latif Husayni Qazvini. The latter lived in Iran during the reign of Shah Tahmasp, and wrote the Lubb al tavarikh. Husayni Qazvini, a

Sunni, was eventually put in prison by Shah Tahmasp and died there two years later in 962/1555. Ten years later, his family left Iran for India (in 973/1565), at Humayun's invitation. 58

Safavid society under Shah Isma'il and

Shah Tahmasn

Shah Tahmasp

After Shah Isma'il established his rule over Iran, the Turkic Qizilbash tribes

(uymdq) that supported him in his bid for power were granted significant posts

53 See Babur, The Baburnama: Memoirs of Babur, prince and emperor, trans, and ed. Wheeler

M. Thackston (New York, 1996), pp. 403, 442.

54 Khvandamir, Qaniin i Humdyunl, ed. M. Hidayat Hosain (Calcutta, 1940).

55 Ibid., p. xv.

56 Khaliq Ahmad Nizami, On history and historians of medieval India (New Delhi, 1982), p. 225.

57 See D.N. Marshall, Mughals in India: A bibliographical survey of manuscripts (London, 1967; repr. New York, 1985), p. 54.

58 C. A. Storey, Persian literature: A bio bibliographical survey, 3 vols. (London, 1927), p. in; rev. and trans. Yu E. Bregel as Persidskaya literatura: Bio bibliograficheskii obzo, 3 vols. (Moscow, 1972), p. 399.

216

Cambridge Histories Online © Cambridge University Press, 201 1

## Iran under Safavid rule

in the new government. In particular, they held the position of amir al 'umara\

or 'chief Qizilbash leader', a term that was interchangeably used with wakil

(deputy). Prominent Qizilbash leaders furthermore received prestigious pro

vincial governorships and the responsibilities of controlling that province and

mobilising their troops at the request of the king. 59 All together, they formed

what could be called a 'military /governing elite' in the new Safavid state.

addition to prominent Qizilbash, the other main element in Safavid society

consisted of the Persian speaking elite who formed the administrative classes

under previous ruling dynasties. The most important positions within this

social group were the vizier, or chief administrator, and the sadr, who was the

chief religious figure. ° Although the oft repeated quote by Minorsky that these two groups, the so called 'Turks and Tajiks', mixed 'like oil and water'

and that their spheres of power were quite separate may have held true to

some degree, there were certainly significant exceptions. : These included, for

example, the famous court secretary and historiographer Iskandar Beg Munshi, who was a Turcoman. Hasan Beg Rumlu, another important chroni

cler from the era of Shah Tahmasp, was also of Qizilbash background, as evidenced by his name 'Rumlu'.

After Shah Tahmasp's reign of fifty two years, the longest reign of any Safavid

or indeed any Persian king of the Islamic period, he was succeeded by his son

Isma'il II (r. 984 5/1576 7), who is best known for having attempted to return

Iran to Sunni Islam. Safavid chroniclers do not have very many good things to

say about Isma'il II's religious policies. For example, Iskandar Beg certainly

shows little admiration for this king in his chronicle. He accuses him of being

'guilty of a number of forbidden practices', such as 'associating with certain

crazy fools among the qizilbash'. 2 In narrating the death of Isma'il II, he states

that 'since mostpeople had suffered as a result of the evil actions of Shah Isma'il

II, no one was particularly disturbed by his death, and the transfer of power was

effected without any disturbances'. 63 Isma'il II did not stay in power for very

long only one year, approximately, until a group of Qizilbash with the assistance of his sister, Pari Khan Khanum, poisoned him. 64 He was succeeded

by his brother, the nearly blind Sultan Muhammad Khudabanda. During this

59 See Dickson, 'Shah Tahmasb and the Uzbeks', pp. 11 13.

60 Ibid., p. 14.

61 Tadhkirat al muluk, trans, and ed. V. Minorsky (London, 1943), p. 188. See also Savory,

Iran under the Safavids, pp. 31 2.

- 62 Iskandar Beg Munshi, 'Alam arayi 'AbbdsT, p. 294; trans., p. 199.
- 63 Ibid., p. 221; trans., p. 330.
- 64 See Savory, Iran under tfte Safavids, p. 68.

217

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

king's reign, real power lay in the hands of his wife, Mahd i 'Ulya\ and his sister,

Pari Khan Khanum. After Mahd i 'Ulya' orchestrated the murder of Pari Khan

Khanum, she reigned supreme, much to the dismay of the Qizilbash. The

that 'harem politics' and Qizilbash supremacy had become a major feature of

Safavid politics at this time reflects the decentralised nature of the Safavid state

in the aftermath of Shah Tahmasp's reign, and indeed, during the reigns of

Isma'il II and Sultan Muhammad Khudabanda, Iran again lapsed into political

fragmentation as individual Qizilbash leaders became increasingly powerful.

They successfully conspired to murder Mahd i 'Ulya 1 and they chose the next

king, 'Abbas. 5 They also enjoyed governorships of important Iranian cities and

provinces. At the same time, the neighbouring Uzbeks and Ottomans encroached upon Safavid territory, eager to take advantage of a weakened

Safavid Iran. It was not until the reign of Shah Abbas (r. 996 1038/1588 1629)

that centralised rule became re established in Iran.

The reign of Shah 'Abbas: changes in the military and administrative structure of the state

Shah 'Abbas came to the throne in 996/1588 in a succession where a Qizilbash

chief, Murshid Qui! Khan Ustajlu, played the most important role, for he was

the one who chose the seventeen year old 'Abbas to be king. Shah Abbas goes down in history perhaps as Safavid Iran's most successful and famous

monarch. However, at the beginning of his reign, he faced the challenge of

'reconquering' Iran before dealing with the ever present external threats to

the Safavid state. The chronicler Iskandar Beg Munshi characterises Shah

'Abbas's challenges in the following manner:

He [Shah 'Abbas] was confronted by two powerful monarchs, the problem of

Qizilbash disunity had not been solved, and he was faced by domestic revolts . . . and by rebellions on the part of the semi independent rulers on

the borders of the Safavid empire, who had taken advantage of fifteen years of

weak Safavid rule since the death of Shah Tahmasb to shake off Safavid suzerainty and assert their independence. 67

65 See Ibid., pp. 70 5.

66 Ibid., p. 75.

67 Iskandar Beg Munshi, 'Alamarayi 'Abbasi, pp. 409 10; trans., p. 587. This is at the

beginning of Iskandar Beg's section on the Year of the Ox, 998/1589 90, in reality 997

and the third regnal (juliis) year, according to McChesney's corrected dating system. See

Robert D. McChesney, 'A note on Iskandar Beg's chronology', Journal of Near Eastern

Studies, 39 (1980), p. 62.

# Cambridge Histories Online © Cambridge University Press, 201 1

#### Iran under Safavid rule

Shah 'Abbas addressed these challenges by implementing a twofold strategy that

consisted of destroying rebellious and disobedient Qizilbash leaders on the one

hand and, on the other, raising a new army consisting of ghiddms, or slaves, who

had been brought into Iran from the Caucasus, and transforming them into a

new elite. In his attempt to suppress Qizilbash power, the monarch systemati

cally removed those Qizilbash who were rebelling against his rule, and replaced

them with ghulam leaders who would show allegiance to the monarch alone.

Perhaps the most dramatic example of Abbas's contest against the Oizilbash

can be seen in his dealings with Ya'qub Khan (d. 998/1590), the Dhu'l Qadr

governor of ShTraz. The chroniclers of Shah Abbas narrate this episode in great

detail, giving it more attention than nearly any other episode in the early period of

his reign. One historian, the chronicler Afushta yi Natanzl, even stated that this

was the event that inspired him to write his history: "When the news of this

manifest victory spread far and wide throughout Iran, it became a source of

astonishment to the masters of knowledge because the fortress of Istakhr, by

virtue of its strength, had been a source of glory to the Eastern kings . . . The

strangeness of this wonderful incident and the good fortune of the Alid king

became the reason for the limping pen to hasten in writing this story/Ya'qub

Khan was the governor of Fars who was effectively ruling the region independ

ently when Shah Abbas came to power. He also controlled Kirman, Abarquh and

Yazd, and therefore posed a threat to the king. 69 Prior to his rebellion, Ya'qub

Khan associated with members of the Ni'matullahi Sufi order, in particular

Mirrnlran Yazdi and his son Shah Khalil Allah, who was allied with Ya'qub Khan

for some time. 70 The khan surrounded himself with a number of Qizilbash rebels

of various tribes, including Mukhtar Sultan of the Sharaf al Din branch of the

Tekelu Qizilbash. 71 In order to avoid what would have been certain execution.

Ya'qub Khan sought refuge in the fortress of Istakhr in Shiraz. Shah 'Abbas tried to

use diplomacy both before and after Ya'qub Khan entered the fortress, and sought

a meeting with the khan, but was unsuccessful in doing so. He was successful,

however, in persuading him to leave the fortress. Ya'qub Khan eventually made

his way to the king's court, where he was ultimately executed in 998/1590.

While the episode of Ya'qub Khan perhaps symbolically marked the victory

of the king over the Qizilbash, at the same time, in order to bypass the

68 Mahmud ibn Hidayat Allah Afashtah yi Natanzl, Naqdvdt al dtharfi dhikr al akhydr, ed.

Ihsan Ishraqi (Tehran, 1350 [1971]), pp. 78.

69 See Szuppe, 'Kinship ties', p. 93.

70 See Said Amir Arjomand, The shadow of God and tfte hidden imam: Religion, political order,

and societal change in Shi'ite Iran from the beginning to 1890 (Chicago, 1984), pp. 116 17.

71 Szuppe, 'Kinship ties', pp. 92 3.

## The New Cambridge History of Islam

Qizilbash problem militarily, Shah 'Abbas developed a new 'pillar of legitimacy'

whereby he called for the direct loyalty of the ghuldtn elite that formed his new

army. By issuing the call for shahsevan, or love for the king', 'Abbas attempted to

bypass the Qizilbash altogether. The fact that Shah Abbas needed to raise this

new army at all reflects some of the political problems that he faced when he

came to power. Most notably, Shah 'Abbas found it difficult to make legitimising

claims on the basis of being the representative of the hidden imam, because the

clerical classes had become increasingly powerful and were acknowledging the

fact that genealogical descent from the imams was irrelevant in officially repre

senting the hidden imam. Furthermore, as the Sufis had increasingly fallen out of

favour, claims on the part of the king to be the head of the Safavid Sufi order also

did not carry much weight. Thus, in addition to appealing to the notion of shahsevan, Shah 'Abbas's chroniclers added another new theme to the legitimis

ing platform: drawing connections between Shah Abbas and Temiir. These

shifts in political currents are reflected in chronicles such as Siyaqi Nizam's

Futuhdt i humayun, a history of Shah Abbas's campaign to Khurasan (1007/

1598). In this history, Siyaqi Nizam goes to considerable lengths to connect

Shah Abbas's name with Temiir's. In his preface, Siyaqi Nizam includes an

interesting passage in which he links, by alphabetical and numerological (abjad)

means, the Safavid and Temurid dynasties. Here, Siyaqi Nizam states that, since

Shah Abbas was a descendant of the Twelve Imams, there were twelve major

events in his reign. He then compares this to Temiir's reign, noting that even

though Temiir, the 'supreme lord of the fortunate conjunction (sahibqiran i a'la)'

did not pay attention to whether the time was auspicious or not, his undertakings

nevertheless occurred at auspicious times/ 2 Thus, Siyaqi Nizam attempts to link

the twelve great events in Shah Abbas's reign (he does not state what they

were) which numbered twelve because of his being a descendent of the Twelve

Imams with the auspiciousness of the events of Temiir's reign.

Other evidence of this new Timurid emphasis as a legitimising factor exists

in Iskandar Beg Munshi's chronicle, where he too refers to Shah 'Abbas as

sahibqiran and explains why he does so:

It will not have escaped the notice of perspicacious persons that the title of

saheb qeran (lord of the auspicious conjunction of planets) has, in the past,

frequently been bestowed on princes by secretaries wishing to flatter their

masters. In the case of Shah 'Abbas, however, it is verifiable by fact. From the

time of his birth up to the present day, there has occurred the conjunction of

72 Siyaqi Nizam, Futukat i humayun, ed., trans, and arm. Chahryar Adle as 'Fotuhat e homayun:

Les victoires augustes, 1007/1598', Ph.D. dissertation, University of Paris (1976), p. 334.

Cambridge Histories Online © Cambridge University Press, 201 1

Iran under Safavid rule

various celestial bodies, the prognostications of which corroborate events in the

life of Shah 'Abbas. According to the calculations of astrologers, each of these

conjunctions foretells the appearance of a powerful and fortunate prince. 73

## Religion during the reign of Shah 'Abbas

Despite the new Timurid emphasis, Shah 'Abbas still presented himself as a

devout Shi'i. One of his chroniclers, Jalal al Dm Munajjim Yazdi, referred to

him as the kalb i dstdn i 'AE('the dog of 'All's threshold'), to express the king's

great humility before Shi'i holy figures. Shah 'Abbas's displays of religiosity

were public and designed to attract attention. Aside from erecting beautiful

and expansive mosques in his new capital city of Isfahan, as will be discussed

below, in 1010/1601 he undertook a pilgrimage on foot to Mashhad in order to

visit the shrine of Imam Riza (d. 203/818). 74 It took him approximately two

months to complete the trip. Although the reason that he gave for making the

pilgrimage was to fulfil a vow, we do not know the specifics of this vow, and the actual rationales were complex and included diplomatic, political and

religious motivations. 75 The political motive may have been to reassert the

legitimacy of the Safavid monarchy after the instability that followed the death

of Shah Tahmasp, and to claim Mashhad for the Safavids after conflicts with

the Uzbeks over the city. 7 At the same time, by establishing Mashhad as a

place for his Shi'i subjects to visit, Shah 'Abbas may have been trying to redirect the pilgrimage to Mecca, which at this time, as a result of conflicts

with the Ottomans, posed major challenges to those living in Iran. 77 It may

also be that he was inspired by the neighbouring Mughal emperor Akbar, who

also undertook pilgrimages on foot several times during his reign. 7

Shi'i religiosity was not just the domain of the king. During this time, Shi'i

scholars and clerics continued to expound the doctrines and beliefs of the state

religion. Perhaps the most important religious figure during the reign of Shah

'Abbas was Shaykh Baha' al Din al 'Amili, sometimes known as Shaykh Baha'T

(d. 1031/1622). Iskandar Beg pays glowing tribute to him in his section on

'Sayyids, Shaykhs and Divines', and 'Notable Deaths', saying that he was profoundly learned in all branches of knowledge, particularly jurisprudence'.

73 Iskandar Beg Munshi, 'Alam drdyi 'Abbasl, p. 1102; trans., p. 519.

74 Charles Melville, 'Shah 'Abbas and the pilgrimage to Mashhad', in Charles Melville (ed.),

Safavid Persia: The history and politics of an Islamic society (London, 1996), pp. 191 229.

75 Ibid., p. 191.

76 Ibid., pp. 197 8.

77 Ibid., pp. 215 16.

78 Ibid., p. 193.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

He also refers to him as 'the foremost scholar of his age', noting that he enjoyed a great deal of royal favour: 'The shah kept him constantly at his side:

both when he was in the capital and when he was making a journey some where, the shah would visit his dwelling to enjoy his company/ 79 Although

Iskandar Beg does not say so, some considered him to be the mujaddid, or

'renewer' of the eleventh/ seventeenth century. ° Shaykh BahaT was appointed to the post of Shaykh al Islam of Isfahan, a position which he held

for a short time. : He was extremely prolific and wrote on a diverse variety of

topics, including scientific works such as treatises on mathematics, numerol

ogy and astrolabes; traditional Islamic sciences such as tafslr and hadith, and

books of poetry, which reflect his Sufi tendencies. He was teacher to several

famous scholars, including Mulla Muhsin al Fayz al Kashani (d. 1091/1680) and

Mulla Sadra (d. 1050/1649), both of whom were significant Shi'i writers and

philosophers in their own right. Shah Abbas respected him greatly, and the

shaykh accompanied the king on various diplomatic and political missions, or

went on such trips on his own as the king's representative. For example, several chroniclers, including the court astrologer and historiographer Jalal al

Din Munajjim Yazdi, Qazi Ahmad Qummi and Natanzi all note several instances in which Shaykh Baha ] i was sent on various missions on Shah 'Abbas's behalf. These include the shaykh's bringing the rebellious vizier Yuli Beg out of the fortress of Tabarak, and his trip to Gilan and elsewhere

for the purpose of arranging temporary marriages. 2 One chronicler, Mirza

Qasim Beg Junabadi, even stated that he was involved in retrieving Ya c qub

Khan, the rebellious Dhu'l Qadr Qizilbash leader, from the fortress in Istakhr. 83

Another important Shi c I philosopher theologian from this period was the

famous philosopher Sayyid Muhammad Baqir Astarabadi, better known as Mir

Damad (d. 1040/1630<sup>^</sup>, who is widely regarded as the founder of the so called

'school of Isfahan'. Astarabadi received the title 'Damad' or 'son in law' as a

result of his marriage to the daughter of the famous theologian Shaykh Ali b.

Husayn Karaki. Although like Shaykh Baha'i, Mir Damad wrote on a variety of

topics, his main interest was in the field of philosophy, where he attempted to

79 Iskandar Beg Munshi, 'Alam ara yi 'Abbasi, p. 157, trans., p. 249.

80 See EIr 'Baha' al Din Ameli (E. Kohlberg).

81 Ibid.

82 See Mulla Jalal al Din Munajjim Yazdi, Tarikh i 'Abbaslyd ruzndma yi Mulla Jalal, ed. Sayf

Allah VahJd Niya ([Tehran], 1366 [1987]), pp. 87, 109, 244 5, 268, 301 and 347; Qazi Ahmad

Munshi Qummi, Khuldsat al tavankh, ed. Ihsan Ishraqi (Tehran, 1363 [1984]), vol. II,

p. 1086; Natanzi, Nagavat al athdr, pp. 334 5, 566.

83 Mirza Beg Junabadi, Rawzat al safaviyya, ed. Ghulam Riza TabatabaT majd (Tehran,

1378 [i999]), P- 719-

Cambridge Histories Online © Cambridge University Press, 201 1

#### Iran under Safavid rule

bring together the philosophies of Avicenna (Ibn sina) (d. 428/1037) and Suhrawardi (d. 587/1191). 84 He also had an interest in the philosophies of time.

and the terminology that earlier philosophers used to describe time related

phenomena. Mir Damad was an important figure at the courts of Shah 'Abbas I

and his successor Shah Safi I (r. 1038 52/1629 42), and at least one of his works.

the Persian aljadhawat, was written at the command of the former.

On a popular level, Shi°i rituals and practices also evolved and developed considerably during the time of Shah Abbas. These practices were, like the

king's own expressions of religiosity, quite public in nature and often promoted

by the king himself. These included, for example, the development of the commemoration of Muharram into an elaborate public festival. 5 Such festivals

included mourning processions, gatherings and pageants. These especially

expanded after the capital was transferred to Isfahan. At the same time, the

people of Iran, including the king, commemorated traditionally Persian festivals

such as the feast of Nawruz (new year), which under 'Abbas was celebrated for

several weeks. Aspects of this festival and other pre Islamic Persian festivities

had an influence on not only observations of Muharram, but also 'Ashura\

Both internal and external sources also point to other expressions of popular culture, some of which are just now beginning to receive scholarly

attention. Shah 'Abbas apparently was responsible for instituting festivals of

'lights' which involved firework displays and the burning of lights whenever

he entered a particular city or on other occasions. 87 The king also encouraged

neighbourhood factionalism between two different groups known as the Haydaris and the Ni'matis. The names come from earlier medieval Sufi shaykhs, and the practice of civic factional competition or strife also dates

back to earlier centuries. According to one traveller's account, Shah 'Abbas

promoted these conflicts in order to 'divide and rule' and to make sure that

expressions of violence were safely contained within the context of these opposing groups fighting each other with sticks and stones.

The era of Shah 'Abbas was therefore one in which notions of legitimacy had changed and evolved from the early Safavid period. 'Abbas developed

new ways to legitimise his rule and, in doing so, transformed the monarchy.

84 See EIr 'Damad, Mir (e), Sayyed Mohammed Bager' (A. Newman).

85 Jean Calmard, 'Shi'i rituals and power II: The consolidation of Safavid Shi'ism: Folklore and popular religion', in Melville (ed.), Safavid Persia, p. 143.

86 Ibid., p. 150.

87 Ibid., p. 148.

88 Ibid., p. 145. See also Hossein Mirjafari, 'The Haydari Ni'mati conflicts in Iran', trans.

and adapt. J. R. Perry, Iranian Studies, 12 (1979), pp. 135-62.

# Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

These developments are reflected in Safavid art and culture, as can be gen

erally seen in the area of architecture and specifically in the city of Isfahan.

Safavid art and culture: the city of Isfahan

The greatest expression of Safavid artistic achievement during the era of Shah

'Abbas was no doubt the city of Isfahan. Abbas moved the capital city to Isfahan from Qazvm in ioo5/i596f. to make the capital safer from potential

Ottoman attack. Isfahan was a planned city, designed to become the commer

cial and political centre of the Safavid state. The entire city was designed to

reflect the power and legitimacy of the king. Symbolically, we may also view

Isfahan as a reflection of Shah Abbas's successful efforts at transforming the

Safavid state into one that reflected the international power of the dynasty, the

increasing importance of the royal household and a new style of kingship that,

in a very tangible way, reflected the Shah's power.

Shah 'Abbas's Isfahan was built around a large square, known as the Maydan i

nagsh i jahan. The square was constructed with shops on both sides of the

two storey perimeter walls. This construction was done in two phases. The

initial phase and purpose of the square, undergone in 998 1003/1590 5, was for

royal entertainment and sports. The second phase, begun in ion 12/1602 4,

expanded or transformed the square into a commercial centre. 89 Each side of the

square had an important building. These included the All Qapu palace, a five

storey edifice with a large balcony from which the king watched polo tourna

ments and other events taking place in the square. On another side was the

Masjid i Shah, the congregational mosque, which was covered with turquoise

tiles. Work on this mosque started approximately seven years after the commer

cial renovation of the square. 90 There was definitely a commercial motivation

even in the building of this mosque, because it was strategically situated at a site

whereby visitors had to cross the market area twice in order to enter the mosque. 91 The Shaykh Lutf Allah mosque, or the Great Dome mosque, the

last major undertaking on the royal square, was not completed until after the king's death. This mosque was intended for the monarch's own private

worship. Like the Masjid i Shah, the Shaykh Lutf Allah mosque is decorated on

the exterior with beautiful painted tiles. Finally, at the other end, opening on to

the square, was the Qaysariyya bazaar, one of the earliest structures to be built

89 Robert D. McChesney, 'Four sources on Shah 'Abbas's building of Isfahan', Muqamas, 5 (1988), pp. 114 15-

90 Ibid., p. 120.

91 Ibid.

224

Cambridge Histories Online © Cambridge University Press, 201 1

Iran under Safavid rule

on the maidan, which became the centre of Safavid trade and commerce. The

Qaysariyya represents the king's attempt to modernise commerce in the city.

This bazaar included separate sections for various types of goods such as carpets,

silks and others. The Qaysariyya complex also included caravans, mosques and

bathhouses, and the entire bazaar complex took up some n square miles. Other

features of the capital city included the chahar bagh, or four gardens complex.

This suburban neighbourhood included a great garden, a boulevard, a bridge

and a district known as the Tabriz! district. 92

## Safavid poetry

Safavid poetry has historically received much less attention than what is considered 'classical' Persian poetry, and what attention it has received has

been negative. This is largely due to the fact that it has been placed within

the context of a later literary development known as the baz gasht i 'adabi

(return) movement, whereby both Iranian and Western scholars viewed the

poetry from this period as qualitatively worse than classical poetry. 93 It has

also been traditionally seen as the poetry of 'decline'. This idea is often still

repeated today. 94 Because much of this poetry was written in India, scholars

referred to Safavid poetry using the problematic phrase sabk i hindT, or the

'Indian style', and pointed out its negatively unique features of 'metaphor ical conceits, personification proverbs, poetic etiology, unusual imagery, colloquialisms, tangled syntax, ellipses and so forth'. 95 Such assessments of

Safavid poetry have also extended into prose writing, in particular histor iography. 96 Many reasons have been given for the migration of Iranian poets

to Mughal India. Earlier assessments suggested that religious persecution

and concern with developing a Shi'i orthodoxy left Safavid kings, Shah Tahmasp in particular, uninterested in promoting poetry. More recently, however, such theories have been discarded in favour of economic explan ations, which show that Safavid poets went to India due to financial

92 Ibid., p. 124.

93 Paul E. Losensky, Welcoming FighdnT: Imitation and poetic individuality in the Safavid Mughal Ghazal (Costa Mesa, 1998), p. 2.

94 For a new approach to understanding Safavid poetry, see Paul E. Losensky, '"The

allusive field of drunkenness': Three Safavid Moghul responses to a lyric by Baba

Fighani', in Suzanne P. Stetkevych (ed.), Reorientations I Arabic and Persian poetry

(Bloomington IN, 1994), pp. 227 62.

95 Losensky, Welcoming Fighani, p. 3.

96 See Sholeh A. Quinn, Historical writing during the reign of Shah 'Abbas: Ideology, imitation and legitimacy in Safavid chronicles (Salt Lake City, 2000).

225

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

incentive; India was wealthier and, furthermore, due to the fact that Mughal

emperors were Persian speaking, they promoted Persian language and culture. 97 In addition to re examining reasons for Persian poets moving to

India, recent scholarship has also re evaluated Safavid poetry and historiog

raphy, and this has led to new appraisals of its quality. In particular, Safavid

poets took earlier models that they used as a basis for innovation. Thus, like

its historiographical counterpart, Safavid poetical writing was imitative in

nature, as poets took earlier metres, themes and other aspects of classical

poems, reworking them in innovative ways. 9

Some of the most important Safavid poets included Baba Figharii (d. 925/1519),

'Urfi Shirazi (d. 999/i59of), Sharii Takallu (d. 1023/1614), Hakim ShafaT of Isfahan

(d. i037/i627f) and Sa ] ib Tabriz! (d. 1087/1676^." Rather than referring to

themselves as proponents of the sabk i hindi, these poets and others considered

themselves to have developed a 'fresh style', or taza gii% suggesting the innovative

and new nature of this poetry. Among the features of this new style of poetry was

the importance of the 'unexpected turn of thought' or 'startling connection

between image and idea'. 100 Although currendy there exists a lively debate

regarding the value of such poets and their work particularly in comparison

with their classical predecessors, there is no doubt that during the Safavid period

itself, promoters of the 'new style' were popular, enjoyed patronage of various

Safavid rulers and were in many cases extremely prolific writers. 101

# Social and economic developments

Perhaps the most significant of all Shah Abbas's economic policies and reforms

was his establishment in 1028/1619 of a royal monopoly out of the silk industry.

Like the construction of Isfahan, this policy was carried out in more than one

phase. It started with his bringing the silk producing regions of Gilan and Mazandaran under his control early on during his reign. Then, in the 1590s, he

transformed these provincial areas into crown lands. After the forced immigration

of Armenian communities into New Julfa, he monopolised the silk industry. 102

97 For an overview of these issues, see Stephen Frederic Dale, 'A Safavid poet in the heart

of darkness', in Stephen Frederic Dale, Safavid Iran and her neighbors (Salt Lake City,

2003), pp. 648.

98 See Losensky, Welcoming Fighani.

99 See ibid., ch. 5.

100 See EIr 'Saeb Tabrizi' (Paul E. Losensky).

101 See ibid.

102 Rudolph P. Matthee, The politics of trade in Safavid Iran: Silk for silver, 1600 1730 (New York, 1999), p. 84.

226

Cambridge Histories Online © Cambridge University Press, 201 1

#### Iran under Safavid rule

In order further to promote trade, in 1012/1604, Shah 'Abbas brought Armenians from Julfa, very much against their will, to live in Isfahan, where

they settled in a neighbourhood called 'New Julfa'. This population transfer

took place at a time when the Ottomans and Safavids were at war with one

another. The Armenians were allowed to construct their own churches and

worship as they pleased, and they became prosperous and powerful mer chants in Isfahan, where they enjoyed special privileges from the state. In

particular, they became very much involved in silk production and export,

and, along with the ghulams, they profited greatly from the silk trade. 103

In addition to the Armenian merchants, the same ghulams who served in Shah

Abbas's new army also formed part of the new elite that developed in the wake

of the Qizilbash decline. While the famous ghwlam Allah Verdi Khan was known

and celebrated as a great general serving under the king, he also sponsored

important building projects in the Shiraz area, such as a bridge, a double dam, a

fort, royal house and a madrasa. 104 Others of the new elite ghulam class also

participated in such projects, thus indicating that this social group engaged in a

range of activities beyond the military. These included Ganj All Khan Zek who

built a maidan complex in Kirman, as well as accompanying the king on military

campaigns and serving as governor of Kirman. 105 The most famous ghulam

patron of the Shah Abbas period was Mirza Muhammad 'Saru' (blonde) Tagi,

who sponsored the construction of entire towns and roads, and contributed to

the upkeep of StrTi shrines. 10 Allah Verdi Khan (d. 1022/1613) and his son Imam

Quli Khan (d. 1042/1633) were also involved in sponsoring other Safavid arts.

The latter, in particular, patronised calligraphy, painting and poetry, as did Saru

Taqi and the Armenian ghulam Qaracahqay Khan, who supported the Safavid

shrine in Ardabil. 107

The land reforms that the king instituted consisted primarily of transforming

significant amounts of state land into crown land. This practice continued under

Abbas's successors. It was initiated in order to pay the new ghulam army.

Qizilbash were traditionally paid through land grants known as tiyul, which

gave them considerable independence, but once Shah 'Abbas consolidated his

own power, he decided to pay the ghulams through his own crown lands. 10

103 S. Babaie, K. Babayan, I. Baghdiantz McCabe and M. Farhad, Slaves of the Shah: New elites of Safavid Iran (London, 2004), p. 52.

104 Ibid., p. 93.

105 Ibid., p. 94.

106 Ibid., pp. 97 8.

107 Ibid., pp. 120 6.

108 Ibid., p. 9.

227

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Travellers in the Safavid era

During the Safavid period, relations and interactions with Europe reached a

new peak of activity. Many Europeans, with the encouragement of the Safavid

kings, came to Iran in hopes of establishing trading houses, engaging in commerce, spreading Christianity, seeking alliances against the Ottomans and

searching for adventure. 109 Numerous such individuals wrote extensively about

their experiences in Iran and their travel narratives became well known and read

in Europe. They provided pen portraits of the various Safavid kings and trans

mitted details about customs and practices not found in other sources. These

merchants and missionaries include Jean Chardin, Tavernier and others.

Many Safavid kings engaged in diplomacy with European rulers, and European travellers helped facilitate the forging of such diplomatic contacts.

These came in the form of correspondence, embassies and other types of interactions. The Portuguese sent embassies to Iran as early as 1523. Their

main interest was protecting their naval base on the island of Hormuz, which

they had occupied since 1515. 110 Shah Isma'il was also involved in efforts to

forge alliances with European powers, in particular Emperor Charles V and

Ludwig II of Hungary, against the Ottomans. Ismail's efforts to correspond

with Charles V were inconclusive due to his death in 930/1524, but relations

with European powers continued during Shah Tahmasp's reign. By this time,

European powers had been successful against the Ottomans at sea, and the

current pope, Pius V (d. 1572), contacted Shah Tahmasp, requesting that the

Safavids attack the Ottomans. Tahmasp, however, was not interested and did

not respond positively to the pope's letter. 111 Another pope, Gregory XIII

(d. 1585), also tried unsuccessfully to instigate interest in a Safavid European

alliance against the Ottomans and sent an ambassador to Iran. Again, the Safavid state was internally weakened by the time the ambassador returned to

Europe in 1587 and did not come to Europe's assistance.

European relations with Iran reached their peak during the reign of Shah 'Abbas. The most famous travellers to Iran during this period were the Sherley brothers, Anthony and Robert. They travelled to Iran as part of vet

another attempt to gain Iran's assistance against the Ottomans, this time sponsored by the British earl of Essex, who sent Anthony and his brother to

109 Laurence Lockhart, 'European contacts with Persia, 1350 1736', in Peter Jackson and

Laurence Lockhart (eds.), The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods (Cambridge, 1986), p. 374.

no Ibid., pp. 380 1.

in Ibid., p. 384.

#### Iran under Safavid rule

Shah 'Abbas. The Shah sent Anthony back to Europe in order to gain further

support against the Ottomans. This return embassy went to Prague, Rome

and Valladolid, where they met the Emperor Rudolph (d. 1612), Pope Clement

VIII (d. 1605) and Philip III (d. 1621), respectively. 112 Both the Emperor Rudolph and the pope sent return embassies to Persia, thereby increasing

Europe's knowledge about Safavid Persia. And Shah 'Abbas in turn sent envoys laden with gifts back to Europe.

Commerce was another strong motivation for European interactions with the Safavids. A trade route was established through Russia for merchants heading to Persia, and this led to numerous contacts and companies seeking to

establish bases in Persia. One of the earliest parties to visit Iran consisted of the

English merchants Anthony Jenkinson and Richard and Robert Johnson. Other merchants also passed through Iran, notably merchants from the Russia Company. When the Sherley brothers went to Iran, they too were interested in promoting trade. Eventually, both the East India Company and

the Dutch Oost Indische Compagnie vied against each other for favour from

Persia. When the Safavids were at their peak of political power, kings con eluded treaties with these companies in order to promote trade. These agree

ments, or 'capitulations', provided protection, tax breaks, living expenses and

other incentives in order to encourage them to engage in trade in Persia. Although such agreements had disastrous effects in the later period, at the

time they were concluded they worked to the Safavids' advantage.

Religious missionaries also went to Iran in hopes, sometimes, that the monarch would convert to Christianity. This was nothing new; mis sionaries entertaining similar hopes had visited the Mongols, but were never successful in their endeavours. Nevertheless, the number of religious figures making the trip to Iran was impressive. They included Carmelites, Portuguese Augustinians, Jesuits, Capuchins and many others.

Shah 'Abbas appears to have been particularly interested in these religious

visitors and even allowed some, such as the Portuguese Augustinians, to build churches in Isfahan. 113 Some of these individuals have recorded their

accounts of visiting Persia. The Carmelites, for instance, described their audiences with Shah 'Abbas, recounting the religious discussions they had

with him about the differences between Catholicism and Protestantism. Here, Shah 'Abbas comes across as a king deeply interested in religious matters, discussing, according to Father Vincent's account of his meeting

112 Ibid., p. 387.

113 Ibid., p. 389.

229

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

with the king, four related topics, including Roman Catholicism and the role of

the pope, fasting, the Cross and free will. 114 These missionaries also included

other sorts of information in their accounts; Father Simon, for example, includes

a valuable physical description of Abbas and his court." 5

Finally, some individuals went to Iran for personal reasons, such as to search for adventure or better health. The most notable of these included Pietro della Valle, who apparently travelled eastward to the court of Shah 'Abbas for a variety of reasons, including 'glory', adventure and possibly to get

over a broken heart. 11 Pietro della Valle (d. 1652) wrote extensively of his

travels. Others who sought adventure and delighted in travel included Jean

Baptiste Tavernier (d. 1689) and Jean de Thevenot (d. 1667).

## Shah 'Abbas's conquests and campaigns

As for external relations, early on in his career, when he was still dealing with the

Qizilbash threat, Shah Abbas lost a significant amount of territory, including

Tabriz, Azerbaijan, Qarabagh, Baghdad and elsewhere to the Ottomans as a

result of the 'Peace of Istanbul', which was concluded in 998/1590. For strategic

reasons, Shah Abbas decided to turn towards the Uzbeks first, and in ioo7/i598f

he embarked on a campaign for Khurasan, accompanied by the famous ghulam

general Allah Verdi Khan. This campaign won back for the Safavids Herat,

Mashhad, Balkh, Marv and Astarabad. The campaign was celebrated in a chronicle devoted entirely to this event: Siyaqi Nizam's Futuhati humdyun.

Other chroniclers who wrote more general histories, after having to justify and

explain years of defeat to the Ottomans, could now narrate a Safavid victory, and

thus they seem to have taken special pleasure in describing the events of this

particular year of Shah Abbas's reign, when Din Muhammad Khan, the Uzbek

ruler, died in the aftermath of the battle at Rabat i Pariyan, near Herat. 117

After his victories against the Uzbeks, Shah c Abbas then turned to the Ottomans, and by ioi2/i6o3f, he was able to retake Azerbaijan, Nakhjavan and Erevan, and, approximately ten years later, conclude a new treaty with the

114 The Islamic world, ed. William H. McNeill and Marilyn Robinson Waldman (Chicago, 1973), P- 383-

115 Ibid., pp. 377 8.

116 Lockhart, 'European contacts', p. 394; John Gurney, 'Pietro della Valle: The limits of

perception', Bulletin of the School of Oriental and African Studies, 49 (1986), p. 103.

117 For more details on Uzbek Safavid relations, see Robert. D. McChesney, 'The con

quest of Herat 995 6/1587 8: Sources for the study of Safavid /Qizilbash Shibanid/

Uzbak relations', in Jean Calmard (ed.), Etudes Safavides (Paris and Tehran, 1993), pp. 69 107.

230

Cambridge Histories Online © Cambridge University Press, 201 1

### Iran under Safavid rule

Ottomans. 11 Late in his reign, in 1031/1622, Abbas was able to bring Kandahar

back into Safavid hands after having been part of the Mughal empire since

Akbar the Mughal emperor captured it in 1003/1594<sup> and, the following vear.</sup>

he recovered Mesopotamian territories, including the city of Baghdad.

### The late Safavid period

Shah 'Abbas died at his summer palace in Mazandaran in 1038/1629. The

period after the death of Shah 'Abbas until the end of the dynasty has tradi

tionally been seen as a period of 'decline', as in the case of traditional period

isations of Ottoman history. But as in the Ottoman case, use of this problematic term has rendered it difficult to understand the transformations

that were taking place in Iran in the later Safavid period.

Of these changes, the most significant actually started at the time of Shah

'Abbas. This was the practice of confining the royal princes to the palace. Instead of succeeding to the throne with experience as governors of provinces

or cities, these sheltered princes knew only the confines of the palace harem.

This practice sometimes resulted in kings having difficulties distinguishing

between important and trivial matters, and not being particularly effective.

Judgement impairments were further exacerbated by increasing incidences of

alcoholism. Courtiers were all too eager to indulge kings in drinking and other

entertainment in order to gain further power and control for themselves. These changes certainly indicate a transformation of power to the palace. Harem politics became increasingly important as mothers of kings and their

favourite wives also tried to gain power either by influencing the current king

or by ensuring that their own sons came to power at the point of succession.

The approximate half century following the death of Shah Abbas saw Iran ruled by his grandson, who took the name Shah Safi (r. 1038 52/1629 42), and his great grandson, 'Abbas II (r. 1052 77/1642 66). These two

kings were different monarchs in many respects, but in other ways they both

carried forward certain of 'Abbas I's policies, in particular his practice of transferring provincial land into crown territories. Shah Safi has suffered from a negative reputation in Western assessments of his reign. He was the

first king to have succeeded to the throne without any experience and having

been confined to the harem. He ruthlessly eliminated any potential rivals both within his own family and without. He was incompetent enough to lose territory, though not a great deal of it, to rival Ottomans, Mughals,

118 Roemer, 'The Safavid period', pp. 266 8.

231

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Uzbeks and Georgians. It must however be kept in mind that in many ways he

was a product of the changes that were instituted by 'Abbas I, most notably the

practice of isolating the royal princes and by extension their families in the

harem. Safi I did not receive the valuable experience of having been ruler of an

important province or city before he came to the throne. His reign marks the

beginning of the transformation of the Safavid dynasty into one that was centred

in the palace and power falling into the hands of the grand vizier and various

other courtiers. Numerous individuals gained power and influence during Safi

I's reign; probably the most influential figure was his grand vizier, the above

mentioned Saru Taqi. 119 It was Saru Taqi who advised Safi I to convert Fars to

crown land, because Qizilbash were no longer needed to ward off external

enemies. 120 Ghulams also continued to play an important role in the state; Imam

QuE Khan, son of Allah Verdi Khan, was another important military figure.

He was responsible for the governorship of Fars and had a great deal of influence and control over southern Iran, but he and his family were subse

quently executed by the king. 121 It has been suggested that part of the reason for

Shah Safi's poor reputation was due to statements made by Fr Krusinski, who

noted that his rule was 'cruel and bloody  ${\bf 1}$  , and a reference to the episode of

Imam Qui! Khan in Carmelite accounts. 122

# Shah Safi's coronation

An examination of Shah Safi's coronations indicates how Safavid religious policies and foci of power had evolved by this time. By the time Shah Safi (r. 1038 52/1629 42) succeeded to the throne, the religious classes were enjoying

much greater power than at the time of Shah Ismail I or II. In particular, the

Safavid kings' claim to be ruling in the name of the hidden imam was seen by the

clerics as illegitimate, and accounts of Shah Safi's coronation reflect this shift. 123

This shift can be seen in the main official who participated in the coronations: in

the sixteenth century, after the reign of Shah Ismail, the Mujtahid of the Age

(mujtahid i zamari), a descendant of the Shl'i scholar al Karaki, participated in the

coronations of Isma'il II and Muhammad Khudabanda (r. 985 95/1578 87). But

by the seventeenth century, the Shaykh al Islam of Isfahan had this duty. 124

119 Ibid., pp. 282 3.

120 Savory, Iran under tfte Safavids, p. 228.

121 Ibid., p. 229.

122 Ibid.

123 Momen, An introduction to Ski'i Islam, p. 112.

124 Arjomand, Shadow of God, p. 177.

232

Cambridge Histories Online © Cambridge University Press, 201 1

### Iran under Safavid rule

Although during his lifetime Shah 'Abbas had caused any potential rivals to

the throne to be blinded, he had apparently made provisions for the succession,

appointing his grandson Sam Mirza (later known as Shah Safi) as his heir. There

was concern, of course, that the succession plan would be challenged, and so

leading government officials tried to hold Sam Mirza's coronation ceremony as

soon as possible. This was achieved in Isfahan with Sam Mirza taking the throne

in 1038/1629 and changing his name to Shah Safi. 12,5 It was during Shah Safi's

coronation that the prayer carpet (sajjdda/qallcha) of the Safavid Sufi order, a

central item used in Safavid coronations, was used for the last time; the fact that it

was subsequently discontinued reflects the declining power of the Qizilbash 12

Shah Safi apparently had two coronation ceremonies; the second one took

place in order to accommodate a very important individual who was unable to

attend the first coronation. This was the philosopher and founder of the Ishraqi school of philosophy, or the 'school of Isfahan', Mir Damad (c. 969 io4o/i56if. i63ofi), mentioned earlier. 127 A later Safavid chronicler, Ma'sum

ibn Khwajagi Isfahan!, author of the Khulasat alsiyar (1052/1642), also notes

that they used Shah Isma'il's belt and sword in the coronation ceremony. The

practice of bestowing a sword upon a ruler goes back at least to the Saljuq

period, when Toghnl Beg (d. 455/1063) was girded with a sword by the caliph. 12 In mentioning the sword and belt of Shah Isma'il, Isfahan! could

be emphasising the early history of the Safavid dynasty without raising the

religious and political implications of the Sufi/ Qizilbash prayer carpet. At the

same time, this Safavid practice could have been established in order to counter, or at least keep up with or compete with, Ottoman legitimising forces. Ottoman sultans took the throne by the 'girding of the sword' cere mony, a tradition which went back to the reign of Murad II (824 48; 850 5/

1421 44; 1446 51). I29 As Ottoman coronation ceremonies became increasingly

elaborate, so did those of the Safavids, who could claim that their king, too,

was enthroned with a significant sword: that of their dynasty's founder. Isfahan! lists other coronation rituals as well, in particular the sounding of

the drum and the flute. The beating of drums was an ancient Iranian practice

125 For more information on Shah Safi in general, see Roemer, 'The Safavid period',

pp. 278 9-

126 Arjomand, Shadow of God, p. 180.

127 For more background on Mir Damad, see S. H. Nasr, 'Spiritual movements, philoso

phy and theology in the Safavid period', in Peter Jackson and Laurence Lockhart (eds.),

The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods (Cambridge, 1986), pp. 669 75-

128 Ef 'Marasim' (J. Burton Page).

129 Ibid.

233

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

rooted in Mithraism, and it was performed on various occasions such as the

king's birthday and other important religious holy days and commemorative events.

After a reign of approximately thirteen years, Safi I died at the age of thirty two, in 1052/1642, probably from weakness due to opium and alcohol

addiction. He was succeeded by his son, 'Abbas II (r. 1052 77/1642 66). 'Abbas II continued many of his father's policies, in particular the practice

of bringing provinces that were traditionally governed by Qizilbash leaders

under direct crown control. Specific provinces that came under crown control included the northern regions of Azerbaijan, Gilan, Mazandaran and Qazvln, the southern regions of Yazd and Kirman, and the eastern region of Khurasan. 131 'Abbas II has been compared to his great grandfather

'Abbas I and indeed may have modelled his reign on that of his illustrious

ancestor. He continued to expand and embellish the city of Isfahan with new

building projects such as the Aqa Nur mosque and the madrasa of Mulla Abd Allah. 132, He also completed projects that 'Abbas I had started, such as

the Chihil Sutun palace, or the palace of forty pillars, and repaired older buildings that needed renovation, such as the Masjid i Shah. 133 'Abbas II died

in 1077/1666, and was succeeded by Shah Safi II (Sulayman), whose rule lasted from 1077 (1078) 1105/1666(1668) 1694.

## The reign of Shah Sulayman

The economic situation of Shah Sulayman's reign can be financially charac

terised as broke. When Shah Sulayman came to the throne, the royal treasury

was 'nearly empty' and, out of necessity, the court had to be extremely frugal in

its spending practices. 134 The situation was so severe that the Shah's grand

vizier, Shaykh 'All Khan, implemented a strict financial policy that resulted in

cutting down court spending, and courtiers, include the ghulams, had to rely on

the king's personal financial generosity. 135 Shaykh 'All Khan was a strict Muslim

who disapproved of, or at least did not himself participate in, the popular

130 Ibid.

- 131 Savory, Iran under the Safavids, p. 228.
- 132 Robert Hillenbrand, 'Safavid architecture', in Peter Jackson and Laurence Lockhart

(eds.), The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods (Cambridge, 1986), p. 796.

- 133 Savory, Iran under the Safavids, p. 232.
- 134 Rudolph P. Matthee, 'Administrative stability and change in late 17th century Iran: The

case of Shaykh 'Ali Zanganah (1669 89)', International Journal of Middle East Studies, 26 (1994), PP- 82 3.

135 Ibid., pp. 83, 88.

Cambridge Histories Online © Cambridge University Press, 201 1

#### Iran under Safavid rule

pastime of drinking parties at the palace, and was disliked at the palace for his

fiscal measures.

### Late Safavid historiography

It was during this late Safavid period that we see a new trend in historical

writing in the form of popular histories emphasising the heroic aspects of the

early Safavid kings, perhaps to forget about the troubled times in which they

were living, or to provide their audiences with a strong contrast to the contemporary period. Nearly all of these texts are of unknown authorship,

although recent scholarship has identified one author as Bijan, the reciter of

the Safavid story' (qissa yi Safavl khwdn), or 'reciter of Safavid history' (tdnkh i

Safavl khwdn), and also uncovered the title of Bijan's history as the Jahdn gushd

yi khdqdn i sahib qirdn. For many years this chronicle was thought to be dated

to the period of Shah Isma'il himself, but now its composition can be placed to

the period of Shah Sulayman. Although there are connections between these

texts and earlier standard chronicles such as Hasan Beg Rumlu's Ahsan al tavdrikh, these authors employ a style which is, overall, direct, unadorned

and straightforward. 136 Furthermore, although early accounts representative

of this tradition do not exist today, its origins might well go back at least to the

time of Shah Tahmasp. 137 The fact that these histories emphasise the origins

and rise of the Safavid dynasty supports the notion that at least some elements

within late Safavid society were looking back, perhaps with a certain amount

of nostalgia, to the past. More evidence supporting this theory can be seen in

the example of Shaykh Husayn ibn Shaykh Abdal's Silsilat al nasab i Safaviyya,

a hagiography drawing heavily on the Safvat alsafd (composed 759/1358, updated 940/1533), dedicated to Shah Sulayman. 138 Although this work does

not form the same tradition as the anonymous popular histories, its emphasis

on Safavid origins and its late composition date support the notion of a revival

of early Safavid history during this time.

Certain aspects of Shah Sulayman's rule could also provide an explanation

for the general characteristics of the late Safavid popular chronicles. The first

136 See A. H. Morton, 'The date and attribution of the Ross Anonymous: Notes on a Persian

history of Shah Isma'il I', in Charles Melville (ed.), Pembroke papers I (Cambridge, 1990),

pp. 185 and 188, for instance, for a discussion of the connections between Bijan's history

and Hasan Beg Rumlu's Ahsan al tavdrikh.

137 See A. H. Morton, 'The early years of Shah Isma'il in the Afzal al tavarikh and else

where', in Charles Melville (ed.), Safavid Persia: Tfte history and politics of an Islamic

society (London, 1996), pp. 44 5.

138 Shaykh Husayn Pirzada Zahidi, Silsilat al nasab i Safaviyya (Berlin, 1924), p. 9.

235

# The New Cambridge History of Islam

has to do with the changing nature of kingship in the late Safavid period. As

princes were increasingly confined to the harem, the inner palace became a

centre of focus and power. 139 Rudi Matthee has outlined the basic features of

this harem system, in which Shah Sulayman relied heavily on a 'secret council

of eunuchs' for advice. 140 It is therefore not surprising that Morton concluded

that Bijan's history may have been commissioned by Aqa Muhammad Rida

Beg, most likely a court eunuch who ordered Bijan to insert portions of a text

similar to the 'Alam am yi Safavi, a history of the genre under discussion here,

into his history. If this is the case, we might conclude that the audience for this

particular strand of historical writing was in the palace, and quite possibly the

inner palace, and consisted chiefly of eunuchs and ghuldms. 141 Indeed, it is

possible that in the late seventeenth century, this 'altered and distorted' tradition of historical writing was even the dominant one, as testified by

fact that we have many surviving copies of these anonymous histories. Furthermore, the fact that many of them were illustrated, some by famous

artists of the time, suggests that these texts enjoyed a certain level of popular

ity and prominence. 142

Ultimately, Shah Sulayman enjoyed a peaceful reign. His administration was marked by an expansion of the tendencies that had displayed themselves

during the reigns of previous post 'Abbas I kings. In particular, the strength

ening position of the vizier, as exemplified in the career of Saru Taqi, continued and reached its pinnacle in the career of Shaykh Ali Khan, who enjoyed tremendous power and prestige for some thirty years (1669 89) before his dramatic fall from power. 143 He put great effort into attempting

to address the financial difficulties that the state was facing, and became known as an official who would not resort to bribery. 144

Shah Sulayman did not officially nominate a successor and so the succession

was determined apparently by his aunt, Princess Maryam Begum, who was a

partisan of Sulayman's son, Sultan Husayn, who was crowned king in 1105/1694. I45 Sultan Husayn ruled for twenty years, during which time the

Safavid state witnessed the consolidation of power on the part of the religious

139 See Matthee, 'Administrative stability and change', pp. 77 98.

140 Ibid., p. 89.

141 Ibid.; Morton, 'Date and attribution', p. 185.

142 See Eleanor Sims, 'A dispersed late Safavid copy of the Tarikh i Jahangusha yi Khaqan

Sahibqirari , in Sheila R. Canby (ed.), Safavid art and architecture (London, 2002), PP- 54 7-

143 Matthee, 'Administrative stability and change', pp. 78 9.

144 Ibid., p. 83.

145 Roemer, 'The Safavid period', p. 311.

236

Cambridge Histories Online © Cambridge University Press, 201 1

Iran under Safavid rule

clerics. This trend is epitomised by the life and career of the famous jurist

Muhammad Baqir Majlisi (1037 1110/ 1627 98). Majlisi, the son of the renowned ShTi 'alitn Hajji Muhammad Taqi Majlisi, was one of the most eminent and powerful clerics of the later Safavid period, and received the highest support from both Shah Sulayman, who conferred upon him the

position of Shaykh al Islam, and Shah Sultan Husayn, who made him Mulla

Bashi. These two positions were among the highest religious positions in the

state, and Majlisi repaid both kings for the honour by dedicating books to them and praising them to the highest degree. 146 Majlisi is widely regarded as

an outstanding hadith scholar and ShTi polymath of the seventeenth century.

He wrote numerous books in both Arabic and Persian. His monumental Bihar

al anwar consists of no less than no printed volumes. This work is basically a

ShTi encyclopaedic compilation of Imami ShTi traditions and all aspects of

doctrine and history from cosmology and the lives of the imams to visitation

accounts and essays on messianism and eschatology. It also includes informa

tion on medicine that indicates Majlisi was influenced and positively disposed

to aspects of Galenic medicine. 147 His other works include the Persian Hayat

al qulub, which gives biographies of the lives of the prophets, the story of Muhammad and the lives of the imams, as a sort of ShTi 'salvation history'.

He also wrote shorter pieces against Sufism, treatises on various aspects of

ShTi legalism, legalistic compilations and much more.

The end of the Safavid dynasty

The Safavid dynasty came to a final end as Safavid rule became increasingly

weak and power became increasingly decentralised. Shah Sultan Husayn was

an ineffectual ruler who grew up in the harem. He was devoutly religious, receiving the nickname of 'Mulla Husayn'. The Safavid state at this time was

facing threats from all of its non Shi'i border areas. One of these, Kandahar,

was taken over by Ghilzais, who opposed and rebelled against Safavid sponsored Georgian oppression. Eventually, a Ghilzai Afghan by the name

of Mahmud was able to take over Kirman while the Safavid army was occupied in dealing with takeovers of Safavid territories in the Persian Gulf.

Although the king eventually turned to the east and Kandahar, there was so

much opposition to such a campaign that they were unable to meet Mahmud

146 See Ef 'Madjlisi, Mulla Muhammad Bakir' (Abdul Hadi Haiti).

147 See Andrew Newman, 'Baqir al Majlisi and Islamicate medicine', in Andrew

J. Newman (ed.), Society and culture in the early modern Middle East: Studies on Iran in

the Safavid period (Leiden, 2003), p. 381.

237

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

there. Instead, Mahmud and his army started marching towards Isfahan. The

Safavid troops first met Mahmud and the Afghans outside the village of Gulnabad. Although Mahmud's forces were outnumbered, they defeated the Safavids and continued their advance on Isfahan, attacking New Julfa.

The king remained in Isfahan, rejected the opportunity for negotiation and did

not allow people to leave the city. This resulted in a devastating famine. The

king finally gave in and abdicated to Mahmud, who entered the city in 1722.

Mahmud and his family did not remain in power for long, as eventually Russian and Turkish designs on Safavid territory carved deeper into the Safavid state. Although Mahmud's invasion of Isfahan marks the end of central

Safavid rule, Safavid pretenders continued to exercise power in various ways

in a politically fragmented Iran until 1087/ 1773. Against the backdrop of Afghan, Afsharid, Zand and Qajar rule, such individuals served as symbolic

'rallying points' of opposition to the Afghans and those who later ruled Iran.

such as Nadir Shah. 148

Conclusion

Although notions that the Safavid state was an early example of a 'nation state'

in the Middle East, or even a 'proto nation state' have long been dispelled, the

Safavids made a long lasting impact on Iran's political, religious and cultural

landscape. As mentioned above, the fact that most of Iran's population subscribes to the Twelver or Imami form of Shi'ism is a direct outcome of Shah Isma'il's 1501 religious policy. Many of the clerics who now hold extremely powerful positions in Iran, and who helped bring about the over

throw of the Pahlavi dynasty, are the spiritual and physical descendants of

those clerics who rose to power in the Safavid era. 149 In terms of historical

geography, although the borders of Iran today are smaller than those of the

Safavid empire, nevertheless, the general outline of the nation today reflects

Safavid borders. Finally, although contact between the Western world and

Iran is taken for granted now, it was during the Safavid period that Iran became involved with Western Europe on a large scale, and vice versa.

J. R. Perry, 'The last Safavids, 1722 73', Iran, 9 (1971), pp. 59 149 See Momen, An introduction to Shi'i Islam, pp. 132 4.

238

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid

restoration: Central Asia in the sixteenth

and seventeenth centuries

R. D. McCHESNEY

At the beginning of the sixteenth century, the Timurids were ousted from Central Asia and a new era of Chinggisid politics began. Although the Timurids had nominally recognised the sovereign rights of descendants of

Chinggis Khan, that recognition had waned as the fifteenth century progressed. Chinggisid rule was restored in Transoxania and Cisoxania (Mawarannahr and Balkh) by a direct descendant of Jochi the eldest son of

Chinggis Khan, Muhammad Shibaq (var. Shahi Beg, Shah Bakht, Shaybak),

but better known by his nom de plume of 'Shibani'. His line went back to Jochi

through the latter's third son, Shlban, hence the dynastic name Shibanid.

Muhammad Shibani's clan took its name, Abu'l Khayrid, from his grandfather.

A collateral (and rival) line of Shibanids, the 'Arabshahid, established itself in

Khwarazm at about the same time. The Shibanids of Mawarannahr and Balkh

ruled until 1599 at which point another Jochid line, claiming descent from the

thirteenth son of Jochi, Tuqay Temiir, took power and remained sovereign

there until the mid eighteenth century. The 'Arabshahids remained sovereign

in Khwarazm until the early eighteenth century. 1

During these two and a half centuries, the Chinggisids operated within an

appanage system of government in which every male member of the ruling

clan was entitled to a share in the territory held by the clan. Presiding over the

entire polity was a khan, chosen on the basis of seniority and with little real

1 For details of the political history of the sixteenth and seventeenth centuries see R. D.

McChesney, 'Central Asia vi. In the 10th 12th/16th 18th centuries', EIr, vol. V, pp. 176 93;

Audrey Burton, The Bukharans: A dynastic, diplomatic and commercial history, vvo 1702

(Richmond, 1997); Yuri Bregel, An historical atlas of Central Asia (Leiden, 2002), pp. 48 60;

and Bregel, 'Arabshahi', EIr, vol. II, pp. 243 5. For the Khwarazm Chinggisids during the

first half of the sixteenth century see Martin B. Dickson, 'Shah Tahmasb and the Uzbeks:

The duel for Khurasan with 'Ubayd Khan (930 946/1524 1540)', Ph.D. dissertation,

Princeton University (1958), Appendix 1 'The Khwarazmian Uzbeks (930 946)', pp. I XLIV.

239

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

authority outside his own appanage. The appanages, initially all held by Abu'l

Khayrid Shibanids, centred on the cities of the region Tashkent, Samarqand,

Bukhara and Balkh. For the first half of the sixteenth century, Bukhara was

held by the Shah Budaqid sub clan, Samarqand by the Kuchkunjids, Balkh and

Karmina by the Jani Begids, and Tashkent by the Suyunjuqids. In the second

half of the century, the Jani Begid sub clan emerged pre eminent. In Khwarazm two great appanages slowly emerged, the so called 'riverside', following the lower reaches of the Oxus river (Amu Darya) and the 'moun tainside', along the northern flanks of the Kopet Dagh.

The appanage system worked best when new territory was being incorporated.

When campaigns to expand the territory ceased being productive and march areas

between the Chinggisid territories and those of their Iranian and Indian compet

itors became static, the dynamics of the appanage system led to internal struggles

and the re formation of appanages. In the latter half of the sixteenth century.

success in such warfare brought the Jani Begid sub clan of the Abu'l Khayrid

Shibanids to a predominant position which lasted about two decades. When its

last and greatest khan, 'Abd Allah (r. 1583 98) died, the resulting struggle among

surviving Jani Begids brought about the rise of the Tuqay (Toghay) Timurids.

The end of the appanage system came about over the course of the seventeenth century as territorial expansion at the expense of the compara

tively powerful states of Safavid Iran and Timurid (Mughal) India proved impossible. Unable to expand, both the Chinggisids and their Uzbek amirs

invested their political capital in holding on to what they had and wherever

possible taking the territory of their appanage neighbours. The seventeenth

century is marked by the formation of two great appanages, that of Bukhara

and Balkh, ruled successively by pairs of Tuqay Timurid brothers (Imam Ouli

and Nadhr Muhammad from 1611 to 1641 and Nadhr Muhammad's sons, c Abd

al 'Aziz and Subhan Quli from 1651 to 1681). Within these great appanages

subinfeudations were created for their amirid supporters and these grants

gradually became seen as belonging to the tribes of those amirs. Thus by

middle of the eighteenth century one finds Badakhshan considered the patri

mony of the Qataghan amirs, Maymana that of the Ming, Bukhara belonging

to the Mangghit, Khoqand to the Yuz, and the Kulab region to the Keneges

(Kanikas), a situation that persisted well into the nineteenth century.

In Khwarazm, the 'Arabshahid clan of the Shibanids had a much longer tenure but with different consequences for the cultural history of the region. 2

The main sources on the politics of the 'Arabshahid Shibanids are: Abu'l Ghazi Bahadur

Khan, Shajara i Turk, ed. and trans. Petr I. Desmaisons as Histoire des Mongols et des Tatarespar Cambridge Histories Online © Cambridge University Press, 201 1

### Islamic culture and the Chinggisid restoration

The Abu'l Khayrid Shibanids and the Tuqay Timurids were thoroughly urbanised, living in garden estates and palaces in the towns of Mawarannahr

and Balkh and forging close ties with the elites of their appanages, whereas in

Khwarazm, the members of the royal clan and their supporters maintained a

nomadic lifestyle, lived in tents and used the towns primarily as fortresses

when threatened by outsiders. 3 They felt little need to cultivate townsmen, to

forge alliances with intellectuals, merchants and other city leaders and so, in

marked contrast to their contemporaries in Mawarannahr and Balkh, have left

little in the way of an urban legacy of cultural patronage.

### Society in the Chinggisid era

The reinstitution of Chinggisid political control in Central Asia had little impact on society as a whole, simply substituting one Turko Mongol ruling

organisation for another. The newcomers in the sixteenth century did intro

duce one new feature probably more important to the political elite than to

the ordinary subject and that was the marked distinction between the khanly

family and its military supporters, the 'Uzbek' amirs. The title of khan (khaqari)

was reserved for the senior member of the Chinggisid family. The male members of the royal clan suffixed the title sultan to their names. The leaders

of the various tribal groups, subsumed under the generic term 'Uzbek used

the title amir. That distinction between khans and amirs, between those who

could rightfully claim supreme authority and those who could not, no matter

how individually powerful, remained central to political philosophy and practice through the entire period. In Central Asian sources of the period,

the amirs are usually identified by a tribal name (e.g. Durman, Naiman, Jalayir,

Arlat, Kamkas, Ming, Manghghit, Yuz, Qataghan, Qunghrat, Barlas, Bahrin,

Qushji, etc.) never as 'Uzbek', a generally derogatory or condescending term

applied to an unlettered person, a bumpkin or rustic. It was outsiders who

used the term 'Uzbek', and often in a pejorative sense, to refer to the entire

state, its rulers and their military supporters.

The Chinggisid revival notwithstanding, there was much societal continu ity from the Timurid to the Shibanid and Tuqay Timurid eras. This was especially true in the case of cultural issues, but even in the political sphere,

where the Shibanid regime had displaced and assumed the prerogatives of its

Aboul Ghazi Behddour Khdn (St Leonards and Amsterdam 1970 repr. of St Petersburg 1871 4

edn); and Mu'nis, Shir Muhammad Mirab and Muhammad Riza Mirab Agahi, Firdaws al

iqbal: History ofKhorezm, ed. and trans. Yuri Bregel (Leiden, 1999). 3 Yuri Bregel, "ArabshahT, Eh, vol. II, p. 244.

241

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Timurid predecessors. Many Timurid supporters, as long as they had com mitted no unforgivable offences against the incoming power, were accom modated in the new order. For the rest of the population, social hierarchies

and cultural norms remained more or less as they had evolved during previous

centuries. To the extent that we can speak of classes or distinct social groups,

Central Asian society comprised first of all the general populace of farmers,

sharecroppers, herders, shopkeepers, artisans, slaves and labourers men, women and children those whose names occasionally appear in written records and then often in conjunction with the doings of the more wealthy

and powerful. But property ownership was something of a leveller and owner

ship of real estate was common to all social groups, with the possible exception

of slaves. Supported by the general population was a group privileged by birth,

education or position, and this group may broadly be divided between a shaykhly and learned caste, a military civil officialdom comprised mainly of

Uzbek amirs, and the relatively small group of royals, the Chinggisids.

Except for membership in the Chinggisid clan, the boundaries between any of

the other groups are blurred and permeable. Learned amirs were common as

were non Uzbeks who had made careers in the military. The fact that there were

no restrictions on the ownership of real estate, including agricultural land, opened

a path to building wealth and thereby improving one's social status. Property

ownership was certainly widespread. Sources from the sixteenth and seventeenth

centuries such as the documents of the Juybari family (family biographies, deeds

of sale and waqf nomas), along with the thousands of waqf deeds in the Uzbek and

Tajik archives, reveal the names of a multitude of small landowners. The access

to property made the accumulation of capital possible and so far as one can tell

the sharVa laws on property were applied without distinction as to class, ethnic

affiliation or gender. In the case of women, some 30 per cent of the more than

3,000 owners of property in and around Bukhara mentioned in the property

deeds of the Juybari family alone 4 were women, either as parties to the trans

actions with the Juybaris, or as owners of adjacent properties.

Occasionally one finds recorded instances of utterly unpredictable and rare

strokes of fortune which suddenly enriched a person and elevated them to local

prominence. Such an instance is the probably apocryphal case of the founder of

one of Bukhara's most famous teaching institutions, the Muhammad Sharif

4 E. Bertel's (ed.), Iz arkhiva Dzhuibari (Leningrad, 1938). On the actual editor and trans

lator of this work, Fedor Borisovich Rostopchin, see R. D. McChesney, 'Some observa

tions on "garden" and its meanings in the property transactions of the Juybari family in

Bukhara, 1544 77', in Attilio Petruccioli (ed.), Gardens in the time of the great Muslim empires

(Leiden, 1997), pp. 105 n. 11 and 107 n. 29.

242

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

madrasa. An early twentieth century Bukharan source reports that Mulla Muhammad Sharif was born poor and became a disciple of a certain Mawlana

Imla 1 . During the Iranian siege of Bukhara in 1740, the Chinggisid ruler, Abu'l

Fayz Khan, and his amirs decided they should seek terms from the Iranians and

chose Mawlana Irnla 1 to negotiate on their behalf. He took his disciple with him

to meet Nadir Shah, the leader of the Iranian force, and, was received with great

honour. Nadir Shah gave Mawlana Imla' a priceless jewel and he in turn passed it

to Muhammad Sharif. With the jewel, Muhammad Sharif "banished the word

"ascetic" from his vocabulary 1 and became a great merchant. After the death of

his mentor, he built a number of buildings including a madrasa and mosque near

the Ghaziyan reservoir in honour of his master, all from the proceeds of the sale

of the jewel. 5 This madrasa, alternately known as the Ghaziyan madrasa, became

one of the chief teaching centres of Bukhara and had a renowned library.

But such incidents were of course extremely rare and for a person not born

to wealth, into the royal clan or into one of the amirid organisations, prestige

and status came through personal effort: as a soldier, farmer, merchant or, as

above, through connection to a prominent teacher or shaykh.

## Patronage patterns

The Abu'l Khayrid Shibanids, the Tuqay Timurids, and the military and intellectual supporters of both Chinggisid lines (but not the 'Arabshahids of

Khwarazm) are noteworthy for their continuation of the Timurid model of artistic and scholarly patronage. Indeed, much of the material and intellectual

legacy of the Timurid period from architecture to Arabic grammar was maintained, preserved and encouraged by the wealthy of the appanage regimes of the sixteenth and seventeenth centuries.

The Chinggisid rulers and their leading amirs were well educated men and,

in the fashion of the time, prided themselves on their skills in poetry. Many of

them were well known, and in a few cases even well regarded, for their poetry

as well as for their support of poets and other producers of literature. In addition, they devoted substantial resources to promoting scholarship

Tamkin, Matdli' alfdkhira wa matalih al tdhira, Tashkent IVAN ms. 8245, fos. 410b 411b.

The late seventeenth century Muzakkir al ashab however places Muhammad Sharif and his madrasa, also known as the Ghaziyan madrasa, in the late seventeenth century, fo.

119a. Tamkin may have been relying more on oral tradition. The story could well be

apocryphal but is nonetheless illustrative of what people thought possible.

Edward A. Allworth (ed.), The personal history of a Bukharan intellectual: The diary of

Muhammad Sharif i Sadr i Ziyd (Leiden, 2004), passim.

243

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

through direct stipends to scholars, in the form of judgeships and other judicial

positions and indirectly through endowments paying salaries for professor

ships. Those with the means also lavished their wealth on great public works

projects to support education, the cult, commerce and the hydraulic needs of

an agrarian society.

In their literary endeavours, most Chinggisids were able to compose in both

Persian and Turki and some, like Shlbanl Khan and the late sixteenth century

Abd Allah Khan, could write in at least passable Arabic as well. These men of

power were also very often conversant in the Qur'anic disciplines. To further

the Islamic sciences, they invested much of their surplus wealth in building

madrasas, the typical venue for encouraging intellectual life. In addition, they

presided over literary assemblies (majalis, mahafil, musha'arat) and encouraged

creativity by awarding monetary prizes as well as salaried positions.

The support of intellectual and artistic activity was influenced, of course, by

both economic and political conditions. The turbulent first half of the six teenth century was marked by the struggles between the Shibanid, Safavid

and Indian Timurid (Mughal) polities until a balance of power was reached

which left the Hindu Kush as the frontier between the Shibanids and the Indian Timurids, and the Hari Rud and Murghab basins as the relatively stable

marches between the Shibanids and the Safavids. During this transitional period, existing patronage ties were broken and many artists, architects, literary figures, scholars and entertainers migrated (or were forcibly moved)

and found new patrons.

The artistic and intellectual community that had formed at Herat with the financial support of men like Mir c Ali Shir Nawa'i, Sultan Husayn Mirza Bayqara and Amir Shaykh Ahmad al Suhayli dispersed to Ottoman territory,

Mawarannahr and India as a consequence not only of the warfare between the

last of the Timurids, the Safavids and the new Chinggisids but also because of

the new and divisive ideological element introduced by the Shi'ite Oizilbash

supporters of the Safavid family and the Hanafi Sunni reaction it produced.

Over time, the flow of patronage seekers became increasingly channelled towards India as the Mughal regime there extended its hold over the country

and increased its resources. By the end of the sixteenth century, 25 30 per cent

of the biography worthy officials of the Mughal state were first generation

immigrants from Iran alone 7 and we can assume that another substantial

7 Masashi Haneda, 'Emigration of Iranian elites to India during the 16th 18th centuries',

Cahiers d'Asie Centrale, 3 4 (1997), p. 131.

Islamic culture and the Chinggisid restoration

percentage, perhaps not quite of this magnitude, was represented by first generation job seekers from Central Asia.

The attraction of India as a destination for patronage seekers took some time

to develop and did not much affect those caught up in the Shibanid Safavid

Timurid struggles in the first half of the century. A good example of a highly

skilled artisan affected by the problems of that period is the landscape architect

Mirak i GhiyasI, who worked for Sultan Husayn Bayqara until the latter's death

in 1506, at which time he was about thirty years old. He then worked under

the Shibanids when they captured the city in 1507. When the Safavids retook it

in 1510, he was imprisoned and was finally forcibly removed to Bukhara when

the Shibanids once again captured Herat in 1513. He eventually peregrinated

between Samarqand, Herat, Agra and Bukhara, spreading Timurid garden

design ideas and leaving known examples of his work in Herat, Agra and Bukhara before disappearing from the scene in the late 1550s.

Other examples of the effect of international politics on scholars are found in

the contrasting cases of Fazl Allah b. Ruzbihan Khunji Isfaham (d. c. 937/1530)

and Amir Sadr al Din Sultan Ibrahim AmiriT (d. 941/1535). The former, born in

Shiraz into an upper class family with a long ShafTite Sunni heritage, was a well

travelled young man before offering a book and his services to the Aq Qoyunlu

sultan Ya'qub, the son of Uzun Hasan (d. 1490). After the latter s death Khunji

Isfaham briefly served some of the last Timurids in Iran. As the Safavid Shi'ite

movement grew, he wrote Ibtal nahj al batil, a polemical anti Shil work, which

reportedly made it impossible for him to live in the Safavid domains. He chose

the court of Shibani Khan and after the latter's death in 1510 lived at Samarqand,

eventually being invited to join the court of TJbayd Allah in Bukhara (r. 1512 40)

for whom he wrote a treatise on government, Suluk al muluk.

Sultan Ibrahim AmiriT, on the other hand, typifies intellectuals moving in the opposite direction. Like Isfahani, he was born into privilege, became a

noted scholar and was attached to the court of a son of Sultan Husayn Bayqara, Muzaffar Husayn, who briefly governed Herat after his father's death in 1506. When Shibani Khan took Herat in 1507, Amini was persecuted

and his properties confiscated but these were restored when Shah Ismail occupied the city in 1510. Ten years later Amini joined Ismail's court in Tabriz

where he began work on a verse history of the shah, Futuhat i shahl. 9

Maria E. Subtelny, 'Mirak i Sayyid Ghiyas and the Timurid tradition of landscape architecture', Stadia Iranica, 24 (1995), pp. 19 60.

C. A. Storey, Persidskaya literatura: Bio bibliograficheskii obzor, rev., trans., and updated Yuri E. Bregel, 3 vols. (Moscow, 1972), vol. II, p. 850.

245

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Probably more often it was economic, rather than political or ideological, circumstances which fuelled the migration of intellectuals and artists. Whatever the reason, these migrations produced a new flowering of cultural

activity in Central Asia, India and Iran. The memoirist anthologist Zayn al Dm

Wasifi paints a vivid picture of the intellectual life at the Bukharan court of

'Ubayd Allah Khan. Many of the literary figures he describes were refugees

from Timurid Herat and Safavid Iran.

In art as well as literature, changing economic and ideological circum stances led to the flowering of new centres. Shaykhzade, a pupil of the great

Bihzad, left Iran sometime after 1532. This probably was connected to Shah

Tahmasp's public 'repentance' and his highly publicised effort to 'promote

virtue and prohibit vice', which was followed by a puritanical clampdown on

cultural activity. In Bukhara, Abd al 'Aziz, the son of 'Ubayd Allah Khan, welcomed Shaykhzade and for two decades or so the artist and his pupils produced manuscripts in 'Abd al 'Aziz Khan's scriptorium (kitdbkhdna) and

created what is known as the 'Bukhara school' of miniature painting. 10

Through the sixteenth and seventeenth centuries the ruling circles' support

of scholarship, art and religious life is well recorded not just in the chronicles

they commissioned to memorialise themselves but in the biographical anthol

ogies (tazkiras) written by those who usually depended on their patronage.

Through the whole period there is a nearly unbroken chain of anthological

writing, one author building on the work of a predecessor. For the sixteenth

century, these writers include Wasifi (writing between 1517 and 1532), Fakhri

Harawi (writing in the years 1551 5), Hasan i Nithari Bukhari (writing between

1566 and 1572) and Mutribi Samarqandi (chronicling the literary scene down to

1605). The seventeenth century anthologists are less well known because they

remain unpublished. But these include Muhammad Sami 'Samarqandi, whose

work covered the period from 1583 (the accession of 'Abd Allah Khan) to 1644 (the abdication of Nadhr Muhammad Khan), and Muhammad Badi' Samarqandi, author of Mudhakkir i ashdb, which he tells us he first conceived

in 1669 and which covers the period up to 1693.

10 See the following works by Yves Porter, 'Remarques sur la peinture a Boukhara au XVI e

siecle', Boukhara La Noble; Cahiers d'Asie Centrale, 5 6 (1998), pp. 147 67; Porter, 'Farhad

le peintre: A propos des ateliers de peinture de Boukhara a l'epoque de 'Abd al 'Aziz

Khan (1645 1680)', L'heritage Timouride: Iran Asie centrale Inde XV'' XVIIf siecles: Cahiers

d'Asie Centrale, 3 4 (1997), pp. 267 78; Porter, 'Le kit&b khdna de 'Abd al Aziz Khan

(1645 1680) et le mecenat de la peinture a Boukhara', Patrimoine manuscrit et vie

intellectuelle de VAsie centrale islamique; Cahiers d'Asie Centrale, 7 (1999), pp. 117 36. Also

see Barbara Schmitz, "Bukhara VI. The Bukharan school of miniature painting', EIr, vol.

IV, pp. 527b 530a.

246

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

While these anthologies show us that composing poetry was a universal phenomenon and did not seem to require any particular preparation, attaining

recognition as a scholar ('dlim), on the other hand, required formal training.

The credentials of individual scholars were recorded in ijdzas (licences to teach

certain books), istljdzas (requests for ijdzas) and mashyakhahs (lists of author

ities"). Other indications of scholarly accomplishment are also to be found in

book endowment lists and in the biographical notices of scholars found in a

wide variety of sources.

What is remarkable about sixteenth and seventeenth century scholarship is

its debt to the work of Timurid era scholars, although pre Timurid scholar

ship was central to the curriculum as well. In this latter category, most prominent are Baha 1 al Din al Marghinani (d. 1197) and the extensive tradition

of legal commentary and glossing to which his great work of jurisprudence,

al Hiddya, gave rise; Ibn Hajib (d. 1249) and his treatise on Arabic syntax, al

Kdfiya; Bayzawi's (d. 1286) commentary on the Qur ] an, Anwar al tanzil; the

Mishkdt al masdbih in the recension of Katib Tabrizi {ft. 1340), a favoured work

on hadlth; and al Nasafi's (d. 1142) statement of belief, al 'AqdHd. These works

all figure prominently in the lists of book collections that survive from the sixteenth and seventeenth centuries.

Yet it is Timurid era works that predominate in these catalogues and book

lists. The body of scholarship left by such Timurid sponsored intellectuals as

Sa c d al Din Mas'ud b. 'Umar al Taftazani (d. 1390), the 'Sayyid al Sharif c Ali b.

Muhammad aljurjani (d. 1413), Shams al Din Muhammad al Jazari (d.1429) (all

three of whom were at Temiir's court), Nur al Din [ Abd al Rahman Jami (d. 1492) and Kamal al Din Husayn b. 'Ali 'al Wa'iz' al Kashifi (d. 1504) (at the late fifteenth century court of Sultan Husayn Mirza) was canonised in the

madrasa curricula of the Shibanids and Tuqay Timurids. Being versed in the

works of the Timurid period as well as in the Marghinani tradition of legal

scholarship qualified an individual for posts injudicial administration (as qddi,

mufti and ra'ls) as well as for the madrasa professorships (tadris) that often

seemed to go along with judicial appointments. An example of the kind of education a middle level judicial appointee would typically have is that of Muhammad Badi [ of Samarqand, known to us today as the compiler of an

anthology of poets. Born in 1050 or 1053/1640 or 1643, he followed in his

father's footsteps to become a mufti in Samarqand. He says that he spent the

11 On these credentials see Maria E. Subtelny and Anas B. Khalidov, 'The curriculum of

Islamic higher learning in Timurid Iran in the light of the Sunni revival under Shah

Rukh', Journal of the American Oriental Society, 115 (1995), pp. 210 36.

247

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

first thirty years of his life under his father's tutelage studying logic, theol

ogy, astronomy and hikmat (which at this point probably meant Galenic medicine). When his father died c. 1670, the Tuqay Timurid khan, c Abd al

'Aziz (r. 1651 81), gave him his father's salary and office. After a three year

trip to Isfahan, he spent seven years in Bukhara and Samarqand acquiring

competence in Arabic, jurisprudence (fiqh), Qur'anic commentary (tafstr) and the discipline ofhadlth criticism. He was never recognised as an L dlim but

his education was considered advanced enough that in 1100/1690 (at the age

of fifty) he was offered the post of qddi of Samarqand and given a professor

ship at the Shibani Khan madrasa as a stipend. 12

The politicians who made the appointments learned of credentials like these through word of mouth, and sometimes through public contest, at assemblies where a person of power would pose a legal or theological problem and often reward the person who provided the best answer with money or a position. (Khunji Isfaharii's Mihmdn ndma i Bukhara (The Bukharan Guestbook) contains many accounts of just such assemblies under

Shibani Khan, and, a century later, Mahmud b. Amir Wall describes numer

ous such gatherings in the Bahr al Asrar.)

# Shibanid khanly patrons and their works

The founder of the Mawarannahr lineage of the Abu'l Khayrid Shibanids, Muhammad Shibani Khan, is portrayed by his contemporaries as a man of

some learning and more importantly as a friend and patron of scholars and an

active supporter of intellectual life. According to those who knew him best,

Shibani had formal instruction himself in at least one Islamic discipline, the

science of qird'a, the variant readings of the Qur'an.

The above mentioned Iranian refugee, Khunji Isfahan!, was commissioned by

Shibani Khan to memorialise him and devotes much of his work, Mihmdn noma i

Bukhara, to the scholarly debates over which Shibani Khan presided and which he

apparently used to resolve some of the legal problems raised by the ouster of the

Timurids. These included the issue of ownership of abandoned property and

questions relating to inheritance. 13 His interest in the law also led to the khan's

sponsoring the compilation of a collection of fatwds named in his honour. 14 He is

- 12 Muhammad Badi', Muzakkir al ashab, ms. 610, fos. 256 9; ms. 4270, fos. 221a 225a.
- 13 Ken'ichi Isogai, 'Yasa and Shariah in early 16th century Central Asia', L'heritage

Timouride: Iran Asie centrale Inde XV" XVIIf siecles; Cahiers d'Asie Centrale, 3 4 (1997), pp. 91 103-

14 'Ali b. Muhammad 'Ali al Khwarazmi, Fatdwd al Shibani, Uzbek IVAN ms. 11282.

248

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

# Islamic culture and the Chinggisid restoration

remembered as well for a love of calligraphy, having pride in his own hand and for

promoting the Turki (or Chaghatay) literary revival usually associated with

the name of Mir 'Ali Shir Nawa'i. He himself wrote a poetry collection (dtwari)

in Chaghatay or Turki, a mixture of political and devotional verses, riddles

(mu'ammds) and ghazals. 15

Baha ] al Din Hasan Nithari Bukhari, writing about a generation after Shibani

Khan's death, portrays him as a devotee of the Naqshbandi Sufi way, compos

ing devotional poetry in Persian in honour of Baha 1 al Din Naqshband. 1 But

the fact that he is credited with also composing a chronogram in Persian commemorating the death of Najm al Din Kubra suggests an affiliation or at

least sympathy with the Kubrawiyya as well; and 125 years later, Mahmud b.

Amir Wali, in a section of his work devoted to naming the great shaykhs who

were the principal spiritual advisers of the Chinggisid khans, identifies Kamal

al Din Husayn Khwarazmi, the early sixteenth century reviver of Kubrawiyya

fortunes, as the most significant spiritual influence on Shibani Khan. 17

might have met when Shibani conquered Khwarazm in 1505 but Husayn Khwarazmi did not come to Samarqand until five years after Shibani's death

and none of the Bukharan centred sources mention the connection. Nonetheless that such a tradition survived for more than a century suggests

there was something to it. It should also be noted that Shibani Khan s dtwan

contained eulogies of the Yasavi Sufi tradition as well. In any event these accounts are an indication of a well known phenomenon, the competition among the Sufi tanqas for the patronage of the ruling circles. And Shibani

Khan's religious sentiments were not exclusively focused on Sufis. Fakhri Haravi, also writing in the 1550s, notes that the campaign which brought Shibani Khan to Mashhad prompted him to compose a qasida in honour of

the Eighth Imam, symptomatic of the universal reverence for the family of the

Prophet and for Husayn's line in particular.

Shibani Khan's interest in promoting Islamic culture was given more monumental form in the Madrasa i 'Aliyya i Khaniya which was under con struction when he was killed in 1510. The madrasa was completed by Muhammad Temiir Sultan, the eldest of his three sons, and the latter's wife,

15 See H. Hofman, Turkish literature: A bio bibliographical survey, Section III: Part 1 (Authors) (6 vols, in 2) (Utrecht, 1969), Part 1, vol. V, pp. 222 33.

16 Khwaja Baha' al Din Hasan Nithari Bukhari, Mudhakkir i ahbab, ed. Syed Muhammad

Fazlullah (New Delhi, 1969), pp. 15 22; also editor's introduction, pp. 14 15

17 Mahmud b. Amir Wall, Bahr al asrarfi manaqib al akhyar, vol. VI, part (rukn) 4, India Office Library ms. 575, fo. 141a.

249

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Mihr Sultan Khanum, left a large endowment for it. The madrasa continued to operate until the late nineteenth century. 1

The pattern of Shibani Khan's support for the cultural life of Central Asia was continued by his successors. The next reigning khan, his uncle Kuchkunji

(or Kuchum Khan, r. 1512 30), whose appanage centre was Samarqand, has left

few literary traces, but a contemporary, Wasifi, who completed his work in

1538 9, relates that he 'honoured and exalted scholars and intellectuals'

and that he renovated and reconstructed 'madrasas, khdnaqds, hermitages

(sawami'), mosques and shrines which had fallen into ruin'. 19 Wasifi also notes that he endowed ten professorships for the Ulugh Beg madrasa khanaqa,

as it was known at the time, as well as four more for Shibani Khan's madrasa,

the subjects to be taught by these professors being (Arabic) grammar, med

icine and law. 2,0 In addition, Kuchkunji commissioned work on a congrega

tional mosque built by the Timurid amir Alikah Kukaltash, adding a stone minbar to replace a wooden one destroyed by fire and making other alterations. 21

Shibani Khan's nephew, 'Ubayd Allah b. Mahmud Sultan (r. 1533 40), won

wide acclaim, even from his enemies, for his literary abilities and his generous

patronage. When not engaged in one of his numerous campaigns against Herat and Khurasan, he composed well regarded poetry in Arabic, Persian

and Turki under the pen name 'Ubaydi and supported an extensive company

of scholars, artists and architects. His own artistic and scholarly accomplish

ments were summed up by MIrza Haydar Dughlat, writing about ten years

after 'Ubayd Allah's death and certainly no friend of the Abu'l Khayrid Shlbanids. In lauding c Ubayd Allah Khan's personal qualities, Haydar Dughlat wrote,

It is my claim that during this period of a hundred years in all the realms of the

world where there have been padishahs, of those who have been heard of and

seen, there has been none like him. First of all he was a Muslim padishah,

religious, pious, and abstinent. In all matters of religion and the nation, in

state, military, and civilian affairs, he made his decisions in accordance with

the religious law and he never tolerated even an iota of transgression. In the

18 On the madrasa and its endowment see R. G. Mukminova, Kistorii agramykh otnoshenii v

Uzbekistane XVI v.: Vakfname (Tashkent, 1966), pp. 9 13.

19 Zayn al Din Wasifi, Badd'i' al waqd'i', ed. Aleksandr Boldyrev, 2 vols. (Moscow, 1961), vol. I, p. 11a.

20 Ibid.

21 Sharaf al Din b. Nur al Din Andijam, Tdnkh i Mir Sayyid Sharif Rdqim, Royal Asiatic Society ms. 163, fos. 116a b.

250

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

forest of courage, he was a lion hunting tiger; in the sea of generosity his hand

rained pearls. 22

Haydar Dughlat, as well as others, states that c Ubayd Allah excelled in writing

the naskh script and copied a number of Qur'ans which he sent as gifts to Mecca

and Medina. Besides poetry, 'Ubayd Allah composed music and some of his

songs were still being sung in Dughlat's time. Nithari Bukhari adds that the

khan was a student ofhadtih andfiqh, that he translated from Persian into Turki

and wrote a work on qirti'a, coincidentally the same Qur'anic science that Shibani Khan studied. Nithari lists twenty one famous scholars, religious figures

and artists who enjoyed 'Ubayd Allah Khan's patronage. Among them was the

calligrapher Mir 'All Harawi, the great master of the nasta'liq script, whose

career began in the Timurid secretariat (dar al inshW) in Herat in the 1490s. In

Bukhara, Mir 'All spent sixteen years under the patronage of first 'Ubayd Allah

and then his son, Abd al 'Aziz, and trained a generation of master calligraphers

as director (matik al kuttab) of the royal scriptorium (kitabkhana). 2 ' 3 c Ubayd Allah

Khan was also patron of the landscape architect Mirak i Ghiyasi, who designed a

public garden for him in Bukhara and then went on to greater fame and fortune

in India.

The 1530s and 1540s saw the major Abu'l Khayrid cities of Bukhara, Samarqand and Balkh thrive as centres of cultural activity, distinguished by

much new architecture. Nithari calls Samarqand a 'science centre' (dar al Him)

under Kuchkunji Khan's son and successor as khan, 'Abd al Latif (r. 1540 52). 24

The latter was particularly noted for his support of astronomy. He refurbished

Ulugh Beg's observatory and sponsored research there. 25 At the same time in

Bukhara, 'Ubayd Allah Khan's son, 'Abd al 'Aziz (d. 1550), maintained his father's cultural legacy as appanage ruler of Bukhara, although he never became supreme khan himself. He composed poetry under the pen name 'Azizi in both Persian and Turki and sponsored much new monumental architecture, including a mosque inside the 'old walls' (hisar i qadim) of Bukhara and a madrasa situated in the south west quadrant of Bukhara, a

madrasa known today as 'The Khan's Mother's Madrasa'. 2 He also built the

great khanaqa which still stands at the tomb of Baha' al Din Naqshband just to

22 Mirza Muhammad Haidar Dughlat, Tdrikh i Rashidi: A history of the khans ofMoghulistan,

Eng. trans, and ann. W. M. Thackston (Cambridge, MA, 1996), p. 182a.

23 P. P. Soucek, "All Heravi, also known as Mir 'Ali Kateb Hosayni', EIr vol. I, pp. 864 5.

24 Nithari, Mudhakkir i ahbab, p. 45.

25 Ibid., pp. 44 5.

26 Bakhtiyar Babajanov, 'Datation de la mosquee Valida ye 'Abd al Aziz Xan a Boukhara',

Studia Iranica, 28 (1999), pp. 227 34.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

the east of the city. 2,7 Another project of his was the expansion of the city walls

which were referred to in later documents as the 'new walls' (hisdr i jadxd).

Balkh was first taken by Shibani Khan after a siege in late 1506, then retaken by the Timurids in 1516 and finally regained once and for all by the

Shibanids in 1526. The Jam Begid Shibanid, Kistan Qara Sultan, ruled Balkh

from then until his death in 1547 or 1548 and during his rule the city under

went major renovation and development. This was contemporary with 'Ubayd Allah Khan's work in Bukhara and that of the Kuchkunjids in Samarqand. He rebuilt walls, erected a palace (Hmdrat) in the citadel (arg),

restored the congregational mosque built by the Timurid Sultan Husayn Bayqara, and added a public bath to its endowment. 2. None of this survives

today, at least above ground.

Another architectural complex of the same period, the shrine and madrasa

of the Parsa'i family, suffered a kinder fate, surviving to the present time though in drastically truncated and altered form. In the first half of the sixteenth century, a new madrasa was built at that site and at the very end

of the century the complex underwent extensive renovation. 2.9

The deaths of 'Abd al 'Aziz at Bukhara in 1550 and 'Abd al Latif at Samarqand in 1552 opened an era of inter appanage warfare that lasted for

the next three decades and ended with the Jam Begid clan as the paramount

Abu'l Khayrid Shibanid clan in Transoxania and Balkh. The cousin clans the

Kuchkunjids, Suyunjukids and Shah Budaqids were all eliminated in this period. Cultural investments came increasingly to be concentrated in the Iam

Begid centre, Bukhara, although some work was still done in Samarqand and

Balkh. Royally sponsored work for the most part is associated with the name

of Abd Allah b. Iskandar, the paramount figure of the Jam Begids. Although

he only became khan in 1583 he was the unquestioned leader and policy maker

of the clan from the mid 1550s onwards, and probably disposed of most of the

family's surplus wealth as well. Besides the khan, the great patrons of the time

were Abd Allah's right hand amir, Qui Baba Kukaltash, and the shaykhly family of the Juybaris who had assisted him and his father to power in Bukhara.

27 Nithari, Mudhakkir i ahbdb, pp. 78 9; Sharaf al Din, Tdnkh i Mir Sayyid Sharif Rdqitn, fos. 131b, 132a, 138a.

28 Sultan Muhammad b. Darwlsh Muhammad, Majma' al ghard'ibfi bayan al 'ajd'ib, IVAN,

Uzbekistan, ms. 1494, fos. 16a 16b; Sharaf al Din, Tdnkh i Mir Sayyid Sharif Kdqim, fos.

116b, 127a; Anon., Tazkirah i tawdrikh, IVAN, Uzbekistan, ms. 361/VI, fo. 128a.

29 R. D. McChesney, 'Architecture and narrative: The Khwaja Abu Nasr Parsa shrine',

(Part One) Muqarnas, 18 (2001), p. 105.

252

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

The records of Abd Allah Khan's public works are extensive and probably

explain his later legendary status as a builder comparable in the region to

Chinggis Khan's mythic reputation as a destroyer. The Abu'l Khayrid Jam Begid khan built at least four madrasas, two in Bukhara and one each in Balkh

and Nasaf (Qarshi). He is also credited with a congregational mosque in Bukhara and several parish mosques in various towns of the region. A great

deal of commercial infrastructure was also erected under his auspices bridges,

large cisterns (sar hawz), caravanserais, warehouses (tints and ribats) and retail

markets (charsus) such as the three still surviving tags in Bukhara. 30 He was a

great patron of architecture on behalf of shrine centres, the Juybari shrine at

Char Bakr outside Bukhara being the most notable beneficiary of his support. 31

His principal chronicler, Hafiz i Tariish, attributes to him a chahar bagh, a

khanaqa, a mosque and a madrasa at the site 32 but it is clear that the Juybari

shaykhly family was also involved in and responsible for at least the mosque. In

any event the khan and the head of the family, Khwaja Sa'd Juybari, were such

intimates that sponsorship of the Char Bakr buildings was in all likelihood a joint endeavour.

### Amirid patronage in the sixteenth century

Like their Chinggisid overlords, the Uzbek amtrs played a major role in furthering Muslim culture. The amtrs were not an undifferentiated mass and

their prominence as patrons depended on their personal ties to the Chinggisid

ruling clan. Hierarchies of amtrs are found in BannaTs Shibani nama for the

early part of the sixteenth century and in Mahmud b. Amir Wall's Bahr al asrar

for the early seventeenth century. Banna'i begins his biography of Shibani

Khan, the reviver of Chinggisid fortunes in Mawarannahr and Balkh, with a

chapter on those 'amtrs and heroes (bahaduran)' who aided Muhammad

Shibani in empire building, primacy of place being given to those who banded

with him during his qdzaql, his period of freebootery, when he had no territory

of his own and his sword was for hire. 33 From a different age and reflecting a

30 G.A. Pugachenkova and E.V. Rtveladze, 'Bukhara V. Archeology and monuments',

EIr, vol. IV, pp. 526b 527b and R. D. McChesney, 'Economic and social aspects of the

public architecture of Bukhara in the 1560s and 1570s', Islamic Art, 2 (1987), pp. 224 30.

31 Bakhtyar Babajanov and Maria Szuppe, Les inscriptions persanes de Char Bakr, necropolc

familiale des khwaja Jiiybdri pres de Boukhara, corpus inscriptionum iranicarum, Part IV:

Persian inscriptions down to the early Safavid period, vol. XXXI: Uzbekistan (London, 2002).

32 Hafiz i Tanish, Sharafndma i Shdhi, ed. and trans. M. A. Salakhetdinova (vols. 1 and 2 only of four projected) (Moscow, 1983 9), fos. 103b 104b, pp. 225 7 (Russian trans.).

33 Kamal al Din Banna'i (Bina'i), Shayhdni ndma, ed. Kazuyuki Kubo (Kyoto, 1997), pp. 57.

253

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

different political reality, the Bahr al asrar divides its discussion of the

between those who were affiliated with the khan in Bukhara and those affiliated with the author's patron in Balkh. Further differentiations are made based on office held, with the 'father surrogate' or 'tutor' (atafiq, ataka) and the 'milk brother' (kukaltash) representing the pinnacle of amirid

proximity to the Chinggisid clan. The leading amirs at least had resources at

their disposal comparable to those available to the Chinggisid ruling clan. One

of Kistan Qara Sultan's amirs, Kama! al Dm Qunaq (fl. 1540), for example, built

and endowed an extensive congregational mosque and madrasa complex in

Balkh just outside the inner city walls. 34 Nithari tells of his own study of astronomy at Kama! al Din Qunaq's madrasa. 35 Yet today, except for the tombs of Kistan Qara and a woman, possibly his daughter, Sharifa Sultan Khanum, no trace of either his or Kamal al Dm Qunaq's extensive architec

tural legacy has survived. 36

Another great amirid patron of literature and architecture was Qui Baba Kukaltash (d. 1598), 'Abd Allah b. Iskandar's chief amir and leading adminis

trator of his regime. Besides leading the army on numerous campaigns, he

oversaw the work of [ Abd Allah's chancellery as mushrifi diwani. He also had

charge of the judicial administration (sadarat i khanT) and in this capacity

apparently was assigned to probate [ Abd Allah Khan's father's estate. 37 Oui

Baba was also a great patron of architecture, some of which survives. He is

best known today for his great Bukharan madrasa of 160 cells (hujras) which

stands on the north side of the Lab i Hawz (see below). According to its endowment deed, it was built in 976/1568. and probably housed more than 300

students in its heyday. He is also said to have built madrasas in Samarqand,

Tashkent, Herat and Taluqan. And while he was governor of Samarqand (after the ouster of the last Kuchkunjid there in the spring of 1578) he devoted

many of his resources to restoring and refurbishing Timurid buildings in the

city. According to Hafiz i Tanish this was done at the instructions of [ Abd Allah Sultan after his visit in January 1580. 3§ Like his khan, Qui Baba is also

34 For a description and the endowment of this complex see R. D. McChesney,

'Reconstructing Balkh: The Vaqftya of 947/1540', in Devin DeWeese (ed.), Studies on

Central Asian history in honor of Yuri Bregel (Bloomington, IN, 2001), pp. 187 243.

35 Nithari, Mudhakkir i ahbdb (New Delhi, 1969), pp. 373 4.

36 For a photograph of Kistan Qara's tomb see Bernard O'Kane, 'The Uzbek architecture

of Afghanistan', La memoire et ses supports en Asie central; Cahiers dAsie Centrale, 8 (2000), pp. 122, 128.

37 Hafiz i Tanish, Sharafndma i Shahi, India Office Library ms. 575, fo. 311a.

38 Ibid., India Office Library ms. 574, fos. 234b, 276b.

254

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

credited with the building of commercial structures, including a serai in Bukhara and a ribdt near Balkh. 39

Qui Baba was a man who loved literature and compiled a large library which he donated to his madrasa in Bukhara. He hosted literary assemblies

and took the pen name 'Muhibbi'. Mutribi Samarqandi, who knew him personally, relates an occasion on which Qui Baba offered him 1,000 tangas

if he could compose five lines of poetry that would appropriately complete an

opening line (matla') which he gave him. But Mutribi felt the number of possible rhyming syllables was limited and, 'the horse of his mind having come up lame in running back and forth searching for those words', he had to

excuse himself. 40

# Shibanid-era shaykhly patronage

Under Abu'l Khayrid auspices, the descendants of Khwaja 'Ubayd Allah Ahrar,

Khwaja Ahmad Kasanl and Khwaja Muhammad Parsa, all Naqshbandis, flour

ished in their respective centres (the Ahraris in Tashkent and Samarqand, the

Kasanls or Dahbidis in Dahbid outside Samarqand and the Parsa'is in Bukhara

and Balkh). One shaykhly family in particular, the Juybaris, stands out for its

political influence and its wealth. Its transformation from a modest family of

shrine caretakers (responsible for the Char Bakr shrine west of Bukhara City) to

an extraordinarily wealthy dynasty of kingmakers was completed in the second

half of the sixteenth century. Along with this transformation came the acquis

ition of enormous wealth. An outsider, Anthony Jenkinson, was mightily impressed by the founder of the family's fortune, Khwaja Muhammad Islam,

when he reached Bukhara in December of 1558:

There is a Metropolitane in this Boghar who causeth this lawe (Shari'a) to be

straightly kept, and he is more obeyed than the King and will depose the king,

and place another at his will and pleasure as he did by this king that reigned at

our being there. 41

The basis of the Juybari family's landed wealth is richly documented but where the capital originated remains something of a mystery. Land and other

real estate in and around Bukhara were purchased in astonishing amounts

39 Ibid., fos. 311b, 456b; Muhammad Bad!' Samarqandi, Muzakkir alashab, IVAN,

Uzbekistan, ms. 4270, fo. 44b.

40 Mutribi Samarqandi, Tazkirat al shu'ara (Tehran, 1377/1998), pp. 460 1.

41 E. Delmar Morgan and C. H. Coote (eds.), Early voyages and travels to Russia and Persia by

Anthony Jenkinson and other Englishmen, (New York repr. of London 1886 edn), vol. I, pp. 83 84.

255

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

over a thirty year period between 1544 and 1577. 42 The Juybaris (Muhammad

Islam 'Khwaja Juybari', his son Khwaja Sa'd 'Khwaja Kalan Khwaja' and subsequent generations) used this wealth to make themselves major patrons

of architecture, scholarship and art from the second half of the sixteenth century down to the early nineteenth, 43 building madrasas and mosques,

patronising painters and calligraphers, and commissioning biographies of the

family. This tradition was carried on by their descendants through subsequent

centuries. Their best known surviving monuments are the Gawkushan Madrasa and Friday Mosque complex straddling the main canal (the Rud i

Shahr) that bisects Bukhara, the Kalabad madrasa in the eastern part of the city

and the Char Bakr complex. The greatest builder in the family was the Khwaja

Sa c d al Din (aka Khwaja Kalan Khwaja, d. 1589) son of the founder of the

family's wealth. He has been credited with at least seventy five major public

works including parish and congregational mosques, madrasas, khanagas,

chahdr bdghs, public baths, caravanserais, canals and underground cisterns

(sarddba). No other figure in either the sixteenth or seventeenth century approached this level of public building.

The Tugay-Timurid era: 1599-1747

In 1598 9, the Shibanid Chinggisids in Mawarannahr and Balkh succumbed to

internecine struggles and external pressures. A new Jochid Chinggisid family,

the Tuqay Timurid, found the needed amirid support to oust the last of the

Jani Begid Shibanids from Bukhara and take power.

As their resources permitted, the Tuqay Timurids followed the established

pattern of their Shibanid predecessors in sponsoring public works projects.

No building activity or other cultural patronage is yet associated with the name of the first Tuqay Timurid khan, Jani Muhammad (r. 1599 1606), but his

sons, Baqi Muhammad and Wall Muhammad, on the other hand are both well

memorialised as builders. The former sponsored the construction of a Friday

mosque and a madrasa in Bukhara, both of which survived into the nineteenth

42 Iz arkhiva Dzhuihari, ed. [F. B. Rostopchin] and E. E. Bertel's (Leningrad, 1938) contains

some 400 deeds of sale for properties throughout Central Asia but mostly concentrated

in Bukhara City and the Bukharan oasis. In addition, collections of individual sale deeds

as well as deeds of gift to the Juybaris and endowments they created are found in the

archives of Uzbekistan and Tajikistan.

43 James B. Fraser, Narrative of a journey into Khorasan in the years 1821 and 1823 (1984 repr. of

London 1825 edn), Appendix B, 83 calls the Juybaris of his day 'the greatest of these holy

personages (i.e. the ulema)' who could be considered 'independent of the king' due to  $\frac{1}{2}$ 

their immense wealth.

256

Islamic culture and the Chinggisid restoration

century, along with a chahdr bdgh, the location of which is no longer known. In

Samarqand, which he briefly held in 1598 9, he is remembered for an assembly

hall (kurnish khdna) and a holiday prayer ground (^idgdh).

Wall Muhammad, who held Balkh before he became khan, is remembered for his patronage of the shrine 'All b. Abi Talib to the east of the city. He had

an avenue (khiydbdn usually implying landscaping with trees and gardens as

well as a road) laid out between Balkh and the village (now the city of Mazar i

Sharif) where the shrine was situated. At the shrine itself, he renovated and

expanded part of the shrine building. He also had a 50 acre chahdr bdgh of

eighteen parterres (chaman) constructed. 44

Imam Quli Khan, who ruled Bukhara from 1611 to 1641, has left virtually no

record of patronage. A single madrasa in Bukhara and a large canal at Tashqurghan are the only projects attributed to him in the textual record. His brother, Nadhr Muhammad, on the other hand, who ruled independently

south of the Oxus river during the same period, was a very active builder. In

the detailed history of his reign at Balkh, the Bahr al asrdrfi mandqib al akhydr

(which he commissioned), Nadhr Muhammad is depicted as a major patron of

architecture. In the outer city, he built a large madrasa of fired brick (begun in

102.1/1612) with four lecture halls and many dormitory rooms and a library of

2,000 volumes. He also built a palace district (dawlat khdna) in several (the cosmological number 'twelve' is given) sections (darband) in a garden

estate that had once belonged to a Jani Begid era amir, Mir Jan Kildi Bi. Although no trace of it remains today, all evidence indicates the complex was brought to completion. The Mughal historian 'Inayat Khan, author of the

Shah Jahdn ndma, mentions its existence in 1056/1646 when a Mughal army

occupied the city. 45 The Tugay Timurid ruler of Balkh also constructed a

congregational mosque in Qunduz. In addition, seven hunting lodges or palaces are also attributed to him and these may well have been inspired by

descriptions he heard of the hunting palaces constructed by Shah Jahan in

India.

His sons and subsequent successors to the khanate, Abd al 'Aziz and Subhan Quli, both left major madrasas with rich endowments as monuments

to their reigns. The Abd al 'Aziz Khan madrasa today stands opposite the madrasa of Ulugh Beg in the Goldsmith's Quarter of Bukhara but only a

44 R. D. McChesney, Waqfin Central Asia: Four hundred years in the history of a Muslim shrine 1480 1889, (Princeton, 1991), pp. 88 90.

45 Inayat Khan, Tfie Shah Jahan Nama, trans. A. R. Fuller, ed. and completed W. E. Begley and Z. A. Desai (Delhi and New York, 1990), p. 350.

257

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

remnant, the entryway, remains of the Subhan Quli Khan madrasa in Balkh,

which was built opposite the Abu Nasr Parsa shrine.

Uzbek amirid patronage under the Tuqay-Timurids

The leading amirs of the seventeenth century, men like Nadr Bi Diwanbegi

Arlat and Yalangtush Bi Alchin, have left a substantially richer record of patronage than their Tuqay Timurid masters. Like their sixteenth century predecessors, they cultivated shaykhly and scholarly figures by building and

endowing madrasas and khanaqas. Today much of the architectural legacy of

Nadr Bi Arlat and Yalangtush Bi Alchin survives in Samarqand and Bukhara.

Nadr Bi Arlat had the nickname 'Taghay', a kinship name referring to the fact that his aunt was Imam Quli Khan's mother. 46 He was Imam Quit's most

trusted amir and held the position of diwanbegi, chief financial officer. He took

a special interest in the Ahrari legacy in Samarqand, erecting a madrasa (recently renovated) at the tomb of Khwaja Ahrar as well as a tomb enclosure

(hazira), presumably around the platform (sujfa) on which Ahrar's tombstone

now stands. Work on the madrasa began in 1630 and was completed in 1635 6.

South of the city he built a hostel (khanaqah) at the shrine called 'c Abdi Biriin'.

The building that survives there today does not, however, seem to be the hostel. In Bukhara, Nadr Bi sponsored the building of what has become the

centre of the old city, the Lab i Hawz (Cistern's Edge). His constructions there

included a madrasa and khanaqah facing each other across a huge stone reservoir (hawz). All three works are intact and have been recently refur bished. The north side of this complex is flanked by the Qui Baba Kukaltash

madrasa. Both the Nadr Bi and Qui Baba Kukaltash madrasas were important

educational centres from the time of their construction well into the Soviet

period.

Nadr Bi was the leading amir under Imam Quli Khan and was called the 'guiding vizier and the righteous amir' by Mahmud b. Amir Wali. Besides his

marital connection to the khan, he had also married one of his daughters to a

Juybari scion and another to Khusraw, the second son of Imam Quli's brother,

Nadhr Muhammad. Intermarriage between khanly, shaykhly and amirid families was common throughout the two centuries discussed here and served

to meld the interests and the constituencies of the three elite groups.

46 Mahmud b. Amir Wall, Bahr al asrdr, vol. VI, part 4, fos. 124a b. Also see L. Z. Budagov,

Sravnitel'nyi slovar' turetsko tatarskikh narechii (St Petersburg, 1869), tagha, taghdy, taghdy

'uncle on the mother's side (elder or younger brother of the mother)'.

258

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic culture and the Chinggisid restoration

Yalangtush Bi Alchin was very much a self made man. His given name was

Jatay Bahadur and he left Shighnaq in the Qipchaq steppe at the age of twelve

to link his fortunes to the Tuqay Timurids. He may have come south with his

father, Bay Khwaja Bi, but we know nothing of the latter. Yalangtush offered

his services to Dm Muhammad apparently during the Shibanid/ Uzbek

pation of Herat and the Tuqay Timurid campaigns in Quhistan, that is in the

early to mid 1590s, and was given the title 'Yalangtush' ('bare chested' 47 ) by

Dm Muhammad for heroic action. He was known by this name from then on.

Once the Tuqay Timurids came to power in Transoxania, he was assigned first to one of the collateral branches of the family and spent a few years fighting the Qazaq threat in the east. He then was with Imam Quit in Samarqand during Wall Muhammad's reign (1606 11). It was in those years

that he not only acquired extensive properties in the Samarqand region but

also forged close ties to the Dahbidi Naqshbandi shaykhs. By the early 1620s he

was with Nadhr Muhammad in Balkh and had been assigned control of the

marches to the south. He built two very large madrasas in Samarqand on the

Rigistan; these madrasas were popularly known as the Shirdar/ Shayrdar

('lion possessing', for the depictions of lions on the spandrels) and the Tilla

Kar ('gilded', for the decoration). They flank the east and north sides of the

Rigistan square respectively. The Shirdar, on which work proceeded from 1619 to 1636 under the supervision of the architect Mulla Abd al Jabbar, faces

the Ulugh Beg madrasa across the square. The Tilla Kar madrasa, constructed

a decade after the Shirdar, at some point came to serve as the main congrega

tional mosque, probably due to the dilapidation of the great Friday mosque of

Temiir, known today as the Bibi Khanum mosque.

Outside Samarqand at Dahbid, the shrine centre of the 'Makhdum i A'zam'

Khwajagi Ahmad i Kasani (d. 1549) and the centre of the missionary organ

isation that was carrying Naqshbandi Sufism eastward into China, Yalangtush

Bi constructed a khdnaqa, no longer extant. He also planted an avenue of plane

trees (chinaf) so that the members of the order could travel to Samargand in

shade. According to Mahmud b. Amir Wall, the endowment for the two madrasas in Samarqand was a 'gift' for the Dahbidi shaykhs.

Yalangtush Bi's wealth in land was considerable. The Uzbek State Archives

contain at least eight documents relating to his properties, including two endowment deeds. A land survey undertaken by the tsarist government in

47 I am grateful to Florian Schwarz for this information. Mahmud b. Amir Wall may have

been referring to a fight in which the warrior went into battle without armour.

259

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

the 1870s revealed that the endowment lands for his madrasas exceeded 5,300 tandbs or about 2,700 acres. 48

These few examples typify the building activity of the elites of Mawarannahr and Balkh and serve to represent the hundreds of other public

building projects chahdr bdghs, parish mosques, canals, bridges, prayer grounds ('Mgahs), assembly halls (kiirnush khdnas), cisterns (sar hawz and

sarddba) and commercial structures (twns, serais, ribats, caravanserais), etc.

for which records exist. Building construction as we know it from texts seems

to have peaked in the last half of the sixteenth century and this would accord

with what is known about the trajectory of the region's economy, fuelled perhaps by New World silver until the early seventeenth century and then

subsiding, in part because of the decline of the precious metal exports from

South and Central America that eventually found their way to Central Asia via

the Philippines and India, and in part perhaps because of the unusual climatic

conditions of the seventeenth century (the so called 'cold century'). Whatever

the causes, after 1650 at the latest, major construction projects are no longer

recorded at the rate sketched above.

# Islamic scholarship

Although monographic studies of the intellectual history of sixteenth and seventeenth century Central Asia have yet to be written, certain trends and

patterns may be discerned in the literature of the time. For one thing, scholars

showed a degree of regional loyalty, not surprising considering that Central

Asia was the nursery of Hanafi legal studies, and Hanafi Islam was the nearly

universal legal tradition followed by Central Asian scholars of the period. Works by authors of Central Asian origin or by authors who had spent a considerable part of their lives working in the madrasas, law courts and political courts of the region but who had immigrated (sometimes involun tarily) from elsewhere dominate the book lists of this era, whether these lists

are found in book endowments, in the curricula vitae of scholars or in licences

to teach (ijdzdt). In addition to the geographical focus, a Timurid era prove

nance of a majority of the books found in the book lists of the seventeenth

century is evidence of the creation and canonisation of a madrasa curriculum

Gosarkhiv Uzbekistana, Kollektsiia vakufnykh dokumentov, Tashkent, 1983, nos. 1180/9,

1197/1 6, 1203/9. See also O. D. Chekhovich, Dokumenty k istorii agrarnykh otnoshenii v

Bukharskom khanstve XVI XIX vv., Tashkent, 1954, documents 1, 2, 6, 9 and 13.

260

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

under Timurid auspices. As noted above, the five most important scholars of

the Timurid period in terms of producing the texts underlying the madrasa

curriculum of later centuries were al Taftazam, al Jurjanl (al Sayyid al Sharif),

al Jazari, Jam! and Kashifi. The first three were either invited or transported to

Temiir's court in Samarqand while the last two were part of the Herat court

scene under Sultan Husayn Mirza and the 'Maecenas of the age', Mir c Ali Shir

Nawa'I Their original works as well as their commentaries, glosses and superglosses make up a substantial part of the lists of books donated to madrasas or cited as the books a well educated person should know. For

example, in one endowment of books to the Ulugh Beg madrasa in Bukhara

eight of the seventy books in the list were titles by al Taftazam alone. 49

The lives of many scholars bridged the unsettling transition from Timurid to Shibanid rule, as already noted. As an example of the importance attributed

to that period for contemporary scholarship, Mahmud b. Amir Wall devotes

several pages to the great scholars who migrated to Transoxania in the early

sixteenth century from Timurid lands and left a legacy of works which students in his own day, a century later, were still studying. One such example

is the philologist 'Isam al Din Ibrahim b. Muhammad al Isfaralm (d. 1537).

Al Isfara'mi taught in Herat at the Shah Rukh Mirza madrasa during the reign

of Sultan Husayn Bayqara but left in 1520 for Bukhara where he enjoyed the

patronage of 'Ubayd Allah Khan until his death. 50 One of the books Mahmud

mentions that students of his time were reading was Isfara'im's gloss (hashiya)

on Abd al Rahman Jami's al Fawa'id al Ziya'iyah, in turn a commentary (shark) on Ibn Hajib's work on Arabic syntax, al Kdfiya. 51 Other standard

works by al Isfara\*im on the madrasa curriculum were a commentary on Nasafi's famous creed, a supergloss (hashiya 'aid hashiya) onjurjam's gloss on

Taftazam's commentary on Khatib al Dimashqi's abridgement of al Sakkaki's

work on rhetoric, Miftah al 'ulum and a gloss on Kashifi's commentary on the

Qur'an.

# Support for scholars and scholarship

Thanks to the observant eye and detailed records kept by Mahmud b. Amir

Wall and later historians of the seventeenth century, the outlines of academic

(as distinct from mystical) scholarship as well as scholarly life are fairly distinct.

- 49 Uzbek State Archives fond 1 323, document no. 114/2.
- 50 Khwandamir, Habib al siyar, 3/3: 358.
- 51 Mahmud b. Amir Wall, Bahr al asrar, vol. VI, part 4, fos. i49aff.

261

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

Besides endowed professorships at madrasas, scholars seeking a stipend to

support their work had a number of government offices to aspire to. Those to

which people of learning were appointed and which were not reserved for

certain families included: sadr, qadi, qadi'askar, mufti, mufti 'askar, ra'is and

ra'is i'askar. The exact functions of all these offices must be inferred from

context in which they appear. What seems clear is that the titles suffixed with

' l askar were connected to the court of the appanage khan while every town

with a shaffa court would have had a qadi, mufti and ra'is. In addition, by

beginning of the seventeenth century one finds the honorary title of a'lam al

'ulama' ('most learned of the learned'). By all accounts conferral of these offices and titles was based on merit, although being the son of such an office holder was a definite advantage if one aspired to the same career.

The offices of shaykh al islam and naqib, on the other hand, were reserved

for individuals from specific families and were not strictly speaking associated

with scholarship. In this period, every major city had a shaykh al islam while

the office of naqib seems to have been restricted to the khanly court. Efforts

have been made to determine the role of the shaykh al islam in Timurid times 52,

but the term occurs there in different contexts and all one can say for certain is

that it was considered the most prestigious title for those connected with Sufi

traditions. During the sixteenth and seventeenth centuries, the tide was reserved for specific shaykhly families. In Jarii Begid Bukhara (i.e. after 1556)

the office of shaykh al islam belonged by right to the Juybari family. In Samarqand it was granted to the Ahraris, in Balkh it had been given to the

Parsa'is in Shah Rukh's time (r. 1409 47), according to Mahmud b. Amir Wall,

and was still held by them in the mid seventeenth century. Throughout Transoxania and Cisoxania, the office of naqib 53 was held by either members

of the Sayyid Ata\*i family itself or members of the Sayyid Ata'i order, an offshoot of the Yasawiyyah. 54 When the Tuqay Timurids came to power (1599

in Transoxania and 1601 in Balkh) those privileges were all reviewed. In Samarqand by the end of the seventeenth century, the office of naqib (niqabat)

was in the hands of the Dahbidis where it seems to have remained, and in Balkh, a Sayyid Ata'i was dismissed from the post in 1634 and replaced by a

Naqshbandi, a shaykhly line connected with the shrine centre at Bukhara.

52 Shiro Ando, 'The shaykh al islam as a Timurid office: A preliminary study', Islamic Studies, 33 (1994), pp. 253 80.

53 Devin DeWeese, 'The descendants of Sayyid Ata and the rank of naqib in Central Asia',

Journal of the American Oriental Society, 115 (1994); pp. 612 34.

54 Devin DeWeese, 'Ata'iya order', EIr, vol. II, pp. 904 5.

262

# Islamic culture and the Chinggisid restoration

All offices were subject to the approval of the appanage khan, whose right

of appointment and dismissal was absolute. Qualifications were made known

to him by the recommendations of others or by a kind of competitive inter

view process over which the khan presided and at which supplicants were

asked to discuss and debate a particular question. Sometimes the credentials

became known to the khan at his more informal assemblies where extempo

raneous skills were challenged: to produce or answer a riddle, for example, or

to compose a verse after being given the matla c (the two opening hemistichs of

a poem). Notable scholars themselves held assemblies at which budding talent

emerged. One of the qaals of Balkh, a man known as Khwaja Mulla yi Qadl, is

a case in point. His father left Khurasan for Mawarannahr probably following

one of c Ubayd Allah's forays there. He entered the service of Iskandar Khan

the Jam Begid and then worked for [ Abd Allah, Iskandar's son and successor as

khan. We are told he frequented the salons of individual scholars and it

through this avenue that he came to the attention of [ Abd al Mu'min, [ Abd

Allah's son, who took him to Balkh and appointed him qadl and professor at

the c Abd Allah Khan madrasa. (The frequency of joint appointments of gadls to

professorships suggests the endowed professorship may have been the source

of the salary.)

The ^ulama 1 proper, that is those who might have sought credentials for,

and eventually aspired to, the formal position of cflam al c ulama' (or a l

for short), by and large tended not to be from shaykhly backgrounds. But not

unlike the shaykhly families, the pre eminent scholars of the time tended to

have a regional importance only and did not generally move from city to city. In Bukhara the pre eminent 'ulamff of the seventeenth century were, first, Mawlana Yusuf Qarabaghi (dates of his death vary from 1624 to 1645)

and after him Mulla Muhammad Sharif al Bukhari (d. after 1699).

Qarabaghi's and Bukhari's work followed the same disciplines glosses on Qur'anic commentaries (Bayzawi especially), on works of Hanafi jurispru dence and on works of logic (particularly those of Taftazam and Jalal al Din

Dawani). The library of the Biruni Institute of Oriental Studies in Tashkent,

Uzbekistan contains two separate glosses on Bayzawi's commentary on the

Swat alfath and a gloss on Dawam's (d. 1502) commentary on al Iji's (d. 1335)

al Mawaqiffi Him al kaldm, an extraordinarily popular handbook on theology, all by Qarabaghi.

The scholarly career of al Bukhari is somewhat more accessible than Qarabaghi's and as his work follows the same path he in fact wrote a gloss

on al Mawaqif avowedly to bring to completion the Dawani Qarabaghi com

mentary it is not unreasonable to think that Bukhari was Qarabaghi's

263

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

student and that therefore we can infer something about Qarabaghi's career

from Bukhari's. Both were connected to the politicians of their time: Qarabaghi reportedly supported Imam Qui! Khan (r. 1611 41 at Bukhara) in

his successful bid to take the khanate from Wall Muhammad Khan (r.  $1606\ 11$ )

and although al Bukhari's direct involvement in politics is unknown, he

dedicate his commentary on al Mawagif to the Tugay Timurid khan at

Bukhara, Abd al 'Aziz (r. 1645 81). When the latter's brother assumed the khanate at Bukhara in 1681, al Bukhari resigned his position as a lam al c ulama'

and his professorships (perhaps in anticipation of losing these to scholars favoured by the incoming khan) and retired to his khanaqa.

Mulla Muhammad Sharif al Bukhari's list of known works again reflects the

very powerful influence of Timurid scholarship on later writing and is most

notable for its similarity to the work of al Isfaralni a century and a half earlier.

He wrote a gloss on Jami's commentary al Fawa'id al ziya'iya on Ibn Hajib's

popular Arabic grammar al Kdfiyah fi'l nahw; the above mentioned gloss on

Dawam's and Qarabaghi's glosses on al Mawaqif and also a supergloss on his

own gloss on those works, and finally a gloss on Taftazarii's widely used textbook on logic, TahdMb al mantiq.

At Balkh, the a'lam al 'ulamff of the first half of the seventeenth century was Mawlana Hasan Qubadyam, a very influential teacher whose students

went on to fill the offices ofqadi, mufti and ra'ls throughout the region. At the

end of the sixteenth century he was studying in Bukhara, and early in the seventeenth came to Balkh at the request of the appanage khan there, Nadhr

Muhammad. By virtue of his brilliant performances at the assemblies for scholars presided over by the khan he won a professorship at the 'Abd Allah

Khan madrasa. When Nadhr Muhammad's own madrasa was completed (sometime after 1612) a professorship there was also given to him. Later Qubadyani set out on the hajj pilgrimage via India and was received by Shah

Jahan but died soon after at Agra without reaching the Holy Cities. His son

was one of his students and was appointed professor at the c Abd Allah Khan

madrasa in Balkh.

For scholars and shaykhly figures alike, styles of living should not be confused with their particular career paths. Individuals could be, and were,

c ulama' in the traditional 'transmitted' disciplines of jurisprudence, Qur'anic

commentary and hadlth and yet follow a life of asceticism more commonly

associated with mystics or Sufis. For example, a certain Mawlana Ali Beg was

described as learned mfiqh, tafsxr and hadith, wore the clothing 'of the people

of poverty and annihilation' (faqrwafana), and avoided contact with 'worldly

people' (abna al zamari). Another man described as 'an extreme mystic who

264

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic culture and the Chinggisid restoration

became a malamati ', a term indicating behaviour or professed belief outside

the norm, held a professorship at the Qui Baba Kukaltash madrasa and was at

one point named to the post ofqadi 'askar. On the other hand many of those

primarily known for their prominence in the Naqshbandi Sufi sub orders were

renowned and indeed celebrated for their affluence and luxurious lifestyles.

Typical is an Ahrari from Samarqand, Khwaja Abu'l Qasim, who 'paraded in

the garments of a possessor of great wealth as a means of concealing the face of

the mysterium. The narratives indicate that society could separate a person's

learning and what that qualified them for from their personal religious beliefs

and practices.

To sum up, scholarship in the sixteenth and seventeenth centuries followed

and built on the scholarship of the Timurid era. Intellectuals were dependent

on the government for positions injudicial administration and teaching for the

living that would provide them the means to carry on their work. Politicians in

turn looked to the output of the great madrasas of Bukhara, Samarqand and

Balkh to staff not only their shari'a courts but to confirm their own roles as

defenders of Islam and as continuators of the great scholarly traditions of Central Asia.

The Chinggisid restoration petered out in Khwarazm, Mawarannahr and Balkh by the middle of the eighteenth century, although vestiges of Chinggisid

norms and practices survived, and in Bukhara and Balkh as nominal khans

were kept in public view for a time. Eventually however, the amirs used their

power as the military support for Chinggisid claims to dispense entirely with

the Chinggisid lines. But, during the restoration, due in no small part to the

economic resources available during that period, the Chinggisids, both Shibanids and Tuqay Timurids, oversaw the continuation and expansion of

Timurid Islamic culture.

265

Cambridge Histories Online © Cambridge University Press, 201 1

8

India under Mughal rule

STEPHEN DALE

Introduction

In 1526 Zahir al Dm Muhammad Babur (888 937/1483 1530) successfully invaded north India and founded the Mughal empire (932 c. 1152/ 1526 c. 1739)

(see Map 6). Babur, as he is generally known from his personal name meaning

leopard or tiger was a Turco Mongol, Hanafi Sunnl Muslim native of western

Central Asia. He was descended from two Central Asian conquerors. These

were the Barlas Turk Temiir (736 807/1336 1405), known in Persian as Timur i

leng, 'Timur the lame', or in European parlance Tamerlane, and Chinggis Oan

(c. 563 625 1 c. 1167 1227), or in Persian spelling Chingiz Khan. As a patrilineal

descendant of Temiir he thought of himself in ethnic, social and dynastic terms

as a Turk and a Timurid, but he also revered his matrilineal Mongol connections

traced through Chinggis Khan's second son Chaghadai. Raised as an observant

Sunni Muslim in the lush Farghana valley east south east of Tashkent, Babur

was also born into the Naqshbandi Sufi order, a doctrinally conservative but

politically active devotional order long connected with Temiir's descendants.

Babur both wrote and spoke Turki, the language common to most contempo

rary Turks and Mongols, but like many other well educated men of the region

he also knew Persian, the lingua franca and dominant literary language of

the Iranian plateau and the cities of Central Asia and north India in the early

modern era.

Babur invaded India for two interrelated reasons. First, he was an ambitious

warrior aristocrat of impeccable lineage, and second, he lacked a decent kingdom after the Uzbeks expelled him from Central Asia in 909/1504. Thus

as a descendant of Temiir and Chinggis Khan, he possessed, what he ingen

uously describes in his autobiographical memoir, the VaqdH\ as 'kingdom seizing' ambitions. His descendants were similarly motivated, although they

rarely expressed themselves so baldly. Then as he looked around from his impoverished base in Kabul, where he took refuge and ruled from 909/1504 to

Cambridge Histories Online © Cambridge University Press, 201 1

# India under Mughal rule

932/1525, Babur saw in north India a politically vulnerable and wealthy agrarian heartland that offered the economic basis for a respectable empire.

He could also claim to be a legitimate ruler of the territory he identifies as

Hindustan, a legacy of Temiir's invasion of India and sack of Delhi in 800/1398. It is quite likely that Temiir's example, commemorated by paintings and

buildings in Samarqand, might have prompted Babur to see India as a potential target for his ambition even before 925/1519, by which time he had

decided on an invasion. By defeating the army of his fellow Muslims, the Afghan Lodis, at the Panipat battlefield north of Delhi in 932/1526, Babur initiated the Timurid renaissance, a dynasty whose eclectic culture was formed from the mutual influence of Babur's Central Asian heritage and the

indigenous traditions of his Indian empire.

In addition to its Central Asian and South Asian strains, the Mughal empire,

or as it is variously known, the Indo Timurid or Timurid Mughul empire, should also be understood within the context of the other three contemporary

early modern Islamic powers: the Ottoman and Safavid empires and the Uzbek confederation. These states were linked with and influenced Babur and his descendants in a variety of ways. All three states were connected to

Mughal India by well established trading patterns and the circulation of literary, religious and scientific elites. However, apart from those common

ties, the Ottomans, who shared the Mughal's Hanafi Sunm orthodoxy, were

particularly influential in Mughal India as experts in military tactics and fire

arms technology. The Safavids, a militantly Shi'i dynasty, exported

capital to India in the form of Persian speaking artists, bureaucrats and literati,

even when the Safavid shahs were fighting Mughal armies for control of the

wealthy and strategic city of Kandahar in south central Afghanistan. The Uzbeks, a Hanafi Sunni tribal confederation, were both the revanchist focus

of Mughal imperial nostalgia and the homeland of the Mughal's Nagshbandi

Sufi order. In addition Uzbek lands functioned as a source of military immi

grants and a reservoir of cavalry horses for the Mughal army. Thus Mughal

India continued to function throughout its history as an interconnected regional variant of a broader Central Asian and Middle Eastern Islamic world. However, compared to the Ottomans, Safavids and Uzbeks, the Mughal empire's ultimate legacy was muted. Unlike those states, which ultimately gave way to ethnically recognisable successors with predominantly

Muslim populations, the Mughals left behind a Muslim minority within an overwhelmingly non Muslim environment ruled by a European trading com

pany. In that respect it is perhaps appropriate that the Taj Mahal, Mughal

India's most exquisite architectural artefact, is a tomb, although it is also

267

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

particularly ironic that the Taj Mahal has come to symbolise India for out siders in modern times.

The Central Asian background

The Mughal empire's Central Asian heritage is a habitually neglected aspect of

its history. It is common to begin accounts of the empire with the reign of Akbar (r. 963 1014/1556 1605), largely ignoring both Babur and his son, Humayun (r. 937 47, 962 3/1530 40,1555 6). Yet the Mughal empire was in

its origin a late Timurid, Central Asian state and aspects of this heritage are

visible throughout the dynasty's Indian history. That heritage involved, first of

all, a dynastic culture characterised by a supremely confident sense of legiti

macy and a perennially unstable succession tradition. The Mughals' confidence in their family's prestige is exhibited prominently in Babur's memoirs,

where he exhibits a casual arrogance and assumption of sovereignty over any territory he fancied born of his impeccable Turco Mongol lineage. Contemporaries and such rulers as the Safavids generally accepted Babur's

political conceit and that of his son Humayun. This recognition sustained both

men during their tumultuous careers that were replete with near death political experiences. Throughout the later history of the Mughal dynasty its

rulers constantly reminded themselves and their courtiers of their genealogy

in histories, paintings, inscriptions and royal titles, and, in truth, no earlier or

contemporary Muslim rulers in India possessed imperial traditions of com

parable grandeur.

If the Mughals' impeccable lineage distinguished them in India, that was partly because few other Timurids or Chinggisids of note survived the debacle

of the Uzbek conquest to challenge their rule in Hindustan. During his Central

Asian years, 888 909/1483 1504, Babur had been just one among many Timurids and Chinggisids who struggled for power in what was an atomised,

fragmented political 'system'. However, it was not just the multitude of legitimate claimants that fuelled the internecine wars of the late Timurid era. These conflicts were also the product of traditional Turco Mongol inher

itance and succession customs that were also noted features of Mughal dynastic history.

In Turco Mongol states any son could legitimately compete for power, a principle institutionalised in the appanage system, in which Timurids and Chinggisids parcelled out territories among their sons, each one of whom could and usually did compete for their father's patrimony during his lifetime and thereafter. Sons were sent to their appanages with military

Cambridge Histories Online © Cambridge University Press, 201 1

## India under Mughal rule

guardians when they were young boys, where each of them developed mini

courts and a sense of their own independence. The competition among them

intensified when, as was common, they were sons of different mothers. As

these boys usually matured apart from their brothers and half brothers they

also lost a sense of family identity or, in Ibn Khaldun's terms, social solidarity,

which understandably atrophied over the time and distance they spent apart

from their natal household. Unlike the Ottomans and Safavids, Mughal rulers

retained these traditions throughout the history of the dynasty, with the result

that sons habitually rebelled against their fathers, whose deaths often trig

gered bloody civil wars among their male descendants.

The Mughals' history of internecine dynastic warfare implicitly raises one other facet of the dynasty's Central Asian heritage, their military tactics. Knowledge of these tactics is especially important for understanding Babur's

pivotal victories in north India in 932 3/1526 7. Babur fought his battles utilising highly structured traditional Central Asian battle formations and tactics. While cavalry raids were a perennial feature of Turco Mongol military

encounters, major confrontations did not usually feature free flowing cavalry

encounters over miles of open steppe, but set piece battles on prepared fields.

Babur himself describes how he and his men dug ditches in a meadow outside

Samarqand before confronting Shibani Khan Uzbek in 906/1501, when he suffered the catastrophic defeat that led to his eventual flight from Central

Asia in 909/1504. In the late fifteenth century such battles were often decided

by disciplined, highly mobile cavalry, as Babur himself acknowledges was the

case in the Uzbek victory. Swift flanking cavalry manoeuvres were the signature Turco Mongol military tactic, which Mongol detachments used to

secure Babur's Indian victories first at Pariipat and then in the following year at

Kanwa against the Hindu Rajputs. Later, sieges became common in an Indian

countryside dotted with formidable fortresses, but Mughal heavy cavalry always remained the principal striking force of the regime's formidable armies.

Despite their Turco Mongol political and military traits, as late Timurids the Mughal emperors espoused the values of the eastern Islamic world, that is,

the norms of Perso Islamic culture. They saw themselves as sedentary Muslim

just sultans', men who encouraged agrarian development, valued urban life

and protected lucrative, taxable commerce. All identified Islam with urban

life and vice versa. The late Timurids' cultural vision of themselves is most.

obvious in their Sunm Muslim orthodoxy and reverence for the Nagshbandi

and Chishti Sufi orders and respect for Persian literary culture. Babur's

religious tutor, Khwaja Maulana Qadi, was a descendant of the important

269

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

'alitn Burhan al Dm Ali Qilich al Marghmani, who, like Babur, was a Farghana valley native. This man was the author of the Hiddya, a book that

became a standard reference of orthodox Hanafi practice widely known throughout the Sunm Muslim world, including the fourteenth century Delhi

sultanate. Al Marghmani personified the dominance of Hanafi Sunni ortho

doxy that was characteristic of theologians in Bukhara and Herat in both the

pre Mongol and Timurid eras. Khwaja Maulana Qadi was also a Naqshbandi

Sufi, and this was virtually a dynastic Timurid devotional order, although Temiir's descendants were also respectful of the Chishtiyya, itself, in origin, a

Central Asian order. Indeed, one of the first shrines Babur visited when he

arrived victorious in Delhi in 1526 was a tomb of a Chishti pir or shaykh who

was a native of Babur's homeland, the Farghana valley.

As was typical of other Timurids of this era, Babur also brought with him to

India a profound respect for and extensive knowledge of Persian poetry and

historical prose. Two centuries earlier many Delhi sultanate rulers and offi

cials had participated in the Persianate culture that enjoyed such high prestige in Central Asia and India. Ibn Battuta testifies to the welcome that

Iranians received when they arrived in sultanate territories in the early four

teenth century. Yet the late fifteenth century witnessed an especially impor

tant florescence of Persian culture in Timurid Central Asia and Khurasan. Temiir's descendants generally and Sultan Husayn Bayqara of Herat (r. 873 911/ 1469 1506) in particular, patronised Persianate culture to the

degree that Samarqand and Herat became the most important centres of Persian artistic and literary activity in the eastern Islamic world. While Babur wrote both prose and poetry in Turki, the language known in nineteenth century Europe as Chaghatay Turkish, it was Persian rather than

still undeveloped Turki that he revered as the canonical literary tradition. In

his memoirs he always cites Persian language poets when he wishes to use

aphorisms to legitimise observations or actions not specifically connected with

the Islamic morality or piety. That is, while Islam was for him and most of his

followers the categorical religious authority, classical Persian poets such as Sa'di (610 90/1213 91), Rumi (604 72/1207 73), Amir Khusrau Dihlavi (651 726/1253 1325) and Hafiz (720 92/1320 89) provided cultural sanctions

of nearly equal weight.

The conquest of Hindustan

Babur marched out of Kabul in 932 /December 1525 intent on conquering Hindustan. At the time he had already seized Lahore and its wealthy

270

Cambridge Histories Online © Cambridge University Press, 201 1

## India under Mughal rule

hinterland, using some of its funds to secure the loyalty of his allies in northern

Afghanistan as he marched into India's heartland. Babur's victory over the

Afghan Lodis in April represented a Timurid dynastic conquest that was undertaken solely to provide an imperial base for his family and their Chaghatay Mongol kin. Islamic ideology played no discernible part in Babur's initial campaign, and even later when he had to confront formidable

Hindu, Rajput armies he invoked religion only as a tactical device to bolster

morale. Even while Aurungzeb, the last great Mughal emperor (r. 1069 1118/

1658 1707), consciously, sincerely and publicly ruled as a conservative Sunni

monarch, the Mughals and their servants generally adopted a pragmatic, laissezfaire attitude towards religious observance similar in some respects to

policies adopted by the British East India Company during the initial period of

its rule. As for Babur's army, it consisted of a melange of Turco Mongol, Badakhshani and Afghan troops whose total number of actual combatants probably did not exceed 8,000 men. Many of the estimated 12,000 men who

accompanied him and whom he had counted when they crossed the Indus were camp followers: merchants, 'ulamff and others. Babur's victory over the

Lodis at Pampat did not represent the triumph of a gunpowder empire,

although he employed at least two types of firearms in the battle. Based upon his own detailed account, which is also the sole description of the battle.

his success represented the triumph of an experienced and perhaps charis

matic Turco Mongol dynast, a man who fought a traditional cavalry battle using Mongol flanking detachments on a field where his foot soldiers were

arrayed defensively behind carts according to Ottoman military practice.

Following his victory at Pampat, Babur occupied the Lodi capital at Agra and began to consolidate his conquests. His military and political strategy is

evident from his memoirs, but little is known of his administrative policies. In

military terms Babur set about subduing major fortresses in the Agra region,

believing, as he convincingly observes in the VaqffV, that defeating his most.

imposing enemies would trigger a cascade of submissions by lesser figures.

However, even as he began to successfully implement this policy against surviving Afghan commandants in 933 4/152.6 7, he was suddenly confronted

by a far more formidable coalition of Hindu Rajputs, who controlled a broad

swathe of territory stretching in an arc from the south of Agra north west into

the Rajasthan desert. As Rajput forces approached Agra in February 933/1527,

Babur's tenuous sovereignty unravelled almost overnight as recently cowed

Afghans quickly repudiated their submission.

Babur confronted the Rajputs near Sikri, later the site of his grandson Akbar's great sandstone capital, Fatehpur Sikri. In a tumultuous, epic batde

271

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

in which his Mongol flanking cavalry again seems to have played the same key

role it did at Pampat, he was victorious. In the few remaining years of his life,

Babur was never again seriously threatened with defeat, although he con stantly campaigned against both Rajput and Afghan forces in order to con

solidate his fragile hegemony in Hindustan. That hegemony consisted of the

imposition of rule of a Turco Mongol military class over a disparate collection

of Muslim and Hindu rulers, most of whom accepted Timurid legitimacy only

to the degree that superior military force dictated. Babur's descendants rarely

tried to eradicate these indigenous ruling lineages, but only coerced their submission to a regime that needed to extract land revenue to support the

Timurid Mughal ruling elite and their military, religious and cultural camp

followers.

Babur saw himself as a Central Asian founder of an Indo Afghan state, which he far preferred to rule from Kabul rather than Agra. He and many of

his men were appalled by the environment and society of India. In fact, many

of his begs or commanders fled back to the temperate climate of Kabul immediately after their Rajput victory. Babur himself did not have that luxury,

and in his memoirs he recorded his acerbic evaluation of his conquests. Noting, first of all, that the trans Indus region known as Hindustan was a 'strange kingdom ... a different world' where even the rocks were unique, he

went on to indicate that the only thing he liked about Hindustan was its wealth and its seemingly limitless human and material resources. He partic

ularly hated north India's flat, featureless landscape, with its lack of geometri

cally precise gardens bisected by waterways, and despised much of what he

knew of Hindu society. Many of his most provocative critiques are contained

in one brief passage, in which he writes that:

The people of Hindustan have no beauty; they have no convivial society, no

social intercourse, no character or genius, no urbanity, no nobility or chivalry.

In the skilled arts and crafts there is no regularity, proportionality, straightness or rectangularity. 1

Apart from a certain racial prejudice and homesickness for life in Kabul or

Central Asia, two elements in this passage are profoundly meaningful as markers along the social boundaries between Muslim and Hindu societies or at least Babur's perception of the fundamental differences between his preferred Turco Mongol, Perso Islamic society of Central Asia and the society

i Stephen F. Dale, The garden of the eight paradises: Babur and the culture of empire in Central

Asia, Afghanistan and India (1483 1530) (Leiden and Boston, 2004), p. 369.

272

Cambridge Histories Online © Cambridge University Press, 201 1

#### India under Mughal rule

and culture of north India. First of all, by criticising the lack of 'convivial society' and 'social intercourse' Babur remarked on the distinction between

his own society, where social equals regularly gathered together to eat, drink

and recite poetry or to govern, from Hindu caste society, where religious pollution rules prevented the kind of interaction that was common in most

Mediterranean and Middle Eastern communities. Second, in criticising the

lack of 'regularity, proportionality, straightness or rectangularity' in Indian

arts and crafts, Babur signalled his own membership in a Greco Islamic culture

that valued geometrical symmetry and, in the case of such Greco Islamic

philosophers as al Birum (363 c. 442/973 1050), regarded Aristotle's logic,

whose reasoning was exemplified by geometrical axioms and theorems, as

the foundation of a truly scientific civilisation.

Despite Babur's distaste for the culture of his newly conquered territories,

he remained in India until his death in 937/December 1530. While almost nothing is known of his administration, it is clear from his memoirs that he

governed Hindustan through a fairly standard type of early modern Islamic

military feudalism. He retained some territories in India as khalisa, demesne

or crown land that supplied income directly to the regime in Agra. Other territories were parcelled out to his begs or amirs as military fiefs to support

themselves and the troops under their command. These fiefs seem to have

been similar to those he knew as tiyul in Afghanistan and Central Asia, that

is, temporary and revocable grants similar to the iqtd c s common to pre Mughal India, Iran and other regions of the Middle East. Such assignments

were the precursors of the elaborate system which his grandson, Akbar, established in the late sixteenth century to support the military class. The major difference between the two systems was that in his grandson's era assignments were usually based on geometric surveys and knowledge of local soil conditions. The quality of Lodi revenue records is not known, but

it is important to understand that Babur himself was familiar with complex

commercial and agrarian revenue systems from reading the Hidaya text of

al Marghmani.

The apparent reason why so litde is known about the details of Babur's administration in India is that the first period of Mughal rule lasted only until

1540, when resurgent Afghan forces drove his son and heir, Humayun, from

India. Led by Shir Shah Suri, Afghans reasserted control over north India,

establishing a sophisticated revenue system and road network that were probably a continuation of Babur's and Humayun's policies. Humayun's difficulties were partly due to the the Turco Mongol appanage system, in which his brothers competed for regional power or outright sovereignty in the

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

Indian heartland. What can never be known is the degree to which his own

military skills were responsible for his loss to Afghan forces, some of whom he

had defeated earlier in his reign. Between 947/1540 and 962/1555 Humayun

was first a wandering refugee in the Indian Afghan borderlands and then a

guest of the Safavid Shah Tahmasp. He apparently purchased Tahmasp's cooperation with lavish presents of jewels that may have included the famous

huh i nur diamond, and a possible promise of conversion to Shi'i Islam. In this

he may have reprised an alliance that Babur had concluded with Tahmasp's

father, the Safavid founder, Shah Isma'il, when in 917/1511 Babur needed

Safavid military aid to retake Samarqand for the third and last time from his

Uzbek enemies. Using Safavid troops Humayun appeared outside Kandahar in

952/1545 to begin the decade long process of reclaiming his patrimony, first

from his recalcitrant brothers in Afghanistan and then from the Suns them

selves. However, Humayun survived only a year in India before accidentally

dying in an accident, tripping on the steep stone steps of his library and possibly fracturing his skull as he hurried to evening prayers.

#### Akbar and the formation of empire

Humayun' s young son Akbar succeeded to the Mughal throne in 963/1556 in

his twelfth year. Initially it was his guardian or tutor, the Qara Qoyunlu Turk Bayram Khan, who directed the affairs of the resuscitated Mughal state during

the first four years of Akbar's rule. Only in 1560 did Akbar, then no longer a

child but an assertive adolescent, dismiss Bayram Khan, presaging his emer

gence as the effective ruler of the state a year later. During the period of Bayram Khan's de facto regency and the early years of Akbar's direct rule up to

975/1567, Mughal armies were preoccupied with recapturing the central core

of territory held by Babur at the time of his death in 937/1530. This comprised

Lahore and much of the Punjab, the Delhi Agra axis and Gwalior to the south,

the western and central Gangetic valley and eastern Rajasthan. Just as Babur

had first fought the Lodis, his descendant began by attacking the formidable

remnants of the Afghan Suri coalition that had retreated down the Ganges

valley following Humayun' s victory. Akbar defeated the last major Suri leader

near Jawnpur in 968/1561, although Afghan resistance continued in eastern

India for many years. Afterwards, Akbar, like Babur before him, secured his

eastern flank with campaigns in 974/1567 and 976/1569 against Chitor and

Ranthambor, the two most formidable Rajput fortresses. These latter cam paigns illustrate that by the mid sixteenth century the Mughal dynasty had

indeed become a gunpowder empire to the extent that Akbar defeated his

274

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

Rajput opponents by besieging their stone fortresses with cannons and sap

ping the walls with mines. 2

In between these Afghan and Rajput campaigns Akbar was preoccupied with dissent and sometimes open rebellion within his own nobility and by competition from his two most legitimate and therefore formidable rivals. It

was especially Uzbek members of his military coalition who revolted in the

mid 1560s, but whatever the motivations of specific individuals, this kind of

activity was a common feature of Timurid and early Mughal history. However, unless they were actual descendants of the Chinggisid founder of

Uzbek power, Shibani Khan, Uzbek nobles were less of a threat to Akbar's

long term prospects than were the challenges posed by Timurids, who pos

sessed legitimacy as valid as Akbar's own. These were his half brother Mirza

Hakim, long the governor of Kabul, and the Timurid Muhammad Sultan Mirza, a grand nephew of Sultan Husayn Bayqara (d. 911/1506), the last Timurid ruler of Herat. The assumption of shared inheritance and the Turco Mongol appanage system lay behind these men's activities, depicted

in Mughal sources as rebellions. Muhammad Sultan Mirza had fought along

side Babur, but he often challenged Humayun's sovereign claims. Along with

Humayun's brothers and another Timurid, Muhammad Zaman Mirza, he had

contributed to Humayun's defeats and expulsion from India. In 974/1566, however, Akbar defeated Muhammad Sultan Mirza after a campaign in which

he drove the Mirza Hakim back to Kabul, following the latter's invasion of the

Punjab.

Akbar enjoys an almost unreservedly positive image in the historiography of India, whether or not written by Muslims, Hindus or Westerners. This is

due to a number of factors, but most of all to his military success, political

skills, administrative acumen, spiritual experiments and liberal religious pol

icies. He is, first of all, acknowledged to have been an exceptionally effective

military leader, one who rarely suffered a serious defeat as he went about

re establishing and then enlarging the Mughal empire. During his long reign

he never ceased campaigning, as he steadily expanded the circumference of

Mughal power outward from its Delhi Agra node in all directions until his small north Indian state became the Mughal empire of legend. Second, in political and administrative terms Akbar was, first of all, an effective monarch

because he ruled himself, and not through viziers or other intermediaries as

became the enervating practice in the Ottoman and Safavid empires. Personal

2 For an introduction to Mughal administrative and political history from Akbar's reign to

the collapse of the empire see John F. Richards, Tfie Mughal empire (Cambridge, 1993).

275

Cambridge Histories Online © Cambridge University Press, 201 1

#### The New Cambridge History of Islam

rule was the custom of Akbar's successors as well. He also effectively inte grated non Muslim groups into the elite ranks of the empire and either created

or at least formalised the basic administrative structures of the regime

endured in one form or another until its collapse in the eighteenth century.

Third, Akbar's inquisitive mind, eclectic religious interests and patronage of

both Islamic and non Muslim Indian culture have not only appealed to scholars who write India's history, but also seem to have engaged the sympathy of contemporary Hindus as well.

Akbar personally commanded the Mughal armies throughout most of his reign; he was still on campaign in 1011/1602, when his son Salim, the future

Jahangir, rebelled against his father's authority in the traditional Turco Mongol manner. After his early campaigns against Suri forces in the eastern Ganges region and successful assaults on the two major Rajput fortresses,

Akbar conquered the wealthy province of Gujarat with its pivotal seaport of

Surat in 980/1572. Subsequently he and then later his generals, including his

Hindu finance minister, Todar Mai, commanded a series of difficult cam paigns against Afghan forces in Bihar and Bengal in the 1570s and 1580s. In one

of these campaigns in 987/1579 Akbar fought against a particularly dangerous

coalition of Afghans, who had allied themselves with Mughal rebels. The coalition challenged Akbar's legitimacy, and orthodox l ulamd\ who objected

to Akbar's religious experiments, sanctified these men's actions. The Mughal

nobles involved also arranged to have Mirza Hakim (d. 993/1585) proclaimed

emperor, whom Akbar now finally deposed as ruler of Kabul after a rapid march to the Afghan capital. The eastern provinces were then gradually pacified in a series of hard fought battles by the late 1580s, when Akbar sent

one of his premier Rajput allies, Man Singh, to administer them. Finally, in the

1590s Akbar turned his attention to the Muslim sultanates of the Deccan. He first demanded their submission in 999/1591, and then attacked the Ahmednagar sultanate in 1003/1595. After a successful siege in 1599, he integrated Ahmednagar into the empire. No less than Babur, Akbar and his

successors possessed inbred, that is Timurid and Chinggisid, 'kingdom seizing

ambitions'.

As the evidence of some of his early campaigns demonstrate, Akbar co opted important Hindu lineages into his regime early in his reign. Todar Mai,

for example, his famous finance minister who also commanded Mughal armies in the east, was a Punjabi Khatri. The Khatris were and are one of the most important north Indian commercial castes, whose members were

concentrated in the Punjab and settled as a mercantile diaspora in Afghanistan,

Iran, Central Asia and, by the mid seventeenth century, even in Moscow.

# India under Mughal rule

Todar Mai provided the regime with financial expertise, just as many Mughal

nobles relied on Hindu advisers to manage their private investments. Man

Singh, the other highly visible Hindu general in Akbar's campaigns, was a

Rajput, and his role reflected the critical military service that these formidable

Hindu chiefs provided to the empire. Rulers of earlier north Indian Muslim

states had previously employed Hindus. Indeed, the fourteenth century his

torian Zia ] al Din Baram complained bitterly in his work Fatdwa yijahdnddri,

that the Delhi sultanate could hardly be considered a Muslim state at all, for

Hindus were so prominent and the sultans acted more like pre Islamic Iranian

emperors than committed Muslims. Akbar liberalised and systematised the

use of Rajput lineages, appointing defeated or intimidated rajas to high ranks

in the Mughal nobility, while also allowing them to retain their historic estates.

The degree to which Akbar co opted Rajput lineages and his appreciation of

their military importance is reflected in the enumeration of Rajput clans that

Abu ] l Fadl Allami, his amanuensis and companion, provided in the A'ln i Akbari, his gazetteer of the Mughal empire that he finished in the late sixteenth

century:

I record the names of a few of the most renowned [Rajputs] that are now in

His Majesty's service, i. The Rathor; there are several tribes of this clan in

service. They number sixty thousand cavalry and two hundred thousand infantry. 2. The Chauhan are divided into several branches, viz., Sungira, Khichi, Deora, Hada, and Narban. The troops of the clan number fifty thousand cavalry and two hundred thousand infantry. 3. The Panwar. In

ancient times, of this tribe was the royal dynasty in Hindustan, and it numbered many clansmen. At the present time their force consists of twelve

thousand cavalry and sixty thousand foot. 3

While these troop figures are probably, like so many such estimates, exagger

ated, the passage simultaneously conveys Mughal respect for these ancient

Hindu lineages and publicises the power of Akbar's empire. It also illustrates

how vitally important these Rajput lineages were for the Mughal state.

Akbar's intimate involvement with the Rajputs had begun when he returned from a pilgrimage to the Chishti Sufi shaykh at Sikri, west of Agra,

in 969/1561. He accepted the offer of marriage to a Rajput princess, whose

father wanted imperial assistance against a local Mughal governor. He mar

ried the girl in Agra. Not only was she allowed to retain her own religion, but

3 Abu'l Fadl 'Allami, A'ln i Akbari, trans. Colonel H. S. Jarrett, ed. Sirjadunath Sarkar (New Delhi, repr. 1988), vol. Ill, p. 131.

\*77

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

also other Rajput princesses who were later brought into the harem were allowed to erect temple structures for their own devotions. Simultaneously

with this first marriage Akbar enrolled the Rajput father, his son and grandson

in Mughal service, presaging the future recruitment of the princely heads of

important Rajput lineages. The influence of Akbar's new Hindu wife and in laws may have led him two years later to abolish the pilgrimage tax levied

on Hindus and subsequently to issue other regulations that allowed Hindus to

repair their temples and forbade the forced conversion of non Muslim captives.

Later Akbar enlisted the princely heads of major Rajput lineages named above in the imperial service, where they were not only given ranks equal to

Muslim officers, but, in fact, were accorded special status. That is, unlike most

imperial officers whose assignments to military fiefs were changed periodi

cally, Rajput officers were allowed to retain their historic family territories as

their permanent fiefs. This policy essentially recognised the entrenched power

of these Rajput lineages and their military value to the Mughal empire. It would have been prohibitively expensive to eradicate these families and

hundreds of other well entrenched Hindu rajas. The survival and indeed the

prosperity of the Rajput kingdoms is only the most prominent example of

phenomenon that explains why, when Mughal centralised power decayed in

the early eighteenth century, its authority and presence could evaporate overnight in many areas, often leaving behind as the imperial tide receded

only the architectural remnants of a great empire.

By 987/1580 Akbar had appointed nearly forty Rajputs to commands within

the imperial forces, whose economic basis of agrarian fiefs was fundamental to

the success of the empire. The basic organisation was a decimal one that reflected the Mughals Turco Mongol heritage. Chinggis Khan, his descend

ants, Temiir and the Timurids, including Babur, divided up their predom inantly cavalry forces into commands of 10, 100, 1,000 10,000, etc. Babur and

Humayun, and initially Akbar also, commanded semi autonomous begs or amirs, to whom they assigned large parcels of villages and agricultural land to

support both their families and the troops under their command. In this early

Mughal period such commanders constituted more of a military coalition than

a centrally controlled army. However, as Akbar gradually extended his control

over the Indian heartland he developed a sophisticated military feudal struc

ture known as the mansabdari jdgirdari system that was formally instituted in

982/i574f In essence each commander of 100, 500, 1,000, 5,000, etc. was assigned a mansab, a rank, which he ddr, held. At the same time nearly every

commander was paid, not in cash, but through an assignment of agricultural

278

Cambridge Histories Online © Cambridge University Press, 201 1

### India under Mughal rule

land known as a jagir, which he also held from the emperor. Most Muslim officers of varying ethnic identities were treated as imperial servants who were not allowed to own land, but only to hold jdgirs temporarily, before being moved at intervals to other assignments, as a way of preventing them

from becoming an entrenched class of regional feudatories. Rajput officers

were also both mansabddrs and jdgirddrs, but as a sign of their special military

status they held their own small kingdoms as watan or homeland jdgirs. Some

were also granted temporary but lucrative assignments outside their historic

territories, thus helping to ensure their loyalty and prevent inter Rajput warfare.

While the mansabddri jdgirddri system served the empire well enough for

more than a century to provide the heavy cavalry core of the imperial armies,

it did not automatically function as the Mughal equivalent of a deist clock,

sprung perfectly operating from the mind of Akbar and remaining functionally

unchanged thereafter. Like any complex administrative system it was subject

to the influence of personal ambition, family ties, political faction and local

interests. In fact almost immediately after he formally initiated the system

Akbar had to adjust it to conform to the realities of the mansabddrs' ambitions

and acquisitive instincts. Among other problems, mansabddrs only rarely kept

up their specified troop levels, a fact that Abu'l Fadl acknowledged when he

noted that 'The monthly grants made to the Mansabdars vary according to the

condition of their contingents.' 4 Abu ] l Fadl's orthodox critic and jealous competitor, Abd al Qadir b. Muluk Shah, known as al Badaum, went further

and wrote scathingly of the mansabddrs that:

As they were wicked and rebellious, and spent large sums on their stores and

workshops, and amassed wealth, they had no leisure to look after their troops

or to take an interest in the people. In cases of emergency, they came themselves with some of their slaves and Moghul attendants to the scene of

war; but of really useful soldiers there were none. 5

A system of branding, troop musters and formal military reviews was devised to ensure minimum compliance with the system. Akbar's son and successor, Jahangir, describes one such review, which took place on 4 April

1618, albeit in this case for his father in law, who was also one of his most

important ministers:

4 Ibid., p. 248.

5 al Badaunl, Muntakhabu 't Tawarikh by 'Abdu I Qadir Ibn i Muluk Shah known as Al

BaddonT, ed. and trans. W. H. Lowe, rev. B. P. Ambashthya (Patna, repr. 1973), vol. II,

P- 193-

279

## The New Cambridge History of Islam

On the twenty fifth [4 April], rtimad ud dawla's troop passed for review in the

field beneath the jharoka [audience window]. There were two thousand fine

horsemen, mostly Moghuls [Mongols], five hundred foot soldiers armed with

bows and guns, and fourteen elephants. The bakhshis [military accountants]

counted them and reported that the troop was fully equipped and appeared to

be formed according to regulation.

According to al Badauni, however, if anything the abuses during Akbar's reign grew steadily worse, observing: 'But notwithstanding this new regula

tion . . . the Amirs did as they pleased.' 7 Al Badauni undoubtedly identified real

problems, but he was so angry and biased his description cannot be assumed

to be based on a comprehensive knowledge of all mansabddrs and, indeed, may

refer to a specific campaign. If the entire system was as corrupt as he suggests,

Akbar could have scarcely remained in power, much less conquered a great

empire. In fact, many of these officers and their descendants, including Rajputs, are known to have loyally served the Timurid house with distinction

and sometimes even sacrificial devotion. However flawed in practice, the system could still produce tens of thousands of troops for campaigns in the

early eighteenth century. It is reasonable to suppose but impossible to prove

that the abuses Badauni describes varied directly with the mansabddrs' geo

graphic distance from Agra, where contingents of the great nobles of the courts could be evaluated with relative ease.

The mansabdafi jdgirddn system generated, by necessity, a large bureauc racy to survey and register lands that became part of the pool for assignments.

These officials represented only one dimension of a complex administrative

system that also included a bifurcated provincial administration of governor

ships and financial officials established after 979/1572. Thus at the level of the

individual province two different officials, both appointed by the emperor,

were responsible for political and military control and financial administra

tion. Governors controlled administrative and military affairs while provincial

diwans or revenue officers drew revenues directly from khalisa or crown lands

for the central administration. The relations among mansabddr jdgirddrs, the

subahddrs or governors and diwans varied with each individual instance. Despite the theoretical rotation of jagirdars around the empire and the division

of political and financial powers, sometimes mansabddrs might be repeatedly

appointed to the same province, or relatives or clients of powerful individuals

6 Jahangir, The Jahangirnama: Memoirs ofjahangir, emperor of India, ed. and trans. Wheeler

M. Thackston (Washington, DC, 1999), p. 219.

7 al Badauni, Muntakhabu 't Tawdrikh, vol. II, p. 193.

8 Richards, The Mughal empire, pp. 107 9.

280

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

might be appointed to the same province and on occasions one man might

simultaneously hold both political and financial posts. An additional compli

eating factor was the presence of varying numbers of entrenched, semi independent lineages or autonomous rajas designated by the Mughals as

zamindars, that is, holders of zamin or land. A map of the administrative and

political situation in any particular Mughal province might reveal a patchwork

of crown, jdgir and zamindar territory, sometimes with zamindars located within a mansabdar'sjagir. The interconnected political and financial authority

of its governors, financial administrators and mansabdar jagirdars constantly

shifted according to the personalities of individual officials, the dynamism of

the imperial government and the ambitions of zamindars.

Akbar: religion and culture

If Akbar's success as a ruler can be attributed to his military leadership, recruitment of local elites and the possession of a systemising intelligence

that led him to construct an effective administration, his later reputation among the Indian public and both Indian and foreign intellectuals stems in

large measure from his intellectual curiosity and religious experiments. Like

his father and grandfather before him, Akbar exhibited a strong attachment to

Sufi devotionalism. He showed a particular preference for the Chishti order

Even though like the Naqshbandi it originated in Central Asia, the Chishtiyya

was a well established order in Hindustan before Babur's invasion, with major

shrines in Delhi, Ajmir and Sikri, near Agra, and in the Ganges valley. From

the 1570s on Akbar seems to have been increasingly absorbed in pantheistic

Sufi doctrines that evolved into a profound belief in the essential oneness of all

religions. Nonetheless, an attachment to Sufism hardly seems a sufficient explanation for the evolution of Akbar's religious interests and state policies

from an unremarkable Islamic piety in the early years of his reign to increas

ingly latitudinarian beliefs and, in the opinion of some Muslims, heretical religious experiments. The possible factors that may have contributed to this

change include his own, well documented intellectual curiosity, a seemingly

restless intelligence reminiscent of his grandfather, the influence of his Rajput

marriages and incorporation of Rajput princes into the regime, his exposure to

Christian ideas following his conquest of Gujarat and contact with the Portuguese on the Indian Ocean coast, the very likely influence of Buddhist

or Jain ideas of non violence prevalent in the same region, his knowledge of

Zoroastrian doctrine and, finally, a possible desire to define his sovereignty in

Iranian imperial rather than just Timurid and Islamic terms. The most

281

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

intractable problem in this regard is the difficulty, the impossibility really, of

accurately determining how Akbar's personal religiosity influenced state policy and vice versa.

Lacking a religious autobiography of the order of Gandhi's work The Story

of My Experiments with Truth, it is only possible to point to several events or

periods that date and document Akbar's religious policies or interests. First is

his initial Rajput marriage, followed so shortly by the abolition of the Hindu

pilgrimage tax and other measures that seem to reflect a growing sensitivity to

his Rajput allies. These include the well known elimination of the jizya, the so

called poll tax on non Muslims that Akbar's historian, Abu'l Fadl, claims was

done in 1564, but may not have been formally implemented until fifteen years

later. Second, Akbar attributed the birth of his first son Salim, later the emperor Jahangir, in 1569 to the prayers of Shaykh Salim Chishti at Sikri in

Rajasthan. This intensified Akbar's devotion to an order and a shrine in nearby

Ajmir that he visited for five consecutive years between 971/1564 and 977/1569. Third, the presence of the Chishti shrine and the residence of Salim Chishti at Sikri was probably one reason why Akbar constructed a new capital at Sikri in 978 / 1571, halfway between Ajmir and Agra. However, it

is also worth recalling that Babur won his great battle against the Rajputs

nearby in 933/1527, where he also later built a Garden of Victory to commem

orate the epic battle. Akbar may have taken the name for his new city, Fatehpur, the 'city of victory', from this event. Fourth, this new capital of Fatehpur Sikri became, in 1575, the site of the famous religious debates that

Akbar sponsored, initially between Muslims and later involving Jains, Zoroastrians and, finally, in 1580, some Christians. Fifth, it was also during

this period that Akbar had an epiphany that seems like a distant but indistinct

echo of the conversion to Buddhism of the great Mauryan emperor, Ashoka

(273 232 BCE), one perhaps influenced by Akbar's contact with Jains in the

Sikri religious debates. In Ashoka's case the slaughter of thousands of enemies

in Orissa prompted him to embrace non violence and the ethical code of Gautama Siddhartha's Indian disciples. Akbar reacted to the slaughter of thousands of animals during a typical Central Asian style royal hunt in 1578

by prohibiting the killing of animals on certain days and by adopting a modified form of vegetarianism.

Finally, during the same period Akbar instituted measures that first of all, in

987/1579, proclaimed his authority to be the final arbiter in Islamic religious

matters. He apparently asserted this right oiijtihdd or interpretation of Muslim

law after becoming disenchanted with the sterile, intolerant religious debates

among Muslim clerics at Fatehpur Sikri. In the decree announcing this

282

# India under Mughal rule

decision, Akbar was described as the imam i 'adl or the just imam, a Shi c

title but perhaps also an echo of the concept of insan i kamil, the perfectly

enlightened Sufi. At the same time his principal religious ideologue at court,

Shaykh Mubarak, the author of this document, suggested that Akbar embod

ied the farr, the divine light of kingship known from pre Islamic Iran. Then

two years after making these religious claims that shocked and alienated some members of the 'ulamff and helped to legitimise the combined Afghan Mughal rebellion in 1579, Akbar initiated a royal cult known as the

din i ildhi or tauhid i ilahi, literally 'the faith of God', or 'the divine unity', in

which he enrolled a small number of disciples who pledged to him an absolute devotion reminiscent also of Sufi disciples' unconditional commit

ment to their spiritual masters.

It was especially Akbar's implied claims to spiritual authority that con vinced al Badaum, the disaffected courtier and religious critic of Akbar's reign,

to consider Akbar an apostate. Even some Rajputs, it might be noted, thought

that Akbar's innovations were quite odd and refused to participate. Reacting

to the controversy over Akbar's religious inclinations and court cult, Abu'l

Fadl repeatedly defended his master's practices, remarking in one passage that

also revealed how infrequently Akbar visited major Friday mosques, such as

the one he had built at Fatehpur Sikri:

Ardently feeling after God, and searching for truth, His Majesty exercises upon himself both inward and outward austerities, though he occasionally

joins public worship, in order to hush the slandering tongues of bigots of the

age. But the great object of his life is the acquisition of that sound morality,

the sublime loftiness of which captivates the hearts of thinking sages, and

silences the taunts of zealots and sectarians. 9

Continuing on to discuss Akbar's known reverence for the sun, which might have been connected with his regard for Zoroastrian ideas and Hindu

fire sacrifices, Abu'l Fadl first convincingly remarks that Akbar 'passed every

moment of his life in self examination or in adoration of God'. He continues,

saying that the emperor 'especially does so at the time, when morning spreads

her azure silk, and scatters abroad her young golden beams, and at noon when

the light of the world illuminating sun embraces'. And why not, Abu'l Fadl continues. After all:

It is incumbent upon us, though our strength may fail, to show gratitude for

the blessings we receive from the sun, the light of all lights ... This is

9 Abu'l Fadl 'Allami, A'ln i Akbaii, vol. I, p. 163. 283

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

essentially the duty of kings, upon whom  $\ldots$  the sovereign of heaven sheds an

immediate light. And this is the very motive, which actuates his Majesty to

venerate fire and reverence lamps. 10

Akbar's personal religious experiments and imperial cult had no perceptible

legacy in the Mughal court of his descendants. In retrospect they seem to be

quixotic manifestations of his restless intellect and heartfelt spiritual quests.

When it came to Mughal court culture, however, Akbar's policies were as formative and substantial as his administrative innovations. It was Akbar, first.

who formally instituted Persian as the official language of the court, thereby

turning away from Babur's Chaghatay Turkic heritage and embracing Persian

as the high court and literary culture of Mughal India. He also actively recruited Persian speaking literati, thus encouraging Iranians increasingly to

leave the relatively impoverished Safavid state to enjoy the patronage of the

stunningly wealthy Mughal empire. After Bayram Khan wrote his diwan, or

collected verse, in Turki, almost no texts were composed in that language in

Mughal India. Akbar's son Jahangir claimed to know Turki, but his claim, even if true, has the air of an exceptional, self conscious achievement. Indeed,

in the seventeenth century scholars had to compile Persian Turki glossaries to

explain the now obscure Central Asian vocabulary. Persian was the language

of all the great histories written during Akbar's reign, the Persian verse of Sa'di

and Hafiz continued to be valued as the classical literary canon, as indeed it had

been by Babur, and both Iranian emigres and Indians composed Persian verse

in the late Timurid style known as sdbk i hindi. Iranian influence was also noticeable in other spheres at this time. Akbar adopted the Iranian or Zoroastrian solar calendar for administrative reasons, and Iranian ideas of

kingship, widely known for centuries if not millennia among Persian speaking

literati and military throughout Central Asia and India, were absorbed by the

Mughal dynasty.

Apart from Persian, the focus of Akbar's patronage is both suggestive of his

self image and intellectually engaging as a complex fusion of Perso Islamic.

Indian and European elements. Akbar was as influential in patronising archi

tecture, literature, music and painting as he was in shaping the Mughal administrative and military systems. He was a great systemiser in every respect, echoing in highly practical ways the systemising intelligence that

Babur displays in his memoirs. The nature and scope of his patronage offer

compelling implicit evidence that he saw himself as the architect of a great

io Ibid.

284

Cambridge Histories Online © Cambridge University Press, 201 1

# India under Mughal rule

empire. Akbar visibly manifested Mughal grandeur, or, more accurately, his

own grandiose ambitions, for the first time in 968/1562 when he ordered the

construction of a monumental tomb for Humayun. Completed eight years later in 1570 and combining both Timurid and Hindu design elements, it dwarfed Temiir's tomb in Samarqand. A year later he began construction of

the massive new city Fatehpur Sikri, whose red sandstone buildings echoed

the design of Muslim wooden buildings in Gujarat. Fatehpur Sikri remained

his capital until he moved to Lahore in 993/1585.

In the last two decades of the sixteenth century Akbar systematically set about creating a historical memory of the now imposing Timurid renaissance

that Babur had consciously recorded in the 1520s. He explicitly linked himself

to his Timurid past in several ways. Not only did he commission several illustrated manuscript versions of Babur's Vaqa'f and a history of Temiir himself, the Temiir noma, but he decreed that anyone who had personal knowledge of Babur and Humayun should record their recollections, and from his order came the second major autobiographical work of the dynasty.

This was the Persian language memoir of Babur's daughter Gulbadan Begim,

a detailed and often touching evocation of a Timurid woman's world and of

the author's humanity. Just as Babur's autobiography is a unique work by a

founder of an Islamic empire of any period so his daughter's memoir is

equally remarkable for offering an aristocratic woman's account of her life.

No comparable text exists for any princess or concubine of the Ottoman or

Safavid regimes at any period in their history. Akbar himself seems to have

been at best only semi literate, some think dyslexic, and so he did not write an

autobiographical account of his long reign. Therefore he enlisted his companion and courtier, Abu ] l Fadl c Allami to commemorate his achievement in

two great historical and statistical works. These were the narrative history of

his reign, the Akbar nama and the massive gazetteer of the empire, the A  $\ensuremath{c}$  In i

Akbafi.

If Akbar had been merely preoccupied with his legitimacy and imperial grandeur he would be a far less interesting man, but he had a passionate interest in music and painting in addition to his lifelong spiritual search. In

969/1562, the same year that he began Humayun's tomb, he forced the most

renowned singer musician of his day, Miyan Tansen, to leave the court of his

Rajput patron and join Akbar where he remained until his death in 994/1586.

Tansen was a Hindu and his music was based in the raga tradition of classical

Indian music. He was especially known for his mastery of the Drupad form of

singing, a classical court genre rendered in local languages and/ or Sanskrit and

associated especially with the Rajput court of Gwalior, located south of Agra.

285

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Nonetheless like the great Persian language poet and musician of the thir

teenth and early fourteenth centuries, Amir Khusrau Dihlavi, he was one who

evidently moved in a world of both Hindu and Muslim devotionalism, that is

bhaktl and Sufism, and he may have been a disciple of the renowned sixteenth

century Sufi, Muhammad Ghaus Gwaliori. Yet Tansen was only the most prominent of the musicians who performed at Akbar's court, many of whom

were Muslims from Iran and Central Asia.

The eclectic musical atmosphere at the court was visibly echoed in the massive output of Persian style miniature paintings, most of them done to illustrate literary or historical texts. This art form was based initially on the

expertise of two Persian artists, Mir Sayyid All and 'Abd al Samad, men whom Humayun had brought to India in 962/1555 after his enforced exile.

They initially supervised the production of such works as the eclectic Tuti noma (the Tales of the Parrot) and the fourteen volume Hamza noma, completed

between 969/1562 and 985/1577 with 100 illustrations per volume, an under

taking so enormous that no other illustrated texts are known to have been

produced in these years. Even these early works illustrate how quickly Mughal miniature painting departed from the restrictive, stylised confines of

Iranian aesthetics, and integrated Hindu techniques into this all important

court art form. Later, Mughal artists and architects experimented with European stylistic influences, derived from their examinations of paintings

first introduced by Jesuits from Goa. 11 Not only did biblical scenes now occasionally emerge from the Mughal atelier, but miniature paintings some

times also exhibited Renaissance perspective and the shading technique known as chiaroscuro.

Most of the well known later productions of Akbar's well organised studio were done after he moved to Lahore in 1585. These included Babur's memoirs,

the Tarlkh i alfl, the history of Islam's first millennium, the Akbar nama itself, a

Hindu text, the Harivamsa and a number of illustrated manuscripts of classical

Persian verse, a reminder of Mughal India's dominant Persian literary culture.

Single artists usually did these later works, in which the verse was rendered in

beautifully rendered nasta'liq calligraphy, itself a major art form at the Mughal

court throughout its history. The most elegant of these texts were the illustrated editions of the works of renowned Persian language poets such as

the Khamsa of Nizami and the Khamsa of Amir Khusrau Dihlavi. One of the

11 Ebba Koch, 'The baluster column: A European motif in Mughal architecture and its

meaning', in Monica Juneja (ed.), Architecture in medieval India: Forms, contexts, histories (Delhi, 2001), pp. 328 51.

286

Cambridge Histories Online © Cambridge University Press, 201 1

#### India under Mughal rule

most engaging features of the mature style of Akbari paintings is the preva

lence of a naturalism in portraying both animals and birds as well as people, a

characteristic that contrasted strongly with the stereotypical art that predomi

nated in both traditional Hindu painting and also Persian miniature art of Safavid Iran. Even when they rendered busy court scenes, Mughal artists painted recognisable individuals in distinct costumes.

Economy and trade in 1009/1600

Akbar's construction of Humayun's tomb and Fatehpur Sikri and his lavish

patronage of artists and musicians hint at the acquisition of wealth that by the

late sixteenth century distinguished the Mughal empire from its Ottoman and

Safavid contemporaries. By the end of his life Akbar had subdued a territory

that may have included more than 100 million people, nearly comparable to

the population of Ming China, the only contemporary state that rivalled Mughal India in territory, population and wealth. At about the same time the populations of the Ottoman and Safavid states comprised an estimated 22

and 10 million people respectively, while Uzbek territories probably held no

more than 5 million. The lavish wealth that many European observers remarked on when they visited the Mughal court was derived from two principal sources, the agricultural tax and a foreign trade surplus. Mughal

India, like most pre industrial states, was in socio economic terms an over

whelmingly agrarian society. It depended for the bulk of its income on the

effective extraction of wealth from the countryside. The social structure of

Mughal controlled rural society varied tremendously from region to region.

In some cases the land was controlled and farmed by landholding peasant

castes such as the Jats, whose extensive corporate lineages were especially

numerous, cohesive and even militarily formidable in the Delhi Agra region

and in the Punjab. In other cases ruling clans or extended family lineages that

the Mughals uniformly classed as zamindars controlled whole districts' worth

of villages.

Yet whether Mughal officials collected agricultural taxes directly from cultivators or from zamindars, they may have taken as much as one third to

two fifths of the produce, an amount consistent, so far as it is possible to estimate, with pre Mughal revenue demands. The precise percentage of Mughal land revenue collections is, however, not documented and remains

a source of dispute. However, what distinguished Mughal agrarian policy was

the regime's thorough study of agrarian conditions, including crop yields, price data and land measurement surveys. Abu'l Fadl gives the state's idealised

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

view of the agrarian taxation system, a balance of imperial and agrarian interests, in the A'in i Akbari, where he describes the duties of the revenue

collector as one who:

Should be a friend of the agriculturalist . . . He should consider himself the

representative of the lord paramount  $\dots$  He should assist the needy husband

man with advances of money and recover them gradually . . . He should ascertain the extent of the soil in cultivation and weigh each several portion  ${\bf r}$ 

in the scales of personal observation and be acquainted with its quality. The

agricultural value of the land varies in different districts and certain soils are

adapted to certain crops. He should deal differently with each agriculturalist

and take his case into consideration. 12

Part of this official's duties was to see that the cultivator brought wasteland

under cultivation, thereby increasing the revenue of the empire.

Precise land measurement was hardly a novelty in the history of Muslim agrarian policy; careful geometric land surveys, for example, were practised

during the period of the 'Abbasid caliphate (132 656/750 1258). Babur himself

was familiar with agrarian revenue based upon field surveys. However, the

Mughal system was distinguished by its officers' detailed local knowledge of

agrarian conditions in the wealthy north Indian heartland and beginning around 988/1580 Akbar's Khatri revenue minister and sometime general, Todar Mai, resumed all the mansabdars' jtigvr holdings and, based upon these

data, gradually reassigned them five years later. By this time the Mughal

treasury demanded its collections in cash, which was paid in either copper or

silver coinage. The increasingly monetised Mughal economy saw enormous

funds flow into the Mughal treasury from demesne or khalisa lands and stable

income fund the jagirddrs' troop contingents. From the 1580s to the end of

Aurungzeb's reign in 1118/1707 the amount of land surveyed rose by nearly

50 per cent, even though Kabul, Sind, Bengal and Orissa were never included

in this system. Apart from the Punjab, the Ganges Yamuna Duab and the central Gangetic valley, where treasury officials steadily increased the amount

of land surveyed, most of the new territories included were in the northern

Deccan, although this did not begin to occur until a half century after Akbar's death.

The breadth and thoroughness of the Mughal revenue settlement in Hindustan had a number of unquantifiable implications for the nature of the

Mughal state. These include the enormous drain of wealth from the

12 Abu'l Fadl 'Allami, A'ln i Akbari, vol. II, p. 46.

288

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

peasantry, the enrichment of the Timirids and the Mughal service class, the

increased demand for luxury and craft products to serve these officers' acquisitive instincts, and the increased size and prosperity of towns and cities

such as Agra, whose population may have reached three quarters of a million

people in the mid seventeenth century, at least when the court was in

residence. Not the least of these questions for its historical significance is the

relatively high degree of centralised control that Mughal emperors exercised

in the north Indian heartland.

Apart from their ability to extract revenue by fiat from the Indian peasantry

in these regions, the Mughals' level of control is partly also indicated by the

standardisation, purity and stable value of coinage throughout the empire. Just

as Akbar regularised so many other aspects of Mughal administration so he

standardised coinage. From the late 1570s on, coins of equal value and identical

design were issued from mints from Gujarat to Lahore, from Bengal to Fatehpur Sikri, and the Mughals enforced an order that all precious metals

entering their territories be recast at mints into Mughal coins. Both Akbar and

his son, Jahangir, also personally saw to their coins' aesthetic appeal. Akbar,

who appointed as mint master c Abd al Samad, the Iranian calligrapher and

painter who oversaw the royal atelier, and Jahangir, whose artistic interests

often seem to have taken precedence over governance, each supervised the

production of coins. In purity, aesthetic standards and precision of design Akbar and Jahangir's issues were superior to any other Muslim coins in the

early modern era or Muslim coinage of any pre modern era. Coinage as an

art form reached its zenith in Jahangir's zodiac coins and imperial portrait

medals that he presented to loyal courtiers.

By the later years of Akbar's reign issues of square silver rupees had become

the standard circulating coin within Mughal territories, a fact that by itself

testifies to the regime's second major source of wealth, the flow of foreign

specie into its territories. This in turn was due to India's perennial trade surplus with lands throughout the Indian Ocean and, after 1498, with Western Europe. No significant silver deposits were located within Mughal

territories. Silver for Mughal coins entered India primarily through north

western and western Indian mint towns and reflected the degree to which

India remained, as it had been since Roman times, a metallurgical 'black hole'

for precious metals exported from the West. Much of the silver for Mughal

coinage came, in fact, from South American silver mines, and after entering

the European economy substantial sums of silver coins flowed eastward and

either reached India directly in European ships or arrived in Mughal territories

after circulating in the Ottoman empire or in Safavid Iran. Those two latter

289

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

empires, like Mediterranean and Western European countries, ran a perennial

trade deficit with India. And only after the industrial revolution did Europe

finally gain the financial upper hand with India and China. Apart from the indirect benefit to the dynasty of a wealthy commercial class and a thoroughly

monetised economy, the Mughal treasury directly profited from mint fees on

the massive but unquantifiable volume of imported specie.

Europeans may have come to India initially for 'Christians and spices,' as one of Vasco da Gama's officers is said to have remarked to a North African

Muslim upon coming ashore near Calicut in 903/1498. They found both commodities in abundance in Calicut and in other port towns along India's

south west coast. This region, known as the Malabar coast and now incorpo

rated within Kerala state, was, however, one of the few areas of the subcon

tinent that Mughal armies never reached. Mughal India's favourable trade

balance was primarily based upon the production of cotton cloth, which had

been sold throughout the Indian Ocean and in the Mediterranean region since

Roman times. Medieval hoards of this cloth have been found in Egypt. Indeed.

when Indian Muslims went on hajj, they often financed their journeys with

sales of Indian textiles. North Indian merchants also sold Indian silk, slaves,

sugar and medicinal herbs in Afghanistan, Central Asia and Iran, but cloth

continued to be the most valuable export commodity until the industrial revolution. Indeed, the cost of Indian cotton cloth in a selfconsciously mercantilist era was one of the economic stimuli for English cotton manufac

turing in the eighteenth century.

One sign of India's regional economic dominance in the Mughal era was the

presence of an Indian mercantile diaspora whose representatives were prom

inent in Iran and Central Asia, and who, after the mid sixteenth century, even

reached Moscow. This diaspora reflected both the strength of India's export

economy and the financial sophistication or ruthlessness, depending on one's point of view of India's mercantile /financial castes. It was also facilitated by the solicitous concern shown to merchants by early modern Islamic states: all three empires protected trade routes, knowing they would

derive substantial economic benefits thereby. During the last years of Akbar's

reign the Indian mercantile diaspora in Iran alone may have numbered as many as 10,000 individuals. Most of these men were Punjabi Khatris; that is,

they were from the same large caste group as Akbar's finance minister, Todar

Mai. They evidently controlled India's foreign trade with Iran as well as functioning as bankers or moneylenders in the Iranian economy. In the late

sixteenth and seventeenth centuries some of these Khatri merchants migrated

from north western Iran to newly conquered Russian territory in the former

Cambridge Histories Online © Cambridge University Press, 201 1

### India under Mughal rule

Astrakhan khanate along the lower Volga, eventually making their way to Moscow. A few Khatris eventually sought permission to trade as far west as

Poland. Members of the same caste group resided in such Central Asian cities

as Samarqand. In Central Asia some Khatris transformed themselves from

exporters to producers by establishing a local putting out system to produce

cloth utilising local cotton. There and in Iran they operated through what were family firms of the type known in Italian Renaissance city states. Their

presence in Iran, Russia and Central Asia at a time when European seaborne

trade with India was steadily growing helps to balance the Eurocentric historiography of the Mughal era by reminding everyone concerned of the

financial strength and mercantile sophistication of just one portion of the Indian merchant class. Other such castes, such as the Chettis from India's

south east or Coromandel coast, carried on extensive trade with South East

Asia in the early modern era, just as centuries and even millennia earlier their

predecessors had spread widely throughout this region.

It is important to appreciate the economic vibrancy of the Indian economy

as a whole and that of Mughal territories in particular. Not only were Indian

merchants expanding their trade and financial activities overland, just as the

Europeans were arriving by sea in greater numbers, but many of these mercantile caste groups increased their wealth and influence within Mughal

India as the Mughals extended their authority and sophisticated extraction

techniques to larger areas of agrarian production. Such well known mercantile

caste groups as the Oswals, natives of the region of Rajasthan known as Marwar, were especially effective in exploiting the new opportunities offered

by the monetised agrarian economy and the relative security provided by Mughal power. The Oswals and other commercial castes became bankers for

the empire. Indeed, when the Europeans arrived in India they discovered a

sophisticated banking system that allowed merchants or government officials

to transmit funds from Bengal to Delhi or further to Afghanistan, Iran, Central

Asia, Iran and Russia via hundis or bills of exchange. The presence of finan

dally astute, well capitalised Indian mercantile castes and the existence of their

elaborate trade and financial networks facilitated European commerce in South Asia and the contiguous regions.

By the time Akbar died in 1605 the three major European seaborne powers

had arrived in India: the Portuguese in 1498, the Dutch and British as united

commercial companies in 1600 and 1602. Initially, as has been noted, the Portuguese as well as their northern European competitors were preoccupied

with the spice trade, and therefore focused their attention on the Malabar

coast, well away from Mughal territories. However, even before Dutch and

291

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

English merchants arrived in India in any numbers, the Portuguese had begun

to reduce the amount of pepper shipped to Europe in favour of indigo and

textiles. In the 1580s this shift was fairly modest, but in the early seventeenth

century as Dutch and British ships began carrying spices to Europe, the price

of pepper and other spices fell precipitously, and the Dutch and the British,

who had quickly usurped the primacy of Indian Ocean commerce from the

Portuguese, increasingly purchased Indian textiles, not only cotton but also

silk from Bengal. 13

By the 1680s textiles, both cotton and raw silk, which were produced in north as well as south India, became the most important Indian exports to

Europe, with most spices arriving from Dutch bases in Indonesia and the Moluccas. Indian textiles also had become critical for Dutch trading in South

East Asia and Japan. The British and Dutch had established commercial posts

in Gujarat at Surat in 1022/1613 and 1038/1628 respectively, and by the 1630s

they had both opened 'factories', that is warehouses, in Bengal. Both Gujarat

and Bengal were by then Mughal territories, and the Mughal economy thus

directly and indirectly profited from this ever increasing volume of commerce

with Europe that the British, Dutch and others largely paid for with specie.

The state directly profited from mint charges and tolls, and Mughal officials,

mansabdar jagirddrs, peasants and craftsmen benefited from increased demand

for local agricultural and manufactured goods. Whether this huge influx of

specie produced significant price inflation in Mughal territories is difficult to

determine, any more than it can be done for the Malabar coast after Vasco da

Gama's arrival there in 903/1498. Nonetheless, there seems to have been only

modest price inflation in Mughal territories during the seventeenth century.

Throughout the seventeenth century Europeans acted as traders and, politically, petitioners with Mughal officials. Not until the Mughal empire had ceased to exist and become a mere city state in Delhi in the 1740s did the

English become a military and territorial power within Mughal dominions. In

consequence, the history of the Mughal empire from the time of Akbar's death

until the death of the last great Mughal emperor, Aurungzeb, in 1707, is primarily an Indian rather than a European matter. There are two major aspects to this narrative: the Mughal emperors and their policies, and indig

enous developments that were sometimes outside or beyond their control.

First of all, the personalities and policies of individual emperors have to be

13 For an introduction to European seaborne commerce see especially Om Prakash,

European commercial enterprise in pre colonial India, The new Cambridge history of India (Cambridge,

292

Cambridge Histories Online © Cambridge University Press, 201 1

#### India under Mughal rule

studied seriously, for nothing is more obvious from Babur's autobiography

and Akbar's exceptionally well documented reign than the fact that the emperors determined how the state functioned. In such an imperial system

the emperor was the linchpin, the capstone, the deus ex machina. A study of

both Babur's and Akbar's reigns demonstrates a pattern of unremitting activity, campaigning during the dry season and personally overseeing every

possible administrative, political and cultural detail. Second, in studying the

history of the Mughal empire it is always important to remember that indigenous religious and social movements that threatened the empire often

developed independently or at the very least were only indirectly caused by a

particular ruler's actions. One of the most obvious cases in point was the evolution of the Sikhs from a syncretic religious movement to a social and

political power led by Khatris and staffed by Jats that threatened Mughal control over the wealthy and strategically crucial Punjab province.

Jahangir: the aesthete as emperor

The reign of Akbar's successor Salim or Jahangir, the 'World seizer' (r. 1014

37/1605 27), vividly illustrates the importance of idiosyncratic personality

while it also witnessed the beginnings of Sikhism as a social and political force. Jahangir, like Babur, wrote an autobiography, and while it seems to

reveal a shallower individual than his great grandfather the work is nonethe

less still a rich, complex text that combines an explicit proclamation of imperial

values as well as implicitly offering an intriguing psychological self portrait.

Jahangir intended it to be a kind of 'mirror for princes' work in which he presents himself as the cultured 'just sultan' who ruled over a fabulously wealthy kingdom that, as he is careful to note, far exceeded the wealth of his

neighbours. By neighbours he seems to have had especially in mind the Safavids of Iran, with whom he shared a language and culture. It is especially

in Jahangir's Twelve Decrees, proclaimed, evidently, in 1016/1607, and which he

included in his memoirs, that he revealed much about both his principles of

government and his self indulgent personality.

The first four of these decrees dealt with economic measures designed to protect merchants and increase trade. These included encouraging jdgirddrs to

build caravanserais and emphasising the sanctity of private property, whether

belonging to Muslims or 'infidels'. In a related edict Jahangir also forbade the

quartering of troops in private houses. Several other measures concerned

social policy. These included the prohibition of mutilation as a punishment,

the construction of hospitals in large cities, the requirement that the

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

'deserving poor' should be brought before him daily, by implication, for alms,

an order against the slaughter of animals on certain days a continuation of

Akbar's custom and the prohibition against jdgirddrs and provincial revenue

officials seizing peasant lands and cultivating the land themselves. This last

measure may have been designed to guard against jdgirddrs becoming entrenched landlords or local chiefs as much as it was intended to protect

cultivators. This is certainly true of the next edict, which forbade jdgirddrs

from intermarrying with the local population without royal permission. Then.

in a series of edicts designed to secure his political position, Jahangir con firmed the appointment of his father's jdgirddrs later substantially raising

their mansab ranks and confirmed also the grants to those who 'formed the

army of prayer'. He also substantially increased the stipend of women in the

harem. Finally, in the one edict, number five, that does not fall under any of

these categories, Jahangir outlawed the manufacture of wine, spirits or intoxicants of any kind. 14

This latter stipulation, which on the evidence of its opening sentence might

be seen merely as a further means to impress the 'army of prayer' with

piety, seems from the remainder of the very long passage more immediately

the consequence of his own well known and here, openly exhibited, alcohol

ism. This was not unusual for members of either the Mughal or the Safavid

ruling class, many of whom were alcoholics and, like Jahangir, opium addicts.

Babur himself drank profusely for about a fifteen year period before he quit in

1527. It is only one of many personal revelations that Jahangir provides in his

memoirs. He writes about this prohibition:

This despite the fact that I myself commit the sin of drinking and have constandy persisted in doing so from the age of eighteen until my present age of thirty eight . . . sometimes I began to drink three or four hours before the

end of the day. Sometimes I drank at night, and occasionally I drank during the

day. Until the age of thirty this is how it was. After that I decided that I would

only drink at night. These days I drink solely to promote digestion. 15

Jahangir later reports that he had begun drinking during a hunting trip along the Indus and 'liked the feeling he got'. Later, however, wine didn't affect him enough so he began drinking hard liquor. 'Things got so bad', he

writes, 'that in my hangovers my hands shook and trembled so badly I couldn't drink myself but had to have others help me.' 1 While reducing his

14 Jahangir, The Jahangirnama, pp. 26 7.

15 Ibid., p. 26.

16 Ibid., p. 185.

294

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

wine consumption he gradually substituted opium, which, he says, at age forty six, he took both day and night.

It is tempting to see Jahangir's debilitating addictions as symptoms of a

weak, dependent personality, if drinking had not been such a common vice

among rulers and military aristocrats in India, Iran and Central Asia at this

period. And yet while Jahangir constantly invokes his father's policies and achievements, he rested on Akbar's laurels rather than trying to win his own.

While he possessed the dynastic arrogance and cultural sensibilities of his

forebears, by the evidence of his own writing he had little taste for actual combat. He relied instead on the imposing imperial foundation that his father

had erected and on Akbar's experienced commanders for the continuous military activity seen by them as a prerequisite for long term political survival.

Jahangir awarded promotions, received embassies, hunted and drank, visited

Muslim and Hindu ascetics, admired and patronised miniature painting, saw

to the design of new coinage and recorded memories of his own emotional

sensitivity and personal attachments that humanise him. Having just reported,

for example, the death of his mother in law, he describes how his minister and

father in law, rtimad ud dawla, never recovered from the grief he felt over his

wife's death:

No husband has ever had the affection and attachment for his spouse that.

rtimad ud dawla had for her. One can imagine what befell the poor, grief stricken old man . . . Although rtimad ud dawla kept himself externally under

control and exhibited forbearance in order to please me, given the attachment

he had for her, forbearance could not replace her as a companion  $\dots$  From the

day his spouse passed away he no longer took care of himself and wasted away day by day . . . He suffered inwardly from loneliness until he died three

months and twenty days later. 17

rtimad ud dawla left behind at least forty one children, whom Jahangir consoled, as he notes, with robes of honour.

Jahangir's ability to convey the pathos of human emotion is unmatched in the

literature of early modern Muslim rulers, including that of his great grandfather, Babur. However, his feeling for his in laws was genuine and unusually strong, springing probably in the first instance from his passionate

17 Ibid., p. 369.

295

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

attachment to his favourite wife, Nur Jahan, whom he had married as a young

widow of a Mughal officer in 1019/1611. By every signjahangir was deeply in

love with and probably emotionally dependent on this beautiful Iranian woman, a guess about marital relations that cannot be hazarded about most

other Muslim rulers in pre colonial times. Nur Jahan seems to have been his

almost constant companion, including accompanying him on many hunting

expeditions, as in the spring of 1026/1617:

On the seventeenth [16 April] after the elapse of two watches and three gharis,

the scouts had cornered four lions. I set out with the ladies of the harem to

hunt them. When the lions came into view, Nurjahan Begam said, 'If so commanded, I will shoot the lions/ I said, 'Let it be so,' She hit two of them

with one shot each and the other two with two shots. 1

Nur Jahan even had coins and imperial decrees issued in her name and until

the death of her father she acted as part of a triumvirate with her father and

brother, Asaf Khan. Together the three effectively ran the empire for long

periods, especially during the prolonged periods when Jahangir was incapa

citated with alcohol and opium. However, the family's supremacy did not presage an Ottoman style administration where the emperor retired from active administration and ceded power to a series of viziers. When Jahangir's

son, Shah Jahan, came to the throne the new emperor again took direct control of Mughal affairs.

Nur Jahan's highly visible role and the importance of her entire family serve

as reminders of two important aspects of Mughal court culture: the active

role of women and the increasing numbers of Iranians in India. Nur Jahan

was one of the most visible and powerful individual women among the Mughal nobility visible at least to historians but she was far from the only influential and identifiable woman at court. The time is long since past

when it was possible to think of the Mughal harem or the woman's quarters

of any early modern Islamic state as an undifferentiated society of passive

pleasure objects. 19 First of all it is important to note two things about the

identity and status of royal women: many were themselves Timurids or Chinggisids, that is, sisters, daughters or nieces of the emperors, and many

of the emperors' numerous wives were members of Muslim or Hindu aristocratic or ruling families. Therefore, unlike the Ottoman harem, with its legions of concubines or slaves, who were often, no doubt, exceptionally

18 Ibid., p. 219.

19 See for example Ruby Lai, Domesticity and power in the early Mughal world (Cambridge, 2005).

296

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

### India under Mughal rule

powerful individuals, a large if indeterminate number of Mughal women were

of high status and highly educated. Timurid and Chinggisid women and favourite wives like Nur Jahan had their own households and often their own houses as well.

Women in Turco Mongol tribal and nomadic societies, while certainly subordinate individuals to a dominant male ethos, nonetheless were both far more physically visible and also politically influential than wives, sisters

and daughters in great urban empires. Temiir's wives were present at his receptions and drank and got drunk with men present, even with the Spanish

ambassador Clavijo in 808/1405. Whether shared intoxication translated into

political influence is not known, as Temiir left no verifiable memoir, but five

generations into the evolution of Timurid society with Babur, women were

known, by Babur's own testimony, to act as his advisers. When describing events in his Farghanah homeland in 899/1494, shortly after inheriting his

father's appanage, he remarks that his grandmother, Isen Devlat Begim, 'was

an exceptional advisor and counsellor. She was extremely intelligent and prudent. Most affairs were settled with her advice.' 20 It is especially noticeable

that in his Vaqa'f Babur carefully publicises his respect for three groups of

individuals: Turco Mongol aristocrats, that is, Timurids and Chinggisids; descendants of Khwaja Ahrar, his Naqshbandi 'patron saint' who died in 895/1490; and Timurid and Chinggisid women. According to his own testi mony Babur almost ostentatiously showed such women his regard by visiting

them as he did male Timurids and Chinggisids and Ahrari Naqshbandis rather than calling them into his presence.

Babur's daughter, Gulbadan Begim (c. 929 1012/1523 1603), herself personi

fied the high status and influence of Timurid women influence in the Mughal house and with posterity. She composed at Akbar's request her own remarkable memoir that not only has a powerful emotional content, but also rescues many other Timurid and Chinggisid women from anonymity.

Speaking for example of her reaction at age ten to the death of her foster mother in 1533, Gulbadan writes that 'I felt lonely and helpless . . . and night and

day would weep, grieve and mourn.' 21 Then a few pages later Gulbadan writes that after the period of mourning Humayun celebrated two splendid

feasts, the so called 'Mystic' or talismanic feast celebrating Humayun's accession and a marriage feast for Humayun's brother, Mirza Hind al. She

20 Dale, The garden of the eight paradises, p. 63.

- 21 Gul Badan Begam, The history of Humayun (Humayun noma), trans, and ed. Annette
- S. Beveridge (Delhi, repr. 1972), fo. 23b.

297

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

names more than eighty women who attended, some of whom were simply

nurses, but most were important Timurids and Chinggisids, and she manages

to bring the court alive by conveying the excitement of the lavish celebratory

occasion. Writing of the events within the 'Mystic House' on the bank of the

Ganges, Gulbadan recalls that:

First there was a large octagonal room with an octagonal tank. In the centre,

and again, in the middle of the reservoir an octagonal platform on which were

spread Persian carpets. Young men and pretty girls and elegant women and

musicians and sweet voiced reciters were ordered to sit in the tank . . . [Later

after gifts were distributed] His majesty [Humayun] was pleased to say [to

Khanzadah Begim [his grand aunt], 'Dearest Lady, if you approve, they might

let water into the tank.' She replied: "Very good,' and went herself and sat at

the top of the steps. People were taking no notice, when all at once [?] the tap

was turned and water came. The young people got very much excited. His

Majesty said 'There is no harm; each of you will eat a pellet of anise and a bit

of comfit [ma'jiin, an intoxicant or confection or both] and come out of there.' 22

Women's agency, at least within the imperial family, is evident from events

in 946/1539. When Humayun was fleeing before the Suri Afghan Shir Khan,

he asked Gulbadan, then perhaps seventeen, to ride to nearby Alwar to make

peace with Humayun's brother Mirza Hind al. Citing Gulbadan's youth, her mother went instead. Then in 983/1575 Gulbadan, at the time a mature

woman in her early fifties, led the pilgrimage to Mecca, accompanied by a

number of her female relatives and wives and relatives of other important

Mughal women. They returned to Fatehpur Sikri only in 990/1582.

It is evident from Gulbadan's memoirs and Nur Jahan's activities that Mughal women were literate, assertive individuals. In fact, daughters of the

Mughal house after the time of Gulbadan Begim were literate in Persian and

often competent in Arabic, with a sophisticated knowledge of both Persian

verse and Sufi religious literature. Zib al Nisa, one of Aurungzeb's daughters,

is a prime example, and probably as influential in her way as Nur Jahan. One

of at least three Mughal princesses who wrote a diwan, or collection of poetry,

Zib al Nisa was tutored by Ashraf Mazandarani, a highly educated and socially

prominent member of the religious literati class in the Safavid capital, Isfahan.

In fact, Mazandarani, who reached Agra in 1658/9, was related by marriage to

the famous Majlisi family of theologians in Isfahan. He was also acquainted

with the eminent poet Sa'ib and the calligrapher Daylami, both of whom had

22 Ibid., fos. 24a, 28a.

298

Cambridge Histories Online © Cambridge University Press, 201 1

### India under Mughal rule

served the Mughal court before returning to Isfahan. Daylami, in fact, had

been tutor to Dara Shikuh, Shah Jahan's eldest son and designated heir. Zib al

Nisa became one of the principal religious and literary patrons during Aurungzeb's early reign. Her activity was all the more important because Aurungzeb's own ascetic habits led him to turn his back on the lavish artistic

and architectural patronage of his predecessors in favour of piety and con

quests. Indeed, it was at Zib al Nisa's initiative that the famous compilation of

Islamic legal decisions, the Fatawa yi 'Alamgifi, was translated from Arabic to

Persian, although she herself had also studied Arabic grammar. Zib al Nisa's

literary and religious interests offer just a fleeting insight into the sophisticated

cultural world of Mughal women who, even if they lived relatively confined

lives, could, if they were so inclined, cultivate vibrant intellectual interests.

#### Indo-Persian literature

The fact that Zib al Nisa studied with an Iranian who was as well connected

as Ashraf Mazandararii is a reminder of the degree to which Mughal India

had become an integral part of the Persianate cultural sphere. Akbar's recruitment of Iranians, the disparity between the wealth of Mughal India

and the relative poverty of Safavid Iran and Safavid persecution of Sufis stimulated a migration of historic proportions from Iran to India. Nur Jahan

and her family were part of this movement of Iranians to India, which continued largely unabated until the Safavid regime collapsed in 1134/1722

and the Mughal empire gradually atrophied during the same period. Many

of the Iranians who settled in India wrote poetry and were part of what the

modern Iranian scholar, Gulchin i Ma'anT, has termed the 'Caravan of Hind'. 23 Ma'am has identified more than 700 such individuals who immi grated to Mughal territories or the Deccan states during the Mughal era. Most

of these men were not court poets, but administrators, warriors, teachers or

'ulamff who wrote poetry in their leisure time, as was so common among educated Iranians.

Mazandararii was not the most influential emigre poet to write Persian verse in India, but he is memorable for the 'exile' verse he wrote in which he

expressed his conflicted feelings about the subcontinent. Among destitute

Iranians', he observed, 'there is nothing but desire for India.' The contrast

between the wealth of the two kingdoms was so great that:

23 Gulchin i Ma'am, Karvan i Hind, 2 vols. (Tehran, 1369/1970).

299

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Whoever comes from Iran to India imagines,

That in India gold is scattered like stars in the evening sky. 24

Yet despite Mughal India's attraction for impoverished Iranians, Mazandaram,

at least, was not entirely happy there. First of all he was simply homesick:

I do not know why there is naught in me but grief, Since the means of happiness have fallen to me in India. 25

Not only did he dislike the climate, but like many Iranians he also regarded Indo

Persian culture as a pale imitation of the Iranian original. Playing on the common

Iranian and Central Asian image of India and Indians as black or dark, he wrote:

How can you compare the soil of Hind with the land of Iran? Do not equate black soil with a rose garden . . . How can you compare the Indian kingdom to Iran? As the copy can never be equal to the original. 2

Most twentieth century Iranian and Western literary scholars also felt that the

quality of Indo Persian verse was a poor, debased imitation of the original, that is,

of the poetry of Sa c di and Hafiz, the two great 'classical' Persian poets. Generally

known as sabk i hindi, the Indian style has been widely considered to be a unique

hothouse variant of Persian verse, characterised by extraordinary or bizarre

imagery and highly intellectualised and obscure conceits. By the late twentieth

century, however, scholars had actually begun to devote serious attention to

Indo Persian verse rather than just repeating stereotypes, and a consensus has

now emerged that the 'Indian style' was in fact a product of literary develop

ments in greater Khurasan, Central Asia and India. It is seen as peculiarly 'Indian'

in modern Iran because Iranians had then turned their backs on the innovative

literary developments of the Safavid Mughal period in a bazgasht or 'return' to

classical traditions. Nonetheless, some of the poets associated with the Indian

style were born in India and did produce verse that was, in certain respects,

distinctly more Indian than the poems written by expatriate Iranians.

The first poet who is usually seen as a practitioner of what he and others saw as a 'new' style that went beyond the verse of Jami of Herat was Baba

Fighani of Shiraz (d. 925/1519). 27 In fact, Fighani and other poets now asso

dated with the Indian style worked with a thorough knowledge of verse of the

24 Stephen Frederic Dale, 'A Safavid poet in the heart of darkness: The Indian poems of

Ashraf Mazandarani', Iranian Studies, 36, 2 (2003), p. 197.

25 Ibid., p. 206.

26 Ibid., p. 207.

27 See Paul Losensky, Welcoming Fighani: Imitation and poetic individuality in the Safavid Mughal ghazal (Costa Mesa,

300

Cambridge Histories Online © Cambridge University Press, 201 1

#### India under Mughal rule

Timurid period. Figharii himself, interestingly enough, might be also consid

ered to be 'Indian', although he lived and died in Iran, because he wrote a

number of 'imitations', that is, innovative variations, on the verse of the first

great Indo Persian poet, Amir Khusrau. Two important Mughal practitioners

of Figham's new style were Abu'l Faiz Faizi (954 1004/ 1547 95), who was

Abu ] l Fadl's older brother and one of a few Indian born poets associated with

this style, and Jamal al Din Muhammad 'Urfi (957 99/1550 91), a native of Shiraz. Faizi, as he is known by his pen name, was, apart from stylistic matters,

an 'Indian' poet in the sense that he sometimes used Hindu sources the

Mahabharata and Bhagavad Gita for his verse. However, the most famous of

the sabk i hindl writers were Sa'ib (1010 89/1601 78), an Isfahan native, and

Bedil (1054 1133/ 1644 172.1), who was born in India at Patna.

A native speaker of Bengali, Bedil is the pre eminent example of a poet whose sabk i hindi verse was not just part of Persian literary evolution, but was

identifiably Indian in certain ways. Bedil, who like so many other Persian language poets was spiritually attracted to Sufism, is known for his elaborate

conceits and ambiguity and for employing colloquialisms and using Indian

vocabulary not found in the verse of other Persian language poets of the era.

The difficulty of his verse is probably more immediately due to his Sufi piety

and his sense of the inexpressible quality of his relationship with God. He.

more than any other than Indo Persian writer in Mughal India, became famous beyond Hindustan, particularly in Central Asia and Afghanistan, and

remains extremely popular in Afghanistan and Tajikistan to this day.

While Persian remained the dominant court and literary language at the Mughal court it is also important to recall that much of what is now considered

classical Hindi or Hinduwi verse was written during the Mughal era and that.

many Mughal emperors and princes both during and after Akbar's reign patron

ised Hindi verse as well as Indian music. This fact also serves as a reminder not

only that the bulk of Mughal India's population always remained Hindu, or at

least non Muslim, but also that fundamentally important cultural and socio

economic changes were occurring in the mid seventeenth century among the

majority population that altered the social and political topography of the Mughal

empire. One such fundamental change was the rise of the Sikh movement.

Internal unrest: Sikhs and Nagshbandis

Sikhism grew out of a syncretistic movement that borrowed both from Sufism

and bhaktl or Hindu devotionalism. Sikhism was monotheistic, protestant both in its scathing criticism of Brahman priests and Muslim 'ulamff, and in

301

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

its egalitarian ideology at the petty bourgeoisie and peasant level. It was founded by a Punjabi Khatri, a member, that is, of the same large caste group as Todar Mai, Akbar's revenue minister. This man, Guru Nanak (b. 1469), strongly criticised the Lodi predecessors of the Mughals as unjust rulers

who discriminated against non Muslims, but he also railed against Hindu caste

and social distinctions. Guru Nanak preached that God could only be under

stood by absorbing the teaching of the divine teachers or gurus, thus initiating

a line of sacred disciples, who became the leaders of the community. 2.

Many of the early Sikhs were, like Guru Nanak, Khatris of modest wealth and status, small merchants and shopkeepers, but cultivators were also prominent among his followers, and many of these agriculturalists were Jats. Part of Sikh ideology was a proud proclamation of their members' middling social status. By the time Guru Nanak died in 1539 members of the

sect had begun to coalesce into a new social group, publicly proclaimed by

their disciples' commensality. When Jahangir came to the throne the Sikhs

had evolved into a self consciously separate and increasingly well organised

community, distinct from Muslims and Hindus, concentrated in the Punjab,

especially in and around Lahore. However, when the fourth Guru Arjan blessed Jahangir's rebel son Khusrau in 1605, Jahangir responded quickly to

the growing Sikh movement and had Guru Arjan arrested and executed. This

prompted the Guru's son to begin transforming the order into an armed sect

that by the 1670s was successful in converting large numbers of Jats and also

some Muslims to the new faith and society. When Aurungzeb executed the

Sikh Guru Tegh Bahadur in 1086/1675 on grounds of blasphemy, the Mughals

earned the undying hatred of a community that had long since become a state

within a state in the Punjab. This was the wealthy and militarily strategic province that Shah Jahan's historian, 'Inayat Khan, described as the 'choicest

portion of the imperial dominions'. 29 A new conflict erupted following Aurungzeb's death, and while Mughal armies were able to defeat poorly armed Sikh forces in 1127/1715, leading to hundreds of additional executions,

the Sikhs quickly extended their influence in the Punjab as Mughal power atrophied in the 1730s and 1740s.

Jahangir, whose execution of the fourth Guru initially provoked the alien ation of Sikh followers from the Mughal regime, was a man who was suspi

cious of all popular religious movements that seemed to threaten public order

 $28\ J.\ S.$  Grewal, The Sikhs of the Punjab, vol. II, part 3 of The new Cambridge history of India

(Cambridge, 1990), 'Introduction' and ch. 2 'Foundation of the Sikh Panth'.

29 W. E. Begley and Z. A. Desai (eds.), The Shahjahan Nama of 'Inayat Khan (Delhi and New York, 1990), p. 121.

302

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

or Mughal supremacy. He publicly revered Hindu and Muslim ascetics, but

was hostile to charismatic or activist figures of any religious stripe. In 1028/

1619 he arrested Shaykh Ahmad Sirhindi, an Indian born member of the Naqshbandi Sufi order that Babur had brought with him from Central Asia.

Sirhindi was a student of a Naqshbandi from Kabul, Baqi Billah Birang, who

was probably an Ahrari Naqshbandi on his mother's side. Baqi Billah had arrived in Delhi in 1602 after visits to the Naqshbandi homeland in the Samarqand region. Litde is known about his teachings in India, but Sirhindi

claimed for himself a semi divine status as an incarnation of the Companions

of the Prophet Muhammad and the 'Renewer of the Second Millennium of Islam', which had begun in 1000/1591. Like many other conservative Muslims

Sirhindi had been offended by Akbar's religious policies and encouragement

of Hindu participation in the Mughal state, and his affiliation with the conservative and largely orthodox Naqshbandis probably reflected his ortho

dox views. However, not only was Jahangir publicly proud of his father's latitudinarian policies but also he was suspicious of Sirhindi's claims and the

enthusiasm he generated among the populace. As he wrote:

Also during these days it was reported that a charlatan in Sirhind named Shaykh Ahmad had spread a net of deceit and deception in which he had trapped many unspiritual worshippers of externality. He had also sent into

every city and region those of his devotees whom he called khalifas, who were best versed in setting up shops in which mysticism could be peddled and

people hoodwinked ... I saw that the only thing to do with him was to let him

spend a few days in prison. 30

Later he released Sirhindi, who, while apologising for his extreme religious

claims, went on to establish the Naqshbandis as a vital, if conservative, Sufi

order in India. From there as the Mujaddidl, or 'Renewal', form of the Naqshbandi order it expanded outward back to Afghanistan and also to the Ottoman empire, where it survived to become influential among upper

class Turks in the twentieth and twenty first centuries.

In certain ways Jahangir personified the goal of Babur's original conquest.

As his memoirs attest, he enjoyed being emperor of a wealthy kingdom where

he could indulge his sophisticated artistic interests. And here was Hindustan,

a wealthy refuge for urbanised, culturally sophisticated Timurids and Chaghatay Chinggisids who were formally observant Sunm Muslims with a

strong attachment to Sufi spiritualism. In retrospect Jahangir's reign seems a

30 Jahangir, The Jahangirnama, p. 304.

303

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

kind of aesthetic interregnum, a pause in the history of a regime that evolved

to become more formally imperial and openly orthodox under the rule of

last two emperors, Shah Jahan and Aurungzeb. Yet Jahangir ruled in a political

system where he faced the same difficulties that he had earlier, as a prince,

visited upon Akbar. In 1622 one of his sons, Prince Khurram, the future Shah

Jahan, revolted, fearing that one of his brothers had gained ascendancy in the

early manoeuvring to succeed Jahangir. His revolt precipitated a series of hard fought campaigns as imperial forces chased Prince Khurram from the

Deccan to Bengal to the middle Ganges region. Khurram apparently intended

to depose his father, had he been victorious, but ultimately he failed and accepted a brokered peace, according to which he remained as governor of the

Deccan. Khurram's rebellion highlights the persistent tensions of the Turco

Mongol inheritance and appanage system that first the Ottomans and then the

Safavids had solved by incarcerating potential heirs to the throne in the harem.

The question remains: why did the Mughals never follow their lead?

Shah Jahan: the Second Temur

Jahangir or Nur Jahan and her brother, Asaf Khan ruled for another five years before the emperor died near Lahore in 1037/ October 1627. After Asaf

Khan came out openly in support of Prince Khurram and defeated one of his

brothers, Khurram was proclaimed emperor and, before reaching Agra, ordered the execution of his brother and four surviving Timurids who could possibly claim the throne. In a way his victory justified chaotic Mughal inheritance practices, even if it doesn't answer the question posed

above. That is, Khurram, now enthroned as Shah Jahan, was an experienced

military leader and practised diplomat in the dangerous world of imperial court politics. He was quite likely the most qualified man to rule. In person

ality, a complete contrast to his father, Jahangir, he was an able, conscientious,

aggressive individual who took and retained direct control of the state. He was

also an openly conservative Sunni Muslim in the mould of al Badauni and Shaykh Ahmad Sirhindi. A European observer said, indeed, that in religious

matters, Shah Jahan was everything unlike his father'. 31 Shah Jahan turned his

back on Akbar's and Jahangir's sympathetic attitude towards non Muslims,

and he also exhibited little of the relentless intellectual curiosity of Akbar or

the deeply emotional artistic sensitivity of Jahangir. Yet the nature of his

31 Quoted in Milo Beach and Ebba Koch, The King of the World: The Padshahnama, trans.

Wheeler Thackston (London, 1997), p. 59.

304

## India under Mughal rule

intellect, emotions and religious convictions can only be inferred from his public actions. Neither did Shah Jahan write or dictate a memoir like Babur

and Jahangir, nor are there the kind of eyewitness reports for his reign

make Akbar seem so human and such a humane individual. Apart from his

actions, inscriptions and monuments, Shah Jahan has to be viewed through

the panegyric rhetoric of court historians, whose prose obscures individuality

in favour of formal presentation of an imperial and imperious figure.

When viewed against the military activities of Shah Jahan's reign, al Badaum's scathing indictment of mansabdars seems even more the bilious

critique of a disaffected courtier and orthodox Sunni Muslim. Whatever the

day to day problems with the mansabddrijagirdari system it survived Jahangir's

intoxicated inertia to be revivified by another strong emperor. Shah Jahan

continuously used troops that the system supplied and throughout his reign

exerted military pressure both within the boundaries of the empire and on its

frontiers. Internally, Mughal troops were dispatched to annex kingdoms and

pressure others, particularly in Rajasthan. Externally, Shah Jahan sent troops

on the missions into: the Deccan in the 1630s, the upper Brahmaputra valley in

1045/1636 and Baltistan or 'Litde Tibet' in 1046/1637; against Balkh in the 1640s

and Kandahar in 1059/1649. He was successful in the Deccan, Bengal and

Baltistan but failed completely after long sieges and arduous campaigns to

capture and secure Balkh and Kandahar, both cities whose climates and locations made campaigns difficult for Mughal armies. Despite the expenses

of his campaigns he was able to replenish the treasury that the self indulgent

Jahangir had nearly exhausted by substantially increasing the revenue

demand, adding new territory and by systematic efforts to expand cultivation.

He also increased the amount of khalisa or state revenue that flowed directly

into the treasury to equal one seventh of the total collections.

Shah Jahan's brief occupation of Balkh in the 1640s is but one indication of

his heightened sense of his exalted lineage, for this campaign was driven by the

revanchist nostalgia that he shared with his predecessors. According to the

historian c Abd al Hamid Lahori, Shah Jahan had his ancestors' exploits read

aloud to him when he retired for the evening:

So that His Majesty may fall into a sweet sleep, the eloquent members of the

assembly read behind the veil works on biography and history, containing

accounts of prophets and saints as well as events of the reigns of former kings

and emperors which are memoirs of vigilance for the blessed who take warning, and reminiscences of pardon for the enlightened who are fortunate.

Especial favourites are the Tuzuk ('Memoirs') of the Emperor Babur and the

Zafar Nama which contains annals and conquests of the reign of His

305

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Majesty's illustrious ancestor the emperor Timur, the Lord of the Auspicious

Planetary Conjunction (Sahib i Qiran). 3X

Shah Jahan, who consistently called himself by the Timurid title that Jahangir occasionally used, the second Sahib i Qiran, showed that he took

his heritage seriously when he dispatched his sons to occupy Balkh in northern

Afghanistan in the 1640s. The conquest of Balkh was meant to provide the

staging ground for the restoration of Timurid banners in Samarqand, Temiir's

capital. Jahangir, when describing his visit to Babur's tomb in Kabul, had himself declared his intention to reconquer the Timurid homelands, but being

Jahangir, never mounted such an arduous campaign. That Shah Jahan made

the attempt even when it was known that it would cost more to conquer these

regions from the Uzbeks than the Mughals could recoup in revenue for many

years, is but one of many testaments to his self image. However, his sense of

grandeur is more easily seen in the architectural monuments of his reign. Grandeur is actually an inadequate term to characterise Shah Jahan's personal

involvement in architectural projects calculated publicly to dramatise the stature of the imperial Mughal state.

## Architecture and empire

One of the earliest signs of Shah Jahan's lofty ambition was the construction of

the Peacock Throne, a gem encrusted monument that was commissioned in

1037/1628 and completed seven years later. The throne came to symbolise the

Mughal empire, and when the Iranian usurper Nadir Shah Afshar invaded India

and plundered the throne in 1739, it signalled the empire's denouement the

actual end came only with a prolonged whimper more than a century later in

1859. In the 1630s and 1640s, however, that pathetic conclusion was unimagin

able as Shah Jahan constructed two other spectacular monuments testifying to

the success of the Timurid Renaissance, the Taj Mahal and a new capital in

Delhi, Shahjahanabad.

Following the death of his favourite wife, Mumtaz Mahal, in 1040 /June 1631

while he was campaigning in the Deccan, Shah Jahan ordered a memorial tomb constructed in Agra on the banks of the Yamuna river. Laid out within a

classic Timurid chahar bagh or four part garden, the Taj is part of an elaborate

complex that also includes two smaller, relatively unobtrusive structures, a

mosque and caravanserai. In architectural terms the Taj is most immediately a

32 Quoted in Begley and Desai (eds.), Tfie Shah Jahan Nama of Inayat Khan, p. 573.

306

Cambridge Histories Online © Cambridge University Press, 201 1

## India under Mughal rule

Timurid building, an exquisite reformulation of the ideas that shaped Humayun's tomb in Delhi, whose garden setting manifested the hasht bihisht

or 'eight paradise' model developed in Timurid Iran. 33 The eschatology of this

concept was appropriate for a garden setting that in pre Islamic Iran was already identified with paradise, the word itself being the Persian term for

an enclosed garden. Then to reinforce these associations the calligraphic inscriptions on the Taj suggest that the tomb represents an architectural metaphor for the resurrection. It is described by c Inayat Khan, who also informs his readers that the entire complex, a city in itself, as he points out,

was sustained by an elaborate waqf or endowment of some thirty villages in

the environs of Agra as well as by rent and sales from its bazaars:

On the 17th Zi'l Qa'da this year 1052 [21 January 1643], the twelfth anniversary

('urs) of Her Late Majesty the Queen's death was celebrated in the customary

manner. His majesty repaired in person to the sacred enclave congregated in

the gardens around her radiant tomb, and distributed both that night and on

the morrow, vast sums of money in charity among the deserving of both sexes ...

Let it not be concealed that the recently completed mausoleum had been erected in the course of twelve years, at a cost of 50 lakhs of rupees [5 million

rupees]; that its gardens were surrounded by squares, serais and bazaars; and

that a great number of substantial workshops were established behind the

serais . . . To maintain the mausoleum and its garden, His Majesty established

an endowment consisting of the annual revenues of  $30\ \text{hamlets}$  . . . and an

identical amount is also realized from the annual rent and proceeds of the

bazaars and serais. 34

Even as the Taj Mahal was being built Shah Jahan began the construction of

a new fortress city in Delhi, Shahjahanabad, a complex comprising ceremonial

buildings, harem apartments, bazaars and gardens that cost a further 6 million

rupees. Women, most noticeably Shah Jahan's sister, the influential Jahan ara

Begim, constructed some of the buildings within the fortress; she was respon

sible for a large serai and hammam or bath. Opposite this great city Shah Jahan

constructed the monumental Jami c Masjid, the largest mosque in India, an

open air building similar to the one Akbar constructed at Fatehpur Sikri. The

foundations for the new city were laid on 29 April 1639, a date chosen by astrologers, and the emperor ceremonially entered the newly constructed city

on 18 April 1648. In summarising the history of the Shahjahanabad 'whose

33 Lisa Golombek, 'From Tamerlane to the Taj Mahal', in Monica Juneja (ed.), Architecture

in medieval India (Delhi, 2001), pp. 21 5.

34 Begley and Desai (eds.), The Shah Jahan Nama of Inayat Khan, pp. 299 300.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Paradise resembling edifices have been constructed along the banks of the

river Yumuna' 'Inayat Khan wrote that:

Several years before, the thought came to His Majesty's omniscient mind that

he should select some pleasant site on the banks of the aforesaid river, distinguished by its genial climate, where he might find a splendid fort and

delightful edifices. In accordance with the promptings of his noble nature, he

envisioned that streams of water should be made to flow through the proposed fort ... [and the newly constructed canal] was designated as the Nahr i Bihisht ('Stream of Paradise'). 35

Given the geographic, economic and political distance that Mughal rulers had come since Babur's day, they might be excused for their profligate expenditure of cosmological metaphors, including one of Shah Jahan's inscrip

tions on his new fortress, a literal echo of Amir Khusrau's panegyric verse:

Agar firdaws bar ru yi zamin ast Hamln ast, hamin ast, hamin ast.

If there is paradise on earth, It is this, it is this, it is this.

It is nowhere noted whether or not Shahjahan had a fine sense of irony to match his sophisticated architectural sensibilities. If so he might have used it to

compose verse contrasting these paradises with his imprisonment in Agra fort

from 1658 until his death eight years later. In essence Shahjahan became the

victim of the Mughal appanage system previously exemplified by his own

succession. Thus, when in September of 1657 he fell seriously ill and desig

nated his eldest son, Dara Shikuh, as heir apparent, his other three sons began

in traditional fashion to seek the throne for themselves. The fact that Shah

Jahan improved dramatically by the time he reached Agra in October, where

he had gone in hope that the change of scene would improve his health, did

nothing to halt the military preparations of the three sons who were provincial

governors and experienced commanders, each with loyal households and reliable troops. These three initially became temporary and uneasy allies against Shah Jahan and Dara Shikuh in Agra. Eventually, however, the war

of succession devolved into a contest between Dara Shikuh and Aurungzeb,

who in 1657 commanded the imperial armies in their assault on Bijapur, a

continuation of the perennial Mughal campaigns to conquer the Deccan.

35 Ibid., pp. 406 7. 308

Cambridge Histories Online © Cambridge University Press, 201 1

#### India under Mughal rule

In Indian historiography the warfare among these four Mughal princes is often portrayed as a Manichean conflict, pitting the culturally sensitive and

religious eclectic Dara Shikuh against the personally austere, religiously orthodox Aurungzeb. Sometimes by implication, at other times more explic

itly, historians argue that a victory for Dara Shikuh, an intellectually inquis

itive, Akbar like figure, would have solidified the Mughal empire as a multicultural edifice, whose legacy would have been Muslim Hindu amity and therefore, in 1947, a peaceful, united transition from British rule to an

undivided, communally peaceful, independent Indian state. In this view Aurungzeb's military triumph, capture and execution of Dara Shikuh set India on a path to the tragedy of partition.

The appanage system, however, rewarded cunning intelligence, ruthless determination and superior military skills. Contemporary as well as modern

intellectuals might have preferred a cultured, religiously syncretistic aesthete.

Both may also have been, like Ashraf Mazandaram, shocked by Aurungzeb's

usurpation of Shah Jahan's throne. Mazandaram, for example, ostensibly addressing Iranians planning to follow him to India, wrote:

O you who have come from our country to India;

In your region have you not heard the news of India? . . .

The Indian born intent on killing his father;

Have you not heard this story on the Indian journey? 36

However, Aurungzeb, like his father, whose orthodox religious outlook he shared, was, if nothing else, an intelligent, indefatigable man and an experi

enced military leader dedicated to the efficient administration and continuous

expansion of the Mughal state.

### Aurungzeb and the Marathas

Aurungzeb ruled longer than any of his predecessors, dying at ninety years of

age in 1118/1707. Even more than his father he persisted in his effort to expand

Mughal control over the border regions of the empire, in his case to Bengal,

Afghanistan and, eventually in the area he knew best, the Deccan. In the 1660s

and 1670s he dispatched his generals to wage war in east Bengal and habitually

unstable Afghanistan. He was modestly successful in both areas, which were

economically valuable for the empire: Bengal for its productive agriculture

and Afghanistan as a commercial crossroads and trading entrepot.

36 Dale, 'A Safavid poet in the heart of darkness', pp. 208 9.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Simultaneously Aurungzeb engaged in what appears to have been a conscious

policy to reduce Rajput influence in the Mughal state and exert greater control

over the Rajput principalities west of Agra. The Mughal emperor never repudiated the well established Mughal policy of utilising Rajput military prowess, but he reduced the number of Rajputs in the imperial service and

interfered much more aggressively in Rajput succession disputes. At the same

time Aurungzeb alienated some Rajput nobles with his increasingly intrusive

Muslim orthodoxy, reimposing the jizya tax on non Muslims, destroying Hindu temples during campaigns and preventing temple construction at other times. In the late 1670s and 1680s Rajput discontent led some chiefs to

persuade Aurungzeb's son, Akbar, to ally with them, rebel against his father

and seize the throne. With the support of his cultured sister, Zib al Nisa, Akbar proclaimed himself emperor in 1091 /January 1681, but he was out manoeuvred by his father in a confrontation near Ajmir, the old Mughal pilgrimage site. Akbar then fled south to the Deccan, where he joined forces

with the confederation that had by then become the greatest threat to Mughal

authority, the Marathas of the western Deccan.

The rise of the Hindu Maratha kingdom was, like the growth of the Sikh community in the Punjab, the appearance of a threat to Mughal dominance

and presumptions of sovereignty over the subcontinent that had not existed at

the time of Babur's initial conquest. As was true of their relations with the

Sikhs, Mughal policies partly catalysed the growth of Maratha power and its

increasingly anti Mughal and even anti Muslim tone. However, the Marathas

had become a formidable regional power in their home territories, the rugged

mountainous regions north and south of Bombay known as the Western Ghats, well before Aurungzeb laid siege to Bijapur as his father's deputy in

1656. Led by the ruthless and charismatic Shivaji, a man of low ritual status in

the Hindu caste hierarchy, the Marathas first served with and then confronted

the increasingly enfeebled Bijapur sultanate that was, by 1656, on the verge of

being conquered by the Mughals. Shivaji first came into direct conflict with

Mughal power in 1663 when he defeated a Mughal general who had earlier

occupied the important Maratha town of Puna. Then in the following year the

Maratha chief plundered the vitally important port of Surat, the single most

important Mughal link with trade in the Arabian Sea and with Europe. While

Mughal forces succeeded in defeating Shivaji and forcing him into Mughal

vassalage in 1076/1665, by 1081/1670 he broke with his nominal overlords and

resumed raids into imperial territories, once again that same year, successfully

occupying and plundering Surat. Four years later Shivaji had himself declared

a kshatriya, in fact a Rajput, using compliant Brahmans to ritually eradicate his

310

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

low caste status, and in a spectacular, expensive ceremony he was crowned

as a Chatrapati, a traditional Hindu ruler, implicitly claiming universal dominion.

Shivaji was an audacious, skilled military leader, an intelligent, efficient administrator and a clever ideologue, who, in his coronation, defined himself

as a Hindu alternative to the Mughal emperors. While his newly created state

fragmented soon after his death in 1091/1680, both he and his successors posed

a formidable, unrelenting threat to the Mughal state. By institutionalising raids

into Mughal territories as state policy, Shivaji financed the expanding Maratha

enterprise in the Deccan and south India and drained resources from Mughal

territories. The fact that Aurungzeb's rebellious son, Akbar, had taken refuge

with the Marathas in 1681 lent greater urgency to the Maratha crisis. Therefore, following a peace with the Rajputs of Mewar, Aurungzeb marched

into the Deccan in 1092/1681 with his main field army and a host of officials,

government clerks and camp followers. He remained there for most of the

rest of his reign. Initially his campaigns were directed against the Marathas,

but the difficulty of ever finally destroying them in the difficult hill country of

the Western Ghats led Aurungzeb to turn his attention back to a long time

personal and dynastic goal, the conquest of the two surviving Deccan sulta

nates, Bijapur and Golconda. In campaigns partly financed by the surplus revenues of Bengal, both of these kingdoms fell to Mughal armies between

1096/1685 and 1099/1688, with most of their Muslim nobles then integrated

into the Mughal mansabdarijdgirdari system. Aurungzeb then climaxed these

triumphs with the capture and execution of Shivaji's son and successor, Shambhaji.

Aurungzeb's dramatic successes in 1688 did not, however, have the intended effect of eliminating Maratha resistance. Instead, the executed Maratha ruler's brother, Rajaram, fled to the formidable fortress of Ginji on

India's south east coast, which the Mughals failed to seize until ten years later.

In the meantime Marathas in their homelands in the Western Ghats opposite

Bombay led multiple plundering campaigns against Mughal territories. Even

though Aurungzeb remained in the Deccan throughout these years until his

death, directing imperial forces, and despite the many successes he and his

commanders enjoyed in seizing Maratha forts, they were never able to suppress what had become a hydra headed monster. As Aurungzeb's reign

drew to a close Maratha forces slowly but inexorably extended their raids further north and by 1111/1700 were regularly raiding Gujarat and Malwa,

across the Narmada river, the traditional boundary between north India and

the Deccan. As the Mughal empire atrophied during the first half of the

311

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

eighteenth century, Marathas founded a series of independent kingdoms, most notably at Gwalior, the strategic fortress south of Agra, and raided east.

as far as the British commercial settlement of Calcutta. By mid century they

had penetrated deep into the Punjab with full scale armies. But for the intrusion of the Afghans and the British the Marathas might have occupied

the wealthy and strategic heartlands of the Mughal empire. However, Afghans

shattered a confederated Maratha army at Babur's famous Pariipat battlefield

in 1174/1761, and in the late eighteenth and early nineteenth century British

military power prevented further Maratha expansion.

The seemingly endless campaigns in the difficult conditions of the Deccan

placed an enormous strain on the heart of the Mughal imperial system, the

mansabddrT jdgirddrl institution. Old trusted nobles were frustrated and

exhausted, and resentful at the influx of new Muslim nobility from Bijapur

and Golconda, who were given extraordinarily high ranks and preferable jdgvrs. Many mansabddrs simply refused to fight or made private arrange

ments with Maratha raiders. Nor was Aurungzeb able to co opt Marathas as

Akbar had done with the Rajputs, even though nearly 100 were appointed to

the imperial service at this period, another source of resentment for older

Mughal amirs. His failure to assimilate Maratha chiefs, despite conscious efforts to do so, may have been due to many factors, two of which seem particularly important. First, unlike the desiccated terrain of Rajasthan, where rajas or lesser lineage chiefs ruled from isolated and ultimately vulnerable fortresses much like Central Asian terrain where the seizure of a city often meant the conquest of a province Marathas lived scattered through the isolated, forested regions of western India, where the narrow valleys and rugged mountains of the Western Ghats gave them shelter. Second, unlike Rajput clans, with their relatively cohesive hierarchies, Maratha society was far more decentralised or fragmented. Aurungzeb's armies defeated Marathas on many occasions, but were unable to halt Maratha raids, which became an institutionalised feature of Maratha culture

and at times, as in the late 1750s, evolved into organised campaigns of conquest.

The imperial denouement

Aurungzeb's death in 1118/1707 is justifiably seen in hindsight as the beginning

of the end of the Mughal empire. However, despite its manifold problems the

empire and its institutions were still intact in that year, drawing substantial

revenues from its core Punjabi and Gangetic provinces that, despite the

312

Cambridge Histories Online © Cambridge University Press, 201 1

India under Mughal rule

extraordinary drain of the Deccan wars, provided a hoard in the central Agra

treasury of more than 240 million rupees. Despite these reserves the empire

slowly disintegrated between 1118 and 1152/1707 and 1739, when the invasion of

the Iranian usurper, Nadir Shah Afshar, acted as the coup de grace, and left the

empire as a tattered remnant, no longer an empire, but a weak north Indian

state. There were several underlying, interrelated causes for the prolonged

imperial death rattle. These were dynastic crises, the consequent disintegra

tion of the imperial system and the seemingly intractable political and military

challenges to Mughal authority throughout the empire.

The dynastic crises were most immediately the result of Aurungzeb's own longevity and the Mughal appanage system. Thus Bahadur Shah, the victor in the

inevitable succession struggle that erupted at Aurungzeb's death, was sixty five

years old when he came to the throne. It is impossible to gauge how much his age

affected his ability to govern, and he was an active commander throughout his

brief reign. However, his death in 1123/1712 disrupted the empire once again with

a prolonged and inevitably expensive war of succession that essentially lasted

from January 1712 until January 1713. In the first phase Bahadur Shah's most

powerful noble, Zulfiqar Khan, enthroned a new Timurid ruler, Jahandar Shah

This was followed by a bloody and distinctly un Mughal purge of amirs who had

supported the losing princes. Jahandar Shah's brief, drunken and self indulgent

year long reign ended when Farruksiyar, the son of one of Jahandar Shah's

defeated younger brothers, was enthroned with the support of two powerful

brothers from the important Sayyid lineage of Barha, a well entrenched Muslim

family long settled north of Delhi. His victory was also marked by the execution

of nobles and Timurid princes, including his own young brother.

Farruksiyar's brief reign of six years was marked by further dramatic erosion of imperial authority as the emperor's conflicts with his erstwhile supporters, the Sayyid brothers, dominated imperial affairs until the brothers

succeeded in seizing, blinding and eventually strangling the emperor in 1719.

This act, an unimaginable event in the days of Shah Jahan and Aurungzeb,

accelerated the downward spiral of the dynasty. The lingering prestige of the

Timurid house dissipated even further in the following year, during which the

Sayyid brothers ruled through two Mughal puppets, both of whom died of tuberculosis. Finally, a third Timurid prince, a grandson of Bahadur Shah,

crowned as Muhammad Shah, was able to break free of the Sayyid brothers'

control with the help of a group of Mughal loyalists, who evidently saw their

own fate tied to the integrity of the Timurid house. However, by this time the

empire was coming apart and, as events were to prove, Muhammad Shah was

not capable of restoring even a fragment of its power and grandeur.

313

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

The memoirs of Babur and the histories of Akbar's reign illustrate how personal qualities intelligence, dynamism, relentless military campaigns and

direct administration created and sustained the early Mughal empire. Early

modern empires depended, in the first instance, on the quality of the monarch,

and especially after 1123/1712, no member of the Timurid house exhibited

the qualities of their great predecessors: Babur, Akbar, Shah Jahan and Aurungzeb. As the character of the emperors deteriorated and the court and

central administration were damaged with purges and vicious partisan con

flicts the entire imperial system fragmented. Fragile ties of loyalty that bound

Muslim and Rajput officers to the Timurid house frayed, imperial orders were

ignored or not given and local officials had to fend for themselves or took the opportunity of the chaotic state of imperial affairs to seize regional power.

This process by which emperors gradually lost control over their empire was

also partly the consequence of indigenous groups asserting their own inde

pendence. Bahadur Shah faced Rajput, Sikh and Maratha challenges as soon as

he was crowned, and while he enjoyed some success in Rajasthan and the Punjab, the Marathas moved inexorably north. Jat lineages in the Agra region

that had rebelled in Aurungzeb's day also asserted their independence.  $\Delta s$ 

affairs deteriorated during Farruksiyar's disastrous reign, Rajputs and many

zamlnddrs seized de facto control of territories previously under Mughal suzerainty. Some Rajput chiefs now re emerged as independent magnates.

Watanjagirs became kingdoms once more. Muslim governors turned inward,

away from Agra and the atrophied empire, and became provincial rulers the

Nawabs of Bengal or the Nizams of Hyderabad.

Loss of Mughal control meant loss of revenue. Loss of revenue meant the reduction in military strength. The reduction in military strength meant the inability to reassert control over revenue resources. The pathetic state of

the Mughal system was marked, finally, by the successful invasion of the ruthless Iranian tribal leader Nadir Shah in 1152/1739. His invasion and rout

of a dispirited, factionalised Mughal army and subsequent seizure of the Mughal treasury and the Peacock Throne, made it impossible for the Mughals to recover. In 1179/1764 the British East India Company itself defeated a fragment of the old Mughal army and, in consequence, became

the diwdn of Bengal. The Company then used its power without responsi bility to plunder the wealthiest province of the empire, impoverish the population and precipitate a famine that may have killed 10 per cent of the

population. Never did Temiir's legacy seem more irrelevant as the Mughals'

kingdom seizing ambitions atrophied to be replaced in the minds of Indian Muslims by an impotent nostalgia.

314

Cambridge Histories Online © Cambridge University Press, 201 1

PART III

THE MARITIME OECUMENE

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade, shipping, port-states and merchant communities in the Indian Ocean, seventh to sixteenth centuries

MICHAEL PEARSON

Introduction

This chapter consists of surveys of the following regions: the Swahili coast, the

Maldive islands, Malabar, Coromandel and Sri Lanka (see Map 7). The period

to be covered is from the seventh to the sixteenth centuries. The concern will

be to describe the arrival of Islam in these areas, the process of conversion and

the state of Islam towards the end of this period. First, however, it is necessary

to provide an overall sketch of trade, shipping and seafaring in the Indian Ocean, in the period from before Islam to the end of the sixteenth century, and

then, before getting to specific areas, to consider some area wide themes.

Pre-Islamic Indian Ocean trade

The sea, more precisely the Arabian Sea, plays a large role in the story. 1 Travel

by sea, facilitated or sometimes circumscribed by the monsoon wind pattern,

has a very long history in this area. The earliest boats were canoes made of

reeds, still to be seen today in the marsh areas of the Tigris Euphrates delta.

Wooden boats, which gain their buoyancy from enclosed air, mark a major

technological step forward. They go back at least some 5,000 years, to the time

of the Indus Valley Civilisation.

The rise of early civilisations in the Tigris Euphrates area and in north west

India, that is those of Mesopotamia and the Indus Valley, had profound effects

for trade by sea. For the first time there were relatively routine maritime connections established, and indeed these extended to the third great early

1 See Michael Pearson, The Indian Ocean (London, 2003), pp. 46 61 for this and subsequent paragraphs.

317

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

civilisation, in Egypt. Most of this trade was carried on by small craft hugging

the coastline, and carrying not only 'luxury' products like beads, gold, silver,

pearls and ivory, but a vast quantity of humble goods: timber, foodstuffs, cloths.

In the first millennium BCE, after the decline of these two early civilisa tions, Arabian Sea trade became focused on India, which is to be seen as the

fulcrum of Indian Ocean trade from very early on. By this time participants

included very diverse people: those described as Greek or Roman, people from the Arabian peninsula, as well as from India. By this time there were

connections far down the Swahili coast, and across all of the Indian Ocean to

the Malay world. Longer connections were facilitated by sailors slowly learn

ing how to use the monsoon wind system to their advantage. This had begun

by at least iooo BCE. From around 400 BCE there is evidence of Indian and

Arab sailors going direct from the mouth of the Red Sea to India.

Unlike seas with constant trade winds, the way in which the monsoons reverse during the year made return voyages in the Indian Ocean relatively

routine. Put most simply, in the Arabian Sea monsoon area, north of about

io°S, winds from the south west prevail from June to October, and from the

north east from November to March. As a result, a passage from say Mombasa

to India would take place during the south west monsoon, and the return trip

while the north east wind prevailed.

In the third to the fifth centuries CE trade in the Indian Ocean was affected

positively by the rise of the Sasanian empire in Persia. Traders from Persia

dominated trade in the Gulf and even the western Indian Ocean. Some may

even have reached South East Asia and China. 2 More usually western Indian

Ocean ships used Sri Lanka as a transhipment place. Persians, and Axumites

from the Axum port of Adulis on the south west coast of the Red Sea, met

traders from East Asia there. Similarly linking the eastern and western oceans

was the south east coastal area of Coromandel: for example, there is evidence

of Tamil products on the Red Sea coast of Egypt, and an inscription in Thailand from the early part of the Common Era. 3

Valeria Fiorani Piacentini, 'International Indian Ocean routes and Gwadar Kuh Batil

settlement in Makran', Nuova Rivista Storica (May Aug. 1988), p. 308 and passim,

pp. 307 44; R. A. Donkin, Beyond price: Pearls and pearl fishing, origins to the age of

discovery (Philadelphia, 1998), p. 95.

George F. Hourani, rev. and expanded by John Carswell, Arab seafaring in the Indian

Ocean in ancient and medieval times (Princeton, 1951, 1995), pp. 40 9; Philip Snow, The star

raft: China's encounter with Africa (Ithaca, 1989), p. 3; K. Rajan, 'Early maritime activities of

the Tamils', in Himanshu Prabha Ray and Jean Francois Salles (eds.), Tradition and

archeology: Early maritime contacts in the Indian Ocean (New Delhi, 1996), pp. 97 108.

318

Cambridge Histories Online © Cambridge University Press, 201 1

### Islamic trade in the Indian Ocean

Navigation in this period, before the arrival of Islam, could be described as wayfinding. It was a craft, something passed on from generation to generation. Sailors learnt to 'read' the stars, sun, winds, ocean swells, the

colour of the sea and the flight of birds. The magnetic compass came late to

the Indian Ocean as compared with Chinese practice, but the astrolabe was

used in the Indian Ocean from quite early times. By observing stars, this made

finding a ship's position much more precise. 4

Islam and trade in the western Indian Ocean: ships and navigation

Arabs played a role in Indian Ocean trade, alongside many others. From the

seventh century these Arabs were converts to the new faith. In religious terms

this of course marks a fundamental break, but trade, navigation and seafaring

in general were little affected. Arabs, now become Muslims, kept on doing

what they had been doing for some centuries, and kept on sailing to the same

places: the Swahili coast, the Gulf, the Arabian Sea islands, especially the Maldives, above all India, and then sometimes further east.

By this time there is better information about the ships which sailed in the

Indian Ocean. Generically these are called, at least by westerners, dhows. 5

While there were and are very substantial variations within this overall nomenclature, for simplicity's sake it seems best to write merely of dhows

tout court. The hull was made of teak from Malabar in south west India, producing a hull using the carvel method, held together by coir fibre stitching.

There were no keels. They had sternpost rudders, and usually only one mast

and a sail made of matting from coconut. These were the famous triangular

lateen sails. The hulls were double ended rather than having square, transom.

sterns. On the largest dhows there may have been a raised poop deck, with

cabins underneath, but most often the holds were open and there was no deck.

Remarkably heavy cargo, camels, horses, even elephants, could be carried.

The navigator of the dhow in this period, such as at the time of the famous

ninth/ fifteenth century sailor Ibn Madjid, was the mu'allim, who sailed the

R. A. L. H. Gunawardana, 'Changing patterns of navigation in the Indian Ocean and their

impact on pre colonial Sri Lanka', in Satish Chandra (ed.), The Indian Ocean: Explorations

in history, commerce and politics (New Delhi, 1987), pp. 61, 77 and passim for a very useful

overview. B. Arunachalam has published extensively on traditional Indian navigation.

See for example 'Traditional sea and sky wisdom of Indian seamen and their practical

application', in Ray and Salles (eds.), Tradition and archeology, pp. 26181.

Pearson, Indian Ocean, pp. 63 71.

319

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

ship and was responsible for what happened on board. He checked the fitting

out, the stores, gear and loading. He was in charge of the crew and passengers,

looked after their safety and health, and solved their quarrels. All this was laid

down in the contract drawn up before the ship left. It was required to take a set

number of passengers, and a set quantity of their effects. There were also bills

of lading governing the cargo. His duty of care ended when he got the ship

back to its home port.

How did captains find their way over the ocean? There is a contrast here between blue water sailing and finding one's way in more restricted water

ways. To a considerable extent oceanic navigation was still wayfaring. Ibn

Madjid for example provides detail on land sightings for guidance into a

port. He also relied on sightings of the sun and the stars. His work is an example of the pilot guides and navigational literature which were commonplace in the ocean from both the Chinese and the Arab side. It may be

that practical navigational charts were not known before the Europeans, but there certainly were maps. It seems that Arab empirical methods were

more than adequate to determine latitude quite accurately. Yet there is no

doubt that Chinese navigational expertise, at its height from about iooo to

1400 CE, was more advanced, including especially the use of the marine compass.

Chinese ships were also very different from the dhows. Once around Cape

Comorin there were huge ships, which will be described in another chapter, in

the Bay of Bengal. However, this was a rather temporary presence. They came south to the Malay world only from the twelfth century, and may have

been displaced for a time in the mid fourteenth century when the powerful

Javanese state of Majapahit was at its height. Under the Ming, from 769/1368

onwards, Chinese ships re entered South East Asian waters, reaching a mas

sive peak with the Zheng He expeditions of the early ninth/fifteenth century.

Soon after this, long distance Chinese voyaging in these monsters ended. 7

Thus for a time Chinese ships had competed with Muslim owned shipping in

the eastern Indian Ocean. Once the Chinese withdrew, Muslims dominated

here, as they had done all the time in the western ocean. This dominance was

next challenged when the Portuguese arrived at the early tenth/late fifteenth century.

6 G. R. Tibbetts, Arab navigation in the Indian Ocean before the coming of the Portuguese (London, 1971), pp. 59, 192 5.

7 Anthony Reid, 'The rise and fall of Sino Javanese shipping', in V.J. H. Houben, H. M.J.

Maier and W. van der Molen (eds.), Looking in odd mirrors: The Java Sea (Leiden, 1992), pp. 177 211.

320

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

Trading networks and products

By at least the end of the first millennium CE there were sophisticated and

complex trading relations all around the Indian Ocean, and indeed far afield to

China and the Mediterranean, and even Russia and Scandinavia. The most

famous trade product was spices that is, pepper, a bulk commodity, and the

rarer and more expensive fine spices: mace, nutmeg, cloves and cinnamon. The

last named came only from Sri Lanka, the other three fine spices from the

distant Maluku islands. Pepper was found in parts of the Malay world, but most

came from India's west coast, from Malabar. A typical passage for a spice from

the Malukus involved a relay trade. If the destination was the Mediterranean,

then the spice would go via an entrepot in the Malay world from the ninth/ fifteenth century this was Melaka then on to the west coast of India,

then across the Arabian Sea to the Red Sea, and so to Alexandria and waiting

Venetian merchants. Remembering however that three quarters of spices were

consumed within Asia, this journey is much longer than a more typical one,

which for example would involve merely taking pepper or ginger up to China.

The great Islamic Abbasid empire centred on Baghdad consumed vast quanti

ties of spices from the second/ eighth century onwards, as also later did the

Islamic states in northern India.

Spices are the best example of a trade in luxuries. Similar was the trade in

coined precious metals, which was revolutionised from the middle of the eleventh/ sixteenth century by the arrival of floods of gold and then silver from the Americas. The slave trade, especially from East Africa to the 'Abbasid

empire, similarly was a luxury trade, as was that in ivory from the same region. Other trades were in humble essentials, such as cloths and food. One

example here was another form of currency, more widespread than gold or

silver. This was the cowry shells from the Maldives, used all around the ocean

and even further afield, for example to Yunnan or West Africa, as basic currency.

The structure of long distance trade changed fundamentally during the period under discussion. Around 290/900 there were direct passages from

the Gulf to China in one ship, though other trade was done in several ships. By

the end of the eleventh century direct trade in one ship had ended. The trade

became segmented, with one merchant and ship doing the Arabian Sea part to

south India, where the goods were exchanged, and then taken on by other

Detail on the spice trade in M. N. Pearson (ed.), Spices in t/ie Indian Ocean world (Aldershot, 1996), pp. xvi xxxiv.

321

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

ships and merchants to South East Asia, where there was another exchange,

and so to China. South India and Sri Lanka were always places where there

was a halt, and exchange, but the difference is that in the earlier time some

times the same merchant and ship kept going beyond there, while later none

did this.

In the earlier period, from say the second/ eighth century, the very long distance trade from the Gulf to China was handled by Muslim merchants from Persia. It was based on the wealth and stability of the 'Abbasid empire

from 132/750, and of Tang China (618 907 CE). Both had a large demand for

foreign luxuries. In the Gulf, Siraf, on the east bank, was the main centre, where were to be found goods from all over the Indian Ocean, including East Africa. Later Julfar, on the west coast, was important, and later still Hormuz. Another old centre was Daybul, in present day Pakistan. Arabs also took part in this trade, and soon became more important than the Persians. Later some Chinese ships also, from the sixth/twelfth century and particularly in the eighth /fourteenth, traded into the Arabian Sea. However, from the end of the seventh/thirteenth century the direct passage

from Baghdad to Canton declined, and instead emporia rose. Shorter

connected the major port cities of Baghdad, Hormuz, Cambay, Calicut, Melaka and Canton, with many minor routes from for example the Bay of Bengal feeding into this network.

From the sixth/ twelfth century or a bit later, then, there were three segments: the Arabian Sea, the Bay of Bengal and the South China Sea. Chinese and Indians went to Melaka, Persians and Arabs only to India. This

important move towards segmentation was partly a result of unsettled con

ditions at both ends of the route as powerful empires declined, and partly because traders realised that the direct passage in the same ship was inefficient,

given that they had to wait for monsoons at several places. South India seems

to act as a fulcrum in this very long distance connection. Later in this period

other Indians joined in, this time Muslims based in the many emporia on the

west coast, and in the major Islamic state of Gujarat from the thirteenth century. Increasingly the trade east from India was controlled by Indian

Muslims, while Arabs, and a few Persians, were restricted to the Arabian Sea. For many centuries Gujarati merchants, both Muslim and Hindu, were

especially prominent. Hindus from Gujarat tended to setde in port cities on

the Indian Ocean littoral, while Muslims had a flourishing trade north and

west to the Gulf and Red Sea, and east and south to Malabar and South East

Asia. These merchants were based in the port cities in the Gulf of Cambay, of

which Cambay itself was the most important.

322

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

Port cities in the Indian Ocean

There are several ways to categorise ports around the Indian Ocean at this

time. Some owed much to geography, either because they were located on

choke points, or because they had productive hinterlands. Some were pure

exchange centres, others had some industry of their own. Some were sub ordinate to a larger inland state, while others were port city states, or perhaps,

to borrow the South East Asian term, port polities. All of them were by definition cosmopolitan, much more so than the inland.

Where were the major port cities in the Indian Ocean area at this time? 9 Starting in East Africa, in the far south, Sofala provided gold and ivory from

the interior. The gold was mined or washed in the inland Mutapa state in present day Zimbabwe and brought to the coast at Sofala to be taken on to

Kilwa and exchanged for cloth and other manufactures from India and the

Middle East. Kilwa was the great emporium on the coast between roughly

648/1250 and 730/1330, from which time a great mosque and palace date, the

latter being the largest roofed stone building south of the Sahara until modern

times. By 957/1500 the greatest port city was Mombasa, an important centre

of exchange for ivory and gold from the south with manufactures from the

east and north. Malindi was a smaller centre at this time, but Mogadishu benefited from its proximity to the Red Sea and the Hadramawt to be another

important port.

Moving along the coast, Aden was usually a great port city because of its location at the entrance to the Red Sea. There were several ports within the

Red Sea, but the greatest certainly was Jiddah. It was the central mart in the

Red Sea, with goods coming down from Cairo, and up from the whole Indian

Ocean. It also had an important religious function as the maritime gateway to

the Holy Cities.

The situation in the Gulf varied from time to time. At the beginning of this

period, around 184/800 when the c Abbasid empire was flourishing, Sohar was

an important port, with contacts up the Gulf and across to Africa. After it was

sacked by the Buyids from Oman it was replaced by Siraf, on the east coast of

the Gulf south of Shiraz, where large boats were unloaded and their goods

taken in smaller ships to the great cities further north. Going south, ships went

from Siraj to Muscat and Sohar, then either to Daybul or ports in Malabar,

then around Sri Lanka to Melaka, then up to Canton or Quanzhou. Typically,

this trade at first was handled in its entirety by Muslim traders, some Persians

9 Pearson, Indian Ocean, pp. 92 4.

# Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

but increasingly Arabs, and from about 390/1000 became more segmented,

with Chinese coming some of the way, and Muslim Indians also involved as

goods were transhipped and sold on at one or other of these entrepots.

10 The

other great port in the Gulf in late 'Abbasid times, in the fifth /eleventh and

sixth/ twelfth centuries, was Qeys, Qais or Kish, on a small island down the

Gulf from Siraf. Here Indians brought in spices, and people from Yemen, Iraq

and Fars provided silks and cloths, wheat, barley and millet. There also was a

large slave trade, and ivory, gold, wood, skins and ambergris from East Africa.

Horses were sent out to the Deccan. Pearls were another export from this

major port, while there have been many finds of Chinese ceramics.

Hormuz, located on the choke point at the entrance to the Gulf, was always

an important exchange centre, but rose to greater prominence in the ninth/

fifteenth century. Most of the great marts described so far were independent

of any exterior political authority at this time, and most had no major productive role, nor extensive hinterland. Rather they were hinges linking

areas to the north with those to the south and east.

Moving south east from the Gulf there are variations on this pattern. Ports

in the area around the Indus delta drew on a large and quite productive hinterland. Daybul, or Bambhore, at the mouth of the Indus, was a very old

emporium, which declined from the fifth/ eleventh century as a result of silting. It was replaced by Lahori Bandar.

The great ports of Gujarat were certainly major centres of exchange, but

they were located on the maritime fringe of important production centres for

such products as indigo, salqjetre and especially a vast variety of cotton cloths.

The greatest was Cambay. From the seventh/thirteenth century Cambay, and

many other ports within and around the gulf, were not independent city states: rather they were part of the important Muslim sultanate of Gujarat.

Here were huge volumes of trade, skilful merchants and a very well articu

lated network of production and exchange and credit.

The ports further down India's west coast were less important, in part because the interior was less productive. The next major group of port cities

were in Malabar, now the Indian state of Kerala. The dominant port here from

the late fifth /eleventh century was Calicut, ruled by a powerful and independent ruler, the Samudri raja or Zamorin. It was an exchange centre for a

host of 'foreign' goods. Equally important, it was a great collection and

10 Moira Tampoe, Maritime trade between China and the West: An archaeological study of the ceramics from Siraf (Persian Gulf, 8th to 15th centuries AD (Oxford, 1989), p. 124; Hourani, Arab seafaring, p. 69.

324

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

distribution centre for the pepper which was harvested in abundance in the

interior. Several other port polities were important at different times in this

region. One of them was Cranganore, some 25 kilometres inland from the

seashore and located on several rivers. There was a vast array of merchants

there dealing in spices. 11 None of these Malabar ports were centres for manufacturing, yet neither were they merely exchange centres. In these cases, location that is, that they made obvious stopping places for trade from west to east and back again joined with an interior where much pepper

was found to ensure that for many centuries there would be major ports in this

region. The main traders in Malabar were Muslims from the Gulf, and later

from the Red Sea. Traders from other areas of India were also present, such as

those from Coromandel and Sri Lanka, who had ethnic and religious ties with

the Malabar locals. However, the most important Indian visitors to Malabar

were those from Gujarat, both Hindu and Muslim. The rulers were Hindu, but they encouraged trade, whether by Muslims or anyone else, because trade

brought them customs revenues.

This also applies quite exactly to Sri Lanka, and its major port of Colombo.

for its location paralleled that of the Malabar ports, while the island was the only place where true, fine cinnamon was produced. Moving around to

the Bay of Bengal, towards the end of the period on the Coromandel coast the

major port was Pulicat, which drew on production, especially textiles, from

the great Hindu kingdom of Vijayanagara, but was little affected politically

by it. There were, however, a host of others; Kayal, for example, was an important centre for pearl fishing. In Bengal the most important port was Chittagong, which similarly was little controlled from the political centre of

Gaur. The last major port relevant to the discussion was Melaka, which rose to

prominence in the ninth/fifteenth century both as a great trade centre, maybe

the greatest of all in the second half of this century, and as a dissemination

centre for Islam.

Politics in the port cities

The rulers of the port cities in Malabar, Coromandel and Sri Lanka were not

Muslim; in the other areas they were, that is on the Swahili coast and in the

Maldives. Nevertheless, in all of them merchants, mostly Muslim but some

others also, enjoyed a very large degree of autonomy. Muslims from specific

11 A. Vallavanthara, India in yoo AD: The narrative of Joseph the Indian (Kottayam, 1984), pp. 152 5.

325

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

areas lived together, and had their own heads. These heads usually settled any

points of contention within the group on their own, or perhaps after taking

advice from some sort of council of more senior members of the community.

Disputes between members of two groups were settled by negotiation between the respective heads. It was very rare indeed for the political author

ity, the sultan of Melaka or the Samudri raja of Calicut, to be involved even in

criminal cases, and almost never in commercial disputes.

Many historians used to claim that the trade of the Indian Ocean in this period was increasingly handled by Muslims: the ocean was a 'Muslim lake'.

There is certainly much truth in this, even if Hindus, Armenians and Jews also

participated. Nor is this a matter for wonder, for Islam had spread from the

heartland of the Red Sea all around the Indian Ocean over water. One could

predict then that coastal people were most likely to be converted first, and

indeed this was the case. However, there was an important change during the

period, for while earlier it was Muslims from the Gulf, and then Muslim Arabs

from the Red Sea and Egypt who dominated Indian Ocean trade and its markets, later it was local converts from such coastal areas as Gujarat and

Bengal, and Middle Eastern Muslims who often had migrated to the Indian

Ocean area, who had the cream of the trade, especially that going past India to

the Bay of Bengal and beyond. Many of these Muslim traders were part of far

flung networks, these being based often not only on trade but also on adherence to a particular religious leader or sect. Merchants and religious

specialists worked hand in hand, indeed could be the same person, in that a

trader could well adhere to a particular Sufi order, and a religious specialist

would trade on his own behalf. One example is traders based in the Iranian

town of Kazarun, whose community solidarity was based on locality as well as

common religious practice. This particular network had people in Cambay,

Calicut, Quilon, and Canton in China. We will say more about this particular

Sufi order presently. 12.

### Islam and trade

The focus now moves to a description of these scattered Muslims in the areas

under discussion, stressing their religious activities. Before attempting an area

by area survey, certain general themes can be sketched. Relatively easy and

even routine maritime links made possible the creation of an Islamic littoral

12 Ibn Battuta, The travels oflbn Battuta, trans. H.A. R. Gibb, 4 vols. (London, 1958 94),

p. 320. (The volumes are paginated consecutively.)

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

community all around the shores of the Arabian Sea, and indeed further east

also. Travel by religious specialists was something new in this area. Previous

travellers had been exclusively traders, apart from an occasional and very

unusual military expedition. Now some travellers were primarily concerned

to inculcate or rectify Islam, though, as is well known, many also traded on the

side. To allocate priority to one or the other motive is hazardous and of dubious validity anyway. The connection is important, for Muslim traders necessarily travelled in order to trade, and so could influence widely scattered

areas around the ocean rim. Risso notes that 'Islam is often described as especially well suited to merchants who needed to conduct complex trans actions, and to travel. Islam not only sustained minority Muslim merchant

communities in non Muslim regions, but also attracted many merchant con

verts.' She then sounds a warning that 'Islam cannot be reduced to commerce,

and commerce in the Indian Ocean region cannot be reduced to Muslims.' 13

Certainly the religion as such had a positive attitude to trade and making profits, deriving no doubt from the Prophet's own early history as a trader.

The oceanic context is important, for arguably it dictated a particular sort of

Islam. Ross Dunn has put the contrast between coastal Islam and that of the

heartland very well:

In the Middle East an individual's sense of being part of an international social

order varied considerably with his education and position in life. But in

Indian Ocean lands where Islam was a minority faith, all Muslims shared

acutely this feeling of participation. Simply to be a Muslim in East Africa, southern India, or Malaysia in the fourteenth century was to have a cosmo

politan frame of mind.

This was reinforced by the coastal location and the fact that most of them were

traders, and so had to be aware of distant markets and people and places. 14

## The spread of Islam

In most of these littoral areas Islam was at first represented by visiting Arab

traders. It is possible to sketch a continuum, to the extent the data allow. First

was the arrival of Arab Muslim traders to the various coastal areas, these to be

seen as merely continuing an existing and long established Arab trade from

long before Islam in most areas. The first mosques were built to service them.

13 Patricia Risso, Merchants and faith: Muslim commerce and culture in the Indian Ocean (Boulder, CO, 1995), pp. 6, 7.

14 Ross Dunn, The adventures oflbn Battuta (Berkeley, 1986), p. 116.

327

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

The New Cambridge History of Islam

It was in the sixth/twelfth century that there was a wave of conversions, as

seen by the larger mosques, though why this occurred in so many places at

roughly the same time remains something of a mystery. Several of the areas

covered in this chapter have firmly held origin narratives to do with the conversion of a local ruler thanks to some miracle, or the arrival of a particularly persuasive Arab exemplar. The ruler converted and then others

followed him.

Parkin has suggested that it is more accurate to write of the

'acceptance' of Islam, which is likely to take longer and to be reciprocally inscribed in pre existing custom and cosmology. The term conversion pre supposes a shift from one to another unambiguously defined religion. Acceptance is less visibly dramatic and does not mean abandonment of a pre existing cosmology. Yet it may well typify much Islamisation in the region

in allowing for Islamic and non Islamic traits to inter mingle steadily. 15

This means that there was additive change much of the time, as opposed to

substitutive change. The former implies that an existing body of belief is added

to, while the latter means existing notions are cast aside and replaced. Conversion then was a process rather than an event, and might extend over

several generations.

Muslim travellers to areas already nominally Muslim often found what they

considered to be deviations and lax practice in some of the areas they visited.

Either by example, or more proactively by exhortation, they worked to improve the quality of Islam around the shores of the ocean. Ibn Battuta, whose travel account will be copiously used in this chapter, was one such.

(While the reliability of his account of South East Asia has been questioned,

his observations on the coasts of the Arabian Sea are usually confirmed by

other sources, and can be considered to be authentic. )The work of exemplars

like him again points to conversion being a process rather than an event. Normative Islamic observance may have taken some generations to be fully

implemented; indeed this process continues today. This is not, however, to

decry the continuance of local practices, some of which may not have been

completely in accord with the sharfa. It is not a matter of erecting some monolithic and unchangeable model of 'pure' Islam against which local

practice can be evaluated, or even condemned. Susan Bayly correctly asked,

'what do we actually mean by the terms "purist" and "syncretic" and are these

15 David Parkin and Stephen C. Headley (eds.), Islamic prayer across the Indian Ocean: Inside and outside tfte mosque (London, 2000), p. 3.

328

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

really useful categories to apply to the historical study of Asian Muslim

communities?' 1

Travelling religious authorities

Most of the normative travellers came from the area conventionally perceived

to be the Muslim heartland, often from southern Arabia, and especially the

Hadramawt region. Many men left this impoverished and infertile homeland

to settle abroad, carrying with them notions about true Islamic observance.

Martin in fact finds discrete waves from this area: to India after 596/1200, to

East Africa after 648/1250 and fifty years later to South East Asia. 17 This

emigration continues today. This is not, however, to say that they were the

only traders and proselytisers: in a major port city like Calicut Muslims hailing

from Morocco to Sumatra were present. There was a constant flow of people

around the Arabian Sea coasts. Some of this was local, men for example going

from one southern Indian coast to another, or down to Sri Lanka. Other intra

oceanic circulation consisted of men travelling on circuits all around the shores. Some routes were more directed, especially back and forth to southern

Arabia, and further north to the Holy Cities, and to Cairo and Baghdad. Religious exemplars came out from the perceived heartland, some 'locals' visited there for instruction and to undertake the hajj. This religious circu lation often mirrored the major trading patterns in the Indian Ocean which

have already been sketched.

The continuing prestige of Arabs, however defined, is well shown in the way many local converts insisted on an Arab ancestry somewhere in the past.

Objectively such claims are problematic, to say the least, for it seems that

almost no free married Arab women moved to these areas. Thus even when

people claimed an Arab background, their progeny over several generations

became less and less Arab. So much more for local converts, who in South Asia

and Sri Lanka at least came from lower areas of society; even so they often

claimed Arab descent. It is notable that the many origin narratives in the area

link the origins of Islam to the Prophet or his family, or more vaguely to Arabia, and not to inland powers like the Mughals or Turks.

16 Susan Bayly, 'Islam in southern India: "Purist" or "syncretic"?', in C.A. Bayly and

D. H. A. Kolff (eds.), Two colonial empires: Comparative essays on the history of India and

Indonesia in the nineteenth century (Leiden, 1986), p. 36.

17 B. G. Martin, 'Arab migration to East Africa in medieval times', International Journal of African Historical Studies, 7 (1975), p. 370.

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

We have described the trade and economic role of the great port cities strung around the Indian Ocean littoral, and the way shifts in long distance

trade routes influenced importantly their rise and fall. They were where the

Islamic elite lived, and where impressive jam? masjids were located. They were distinctive from the interiors economically, and in terms of being much

more cosmopolitan. This distinctiveness also applies to religion. First, the port

cities were largely Muslim, or had important Muslim groups within their populations. This did not apply to the interiors of any of the areas to be discussed in this chapter. Second, a vital connecting link which set off the coast

from the interior was the dominance of the Shafi'i madhhab on the coast, as

opposed (in India) to the Hanafi interior. It may be that the Shafi c i school fitted

better doctrinally with the needs of travellers and traders, and men living in

areas not part of dar al islam. This school, named after Muhammad ibn Idris

al Shafi'i (d. 204/820), was very influential in the Islamic heartland in the centuries preceding the emergence of the Ottoman empire, and indeed up to

the sixteenth century. Today it is the dominant school in East Africa, the Comoro and Maldive islands, the west coast of India, Indonesia, and also in

part of Egypt and in its original home, the port towns of southern Arabia and

the Gulf. While it is important not to overemphasise differences between the

four orthodox Sunni madhhabs, the Shafi'i school was much more relaxed about Muslims living in areas ruled by non Muslims, while in theory at least.

Malik! Muslims should avoid this completely. Yet Ibn Battuta, a Maliki, wrote

positively about the favourable treatment that the Hindu rulers of Malabar

gave to their Muslim residents and visitors.

It was during this period, from around the fifth/ eleventh century, that followers of the mystical Sufi path gradually became integrated into norma

tive, book based, Islam. From this time various Sufi orders were present and

influential. The Qadiriyya order was prominent around the shores of the ocean, and seems to have had a close relationship with the Shafi'i madhhab. Ibn

Battuta also found much evidence of an influential, though now extinct, Sufi

order based on the Persian town of Kazarun.

This chapter will by and large be concerned with slow moving change, a gradual accretion of numbers of Muslims and changes in their practice. However, there seem to be two more dramatic gaps. The change in long distance trading patterns which was mentioned above marks one important

caesura in the period. In particular, the end of the direct route between Baghdad and Canton led to the rise of several port cities, especially Calicut,

where goods were exchanged. This in turn led to Muslim settlement in, as

opposed to visits to, these port cities; the consequences for the spread of Islam

330

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

are obvious. The other is the arrival of the Portuguese at the end of the ninth/ fifteenth century, which is covered in detail in Chapter 12. For eco nomic and religious reasons their hostility was focused precisely on Muslims. Nevertheless, they had very limited success in their attempts to take over existing Muslim dominated trade routes, or in blocking access to

the Holy Cities. Preaching, conversions and solidification of the faith kept

going under their noses. They fulminated against the way people they called

'cacizes' travelled around the ocean with impunity, spreading Islam as they

went and indeed having much more success than did Portuguese mission aries. Some of them even took passage on Portuguese ships. 1

The arrival of Islam on the Swahili coast

Arab traders from Yemen and further along the southern Arabian coast had

been visiting the Swahili coast since about the beginning of the Common Era. 19

When they converted they continued to trade, and from the second/eighth

century in the northern port city of Shanga and other places there is evidence of

rudimentary mosques, made of timber and mud, which serviced these visitors.

No doubt there was interaction, and intermarriage, with the local Bantu population, but the earliest Muslim accounts of East Africa reflect very clearly

that the locals had not converted. The fourth/tenth century 'Wonders of India'.

a collection of Arab stories, describes 'Zanf as a strange, uncouth place, with

sorcerers, cannibals, strange birds and fishes. 20 Al Biruni in the early fifth/

eleventh century still found East Africa to be a wild and largely un Islamic

place. 21

Beginning in the sixth/twelfth century, or a few decades before, large scale

conversions took place among the indigenes. In material terms this can be

seen in the way the mosque at Kilwa, the most important port city from about

648/1250 to 730/1330, was enlarged and now constructed in stone. By around

700/1300 it measured some 12 metres by 30 metres, implying a very large

18 A caciz is a Muslim religious specialist. For details see M. N. Pearson, Pious passengers:

The hajj in earlier times (Delhi and London, 1994), pp. 71 2.

19 For an earlier discussion of Islam on the Swahili coast see my 'Gateways to Africa: The

Indian Ocean and the Red Sea', in Nehemia Levtzion and Randall Pouwels (eds.), The

History of Islam in Africa (Athens, OH, 2000), pp. 37 59. By far the best modern survey is

Mark Horton and John Middleton, The Swahili: The social landscape of a mercantile society (Oxford, 2000).

20 Buzurg ibn Shahriyar, The hook of the wonders of India [Kitah alAjaid al Hind], trans, and

ed. G. S. P. Freeman Grenville (London, 1981), pp. 10, 31 6, 38, 102, 105.

21 al Biruni, Alheruni's India, trans, and ed. Edward Sachau, 2 vols. (Delhi, 1964), vol. I, p. 270.

331

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Muslim resident population. 22. By this time there were more than thirty communities on the coast which had one mosque, and many had several. 23

These mosques were located in the port cities strung down the East African

coast, over a length of some 3,000 kilometres from north to south. Some of

them, especially in the south, drew in goods from the interior: gold, ivory and

slaves were the main products. These were exchanged for imported goods, for

there was little manufacturing on the coast. Cotton cloths from India were

overwhelmingly important as imports, though obviously they have left few

traces as compared with considerable finds of pottery, and even porcelain

from far distant China. The Swahili in the port cities seem to have played a

comparatively passive role. There is no evidence of their sailing far, except up

the coast to southern Arabia and the Red Sea. Nor did they travel inland to

collect goods for export: rather, particular tribes, none of them Muslim, brought goods to the coast. Certainly they were mediatory not only in economic terms but in other ways also: between Asia and Africa, between Islam and non Islam. The Swahili were essentially Bantu, and a trickle of visitors and settlers from Arabia did not change this. Yet they were set apart

from their fellow Africans by their exposure to a wider Indian Ocean world.

Their port cities were much more cosmopolitan than the interior, as indeed

were other port cities located on coasts with much more advanced civilisations

close inland, such as those in India. Conversion led to them becoming more

isolated from their Bantu kin. Before the coming of Islam they were quite small settlements, with little trade. Over the centuries covered in this chapter

they became much bigger, richer and more cosmopolitan. Most important,

their inhabitants were now followers of a great tradition religion, and so were

set off from the interior Bantu.

The conversion of these port city dwellers was a slow process, really an accretion of Islamic practice, something which applies in all the areas under

discussion. Nurse and Spear provide a succinct account of Swahili motivations:

Many townspeople . . . operated in a wider world than the microcosm of the  $\,$ 

village, living in towns with other peoples, sailing from town to town along

the coast, and trading with people from across the Indian Ocean. These people lived in a macrocosmic world inhabited by peoples speaking different

languages, having different ancestors, and working in different occupations.

- 22 John Sutton, A thousand years of East Africa (Nairobi, 1990), pp. 67 8.
- 23 Randall Pouwels, 'The East African coast, c. 780 to 1900 CE', in Levtzion and Pouwels

(eds.), Islam in Africa, p. 252.

332

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

In this world the beliefs of the microcosm were too parochial; what was needed were beliefs that were universal. And so townspeople began to adopt

Islam, and in so doing they adopted a set of beliefs and a framework for action

that were held in common by others in the town, by people in other towns,

and by people from the whole Indian Ocean world. 24

This was very much a reciprocal process, not a matter of an imposition of a

new faith from outside. Horton some time ago produced a strong statement

which reflects well the current scholarly consensus:

The East African coast was always inhabited by African communities, who in

time gradually absorbed the culture and teachings of Islam as they were drawn into contact through commercial dealings and missionary activities.

The archaeological evidence shows how first material culture, then architec

ture, and finally religion itself was grafted from the Islamic world onto the

East African coast. There was no interest in either conquest or settlement but

rather in the establishment of reliable local trading partners. 25

### The Swahili coast and a wider world

Muslims from the heartland, from Yemen, Hadramawt and Oman, moved south to East Africa for various reasons. Often they were traders, for the strong nexus between trade and the spread of Islam has been much noted all

over the Indian Ocean world. Some moved as a result of push factors, in other

words they exchanged a life of poverty in the inhospitable regions of southern

Arabia for the more benign region of East Africa. But what may be the very

first Muslims to move to the far south seem to have been people escaping religious persecution. These were the followers of Ibadi Islam, part of the heterodox Khariji group, originating from Oman and further into the Gulf. This group moved further and further south, and by the eighth/fourteenth century the coast was thoroughly Shafi'i Muslim. The decline (until the early

thirteenth/late eighteenth century) of Omani influence may have been a result of changes in Indian Ocean trading patterns. When Baghdad was at its

height, from about 132/750 to 442/1050, trade with East Africa linked in to the

great Baghdad Canton route. As this declined East African trade became oriented to southern Arabia, especially the Red Sea and Hadramawt area. Nevertheless, several of the ruling dynasties of the coastal port cities proudly

24 D. Nurse and T. T. Spear, The Swahili: Reconstructing tfte history and language of an African society, AD soo isoo (Philadelphia, 1984), pp. 94 5.

25 M. C. Horton, 'Asiatic colonisation of the East African coasdine: The Manda evidence', Journal of the Royal Asiatic Society, 2 (1986), p. 211.

333

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

claimed to come from Shiraz: Kilwa from the fourth/tenth century, and also

Mombasa, Malindi and Zanzibar. 2, These rulers shared a common narrative of

origin, and had lineage ties with each other. The claim of a direct link with

Shiraz, or the Gulf in general, can be discounted. It is revealing of the change

from Omani influence to that from further west along the southern Arabian

coast that from late in the seventh /thirteenth century the rulers of Kilwa, the

dominant port city at the time, were a family, the Mahdali, of sharifs from Yemen. One of them did the hajj in 813 14/1410 11, and then spent time at

home in Yemen before returning to Kilwa. The ruler of Mozambique was a

Sharif who claimed kinship with the ruling families of the Somali coast and

Kilwa. Also in the seventh/thirteenth century the Nabhani rulers of Pate arrived from Oman, and continued in power into the thirteenth/nineteenth

century. Over time these ruling families indigenised, giving something to the people they ruled and getting much from these same subjects. They rapidly became merged into the Swahili world. In other words, through acculturation and intermarriage they became another element, albeit a poli

tically important one, in the Swahili world.

These rulers, and the many other anonymous sojourners or settlers from Arabia, especially Yemen, brought with them very considerable prestige. They of course brought the Shafi'i madhhab. They also brought with them,

if they were sharifs or sayyids, very considerable baraka, or prestige, based on

their claim to be direct descendants of the Prophet. As an twelfth/eighteenth

century Hadrami sharif wrote rather self servingly,

They are the guarantee of the earth from fear Guides of the People along Right Paths Take refuge with them from catastrophe Ask God's help through them. 27

Such men were very influential by the middle of the seventh/thirteenth century at least, though this was never a matter of large scale migration. Some

were reformers who tried to end non Islamic practices in coastal religion, while others merely integrated into local coastal society. This learned elite

retained important ties back to their homeland and its famous Islamic centres.

It was also from the seventh/ thirteenth century that contact with, and migration from, the Hadramawt flourished, over time perhaps becoming more important than that from Yemen further west. Coastal towns in the

26 On the Shirazi matter the best modern summing up is Horton and Middleton, Swahili, pp. 52 61.

27 Martin, 'Arab migration', p. 390.

334

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

Hadramawt such as al Shihr and al Mukalla, and also inland towns, connected

to the Swahili coast. As Martin noted, 'Sometimes the appearance of a sharif

triggered a religious revival or led to acceleration of the process of ongoing

islamization.' A prestigious migrant might marry the daughter of a local sultan, and over generations the Arab 'blood' was diluted and the lineages'

baraka diminished. Then another migrant might come in from Yemen or Hadramawt with fresh new baraka and he would take over. An example of an

influential lineage is that of Abu Bakr bin Salim, whose tomb is at Inat, near

Tarim in Hadramawt. This famous saint died in 992/1584. His sons moved to

East Africa during his lifetime, to Pate. Later members of the dynasty spread as

far as the Comoro islands, Lamu, Mombasa and Zanzibar. 2 Indeed, it may

have been a member of this lineage that a Portuguese observer noted in Pate

about 978/1570. He wrote that Pate 'has considerable trade with Mecca [sc. the

Red Sea] and other parts. The town is very large and has many buildings. It was here that a Moorish caciz, the greatest in the entire coast, resided.' 29

There is almost no contemporary information on any Sufi presence in Fast

Africa during this period. However, all over the world of Islam most of the great

scholars and 'ufomff were also members of Sufi orders. This being the case, it

would be extraordinary indeed if the scholars on the Swahili coast were not also

Sufis. There is a much clearer picture of the situation during the colonial period,

and it may not be completely invalid to 'read back' from here to this period. In

the colonial period the most influential brotherhood was the austere Alawiyya

one, whose main shrine was at Inat. There is some detail on this and other

brotherhoods only from the thirteenth /nineteenth century, though there is no

doubt that the Alawis had been tied in with the various sharif lineages for centuries before this. The same is probably true for the Qadiriyya order, followers of Abd al Qadir, whose adherents in the colonial period were scattered

from West Africa to Indonesia. As we noted earlier, there is a strong link between jurists of the Shafi c i school and Sufis who follow the Qadiriyya order.

The Portuguese, who were firmly opposed to these Muslims, even so provide important information which particularly reinforces the link between

trade and religion. In 903/1498 the first Portuguese fleet, under Vasco da Gama, in Mozambique found a Muslim who came from near Mecca, and

a pilot on one of the ships. Later in his voyage he received an ambassador from

the sultan of Malindi, who he noted was a white Moor, as compared with a

local convert, and also a sharif, that is, according to the Portuguese, a priest.

28 Ibid., pp. 378 82.

29 Quoted in Pearson, 'Gateways to Africa', p.

# Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

A letter to the Portuguese king from Mozambique in 914/1508 claimed that

'these others who do the damage are merchants and foreigners, one from Ormuz, another from Aden, others from other parts and they are men of knowledge who have traded all their lives and these are the ones who should

be expelled'. 30

The much quoted travel account of Ibn Battuta can give us something of the flavour of this very cosmopolitan interchange in the mid fourteenth century, when this prestigious and experienced Muslim scholar was on the

coast. In 731/1331 he arrived at Mogadishu. He was immediately singled out as

a person of importance, perhaps even one with baraka. 'When the young men

came on board the vessel in which I was, one of them came up to me. My companions said to him "This man is not a merchant, but a doctor of the law," whereupon he called out to his friends and said to them "This is the

guest of the qadV" He went ashore and was told, 'It is the custom that whenever there comes a jurist or a sharif or a man of religion he must first.

see the sultan before taking a lodging/ Arriving at the sultan's residence, 'one

of the serving boys came out and saluted the qddT, who said to him "Take word

to the intendant's office and inform the Shaikh [sc. sultan] that this man has

come from the land of al Hijaz.'" He was given robes, including a tunic of Egyptian linen, a furred mantle of Jerusalem stuff and an Egyptian turban. He

leaves a picture of a very Islamic town, where the sultan, who spoke Arabic

although his first language was Maqdishi, used a type of ceremonial parasol

which was introduced by the Fatimids in Egypt and which spread all over the

Muslim world. There were many jurists, sharlfs and people who had done a

hajj, and shaykhs. Ibn Battuta said little about Mombasa, but in Kilwa, then at

its height of power and riches, he found the sultan to be very generous. He

often raided in the black interior, and set aside one fifth of the booty for the

purposes set out in the Qur ] an: 'whenever he was visited by sharlfs he would

pay it [this fifth] out to them, and the sharlfs used to come to visit him from al

Iraq and al Hijaz and other countries'. 31

The nature of Islam on the coast

The description earlier of how becoming Muslim is a process rather than an

event, a matter of adding on Islamic ideas to existing beliefs, raises the

30 Quoted in Michael Pearson, Port cities and intruders: The Swahili coast, India, and Portugal in the early modern era (Baltimore, 1998), p. 61.

31 Ibn Battuta, Travels, pp. 374 81.

336

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

controversial matter of the 'purity' of Islam at this time. Ibn Battuta, who was

critical enough in other places he visited, cast no aspersions on Swahili Islam.

Horton and Middleton claim there is little evidence of syncretism; for exam

pie, the importance of spirits in coastal Islam is a later development, beginning

from the end of slavery. However, they also note that there are really two

religious trends: din, religion, and mila, custom. While not completely sepa

rate, the former includes the Qur'an, the hadith and learned writings, all of this

in Arabic, while the latter predates Islam, and is often communicated orally in

the local language. 32

Testimony from the early Portuguese must be used with caution, given their anti Muslim attitudes. They took malicious delight in finding fault. Yet it

is perhaps revealing that they noted many examples of what they claimed to

be lax Islam on the coast in the sixteenth century. In 903/1498 the ambassador

of the ruler of Malindi was 'a white Moor and sharif, that is priest, and at the

same time a great drunkard'. One Jesuit debated with a senior Islamic scholar,

who believed that Muhammad was the first man created by God. In 949/1542

in Malindi the Jesuit missionary Francis Xavier was told by an Islamic notable

that the locals were quite unobservant. Once there had been sixteen mosques,

but now only three, and these little frequented and badly served. 33

What influence did the Portuguese political presence on the coast have on

Islam? While they had friendly relations with the ruler of Malindi, their main

effort in the sixteenth century was further south, below Cape Delgado. There

is no doubt that in this area Muslim trade was disrupted to an extent, and

doubt contact with Islamic areas further north was hindered, if not broken. It

may even be that this contributed not only to a diminution of contacts, but

flowing on from this that the 'quality' of Islam was changed, or in other words

Islam in the south was more indigenised precisely because contact with

normative centre was blocked. The malicious comments from Portuguese on

the quality of Islam which were quoted above may bear this out. There is another example of what may well be the effects of Portuguese hostility on the quality of Islam in the south. An account of Sofala, in the far south, from

996/1588 noted that:

The Mahometans that at this present doe inhabite those Countries, are not

naturally borne there, but before the Portugals came into those quarters, they

Trafficked thither in small Barkes, from the Coast of Arabia Felix. And when

the Portugals had conquered that Realme, the Mahometans stayed there still,

- 32 Horton and Middleton, Swahili, pp. 180 1.
- 33 Pearson, Port cities and intruders, p. 61 and sources there cited.

337

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

and now they are become neither utter Pagans, nor holding the Sect of Mahomet. 34

Late in the tenth/ sixteenth century, in response to the threat of Ottoman attacks, the Portuguese established a strong base further north in Mombasa,

where Fort Jesus was built. The result seems to be that contact with the perceived heartland was reinforced further north again, in the Lamu and Pate

area, partly as this area was closest to the centre anyway, and partly as Portuguese power was seldom evident this far north. The broad pattern in

this early modern period seems to be of Pate and Lamu maintaining close contacts, and, once the power of the Portuguese had waned late in the eleventh/seventeenth century, spreading their ideas further south to areas

which had been to an extent cut off from the heartland. Yet although the Portuguese, for both religious and economic reasons, opposed the Muslims, it

is important not to exaggerate their success. Horton and Middleton point out

that there were many mosques, tombs and houses built in the tenth/sixteenth century. 35

## Islam reaches the Maldive islands

The Maldives consist of about 1,200 islands, though fewer than 200 of them are

permanently inhabited. Lying as they do astride the major route from the Red

Sea and southern Arabia to India and Sri Lanka, they have long served as places to trade, or merely to take on food and water. The only products of any

note are the many uses of the coconut palm (coir thread from the Maldives

was considered to be especially strong), and cowry shells, which served as

humble currency for many centuries all around the shores of the Indian Ocean, and indeed as far as West Africa. This connection with the trade of

the Indian Ocean is typical of all the coastal regions covered in this chapter.

There is also evidence of continuing ties with the heartland of Islam. Another

theme is the importance of a conversion narrative, that is, that Islam was brought to the islands by a particular historic person at a particular time. Finally, Ibn Battuta, the main authority, went to some lengths to praise the

quality of Islam while he was resident, though he and others also mention some practices which may not be completely 'orthodox', in Swahili terms mila

perhaps as compared with Ami.

- 34 Quoted in Pearson, Indian Ocean, p. 176.
- 35 Horton and Middleton, Swahili, p. 84.

338

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

The first authenticated settlers in the Maldives were Sinhalese, who arrived

from around 500 BCE. Archaeological remains show that from around 300 CE  $\,$ 

Theravada Buddhism was supreme, as shown in numerous monasteries and

stupas. A reminder of this Sinhala Buddhist past is seen in the language of the

Maldivians, which is Divehi, an Indo European language closely related to

Sinhalese, and which used to be written in a script like early Sinhalese scripts. 36

The Maldives lie on the direct route between India and southern Arabia, so

one can assume that they were visited by Arabs and others long before Islam,

indeed probably once the monsoon wind system had been worked out. 37 It is

likely that the first Muslims arrived very soon after the life of the Prophet, if

not during his lifetime. Certainly the charts in Tibbetts's work on Arab navigation show the Maldives were well known and visited. 38 Some Muslims settled and intermarried. However, it was only in the twelfth century

that the local population was converted to Islam.

## The Maldivian origin narrative

The traditional version of how Islam arrived is best told by Ibn Battuta, who

spent eighteen months in 744 5/1343 4 in the islands. His account constitutes

an excellent example of an origin narrative, one which is widely and officially

accepted in the islands today. 39 There are however several variant versions of

the narrative, and these will be noted below as examples of how Muslim communities can modify and change historical events according to present

circumstances.

Trustworthy people told Ibn Battuta that the islanders used to be infidels.

Each month a jinn would come from the sea. The islanders would take a virgin

girl to the idol (Buddhist) temple on the seashore, and when they came back in

the morning they would find that she had been violated and killed by the jinn.

Each month they drew lots to see whose daughter was next to undertake this

melancholy task. Then in 548/1153 a man from the Maghrib came among

36 Clarence Maloney, People of the Maldive islands (Bombay, 1980), p. 104; Ef 'Maldives'

(Andrew Forbes). The fundamental study of Maldivian Islam for this period is Andrew

 $\ensuremath{\mathrm{D}}.$  W. Forbes, 'Southern Arabia and the Islamicisation of the central Indian Ocean

archipelagos', Archipel, 21 (1981), pp. 55 92.

37 Albert Gray's long appendix 'Early notices of the Maldives' in Francois Pyrard, The voyage

of Francois Pyrard of Laval to the East Indies, the Maldives, the Moluccas and Brazil, trans, and

ed. Albert Gray, Hakluyt Society, nos. 76, 77, 80, 2 vols. (London, 1887 9), vol. II, part 2,

pp. 423 508 shows copious Muslim knowledge of, and visits to, the Maldives before their conversion to Islam.

38 Tibbetts, Arab navigation, passim.

39 Ibn Battuta, Travels, pp. 829 30.

339

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

them, called Abu'l Barakat al Barbari, who could recite by heart the holy Qur'an. He lodged in the house of an old woman. One day she was very upset,

because her only daughter had been chosen. Having made his ablutions, Abu'l

Barakat, being beardless, went in her place, and spent the night reciting the

Qur'an. When the jinn came he heard the recital and plunged into the sea. The

old woman and her relatives came in the morning, expecting to have to collect

a body and burn it. Instead they found Abu'l Barakat alive and well, still reciting the Qur'an. He was taken before the king, and expounded Islam to

him to explain the miracle. Impressed, the king promised to convert if Abu'l Barakat could repeat his performance next month. He did so, and the

king, his family and courtiers all converted, as did the rest of the islanders soon

after. By the seventh/thirteenth century Buddhism had been totally replaced

by Islam, of the Malik! madhhab, which was what Abu'l Barakat, and also Ibn

Battuta, followed.

There are some minor variations and additions to Ibn Battuta's account, which do not however alter the basic story in any important respect. Different

names, and places of origin, are given to the sage. Rizwan Ahmad quotes the

version from the Ta'nfeh, the Maldivian state chronicle. The agent was Maulana Shaykh Yusuf Shams ud din of Tabriz. He arrived in the Maldives

but failed to convert the locals, who wanted him to perform a miracle to demonstrate his credentials. The sage obliged by showing a great man whose

head nearly touched the sky. The terrified king and local inhabitants converted

at once, and the king also forcibly or otherwise got the population of all the

islands to convert. He was given the tide of Sultan Muhammad. This occurred

in 548/1153, when he had reigned thirteen years, and he reigned another thirteen years as a very pious and observant Muslim, after which, in 561/1166, he set off on hajj. Shaykh Yusuf died and was buried in Male and

his tomb is greatly venerated. 40 Some versions name the king who converted

as Kalaminja when he was a Buddhist, and subsequently Sultan Muhammad

al 'Adil. He had reigned for twelve years as a Buddhist, but the times were

bad. After the conversion, peace and happiness prevailed. In 561 / 1166 he set off

on a hajj, and never returned; this is a common part of most such origin narratives, where the original convert leaves for the holy places after some

time. Another variant has the sage accompanying the virgin to the Buddhist

temple and protecting her by chanting the Qur'an. 41 A very confused popular

40 Quoted in Rizwan A. Ahmad, 'The state and national foundation in the Maldives',

Cultural Dynamics, 13 (2001), pp. 295 6, and passim for various versions.

41 V. Vitharana, Sri Lankan Maldivian cultural affinities (Polgasovita, 1997), pp. 5 12, 192.

340

Cambridge Histories Online © Cambridge University Press, 201 1

## Islamic trade in the Indian Ocean

version on one website says that it was Ibn Battuta who confronted the jinn, and

as a result was made aadi, and married the sultan's sister! 42 Yet another version,

widely believed today, has it that it was the king who raped and killed the young

girls. The story of an arrival from the sea was a subterfuge. It has even been

claimed that a saint called Shaykh Barkhandle, who spread Islam in the interior of

the Horn of Africa between 700 and 900 years ago, and whose religious name was

Shaykh Yusuf al Kawneyn, is the same saint whom the people in the Maldives call

Saint Abu ] l Barakat al Barbari. 43 However, the tomb of this Somali saint is in

Somalia, while the tomb of Abu'l Barakat is in the grounds of the Hukuru mosque in the capital of Male. Built in 1066/ 1656, this is the oldest mosque in

the Maldives. The tomb is an object of great veneration and pilgrimage.

Sultan Muhammad al c Adil succeeded in initiating a series of six dynasties

consisting of eighty four sultans and sultanas that lasted until 1351/1932. There

followed a puppet sultan controlled by the British, then a revolution and then

a new sultan who was deposed in 1388/1968. In our period the only caesura

occurred between 965/1558 and 981/1573, when the Portuguese occupied

Male. Their vigorous anti Muslim activities had an important consequence

for the islands. Many of the Maliki 'ulam<V were killed by them. After they

were driven out a famous shaykh from Hadramawt, Shaykh Muhammad Jamal ud din, arrived. He was received by the sultan with great honours. He

had spent fifteen years in Arabia studying at Shafrl centres, and he introduced

the Shafrl madhhab to the islands. Then he retired to become a recluse.

A century later his work was carried on by another Hadrami, Sayyid Muhammad Shams al Dm, who acted just like Ibn Battuta earlier as a classic

rectifier and also as an example of a peripatetic Muslim authority. He

studied in Cairo and Mecca, and then went to Malabar and made many converts. After a visit to Aceh, he was on his way home when he stopped off at Male in 1097/ 1686. For a time he was treated with great honour, and

instituted reforms. Every man was to grow a beard, and every woman must

be veiled. He ended up in Hugh after being expelled from the Maldives, but

returned when a new sultan took power. Indeed, the sayyid himself became

sultan for one year, in 1103/1692. 45 Thus the Maldivians joined the rest of the

population of the Indian Ocean littoral as followers of the Shafri school.

42 www.soc.soton.ac.uk/ OTHERS / CSMS / OCHAL / ibn.htm.

43 Musa H. I. Galaal, 'Historical relations between the Horn of Africa and the Persian Gulf

and the Indian Ocean islands through Islam', in UNESCO, Historical relations across the

Indian Ocean (Paris, 1980), p. 24.

44 EP 'Maldives' (Forbes).

45 Forbes, 'Southern Arabia and the Islamicisation', pp. 89 90.

341

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Islam in the Maldives

Knowledge of Islamic practice in the Maldives is based on the accounts of the

Muslim visitor Ibn Battuta, who was a qddiin the Maldives, in the capital Male.

for eighteen months in 744 5/1343 4, and the Frenchman Pyrard de Laval,

who was there for five years from 1011/1602 to 1016/1607. In the former time

the dominant madhhab was, as noted, Maliki, and in the latter Shafi c i, but it is

unlikely that this change affected the lives of most of the islanders, apart from

the 'ulama' who administered the sharfa.

Ibn Battuta had good things to say about Islam in the Maldives. He wrote that The people of these islands are upright and pious, sound in belief, and

sincere in purpose; they keep to lawful foods, and their prayers are answered.'

There were beautiful mosques on all the islands, mostly made of wood. Islamic authorities were greatly venerated. Not that they were perfect. He

was scandalised that the women went around naked from the waist up, and

refused to eat with their husbands. 46

He had good cause to comment on the islanders' respect for authority, for he

became the qadl in Male. This is a very common occurrence, that is, of an authority

from the heardand receiving respect, and important positions, simply because they

can present themselves as cynosures of Islam. Indeed, as noted, this happened to

Ibn Battuta on the Swahili coast, and he also was much patronised when he was in

Delhi, where Muhammad b. Tughluq made him an ambassador. He not only

commanded respect, he also acted as a classic rectifier, trying to bring the islanders

closer to what he considered to be normative Islam, that is, in Swahili terms to have

less mila and more dmi. 'I strove my utmost to establish the prescriptions of the

Sacred Law. Lawsuits there are not like those in our land.' He stopped divorced

women from staying on in the house of their previous husband, made sure prayers

were observed and 'I compelled the salaried prayer leaders and muezzins to be

assiduous in their duties and sent letters to all the islands to the same effect. I tried

also to determine how women dressed, but I could not manage this.' 47

Pyrard left an extremely detailed account which, although by an outsider, nevertheless confirms many of Ibn Battuta's claims. 48 He describes the teaching

of Arabic, though the home language was Divehi. Overall he confirms that this

was a deeply rooted faith in an observant community. He comments on pray

ers, circumcision, the observance of Ramadan, Friday prayers, strictly observed

46 Ibn Battuta, Travels, pp. 822 4.

47 Ibid., pp. 840 1.

iS Pyrard, Voyage, vol. I, pp. 123 207.

## Islamic trade in the Indian Ocean

social divisions, legal matters and the administration of justice, the seclusion of

women, hcdal slaughtering of animals, and respect for the learned and for

dignitaries in general. Those who had done the hajj were especially esteemed;

they were allowed to wear their beards in a particular way:

Those who have been to Arabia, and have visited the sepulchre of Mahomet.

at Mecca [sic, but a very common European error at this time], are held in

high respect by all the world, whatever be their rank, and whether they be

poor or rich; and, indeed, a great number of the poor have been there. These

have peculiar privileges: they are called Agy; and in order to be recognised

and remarked among the others, they all wear very white cotton frocks,

on their heads little round bonnets, also white, and carry beads in their hands

without crosses; and when they have not the means to maintain themselves in

this attire, the king or the nobles supply them, and fail not to do so. 49

Both observers also noted some practices which seem to lie a little outside

the bounds of normative Islam. On one occasion Ibn Battuta gave a banquet,

which the sultan attended:

The food was served, and when the guests had eaten the Qur'an readers chanted in beautiful voices. The poor brethren [Muslims from Malabar whom

Ibn Battuta had looked after] then began their ritual chants and dances. I had

made ready a fire and they went into it, treading it with their feet, and some of

them ate it as one eats sweetmeats, until it was extinguished. 50

Pyrard has a quite lengthy discussion of the widespread use of charms by the

islanders. They were kept in boxes and carried under people's clothes. Most of

them were multipurpose, for example offensive and defensive, making well

and making sick and so on. 51

They also commented on sexual matters. Ibn Battuta prudishly tried to get

the local women to cover up, yet he also complacently wrote about how the

products of the local coconut palm and fish

have an amazing and unparalleled effect in sexual intercourse, and the people

of these islands perform wonders in this respect. I had there myself four wives

and concubines as well, and I used to visit all of them every day and pass the

night with the wife whose turn it was, and this I continued to do the whole

year and a half I was there. 52

49 Ibid., pp. no, 165.

50 Ibn Battuta, Travels, p. 836.

51 Pyrard, Voyage, vol. I, pp. 178 80.

52 Ibn Battuta, Travels, pp. 822 3.

343

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Pyrard was much less relaxed about this. He wrote a long account of their

'lasciviousness': 'Adultery, incest, and sodomy are common, notwithstanding

the severity of the law and penalties.' 53

The Maldives were emphatically part of a wider Muslim world. Ibn Battuta's account is full of notices of contact with far places: Quilon, Macassar, Coromandel, Mogadishu and the Islamic heartland. The respect

paid to those who had done the hajj, who had undertaken this long, dangerous

and expensive voyage, shows another distant connection. Abu'l Barakat may

have been a Maghribi, but soon after his time Hadrami influence became most

important. 54 No doubt this was reinforced once the Shafi'i madhhab became

dominant. Just as in East Africa, many of these migrants or visitors were shaykhs or sayyids, learned men with much baraka. Ibn Battuta was one such.

and Pyrard noticed another example, a 'Cherife of Arabia, that is, one of a

family the most respected and noble among these people as being of the race

of Mahomet. He was a very good man, and was greatly beloved of the king.' 55

This person had come from Aceh, and was on his way back to Arabia; like Ihn

Battuta he fulfilled some judicial functions while he was in the islands. Some of

the visitors may have had Sufi connections also. Forbes says that while there is

no firm evidence of Sufi influences in the Maldives, many of the learned visitors were probably members of the Qadiriyya Sufi order. Ibn Battuta once

stayed in a hospice built by the pious Shaykh Najib, but there is no indication

of which order he belonged to. 56 The most intimate connections may have been

with the Malabar coast, from where came the fire walkers that Ibn Battuta

described. Most immigrants, and visitors, were males who formed local alliances,

just like Ibn Battuta, but the Mappilas, who will be described in detail soon, came

in families, as Pyrard noted: 'Malabars [sc. Mappilas] come there frequently with

their wives, children and servants. These are permitted to traffic everywhere,

like the folk of the country, and are subject to the same police and regulations.' 57

The Lakshadweep islands

The Lakshadweep islands, formerly the Laccadives, have a rather different,

and much more obscure, history. They consist of twenty seven islands, of which ten are inhabited. Like the Maldives, they lie on the direct trade route

53 Pyrard, Voyage, vol. I, pp. 195 7, and more on this topic pp. 304 7.

54 See especially Forbes, 'Southern Arabia and the Islamicisation', passim.

55 Pyrard, Voyage, vol. I, p. 304.

56 Ibn Battuta, Travels, p. 835.

57 Pyrard, Voyage, vol. I, p. 300.

344

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

from Arabia to India. The original settlers were Hindus from the north Malabar

coast, who arrived perhaps as early as the second century CE. They were conquered by the expansionist Cola south Indian state in the fourth/ tenth

century, though there is no evidence of close control. It seems that the islands

were converted to Islam in the sixth/twelfth or seventh/thirteenth century.

However, according to the island origin narrative the founder was 'Ubaid Allah.

He was a grandson of Abu Bakr, a companion of the Prophet and his immediate

successor as head of the Muslim community. It is claimed that 'Ubaid Allah was

shipwrecked on the islands in 43/663. Initially he was met with hostility, but

after he performed a series of miracles all the islanders converted. His tomb in

Androth is venerated up to today. In the mid tenth/ sixteenth century the islands

were conquered by a Mappila ruling family from Cannanor. Concentrated western Indian influence is reflected in the language of the islands, which is

Malayalam, but with some Arabic words and written in the Arabic script, and

in the importance of 'caste' divisions, which are almost identical with the Hindu practice from which they are derived. Like the Maldives, they are Sunni Muslims and follow the Shaft'! madhhab. Two Sufi orders are especially

important, the Qadiriyya and the Rifa'iyya. Both were introduced to the islands

in the sixth/twelfth century by a visiting Sufi sayyid, who married a descendant

of 'Ubaid Allah. However, while in the Maldives succession is orthodox, that

is patrilineal, the Lakshadweep islands are matrilineal, with descent traced

through the mother. This seems to be another example of influence from the

Malabar region, where, as we will see, matrilineal succession is not uncommon

among both Muslim and Hindu communities. 58

#### Malabar

The Malabar coast stretches some 400 kilometres from Cannanor to Quilon,

and is more or less coterminous with the coast of the modern Indian state of

Kerala. According to Ibn Battuta it was two months' journey from Sandabur to

Quilon. 59 This region shares many characteristics with the other areas described in this chapter. Dale notes that its geography is more like the

58 This account relies on Ef 'Laccadives,' (Andrew Forbes); Forbes, 'Sources towards a

history of the Laccadive Islands,' South Asia, 2 (1979), pp. 130 50; Genevieve Bouchon,

'Regent of the sea': Cannanore's response to Portuguese expansion, 1507 1528 (Delhi, 1988),

pp. 39 50; and especially Theodore Gabriel, 'Islamic mystics of the Lakshadweep

islands, India', in Theodore P. Gabriel and C. H. Partridge (eds.), Mysticisms east and

west (Carlisle, 2003), pp. 44 53.

59 Ibn Battuta, Travels, pp. 805 7.

345

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

South East Asian Malay world than the rest of India, and this notion could

easily be extended to the Swahili coast, to the Maldives, and to the coasts of

Sri Lanka and Coromandel. All are more outward looking, international, cosmopolitan, than are the interiors. Malabar however is different in two respects. Unlike all the other littorals, its near interior boasted copious supplies of a very important early modern trade product, that is, pepper. To Arabs the region was known as Bilad al fulfill, the land of pepper. Pepper

was by far the main spice traded in this period, being the only one which was

consumed en masse, unlike the 'fine spices' of mace, nutmeg, cloves and cinnamon. Malabar thus was a focus for international trade. Indeed, its major port cities, of which Calicut was the most important from the sixth/twelfth century, not only funnelled pepper from the interior towards distant

markets, but also was a major transhipment port, where goods from further

east, west and north, as far as China and Europe, were landed, broken up and

sold, and sent on to their markets. As an example, those fine spices from the

Malukus (mace, nutmeg and cloves) which were bound for the Middle East

or the Mediterranean and so Europe, proceeded from Melaka to Calicut and

so on across the Arabian Sea.

The second way in which Malabar is different to the other coasts for Muslims is that while Muslims dominated much of the trade of the coast, inland they encountered a very sophisticated different great tradition religion,

Hinduism. To an extent Sri Lankan Muslims were in a similar situation vis a

vis the Buddhist interior, but this does not apply to the Maldives or to the Swahili coast. There was a major difference between interior and coastal Muslims. North India was ruled by Muslim dynasties which were Hanafi and Persianised, but coastal Muslims were Arabicised and Shafi'i. ° However,

the majority of the population of Malabar remained Hindu, while only two of

the many port cities, Cannanor and Honavar, both rather minor ports in this

period, were ruled by Muslims. All the other rulers were Hindu.

The Malabari origin narrative and the arrival of Islam

The local Muslim community in Malabar, the Mappila Muslims, have their

own origin narrative to explain the arrival of Islam in their area. Like similar

ones elsewhere, there is considerable variation in the details and it is very

60 Stephen F. Dale, Islamic society on the South Asian frontier: The Mappilas of Malabar, 1498 1922 (Oxford, 1980), pp. 5 11.

346

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

difficult for the modern historian to separate 'fact' from 'fiction'. In any case,

the real point is that this narrative is accepted by the community then and

now. There are two main versions, though both involve a ruler of the Hindu

Cera dynasty called Cheraman Perumal. In one version this ruler dreamed

that the moon had split. Soon after a group of Muslims arrived at Cranganore,

on their way to visit Adam's Peak in Sri Lanka,

and intelligence of their arrival having reached the King, sending for them

into his presence, he manifested towards them much kindness, conversing

with them without reserve: and enquiring of them their circumstances and

condition, the Shaykh, encouraged by the King's condescension, related to

him the history of our prophet Mahomed (upon whom may the divine favour

and blessing ever rest!), explaining also to the monarch the tenets of Islamism;

whilst, for a confirmation of their truth, he narrated to him the miracle of the

division of the moon [which purportedly the Prophet had done]. Now, conviction of the Prophet's divine mission, under the blessing of Almighty God, having followed this relation, the heart of the King became warmed with a holy affection towards Mahomet (on whom be peace!)

and he and later many others converted to Islam. : A variant is that after Perumal decided to convert to Islam he divided up his kingdom. When the

pilgrims came back from Sri Lanka he accompanied them back to Arabia in

210/825. He died there, but he charged his companions to return to Malabar.

where they gained many conversions and built nine mosques. Another version relates how the Cera ruler had a dream about the splitting of the moon at the same time as the Prophet actually did this. He went off to Arabia and met the Prophet himself, dying in 2/624. It is notable that the tenth/ sixteenth century local historian Shaykh Ahmad Zayn al Din rejects this

version, even though it is widely believed by local Muslims. He says the visit

to Arabia occurred some two centuries after the death of the Prophet. 2  $\mathop{\rm Yet}\nolimits$ 

another variant is recounted by a scribe who accompanied a Persian traveller/

ambassador, who was on the coast in the 1090s/ 1680s. He was told by the

locals that a ruler in Malabar saw with his own eyes the division of the moon

by the Prophet. He and his family then set out for the Hijaz. However, the ship encountered a storm and was in danger of sinking. In a dream the raja was

61 Zayn al Din, Tohfut ul Mujahideen, trans. M.J. Rowlandson (London, 1833), pp. 48 50.

62 R. E. Miller, Mappila Muslims of Kerala (Madras, 1976), pp. 46 51; Dale, Islamic society,

p. 12; Zayn al Dm, Tohfut, pp. 48 56. For a long analysis see Genevieve Bouchon, 'Les

Musulmans du Kerala a l'epoque de la decouverte portugaise', Mare huso Indicum, 2

(1973), PP- 21 4- See also A. P. Ibrahim Kunju, 'Origin and spread of Islam in Kerala', in

Asghar AH Engineer (ed.), Kerala Muslims: A historical perspective (Delhi, 1995), pp. 17 23

for a good discussion based on Hindu, Muslim and Portuguese sources.

347

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

told that blood must be shed if the boat was to survive. None in his entourage

volunteered to be sacrificed. However, one of his sisters pointed out that a

small cut on her son's leg would produce enough blood to satisfy the require

ment. Sure enough, a little blood was shed, the storm abated, and the raja

went on to meet the Prophet. His sister's sagacity made the raja decree that

accession to the throne should go to the son of the sister of the ruling raja. The

scribe then notes that the rulers of Cochin soon lapsed; matrilineal succession

however continued, 63

Ibn Battuta relates another story of miraculous conversions. In Dharmapatam,

where there was a large ba'in (tank) and a congregational mosque, the head of the

Muslims was called Kuwail. His ancestor had been converted thanks to a miracle.

Beside the mosque was a tree, and in the autumn of each year a single leaf fell

from the tree, and written on this leaf was the shahada. Ibn Battuta said that the

jurist Husain and other trustworthy people had seen this happen, and read the

words. At the time that it fell various trustworthy people both Muslim and infidel

sat under the tree, and when the leaf fell the Muslims took half, and the other half

was placed in the treasury of the infidel ruler, and they used it for healing of the

sick. This tree was the cause of the conversion of the ancestor of Kuwail, the one

who constructed the tank and mosque. He was able to read Arabic, and when he

read the shahada he embraced Islam. 'His story has been handed down amongst

them by many witnesses.' 64

A more sober, though less interesting, version of the conversion of many coastal people to Islam, thus creating the Mappila community, would note

that Arabs, along with others, had been visiting this area long before Islam

According to the first century CE Periplus, Cranganore was the main interna

tional port at the time, much frequented by ships from Arabia, which often

then went on to Sri Lanka and China. 65 Just as elsewhere, these Arab traders

continued to visit when they became Muslims, so that the first Muslims in Malabar must date from the time of the Prophet, or very soon afterwards. Barbosa early in the tenth/ sixteenth century claimed that Muslims arrived in

the area 610 years ago, that is, early in the fourth/tenth century, but this

63 Ibn Muhammad Ibrahim, The ship of Sulaiman, trans. John O'Kane, Persian Heritage

Series, 11 (London, 1972), pp. 219 23.

64 Ibn Battuta, Travels, pp. 810 11. The text is rather confused; this seems to be the right account.

65 Andre Wink, Al Hind: The making of the Indo Islamic world, 3 vols. (Leiden, 1990 2004), vol. I, p. 67, vol. II, p. 276.

66 Duarte Barbosa, A description of the coasts of East Africa and Malabar in the beginning of the 16th century, trans. Henry E.J. Stanley, Hakluyt Society, 35 (London, 1866), p. 102, and generally pp. 101 60.

348

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

seems to be far too late an estimate. Rather, this was the earliest Muslim community, however small, in South Asia, predating by a good margin the

arrival of Muslim armies in Sind in 92/711. The earliest extant Muslim remains

which can be dated include a tomb from the 170s /780s near Calicut. Shokoohy's excellent study of mosques in Malabar notes that many of the early ones were destroyed by the Portuguese in the tenth/ sixteenth century.

The Jami' Masjid in Calicut has an inscription from 885/i48of. in very elegant

naskh script, and this mosque must have been maybe a century old already.

Others in Calicut and Cochin date from the tenth/sixteenth century, while an

early Shi'a mosque in Quilon is probably a century or so earlier than this. Tradition claims that there was one in Cranganore which was founded in 8/630. The locals accept this tradition as authentic. Interestingly, it is associ

ated with the legend of the conversion of Raja Cheraman Perumal by an Arab

■ . 67 saint.

Again in familiar fashion, some of these Arabs setded and intermarried.

Certainly by the third/ninth century there were many Muslim settlements on

the coast. The result of this interbreeding, along with many conversions of

local Hindus, produced the local Mappila community, which is to be distin

guished from the Pardesi, 'foreign', Muslim group. A detailed Portuguese account from the early tenth/ sixteenth century explains why so many local

Hindus converted. The central claim, one familiar to anthropologists though

not always now accepted by them, is that oppressed low caste people are likely to convert to a religion perceived to be more egalitarian. Correia's account describes both the mix of trade and religion which proved so sue cessful, and the way the Islamic stress on the equality of all believers fostered

conversions, producing the indigenous Muslim Mappila community. He described the dominance of the Nayyars in this area, and the degraded position of the lower castes. Muslims, presumably from the Red Sea area given that this was the major trading area for Malabar, pointed out to the (Hindu) rulers that the low caste porters were unable to move about freely in

the area, because if they ran into Nayyars they would be killed. But if these

low caste Malabaris converted to Islam 'they would be able to go freely where

they wished, because once they became Muslims they were immediately outside of the law of the Malabaris, and their customs, and they would be able to travel on the roads and mingle with all sorts of people'. This argument,

67 Mehrdad Shokoohy, Muslim architecture of south India: The sultanate of Ma'bar and the

traditions of the maritime settlers on the Malabar and Coromandel coasts (Tamil Nadu, Kerala and Goa) (London, 2003), pp. 137 44.

U9

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

plus a few bribes, convinced the rulers, who gave their consent. The

conversion of these much oppressed people was easy, for they then could live

where they pleased and eat what they wanted. They also received clothing

from the Muslims. The result was a great success for this Muslim conversion

drive, which in turn spilt over into trading success, especially in the spice trade

to the Red Sea. It is to be noted that this account by an outsider shows clearly

that most local converts came from lower levels of Hindu society in Malabar.

Shaykh Ahmad Zayn al Din confirms this.

Pardesi Muslims

The Pardesi Muslims resident in or visiting Malabar were a very diverse group,

who however could claim more or less 'pure' Arab ancestry. Their primary

differentiator from the locals was that they were essentially sojourners, or at

least that they looked back to their place of origin as their real home, regardless of how long they had been in Malabar or how well they had done there. Barbosa, who generally is well informed, wrote that there were

many foreign Muslims in Calicut, 'These are Arabs, Persians, Guzarates, Khurasanys, and Decanys: they are great merchants, and possess in this place wives and children, and ships for sailing to all parts with all kinds of

goods/ 69 There is a textual matter to note here. The more recent edition of

Barbosa reads, 'they gathered here in great numbers with their wives and

sons'. 70 The difference is of some importance, for if they indeed brought their

families with them this implies that they were settled, and also this would reduce the possibility of having local wives and children. Contrariwise, if they

came as single men they would be much more likely to interbreed, thus increasing the number of local Muslims. The general history of Muslim diasporas around the Indian Ocean littoral usually stresses that only men moved, and even they would retain ties to their homeland and try to return

there for domestic matters from time to time. Thus on this occasion it seems

prudent to favour the earlier translation of Barbosa, which implies that the

wives and children were locals.

The Mappilas claimed Arab ancestry, too, but with much less credibility, for

even if there was an Arab somewhere in their background this ethnicity had

68 Caspar Correia, Lendasde India, 4 vols. (Coimbra, 1921 31, Lisbon, 1969), vol. I, pp. 75 6.

69 Barbosa, A description, p. 147.

70 Duarte Barbosa, The hook ofDuarte Barbosa: An account of the countries bordering on the

Indian Ocean and their inhabitants, trans, and ed. Mansel Longworth Dames, Hakluyt

Society, ser. 2, nos. 44, 49, 2 vols. (London, 1918 21), vol. II, p. 76.

350

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

been radically diluted by intermarriage with local Hindu women. In any case

many of them were converted Hindus tout court. This said, there is really a

continuum of 'arabness' rather than a bipolar situation; nevertheless, for heuristic reasons the Mappila /Pardesi division will be followed here.

There are available copious descriptions of the Pardesi Muslims. They came

primarily for trade, to participate in and even dominate the lucrative spice

trade to the Red Sea. Some Mappilas were also able to enter this trade, but not

nearly to the extent of the foreigners. The internal economy was controlled by

other people: some local Christians played a role in the collection and trans

portation of pepper, but the two main groups were Gujarati Vanias and Coromandel Chettyars, both of these of course being Hindu and not native

to Malabar. All of these 'foreign' groups lived in the Hindu ruled port cities

under conditions of considerable autonomy. One account of the Pardesi noted that 'They have among them a Moorish governor who rules over and

chastises them, without the king meddling with them.' 71 Most legal matters,

especially commercial ones, were settled within the group, or by negotiation

between the heads of several groups: for example, a debt owed by a Cairo

merchant to a Gujarati would be arbitrated between the heads of the two groups. The Hindu rulers were appreciative of the customs revenues these wealthy traders brought in, and by and large left them alone, or even actively

encouraged them to call. Another account, which mirrors what Ibn Battuta

found in Mogadishu and other places, describes how 'The king gave to each

one a nair to guard and serve him, a Chety scribe for his accounts, and to take

care of his property, and a broker for his trade. To these three persons such a

merchant would pay something for their maintenance' and they also received

a commission from those who sold goods to the Pardesi merchant. 72.

The rulers had to treat visiting merchants well, for the Pardesi did have choices. There were a host of competing port cities up and down the coast.

Curiously, almost none of these ports had adequate harbours. Except for Cochin, they all were open, and often dangerous, roadsteads where cargo had

to be perilously transhipped to lighters which took the goods to the shore. Yet

despite having no harbour, Calicut had been dominant from soon after its founding in the late fifth/ eleventh century. As noted, this rise seems to have

been a result of a fundamental shift in trading patterns, consequent on the

decline of the direct trade between Baghdad and Canton. The result was the

rise of entrepots such as Calicut and later Melaka.

71 Barbosa, A description, p. 147. 72 Ibid., p. 148.

351

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

A contemporary Portuguese account gives some detail on the Pardesi trade

of Calicut in the early tenth/sixteenth century, before the Portuguese had affected it. After a description of their ships, it goes on to say:

And in this manner ten or twelve ships laden with these goods sailed every

year in the month of February, and made their voyage to the Red Sea, and

some of them were for the city of Aden, and some for Jiddah the port of Mekkah, where they sold their merchandise to others, who transported them

thence in other smaller vessels to Turkey and to Suez, and thence by land to

Cairo, and from Cairo to Alexandria. 73

The Pardesi came from very diverse places. There were Persians, Turks, Arabs from Egypt, Arabia, Syria and Tunis, an important 'nation' from the Maghrib, and also some refugees from Granada. After the collapse of Baghdad, Egyptian merchants from Cairo, the Karimi merchants, were espe

daily important. From early in the seventh/thirteenth century Hadramis flowed in. Other Pardesi came from Ethiopia, Sumatra and Pegu. 74

These wealthy traders lived in some style. Abd al Razzaq was in Calicut in

846/i442f. and said it was a prosperous trading town, with two mosques to

service the resident Muslim community. There was a qadl, and a 'priest', and

most of them were followers of the Shaf? 1 madhhab. As to the Mussulmauns,

they dress themselves in magnificent apparel after the manner of the Arabs, and

manifest luxury in every particular.' Another account says: 'These are white men

and very gentlemanlike and of good appearance, they go well dressed, and

adorned with silk stuffs, scarlet, cloth, camlets and cottons; their head dress

wrapped round their heads. They have large houses and many servants: they are

very luxurious in eating, drinking, and sleeping.' 75 They were joined by fellow

Muslims, especially from Gujarat, and also by Jews and Hindu merchants, Banias.

## Muslim exemplars and Sufism

We have so far presented these Pardesi as successful merchants. However,

there were among them other foreign Muslims, many of whom seem to be

73 Ibid., p. 147.

74 Wink, Al Hind, vol. II, pp. 276 80; Genevieve Bouchon, 'Quelques aspects de l'islam

isation des regions maritimes de l'Inde a l'epoque medievale (Xlle XVIe s.)', Purusartha,

9 (1986), p. 32; Bouchon, 'Les Musulmans du Kerala', p. 50.

75 'Abd al Razzaq's account in R. H. Major (ed.), India in the fifteenth century: Being a

collection of narratives of voyages to India in the century preceding the Portuguese discovery

of the Cape of Good Hope; from Latin, Persian, Russian, and Italian sources, now first translated

into English, Hakluyt Society, 22 (London, 1857), pp. 13 17; Barbosa, A description, p. 148.

352

Cambridge Histories Online © Cambridge University Press, 201 1

## Islamic trade in the Indian Ocean

more settled, whose primary interest was not trade but religion, remembering

however again that 'piety and pelf (property) could easily coexist. From around 600/1204 many of the religious authorities in Malabar were Hadrami. It will be remembered that there seem to be a series of outflows

from this inhospitable area. Thus was created a network of Shaft 1! scholars

not only from the Hadramawt but also from Yemen, Oman, Bahrayn and Baghdad who had connections with, and travelled between, all the Muslim

communities around the shores of the Indian Ocean. Many of these men were

sayyids and sharifs, and were learned in Shafi'i jurisprudence. There were

close ties to the Hadramawt and, just as on the East African coast, people went

back there to study/6

Ibn Battuta's account from the 740S/1340S reveals prosperous, substantial

and pious Muslim communities up and down the coast, many of them like him of foreign origin. Like Shaykh Ahmad Zayn al Din two centuries later, he

stressed mostly friendly ties with the local Hindus, including the rulers, except

that Muslims and Hindus did not eat together, or go into each other's houses.

It is worth noting that Ibn Battuta, being from Morocco, was Maliki, and so in

theory should have been opposed to Muslims living under non Muslim rule;

yet this seems in no way to colour his observations of Malabar, which are mostly very positive.

A brief summary of his travels down the coast in the early 740s /1340s will

give a picture of the Pardesi community at this time: he says little about Mappilas. 77 In Panderani, near Calicut, the qddl and preacher was from Oman, and the amir of the merchants in Calicut was from Bahrayn. This man was also the shdhbandar, the main port official, and all the merchants used

to gather and eat at his table. The factor on one of the ships was from Syria. In

Quilon the chief Muslim merchant was from Iraq and was a Shi'a. The qddl

originated in Qazvm. There was a great Jam'i Masjid there, constructed by a

merchant. 'Muslims are honoured and respected there/

The ruler in Honavar was a Muslim. The people were Shafi'i. He met various shaykhs and jurists and the qadi. The women were modest and beautiful. They all knew the Qur'an by heart. There were thirteen schools for girls and twenty three for boys, 'a thing which I have never seen else where'. The ruler was very pious. He would come to the mosque before daybreak and read the Qur'an until dawn, when he would do his first prayers

of the day. He fasted when the moon was full, and wore silks and fine linen.

76 Wink, Al Hind, vol. II, pp. 276 8c 77 Ibn Battuta, Travels, pp. 803 19.

353

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

In Mangalore, north of Malabar proper, Ibn Battuta found 4,000 Muslims serviced by a very distinguished qddl. Then he went on to Hili, where there

was a large mosque of great blessedness. It had a rich treasury under the control of the preacher Husain and the chief of the Muslims, Hasan al Wazzan. Also in the mosque were several students of religious science who

got stipends from its revenue, and a kitchen where all travellers and poor Muslims could get food. He also found in Hili a pious jurist from Mogadishu

called Sa'id, 'of fine figure and character. He used to fast continually, and I was

told that he had studied at Mecca for fourteen years and for the same length of

time at al Madina, had met Abu Numayy the Amir of Mecca and Mansur b. Jammaz, the Amir of al Madina, and had travelled in India and China.' Another example of widespread connections came from Cannanore, where he

met a jurist from Baghdad, who had charge of his deceased brother's children,

and was going to take them to Baghdad. Finally, in Panderani there were three

Muslim quarters or localities, and each had a mosque, one of them very fine.

The gddl and preacher was from Oman.

Ibn Battuta's baraka is shown many times all around the shores of the Arabian

Sea. We saw how he was looked after in Mogadishu and the Maldives. Similarly

on the Malabar coast. During his travels his ship was attacked by pirates:

They took everything I had preserved for emergencies; they took the pearls

and rubies that the king of Ceylon had given me, they took my clothes and the

supplies given me by pious people and saints. They left me no covering except my trousers. They took everything everybody had and set us down on

the shore. I returned to Qaliqut [Calicut] and went into one of the mosques.

One of the jurists sent me a robe, the qadi a turban and one of the merchants

another robe, 78

Ibn Battuta also gives us some information on Sufism on the coast. When he

was in southern Iran, at Kazarun, he stayed in the hospice of the Shaykh Abu

Ishaq. He was highly venerated by the people of India and China. When travellers in the sea of China got a bad wind or feared pirates they would make

a vow to him and write down how much their obligation was. When they reached land people from the hospice would come on board and collect the

vows. 'There is not a ship that comes from China or from India but has thousands of dinars in it vowed to the saint, and the agents on behalf of the

intendant of the hospice come to take delivery of that sum.' Poor believers

could come to the head of the hospice and get a written order for a certain

78 Ibid., p. 865.

354

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

amount. The mendicant then found someone who owed a vow and collected

the money from him, and gave him a receipt. Once a king of India vowed ten

thousand dinars to the shaykh, and when one of the poor brethren at the hospice

in Kazarun heard of this he went off to India and collected that money. 79

This hospice in Kazarun was the original home of the early Sufi order called

Kazaruniyya, founded in southern Iran by the eminent Shaykh Abu Ishaq Ibrahim b. Shahriyar of Kazarun (d. 426/1033). It spread widely, and was very

influential in the eighth/fourteenth and ninth/ fifteenth centuries. The home

khdnaqd was suppressed early in the tenth/ sixteenth century by the Safavids,

and the order seems to have died out. ° In Ibn Battuta's time it was quite widespread. It had a hospice in Calicut, whose superior was Shaykh Shihab

al Dm of Kazarun, 'to whom are the offerings made in vows by the people of

India and China to the Sheikh Abu Ishaq, God profit us by him 1 . Then in Quilon, Ibn Battuta stayed at another hospice of this order, run by Shavkh

Fakhr al Dm, the son of Shihad al Din. There was yet another hospice of the

same fraternity in Quanzhou (Polo's Zaitun). 81 However, it seems that the

dominant Sufi order in Malabar was again the Qadiriyyas, who established

numerous hospices and were influential in the region.

Overall the picture is of a dynamic and pious Pardesi Muslim community on

the coast, one with widespread ties all around the shores of the ocean. It is

appropriate to close this account with a nice little vignette, which is Ibn Battuta's

own account of what he did while he was delayed in Honavar:

I spent most of my time in his [the sultan's] mosque and used to read the Qur'an through every day, and later twice a day, beginning the first recital

after the dawn prayer and ending it in the early afternoon, then after making

fresh ablutions I would begin the second recital and end it about sunset. I continued to do this for the space of three months, during which I went into

retreat for forty days. 83

The Mappila Muslims

Ibn Battuta says little about indigenous Muslims, the Mappilas, and none of it

is very positive. His praise is reserved for those who like himself were Arabs

from the heartland, and indeed he always commented on their presence, while

79 Ibid., p. 320.

80 EI\* 'Kazarun!'. (H. Algar).

81 Ibn Battuta, Travels, pp. 812 13, 895.

82 Kunju, 'Origin and spread', pp. 23 8

83 Ibn Battuta, Travels, p. 819.

355

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

either ignoring or belittling the locals. Typical was his experience in the back

waters when he was travelling from Calicut to Quilon. The trip took ten days,

and they anchored at night and stayed in villages. It was not a pleasant trip. 'There

was no Muslim on board the boat except the man I had hired, and he used to

drink wine with the infidels when we went ashore and annoy me with his brawling.' 84 Much of what is known about the Mappila community in this period

comes from Portuguese sources, which have their own biases and prejudices.

Bouchon's detailed and elaborately referenced survey covers well their economic

and political roles, but says little about their religion. Miller's survey is a rather

unscholarly account of their history which stresses that before the Portuguese this

was an irenical age, which the Portuguese destroyed. 85 It certainly was, by say

905/1500, a substantial community, perhaps 10 per cent of Malabar's total. In

modern times they make up some 20 per cent of the total population of Kerala.

Ludovico di Varthema claimed there were 15,000 or more in Calicut, and indeed

it seems that the bulk of the Muslim population lived in the north of the region, in

areas controlled by the Zamorin. Barbosa left an invaluable account of them:

In all this said country of Malabar there are a great quantity of Moors, who are

of the same language and colour as the gentiles of the country. They go bare

like the nairs, only they wear, to distinguish themselves from the gentiles,

small round caps on their heads and their beards fully grown. So that it appears to me that these people are a fifth part of all the inhabitants that there

are in this country. They call these Moors Mapulers, they carry on nearly all

the trade of the seaports: and in the interior of the country they are very well

provided with estates and farms.

The tenth/ sixteenth century Muslim authority Shaykh Ahmad Zayn al Dm noted how even though they studied and were apparently pious, their succession customs, just as in the Laccadive islands, were matrilineal. He noted matrilineal succession among Nayyars, and this 'has been adopted by

the greater part of the Mahomedans of Cannanore, and those who are dependent on them . . . although there are not wanting among them, who read the Koran, treasure up its maxims, and study it with apparent zeal, being

seemingly desirous to improve themselves by science, and who are regular in

the performance of religious worship'. Thus even apparently orthodox Mappila still practised distinctly unorthodox matrilineal succession. 87 This

84 Ibid., p. 816.

Bouchon, 'Les Musulmans du Kerala'; Miller, Mappila Muslims.

86 Barbosa, A description, p. 146.

87 Zayn al Din, Tohfkt, p. 63.

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

matrilinearity seems to apply mostly to Mappila groups in the north, where at

least some of them were converted Nayyars. In the south many of the converts came from other castes, and did not follow matrilineal custom.

The quotation from Barbosa stresses their continuing much Hindu Malabari

practice, and this is shown in other ways also. Their language was Malayalam,

with some Arabic additions. The mosques in Malabar, though always remem

bering that many of the oldest ones which Ibn Battuta described were destroyed

by the Portuguese, were quite different from those in the rest of the subcon

tinent. Curiously Ibn Battuta, who spent so much time in them, says nothing

about this, but merely notes that some were very grand and blessed. In Malabar

they used timber in the upper storeys, which often had elaborate wood carving.

The roofs were tiered or peaked, as are many secular buildings in the region.

In economic terms the Mappilas were a subaltern group, who engaged in local trade up and down the west coast of India and to the interior, or served in

local navies. Some apparently reached higher levels, taking part, along with

the Pardesi, in oceanic trade. Their maritime role may have been advantaged

by changes in Hinduism at this time. In south India the third/ninth century

Hindu reformer Sankara was influential. His stress on orthodoxy, or what he

considered to be orthodox, meant that Hindus became much less likely to travel by sea, over the Black Water, considering this to be ritually polluting.

Marco Polo in the seventh/thirteenth century wrote that Hindus in Coromandel did not drink wine, 'so shameful would it be thought that his evidence would not be accepted in court. A similar prejudice exists against

persons sailing the sea, who, they observe, must be desperate, and whose testimony in court ought not to be admitted.' 89 Thus the field was left open for

Muslims. It is notable that while Hindus from Gujarat sometimes did travel by

sea, and even settle overseas, it seems that Malabar Hindus did not. 90

### Portuguese in Malabar

The arrival of the Portuguese in 903/1498 led to profound changes in Malabari

Islam. Yet how to interpret this is a bit of a minefield. Shaykh Ahmad Zayn

al Dm stressed tolerance and good relations between Hindus and Muslims,

as also does the modern author Miller with his description of relations as being

irenical. Can it be said that with the Portuguese, religious intolerance entered

88 See K.J. John, 'The Muslim Arabs and mosque architecture in Malabar', in Engineer (ed.), Kerala Muslims, pp. 47 55.

89 Marco Polo, The travels of Marco Polo (New York, 1961), p. 251.

90 Bouchon, 'Les Musulmans du Kerala', pp. 9 14.

357

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Malabar de novo! This matter will be covered in detail elsewhere in this volume, but certainly their virulent anti Muslim actions, resulting from both

economic and religious competition, caused the Pardesi to move off to safer

places even as early as 921/1515. Easy enough for them to do this, given the

widespread connections we have noted so often. The Mappilas of course, being local people, did not have this option. Some accommodated to the Portuguese, others resisted, especially by continuing the coastal trade in pepper which they had been doing for so long. The main naval opponents of the Portuguese, the famous Kunj 'All Marakkars, or Kunhali Marakkars, a

dynasty of guerrilla naval commanders, came from a family of legists in Cochin who, when this became a Portuguese vassal port, moved on to Calicut, where throughout the tenth/ sixteenth century they opposed the Portuguese, sometimes in alliance with the Zamorins, sometimes not. The tenth/ sixteenth century Muslim writer Shaykh Ahmad Zayn al Din called on

the Mappilas to undertake a jihad against the Portuguese; implicitly he saw

Malabar as dar al islam, and being attacked by the Portuguese from dar al harb.

When Aceh was attacked by the Portuguese in the sixteenth century they were helped by Muslims from various areas, including southern Arabia, but

also by Mappilas from Malabar. Later, when they opposed the pretensions of

the Dutch and English, a Hadrami chronicle praised the Mappilas for their

courage: they are 'people of great courage and zeal for Islam', even though

'they have few scholars among them, and [know] no more of Islam than the

merest name of it'. 91

This denigration of their religious purity points to another consequence of

Portuguese hostility. They tried, with some success, to control trade and navigation in the Arabian Sea. One of the effects of this was that the sort of

dense circulation of religious authorities which have been described in such

detail was now hindered. Mappila access to the heartland, to the hajj and to

authorities from there, was reduced, and there seems little doubt that, as the

Hadrami chronicle noted, the quality of Islam suffered. It is an open question

whether this should be seen as a negative, a falling away from normative practice, or rather a healthy process of indigenisation, or Indianisation.

Perhaps in its isolation Mappila Islam stressed mila more than dini, though if

this be so, it is also worth remembering that even before the Portuguese, local

Islam in Malabar was distinctive, as noted, in terms of succession matters,

mosque architecture and the continuing influence of some pre Islamic practices.

91 Dale, Islamic society, pp. 51, 53. 358

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

Sri Lankan Muslims

Sri Lanka's Muslim population makes up less than 10 per cent of the island's

total today. They are conventionally divided into two groups, the so called

Moors and the Malays. 92, The latter, despite some claims for an ancient past, in

fact arrived only under Dutch rule, primarily in the late eleventh/ seventeenth

and twelfth/ eighteenth centuries. They make up about one fifth of the total

Muslim population, and speak a language which includes some Malay elements mixed in with local Sinhalese dialects.

The term 'Moor' is a derogatory one, being used by the Portuguese to describe all their Muslim adversaries. However, in Sri Lanka it appears to be

sanctioned by custom, and will be used here. Their history has, as one would

expect, many similarities with that of the other coastal Muslim communities

already discussed. They claim descent from Arab traders who arrived very

early in the Muslim period, and some claim that in terms of ethnicity they are

more Arab than Sinhalese. Certainly Sri Lanka was known to Arab and other

traders long before Islam, being a source of precious stones, pearls from the

Gulf of Mannar (or Fishery coast), between south east India and Sri Lanka, and

cinnamon, and serving as a convenient way station for east west and vice versa trade. These Arab traders knew the island as Serendip, an indication then

of its appeal to them, for this is the root of the English word 'serendipity'. One

can then assume that when Arabs converted they continued to call at Sri Lanka, and that there they intermarried with local women, both Sinhalese and

Tamil, thus forming a mestizo Muslim population, though one which over time became less and less 'Arab' in terms of ethnicity. These descendants of

foreign merchants merged into the majority of the Muslim population, who

were Sinhalese by ethnicity, and usually from lower levels in the society. Their

main settlements were on the north east, north and west coasts, such as Jaffna,

Colombo and Galle.

Apart from trade, the main attraction of the island for Muslims was the presence in the interior of Adam's Peak, where it was believed an indentation

in the rock was the footprint of Adam himself. (Buddhists believe it is that of

Gautama the Buddha.) It will be remembered that the legendary facilitators of

the conversion of Malabar were a party of Arab pilgrims bound for Adam's

Peak. A later pilgrim was Ibn Battuta, in 745/1344, who left an impression of a

quite flourishing Muslim community. As he ascended he noticed several

92 Generally see Wink, Al Hind, vol. I, pp. 80 1; EI 1 'Ceylon' (A. M. A. Azeez). and the

rather unsatisfactory Vasundhara Mohan, Muslims in Sri Lanka (Jaipur, 1985).

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Muslim associated places, and especially a mosque of a shaykh from Shiraz,

whose tomb was nearby and was venerated by all. However, his account gives

none of the useful detail which he provides for other places already commented on. 93

It appears that relations with the majority Buddhist rulers in Sri Lanka were

cordial, as also with the Hindu rulers in the north. The Muslims with their

international trading connections brought in much needed customs revenues,

and goods from far away. Thus they were patronised and encouraged. A good

deal of interaction between the three religions is to be expected, and among

other things is shown by the home language of the Moors, which is over whelmingly Tamil though with the addition of a large number of Arabic words. In this period there was some writing in Arabic script but it seems that

Tamil was more common, and this points to close ties with Tamil speaking

Muslims in Coromandel, especially focused on the pearl fisheries, along with

their location in Sri Lanka, which was often in Tamil speaking areas.

Sri Lankan Muslims operated in two zones, one local, one very extensive. They had closest ties with their fellow Shafi'i Muslims in Malabar and Coromandel. This area made up a distinctive commercial region, where the

main trade products were pepper from Malabar, cinnamon from Sri Lanka and

pearls from the Gulf of Mannar. Indeed the way in which the pearl fisheries lay

between Sri Lanka and Coromandel, and were shared by the two areas, plus

the fact that Mappilas tried to stop the Portuguese from interfering in them,

typifies the interconnectedness of these three areas. There was considerable

interchange of people and products in what was a defined trading arena. To separate out Muslims from any one of these regions as distinctive would

be to ignore the dense interaction, intermingling and intermarriage which in

fact occurred. Local Muslims from the three areas collected the products, and

fed them into the wider Indian Ocean circuit, indeed into a worldwide circuit.

for these three products had universal appeal.

Some authors see the period up to 905/1500 as a golden age for Sri Lanka's

Moors, when they prospered and had good relations with local rulers. This

changed dramatically with the arrival of the Portuguese, who extended their

anti Muslim activities to Sri Lanka as well as India. In the sixteenth century they

attacked Muslim traders on sight, and later occupied much of the Sri Lankan

coast. When the Dutch took the island in the middle of the eleventh/ seven

teenth century they instituted a monopoly policy over cinnamon, thus again

detrimentally affecting the Moors.

93 Ibn Battuta, Travels, pp. 847 56.

360

Cambridge Histories Online © Cambridge University Press, 201 1

Islamic trade in the Indian Ocean

#### Coromandel

We have much less data on the Muslim presence in Coromandel and the Tamil interior. It is impossible to describe them in the comparative depth which was available for other littoral areas, and what we do know is bedevilled

by considerable terminological confusion in the existing literature. For our

purposes the area under discussion is essentially the same as the coastal area of

the present Indian state of Tamil Nadu. Arab writers knew this region as Ma'bar, though confusingly sometimes this term refers to part of the Malabar

coast.

The first evidence of Muslims on the Coromandel coast comes from an inscription of 261/875. The area was known to Arab geographers from very

early. 94 Muslims became a more substantial presence only from the fifth/ ele

venth century, and conversions on the coast reached any great numbers only

from the seventh/ thirteenth. 95 Alone of the areas under discussion in this

chapter, the Coromandel region was conquered early in the eighth/ fourteenth

century by Muslim armies from the north, that is, those of the Delhi sultanate. It

seems that these northerners were unimpressed by the quality of Islam that they

found in Coromandel. 96 Their incursion was soon ended, though it did result in

a shortlived Muslim sultanate in Madurai (733 80/1333 78), which was taken

over by the Hindu kingdom of Vijayanagara. From the last decades of the tenth/sixteenth century, after the defeat of Vijayanagara by Muslim armies.

Coromandel was again subject to Muslim rule. However, here and elsewhere

we must avoid any communal tinge in our discussion; thus Muslims happily

served in the armies of Hindu rulers such as the Pandyas.

Any discussion of the Muslim communities of the Coromandel coast and Tamil interior must first try to make sense of a very complex matter of terminologies. There are both collective and specific terms in use, but some

of these have changed over time, as have the fortunes of the various groups.

Since the British began to categorise people in the late nineteenth century four

distinct groups within the Tamil Muslim community have been recognised.

However, this does not necessarily apply to the early modern period. Some

authorities refer to Labbai as a generic term which encompasses all four.

94 S. Muhammad Husayn Nainar, Arab geographers' knowledge of southern India (Madras, 1942).

95 Wink, Al Hind, vol. I, pp. 78 80, vol. II, p. 280. See also Shokoohy, Muslim architecture of south India, pp. 275 90.

96 J. B. P. More, Muslim identity, print culture and the Dravidian factor in Tamil Nadu (New Delhi, 2004), pp. 10 11.

361

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

It may be that this is a modern usage. Alternatively, according to Arasaratnam

the term Chulia was a collective one which included all four groups. Chulia is

not an indigenous word, and may be a corruption by Europeans of the local

name for the area: Cholamandalam. However, Ibn Battuta in Quilon found

very wealthy merchants whom he called Suli, that is Chulia. For the early Europeans the Hindu traders of the Coromandel coast were Klings, later often

called Chetties, more correctly Chettyars, who were Hindu, while the Muslims were Chulias. 97

The four divisions for the community, used once censuses began to make inchoate divisions firmer, are Maraikkayar, Kayalar, Rawther and Labbai. The

Maraikkayar and Kayalar groups are Sunni, and follow the Shafi'I madhhab.

They were and are merchants who lived on the southern part of the Tamil

Nadu coast and traded extensively in South East Asia. The Rawther and Labbai

groups are also Sunni, but Hanafi. They live inland in the northern areas, and

are much poorer than their coastal co religionists. The division between inland

Hanafi and coastal Shafi'i is one found generally in South Asia at this time.

The coastal Maraikkayar today claim that they are descended from Arab traders, and are more Arab than Tamil. According to them the interior two

groups are mere converts, and not very observant Muslims at all. Susan Bayly

makes clear that this exclusiveness and intolerance is a nineteenth century

development. In previous times, including the period under discussion, there

was less differentiation, and all Coromandel Muslims were syncretic. In terms of

literature, 980/i572f. is the year in which the earliest extant complete Islamic

poem in the Tamil language, the Ayiramacala, was composed. From that point

onward, we have texts written by Tamil Muslims in both Tamil and Arabic on

Islamic topics, using both the Tamil and Arabic scripts for the Tamil language. 98

However, while some recent writers stress interaction between Hindus and

Muslims, such as common worship at Muslim dargahs (shrines), and grants to

them from local Hindu rulers, we have very litde contemporary evidence of

this. Bayly discusses the shrine of a Qadiriyya Sufi master in Nagore. He established a khanaqa in 950/1543. His dargah was a focus of worship for both

Hindus and Muslims, with a lot of practices taken from Hindu worship. 99

 $97\ Sinnappah\ Arasaratnam,\ Merchants,\ companies\ and\ commerce\ on\ the\ Coromandel\ coast,\ i6p\ 1740$ 

(Delhi, 1986), p. 219; Ibn Battuta, Travels, p. 816.

98 This section owes almost everything to Torsten Tschacher, then of the South Asian

Studies Program at the National University of Singapore. He provided help with

bibliography, and extensive comments on my first draft. Space limitations dictated

that I could not use much of what he provided, but I am grateful even so.

99 See Bayly, 'Islam in southern India', pp. 35 73 for an account which perhaps relies too

much on nineteenth and twentieth century sources to tell the story of earlier periods.

362

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

This saint used a common religious vocabulary, derived from Hindu, Muslim

and Christian ideas. His shrine received donations from the Hindu elite

even from Europeans, as well as Muslims. In the early twelfth/ eighteenth century the famous Labbai poet Umaru Pulavar wrote a 5,000 stanza epic called

Sirapuranam on the life of the Prophet based on the Tamil version of the Ramayana. Subrahmanyam emphasises the lack of religious particularism at

this time, and earlier. None of these men saw themselves as being forced to

choose between an Arab Islamic culture and a Tamil one. 100

The Maraikkayar in the early modern period had important trading con nections in their immediate area, that is, to Sri Lanka, to the pearl fisheries in

the Gulf of Mannar and around the corner to Malabar, where there were close

connections with the Mappilas. In the 930s and 940S/1520S and 1530s Mappila

fleets led by the Kunjali Marakkars of Malabar operated in southern Coromandel, too, to support the Tamil Maraikkayars and to oppose (ulti mately unsuccessfully) the Portuguese attempt to take over the pearl fisheries in the Gulf of Mannar. In these lucrative diving areas the Maraikkayar worked

as divers and also as entrepreneurs. 101 Their most important centres at this

time, in the early sixteenth century, were Kayalpatnam and Kilakkarai. They

married into families with similar Shafi'I allegiance from Malabar and Sri Lanka rather than with the Hanafi of the interior, despite having a common

language of Tamil with the latter.

These ties with contiguous areas seem to have existed from early on in the history of the Coromandel Muslim merchant presence. However, it may be that their more extensive trading role began around the middle of the ninth /fifteenth century with the rise of the Melaka sultanate. They became an important element in the very diverse mercantile world of this port city, and played a major role in the Malay world in general both in trade and in the process of the conversion of the Malays to Islam. In the eleventh/ seventeenth century Tamil commercial groups were important traders in Johor, Banten and Perak. Chulia traders moved in to Aceh once the Gujaratis left this port to concentrate on the trade to the Red Sea. In the

100 See Sanjay Subrahmanyam, 'Diversity in South Asian Islam', Akhbar, 5 (2002); David

Shulman and Sanjay Subrahmanyam, 'Prince of poets and ports: Citakkati. the

Maraikkayars and Ramnad, ca 1690 1710', in Anna Libera Dallapiccola and Stephanie

Zingel Ave Lallaemant (eds.), Islam and tfte Indian regions, vol. I (Stuttgart, 1993), PP- 497 535-

101 Barbosa, The book ofDuarte Barbosa, vol. II, pp. 116 25; Sanjay Subrahmanyam, 'Noble

harvest from the sea: Managing the pearl fishery of Mannar, 1500 1925', in Burton Stein

and Sanjay Subrahmanyam (eds.), Institutions and economic change in South Asia (Delhi,

1996), PP- 134 72-

### The New Cambridge History of Islam

second half of the eleventh/ seventeenth century they had a massive trade

in Aceh. Everywhere they functioned as key middle merchants and brokers. One family called Lebbe, who were Chulia Muslims, were prom inent commercial advisers to the sultan of Johor towards the end of the seventeenth century. IC2,

Knowledge of religious practice, perhaps visits from heartland shaykhs, or

religious connections with the wider Shafi'i world, is very slight. However,

the Coromandel coast was an important source of textiles, and we have just

noted extensive trade by Muslims from this coast with Sri Lanka, Malabar and

especially the Malay world. It would then be extraordinary if there did not

exist the sort of mingling of commerce and religion which we have found in

other areas. The dominant Sufi order was the Qadiriyya. The usually informa

tive Ibn Battuta tells us little, except to point to a group of faqirs in an obscure

town: this points to an active Muslim community. He was with a ruler called

Ghiyath al Dm, who was part of a short lived Muslim dynasty in Madurai. In

Fattan, an unidentified port near Madurai, he noticed a fine stone built mosque, and met there the pious Shaykh Muhammad of Naisabur, one of the distraught faqirs who let their hair grow down to their shoulders. He had

about thirty faqirs with him. 103

#### Conclusion

It would be tempting to see the Muslim communities strung around the shores of the Arabian Sea, and further to Coromandel, as existing in a golden

age of peace and prosperity which was rudely ended by the arrival of fanatical

Portuguese. Another chapter in this volume considers the role of the first Europeans to operate extensively in our area; generally the literature today tends to belittle the impact of the Portuguese in the region. What is more important is to stress several themes which have been prominent in this chapter. In most of these areas conversion narratives have been important.

These attribute the conversion of local people resulting from the baraka of a

visitor from the Arab world. This points to wide connections back and forth

between the heartland of Islam and its outposts in the Arabian Sea littoral.

This interplay continued, and continues today. Scholars and saints travelled

widely, resulting first in conversions and then attempts to inculcate a more

102 Sinnappah Arasaratnam, 'The Chulia Muslim merchants in Southeast Asia, 1650 1800',

in Sanjay Subrahmanyam (ed.), Merchant networks in the early modern world (Aldershot,

1996), pp. 159 77-

103 Ibn Battuta, Travels, p. 862.

364

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islamic trade in the Indian Ocean

'orthodox' version of the religion. The cosmopolitan nature of these coastal

Muslims must be emphasised in terms of both their trading activities and their

religious ties to Arabia. They were thus very largely set off from their inland

neighbours. Yet some at least of their religious practice continued to draw on

themes and motifs which lay deep in the coastal soil, and which long predated

Islam. In none of this are Arabian Sea Muslims unusual within the wider world

of Islam; all of these themes are to be found in most other areas which today

are Muslim.

365

Cambridge Histories Online © Cambridge University Press, 201 1

10

Early Muslim expansion in South-East Asia, eighth to fifteenth centuries

**GEOFF WADE** 

#### Introduction

Islam was to come to the polities and societies of South East Asia by sea, along

the girdle of trade which extended from the Middle East through the ports of

southern Asia, to South East Asia and onwards to the southern extensions of the

Chinese world in the East China Sea. 1 Islamic influences extended into South

East Asia from both ends of this trade route in different periods. In examining

historical processes, periodisation is often a helpful tool, and it is thus proposed

that we examine the extension of Islam to South East Asia up until the ninth/

fifteenth century in three major stages: (i) The period from the emergence of

Islam until the Cola invasions of South East Asia in the fifth /eleventh century;

(2) The end of the fifth/ eleventh century until the seventh/ thirteenth century;

(3) The eighth/fourteenth and ninth/ fifteenth centuries, following the establish

ment of the first Islamic South East Asian polities in the seventh/

century. The reconstruction of the earlier periods is of course restricted by

the dearth of sources, but newly available materials from Chinese texts and the

archaeological record help to extend the existing histories of the religion in the

South East Asian region. The intimate interactions between this region and

the ports of southern China demand that the latter also be considered in any

study of the emergence of Islam in the area we today term South East Asia.

From the emergence of Islam until the Cola attacks on South-East Asia in the fifth/ eleventh century

There is little doubt that the earliest introduction of Islam to South East Asia

was by Muslim merchants who travelled along the maritime routes which, for

1 The author wishes to thank Azyumardi Azra, James Chin, Edmund Edwards McKinnon,

Michael Feener, Michael Laffan, Elizabeth Lamboum, Li Tana, Pierre Yves Manguin,

John Miksic, Michael Pearson, Anthony Reid, Merle Ricklefs, Claudine Salmon and

Torsten Tschacher for comments and suggestions.

366

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

at least a millennium earlier, connected the two ends of the Eurasian con tinent. The foundation of the urban centre of Baghdad in 145/762 with Basra

as its outlet to the Arabian Sea was a major impetus in the transformation of

trade and the development of commerce between the Persian Gulf and East

Asia. 2 The early importance of the maritime vector is still evident today, as it is

in maritime rather than mainland South East Asia that the major Muslim communities reside. The specific activities of the early Persian and Arab traders 3 in South East Asia are poorly documented, but at least one Chinese

source notes contact between a South East Asian polity and Arab people during the first/seventh century. The New History of the Tang notes in its account of He ling, likely located in Java:

During the shang yuan reign (54 5/674 5) the people of the country promoted

a woman as their ruler, and she was entitled Xi mo. Her stern majesty ensured

that society was stricdy ordered so that not even things lost on the road were

picked up by others. A prince of the Arab lands 4 heard of this and placed a

bag full of gold in her suburbs. There it remained for three years without pedestrians touching it. Once the crown prince kicked it while passing and

Xi mo was greatly angered and was going to behead him, but the assembled

ministers strongly urged her against that action. Xi mo then said 'The fault lies

with your feet. They need to be cut off.' Again the ministers urged her not to

pursue this action, so in the end she just cut off his toes as a warning. Those of

the Arab lands heard of this, and in fear, dared not attack them. 5

It may well have been that the 'prince of the Arab lands' described resided

in Sumatra, as Sumatran ports were long known as transit points on the maritime routes described above, as well as entrepots for trading the products

from the hinterland of that island. From Arab texts we glean further knowl

edge of the extent of these trade routes, extending to destination ports in southern China. In the third /ninth century, for example, Ibn Khordadbeh recorded the trade ports at the furthest extension from the Arab world as Lugxn

(likely Loukin, situated in what is today Vietnam), Khanfu (Guangzhou/Canton),

2 Pierre Yves Manguin, 'The introduction of Islam into Champa', in Alijah Gordon (ed.), The

propagation of Islam in the Indonesian Malay archipelago (Kuala Lumpur, 2001), pp. 287 328.

See p. 311 n. 12.

3 The 'Persian and Arab traders' referred to here is a generic reference to peoples from the

Middle East trading on ships crewed by people of a likely diverse range of ethnicities and religions.

4 The term translated here as Arab lands is Da shi (^Cft), a term deriving from the Persian

name Tazi, referring to a people in Persia. It was later used by the Persians to refer to the

Arab lands. The Chinese used the term from the Tang dynasty until the sixth/twelfth

century to refer to the Arabs.

5 Ouyang Xiu et ah, Xin Tang Shu [New history of the Tang dynasty], (Beijing, 1975), juan 222.

367

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Khanjii (Quanzhou), with Qansu (Yangzhou) marking the end of the maritime

route (see Map 8). In the middle of the same century (141/758), following the

An Lu shan rebellion in China, the major Chinese port of Guangzhou was sacked by 'Arab' people. By a century later, there was evidence in the same

city of a quite large Islamic community. Sulayman, who visited Guangzhou in

236/851, noted that the city had a Muslim community governing itself according

to the sharfa under a qddT, whose appointment had to be confirmed by the

Chinese authorities. It is likely that this was the port from which the Arab/

Indian ship wrecked off Belitung island in about 210/826 and carrying southern

Chinese cargo seemingly bound for western Asia had sailed. 7 The foreign

community in Guangzhou was quite large in the ninth century, as Abu Zayd

reports that some 120,000 Muslims, Jews, Christians and Parsis were killed

when the city was taken in 264/878 by Huang Chao, a rebel against the ruling

Tang dynasty. The reasons behind the massacre are not clear, and it is not

recorded whether similar depredations were inflicted on Islamic communities

in the ports further north. Given that Guangzhou's early Muslim and other

foreign communities would have arrived by sea, they would probably have been connected with similar communities in South East Asia at this time. Flight from the massacre would thus have undoubtedly been towards

South East Asia. The successive Arab geographers wrote of many places in

South East Asia between the second/eighth and third/ninth centuries, many

experienced at first hand by their informers, suggesting that Islamic traders

were regularly passing through and perhaps sojourning in the port polities of

South East Asia. 9

The fourth/tenth century saw the development of further linkages between the Middle East and South East Asia through the ports of the Indian subcontinent, 10 and at the same time there is much evidence of Islamic connections between China and South East Asia. During this early

6 Again 'Da shi'. See Liu Xu et al., Jiu Tang shu [Old history of the Tang dynasty], (Beijing, 1975), juan 10.

7 Michael Flecker, 'A ninth century AD Arab or Indian shipwreck in Indonesia: First

evidence for direct trade with China', World Archaeology, 32, 3 (Feb. 2001), pp. 335 54.

8 Note, by comparison, the 10,000 Muslim population of Chaul (Saymur), the main port

for the Konkan coast as given by al Ma'sudi. Wink suggests that the exodus of Arabs

from China at this time was responsible for the rise of the major ports in the Thai

isthmian region, particularly Kalah. See Andre Wink, Al Hind: The making of tfte Indo

Islamic world, (Leiden, 1990), vol. I, p. 84.

9 See G. R. Tibbetts, A study of tfte Arabic texts containing material on South East Asia (Leiden, 1979).

10 As detailed in Andre Wink's contribution above, Chapter 2, and his Al Hind, vol. I, pp. 67 83.

368

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

period, Chinese texts record the arrival at the Northern Song court (at Kaifeng) of envoys from Da shi (the Arab lands), the Cola empire, Zabaj/Zabag 11 (likely Sriwijaya) and Champa, all bearing names which can be reconstructed as being Muslim. These arrivals reflect the great maritime trade route which connected the Arab lands with China, passing through southern India, Zabaj/Sriwijaya in Sumatra and Champa in what is today central Vietnam. It thus appears that during this century, the more prominent

Muslim communities in South East Asia likely resided in or traded out of the

capital of Zabaj (either Palembang or Jambi) and the capital of Champa.

The listing of the names of the envoys who arrived in China in the fourth/ tenth and fifth/ eleventh centuries (see Appendix i, at the end of this chapter)

suggests a number of salient points. That the envoys to China from the polities

of Zabaj and Champa during this period were Muslim is undoubted, and

verified by their names. The 'tribute' missions to China were often the only

way to obtain trade concessions in China, and it is thus obvious why mer chants desired to be recognised as representatives of South East Asian polities

in coming to the Song court. 11 Whether these merchants were trading on their

own account, acting as agents for local rulers or some combination of the two

remains unknown, but we can say with some certainty that Muslim merchants

were well ensconced in South East Asia by the fourth/tenth century. The names borne by these people, or at least the Chinese equivalents which the texts ascribed to them, are interesting in themselves, and the repetition

of the same names often associated with different states suggests that these merchants were acting as 'envoys' for a range of polities. Some also

appear to have become part of the ruling structure. The viceroy of Champa in

357/968 was named in Chinese sources as Li Nou, which might be tentatively

reconstructed as 'Ali Nur. It is also apparent, again from Chinese texts, that

Muslim traders were operating into China through Brunei in Borneo and Butuan in the modern Philippines by the early fifth/ eleventh century. 13 Further, in one of the few references to Muslims in the Cambodian court, in

11 For details of which see Michael Laffan, Finding Java: Muslim nomenclature of insular

Southeast Asia from Srivijaya to Snouk Hurgronje, Asia Research Institute Working Paper

Series, 52, Singapore (Nov. 2005).

12 Elizabeth Lambourn's research (e.g. 'Tombstones, texts and typologies seeing Sources

for the early history of Islam in Southeast Asia', Journal of the Economic and Social History

of the Orient, 51, 2 (2008), pp. 252 86) suggests that, at least in the subcontinent, some

Muslim merchants were formally integrated into the administrative structures of coastal

polities and thus did operate as formal envoys of those polities.

13 Friedrich Hirth and W. W. Rockhill, Chauju Kua (St Petersburg, 1911; repr. Taipei, 1970),

p. 157.

369

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

about 290/903, Ibn Rusta wrote that an Arab merchant, Abu c Abd Allah Muhammad bin Ishaq, had spent two years at the court of the Khmer ruler,

presumably at Angkor. 14 And in a recently excavated shipwreck found in the

ocean 100 kilometres north of Java and dated to approximately 349/960, there

was discovered a stone mould for casting dual medallions, both bearing an

Islamic inscription which has been tentatively identified as reading in three

lines Al mulk li llahi / al wahid / al qahhar' (Fig. 1). 15 The function of such

medallions remains unknown, but the ship's cargo suggests a regional trading

vessel touching at a range of South East Asian ports. 1 Arab texts also provide

us with details of the South East Asian ports visited by Middle Eastern traders

during this period. 17

What are particularly notable about the envoys from South East Asian ports to China during the fourth/tenth and fifth/ eleventh centuries are their

names. The vast majority of them, according to the Chinese sources, bore a

'surname' either Li (\$) or Pu (yjf ), followed by phonetic representations of

names which are obviously Islamic. The likelihood of all these people being of

the same two families is almost negligible. These merchants, some of whom

were apparently Sino Arab, had thus either adopted a surname to accord with

14 P. Y. Manguin, 'The introduction of Islam into Champa', in Alijah Gordon (ed.), The

propagation of Islam in the Indonesian Malay archipelago (Kuala Lumpur, 2001), p. 293,

after Gabriel Ferrand, Relations de voyages et textes geographiques, arabes, persans et turks

relatifs a VExtreme Orient du VIII au XVIII siecles (Paris, 1912).

15 'Allah, the Possessor of all Sovereignty, the One and Only, the Dominator'. The

transcription follows a reading by Elizabeth Lambourn.

16 This tenth century wreck, assigned the name Five Dynasties Wreck, was excavated in

2005. Much Middle Eastern glass as well as a huge range of Chinese ceramics and South

East Asian commodities were found on the wreck. Another tenth century wreck

discovered in the Java Sea, and known as the Intan, has also been excavated and

analysed. For details, see Michael Flecker, 'The archaeological excavation of the 10th

century Intan wreck', Ph.D. thesis, National University of Singapore (2001). Published in

the BAR International Series 1047 (Oxford, 2002). For details of the cargoes of these

wrecks, see http://maritime explorations.com.

17 Including the work of Abu Zayd (303/916) which mentions Zabaj and Qmar; the Muriji al

dhahab of Ma'sudi (fourth/tenth century) which mentions Zabaj, China, India, Kalah,

Sirandib, Sribuza and the sea of Sanf; the work of Abu Dulaf (c. 330/940) which recorded

Sandabil, China, Kalah and Qamrun; the work of Ibn Serapion (c. 340/950) which

mentions Kalah, Zabaj, Harang and Fansur; the work of Ibn alNadim (378/988) which

notes Qmar, Sanf and Luqm; the 'Ajfi'ib alHind (c. 390/1000) which mentions Malayu,

China, Sanf, Ma'it, Sribuza, Zabaj, Lamuri, Fansur, Kalah and Qaqulla; the Mukhtasar al

'aja'ib (c. 390 / 1000) which records Sanf, Kalah, Jaba, Salahit and Zabaj; BTruni's India (early

fifth /eleventh century) which records Zabaj and Qmar; the work of Marwazi (c. 515/1120)

which records Zabaj and Lankabalus; and the text of Idrisi (of the mid sixth/twelfth

century) which lists Zabaj, Karimata, Ramni, China, Qmur, Niyan, Balus, Kalah, Harang,

Jaba, Salahit, Ma'it, Tiyuma, Sanf, Qmar, Luqin and China. See Tibbetts, A study of the

Arabic texts and Gabriel Ferrand, Relations de voyages et texts relatifs a VExtreme Orient, 2 vols.

(Paris, 1913 14). See also, for some new interpretations, Laffan, Findingjava.

370

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

```
r
■at.' "-~~

1
■MB r, ■ . : . fj
*u 1
" i » •- f«
```

li '^'''-"

\*\***■**\***■** i ^8 a

•?« V \*.

•Hfv\*\*

1 \*•\* \* 1

i£i\*£

1\$ \*

:

j

^te' ^ i

1 ^

l^f -' T % .\*

ft

TM \

.

i Mould for jewellery, bearing inscription 'Al mulk li llahi / al wahid / al gahhar'. This

was recovered from a mid fourth/tenth century shipwreck in the Java Sea and is one of the

earliest known physical vestiges of Islam in South East Asia.

Chinese expectations, or provided an 'origin' or 'genealogy' name which was

then used as a surname either by themselves or by the Chinese chroniclers or

both. It is now accepted that 'Li' derived from 'c Ali' and 'Pu' represents

As can be seen from the listing in Appendix i, envoys to China from maritime polities and bearing the 'surname' Li are recorded regularly in Chinese texts beginning in the 350s /960s. This is not to say that such people

had not been travelling to Chinese ports and polities prior to that. It is just that

these are the earliest of such detailed sources available to us. During the fourth/tenth century, the majority of these Li 'surnamed' envoys came from

San fo qi/Zabaj and Champa, with some from the Arab lands and one from

Butuan in the southern Philippines.

# Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

2 A tasbih recovered from a mid fourth /tenth century shipwreck in the Java Sea and one of

the earliest known physical vestiges of Islam in South East Asia.

Zhao Ru gua's (^ii?if iS) Zhufan zhi (Wi^lr'M) ('Account of the various/an')

of 622/1225 also includes references to envoys 'surnamed' Li during the fourth/tenth century. He notes, for example,

In the fourth year of the shun hua period [383/993], they [the country of Da

shi] sent tribute through the Assistant Envoy Li a wu (\$ 55^3) [ c Ali Ahmad],

who stated, at an audience granted him in the Chung Chong Hall [of the palace], that his country bordered on Ta ts'in, and that it produced ivory and

rhinoceros horns. The Emperor T'ai tsung asked him how rhinoceros and elephants were captured. He replied, 'To capture elephants, we use decoy

elephants to get so near them that we can catch them with a big lasso. To catch a rhinoceros, a man with a bow and arrow climbs a big tree, where he

watches for the animal until he can shoot and kill it. The young rhinoceros are

not shot as they can be caught.' 1

A reference to this mission is also included in juan 490 of the Song Shi, where it

is recorded that the head of the mission was Pu Xi mi (Abu Hamid?), the master of an Arab vessel. It noted that, as Pu Xi mi was old and sick, he sent his

assistant Li Ya wu with his credentials to the court on his behalf. The mention

of methods for capturing rhinoceros and elephants suggests that at least the

'Da shi' deputy envoy 'Ali Ahmad was domiciled in Sumatra or Champa. While not all of the names of these Li 'surnamed' envoys can be recon structed, and some of those from Champa may actually be Chinese or Viet in

18 Hirth and Rockhill, Chauju kua, pp. 117 18.

372

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

origin, there are sufficient names which can be firmly reconstructed to

elude that the people who bore them were Muslims. That this name repre sented "Ali" is widely acknowledged. The question then arises as to why so

many of these Islamic envoys should have borne the name 'c Ali' or have had it

assigned to them by the Chinese chroniclers.

One possibility is that the people who adopted or were assigned the 'Li' surname were those who traced their religious origins to c Ali ibn Abi Talib,

the son in law of the Prophet, and who thus were 'Alids/Shi'a. 19 Did they perhaps move into South East Asia as a result of persecutions in the Arab lands? An eighth/fourteenth century Arab source suggests that was indeed the

case. The description of Sanf (Champa) from Mehren's edition of Dimashqi

(pp. 168 9) has been translated from the Arabic by Mike Laffan, and notes: 2,0

the city of Sanf is on the coast and its people are Muslims, Christians and idolaters. The Islamic call (da'wa) reached them in the time of Uthman (may

God be pleased with him).

An interpolation from a variant edition continues:

The 'Aliyyun fleeing from the Bani Ummaya and al Hajjaj 21 settled there and

entered the Sea of Zifti 22 and settled on [p. 169] the island for which they are

known to this day. 23

Even though this is from an eighth/fourteenth century text, it suggests a tradition that 'Alids had been in the South East Asian region from the time of

the third caliph c Uthman, who died in 35/656. 24 It also provides powerful

19 On the emergence and evolution of the Shi'ites (more formally shTat 'Alt, 'the party of

'AH'), see Chase F. Robinson's 'The rise of Islam, 600 705' (The new Cambridge history of Islam, vol. I, ch. 5).

20 Personal correspondence, June 2005. Mehren, August Ferdinand, Manuel de la cosnw

graphic du moyendge traduit de Varabe 'Nokhbet ed dahrfi 'Adjaib il birr wal bahr' de Shems

ed Din Abou 'Abdallah Chapter 2 Moh'ammed de Damns, et accompagne d'eclaiteissements

(Copenhagen, 1874).

21 For al Hajjaj, see www.princeton.edu/~batke/itl/denise/hajjaj.htm. In his chapter

above, Andre Wink notes that some of the Mappilas of the Malabar coast also traced

their origins to those who fled from al Hajjaj.

22 Laffan assumes that Zifti (^ii. j) should be read as Zanqi or Zanqay (i^j) and that the

following insular reference is to Hainan.

23 Pierre Yves Manguin provides another translation of this from Ferrand's French ver

sion: 'the country of Champa, with its principal town of the same name ... is peopled by

Muslims, Christians and idolators. The Muslim religion went there in the time of

Othman ... and the Alids, expelled by the Omeyyads and by Hajjaj, took refuge

there.', Manguin, 'The introduction of Islam into Champa', pp. 290 1.

24 Similar claims were made by Marvazi (sixth/ twelfth century) and 'Aufl (seventh/

thirteenth century). See D. D. Leslie, Islam in traditional China (Canberra, 1986), p. 39

and S. Q. Fatimi, Islam comes to Malaysia (Singapore, 1963), pp. 53 6.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

support for the thesis that the people surnamed 'Li' in the Chinese texts were

descendants of refugee c Alids, 25 who adopted that 'surname' through their

religious affiliation with 'Ali ibn Abi Talib. We can also draw comparisons with the names of the Muslim rulers of Kilwa on the East African coast, albeit

of a slightly later date. 2.

What is also worth noting is that we observe no more confirmed Islamic envoys to China bearing the Li 'surname' after the first two decades of the

fifth/ eleventh century, suggesting that perhaps the Cola attacks on maritime

South East Asia in 415/1024, 27 which were obviously quite traumatic for the

region, affected the traders who bore this 'surname'. 2. This further suggests

that these traders /envoys had been based at the port/s of Sriwijaya.

A selection of envoy names which included the Pu 'surname', extracted from

Chinese texts relating to the tenth twelfth centuries, is provided in Appendix 2.

Again, given the reconstructions, there can be little doubt that the majority of the

envoys bearing these names were Muslims. The list of polities represented over

laps a great deal with those from which the 'Li' envoys came San fo qi/Zabaj,

Champa and the Arab lands but with occasional envoys noted from Bo ni/Brunei, Java and Zhu nian/the Cola empire. In one case, comprising two refer

ences, we can identify the envoy from 'the Arab lands' as having had (or having

been assigned) a name which can be reconstructed as Abu Mahmud Tabriz!

suggesting that he was either from or was associated with the city of Tabriz.

Some other interesting elements are notable. One envoy, Pu Ma wu (yif ]#

vJ\) whose name can be reconstructed, with Hokkien or Cantonese pronun

ciation, as Abu Mahmud is recorded as being an envoy of the Arab lands in

466/1073 and as a representative of Champa in 479/1086. Does this suggest a

wide ranging trader who represented a variety of people or polities in the tribute trade with Song China?

25 For whom, see Ef 'Alids' (Bernard Lewis).

26 The period from the fourth/ tenth century to the fifth/eleventh century was a key period

in the introduction of Islam to the East African coast. The founder of Kilwa was known as

'Ali ibn al Hussain ibn Ali, while the frequency of the name 'AH among subsequent rulers

suggests that the name had a special significance for some Islamic communities in this

period. Joao de Barros, Da Asia, four Decadas in 9 vols. (Lisbon, 1777), I: Livro VIII: Cap. VI

notes, from the chronicle existing at that time, rulers of Kilwa with the names Ale Bumale,

Ale Bufoloquete, Ale Bonebaquer, Ale Ben Daiite and Ale Boni.

27 For which see G. Coedes, The Indianized states of Southeast Asia (Honolulu, 1968), pp. 141 4,

and Hermann Kulke, K Kesavapany and Vijay Sakhuja (eds.),

Nagapattinam to

Suvarnadwipa: Reflections on the Chola naval expeditions to Southeast Asia (Singapore, 2009).

28 The last Muslim envoy from San fo qi to China in the first half of the fifth/ eleventh

century was Abu Abd Allah in 419/ 1028. The next envoy was Di huajia luo (Dewakara)

in 468/1077. This fifty year hiatus seems to suggest that the C6la attacks on the

Sriwijayan realm had quite serious repercussions.

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

As noted above, the frequency of the appearance of Li 'surname' trader envoys

in Chinese texts declined after the first few decades of the fifth /eleventh century,

but those bearing the Pu 'surname' seem to have continued their links with

the Chinese court, almost as many arriving in China during the fifth/eleventh

century as in the fourth/tenth. It was also people bearing the Pu 'surname' who

were to later settle in China and become important in the maritime trade relations

of the Southern Song, of which more below.

From whence came the Pu 'surname'? In their translation and study of the

account of San fo qi 29 in Zhao Rugua's Zhufan zhi, Hirth and Rockhill record

that 'a large proportion of the people of the country are surnamed "P'u" (m)'.

A similar claim was made for Hainan at about the same time. These translators

also drew attention to the likely equivalence between 'Pu' and the Arabic kunya element Abu. 3 ° Today it is widely accepted that the Chinese Pu, as used

as a 'surname' for maritime traders, indeed derives from the Arabic 'Abu'. But,

while the 'surname' Pu was apparently derived from the Arabic kunya element

Abu, it was used in a very different way within the Chinese texts in assigning

names to these Muslim traders.

That the activities of those Muslim maritime traders who were 'surnamed'

Pu in the Chinese records were not greatly affected by the Cola attacks of the

early fifth /eleventh century suggests that a large number were based in the

ports of Champa rather than Sriwijaya. But their links with China were to grow ever closer over the ensuing centuries. In 292/904, the head of the foreigners in Guangzhou/ Canton was recorded as Pu Ho li (Abu 'Ali). 31

In 376/986, a member of the Pu clan Pu Luo e (Abu Nur?) led members of his community from Champa to Hainan to escape what is described in the

Song Hui yao as pressure from Jiaozhou (the early Viet polity). 32 Two years

later, another Muslim from Champa, Hu xuan (Husayn), reportedly led 300

members of his clan to Guangzhou. 33 This suggests, first, that these Muslim

29 The Chinese transcription of the name Zabaj /Zabag, for which see Laffan, Findingjava.

30 Hirth and Rockhill, Chauju kua, p. 60. Their note to this part of the text (p. 64 n. 3)

suggests: 'P'u stands for Bu, an abbreviation of Abu "father", which precedes so many

Arabic names. The phrase j|J\$:i:})f "many are surnamed P'u", occurring here and there

in Chinese ethnographical literature may safely be taken to indicate Arab settlements.

Hirth, Die Insel Hainan 487, note.'

- 31 Wang Bu et at, Tang Hui yao [Collected statutes of the Tang] (Beijing, 1957), juan 100,
- p. 1799. See Leslie, Islam in traditional China, p. 38.
- 32 See Geoff Wade, Champa in the Song Hui yao, Asia Research Institute Working Paper

Series, 53 (Singapore, Nov. 2005).

33 See Appendix 3 below. See also Manguin, 'The introduction of Islam into Champa', p. 292.

375

## The New Cambridge History of Islam

groups in Champa were quite large and, second, that in the late fourth/tenth

century, they had began to establish Islamic communities in the ports of Hainan and Guangzhou.

The Champa Muslims who settled in Hainan appear to have been key links

between Islamic communities in Champa and those in China. An eleventh/

seventeenth century Chinese encyclopaedia, Gujin tushu jicheng, which brings

together much earlier material, informs us of the following about Aizhou, which was located on the southern coast of Hainan:

The foreigners [here] were originally from Champa. During the Song and Yuan dynasties [tenth thirteenth centuries], because of great disorder, they

brought their families in ships and came to this place. They settled along the

coast and these places are now called 'foreigners' villages' or 'foreigners' coast'. The people now registered in Sanya village are all of this tribe. Many of

them are surnamed 'Pu' and they do not eat pork. Within the home, they

not worship their ancestors, but they have a deity hall, where they chant scriptures and worship their deity. Their language is similar to that of the Hui

hui 34 ... They do not marry the natives and the latter do not marry them.

Here, then, we have strong evidence of a Muslim community, including many members of the Pu clan, tied to both Champa and China and situated on

the maritime route linking the two. 35 Little is heard of these communities

during the fifth/ eleventh century, but we do have an account from Dongnan

jiwen (j^P^iiSISH), a Yuan work which refers to Song dynasty events. It notes

of the period: 'Many Sea Lao (\$f \$\frac{1}{2}E) lived scattered about in Canton. The most

prominent among them was a man surnamed Pu (fff) who was by birth a noble of Chan ch'ong [Champa]. Later on, he took up his permanent resi dence in China, to attend to his import and export trade. He lived inside the

city where his home was furnished in the most luxurious fashion, for in wealth

he was the first of the time.' 36 This was the beginning of the Pu clan in China

a major element in the story of Islam in the maritime realm which connected

South East Asia and South China, and of which more below.

34 Referring mainly to Islamic peoples of Central Asia.

35 Hirth also cites from the Tushu jicheng (juan 1380) a fourteenth century reference to a

temple at the port of Liantang on Hainan, where the deity was known as Bo zhu (Jfti),

or Master of the Ship, where pork was forbidden and where everyone referred to the

temple as the fan shen miao (llrttMB), or 'temple of the foreign deity'. See Kuwabara

Jitsuzo, 'On P'u Shou keng', Memoirs of tfte Research Department of the Toyo Bunko, 2 (1928), p. 21.

36 Hirth and Rockhill, Chauju kua, p. 16 n. 2. See also Kuwabara, 'On P'u Shou keng', 1, p. 44 for full text.

376

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

Another mystery of this period relates to the polity of Kalah/Killah/Kra, which was, according to the Arab geographers, an entrepot, a place marking

the border of India, 'the general rendezvous of the ships of Siraf and Oman,

where they meet the ships of China', a producer of tin, and a place frequented

by Indians. The conditions described are all met by a polity centred on the

portages linking the western coastal region of what is today the southern Thai

peninsula, and its eastern seaboard, with tin being found throughout the Phuket and Kedah areas, and trans peninsular portage available between 'the ships of Siraf and Oman' and the ships of China. In the Chinese texts, the polity was named Gu luo 37 and in these texts it is noted that Gu luo controlled twenty four subordinate polities and had a sizeable army. In the

story of Islam in South East Asia, this must have been one of the main ports

frequented by ships from the Arab and Persian worlds from the second / eighth

to fourth/tenth centuries, and in fact it was the South East Asian polity most

frequently mentioned in the Arab texts. Its precise identification, location and

extent remain to be ascertained, but its centre likely lay near Takuapa on the

peninsula. The excavation in Sungei Bujang, Kedah, of two silver coins issued

by the c Abbasid caliph Al Mutawakkil (r. 232 47/847 61) suggests that Kedah

was not outside this trade zone in the third/ninth century. 38

We also need to examine the Sumatran port polity of Barus for what it tells

us of Islamic traders in the fourth/tenth and fifth/ eleventh centuries. References to Barus /Fansur, famed as a port for camphor exports, date back

to the second /eighth century. 39 Barus was also already well known to the

Arab geographers in the fourth/tenth century as a source of excellent cam

phor, the Fansuri camphor. 40 We can certainly thus assume that Islamic merchants traded through this port during its heyday in the third/ninth to fifth/ eleventh centuries in their quest for camphor and other Sumatran

### 37 Likely 'Kra'.

38 For further details, see Tibbetts, A study of the Arabic texts, pp. 118 28. The Middle Eastern

ceramics found in the area are described in Bennet Bronson, 'Chinese and Middle Eastern

trade in southern Thailand during the 9th century AD', in Amara Srisuchat (ed.), Ancient

trades and cultural contacts in Southeast Asia (Bangkok, 1996), pp. 181 200. For the two

silver coins see H. G. Quaritch Wales, 'Archaeological researches on ancient Indian

colonization in Malaya', JMBRAS, 18, 1 (1940), pp. 32 3.

39 Under the early name Po lu shi and Po luo suo (sometimes obviously confused in

Chinese texts with Bo si or Persia) and later under the names Bin su, Bian shu and

Bin cuo for Pansur/Pancur. See Roderich Ptak, 'Possible Chinese references to the

Barus area (Tang to Ming)', in Claude Guillot (ed.), Histoire de Barus, Sumatra: Le site de

Lobu Tua, I Etudes et documents, Cahier d'Archipel 30 (Paris, 1998), pp. 119 38.

40 See Tibbetts, A study of the Arabic texts, pp. 92 3, 95 6, 114 15, 140 3. Jane Drakard has

also studied these sources in her 'An Indian Ocean port: Sources for the earlier history of

Barus', Archypel, 37 (1989), pp. 53 82.

377

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

products. 41 The third/ninth to fifth /eleventh century Islamic glass and ceramics excavated at the site also suggest linkages with the Middle East 42 and

these correlate with the Chinese ceramics of the same period discovered there. 43

An important piece excavated in Barus is a glass seal of the fourth/tenth to fifth/

eleventh centuries, likely deriving originally from Iran, and bearing a Kufic style

inscription 'Allah. Muhammad'. 44 This and the other Middle Eastern trade

products certainly suggest an Islamic presence in west Sumatra during these

centuries. Separately, it appears that Islamic influence continued in Champa.

Zhao Rugua noted that in 377/987 the Cham polity of Panduranga brought

tribute to the Chinese court, in the company of those of Da shi (Arabs). 45

Two political events affecting Muslims in South East Asia stand out from the

available records of the fourth/tenth and fifth/ eleventh centuries. As noted

above, some hundreds of Muslims removed in the 370s /980s to Hainan and

Guangzhou to escape political turmoil in Champa. It is likely that it was these

people who formed the nucleus of the Muslim community at Sanya on the southern coast of Hainan, which has continued into the present day. 46 The

other event, reflected in the listings of Muslim envoys to the Song court, was

the Cola attacks on South East Asia. The reasons for these attacks are not clear,

but the possibility that the Cola ruler Rajendra I wished to take control of the

trade passing through the Straits of Malacca should not be excluded. Raids are

suggested for 408/1017 and 416/1025. While missions to China from Da shi (the

Arab lands') saw a hiatus from 410/1019 until the 440S/1050S, Champa missions

to China led by Muslims continued during this period. It thus appears that

Islamic trading links with the Straits were affected by the attacks on, and probable capture of, the major ports in the region by Cola forces. These military activities likely permanently changed the patterns of Middle Eastern

41 The links between Barus and the various ports of the Middle East are discussed in

Claude Guillot (ed.), Histoire de Barus, Sumatra: Le Site de Lobu Tua, II Etude

archeologique et Documents, Cahier d'Archipel 30, (Paris, 2003), 'Ch. II 'Conclusions

historiques', pp. 45 6 and 60 2.

42 Claude Guillot and Sonny Ch. Wibisono, 'Le verre a Lobu Tua: Etude preliminaire', in

Guillot (ed.), Histoire de Barus I, pp. 189 206; and Guillot (ed.), Histoire de Barus II, ch. V

'Ceramique du Proche Orient', pp. 171 96.

43 Marie France Dupoizat, ch. IV 'Ceramique chinoise', in Guillot (ed.), Histoire de Barus II, pp. 103 69.

44 Guillot (ed.), Histoire de Barus II. See 'ch. VII Verre', p. 268, plate 58. See also Ludvik

Kalus, 'Le plus ancienne inscription islamique du monde malais?', Archipel, 59 (2000), pp. 23 4.

45 Hirth and Rockhill, Chauju kua, p. 51.

46 For one of the few historical reports on this community, see Chen Da sheng and

Claudine Salmon, 'Rapport preliminaire sur la decouverte de tombes musulmanes

dans l'lle de Hainan', Archipel, 38 (1989), pp. 75 106.

378

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

trade to the archipelago. We certainly have evidence of the likely related rise of

the Tamil guilds in Barus during that century. 47 Muslims resident in Champa,

however, continued to operate their tribute trade missions to China.

Islam in South-East Asia from the eleventh to the thirteenth centuries

By the second half of the fifth/ eleventh century, envoy merchants from the

Middle East were again arriving in China by sea, through South East Asia.

This period also saw a major shift in the region's maritime trade, with the Fujian port of Quanzhou eclipsing the former trade centre of Guangzhou. Quanzhou quickly became the site of mosques 48 and Tamil temples, as the

maritime merchants from lands extending all the way to West Asia brought

trade products to China and took Chinese products on their return journeys.

On this voyage, it is clear that Champa was a major staging post. As noted

above, Muslim traders were leading Champa missions into China throughout

the fourth/tenth and fifth/eleventh centuries. A Chinese official text the SongHui yao records the following of Champa in the fifth/eleventh or sixth/

twelfth century: 'There are also mountain cattle, but they cannot be used for

ploughing. They are only killed in sacrifice to the spirits. When they are about

to be slaughtered, a medium is instructed to offer prayers, which sound thus:

"Allahu Akhbar". In translation, this means: "May he be early reborn.'" Here

then we have a Chinese account which, although somewhat erroneous in interpretation, clearly records that an important element of animal slaughter

in at least part of Champa society was the affirmation of the supreme greatness

of Allah. The same work notes: 'Their customs and clothing are similar to those of the country of Da shi [the Arab world].' In that the Chinese chronicler

considers these to have been aspects of Champa society, there must have been

a considerable Islamic community residing in at least the major trade port of

that polity during this period. The provenance of two Kufic inscriptions earlier

ascribed to Champa has been shown to be very suspect, 49 but are now not

needed for us to demonstrate an Islamic community in Champa at this time.

That the Islamic communities of China and South East Asia were intimately

47 See, for example, Y. Subbarayalu, 'The Tamil merchant guild inscription at Barus: A

rediscovery', in Guillot (ed.), Histoire de Barus I, pp. 25 33. The inscription is dated to the equivalent of 1088 CE.

48 The oldest mosque in Quanzhou the Qingjing mosque reputedly dates from the

eleventh century when the port began to rise in importance.

49 Ludvik Kalus, 'Reinterpretation des plus anciennes steles funeraires islamiques nou

santariennes: I. Les deux inscriptions du "Champa", Archipel, 66 (2003).

379

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

tied during the sixth/twelfth century is apparent from a comment by al Idrisi

(493 560/1100 65), who stated that when China was convulsed by troubles,

the (Muslim) merchants would descend to the harbours of a place they called Zabaj. 50 This was a reference to the ports of Sumatra and surround

ing areas.

Halfway around the globe, in and near the Red Sea, the sixth/twelfth and seventh/thirteenth centuries saw Yemeni ports developing their links with regions to the east under the aegis of the Ayyubids (566 648/1171 1250)

in Egypt and subsequently the local Rasulid dynasty (625 858/1228 1454).

This revitalised the luxury and spice trades with India and ports further east, providing further avenues for Muslims to travel to and interact with people from the South East Asian realm, as well as further reasons for South

East Asians and Chinese to travel to the major Islamic centres in the Middle

East.

Quanzhou thus became the end port for the long journey from the Arab and Persian lands, as well as a key port for those Muslims trading from South East Asia. From the sources we have available, more than half of the

foreign trade into Quanzhou appears to have been controlled by Muslims in this period. By the seventh/ thirteenth century, when the Mongols ruled

over China, it appears that Quanzhou was being administered as a Muslim

polity, funded through its trade with South East Asia and beyond. The boom

in maritime trade during the sixth/twelfth and seventh/thirteenth centuries

underwrote Islamic power in Quanzhou, and in this, Pu Shougeng and his family were major players.

Islamic links between Quanzhou and Brunei during this period are evidenced by material remains. A grave of a Song dynasty official surnamed Pu

and likely from Quanzhou has been found in Brunei. Dated to the equivalent

of 662/1264, it is the earliest Chinese script gravestone in South East Asia as

well as one of the earliest Muslim gravestones. 51 The Pu clan was a major

element in the story of Islam in the maritime realm which connected South

East Asia and south China. One account suggests that an unnamed Pu

50 al Idrisi, Opus geographicum, ed. E. Cerulli et at, 2 vols. (Rome, 1970), vol. I, p. 62. Cited in Laffan, Findingjava, p. 22 n. 65.

51 The assumption is that this official surnamed Pu was, like other members of the Pu clan,

a Muslim. There exists in Leran, east Java an Islamic gravestone dated 475/1082 of a

woman, the daughter of Maimun. However, there is no firm evidence that the grave

stone originated in Java, and it has been suggested that it was possibly brought there as

ballast. See Ludvik Kalus and Claude Guillot, 'Reinterpretation des plus anciennes steles

funeraires islamiques nousantariennes: II. La stele de Leran (Java) datee de 475/1082 et

les steles associees', Archipel, 67 (2004), pp. 17 36.

380

Cambridge Histories Online © Cambridge University Press, 201 1

## Early Muslim expansion in South East Asia

ancestor had originally come to Guangzhou from somewhere in the Arab world and was appointed as the headman of the foreign quarter in that city,

eventually becoming the richest man in the entire region. Another version

suggests that this person was a noble from Champa which, as noted above,

does not preclude him from having been an Arab. Could he have been a descendant of the Pu Luo e who led his family members to Hainan from Champa in 376/986 following political disturbance in that place? The fact remains that during the sixth/ twelfth century a person 'surnamed' Pu, a Muslim, was one of the richest men in the city of Guangzhou, and behind whose residence was a giant 'stupa' that was unlike Buddhist ones. This was

likely the minaret of the Huai sheng si, the famous mosque of Guangzhou.

The wealth of the family, however, declined, and the son of the Guangzhou

foreign headman, named Pu Kaizong (ifW/K), removed the family to Quanzhou, 52 as that port rose to dominate the trade with South East Asia

and beyond. It was his son, Pu Shougeng (fltlJPJit), who was to become famed in the histories of Quanzhou, Chinese Islam and maritime trade with

South East Asia. 53 Reputedly for his assistance in suppressing pirates in the

region of Quanzhou, Pu Shougeng was rewarded by the Song court in 672/

1274 with the position of maritime trade supervisor in the port. All maritime

trade through Quanzhou was subject to his control, and as this was the major

port of the entire polity, the opportunities for gain would have been enor mous. He and his brother also operated many ships. Pu Shougeng was subsequently appointed to even higher office with a provincial post, only a

few years before the Yuan armies crushed the Southern Song capital at Hangzhou and the Song dynasty came to an end.

Even before they took Hangzhou, the Yuan generals had recognised the power of Pu Shougeng and his brother in south eastern China and had sent

envoys to invite them to side with the Yuan. The Pu brothers knew where their future lay, and they gave their allegiance to the incoming Mongols, probably by 674/1276. The importance of this to the Yuan was enormous, as it

provided them with a local regime possessing access to the sea, something

which the Mongols had never commanded. Their new ally subsequently massacred the Song imperial clansmen who resided in Quanzhou, showing

his allegiance to the Mongols. The Yuan rulers richly rewarded those who had

assisted them and Pu Shougeng was appointed as the Grand Commander of

52 This is noted in He Qiaoyuan, MinShii (Ullif) [An account of Fujtan] (Fuzhou, 1994), juan 152.

53 For the most detailed account of Pu Shougeng, see Kuwabara, 'On P'u Shou keng', 2,

pp. 179, and 7 (i935), PP- i 104.

381

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Fujian and Guangdong, and subsequently as a vice minister of the Fujian administration. Pu was tasked with assisting the Mongols in both promoting

maritime trade and providing ships and personnel for some of the Mongol

invasions of overseas polities. It is not surprising that the first countries to

respond to Pu Shougeng's invitation to resume trade were Champa in South

East Asia and Ma'abar on the subcontinent both major trading polities with

large Muslim populations. One of the latest reports we have of Pu Shougeng,

dating from 680/1281, notes that he had been ordered by the Yuan emperor to

build 200 ocean going ships, of which 50 had been finished.

The arrival of the Yuan forces in southern China in the 670s /1270s and the

violence which accompanied that arrival had apparently spurred some Muslims to leave Chinese ports and, as in the past, flee south. Li Tana has

examined the Vietnamese annals on this point and found reference to Muslim

refugees from China arriving in the Vietnamese polity in 672/1274. 54 This date

fits well with the last ditch Song defence of Yangzhou during the Yuan attack

on that city in 673/1275. Yangzhou was a very cosmopolitan city and it would

not have been surprising if some of the Muslims resident there would have

opted for safer climes to the south prior to the attack. 55

At approximately the same time, on the other side of the archipelago, we begin to see evidence of the emergence of Muslim rulers in South East Asia.

An Islamic gravestone is reported for a Sultan Sulayman bin 'Abd Allah bin al

Basir of Lamreh dated 608/1211. 56 The dating of the gravestone remains

controversial, but if confirmed this will be the first evidence of a Muslim ruler in the Nusantaran world. Separately, in the account of his return journey

by sea from China, Marco Polo reported in the 690s/1290s that the Sumatran

city of Perlak/Ferlec was Muslim, 57 but neighbouring urban centres named

Basman and Samara were not. The latter polity was more than likely Samudera, where a gravestone of the reputed first Islamic ruler of that

54 Personal communication from Li Tana. For original text, see Chen Ching ho, mljfi f^ll

(ISftjtt-n ^ < i:@iH5^# , (3 :£), (Dai Viet su ky loan thu) (Tokyo, 1985 6), pp.348 9.

55 One apparent victim of the battles at this time was Pu Ha ting, a sayyid of the sixteenth

generation and builder of the Xianhe mosque in Yangzhou, who died in 673/1275. See

Leslie, Islam in traditional China, p. 48.

56 Suwedi Montana, 'Nouvelles donnees sur les royaumes de Lamuri et Barat', Archipel, 53

(1997), PP- 85 96. See p. 92. There remains much dispute over the dating and other

aspects of this gravestone.

57 'This kingdom, you must know, is so frequented by the Saracen merchants that they

have converted the natives to the Law of Mahommet I mean the townspeople only,

for the hill people live for all the world like beasts.' Henry Yule (trans, and ed.), The book

of Ser Marco Polo, 2 vols., 3rd edn (London, 1929), vol. II, p. 284.

382

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

polity Sultan Malik al Salih dated 696/1297 has been found. 58 In the 680s/

1280s, two envoys came to the Yuan court from Samudera (Su mu da), and

they bore patently Islamic names Hasan and Sulayman. These phenomena

suggest a new age in the relationship between Islam and South East Asia, with

rulers of polities adopting the new religion. That the rise of these Islamic polities was linked with the rise and expansion of the Mamluks (648 923/1250

1517) in Egypt is suggested by the adoption by Samuderan sultans of the title

al Malik al Zahir, an apparent commemoration of the Mamluk sultan al Malik

al Zahir Rukn al Din Baybars al Bunduqdari (r. 658 76/1260 77) of Egypt and

Syria, who had defeated the Seventh Crusade sent by Louis IX, as well as the

Mongol forces at 'Aynjalut in Palestine in 658/1260. The indigenous tradition

relating to these earliest Islamic polities in Sumatra was later recorded, some

what anachronistically, in Hikayat Raja raja Pasai. 59

More direct links between Samudera and the ports of western India are

evidenced by the material remains of the age. The cemeteries of Samudera have

a range of gravestones, some with bismillahs in Kufic script, and these have been

shown to be linked with the gravestones of Cambay in Gujarat. These stones

were seemingly imported from Cambay, but were carved locally with local

artistic elements. ° Muslim traders from the Arab world had long traded through Cambay, and Elizabeth Lambourn provides a revealing study detailing

the pre conquest regional networks of Islamic judges and clerics connecting

Rasulid Yemen with the ports along the western coast of India. \* It was only in

the early eighth/fourteenth century however that Gujarat was taken by the

Khaljis and Islamic rule was instituted in the region. The links between Gujarat

and the archipelago strengthened through the eighth/fourteenth and ninth/

fifteenth centuries, with 1,000 Gujarati merchants residing in Melaka in the early

58 For further details of the gravestones, see Elizabeth Lambourn, 'The formation of the

batu Aceh tradition in fifteenth century Samudera Pasai', Indonesia ami the Malay World,

32 (2004), pp. 211 48.

59 See A. H. Hill, 'Hikayat Raja raja Pasai', journal of the Malaysian Branch of the Royal

Asiatic Society, 33, 2 (June i960).

60 More details can be found in Lambourn, 'The formation of the batu Aceh tradition'. See

also Lambourn, 'From Cambay to Pasai and Gresik the export of Gujarati grave

memorials to Sumatra and Java in the 15th century AD', Indonesia and the Malay World,

31, 90 (2003), pp. 221 89; and Lambourn, 'La production de marbre sculpte a Cambaye

au Gujarat et son exportation dans l'Ocean Indien (XHIe XVe siecles Ap. J. C.)', in J. M.

dos Santos Alves, C. Guillot and R. Ptak (eds.), Mirabilia Asiatica: Produtos raws no

comercio maritime Produits rares dans le commerce maritime. Seltene Waren im Seehandel

(Wiesbaden and Lisbon, 2003), pp. 209 52.

61 Elizabeth Lambourn, 'India from Aden: Khutba and Muslim urban networks in late

thirteenth century India', in Kenneth R. Hall (ed.), Secondary cities and urban netwo

in the Indian Ocean realm c. 1400 1800, (Lanham, MD, 2008), pp. 55 98.

38.3

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

tenth/ sixteenth century when the Portuguese arrived there. Such connections

drew Kern to note: 'The gravestones erected on Malik al Salih's grave were

brought in ready made from Cambay. 2 This is then where we must look for

the source of the spiritual and material links which joined Samudera to the

world of Islam.' 3 This opinion is disputed by other scholars. Marrison, for

example, proposes that south India was a far more obvious source, given the

long term existence of Islamic communities there, the local title Perumal used

in both southern India and Pasai, along with the dominance of the ShafTi school.

something which was not the case in Gujarat. 64 Marrison was, in some ways,

repeating the arguments put earlier by Snouk Hurgronje. 65 The arguments

hinge on the emergence of Islam in Kerala, but the chronology of this remains a

disputed issue. While there are Islamic gravestones there dated as early as the

second/eighth century, the tradition of local adherents appears to date only

from the early sixth/twelfth century.

The new appearance of the name 'Java' in Arab sailing itineraries (with the

concurrent decline of the earlier generic term Zabaj) in the early part of the

seventh/thirteenth century, and the description of Jawa as 'one of the lands of

China', suggests new trade routes at this time, resultant from changes both in

China, where maritime trade was being encouraged by the Southern Song

dynasty, and in South East Asia and India. These changes were also reflected

in the patterns of the spread of Islam.

Islam in South-East Asia in the fourteenth and fifteenth centuries

Why Islamic polities should have emerged in northern Sumatra in the seventh/

thirteenth century remains an enigma. It is obvious that Muslim traders had

been passing and stopping at these port polities for centuries before this. It is

likely that the rise of Islamic states in Sumatra was linked with the decline of the

Cola dynasty in southern India, the collapse of that country into war and the end

62 Lambourn dismisses this and notes that these gravestones were in fact ninth/fifteenth

or tenth/sixteenth century local remakes of earlier stones, perhaps commissioned by

the Acehnese after their conquest of Samudera Pasai in 1524.

- 63 R. A. Kern, De Islam in Indonesia (The Hague, 1947), p. 9.
- 64 G. E. Marrison, 'The coming of Islam to the East Indies', Journal of the Malaysian Branch

of the Royal Asiatic Society, 24, 1 (Feb. 1951), pp. 28 37.

65 G. W. J. Drewes, 'New light on the coming of Islam to Indonesia?', Bijdragen tot de Taal,

Land en Volkenkunde, 124 (1968), p. 441.

66 A. P. Ibrahim Kunju, 'Origin and spread of Islam in Kerala', in Ashgar Ali Engineer (ed.),

Kerala Muslims: A historical perspective (New Delhi, 1995). See pp. 18 21. See also

Chapter 9 in the present volume by Michael Pearson.

384

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

of the integrated regional economy which incorporated the northern Sumatran

polities. With the rise of the more domestically oriented Vijayanagara in south

ern India, the linkages of the Hindu Buddhist polities of Sumatra with the subcontinent would have declined, as would have the Tamil guilds, likely providing new avenues for religious conversion. However, the ports of the

Malabar coast and Sumatra continued to be meeting places and commercial

marts for traders from Yemen, South East Asia and China. The expansion of

Islamic trading networks, and some have suggested Sufi guilds, along these

maritime trade routes appears to have thus burgeoned.

From the eighth/fourteenth century we see growing evidence of the expansion of Islam in South East Asia. In Sumatra (or al Jawa as he referred

to it), Ibn Battuta recorded what he, or his informants, observed when passing

through the port polity of Samudera in 746/1345 and 747/1346. He noted that

the ruler one Sultan al Malik al Zahir was 'a Shafi c i in madhhab and a lover

of jurists' who 'often fights against and raids the infidels'. It was further noted

that 'the people of his country are Shafi'i who are eager to fight infidels and

readily go on campaign with him. They dominate the neighbouring infidels

who pay jizya to have peace.' 67 Through the account provided, we see a polity

whose ruler was engaged in frequent jihad, who sent missions to Delhi and to

Zaitun/Quanzhou, and who, at home, was surrounded by viziers, secretaries,

sharifs, jurists, poets and army commanders, and who obviously had close

links with Islamic societies to the west, and direct sea links with Quilon. The

Shafi'i school which the sultan followed has remained important throughout

Indonesia and in the coastal areas of India. We should not, however, consider

this to have been simply a Middle Eastern society or ruling structure trans

planted to South East Asia. It has been remarked that Ibn Battuta likely concentrated excessively on the cosmopolitan Arab /Iranian aspects of the

court, and ignored the Indie and local elements unfamiliar to him. Certainly,

the batu Aceh of the period reflect a strong indigenous element to the polity.

Ibn Battuta then visited Mul Jawa, the 'country of the infidels', which is accepted to mean that Islam had not gained any real foothold in the island of

Java by the mid eighth/fourteenth century. The only other major stop on the

voyage to China was Tawalisi, which has never been definitively identified.

The long standing importance of Champa as a stop on the Islamic trade route to China, however, makes it the leading candidate. This supposition is

67 H. A. R. Gibb, The travels of Ibn Battuta AD 1325 1354, trans, with revisions and notes from

the Arabic text, ed. C. Defremery and B. R. Sanguinetti, completed with annotations by

C. F. Beckingham, Hakluyt Society (London, 1994), vol. IV, pp. 876 7.

68 Lambourn, 'The formation of the batu Aceh tradition'.

385

## The New Cambridge History of Islam

supported by Yamamoto Tatsuro's equation of Kailukari, the name of the largest city in Tawalisi according to Ibn Battuta, with the Cham name Klaung

Garai, 69

The earlier West Asian links of Champa are manifested in the princess whom Ibn Battuta met in this polity, who spoke to him in Turkish, who was

literate in Arabic and who wrote out the bismilldh in the presence of the visitor.

The polity itself, however, he considered to be outside of Islam. He then travelled on to China, where Ibn Battuta noted the option of staying with Muslim merchants resident there, and that in Zaitun/ Quanzhou, the 'Muslims live in a separate city'. There he met Muslims from Isfahan and Tabriz. It thus appears that, for Ibn Battuta in the mid eighth/ fourteenth century, all the areas between the Islamic polity at Samudera and China remained outside Islam.

Events which occurred in southern China not long after the visit by Ibn Battuta, however, were to have major effects on Islam in South East Asia. The

port of Quanzhou was controlled by Muslims during this period, the Mongol

Yuan rulers including them within the semu 7  $^{\circ}$  group of Central Asian and

Middle Eastern officials who exercised Yuan power over the Chinese inhab

itants. The two major groups competing for power over the city and its foreign trade were the locally born Islamic families, including that of Pu Shougeng, and the newly arrived Isfahan group of Persians, both merchants

and troops, who had come to the area with the Yuan armies. In the 750s /1350s,

a descendant of Pu Shougeng, named Na wu na, controlled the local maritime

trade supervisorate for the Yuan court, while the Persians were represented

by two people Sai fu ding and A mi li ding both holding military positions as brigade commanders. At a time when the Yuan was in steep decline, and

when rebellions against the Yuan administration were occurring widely throughout China, it is not surprising that the tensions in Quanzhou also spilled over. The Yuan History tells us: 'In the spring of the seventeenth year of

the Zhi zheng reign [758/1357], the local brigade commanders Sai fu ding and

A mi li ding rebelled and took control of Quanzhou.' This so called Isfahan 71

rebellion was to last for ten years. It is possible that the prominent merchant

69 The name of a Cham temple complex (Po Klaung Garai) located at Phanrang in what is

today Ninh Thuan province. It comprises three towers dating back to about 700/1300,

built during the reign of Cham kingjaya Simhavarman II. See Tatsuro Yamamoto, 'On

Tawalisi as described by Ibn Battuta', Memoirs of the Research Department of the Toyo Bunko, 8, 1936, p. 117.

70 A reference to people from Central Asia and West Asia.

71 Chen and Kalus, following Maejima Shinji, suggest an alternative that the Chinese

term 'yi xi ba xi' should be reconstructed as ispdh and that it derives from the Persian

386

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

Sharaf al Dm of Tabriz, whom Ibn Battuta met in Quanzhou and from whom

he noted that he had borrowed money in India, was the same 'Sai fu ding' who is mentioned in the Yuan text. 72.

By 763/1362, the forces of Sai fu ding controlled much of the area around the

provincial capital Fuzhou, but were then defeated by Yuan forces and fled back

to Quanzhou, where it is reported that A mi li ding was killed by the maritime

trade supervisor Na wu na, who seized control of the Isfahan forces. He was in

turn killed and his forces destroyed in 767/1366. It has been suggested that the

members of the Pu Shougeng clan and others from earlier Arab and Cham

inflows into Quanzhou were Sunni, while the Isfahan forces were Shi'ite. This

possibly intra Islamic struggle in Quanzhou also quickly involved Mongol forces

of the Yuan and then the Chinese themselves who felt that they had been maltreated under Yuan rule. The breakdown of dynastic order gave an oppor

tunity to a more powerful contender for regional power Chen Youding, a former Yuan general, who was appointed governor of Fujian province. With the

assistance of Jinji, a general of Persian origin, he began methodically murdering

Sunni followers, as well as destroying Sunni graves, mosques and residences. It

appears that initially the purge was directed at Sunni followers, but that it was

later expanded by some of the forces into a broader anti Islamic campaign, with

the depredations lasting for almost a decade after Chen Youding captured

Quanzhou. Those who escaped the purge either fled into the mountains or

set sail. This flight of Muslims by sea from Quanzhou and elsewhere in Fujian

into South East Asia in the 760s /1360s greatly stimulated the development of

Islam in the latter region. Those who remained in Quanzhou, including the

prominent Guo clan, appear to have been descendants of the Persian ShTites.

Not much more than a decade after the first massacres in Fujian, Muslim tombs began to appear in Java. Most of these were devoted to elite figures

apparently intimately involved with the administration of the Majapahit state. These gravestones (maesan) began appearing at Trowulan and Trayala

near ancient Majapahit in the 770s /1370s and their dates extend well into the

second half of the ninth/fifteenth century. 73 They were inscribed with the

Saka year in ancient Javanese script on one side of the stone, and with pious

term sepah, meaning 'great army'. See Chen Da sheng and Ludvik Kalus, Corpus

d' inscriptions arabes et persanes en Chine, 1. Province de Fujian (Quanzhou, Fuzhou,

Xiamen) (Paris, 1991). See p. 45 n. 151.

72 It is also likely not coincident that another senior person whom Ibn Battuta met in

Quanzhou was Shaykh al Islam Kamal al Din, 'a pious man' who indeed came from

Isfahan. Was he the other leader of the rebellion, 'A mi li ding' (Kamal al Din)?

73 See Louis Charles Damais, 'Etudes javanaises: Les tombes musulmans datees de

Tralaya', Bulletin de VEcole Francaise d'Extreme Orient, 48 (1956), pp. 353 415. See listing and dates of the graves on p. 411.

387

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Islamic inscriptions in Arabic on the other. Given what we know of the situation

in Quanzhou in the 760s/ 1360s and the links already established between

Champa and Quanzhou in this period, the existence of the tomb of Puteri Cempa (the Champa princess) in Trowulan, 74 dated to 852/1448, underlines

the likelihood that these graves belong to Muslims who fled the conflagrations

in southern China in the 760s /1360s, and were then engaged in various capaci

ties by the Majapahit court, maintaining links with both Champa and the southern Chinese ports. The sudden appearance of a group of Muslims, possibly

Sunnl, intimately tied to the Javanese administration is otherwise difficult to

explain. It is possible that this Puteri Cempa was Haji Ma Hong Fu's wife, whom

Parlindungan's 'Annals of Semarang and Cirebon' tell us, 'had passed away and

was buried in Majapahit according to Islamic rites' in or just before 853/1449. 75

Earlier references in these annals tell us that Haji Ma Hong Fu, who had his

origins in Yunnan, had been married to the daughter of Haji Bong Tak Keng,

who had been appointed by the Chinese in Champa/ 6 At Surabaya, the pecat

tanda, that is, the 'head of the market', at Terung was also a Chinese person

employed as an official by the Majapahit court, and it was he who protected a

young Muslim who had come from Champa and who would later become Raden Rahmat. 77 While Damais and others believe that the people interred in

the Trowalan and Trayala graves were Javanese, the possibility should thus also

be considered that these were people from abroad who had given their allegiance to the Majapahit polity. New polities on Java also suggest new arrivals

at this time. Demak on the northern Javanese coast first appeared in the his

torical record in 779/1377, and is recorded as having sent 'tribute' to the Ming

court in 796/1394. The possible founding of this pesisir (coast) polity by refugees

in the 760s / 1360s or 770s / 1370s conforms to all that we know of it. Javanese texts

also record Muslim leaders coming to Java from Champa, and settling in the

three most important early centres of Islamic propaganda Surabaya

74 The grave remains today an Islamic pilgrimage site.

75 H.J. de Graaf and G. Th. Pigeaud, Chinese Muslims in Java in the 15th and 16th centuries:

The Malay Annals of Semarang and Cerbon, ed. M. C. Ricklefs, Monash Papers on

Southeast Asia, 12 (Melbourne, 1984), p. 20. I am assigning this text more veracity

than hitherto accorded to it for reasons detailed below. For Parlindungan see pp. 396 7.

76 Ibid., p. 14. This fits precisely with the date of the Trowulan tomb, but those who are

suspicious of the Parlindungan source might point to the fact that Damais's article on

the tombs was published in 1956, while Parlindungan's work Tuanku Rao within which

the 'Annals' are contained, was only published in 1964, allowing for the information on

the tombs to be incorporated in the latter work.

 $77\ \mathrm{Denys}\ \mathrm{Lombard}$  and Claudine Salmon, 'Islam and Chineseness', in Gordon, The

Propagation of Islam, p. 184. See also the correlation in Javanese texts between Champa

and the spread of Islam as detailed by Manguin in 'The introduction of Islam into

Champa', pp. 294 5.

388

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

(Ngampel), Gresik (Giri) and Cirebon (Gunung Jati). By the early ninth/fifteenth century, Gresik had over 1,000 'Chinese' families, likely including the

Muslim people of diverse ethnic origins who had fled from Fujian.

Evidence from Sumatra also supports the argument for a flight of hybrid Persian Arab Cham Chinese Muslims out of southern China into maritime South East Asia during the 760s /1360s. Recent archaeological surveys and

excavations in Barus reveal that the earliest Islamic tombstone found there

dates from 772/1370, 78 which fits excellently with the chronology proposed

above. The name of the woman buried beneath the tombstone Suy may be

Chinese, while the inscription itself contains Persian grammar and Arabic terms. Thus, the 760s /1360s likely saw the return of an Islamic community to

Barus following the driving out of the earlier community in the fifth/ eleventh

century by the Colas. By the beginning of the tenth/ sixteenth century, Tome

Pires spoke of Barus as being a wealthy port and well known to the Gujaratis,

Persians, Arabs, Tamils and Bengalis.

Brunei's adoption of Islam in this period is reflected in the gravestone of a

eighth/fourteenth century sultan, named 'Maharaja Brum', found in the Residency cemetery in Bandar Seri Begawan. Links between that community

and China are indicated by the fact that the gravestone was certainly manu

factured in Quanzhou and transported to Brunei, as it is almost identical to

those carved in China and, like them, is also made of diabase and inscribed

completely in Arabic. In Terengganu, a stone inscribed in Malay written in

Arabic script and dating from the eighth/fourteenth century suggests that Islamic law was being promoted in at least this estuary of the Malay peninsula.

In both these places, there is evidence that Islam had been a recent arrival, and

the process of adjustment was still taking place. The Brunei ruler, for example,

was still being entitled maharaja 79 while the Terengganu inscription referred

to the Almighty by the Sanskritic name 'Dewata Mulia Raya' alongside the

name Allah. In addition, the Terengganu law code provided for differentiated

fines depending on social rank, a practice unknown to more orthodox Islam.

Kern suggested that 'we have here a stone inscription from a convert, undoubtedly assisted by someone learned in the law, among a population yet to be converted'. ° The same phenomenon is manifested in two late

78 Ludvik Kalus, ch. XIV 'Les sources epigraphiques musulmanes de Barus', in Guillot

(ed.), Histoire de Barus II, pp. 303 38. For the tombstone cited, see pp. 305 6. John Miksic

drew my attention to this artefact.

79 The title maharaja was still in use for the ruler of Brunei in the early fifteenth century.

80 R. A. Kern, 'The propagation of Islam in the Indonesian Malay archipelago', in Gordon (ed.), Tfte propagation of Islam, p. 36.

389

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

eighth/fourteenth century gravestones at Minye Tujuh in north Sumatra for

the daughter of Sultan al Malik al Zahir, J which have inscriptions in both Arabic and in Old Malay written in an Indie inspired Sumatran script. That

sometimes political power in the Islamic polities of South East Asia reverted to

persons who were not Muslims is suggested by the fact that in the early tenth/

sixteenth century, the governor of Melaka wrote to the king of Portugal noting that 'the king of Brunei is a pagan, the traders are Moors'.

Thus, the eighth/ fourteenth century can certainly be seen as a period of wider extension of Islam within South East Asia. Apart from those manifesta

tions noted above, Chinese texts note the existence of other Islamic rulers

including Sultan 'Melayu Daxi', ruler of Samudera in 785/1383, and Sultan

Zayn al Abidm, who had assumed the rulership of that polity by 822/1419,

Sultan Husayn, the ruler of Aru in 814/1411, and Muhammad Shah, the ruler of

Lambri in 815/1412. Thus, by the beginning of the ninth/ fifteenth century, the

northern and eastern coasts of Sumatra were the location of at least three

Muslim polities. Was the extension of the presence of Islam the result of the

raids by Sultan al Malik al Zahir and his successors, as suggested by Ibn Battuta?

If so, can we assume that these polities also followed the Shaffi school?

Samudera remained a cosmopolitan centre of Islam in the early ninth/fifteenth century. The grave of Naina Husam al Din, son of Naina Amm, dated Shawwal 823/Oct 1420, is headed by a gravestone which bears verses in

Persian, apparently from Tayyibat. These Sumatran polities were the intellec

tual and cultural centres of Islam in ninth/fifteenth century South East Asia.

thanks to their location, linking through maritime routes with the subcon tinent and the Middle East. Links with Gujarat appear to have been close and

regular, with cemeteries at Samudera having some representations of grave

stones from Cambay. 83

From the meagre evidence available, it also appears that Sufi influences came to South East Asia through Sumatra. A predecessor of the famous ninth

tenth/fifteenth sixteenth century Sumatran mystic Hamzah Fansuri bearing

the rdsba 'aljawi', which suggests a South East Asian and likely Sumatran origin appears in a ninth/fifteenth century collection of Sufi biographies.

- 81 Either the same sultan whom Ibn Battuta had met in the 1340s, or his son.
- 82 Kern, 'The propagation of Islam', p. 66.
- 83 Lambourn also describes booming local tombstone production during this period. See

Lambourn, 'The formation of the batu Aceh tradition'.

84 See R. Michael Feener and Michael F. Laffan, 'Sufi scents across the Indian Ocean:

Yemeni hagiography as a source for the earliest history of Southeast Asian Islam',

Archipel, 70 (2005), pp. 185 208.

390

## Early Muslim expansion in South East Asia

Abu 'Abd Allah Mas'ud b. Muhammad aljawi is recorded as having been involved with major mystics and jurists in Aden and elsewhere in the Yemen

during the seventh /thirteenth century, at a time when links with South East.

Asia were growing. The great shaykhs of Yemen, and their spiritual guide the famous Hanbali mystic [ Abd al Qadir aljilani (469 561/1077 1166) sub

sequently featured in the spiritual genealogy of many South East Asian Muslims, in Sumatra and beyond. The name of aljilani was, for example, later evoked in edicts issued by the Acehnese sultans.

By the end of the eighth/fourteenth century, it appears that the influx of Muslims from southern China and the links with the Indian subcontinent had

already begun to change the religious nature of Nusantara. It was at this juncture, following the coming to power in China of the usurping Ming emperor Yongle, that another southward push from China was to occur. The voyages of the eunuch Muslim admiral Zheng He, which extended over

the period 807/1405 to 838/1435, have attracted a wide range of explanations as

to their impetus and functions. The most appealing is that the usurping emperor Yongle needed to boost his legitimacy by extending Ming power over as great an area as possible. 85 The sending of these vast armadas under

the command of Zheng He and other eunuch officials was intended to bring

the known maritime world to submission. Thereby, a pax Ming could be established, trade nodes and routes to the West could be controlled, and both

political and economic power would reside in the hands of the Ming emperor.

It was thus that these missions proceeded along the trade routes which the

Arabs and Persians had been using for centuries, all the way to the east coast of

Africa.

The prominence of Muslim traders and Muslim polities along the existing trade routes may have influenced the decision to have Muslims lead these

massive missions, each of which comprised up to hundreds of ships and up to

30,000 troops. Like Zheng He, some of the other senior commanders were

Muslims, as were some of the soldiers and seamen who accompanied the missions. It was thus at this time, in an effort to soothe the remaining Muslims

of Fujian, to aid the conscription of interpreters and pilots for the eunuch led

armadas and to facilitate links with those who had fled southwards, that the

Yongle emperor issued a proclamation in 810/1407 ordering that no more violence was to be perpetrated against Muslims. 'No official, military or

85 The claim that Yongle and other Ming emperors were secret Muslims is unsubstantiated by any accepted source.

391

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

civilian personnel shall despise, insult or bully [Muslims] and whoever dis obeys this order by doing so shall bear the consequences.'

The Zheng He led navies established bases in the Straits of Malacca at Melaka itself and at Samudera in order to be able to control trade through

that narrow waterway. The newly emergent polity of Melaka provided the Ming forces with a useful base, while the Ming forces provided Parameswara,

the first ruler of Melaka, with the protection necessary to prosper without

concern about the continuing threats from the Siamese and the Javanese. The

Ming missions were certainly not intended by the Ming court to have a religious proselytising function, but given the religious affiliations of many

of the senior members of the missions, it would not have been surprising if

there had been efforts to encourage the adoption of a new religion among

some of the political leaders met on the voyages. These missions had the added unintentional effect of linking together the major Muslim communities

in southern China, and those throughout South East Asia and India, with the

societies of the great Islamic centres of West Asia. Many of the rulers, or at

least senior envoys, from places visited in South East Asia and beyond were

carried in the Ming ships to the Chinese capital together with envoys from

Islamic polities further west Cochin, Hormuz, Aden, Dhofar and even Mecca. Awareness of the extent and influence of Islam in these areas may

have contributed to the ongoing Islamisation in South East Asia.

Two urban areas Melaka and the northern coastal cities of Java provide helpful data about the adoption of Islam among South East Asians during the first half of the ninth/ fifteenth century. Ma Huan, a Muslim who accom

panied Zheng He on some voyages, recorded much about the ports and peoples visited during these voyages at the beginning of the ninth/fifteenth

century. He is known to have accompanied the voyages of 816 18/1413 15.

824 5/1421 2 and 834 6/1431 3. These descriptions he collected into a volume entitled Ying yai sheng Ian (or 'Supreme Survey of the Ocean Shores').

Of Java, which he visited on the 816 18/1413 15 mission, he noted:

The country contains three classes of persons. One class consists of the Muslim 87 people; they are all people from every foreign kingdom in the west who have flowed to this place as merchants; and in all matters of dressing and eating, they are all very clean. One class consists of T'ang

 $86\ \mathrm{Chen}\ \mathrm{Da}\ \mathrm{sheng}\ \mathrm{(chief}\ \mathrm{ed.)},\ \mathrm{(Quanzhou}\ \mathrm{Yisilanjiao}\ \mathrm{shike}\ \mathrm{(Islamic}\ \mathrm{stone}\ \mathrm{inscriptions}\ \mathrm{from}$ 

Quanzhou) (Quanzhou, 1984). See pp. n 13.

87 The term used was 'Hui hui', likely derived from Hui gu, the term by which the

Chinese knew the Uighurs.

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

people, and they are all people from Guangdong and from Zhangzhou and

Quanzhou and such places, who fled away and now live in this country; the food of these people, too, is choice and clean; and many of them follow

the Muslim religion, observing the precepts and fasting. One class consists

of the local people; they have very ugly and strange appearance, tousled hair

and go in bare feet. They are devoted to devil worship, this country being among the 'devil countries' spoken of in Buddhist books. The food which these people eat is very dirty and bad.

Of the new polity of Melaka, Ma Huan specifically states that: 'The king of the

country and the people of the country all follow the Muslim religion, fasting,

doing penance and chanting liturgies.'

Further to the north, of Aru near Deli in Sumatra, Ma's text notes: 'The king

of the country and the people of the country are all Muslim,' while of Lambri

on the northern coast of Sumatra, he recorded: 'This country lies beside the

sea and the population comprises only something over a thousand families. All

are Muslims and they are very honest and genuine ... The king is also a Muslim.' Even further north, in reference to the Bengal kingdom, the account

reads:

As to the dress worn by the king of the country and the chiefs, they all observe

the ordinances of the Muslim religion, and their headwear and clothes are

very neat and elegant ... there are also some people who speak the Farsi language . . . The customs of the people, and the rites relating to coming of

age, funerals, sacrifices and marriages all conform with the regulations of the

Muslim religion.

A number of points emerge from Ma Huan's account. The first is that by the early part of the ninth/fifteenth century, there were already quite a large

number of Muslims, both Chinese and those from further west, resident in

Tuban, Gresik, Surabaya and Majapahit on the northern coast of Java, but the

'local people' had not adopted the religion. The second, is that many of the

Chinese Muslims in Java had 'fled' from China, endorsing the thesis that they

had fled the repercussions of the 'Isfahan rebellion' in Quanzhou.

The process of the introduction of Islam to Melaka is worthy of a little further attention. 89 Who was this king whom Ma Huan wrote of as being a

Muslim? Ma Huan visited Melaka several times from 816/1413 to 836/1433, and

88 An endonym for Chinese people.

89 Christopher Wake has made a detailed study of the complexities of this process in his

'Melaka in the fifteenth century', in Kernial Singh Sandhu and Paul Wheadey (eds.),

Melaka: The transformation of a Malay capital c. 1400 1980, (Kuala Lumpur, 1983), vol. I, pp. 128 61.

393

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

over these twenty years there had been a number of rulers. The first ruler.

Parameswara, who had come to Melaka from Sumatra, appears to have

retained this Indie title until his death, which occurred sometime about 816/

1413. While he was probably not Muslim, he certainly employed Muslims in

his relations with the Ming. The envoy he sent to China in 811/1408, for example, was named Abd Allah Hasan. Parameswara was succeeded by his

son Megat Iskandar Shah in about 817/1414, who, like his father, also travelled

to the Ming court with the Zheng He missions. 90 His successor, known by

the title Sri Maharaja, likewise travelled to the Ming court, with Ma Huan in

836/1433. By 849/1445, the Melakan ruler being recorded in Chinese texts was

Sri Parameswara Dewa Shah, also a distinctly Indie title. Rivalry between Islamic and non Islamic contenders for the throne thus seems possible.

91 It

might be posited that Islamic rule in Melaka, perhaps up to the 830s /1430s, was

underwritten by the power of the Ming forces who maintained a base in the

city, and that when the Ming withdrew from South East Asia from the late

830S/1430S, the power of those who had been supported by the Ming declined.

This was certainly the case with the Ming installed Chinese rulers of Palembang over the same period. However, the re emergence of an Indie titled ruler in Melaka appears to have been a brief interregnum, as by the 850S/1450S we read of a new ruler bearing a distinctly Islamic name Sultan

Muzaffar Shah. His is the first reign we can firmly associate with any coinage,

with the coins he minted bearing the legend: 'Muzaffar Shah al Sultan / Nasir

al dunya wa'l Din.

The expansion of Islam within the peninsula is likely to have been stimu lated by the existence of the sultanate at Melaka, and the spread of Malay

people throughout this region. The monuments at Pengkalen Kempas not far

90 Ibid., p. 143. Tome Pires's account of the history of Melaka, which he collected during

the early sixteenth century, specifically states that Iskandar Shah, whom he noted as

Parameswara's son, was initially not a Muslim. The account relates that only at the age

of seventy two did he agree to marriage with some of the daughters of the ruler of Pasai

and at the same time to accept the Islamic faith. See Armando Cortesao, Tfte Suma

oriental of Tome Fires, Hakluyt Society (London, 1944), vol. II, pp. 241 2.

91 The questions of conversion and naming are hugely complex, and when one examines

the situations in these polities, we observe much hybridity in the situations of early

Islam in South and South East Asia. The question of how the Muslim trade commun

ities related to their host polities is an integral element of this. The term 'sultan' was

Sanskritised and adopted by Hindu rulers, Muslim governors administered for Hindu

kings, Hindus adopted Islamic garb and so forth. The complexities of the gradual

process of Islamisation thus require much more detailed and specific studies than is

allowed by this general overview. The various works of Wink, Eaton, Lambourn and

Feener are useful for elucidating the issues of Islamic hybridity in South Asia, the Indian

Ocean and South East Asia.

394

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

from the sultanate's core suggest that this region was in transition to Islam in

the 86os/ 1460s, 92, while the first sultan of Pahang, who died in 880/1475, was a

son of the sultan of Melaka, 93 suggesting a spread of the religion to the east of

the peninsula. The role of South East Asians in this continuing spread of

religion in the region should not be ignored.

How important then were the Zheng He voyages in stimulating conversion

or otherwise promoting the spread of Islam in South East Asia? As noted, the

purges in Fujian in the 760S/1360S had created an earlier influx of Muslims and

therefore potential agents of Islamic conversion into South East Asia. It appears

that the Ming voyages in the early ninth /fifteenth century made use of these

people and their connections with Fujian, with South East Asia and with areas to

the west. Anti Islamic violence had continued in Quanzhou and elsewhere in

Fujian until the beginning of the ninth /fifteenth century, as evidenced by the

810/1407 edict by the Yongle emperor forbidding any harassment of Muslims. 94

The emperor also needed the Quanzhou Islamic connections with South East

Asia to assist with these voyages. Navigators, translators and specialists in the

Islamic societies of the Indian Ocean could be found in Quanzhou, which thus

became an important port of call for the Chinese voyages to the Western Ocean.

The Ming naval forces definitely became engaged in the politics of Java in the early part of the ninth/fifteenth century. Chinese texts inform us that two

competing rulers of Java a Western king and an Eastern king were both in

contact with the Ming state in the early years of the century. The Ming naval

forces were apparently in close contact with the Eastern ruler before he was

killed by the Western ruler in 809/1406. A further 170 Ming troops involved

with the Eastern kingdom were also killed, and as compensation for these

people, the Ming court demanded 60,000 ounces of gold. As the Western king

was the ruler of Majapahit, we may well surmise that the Eastern king ruled a

newly emergent coastal polity, probably in Semarang Demak, 95 where a new

92 See Journal of the Federated Malay States Museums, 9, 3 (1921), which contains Ivor H. N.

Evans, 'A grave and megaliths in Negri Sembilan with an account of some excavations';

W. A. Wallace, 'Plans of the Negri Sembilan grave and megaliths with notes'; and

C. Boden Kloss, 'Notes on the Pengkalan Kempas tombstone'. See also R.J. Wilkinson,

'The Pengkalan Kempas "saint"', Journal of the Malayan Branch Royal Asiatic Society, 9, 1 (1931), PP- 134 5-

93 The gravestone, which is extant, is an example of the batu Aceh tradition.

94 See Chen, Quanzhou Yisilan jiao shike.

95 Demak first appeared in Ming texts (under the name Dan ba) in 779/1377, which gels

well with the thesis that it emerged as a base for the Muslim refugees who had fled from

southern China in the 760s/1360s. See Geoff Wade (trans.), Southeast Asia in the Ming Shi

hi: An open access resource, http://epress.nus.edu.sg/msl/entry/1883.

395

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

power base had arisen around the Muslim refugees who had fled from Fujian

to South East Asia in the 760s / 1360s and subsequently. This group would have

had connections with the forces commanded by Zheng He, and been able to

draw them into support for the new pesisir polity, resulting in the friction with

the Western king the ruler of Majapahit. 9

This scenario lends credence to the otherwise quite contentious Malay

language Peranakan chronicles of Semarang and Cirebon 'discovered' and

published by Mangaradja Parlindungan in the 1960s. Parlindungan's account,

supposedly derived from the Chinese community archives in these cities, depicts a wide ranging early ninth /fifteenth century network of Chinese Hanafi Muslims, spread throughout South East Asia, and tightly connected to

Ming agents such as Zheng He. These Chinese Hanafi communities were supposedly established in Palembang, Sambas, Melaka and Luzon, as well as

all along the north coast of Java at Ancol, Cirebon, Lasem, Tuban, Semarang,

Gresik and Joratan. The account further assigns Chinese origins to some of the

Islamic saints of Java, including Sunan Ngampel and Sunan Giri, as well as to

Njai Cede Pinatih, the Great Lady of Gresik 97

It must be affirmed that much of the Parlindungan account is in accord with

the evolution of the Chinese Muslim communities overseas as reflected in the

foregoing history. People did flee from Quanzhou to various ports in South East

Asia in the late eighth/fourteenth century, and the links which Parlindungan

suggests are congruent with other sources he was unlikely to have known. The

ninth/fifteenth century Xi yangfan guo zhi actually stated that all of the Chinese

in Java were Muslims, 98 and within Java there are traditions of Chinese involve

ment in the Islamisation of Java. 99 The Sino Javanese envoy Ma Yong long (Ma

Yong Hang) is well attested in other sources, but, most interestingly, another of

the leaders of the Javanese Hanafi community as reported in Parlindungan's

work Gan Eng Cu is found to have a correlate only in the Ming veritable records (Ming shi hi) which would not have been available to Parlindungan. Of

Gan Eng Cu, the Parlindungan account reads:

96 Relevant materials can be gleaned from the Ming Shi hi, Ming shi and Shu yu zhou zi hi.

The last of these works notes that the Chinese who sojourned in Java were generally Muslims.

97 See de Graaf and Pigeaud, Chinese Muslims in Java; D.A. Rinkes, Nine saints of Java (Kuala

Lumpur, 1996); and Tan Yeok Seong, 'Chinese element in the Islamisation of Southeast

Asia', Journal of the South Seas Society, 30, 1 and 2 (1975).

98 Lombard and Salmon, 'Islam and Chineseness', p. 183.

99 Slamet Muljana, Runtuhnja keradjaan Hindu Djawa dan timbulnja negara negara Islam di

Nusantara (Jakarta, 1968), as quoted in Lombard and Salmon, 'Islam and Chineseness', p. 184.

396

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

1423: Haji Bong Tak Keng transferred Haji Gan Eng Cu from Manila/ Philippines to Tuban/Java to control the flourishing Hanaflte Muslim com munities in Java, Kukang and Sambas. At that time, Tuban was Java's main

port, with the kingdom of Majapahit as hinterland. Haji Gan Eng Cu became

a kind of consul general of the Chinese government, the Ming Emperor, having control of all Muslim Chinese communities in the southern Nan Yang

countries including Java, Kukang and Sambas. 100

In the Ming veritable records, we read of Gong Yong cai (Jtfflyf in Hokkien 'Giong Eng cai'), a Chinese person acting as an envoy from Java, travelling to the Ming court in 832/1429, and receiving robes from the Chinese

emperor, exactly as was recorded of Gan Eng Cu in Parlindungan's work. 101

This reference opens up the possibility that these annals do provide us with

new factual material on Sino Javanese Islamic networks of the ninth /fifteenth century.

Regardless of the veracity of this account, we do observe in this period the

beginning of a new age of Islamisation along the Javanese northern coast. 102

We have evidence of Islam in Gresikby 822/1419, 103 and further indications of

the religion's gradual growth along this coast. These pesisir communities were

to become some of the most powerful agents of Islamic expansion in South

East Asia both during the ninth/fifteenth century and beyond. Demak is depicted in some accounts as having waged jihad against other pesisir polities

through the ninth/fifteenth century. 104

Further north, we also observe changes in the religious topography of the

western littoral of the South East Asian mainland during the early ninth/fifteenth

century, which were also to affect maritime South East Asia. Bengal had become

part of the Delhi sultanate following its capture by Turkish forces under Muhammad Bakhtiyar in the early seventh/thirteenth century, after which the

khutba, diverse elements of Islamic administration and mosques were introduced

to that place. Repeated attempts to throw off the controls of Delhi saw successive

military expeditions against the region by Delhi, bringing ever more Muslim

forces into the Bengali cultural region. In the middle of the eighth/fourteenth

100 De Graaf and Pigeaud, Chinese Muslims in Java, p. 15.

101 Ibid., pp. 15 16.

102 For further details of which, see Lombard and Salmon, 'Islam and Chineseness', pp. 115 17.

103 J. P. Moquette, 'De datum op den grafsteen van Malik Ibrahim te Grisse', Tijdschrift

voor Indische Taal , Land en Volkenkunde, 54 (1912), pp. 208 14. Again the gravestone

derived from Cambay.

104 De Graaf and Pigeaud, however, write of a tradition which holds that the first Muslim

ruler of Demak (who was of Chinese origin) did not emerge until the last quarter of the

ninth /fifteenth century. See H.J. de Graaf and Th. Pigeaud, Islamic states injava, yoo

1700 (The Hague, 1976), pp. 68.

397

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

century, Shams al Dm Ilyas Shah (r. 743 58/1342 57) established his own Bengal

sultanate free of Delhi. The mid eighth/fourteenth century historian Shams i

Siraj Afif referred to him as the 'sultan of the Bengalis' and the 'king of Bengal',

while his coins called him: 'The just sultan, Shams al dunya wa al din, Abu'l

Muzaffar Ilyas Shah, the sultan: The second Alexander, the right hand of the

caliphate, the defender of the Commander of the Faithful'. 105

This rising polity promoted Islam as a state sponsored religion in a pan Islamic spirit. Later rulers also drew on imperial Persian symbols of authority,

and tried to attract great poets from Shiraz to grace their courts. It was towards the end of the eighth /fourteenth century that a new force appeared

in Bengal politics Sufis of the Chishti and Firdausi orders. Championing a reformed and purified Islam, they insisted that the state's foreign and Islamic

identity not be diluted by admitting Bengalis into the ruling class. 10 Similar

influences were felt to the south, in the coastal polities of Sumatra and beyond.

The history of early Bengali Islam aids an understanding not only of that

South East Asian borderland itself, but also of the Islamic links and influences

exerted on its many trading and political partners to the south east. Arakan, for

example, was certainly influenced by the Bengal polity, politically and other

wise, during the ninth/fifteenth century, even if Bengal's support for the Arakanese king Naramithla in his battles with Ava remains unproven. Arakanese expansion was always northwards towards the ports of Bengal and it is likely through such temporary control over ports where Islam would

have been most influential that the religion would come to have increasing

influence within Arakan society. 107

In addition, early tenth/sixteenth century accounts show Bengali mer chants spread widely across the ports of the archipelago. In the peninsula

and Sumatra, while tenth /sixteenth century rulers were already called sultan,

as in Bengal, further east the title raja or patih was used. Tome Pires noted in

addition that 'the people of Pase are for the most part Bengalees and the natives descend from this stock'. 10 He expanded: 'Pase used to have heathen

kings, and it must be a hundred and sixty years now since the said kings were

worn out by the cunning of the merchant Moors there were in the kingdom of

105 Richard M. Eaton, Tfie rise of Islam and the Bengal frontier, 1204 1760 (Berkeley and Los Angeles, 1993), p. 41.

106 Ibid., p. 50.

107 For further details, see the various contributions to Jos Gommans and Jacques Leider

(eds.), The maritime frontier of Burma: Exploring political, cultural and commercial inter

action in the Indian Ocean world, 1200 1800 (Leiden, 2002).

108 Cortesao, The Suma oriental of Tome Pires, p. 142.

### Cambridge Histories Online © Cambridge University Press, 201 1

### Early Muslim expansion in South East Asia

Pase, and the said Moors held the sea coast and they made a Moorish king of the

Bengali caste, and from that time until now the kings of Pase have always been

Moors/ 109 If we are to assign credence to Pires's dates, we can say that his

account supports the supposition which is suggested by other evidence, that

Pasai was actually originally a separate polity from Samudera, and that, on the

latter s demise, Pasai incorporated Samudera' s history into its own hikayat. 110

The Samudera Bengal connection in the middle of the ninth/ fifteenth century

is also evidenced by Chinese texts which record that Ai yan, the nephew of Song

Yun, who had travelled to the Ming court in the 840s /1440s as an emissary of

Bengal, was at the time based in Samudera. 111 S. Q. Fatirni based his argument

that Islam came to the Straits of Malacca from Bengal mainly on the claims of

Pires. 112 Hooker has suggested that this is unlikely, given that the Hanafl school

was predominant in Bengal, whereas throughout the archipelago it is the ShafTi

school which dominates. 113 However, the envoy Song Yun mentioned above

was likely at least partly Chinese and it may be significant that both the Bengali

and early South East Asian Chinese versions of Islam were Hanafi, which were

later overwhelmed or surpassed by that of the Shafi'I school.

When Tome Pires wrote his unparalleled account of South East Asia in the

early tenth/sixteenth century, he reported a situation where Islam had become a very integral part of the region. 114 The ruler of Bengal was recorded

as 'a faithful Mohammedan'. Of Siam, Pires noted that while it did not have

many 'Moors', there were Arabs, Persians, Bengalis and Klings found in the

trade ports. Champa was said to have no Muslims, while Cochin China was

reportedly unfriendly to Muslims. Of Sumatra, he noted: 'The land of Palembang used to have heathen kings of its own and it was subject to the

cafre king of Java, and after the Moorish pates of Java had made themselves

masters of the sea coasts, they made war on Palembang for a long time and

took the land, and it had no more kings, only pates.' This suggests an extension

to Sumatra of the jihad which had been waged along the northern coast of Java

during the early ninth/fifteenth century. The rulers of Aru, Arcat, Siak, Kampar and Jambi, all on the island of Sumatra, are also noted as being

109 Ibid., p. 143.

no For which see Hill, 'Hikayat Raja raja Pasai'.

in Ming Yingzongshi lu,juan 54.7b of 843/1439 and juan 141.1a of 850/1446. Song Yun was

later killed in China by one of the Javanese envoys, but whether there was any political

intent in the killing remains unknown.

112 Fatimi, Islam comes to Malaysia, pp. 12 29.

113 M. B. Hooker, 'Introduction: The translation of Islam into South East Asia', in M. B.

Hooker (ed.), Islam in South East Asia (Leiden, 1983), pp. 122. See p. 6.

114 Cortesao, The Suma oriental of Tome Pires, passim.

399

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

Muslims, while Palembang itself was controlled by Pate Rodim, 'lord of Demak', and Bangka and associated islands were under the control of Pate

Unus, 'a Javanese Moor'. Muslims were, however, reportedly forbidden by

local lords from travelling to the gold mines of Minangkabau. Aceh had already begun its rise and its ruler was noted by Pires as being 'a Moor'.

On the island of Java itself, 'the kingdom of Sunda does not allow Moors in

it, except for a few, because it is feared that with their cunning they may

there what has been done in Java, because the Moors are cunning and they

make themselves masters of countries by cunning, because apparently they

have no power'. Muslim populations are recorded for the north coast port polities of Chi Manuk (Chemano), but Guste Pate, the viceroy and chief captain

of the king of Java, is said to have been 'always at war with the Moors on the

seacoast, especially with the lord of Demak'. The port of Tuban was con trolled by Daria Tima de Raja, 'a Moor who is the vassal of the said king'.

In describing the 'Mohammedan pates who are on the seacoast' of Java, Pires

claimed that: 'These lord pates are not Javanese of long standing in the country,

but they are descended from Chinese, from Parsees and Kling', a suggestion

well in accord with the sources cited above. The succession of Muslim ports

along the northern Javanese coast are then enumerated Chiremon, controlled

by Lebe Uca, vassal of Pate Rodim, lord of Demak Japura, the pate of which was

a cousin of Pate Rodim; Tegal, controlled by an uncle of Pate Unus; Samarang,

controlled by Pate Mamet, uncle of Pate Rodim; Demak itself, controlled by Pate

Rodim, chief pate of Java; Tidunan, under the charge of Pate Orob, uncle of Pate

Unus; Japara, controlled by Pate Unus; Rembang under Pate Morob, also an uncle

of Pate Unus; Tuban, the nearest port to the inland capital of Daha/Daya, which

was under Pate Vira, who was subject to the anti Islamic Guste Pate. Next along

the coast was another Islamic port polity, Sidayu, with a lord named PateAmiza,

cousin of Pate Unus, but the population of which was mainly heathen. To its east

lay Grisee/Grisik, 'the best trading port in Java', divided between two rival

Muslim lords, one intimately linked with Melaka, and trading into the Moluccas

and Banda, and the other closely tied to the Javanese aristocracy. Thence one

arrived at Surabaya, controlled by Pate Bubat, a vassal of Guste Pate, but 'closely

related to the Moorish pates'. The next port polity was Gamda, under the control of Pate Sepetat, a heathen, son of Guste Pate, and son in law of the

ruler of Madura. Pires noted that Pate Sepetat had, with the help of his father

in law, 'prevented the Moors from passing beyond Surabaya for a long time';

then followed the smaller polities of Cantjam, Panarukan and Pajarakan, and

finally Blambangan, whose lord was known as Pate Pimtor, and was a nephew

and ally of Guste Pate. A phenomenon recorded in Java by Pires was that of

400

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia

'tapas', which he says means 'observants', apparently some kind of religious

ascetics, numbering, according to the Portuguese scribe, 50,000 in the island.

These people, he claimed, were 'also worshipped by the Moors'. This suggests

another element of the syncretism which has long marked Javanese Islam the

agamajawa described by Brakel. 115

On the islands further east, Pires also noted the dispersed presence of Muslims. Of Banda, he recorded, 'Those along the seacoast are Moorish mer

chants.' That they were fairly recent arrivals was apparent: 'It is thirty years

since there began to be Moors in the Banda islands.' In respect of the Moluccas,

Pires declared: 'According to what they say, Mohammedanism in the Molucca

islands began fifty years ago. The kings of the islands are Mohammedans, but not

very deeply involved in the sect. Many are Mohammedans without being circumcised and there are not many Mohammedans. The heathens are three

parts and more out of four.' The king of Ternate was known as sultan, while

other local rulers were termed simply raja. The island of Gillolo (Jeilolo) was also

noted as having a 'Mohammedan ruler'.

Regarding Melaka, the Suma oriental provides a great amount of information.

Pires recounts, obviously on the basis of local accounts, how Xaquem Darxa

(Iskandar Shah), the son of Paramjcura (Parameswara), the founder of Melaka,

provided great hospitality to Islamic merchants as he endeavoured to build his

polity, and eventually also converted to Islam upon marriage to the daughter of

the sultan of Pasai. This account needs to be read in conjunction with the analysis of Islam in Melaka provided above. The later sultan Mansur Shah is

lauded as a great ruler and as the builder of a 'beautiful mosque which used to

be where now is the famous fortress of Melaka, and which was the finest known

in these parts'. Mansur Shah is also noted as having employed non Muslim

officials, reminding one of the Bengali sultans who were very cosmopolitan in

their outlook and actions. The recorded links between Melaka and the diverse

polities up and down the Straits of Malacca in Suma oriental suggest that Melaka

was indeed the major centre of commerce and likely intellectual and religious

intercourse in the region during the latter part of the ninth /fifteenth century.

Tome Pires's overview of the archipelago at the beginning of the tenth/sixteenth century is a fitting way by which to conclude this chapter. We observe, at this time, Islamic polities already established up and down both

sides of the Straits of Malacca and all along the northern coast of Java the

latter albeit engaged in rivalry with non Muslim polities, both coastal and

115 L. F. Brakel, 'Islam and local traditions: Syncretic ideas and practices', Indonesia and the Malay World, 32, 92 (2004), p. 12.

401

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

inland. There were also the beginnings of Islamic states in the eastern islands

of the archipelago. Thus was the stage set for a renewed expansion of Islam in

tenth/ sixteenth century South East Asia, a period which was also to see the

arrival of a new religious competitor the Christianity of the Portuguese and

the Spanish.

The history of Islam in South East Asia obviously cannot be understood without examining the component phenomena on a global scale. When we

lookback at the three periods discussed above, we see in the period up until the

fifth /eleventh century the emergence of Islamic trading communities along the

southern coast of China, in Champa, undoubtedly in Sumatra and possibly in

Brunei or what is today the southern Philippines. These were tied to the Indian

subcontinent and thence on to the Middle East. It is quite possible that Shi'a

influence was quite strong during this period. With the breaking of the trade

routes through the Cola attacks in the early fifth /eleventh century, a certain

independence and innovation occurred within the Muslim communities in South East Asia. At that time, the Muslim community in Champa was obviously

large enough for the Chinese envoy to see it as being representative of Champa

perse. Muslim communities appeared in Hainan and Brunei, and the first Islamic

polities began to be observed in seventh /thirteenth century northern Sumatra.

It must be affirmed that the eighth/fourteenth and ninth /fifteenth centuries

constituted an important period in the spread of Islam through South East Asia,

particularly in the Islamisation of pesisir Java. While the Sumatran states were

developing their links with polities and rulers in the Middle East and the subcontinent, Muslim refugees from disturbances in Quanzhou and other major Islamic centres of southern China began to flow into South East Asia in

the 760S/1360S and 770S/1370S, becoming key catalysts in the emergence and

growth of coastal Javanese Islamic polities.

During these periods, Muslim traders appear to have been the most usual carriers of Islam. With the importance of the Sufis in the development of Islam

in Bengal, and the existence of al Jawi (probably Sumatran) Sufis from possibly

the seventh/thirteenth and definitely the eighth/fourteenth century, we can

affirm that during the eighth/fourteenth and ninth/ fifteenth centuries, Sufis"

were an important channel for transmission of the faith in South East Asia, a

phenomenon discussed by both Johns" 7 and Fatimi."

116 Here Sufi is not intended as an absolute category. A Sufi could have been a soldier, an administrator, a cleric or a trader.

117 A. H.Johns, 'Sufism as a category in Indonesian literature and history ', Journal of South east Asian History, 2, 2 (July 1961), pp. 10 23.

118 Fatimi, Islam comes to Malaysia, pp. 23 4, passim.

402

Cambridge Histories Online © Cambridge University Press, 201 1

Early Muslim expansion in South East Asia


Throughout these processes of Islamic expansion a multitude of changes took place in the physical as well as mental topographies of the region. New

ideas of law and jurisprudence emerged, along with new moralities. New forms of dress, new types of tombs and new forms of architecture also appeared. The Malay languages of the archipelago began to absorb the terminology of Islamic theology and law, as well as the new Arabic based script, together with the many new external links this world religion provided

them with. Iconography diminished greatly in the archipelago, and the Hindu Buddhist style of architecture went into decline. The processes by which these aspects were continued or arrested will be discussed in the succeeding chapters.

Appendix i Envoys and others with Li 'surname' from maritime polities to China

tenth to early twelfth centuries



'All Leyli 'All Ahmad San fo qi

Song Sfii juan 489

963

Li Ban (\$ % (alt. Lie Mie \$ 1%

Champa

SHY FY 4: Champa

968/9

Li Ban (\$ % Li Bei qiang

& WlM)


Champa

SHY FY 4:

Champa Song Sfii gives

second

name as Li
Bei cuo & «)
971
Li He mo
'Ah Hamid
San fo qi
SHY FY 7
(\$ fa*)
or
the Arab lands
Yu Hai juan 154
971/2
Li Nou (\$ ?)
'All Nur
Champa



# remarks

977

Envoy Li Pai (\$ Ji\$); deputy envoy Li Ma na (\$ M IP), and administrator Li Tu (\$ Jf)

'All Bahij (?)

Champa

SHY FY 4: Champa

979/80

Li Mu zha duo (\$

'Ah Muzaffar

Champa

SHY FY 4: Champa

980


Li Fu hui

```
San fo qi
Song Shi
(^ittS)
(A merchant)
juan 489
986
Li Chao xian ($ §H
Ml)
Champa
SHY FY 4:
Champa
Possibly a Viet
or Chinese
name
990
Li Zhen (^ If)
'Ah Zayn (?)
```

# Champa SHY FY 4: Champa 993 Li a wu (^55^)) 'Ah Ahmad The Arab lands SHY FY 7 995 Li Bo zhu (\$\$#&) Li He san (^HSffifc) Li Mo wu (^0^1) 'All Bashir (?) 'Ah Hasan 'Ah Mahmud

Champa

SHY FY 4:



'Ah ... 'Ah ... San fo qi SHY FY 4: San fo qi 1003 Li Yi han 'Ah...

Butuan SHY FY 4: Butuan 1008 Li Mei di (^ Sift) 'Ali Badi San fo qi SHY FY 7: Possibly same person as the Ya li

Baidi

mentioned

Cambridge Histories Online © Cambridge University Press, 201 1
Early Muslim expansion in South East Asia
Appendix i (cont.)
Proposed
Polity
Source and
Date (CE)
Name
reconstruction
affiliation
remarks

under date

ion in

Appendix 3

ion

Li Yu xie

'All Yusuf

Butuan

SHY FY 4: Butuan


1029

Li Pu sa



'All ...

Champa



# Champa SHY FY 4: Champa 961 Pu Mie mm) Abu Mat San fo qi Song Shi juan 489 972 Pu He san mmwv Abu Hasan

Source and remarks

960/1

Pu He san


Abu Hasan

Bu Luo hai
(^ri?4)
Abu
The Arab lands
SHY FY 7
976
PuXimi
(fI#S?)
Abu Hamid
The Arab lands
SHY FY 7
976
Pu Tuo han
OOTfiil)

Champa

975

SHY FY 4: Champa



affiliation
Source and remarks
977
Pu Ya li (*55M)
Abu 'All
Bo ni (Brunei)
SHY FY 7
977
Pu Lu xie
AbuYusuf(?)
China/
Song Shi
(tiJtlt)

Bo ni

juan 4 977 Pu Si na (»©IP) Pu Luo (ft\*) Abu Cina Abu Nur The Arab lands SHY FY 7 983 Pu Ya tuo luo (\*1#KS) Abu Abd Allah San fo qi SHY FY 7 986 Pu Luo e (\$f Sit)

Abu Nur (?)
Champa
SHY FY 4: Champa (Led 100 members of clan to Hainan)
988
Pu Ya tuo li
Abu 'Abd Allah
San fo qi
SHY FY 7
990
Pu He san
Abu Hasan
Champa
SHY FY 4: Champa
992
Pu Ya li
(*3SM)

Abu 'All
Java
SHY FY 4: She po
993
PuXimi
Abu Hamid
The Arab
Song Shi:
(M%&)
lands
Da shi (Master of ship) jflji
995
Pu Ya tuo li

The Arab
SHY FY 7:
mnmm
Allah
lands
(Master of ship) Jflji See Kuwabara I p. 78
998
Pu Ya ti li
Abu Abd
The Arab
SHY FY 4
(fifttJI*)
Allah
lands

Pu Jia xin (ffJB'fr)
Abu Qasim
The Arab lands
SHY FY 7
1008
Pu Ma wu
Abu Mahmud
The Arab
Xu Zi zhi tongjian
Tuo po li
Tabriz
lands
chang bian,

oI)#M»fi)
juan 69.9a
(Master of ship) JtflTtt
1008
Pu Po Ian
Abu Burhan
San fo qi

SHY FY 7 San fo qi

IOII

Pu Ma wu


Abu Mahmud

The Arab

SHY FY 7

Tuo po li

Tabriz



Name
reconstruction
affiliation
Source and remarks
1015
Pu Jia xin
Abu Qasim or
Zhu Kan
SHY FY 7
(fifJP'h)
Abu Hasan
(Chola)
1017
Pu Mou xi
(fffftffi)

SHY FY 7		
1019		
Pu Ma wu		
Abu Mahmud		
The Arab lands		
SHY FY 4		
Tuo po li		
Abu Tabriz		
And FY 7		
OiJ#^jR»)		

Abu Musi

San fo qi

Pu Jia xin

Abu Hasan

(5111\*)

1028

Pu Ya tuo luo

xie(5ittK

Mb

Abu Abd Allah

San fo qi

SHY FY 7

1033

Pu Ya tuo li

Abu c Abd
Zhu Kan
SHY FY 7
(viffPfiH)
Allah
(Chola)
1053
Pu Si ma ying
Abu Isma'il (?)
Champa
SHY FY 4: Champa
1055
Pu Sha yi
{WiPZ*)
Abu Sayyid
The Arab

lands
SHY FY 7
1060
Pu Sha yi
{W&z,)
Abu Sayyid
The Arab lands
SHY FY 7
1068
Pu Ma wu
(5lJ#^J)
Abu Mahmud
Champa
SHY FY 4: Champa
1073
Pu Ma wu
(5lfi*^J)

# Abu Mahmud

The Arab lands

SHY FY 7

1086

Pu Ma wu {WM9})

Abu Mahmud

Champa

SHY FY 4: Champa

1087

Pu Xia xin

(5ffM\*)

Abu Husayn

Champa

Luan chengji (§ft

\$M) 28.6a

"37

```
Pu Ya li
G&35M)
Abu l Ah
Unknown
SHY
See Kuwabara I
p. 56
FY = Fan yi (a section of SHY)
Kuwabara I = see n. 53
Luan chengji = Su Shi, Luan Chengji (Shanghai, 1987)
SHY = Song Hui yao
Xu Zi zhi tongjian chang bian = Bi Yuan, Xu zizhi tongjian changhian
(Beijing, 1957)
407
```

Cambridge Histories Online © Cambridge University Press, 201 1


The New Cambridge History of Islam

Appendix 3 Other envoys with Islamic names from maritime polities to China, tenth to eleventh centuries

Affiliation or
Source and
Date (CE)
Name
reconstruction
sent by
remarks
977
Ge xin
Qasim
Bo ni
(Brunei)
SHY FY 7

977


Proposed



Mo he mo

 $(M <> J^*)$ 

Muhammad



<Abd Allah

Champa

SHY FY 4 (SSfiJft) (possibly Zamboanga) Possibly same person as the Li Mei di mentioned in Appendix 1 under date 1008 1017 Ma si li (JtflfO) Masn

Ya li Bai di

<Ali Badi

San ma Ian guo

Arab merchant
SHY
Shi bo si section
1088
Hu xian
Husayn
San fo qi
Wen xian tong kaojuan 332
FY= t
Fanyi
(a section of the SHI)
SHY =
- Song
Hui yao

Cambridge Histories Online © Cambridge University Press, 201 1

TT

Follow the white camel: Islam in China to 1800

**ZVI BEN-DOR BENITE** 

### Introduction

The inhabitants of Jiezi, a Muslim village of the Salar ethnic group in Qinghai,

China, tell an interesting story about the circumstances of their migration

from Central Asia many centuries ago. As the story goes, they had left Samarqand centuries earlier, fleeing injustice and tyranny. They had moved

generally eastward to 'China, the Land of Peace and Harmony' but arrived

in the specific location of Jiezi 'following the lead of a white camel with a Qur ] an strapped to its head for guidance'. 1 The white camel in this story is

noteworthy. Recall that the caliph 'Umar entered Jerusalem on a white camel,

thereby sending a message of peace and harmony; more importantly, the Prophet Muhammad determined the spot of his mosque in Medina by letting

his white camel loose and following it until it stopped to rest. The implications

of the story are quite clear: the journey of Muslims from Samarqand to China outside the 'House of Islam' was justified and even divinely approved. It was to be seen as akin to other significant events in Islamic history: the making of Jerusalem part of the Islamic world, and the very creation of the first Islamic polity. One could take it even a step further: the

journey to Jiezi was nothing less than a re enactment of the hijra. Just as Muhammad had fled tyranny and injustice, so too the Muslims from Samarqand. Just as he used a white camel to transform Yathrib into Medina,

so too the Muslims of Jiezi. This story is but one piece of a broader Chinese

Muslim strategy of making China home to Muslims and transforming it

1 Mi Yizhi, Sala zu ski (Chengdu, 2004), pp. 6 8; Ma Jianzhong, 'Stone camels and clear

springs: The Salar's Samarkand origins', Asian Folklore Studies, 55 (1996), pp. 287 98. For

issues of space I refer the reader to an excellent bibliography on Islam in China: Donald

Daniel Leslie, Yang Daye and Ahmad Youssef, Islam in traditional China: A bibliographical quide (Nettetal, 2006).

409

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

into an 'Islamic space' in spite of the fact that it actually lies outside the ddr

al islam. 2

Grasping this duality between China being 'distant' and China being an Islamic home is crucial to the understanding of the history of Islam and Muslims in China. It reflects the sense of 'diasporic homeland' 3 that resulted

from an acute sense of distance from the Islamic world among Chinese Muslims and the need for conscious negotiation of the place of Islam and Muslims within Chinese society and culture. This process of negotiation eventually gave rise to an Islam that is uniquely Chinese in its self perception,

and to a Muslim community that, while emphasising the 'foreign' origins of its

religious tradition, considers itself specifically Chinese.

The historical, as opposed to mythical, circumstances of the Muslims' migration to and arrival in China contribute significantly to their subsequent

history. Furthermore, the distance and the sporadic and disorganised nature of

Muslim migration to China created different, and sometimes separate, Muslim communities within Chinese territory. Until, perhaps, the twentieth

century and the creation of the Republic and the People's Republic, there is no

truly unified history of 'Islam in China' to speak of 4 Only the modern Chinese

state was able to classify the Muslims of China as members of several distinct

collectivities known to be Muslim. Even though Chinese Muslims within China's old territories ('China Proper') tend to believe and understand their

history to be one unified historical trajectory of a 'Muslim nationality', this

was certainly not the case. However, the main Muslim community in China

was already engaged during the seventeenth and eighteenth centuries in creating what would later become a more unified, transregional Chinese Muslim identity. In many respects, though, it is more accurate to speak of

histories of Islam and of Muslims in China, rather than of a singular historical

trajectory, 'Islam in China'.

Another important point to bear in mind is the fact that the term 'China' was itself profoundly transformed several times over the course of the period

discussed in this essay. Politically speaking, 'China' moved from a huge

Zvi Ben Dor Benite, '"Even unto China": Displacement and Chinese Muslim myths of

origin', Bulletin of the Royal Institute for Inter Faith Studies, Winter, (2003), pp. 93 114.

This term is my own. Other scholars in the field might have slightly different ways to

describe this condition. Jonathan Lipman implies another meaning when he speaks of

'Familiar Strangers' . Jonathan Lipman, Familiar strangers: A history of Muslims in north west

China (Seattle, 1997). Also see Zvi Ben Dor Benite, The Dao of Muhammad: A cultural

history of Muslims in late imperial China (Cambridge, 2005), pp. 12 20.

Dru C. Gladney, Muslim Chinese: Ethnic nationalism in the People's Republic (Cambridge,

MA, 1991), pp. 36 60.

410

Cambridge Histories Online © Cambridge University Press, 201 1

## Islam in China

empire during Tang times (618 907); to a small and embattled empire during

Song times (960 1279); to be part of a huge Mongol khanate known as the

Yuan (1279 1368); to a rather strong empire (though much smaller than the

khanate) during Ming times (1368 1644); to a huge empire twice the size of its

predecessor during Qing times (1644 1911). Geographically speaking, these

transformations meant that at certain times different Muslims were or were

not under Chinese rule. For instance, Central Asian Muslim communities that

were under the yoke of the khan in Khanbaliq (Beijing) during Yuan times were not subjects of China during the Ming. Similarly, the Qing conquests in

Central Asia during the eighteenth century brought many more communities

that were Muslim into the fold. 5 From a cultural point of view, China itself was

also transformed by these shifts. In Tang times, it tended to be quite open

about its affinities with Central Asia. During Song times, it was 'Chinese', but

during Yuan times, it became a multilayered society with Mongols at the top.

During Ming times it was a Chinese polity striving for a greater degree of

homogenisation and seeking to revive an imagined pure 'Han' Chinese past.

Finally, during Qing times, China became part of a consciously multiethnic

empire again ruled by a non Chinese people.

As we shall see, these transformations had a tremendous impact on the history of Islam in China. These transformations are also important because

they allow us to understand the various possible periodisations of its history.

Given the multiple trajectories of Chinese Islamic history over the years, it is

impossible to offer a simple unified periodisation. Joseph Fletcher offered an

approach that divided Chinese Islamic history into 'tides', each connected to

the 'influence and impact of individuals who entered China during critical periods of exchange with the outside world'. However, the dramatic changes

and wealth of research in the field since Fletcher's untimely death mandate

that internal developments and transformations within Chinese Islamic soci

ety, as well as the 'general' trajectory of Chinese history, be taken into account

as well. This essay therefore offers an 'unfastened' periodisation, divided into

'phases' (rather than strict stages) that highlight the main features of each

period in the history of Chinese Islam. The phases are organised in a loose

chronological order, and for simplicity's sake each carries the name of

5 For a bibliographical manual of Chinese history see Endymion Wilkinson, Chinese history:

A manual (Cambridge, 2000).

6 Gladney, Muslim Chinese, 36; Joseph Fletcher, Les 'voies' (turuq) soufies en Chine (Paris,

1986). See Gladney's elaboration on each tide in Gladney, Muslim Chinese, pp. 6 59;

Joseph Fletcher, Studies on Chinese and Islamic Inner Asia, ed. Beatrice Forbes Manz

(London, 1995).

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

significant locations that mark turning points in Chinese Islamic history. I should caution readers that the division into phases does not mean that all

Muslims in China had similar historical experiences at the same time.

condition does not exist in China even today, when there is an unprecedented

degree of homogeneity in Chinese Islam. In fact, during the pre modern era in

many areas of China one phase continued well after another phase had already

started elsewhere. Therefore, the locales I choose as titles for each phase are

best seen as marking the highlight of a specific era.

## Phase one: Chang' an and Quanzhou

The first significant marker of Muslim presence in China is the Great mosque in Xian (then Chang' an). The original structure was built on what

was apparently a Buddhist site, according to tradition in 742 CE (but certainly at least somewhat later). 7 This period precedes the designated scope of this chapter, but a brief summary is crucial for the understanding

of subsequent periods. The location of the first mosque in Xian should not be surprising at all. Chang' an was then the capital of the Tang dynasty

(618 907), and a major world and Asian commercial centre. The Tang empire at that time stretched its long 'arm' to Central Asia reaching as far

west as the north eastern provinces of today's Iran. The Tang emperors, themselves related to the Turkic tribes which they often fought, maintained

complex military and commercial relationships with various Central Asian

nomadic groups as well as with Sasanid Iran. The Tang also had similar

diplomatic ties with the Islamic empire that replaced the Persians. The Muslim presence in the region was felt in China in different ways during the

early eighth century. Already, during the 710s, the Arab general Qutayba arrived at the Tang borders with his armies. The event was recorded in both

Arab and Chinese histories of the time, but no major military clash took place. 9 In 751, a large Muslim force clashed with and defeated a much smaller

Tang garrison at the battle of Talas, thereby triggering the long retreat of the

Tang from Central Asia. 10

7 Wu Jianwei (ed.), Zhongguo Qingzhensi Zonglan (Yinchuan, 1995), pp. 304 5.

 $8\ Denis\ C.$  Twitchett (ed.), The Cambridge history of China, vol. Ill: Sui and Tang China, sSg 906

(Cambridge, 1979), pp. 279 81. See also Tazaka Kodo, Chugbku ni okeru Kaikyd no denrai to

sono MBtsu (Tokyo, 1964), pp. 261 90.

9 Donald Leslie, Tfie integration of religious minorities in China: The case of Chinese Muslims (Canberra, 1998), p. 5.

10 Twitchett (ed.), The Cambridge history of China, pp. 34 8.

412

Cambridge Histories Online © Cambridge University Press, 201 1

### Islam in China

Muslim armies did not arrive in China following the battle, but Muslim merchants did, as part of the increasing presence of Muslims in various locations

along the 'Silk Road'. Soon after, Arab merchants arrived in the Central Asian

trade posts on the Silk Road. Some of them came to the Tang capital of Chang' an, where they joined countless other people of many ethnicities,

religions and locations from the old world. Chang' an, the capital of the entire

East Asian region, with over a million people, was the easternmost and most

significant location on the Silk Road. The establishment of the mosque in the

city suggests the creation of a more stable community. 11 At about the same time,

or shortly thereafter, Muslim merchants, mainly from the Gulf, began arriving

in China via Indian Ocean trade routes. These early connections with the Islamic world gave rise to several significant Muslim communities in China:

the aforementioned Chang'an in the north west, and the port cities of Canton

(Guangzhou) in the south, and Quanzhou on the south eastern coast of China.

New communities subsequently emerged in other central cities along major

communication lines. Hangzhou and Kaifeng, major commercial hubs on the

Chinese Grand Canal, and later Song capitals; and Yangzhou on the northern

banks of the Yangzi river, are good examples. All of these housed large sojourner populations of merchants, soldiers and mercenaries, refugees and

adventurers of all sorts. The rapid rise of these Islamic communities, it is very

important to note, was also a quintessential sign of the high degree of cosmo

politanism and openness that characterised particularly the early Tang empire. 12

These features allowed Muslim communities to prosper. A rather rare case is

cited of one Li Yansheng, identified in Tang sources as 'an Arab' (Dashiguo ren),

who passed the civil service exams in 847, and was recommended to a post at the

palace. The incident sparked a debate among Chinese scholars about the meaning of "being Chinese' in the wake of this appointment. Li's achievement

in passing the exams and gaining the court attention shows the degree of integration into Chinese society and culture that could be attained by individual

Muslims if so desired. Chinese Islamic memory many centuries later would

'translate' this cosmopolitanism of the Tang into a perception of friendship and

hospitality between the Tang and Islamic empires.

11 Lipman, Familiar strangers, pp. 24 31. For a more detailed summary based on Chinese

sources see Li Xinghua, Huibin Qin, Jinyuan Feng and Qiuzhen Sha, Zhongguo YisiUnjiao

ski (Beijing, 1998), pp. 3 57; Qiu Shusen, Zhongguo huizu ski (Yinchuan, 1996), pp. 2 30.

12 Charles Holcombe, 'Immigrants and strangers: From cosmopolitanism to Confucian

universalism in Tang China', Tang Studies, 20 1 (June 2002), pp. 71 112; see also Marc

Abramson's careful assessment of that question: Marc Samuel Abramson, Ethnic identity

in Tang China (Philadelphia, 2008).

413

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

The Muslims in China maintained contacts with the wider Islamic world.

this key regard, Muslims were different from the other sojourning popula tions. Nestorian Christians, for instance, had arrived in Chang' an as part of a

general migration eastward following persecution in the Middle East. The

Muslims, in contrast, had an increasingly strong and dominant Islamic world

'behind them', as external referent. This meant that so long as trade routes

with China were dominated by Muslims, more and more Muslims came to dwell in the country. It also meant that, as the Islamisation of Central Asian

peoples prevailed, more and more Muslims arrived in China. Thus, while the

original community of Indian Buddhists that had resided in Quanzhou since

well before the Muslims became greatly diminished, Muslims dominated this

centuries old city, and even gave it an Arab name, Zaitun. 13 Similarly, the

Jewish community of Kaifeng always remained small, whereas the Muslim

community in the city kept increasing, and thus in the seventeenth century

was to become a major centre of Islamic learning. 14 The increasing size of China's Islamic communities also meant that Muslim wealth could sustain communal life and its institutions. This phase saw the construction

of several important mosques in various communities. China's 'Four Ancient

Mosques' the Huaisheng mosque in Canton, the Qingjing mosque in Quanzhou (Masjid al Ashab), the Xianhe mosque in Yangzhou and the Fenghuang mosque in Hangzhou were all constructed or purchased during

the period of the Tang and Song dynasties. The Quanzhou Muslims (who had

been particularly dominant) left an impressive cemetery with beautiful inscriptions in Arabic on tombstones and on mosque tablets. Smaller monu

ments and tombs of this kind can be found elsewhere in China. 15

Quanzhou /Zaitun was certainly the most significant community, and was so for centuries. It bore the key hallmarks of Islamic presence in China between the eighth and thirteenth centuries: a maritime community of merchants, with close and frequent commercial ties to the Islamic world to

ensure a steady migration of Muslims. An examination of the aforementioned

inscriptions shows that most of the Muslims in the city came from the Persian

Gulf, or from locations with access to the Indian Ocean, such as Yemen.

- 13 Tansen Sen, Buddhism, diplomacy, and trade: The realignment of Sino Indian relations, 600 1400 (Honolulu, 2003).
- 14 Donald Leslie, The survival of the Chinese Jews: The Jewish community of Kaifeng (Leiden, 1972).
- 15 Fujian sheng Quanzhou haiwai jiatongshi bowuguan, Quanzhou Yisilan jiao yan jiu lun

wen xuan (Fuzhou, 1983); Chen Dasheng and Ludvik Kalus, Corpus d'inscriptions arabes et

persanes en Chine, vol. I: Province de Fujian (Quanzhou, Fu zhou, Xia men) (Paris, 1991).

414

Cambridge Histories Online © Cambridge University Press, 201 1

### Islam in China

However, a few also came from Central Asian locations, suggesting that the

city also attracted Muslims who were part of a different trade system. By the

end of the Song period, during the thirteenth century, Muslim dominance in

the city was such that Muslims were appointed by the state as officials in the

Trade and Customs office. Most well known is the case of Pu Shougeng, whose family moved to the city from Canton, and who served as super intendent (tiju) of the office from 1250 to 1280. J Evidently, this appointment

signified not only the importance of the Muslims in the city, but also their crucial role in China's dealings with other regions of the southern and western

oceans. The Song dynasty was less cosmopolitan and confident than its Tang

predecessor, but by its time Muslim communities were so significant that they

were at the very least tolerated and accepted.

The Islamic communities in China attracted attention in the Islamic world,

mainly because of the supposed 'enchantedness' of China and its distance from

the core Islamic regions. The famous Akhbdr al Sin wa I Hind (published c. 915)

tells of large Arab communities in southern China; even though the numbers

are undoubtedly exaggerated, they clearly reflect sizeable communities. 17 The

distance of China had always to be accounted for in tales of adventures of the

Arabs going there. For instance, al Sirafi's account tells of one Ibn Wahb al

Quraishi who was originally from Basra but left this city for Siraf after it was

sacked by rebels (probably in 898 by Qaramita), and 'found himself on a boat

going to al Sin. The description of the journey to China reflects the reality: a

constant movement back and forth to China from various ports in the Islamic

world, taking along merchants and merchandise and the occasional adven

turer like Ibn Wahb.

Even though Arab accounts such as those of al Sirafi or the later Ibn Battuta,

who toured China in the fourteenth century (whose depictions of Muslim life

focus mostly on merchants in the port cities), describe a degree of communi

cation and interaction with the local Chinese population, it is quite clear that

most Muslims lived in secluded neighbourhoods in the large cities where they

could maintain a more 'halal' culture free from idols and pork, but quite autonomous in every other regard, as well. 1 Ibn Battuta, serious cleric that he

16 Jitsuzo Kuwabara, 'On P'u Shou keng', Memoirs of the Research Department of the Toyo

Bunko, 2 (1928), pp. 1 79, and 7 (1935), pp. 1 104. For this appointment in the context of

China's maritime history see Gang Deng, Maritime sector, institutions, and sea power of

premodern China (Westport, CT, 1999), pp. 1202.

17 Sulayman al Tajir and Abu Zayd Hasan ibn Yazid Sirafi, Akhbdr al Sin wa I Hind (Cairo,

2000), pp. 54 61. See more on this in Ben Dor Benite, 'Even unto China', pp. 99 101.

18 Lipman, Familiar strangers, pp. 28 33.

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

was, reflects this sequestration nicely: 'China, for all its magnificence, did not

please me. I was deeply depressed by the prevalence of infidelity and, when I left

my lodging, I saw many offensive things that distressed me so much that I stayed at home and went out only when necessary.' 19 Far away from home.

the Muslims Ibn Battuta encountered were very hospitable: 'they are delighted

when a Muslim arrives among them and they say, "He has come from the land

of Islam" and give then zakat  $\dots$  so that he becomes as rich as one of them.' 20 In

'Khansa' (Hangzhou), Ibn Battuta stayed with ''Uthman ibn 'Affan the Egyptian, . . . one of the important merchants who became fond of this city

and settled [here]'. In Zaitun, he stayed with a 'a merchant from Isfahan'. In

Guangzhou (Sin kalan), he lodged with 'Awhad al Din from Sinjar, a distinguished, important and very wealthy man'. These wealthy merchants could

easily support the religious life of their communities and hire teachers, imams

and clerics for their mosques and madrasas, so that Ibn Battuta kept meeting

people like 'a god! from Ardabil', or 'a shaykh from Kazarun'. His claim that 'in

every one of their [the Muslims'] quarters there is a Shaykh al Islam' is probably

an exaggeration, but certainly it reflects an image of rich and self sustaining

religious life. 21 The wealth of Islamic literature religious books of all sorts and

Qur'ans from that period that was preserved in China suggests that the Muslim communities of the time were major consumers and importers of Islamic education and educators. 22

Despite the comfort and wealth, it is clear that Muslim life in China was

perceived more as a matter of sojourn and tenancy rather than permanent

habitation. The terminology used by the Song state to define Muslims cer tainly reflects this in calling their neighbourhood 'foreigners' quarters' (fan

fang) and insisting on using the term 'guests' (fee) in reference to them. Thus.

for instance, we can find designations such as 'native born foreign sojourners'

(tusheng fanke) or 'fifth generation foreign sojourners' (wushi fanke). 23 Even

after more than a hundred years in China, one was still not 'Chinese'. This was

the quintessential 'merchant diaspora', and the numerous references in Ibn

19 Abu 'Abd Allah ibn Battuta, Rihlnt Ibn Battuta (Beirut, 1997), p. 639. Translations are from

Ibn Battuta, The travels of Ibn Battuta, trans, and ed. H.A. R. Gibb, Hakluyt Society

(London, 1994), p. 900, with my minor amendments.

20 Ibn Battuta, Rihla, p. 633. In Gibb, Travels, pp. 894 5.

21 Ibn Battuta, Rihla, pp. 633 5. In Gibb, Travels, pp. 894 7.

22 M. J. Shari'at, 'The library of the Tung his [sic; i.e. Tongsi] mosque at Peking', Asian

Affairs, 11, 1 (1980), pp. 68 70; Donald D. Leslie and Mohamed Wassel, Arabic and

Persian sources used by Liu Chih', Central Asiatic Journal, 26, 1 2 (1982), pp. 78 104.

23 Yang Huaizhong, 'Tangdai de fanke'; 'Songdai de fanke', in Yang Huaizhong, Huizushi lungao (Yinchuan, 1991), pp. 50 128.

416

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

### Islam in China

Battuta to merchants, on the one hand, and to the acute sense of distance from

the Islamic world, on the other, account for both parts of this term. 24

Phase two: Khanbaliq and Yunnan

The Mongol conquest of China, completed in the second half of the thirteenth

century, dramatically transformed Muslim presence and Islamic life in China. In

many regards, the 'Quanzhou phase' was not disrupted and was even further

intensified in the wake of the Mongol unification of Asia and the effects of the

'Pax Mongolica'. More merchants than ever before came to China many of

them from the Islamic world. 25 They also became stronger politically. The

aforementioned Pu Shougeng, the Song appointed official in Quanzhou, sur

rendered the city to the Mongol armies in 1276, and offered them naval forces.

He remained in office until 1280, and the grateful khan, Qubilai, made him

responsible for all trade in southern China, including Canton. He passed away

peacefully in 1296. 2 During the Yuan period, a third of the superintendents of

trade ships in Fujian were Muslims, located in several ports.

The bigger change, however, came with the different type of Muslims and

Muslim settlements introduced to China during the Mongol period. The Mongols created in China a 'professional diaspora', in which Muslims were

the largest element, by bringing in technocrats, scientists, administrators,

soldiers, musicians and artisans of all sorts, to settle and help govern and administer China. 27 (It is important to note, however, that Muslims had served

in various Mongol courts from early on, even before the conquest of China.) 2

This professional diaspora did not replace the merchant diaspora but added an

important layer to it. The massive influx of Muslims during the period also

created rural Muslim communities particularly, but not only, in north western

and south western China. Migrants and discharged Muslim soldiers were encouraged to settle and farm areas that were depopulated after the wars,

so as to revive the economy and enhance the control over the local popula

tion. This policy helped create a large rural Muslim population. 29 Finally, just

24 Ben Dor Benite, 'Even unto China'.

25 See Yang Zhijiu, Yuan dai Hui zu shi gao (Tianjin, 2003), pp.77 125; also see Jerry Bentley, Old world encounters: Cross cultural contacts and exchanges in pre modern Times (New York, 1993).

26 Kuwabara, 'On P'u Shou keng'.

27 Yang, Yuan dai Hui zu ski gao.

28 Morris Rossabi, 'The Muslims in the early Yuan dynasty', in J. Langlois (ed.), China under Mongol rule (Princeton, 1981), pp. 257 94. See also Yu Zhengui, Zhongguo li dai zheng quan yu Yisilanjiao (Yinchuan, 1996), pp. 76 114.

29 Yang, Yuan dai Hui zushigao, pp. 149 89,237 62; andlipman, Familiar strangers, pp. 34 5.

417

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

as Muslims had been introduced to China, the Mongols introduced China to

the world. 'China' was now part of the 'Yuan khanate' and was incorporated

with other territories, among them Central Asia, Mongolia, Tibet, northern

Vietnam, and the kingdom of Dali in the south west. This meant that more

Muslims, particularly in the Islamised and Islamising Central Asian territories,

were now sharing the same rulers with the Chinese and coming into closer

contact with China.

Thus, in addition to the 'Quanzhou' Muslim merchant, semi secluded in the Muslim quarter in port cities, we now encounter figures like 'Abd al Rahman, Fatima, or Ahmad, the all powerful minister at the Mongol court in Khanbaliq (future Beijing) who appears in Marco Polo's travelogue.

Marco Polo's account of this man is quite hostile. Its mention of Ahmad's sexual voraciousness suggests that Polo was influenced by European images

of the Prophet Muhammad when he was writing. But, the basic description

of the 'saracen named Ahmac' (A ha ma in the Chinese sources), 'a crafty and bold man, whose influence with the Grand Khan surpassed that of all others', reflects the power that certain Muslims had at the court. This Ahmad was a finance and treasury man, like numerous other, less important,

Muslims at all levels of the Yuan treasury and tax administration. 30 Other

wings of the Yuan government such as medicine and engineering housed large numbers of Muslims as well. The official records of the Yuan dynasty

tell us of two Ahmad and Isma'il who came from Mosul to China at the invitation of Qubilai to make cannons. It was also at this time that Ibn Sina's

studies in pharmacology arrived in China.

But perhaps more interesting than the political figures at the court were the

Muslim scientists and other learned men. Perhaps more than the previous

rulers of China, the Mongols considered astronomy and calendar making to

be important tools of power. They populated their newly built observatory in

Khanbaliq with astronomers brought in from the Islamic world, where astronomy and mathematics were the most advanced in the world. The records of the period mention men like Jamal al Din, a Persian astronomer

in charge of the most significant calendar reform in China in centuries. Soon

after the establishment of the Yuan dynasty, Jamal presented the court with his

'Thousand Year Calendar'. Islamic astronomy was so important in the court

that the Mongols created a 'Bureau of Muslim Astronomy' (Huihui si tianjian)

alongside the regular office of astronomy. An independent office was certainly

necessary since the Muslim astronomers introduced new tools and new

30 Marco Polo, Travels (London, 1929), pp. 275 8; Lipman, Familiar strangers, pp. 31 2.

418

Cambridge Histories Online © Cambridge University Press, 201 1

### Islam in China

methods to Chinese astronomy. 31 Jamal al Dm also introduced new methods

of geography and mapmaking and was very instrumental in producing the

first 'all national record' (da yi tongzhi), encompassing all of China's geogra

phy. 32 As we shall see, one of the most important projects during the Ming

would be the translation of this knowledge into Chinese. In any event, from

the early Yuan period on, until the arrival of Jesuit astronomers in the seventeenth century, Islamic astronomy would play an important role in the

history of Chinese science.

Alongside the Khanbaliq scientists and administrators came massive num bers of Muslims in the military system who settled elsewhere in China. As is

well known, the Mongol armies that conquered and governed China included

many non Mongols and Muslims. After the conquest, the Mongols used these

soldiers in garrisons all over China and encouraged them to settle in different

regions in eastern, as well as north western China. The rather high numbers

of Muslims in Chinese military organisations later on is partially connected to

this policy. The most significant activity, however, was in what was to become

the south western Chinese province of Yunnan. This large region, originally

not part of China, was incorporated with the khanate, and its inhabitants 'civilised' for the Mongols, by Shams al Dm 'Umar (1211 79). 'Umar, a noble

man and a sayyid from Bukhara, had a long career in the Mongol military after

the surrender of Bukhara to the Mongols during the wars of Central Asia. In

China, he held a number of high military appointments in the Mongol government before taking over as governor of the newly conquered Yunnan in 1274. 'Umar was responsible not only for the successful 'stabilisa

tion' of Yunnan, which meant by and large bringing Chinese administration.

agriculture and farming as well as culture to the province, but also for its (perhaps unintended) Islamisation. There is some controversy among Western scholars concerning the depth of Shams al Din's faith in Islam. But

there should be little doubt that this Bukharan prince is at least partially responsible for the influx of Muslims into the province during this period, an immigration that created a vibrant Muslim community in Yunnan. 33 Two

of 'Umar's sons succeeded him as governor and this family of Muslims domi

nated the province well into the Ming period, when the government forced

31 Benno van Dalen, 'Islamic astronomy in China during the Yuan and Ming dynasties',

Historia Scientiarium, 7 (1997), pp. 11 43. Also, Tazaka Kodo, 'An aspect of Islam [sic]

culture introduced into China', Memoirs of the Research Department of the Toyo Bunko,

16 (1957), PP- 75 160.

32 Yang, Yuan dai Hui zu shi gao, pp. 303 14.

33 Ibid., pp. 347 55-

# Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Han settlers to move to the province. During the nineteenth century, Yunnan

was an important centre of Islamic activity political, cultural and military.

The Yunnan Khanbaliq phase was crucial as a transition away from the Tang Song relative isolation of 'non Chinese' Muslims living in China. In addition to the merchants, we now had also Muslims who were soldiers, farmers, artisans, administrators and scientists all professions that require

greater and more intensive contacts with the population at all levels. During

the Tang and the Song periods, cases of Muslims who adopted Chinese names

and/or were intimately familiar with Chinese culture, such as the 'Arab mandarin' Li Yansheng, or the Pus of Quanzhou, were quite rare. During the Yuan period, this began to change. Mongol policies had generally tended

to keep the different populations under their control separate, and Ibn Battuta's description of the Muslim communities reflects a picture of Muslims living in distinct quarters within large cities. Now, the presence of

Muslims in the government and the administration meant, in the long run,

that more and more Muslims became increasingly familiar with Chinese culture, styles and norms. This was probably true towards the end of the Yuan dynasty, when its Mongol rulers themselves became acculturated to Chinese culture to a considerable degree.

One can understand this process on different levels administrative, economic and cultural. First, the various designators with the fee (guest) character to them that prevailed during the previous periods disappeared.

Instead, the state used a new administrative term for identifying its foreigners

(and therefore Muslims): semu (lit. 'coloured eyes'), which meant 'people of

various categories'. 34 Furthermore, the term 'huihui' became exclusively associated with Muslims. 35 Huihui has its origins in the Tang period, and to

this day it is not quite clear why it became associated with Islam and Muslims.

Nevertheless, it became the most common designator for Muslims during the

Yuan period, as the aforementioned title of the Islamic bureau of astronomy

and the numerous figures identified in the official records as 'huihui' testify.

Huihui also developed several variations huimin (hui people), huizei (Muslim

bandits), huijiao (hui teaching; that is, Islam) and huizu (Muslim national), to

name a few, and became the first word used for Islam in Japanese as well (kaikai, and kaikyo). Finally, in terms of culture, the Yuan period saw the first

instance of Muslim literary activity in Chinese most notably Chinese poetry.

Traditionally less socially and culturally rigid a field than classical learning,

34 Lipman, Familiar strangers, pp. 32 5.

35 Zhang Yingsheng. Yuan Aai Hui zu wen xuejia (Beijing, 2004), pp. 129.

420

Cambridge Histories Online © Cambridge University Press, 201 1

## Islam in China

Chinese poetry already had one great hero of non Chinese descent, the Sogdian Li Bai (701 62). During the Yuan his successors were the Muslims

Gao Kegong (1248 1310), Saadulla (1272 1355), Ma Zuchang (1279 1338), Ma

Jiugao (1268 1350), Nai Jian (1309 68), Qin Buhua (1304 52) and many others.

It should be noted that with the exception of the first poet, all the others were

born in China after the founding of the Yuan. 3

Phase three: Nanjing

The Nanjing phase, which corresponds quite closely to the rise of the Ming

dynasty in the fourteenth century, is the most dramatic turning point in the

Chinese Muslim history sketched here. Just as the transformation of the state

and the empire during the Song Yuan transition had a tremendous impact on

China's Muslims, the transition from the Yuan, a huge multiethnic empire headed by Mongols, to the smaller and Chinese Ming had its impact. Simply

put, it marks the ideational transformation of 'Muslims in China' into 'Chinese

Muslims', as the Muslims living in China adopted Chinese culture. The other

side of this process was the disappearance of Arab and Persian culture and

language, leaving 'Islam' as the most significant element in the 'Islamic' side of

the new emerging Chinese Islamic identity. For instance, Arab and Persian

language and names disappeared, giving way to Chinese names or Chinese

variations on Arab names Mahmud and Muhammad turned into 'Ma'. Similarly, Middle Eastern and Central Asian styles of clothing and architecture

also gave way to Chinese styles. Other Islamic practices were modified. Finally, towards the end of the Nanjing phase we see the rise of a specific form of Islam that was particularly Chinese. And next to the term Huihui, we

now see the rise of two more terms designating Islam and Muslims: 'Qing Zhen' (lit. Pure and True, which should be read as 'authentic halal), and 'Tian

Fang' (lit. 'Heavenly Square', referring to the Ka'ba). The term semu disap

peared with the Yuan state that created it. The Nanjing phase also marks the

decisive end of the Quanzhou phase. Of course, Muslim merchants did not

disappear. But the Arabic or Persian speaking merchant who had traded quite

freely with the Islamic world was now gone. This development also had to do

with changes in trade in the Indian Ocean. But within China, Nanjing the first capital of the Ming dynasty played the key role in such processes.

Muslims were greatly affected by the rebellions that eventually drove the

Mongols out in the mid fourteenth century and created the Ming dynasty. The

36 Ibid., pp. 51 297.

421

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

strong Muslim military presence and their basic alliance with the Mongol state

were both key in this transition. On the one hand, a Yuan garrison of Muslim

soldiers near Quanzhou fought against the Ming armies when they arrived in

the region after having defeated the Mongols elsewhere. This episode resulted

in harsh Ming policies against the Muslims of Quanzhou after the 'rebellion'

was crushed, and many families left the city and migrated elsewhere. 37 On the

other hand, however, some prominent members of the Ming founder's original warband were Muslim. These men, like the Ming founder Zhu Yuanzhang (1328 98) himself, all hailed from a region in Anhui province where the Mongols had previously settled many Muslim soldiers. 3

This duality affected Ming policies towards the Muslims. On the one hand they were suspect, on the other they were recognised as a social force to reckon with. Thus, for instance, when all 'foreign' religions were banned after

the rise of the Ming, Islam was not. But the regime, striving for greater homogeneity along (imagined) 'authentic Chinese' cultural norms, dictated

a much less conspicuous Islamic presence in the public sphere. As a result,

minarets disappeared from Chinese mosques, and the call for prayer was abolished. Zhu Yuanzhang's son, Zhu Di (r. 1402 24), permitted and even sponsored the renovation of several mosques all over China. Similarly, at first,

Zhu Yuanzhang sought to isolate the Muslims by banning intermarriage and

the adoption of Chinese names. Soon thereafter, however, both were encour

aged by the regime. At the court itself, the Muslim presence continued as,

famously, the Ming rulers sponsored the translation of Islamic scientific knowledge into Chinese, a project that produced some of the most important

Chinese works in astronomy and medicine. 39 Later on, such policies would

give rise to the image of the Ming dynasty as a 'patron of Islam' and to the

persistent claim that Zhu Yuanzhang himself was a 'secret Muslim'. 40 Soon

enough, sizeable and highly acculturated Muslim communities emerged in

Nanjing itself and elsewhere in eastern China. Many members of these communities began to compete for official positions through participation in

the Chinese civil service examination system. 41

37 Shinji Maejima, 'The Muslims in Ch'uan chou at the end of the Yuan dynasty', Memoirs of the Research Department of the Toyo Bunko, 31 2(1973 4)-

38 Zvi Ben Dor Benite, 'The Marrano emperor: The mysterious bond between Zhu

Yuanzhang and the Chinese Muslims', in Sarah Schneewind (ed.), Long live the emperor!:

Uses of the Ming founder across six centuries of East Asian history, Ming Studies Research

Series, 4, Minneapolis, 2008, pp. 292 3.

39 Ibid., pp. 281 4.

40 Ben Dor Benite, 'The Marrano emperor'.

41 Ben Dor Benite, Dao of Muhammad.

422

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

## Islam in China

Another important aspect of Ming policy that greatly affected Muslims was

its attitude of 'conciliate and control' vis a vis Central Asia and its Muslims.

The collapse of the Yuan khanate effectively created a border between the

Muslim communities of Central Asia and the Muslims of China, particularly

those of the north west, which the Ming rulers tried hard to keep sealed. Nevertheless, Muslims kept migrating from Central Asia to China. Two centuries after the founding of the Ming, the Jesuit Matteo Ricci (1552 1610)

gives us an invaluable testimony that reflects this situation and the results of

the Ming transformation. Accounting for a wide range of forms of Muslim life

in China and reflecting the condition of 'co habitation' between Chinese law

and Islamic ritual, Ricci writes:

since in the far western regions China borders on Persia, at various times many

followers of Mohammedan faith entered this country, and their children and

descendants multiplied so much that they have spread over all China with

thousands of families. They are residing in nearly all provinces, where they

have sumptuous mosques, recite their prayers, are circumcised, conduct their

ceremonies . . . and live subject to Chinese laws . . . For these reasons, they are

treated as native Chinese, and not being suspected of plotting rebellion, they are

allowed to study and enter the ranks of [the] bureaucracy. Many of them, having

received official rank, abandon their old beliefs, retaining only their prohibitions

against eating pork, to which they have never become accustomed. 42

The most important outcome of the Nanjing phase was produced by a group

of people located socially somewhere between the highly acculturated bureaucratic elite and the mosque goers. The Han Kitab, a hybrid of Chinese and Arabic words that means 'The Chinese Book', is a huge collection of books and treatises on Islam, in classical Chinese, by scholars

educated both in the Confucian classics and in Islamic textual tradition. Few

Han Kitab scholars had passed through the official Chinese examination system. Most came from a unique education system, one that combined classical Chinese studies with Islam, which began emerging in the late 1500s.

The system originated in the Muslim communities of north western China.

but it really gained ground and prospered after its second generation of teachers moved eastward, and settled within the highly acculturated urban

communities of the Yangzi delta Nanjing in particular. Even scholars from

as far away as Yunnan, such as Ma Zhu (d. c. 1680), a descendant of the aforementioned Shams al Din, spent time in the city teaching. 43

42 Cited in Jonathan Spence, The memory palace of Matteo Ricci (New York, 1984), p. 118.

Translation is Spence's with some of my own edits and amendments.

43 Ben Dor Benite, Dao of Muhammad, pp. 26 71, 115 62.

423

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Drawing heavily on Chinese norms of scholarship and transmission of knowledge, the Han Kitab scholars understood themselves as a 'school of scholarship' within the wider community of Chinese scholars, a school whose

traditional teaching was Islam. Accordingly, the study of Islam was defined as

the study of the 'Dao of Muhammad', that is, the 'Way' that originates in Muhammad's teachings. As an originator of knowledge, the prophet was compared to great Chinese sages of antiquity so as to legitimate the study of

his teachings by his followers in China. 44 The Han Kitab books consisted at first

mostly of translations of Islamic (Persian Sufi) texts. From the mid seventeenth

century, shordy after the rise of the Manchu Qing dynasty in 1644, scholars also

began producing original works mostly highly sophisticated combinations of

Sufi and classical Chinese thought. The purpose of learning (xue) was renzhu

('Knowledge of the Lord'), an adaptation of the Sufi ma c rifa I Hrfdn. In this way,

not Islam per se, but the study of Islam was rendered compatible with the Neo

Confucian definition of the purpose of learning, which tended to assign it mystical dimensions. 45 It is important to note that the Manchu Qing dynasty's

'multiethnic' imperial policies had a direct impact on the identitarian tone that

Han Kitab books began taking on from the later seventeenth century. As opposed to the 'China centred', homogenising policies of the Ming, the Manchus, 'foreigners' themselves, redefined the empire as a multiethnic and

diverse entity over which they presided. Their policies did not specifically single

out Chinese Muslims, but they certainly enabled Han Kitab scholars to articu

late a specific Chinese Islamic identity in their writing, and to offer a unifying

narrative for the history of Islam in China and its relationship with the wider

Islamic world. These efforts were crucial during the emergence of the new

'national' Chinese Muslim identity in the twentieth century. 46

Phase four: Lanzhou and Xinjiang

Whereas the Nanjing phase of Chinese Islamic history was mostly cultural in

nature, the final phase discussed in this essay is marked by a mixture of cultural shifts, military activity and violence. The heading, the place name

44 Ibid., pp. 163 213.

45 Sachiko Murata, Chinese gleams of Sufi light (Albany, NY, 2000); Murata, William C. Chittick and Weiming Tu, The sage learning of Liu Zhi: Islamic thought in Confucian terms (Cambridge, MA, 2009).

46 Ben Dor Benite, Dao of Muhammad, pp. 1 20, 214 38; Ben Dor Benite, 'From "Literati"

to "'ulama'": The origins of Chinese Muslim nationalist historiography', Nationalism and

Ethnic Politics, 9, 4 (Winter, 2003/4), PP-83 109.

424

Cambridge Histories Online © Cambridge University Press, 201 1

#### Islam in China

'Lanzhou', the provincial capital of Gansu, or 'China's Mecca', derives from

the fact that beginning in the mid eighteenth century it emerged as a major

regional centre for the numerous Muslims living in China's north west.

transformations of Muslim life in the region are closely connected to the Qing

expansion to the almost entirely Muslim region of eastern Turkistan, which

came to be known after its conquest by the term Xinjiang, or 'new dominion'.

More specifically, Xinjiang refers to the several oasis towns along the old Silk

Road such as Urumqi, Kashghar, Turpan and Hami all populated mostly with Muslims of various Turkic ethnicities, most notably people who are known today as 'Uighurs', a name taken from an ethnicity that has lived in this

region since antiquity. Whereas the Ming severed the strong ties that north

western Muslims had with the inhabitants of Xinjiang's oases, the Qing's expansion to the region greatly affected their lives. The conquest and creation

of the province of Xinjiang brought into the empire a whole new group of Muslims that was culturally different from the Muslims of 'China proper'. In this regard, a whole new chapter of the history of Islam in China began in the

1760s (and has not yet ended). 47 More specifically, the conquest of Xinjiang

gave rise to a distinction between the Chinese Muslims across the border with

Xinjiang, who came to be known as 'inner land' Muslims (neidi hut), and the

Turkic speaking Muslims of Xinjiang. 48 More importantly, Uighur resistance

to the Qing conquest became a source of constant friction and tension between Muslims and the government and often affected the relationship between Muslims and an increasingly hostile and suspicious government. Up until the 1780s, relations between the state and the Muslims in the north

west were relatively peaceful. But the tension and the violence between Muslims and the state in Xinjiang triggered a bloody history of tension that

swept up Muslims from both sides of the provincial border. It largely ended

only with the rise of the Communist state in 1949; in the case of Xinjiang the

tensions are very much ongoing.

The second significant result of renewed connections with Central Asia was

the introduction of Naqshbandi Sufi tafiqas to north western Chinese Muslim

communities. Initial Sufi paths to China had been forged already at the end of

the seventeenth century, when Central Asian Sufi leaders came to the Muslim

north west seeking new followers. But the phenomenon really gained

47 Peter C. Perdue, China marches west: Tfie Qing conquest of central Eurasia (Cambridge, MA, 2005).

48 James A. Millward, Beyond the pass: Economy, ethnicity, and empire in Qing Central Asia,

1759 1864 (Stanford, 1998); Millward, Eurasian crossroads: A history of Xinjiang (New York, 2007).

# Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

momentum when local charismatic individuals imported the new practices to

the region. Two stand out in this history: Ma Laichi (1681 1766), a disciple of a

disciple of the Kashghari master Afaq Khoja (d. c. 1694), who founded the

Khafhya order and had sojourned in China himself; and Ma Mingxin (1719 81),

founder of the Jahriyya order. As opposed to the doctrinal Sufism that helped

create a school of scholarship in eastern China, the much more rural north

west engaged in practical Sufism. The coming of Sufi orders to the region greatly transformed Muslim life, both socially and religiously. The form of Islam practised in the area before the coming of Sufism, adhered to now by

only a small part of the population, came to be known as gedimu (from qadim,

that is, 'old', or 'original'). More importantly, the orders reorganised the Muslim society in the region, forming groups of adherents around certain figures who were treated as saints. The saints and the lineages they started

became major loci of power that often competed with each other, and, crucially, with the suspicious state. Quarrels between followers of these orders led to the brutal execution of Ma Mingxin by the government of Lanzhou in 1781, triggering repeated major waves of violence between Muslims and the state that lasted for over a century and devastated the Muslim population of the region. 49

The subsequent two Islamic centuries in China were quite different phases

in terms of intensity, magnitude, nature of events and transformations, and in

terms of the scope and nature of Chinese Muslim relationships with the state

and with the Islamic world. Yet the phases discussed in this essay still resonate

and their traces can be seen in the intensely diverse forms of Muslim life in

China today.

49 Lipman, Familiar strangers, pp. 59 71.

426

Cambridge Histories Online © Cambridge University Press, 201 1

12

Islam in South-East Asia and the Indian Ocean littoral, 1500 1800: expansion, polarisation, synthesis

ANTHONY REID

Over the past half century historians have endeavoured to moderate the exaggerated importance long attached to 1498 and the arrival in the Indian

Ocean of a small band of Portuguese. The Portuguese introduced consistent

reportage in a language still relatively accessible, and in this sense 1498 may

stand as a turning point in the literature. Asia was henceforth linked to Europe

directly, and the exchange of ideas and technologies was possible without

Arab or Central Asian mediation. Apart from an aggressive naval strategy and

more effective technologies of navigation, time keeping and warfare, how ever, the Portuguese had little more to offer by way of modernisation of commerce, science and technology. They made the great effort to join the maritime trade of the Indian Ocean precisely because it was already highly

developed, delivering spices to Europe through Alexandria and Venice, and

using some sophisticated financial techniques unknown to the Portuguese.

To this Muslim dominated trade the Iberians initially brought only plunder

and disruption, and were naturally seen as a scourge. In the longer term the

establishment of a direct maritime route of trade around the Cape of Good

Hope was profoundly important in depriving the Islamic commercial networks

of their monopoly of east west trade and intellectual mediation. It also intro

duced to the world of the Indian Ocean a sharp polarisation between Islam and

its rivals from which the maritime world had previously been spared.

The 'Muslim lake' of the late fifteenth century

The carriage of goods between the various key centres of production in maritime Asia coastal China, the islands of South East Asia, India and the Middle East grew in sophistication as southern Chinese, Javanese, Tamils and

Arabs became more active in it. The movement of population southward in

427

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

China, together with the great prosperity of the Song dynasty there (960 1279),

helped China replace India as the largest single market for South East Asian

tropical produce. But the prosperity of the countries at the opposite end of

Eurasia, in Europe, following their recovery from the fourteenth century Black

Death, made this the other great magnet of long distance trade in the fifteenth century.

Exotic items of food, aromatics and medicine, along with the universally prized gold, silver and jewels, were still the most important items of the long

distance trade in the fifteenth century. Within the Indian Ocean world more

bulky items cloth, rice, ceramics, cowry shells already dominated in volume if not in value. If Muslim traders had been crucial all along the trading

route to China since the eighth century CE, it was only the fifteenth century

European infatuation with eastern spices that took them to the extremity of

the commercial Eurasian world, the Maluku archipelago of eastern Indonesia.

Cloves were then harvested for export only in the tiny rival volcanic islands of

Ternate and Tidore (north Maluku) and nutmeg in the cluster of five volcanic

islands of Banda (south east Maluku). (See Map 8.)

The key feature of these commercial carriers of Islamic beliefs and customs

was that they were trading communities, not representatives of states. They

were often effective warriors, with some of the same superiorities of weapons

and motivation as the Europeans who followed them. But unlike either the

expanding khanates of central Asia or the Portuguese, Dutch and English, they

did not fight in the name of a distant state or receive reinforcements over

long term from a power centre. Only in the sixteenth century did states become the major factor in Islamic expansion also in maritime Asia.

Communities of traders of diverse ethnolinguistic background had earlier found in Islam a powerful rallying point as small minorities in the vast countries they linked through trade. Like Hindu, Jewish and Nestorian merchants, they received from Indian, South East Asian and Chinese rulers

the rights to build their place of worship and to apply their own rules in matters of marriage, inheritance and business contracts. Traders could not

operate alone and could not expect the local state to intervene on their behalf

to recover debts and so forth. In this world the commercial communities which flourished were those which had an internal mechanism for enforcing

contracts, somewhat like the medieval natio of Europe or the millet of

Turkey. 1 For Arabs, Persians, south Indian Muslims and 'Malays' of various

1 R.J. Barendse, The Arabian seas: The Indian Ocean world of the seventeenth century (New York, 2002), pp. 88 93.

428

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

origins, the Muslim identity was more useful in this regard than their ethno

linguistic one. Where the Muslims were small minorities, even Sunm ShTa

distinctions were generally subordinated to the advantages of solidarity with

those who shared an Islamic sense of propriety and acceptable food. Ibn Battuta, for example, made no mention of Sunm or ShTa, Malay or Persian,

in a lengthy description of Quanzhou and other maritime Chinese cities, where 'there is a quarter for Muslims, in which they live by themselves, and

in which they have mosques both for the Friday services and for other religious purposes. The Muslims are honoured and respected.' 2

Of course ports governed by Muslims offered more attractive opportunities.

and there are numerous examples of the Muslim commercial minority playing

a major role in putting a Muslim ruler on the throne. By around 1500, the major

Indian Ocean ports for the long distance trade were Muslim ruled (see Map 7)

Jiddah, Aden, Basra and Muscat in the Arab world, Cambay in Gujarat, Melaka

on the peninsula and Pasai, Pidie (Pedir) and Aceh competing in northern Sumatra (see Map 9). Even in Hindu ruled Java the Muslim ports of the north

coast Gresik and Japara (see Map 10) had asserted their independence of Hindu Majapahit. But the Muslim commercial minority was almost as much

at home in ports such as Calicut in Malabar (Kerala), where Muslim writers like

Ibn Battuta in the fourteenth century and Abdul Razzaq in the fifteenth appre

dated the strict justice and security offered by its Hindu rulers 'Security and

justice are so firmly established in this city' that every vessel was treated with

the same strict honesty no matter what the religion or provenance of its owner. 3

In the Cham ports of what is today the Vietnamese coast, in Siam, Pegu (Burma), Cambodia and Brunei, as in China, the Muslim traders were rich and

powerful enough in their respective quarters to be treated with respect and care.

The Muslim spice trade was particularly flourishing around 1500, when over 100 tons of Malukan spices (cloves, nutmeg, mace) were arriving each

year on the docks of Venice. Though small items of trade in comparison with

pepper, sandalwood and cinnamon, these were valuable and well docu mented, and travelled the whole route from easternmost Asia to the Mediterranean. The system worked in sectors, hinged around the great entrepots just mentioned where the items would be sold and redistributed

to onward markets. Javanese and Bandanese Muslims would carry the spices

from Maluku to Java, particularly its Muslim ports; Javanese and Malays

2 Ibn Battuta: Travels in Asia and Africa, 132; 1354, ed. H. A. R. Gibb, Hakluyt Society

(London, 1929, repr. New Delhi, 2001), p. 283.

3 'J ourne y of Abd er Razzak', in India in the fifteenth century, heing a collection of narratives of voyages to India, ed. R. H. Major, Hakluyt Society (London, 1857), p. 14.

429

# The New Cambridge History of Islam

would carry them onward to Melaka, whence a variety of Chinese, Ryukyuan,

'Luzon' (hybrid Muslim Filipinos) and Malays would take them to north east

Asia, while Gujaratis, predominantly Muslim south Indians (known locally as

Klings), Malays and assorted others would take them to Calicut and Cambay.

Gujaratis, Persians and Arabs (notably the Karimi merchant guild from Hadramawt) dominated the onward trade to the Red Sea and Persian Gulf.

while Venetian galleys plied the last stage of this maritime route, from Alexandria and Beirut to the chief European market for eastern spices in Venice. Virtually the whole route from Maluku to the Mediterranean was in

Muslim hands. Each stage of the route was travelled when the annually alternating monsoon winds were in the correct direction, so that the entrepots that formed the hinges of the system saw huge crowds of traders

from diverse communities mingling for a period of months as they awaited

the monsoon change.

The key to these ports was cosmopolitanism. Their lifeblood was in welcoming different kinds of merchants, each group playing its necessary role in the trade. Even though Muslim shipping was dominant, every port needed also its Hindu financial castes, the south Indian Chettyars and Guiarati

Sarrafs, to provide finance and letters of credit on other ports. With them came the Hindu temples essential to their operations. In South East Asia all

welcomed the Chinese merchants with their religious traditions. Of Melaka at

this time it was said that eighty four languages could be heard in its streets.

Frequently voyages were equipped using crews who were Muslim and Buddhist, and finance capital that might be Hindu or Jewish. The Arab pilot

Shihab al Din Ahmad ibn Majid complained of Melaka at its Muslim height

that 'The infidel marries Muslim women while the Muslim takes pagans to

wife. You do not know whether they are Muslim or not . . . They drink wine in

the markets and do not treat divorce as a religious act.  $^{\prime}$  4

Portuguese disruption, Muslim regrouping and the rise of Aceh

The Portuguese brought to the Indian Ocean a different kind of naval warfare.

motivated by ethnic and religious solidarities of a new kind. A tight fit between

national self interest and religious zeal had propelled the Portuguese southward

in a long series of battles with Islam, first to complete the reconquest of Portugal

4 Hawiyat al Ikhtisarfi Hm al Bihar (1462), trans. G. R. Tibbetts in A study of the Arabic texts containing material on South East Asia (Leiden, 1979), p. 206.

430

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

itself, and then to carry the fight to the coast of Africa. Once into the Indian

Ocean in 1498 their objective was to locate the sources of pepper and spices and

seize control of them from the Muslim traders by whatever means it took. It was

less a missionary imperative than a crusading one, which justified plunder in

terms of a military political struggle with Islam.

The first two Portuguese fleets, of Vasco da Gama (1498 9) and Cabral (1500 1), seized or sank enough Muslim shipping to make their intentions plain. The Muslim traders of Calicut and Gujarat appealed through their partners in Cairo to the Mamluk rulers of Egypt to send a military force to

combat this new threat. A forty galley Mamluk fleet reached Calicut in time to

do battle against the third Portuguese expedition, in 1502, but was defeated by

da Gama's cannons. A second Mamluk fleet sent out in 1504 to stiffen Muslim

resistance in Gujarat and the south was more successful in a battle off Sri Lanka, but was eventually routed off Diu by Almeida in 1509. They could not

prevent the Portuguese entrenching themselves in fortified strategic points,

initially at Calicut (where the Muslim population became their bitter enemies,

making nearby Cochin a more satisfactory base), then at Goa (1510), Melaka

(1511) and Hormuz (1515). In the first fifteen years of the new century the flow

of Indian Ocean spices along the Muslim route to the Mediterranean faltered

and almost died.

This onslaught forced the trade of the Indian Ocean to adjust in a variety of

ways. Hindu and Buddhist actors quickly worked out modes of operating with

the Portuguese. But the dominant Muslim trade was obliged to arm itself more effectively, and to regroup around stronger rulers able and willing to

confront the Portuguese threat. The Portuguese capture of Melaka, at that

time the largest entrepot of South East Asia, was particularly disruptive. Although the Javanese tried for a time to continue their strong relation with

the city, the other major sectors of the Islamic trade had to attach themselves

to different entrepots. The long term beneficiary was Aceh, but many also shifted their operations to Johor, Patani or Palembang. In Kerala the Mappilas

eventually made Calicut impossible as a Portuguese base, but from nearby

Cochin the Portuguese remained able to form local alliances and to take a

share of the pepper crop.

The key political institution of Indian Ocean trade in the fifteenth century had been the city state, a cosmopolitan autonomous polity dedicated to trade

and dependent on it. Polities such as Calicut, Pulicat (Coromandel coast), Melaka, Pasai, Japara and Gresik tried to stay aloof from the warfare of continental powers, buying their autonomy when necessary by sending tribute to those in a position to threaten. Dependent for even their rice staple

43i

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

on imports by sea, they were potentially vulnerable to the kind of naval attack

launched by the Portuguese.

It was precisely such port states that the Portuguese sought to overpower,

and in the first years of the century they achieved amazing success in doing so.

Virtually all of the port states on which the Muslim trade depended in south

ern India and the archipelago were threatened. It was as Muslims that the

traders had been attacked, and it needed to be as Muslims that they responded.

Their complex links with Hindu rulers or financiers were called into question

by the Portuguese challenge, and they transferred their support to rulers strong enough to defend them against Portuguese attack. As Barros acknowl

edged in mid century in regard to Sumatra, since the Portuguese arrival many

of the numerous port states 'have been absorbed into the territory of their

most powerful neighbours'. 5

The origins of the Aceh sultanate at the mouth of the Aceh river in north western Sumatra appear no older than the late fifteenth century, although

Muslims were well placed since the thirteenth century in the older port of

Lamri, 50 kilometres further east. The advent of a group of prominent merchants and aristocrats from the Champa capital, after that city fell to the

Vietnamese in 1471, appears to have been the stimulus for a new Islamic

dynasty to form in Aceh and incorporate Lamri. Nevertheless it was not sufficiently established as a port state to attract the initial attention of the

Portuguese, who from 1509 sought a foothold in the two older and larger ports

of northern Sumatra Pidie (modern Sigli) and Pasai, which since its con version around 1292 had been the beacon of South East Asian Islam. The Portuguese establishment of fortified strongholds in both ports and interfer

ence in their succession disputes increased the instability to which they were

already prey, and particularly alienated the Indian and Arab merchants. Only

in 1518 did a Portuguese fleet rashly attempt a raid on Aceh, lured by stories of

a 'heathen temple' (possibly Chettyar) stocked with gold there. Aceh's defeat

of this raiding party and seizure of many of its weapons set it on the road to

driving the Portuguese from Pidie and Pasai in the early 1520s, no doubt with

the support of Muslim merchants. By 1530 Aceh had unified the whole north

Sumatran coast under a militantly anti Portuguese dynasty. From that point

Aceh provided a secure base for Muslim traders, who gradually developed

new routes avoiding the centres of Portuguese power. Throughout the remainder of the century, it was the most consistent and militant enemy of

5 Joao de Barros (1563), Decadas da Asia (Lisbon, 1777, repr. 1973), Dec. 3, Livro V, 1.

432

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

the Portuguese, laying siege to the fortress of Melaka itself on multiple

occasions.

The rise of Banten, eventually the strongest maritime sultanate in Java, has

a similar origin. West Java was still Hindu at the Portuguese arrival, including

its main port of Sunda Kelapa, modern Jakarta. The Portuguese saw it as a

promising source of pepper and slaves and made an alliance with it in 1522.

A backlash occurred against them at about the same time as Aceh conquered

the Portuguese strongholds in northern Sumatra. The founder of Islamic power on the west Java coast, through the two west Java sultanates of Cirebon and Banten, is known in Javanese tradition as Sunan Gunung Jati.

While it is possible that the military conquest of Banten and Sunda Kelapa was

the work of his son in law Fatahillah (for whom there is a Cirebon grave dated

1570, quite distinct from that of Gunungjati dated 1568), most sources attribute

everything to Sunan Gunung Jati himself.

This wall or apostle (from Ar. wall, saint) was by origin a Sumatran from Pasai. Angered by the intrusion of the Portuguese in Pasai, he travelled to

Jiddah and Mecca with the spice ships around 1515, and spent about three years

as a religious student there. When he returned the Portuguese were still entrenched, and he moved on to the principal Muslim stronghold in Java, the

port state of Demak There he reputedly married the sister of the ruler, Sultan

Trenggana, and encouraged him to use his power to expand Islam on the island. Presumably learning of the Portuguese beachhead in the west, Gunung

Jati obtained Demak assistance to go there and establish Muslim control at

Banten, west of Jakarta. From there he conquered the main Sundanese (west

Java) port of Sunda Kelapa in 1527, and renamed it Jakarta. His descendants

became the sultans of Banten, developing in the coastal strip of west Java a

substantial port and polity, distinct by its Javanese language and its literal Islam

from the Sundanese of the interior, but also a formidable rival of the Javanese

state centred eventually in Mataram. Once again, Portuguese intervention had provoked a strong Islamic riposte.

In southern India it was the Mappilas who emerged as the implacable Muslim opponents of the Portuguese, even though they had initially been more localised trade rivals of the Arabs and Gujaratis. The Mappilas were indigenous or hybridised Malayalam speaking Muslims, who dominated the

regional trade around the coasts of southern India and Sri Lanka. Virtually

throughout the 1520s and 1530s they were at war with the Portuguese, fighting

particularly over the pearl fisheries and the trade in pepper and cinnamon.

Like the Acehnese they adopted the language of jihad, laying siege to Portuguese forts in Calicut (where they forced its abandonment), Kollam

433

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

and Colombo. Of major ports they were strongest in Calicut, and enabled its

rulers to hold off the Portuguese, who made their major Kerala base for the

pepper trade in Cochin further south. But they never controlled a state, and

had a difficult relationship even with their prime protector, Hindu ruled Calicut.

The rise of a few powerful 'gunpowder empires' in the sixteenth century at

the expense of less defensible commercial ports was a wider phenomenon

than the Indian Ocean world, and Christian Muslim rivalry was by no means

the only factor at work. The military revolution making more effective use of

cannon and other technologies spread unevenly, and assisted some military

innovators in becoming unprecedentedly strong. Portugal's invasion of the

Indian Ocean coincided with the rise of two mighty Turkish empires. The Ottomans expanded towards the Indian Ocean by annexing Egypt in 1517, and

extended their rule to the Hijaz and Hadramawt in the subsequent years. In

India the victory of Babur's armies at Panipat inaugurated Mughal rule, which

quickly came to dominate all of northern India.

The Ottoman Turks were far the more important of the two as a maritime factor. Their claims on the caliphate, their control of the land passages of the

old Islamic spice route and their wars with the European powers made them

the only conceivable leaders of any concerted Islamic response to the Portuguese threat. The first Asian maritime state to contact them and support

their claim to the caliphate was the Bahmani sultanate of the Deccan, then

master of the west coast around Goa. Its sultans exchanged letters with the

Ottomans as early as the 1480s, despite the obstruction of the Mamluks in

Egypt. After the fall of the Bahmanis in 1527, these contacts appear to have

been revived by Bijapur, the Muslim successor state in that section of the coast.

Gujarat, independent at the time under Muzaffar Shah II (r. 1511 26), had

much more intimate commercial relations with the Red Sea and Persian Gulf

ports as they fell under Ottoman control. In 1518 Muzaffar Shah congratulated

the Ottoman sultan Selim I (r. 1512 20) on his victories and sought his assistance against the accursed Portuguese. Turks were prominent in Gujarat's armed forces, and Gujarat became the first strategic partner of the

Ottomans in their attempts to become an Indian Ocean power.

6 Naimur Rahman Farooqi, 'Mughal Ottoman relations: A study of political and diplo

matic relations between Mughal India and the Ottoman empire, 1556 1748', Ph.D.

dissertation, University of Wisconsin, (1986), pp. 20 3. This was subsequently published with the same title in Delhi in 1989.

434

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

By 1537, when the strongest of Ottoman rulers, Siileyman 'the Magnificent'

(r. 1520 66), was ready to initiate a new phase of concerted anti Portuguese

action, Aceh was established as another enthusiastic strategic partner. Aceh's

pepper, still grown chiefly in the formerly independent Pasai and Pidie regions, had mostly been destined to China during the fifteenth century. But Portuguese disruption of Muslim export from the south west coast of India led Gujarati and Arab shippers to seek new supplies from Aceh, now

firmly anti Portuguese. By the mid 1530s, a new Islamic route was well established, probably shipping pepper directly from Aceh ruled Pasai via the

Islamic Maldives to the Red Sea. This quickly came to rival the Portuguese

route in the volume of pepper shipped to Europe. It also established direct

relations between Aceh and the Ottoman ruled ports of Jiddah, Aden and Suez, and gave Aceh its claim to be 'the verandah of Mecca' (serambi Mekkah),

the place of departure for South East Asian pilgrims making the hajj.

Sultan Siileyman received petitions from Indian Ocean littoral states plead

ing for protection of shipping, and appealing to the Ottoman role as 'servitor

of the Holy Cities' (Khadim al Haramayn). In 1537 he sent envoys to Gujarat and

other Indian Ocean ports to gain their support for the attack on the Portuguese. 7 We do not know if these envoys also went as far as Aceh, but

it seems likely that the first Acehnese attack on Portuguese Melaka, in 1537,

was partly motivated by the Ottoman initiative. From this point onward, Portuguese sources are full of references to Turkish soldiers and weapons

playing a key role in Aceh's campaigns, against both the neighbouring Hindu/

animist Bataks and the Portuguese in Melaka. Mendes Pinto, more valuable

for his evocative detail than for his accuracy with numbers, portrayed 300

Turkish troops, together with others from Gujarat and Malabar (Kerala), turning the tide in Aceh's contest with the Batak king, who was for his part

bolstered by presumably non Muslim auxiliaries from other parts of Sumatra

and Borneo, and from Portuguese Melaka.

However, the naval expedition under the Ottoman governor of Egypt, 20,000 men strong, proved a dismal failure. Its attempt to besiege the Portuguese fortress in Diu in September 1538 was defeated, and the Ottoman Gujarat alliance broke up. Since many of this large army reportedly

'dispersed because the people of India had induced them away', 9 they must

7 R. B. Serjeant, The Portuguese off the South Arabian eoast, Hadhrami chronicles (Oxford, 1963), PP- 76 7, 79 80.

8 The travels of Mendes Pinto, ed. Rebecca Catz (Chicago and London, 1989), pp. 21, 26.

9 Hadrami chronicle al Sana al Bahir, quoted in Serjeant, The Portuguese, p. 97.

435

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

have played a role nevertheless in subsequent attacks on Portuguese around

the littoral.

The anti Portuguese activities of Aceh in the period 1537 9 were probably the work of the warlike local ruler of Pasai, Ala ud din Ri'ayat Shah al Kahar,

brother and successor of the Aceh sultan. His control of the then major pepper

port probably made him also the recipient of the additional Turkish military

assistance which came with these ships. This may have enabled him both to

lead the first expedition against Melaka, and to topple his brother and seize the

throne sometime in the period between 1537 and 1539. Al Kahar then ruled

until 1571, and became the major scourge of the Portuguese in the Malacca

Straits. Alliances between the Portuguese and Aceh's rivals in northern Sumatra, syncretically Muslim Aru and a non Muslim Batak federation, increased the militant quality of al Kahar's rhetoric. Acehnese remembered

him as the one who established the Turkish alliance and first employed the

ghdzi ideal of 'fighting all the unbelievers', 10 while Portuguese sources por

trayed him as a bloodthirsty exponent of pure jihad. Pinto included the interesting detail that al Kahar took special pride in a title of holy warrior against the infidels, bestowed by the sharif of Mecca in acknowledgement of

the annual gifts of two golden lamps that he sent to the Holy City. 11

Siileyman the Magnificent must have been discouraged by the defeat in 1538, and subsequently directed his attention to Europe and the Mediterranean. Aceh also encountered some local setbacks in the 1540s. The

only substantial Turkish fleet sent into the Indian Ocean in the remainder of

Siileyman's reign was that of Piri Bey in 1551, destroyed by the Portuguese in

the Persian Gulf. Even that ineffective thrust may have stimulated another

anti Portuguese coalition in the Islamic Far East. The Portuguese reported

that Johor, one of Aceh's usual rivals, tried to rally Japara, the leadingjava port

and Portugal's main rival in the Maluku spice trade, into a holy war against

Portuguese Melaka in 1550 i. 12 More fundamentally, the important Muslim

states all along the Indian Ocean trading route, including the Mughals, Bijapur

and Golconda in India, the Mappilas in Kerala and the port states of South East

Asia, became committed in this period to orthodox Sunni Islam, with implicit

or overt acceptance that the umma ought to be a political community united

behind a caliph in Turkey.

10 'ghdzi dengan segala kafir'; Nuru'd din ar Raniri, Bustanu's Scdatan Bab II, Fasal 13, ed.

T. Iskandar (Kuala Lumpur, 1966), p. 32.

11 The travels of Mendes Pinto, p. 30.

12 H.J. de Graaf, 'De regering van Panembahan Senapati Ingalaga', Verhandelingen van bet Koninklijk Instituut, 13 (1954), pp. 33 4.

436

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

The peak of this great power rivalry in the Indian Ocean came in the 1560s,

probably also the peak for the Islamic trading route from Aceh to Jiddah. By

this time Aceh's pepper production had greatly expanded on the west coast of

Sumatra, while the Muslim share of the spices of Maluku was also expanding

through commercial strongholds in Japara and Banda. In this period Venetian,

Portuguese, Turkish and Acehnese sources all make note of the diplomatic

and military ties expanding along the trade route between the Ottoman realm

and Muslim South East Asia.

The chief initiatives this time came from Aceh. There were Venetian and Portuguese reports as early as 1561 2 about well endowed Aceh embassies to

the Turkish capital. Sultan Siileyman sent out eight Turkish gunners in response to this early request. A later and better documented embassy of the Acehnese envoy Husain, however, carried a still extant letter from al Kahar, appealing for the sultan's help as caliph to protect Muslim pilgrims

and merchants on the way to the holy places. This arrived only after Siileyman

had died in 1566. The new Ottoman sultan, Selim II, began with enthusiasm to

aid these distant tributaries. In decrees of September 1567 he commanded an

expedition of seventeen vessels equipped with guns and gunsmiths to proceed

to assist Aceh to crush the Portuguese and take Melaka. An ambassador was

despatched to Aceh to carry the royal response. Three centuries before its

time, Selim commanded the investigation of a route for a canal to link the Mediterranean and the Red Sea, to make it easier for Turkish naval power to

be projected into the Indian Ocean. 13

The fleet never reached Aceh; it was diverted to suppress a rebellion in Yemen. Selim II, like his predecessor, soon lost interest in Oceanic enterprises.

But both Portuguese chroniclers and Acehnese memory insist that some Turkish help arrived in Sumatra. In the period leading up to a major Aceh attack on Melaka in January 1568 the Portuguese were convinced not only that

500 Turks arrived to strengthen Aceh, but that the Sumatran sultanate galvanised further support for a concerted jihad against the Portuguese by

the rulers of Calicut, Masulipatam (Coromandel or Tamil coast), the local Gujarati ruler at Broach, and Demak in Java. 14 While most of this was rhetoric,

there was an undoubted peak of militancy at this period. In 1565 Bijapur, Golconda and other Muslim states of the Deccan combined to destroy the Hindu empire of Vijayanagara. In 1570 there was another Acehnese siege of

13 Anthony Reid, An Indonesian frontier: Acehnese and other histories of Sumatra (Singapore,

2004), pp. 78 86; Farooqi, 'Mughal Ottoman relations', pp. 267 9.

14 Diogo do Couto, Da Asia (Lisbon, 1778 88, repr. 1973 4), Decada 8, cap. 21, pp. 130 2.

437

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Melaka and attacks at the same time by Calicut, Bijapur and Gujarat against

Portuguese possessions in India. This was one of the most difficult moments

for the Portuguese in Asia. Even as far east as Ternate in Maluku, the Portuguese were ejected from their fort when a militant Muslim for the first.

time assumed the Ternate throne.

It is rightly said that Islam came to these maritime realms by sea and by trade, interacting with and adapting to local beliefs as it made converts among

the local commercial population. In this early stage force was seldom of much

utility, and the community was essentially a commercial one living as an enclave minority in a very plural world. The sixteenth century, however, brought a quite different quality to political Islam. In a number of areas holy

war was embraced as the appropriate response to the Portuguese onslaught,

and then extended to local non Muslims. New gunpowder empires arose on

the back of trade wealth and firearms, and adopted a militant vision of Islam as

the rationale for their expansion. In such areas the line between Muslim and

unbeliever became explicitly political.

Crossing the line had clear political as well as behavioural consequences. Some groups who felt themselves the victims of this militant period, including

al Kahar's Batak rivals, the Hindu Balinese and some Torajans of Sulawesi,

developed their sense of modern identity in consequence as specifically non Muslim. Other communities, like the pearl fishers of southernmost India or one of the two traditional moieties of Ambon, consolidated their identity by allying with the Portuguese as Christians against this political Islam

of mid century.

Sixteenth-century consolidation of Muslim institutions

Much energy has been expended pushing back the first indications of Islamic

presence in one place or another, usually in the form of a tombstone or a name

in the Chinese record. Too little has been given to the crucial process by which

Islam extended its reach from harbour communities to major states, essen

tially in the sixteenth and early seventeenth centuries. At the beginning of this

'age of commerce' in the fifteenth century Pasai was probably the only state

which espoused and institutionalised Islam as a central part of state identity.

By its end in the mid seventeenth century Islam had occupied most of its modern extent in South East Asia, mosques and religious schools were built at

substantial settlements, most Muslim rulers had ensured that pork was not

438

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

eaten and that funerals and key public ceremonies were Islamised, while a few

had imposed what they believed to be Islamic law in their capitals.

Writing around 1515, Tome Pires pointed out that although the king of the

Minangkabau (Sumatra's most numerous people) had accepted Islam when he

married the Melaka sultan's sister, many said he was not truly Muslim. 'The

truth is that he is a Moor [Muslim], with about a hundred of his men; all the

other people are heathens'. 'In Borneo there were Muslims only at the Brunei

capital, where the king had recently converted; in northern Maluku, the bastion of Islam in eastern Indonesia, the kings of Ternate and Tidore were

Muslims 'but not deeply involved', while 'three parts and more out of four'

were still heathen. 15

The chronicle of Patani, in the Thai Malay borderlands on the east coast of

the peninsula, tells the story of that kingdom's Islamisation in two stages. Sometime in the early 1500s the king promised to become a Muslim if miraculously cured of an illness by a visiting shaykh from Pasai. After twice

reneging on his promise, he finally submitted to the shaykh's requirements.

He recited the shahdda, accepted an Islamic name and instructed all his court.

likewise to become Muslim. In his lifetime, 'all the people within the town adopted Islam, but of the people outside the town area not one accepted Islam. And although the raja accepted Islam, the only habits he abandoned

were worshipping idols and eating pork. Apart from that he changed not one

of his heathen habits.' It was only considerably later in the reign of his son

Mudhaffar (d. 1564) that another shaykh from Pasai visited and complained

that 'if there is no mosque [in a country] there is no sign of the Islamic religion'. So a mosque was built, and only then the country people too became

Muslim and permanently accepted the laws of the Prophet. Although they in

turn abandoned pork and the worship of idols (berhala), perhaps as a Hindu

cult, they continued to worship stones, trees and spirits. 1

In Pasai there were certainly mosques at the time of Ibn Battuta's visit in 1345, and in Melaka 'the beautiful mosque ... the finest known in these parts'

was built by Sultan Mansur Shah (r. 1459 77). I7 In his time there was also a qddi

of Melaka, as there had been earlier in Pasai. But outside the quarters of the

traders from 'above the winds' (Persia, Arabia and India), there was little

15 The Suma oriental of Tome Pires, trans. Armando Cortesao, Hakluyt Society (London,

1944), pp. 132, 213, 248.

16 Hikayat Patani: The story of Patani, ed. A. Teeuw and D. K. Wyatt (The Hague, 1970),

vol. I, pp. 75, 78 9. An English translation, somewhat different from mine, is given in

vol. II, pp. 151 2, 154 5.

17 Suma oriental of Tome Pires, p. 249.

439

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

evidence of Islamic scholarship in South East Asia before the sixteenth cen

tury. Only then do we begin to read of L ulama' spreading out from strong

holds such as Pasai to teach in other ports. The political polarisation referred

to above encouraged rulers who aligned with the Islamic side of the contest to

seek out religious teachers and embrace their new ways of thinking as a bulwark against the Portuguese, and at the same time a justification for expanding their realms.

Muslims and Christians developed their institutional arrangements for

proselytising South East Asia in tandem with each other, and often provoking

each other into further efforts. The initial crusading impetus of the Portuguese

had left little room for preaching or proselytising. Only in mid century with

the Jesuit mission of Francis Xavier were there serious efforts at conversion for

its own sake, rather than as a sign of political loyalty. Xavier went first (1542) to

the impoverished Paravas of the pearl fisheries opposite Sri Lanka, who had

sided with the Portuguese in the bitter Christian Muslim fighting over the pearl trade in the 1530s. He laid the basis for a permanent Tamil speaking

Christian community there, and a Malay speaking one in eastern Indonesia,

notably Ambon. The Spanish, colonising the Philippines after the full effect of

the Catholic Counter Reformation, put a higher priority than the Portuguese

on sending missionaries to convert the islanders.

From mid century, then, the competition between Muslim and Christian also took on a proselytising quality. Centres such as Aceh, Demak, Gresik.

Brunei and Ternate sent learned 'ulamff on the trading ships to frontier areas,

to set up schools and communities. In the first stage up to the fifteenth century

the lingua franca of Islamic commercial communities around the Indian Ocean had been Arabic, but Malay now became established as the language

of South East Asian Islam. The Melaka chronicle noted that the people of fourteenth century Pasai all spoke Arabic, whereas in fifteenth century Melaka the chief lingua franca was Malay, with Arabic script. The Melaka chronicle, in its story of the Portuguese conquest of 1511, mentions the Hikayat

Muhammad Hanafiah and the Hikayat Amir Hamza, versions of two famous

Arab stories of warrior heroes of the Prophet's time rendered into Malay verse. On the eve of battle the young Melaka nobles asked the sultan to have

the first of these read to stir their courage, while he initially offered instead the

latter. 1

18 'Sejarah Melayu or "Malay Annals'", trans. C. C. Brown, Journal of the Malaysian Branch of the Royal Asiatic Society, 25, parts 2 and 3 (1952), p. 168.

440

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

Evidence for the development of a corpus of theological and mystical writing in Malay comes later. The earliest of the great Malay writers known

by name, Hamzah Fansuri, was thought to have flourished around 1600 until a

copy recendy came to light of a gravestone in Mecca of one Hamza ibn Abdullah al Fansuri, dated 1527. I9 He felt the need to say that he was writing

his mystical text in Malay so that the Muslims who did not know Arabic or

Persian could understand it. If such writing was then still relatively rare, it

reached its flowering within a century. Many of the key writers of the seventeenth century read and quoted Hamzah, and like him taught and wrote in Aceh, the principal domesticator of Arabic and Persian ideas into

the Malay world.

The most prolific of these Malay writers, the Gujarati born Nur al Din al Raniri, recorded some of the history of this process. Some noted scholars

arrived in Aceh from the Arab world on the pepper ships, and began to teach

in this new frontier. The Egyptian Muhammad 'Azhari Shaykh Nur al Din came from Mecca in the 1570s and taught inferential theology (maqulat). In the

1580s two more well known ^ulamff came from Mecca to teach fikh and usul

respectively. A little later al Raniri's uncle, Shaykh Muhammad Jailani, arrived

from Gujarat to teach fikh, usul and tasawwuf. 2 ' While these learned men

presumably taught and wrote in Arabic, their students and successors, includ

ing al Raniri himself, were masters of Malay. One of the most prolific was the

Pasai born Shams al Din al Sumatrani al Pasa\*!, who composed many texts in

Malay and Arabic advocating a mystical monism influenced by the Naqshbandi Sufi order. His chief tool for proselytisation was a Malay cate chism of 1601, in the form of 211 questions and answers, the Mxrat al Mumin. He

is also widely thought to have been the qadi or Shaykh al Islam ('bishop') of

Aceh who was able to use his Arabic to discuss matters with James Lancaster's

first English fleet in 1602.

The direct political and economic connection between Aceh and the Ottoman ruled Arabian peninsula, in other words, laid the basis for Aceh's

emergence as the intellectual centre of Islamic South East Asia (Fig. 3). We

shall return below to the main preoccupations and debates of the schools of

Islamic writing that developed there.

19 Claude Guillot and Ludvik Kalus, 'La stele funeraire de Hamzah Fansuri', Archipel, 60 (2000), pp. 3 24.

20 Nuru'd din ar Raniri, Bustanu's Salatin, pp. 32 3.

441

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

3 Mainstream South East Asian mosque type before the twentieth century, exemplified in

the multi tiered roof of the seventeenth century Indrapuri mosque in Aceh, on a base

which may well have supported an earlier Buddhist shrine (photo: Anthony Reid)

### The conversion of Java

As home of the only substantial Indianised kingdoms in South East Asia that.

subsequently became Muslim, Java is especially interesting. Almost the whole

of Javanese speaking (central and east) Java became nominally Muslim in the

long sixteenth century, with some of the Hindu elite taking refuge in Bali. This

contrasts not only with Bali and the eventually Buddhist states of mainland

South East Asia, but with India itself, where major Hindu communities continued in those parts of India which were conquered by Muslims. Even

in other parts of South East Asia where Islam made an early and deep impression, there remained large interior communities that resisted Islam.

as with the Batak case mentioned above. The key to Java's distinctiveness appears paradoxically to lie in the very strength of the older Hindu Buddhist

tradition exemplified by Majapahit, on to which Islam was successfully grafted. Warfare played a major part in the Muslim conquest, but a creative

process of selecting and filtering the new religious and cultural elements was

442

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

equally important. Akbar's synthetic project in Mughal India of developing a

religious system which could carry all his subjects with him was a failure, but

the analogous project in Java may be said to have prevailed under the Mataram kings.

### The political conquest

The long sixteenth century was critical for this process in Java, even more

decisively than elsewhere in the archipelago. Around 1500, according to Portuguese reports, Islam was still limited to the coastal trading cities of what had been the Majapahit kingdom that is Javanese speaking central and east Java. As the previous chapter has made clear, these were cosmopol

itan trading centres, which owed their Islam partly to the (partly Hanafi) trade

and tribute connection with Champa, Canton and Quanzhou, and partly to

the (principally Shafi'i) Islamic spice trading route to the west, through first

Pasai and Palembang, but after about 1460 primarily Melaka, to the Indian

Ocean world beyond.

Demak was by 1500 the strongest of these Muslim port states, while its erstwhile patron, Hindu Majapahit, was in disarray. Dynastic upheavals after

i486 led to the move of its capital further inland, to Kediri, where it lost influence over all the coastal ports except Tuban. The wealth of Demak had

been built in the last quarter of the fifteenth century by a very successful Sino

Malay trader from Palembang, in some chronicles called Ko Po. He built a

fleet of ships trading around the Java Sea, dominating the spice trade from

Maluku and the supply of Java rice to Melaka. He had reputedly spent time in

Gresik, an older Islamic centre and port for Majapahit, but as Majapahit crumbled he moved his base of operations to Demak, and central Java became

the centre of Javanese rice exports. He was not himself a ruler as much as a

politically astute merchant, who married his daughters to several of the key

coastal kings. His descendants became rulers of Demak, and made it the clear

leader of the Islamic alliance and the major power of the Java Sea. He or his

son must have been one of the historical identities whose memory went into

the construction of the legendary Javanese hero Raden Patah ('the con queror'). In the eighteenth century Mataram historical epic, Babad Tanah Jawi, this figure was used to legitimate the non Javanese or mestizo Muslim

coastal rulers as appropriate heirs of Majapahit. He was made the son of the

last Majapahit Hindu ruler by a Chinese princess, banished to Palembang as a

child and brought up by a client ruler there. His conquest of Majapahit, in the

also legendary year 1478 (the Javanese year 1400, thought appropriate for a

443

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

change of dynasty), could therefore be seen as a restoration of the Majapahit lineage.

The first firmly historical ruler of Demak was known posthumously as Sultan Trenggana. Son or grandson of the Sino Malay shipping magnate, he

may have come to the throne around 1505. He patronised the building or rebuilding of the great mosque of Demak, in 1507, and presumably the casting

of the great cannon Ki Jimat, dated to 1527/8 and bearing the inscription 'the

supreme result is the triumph of the faith'. 2,1 He may have patronised some of

the semi legendary holy men (wall) of Java, such as Sunan Kalijaga, whom

popular tradition credits with the conversion of much of interior central Java.

This king appears to have ruled until his death on the battlefield in 1546,

though eclipsed during part of his youth by his forceful brother in law Patih

Yunus of Japara, another successful shipowner who took over some of Demak's maritime networks and confronted the Portuguese in the second decade of the century.

Trenggana's long reign coincided with the transition of Javanese Islam from

a cosmopolitan commercial enclave situation to an aggressive competitor for

power in Java. The challenge of the Portuguese, vividly experienced by refugees from Melaka and Pasai, must have been connected with this tran

sition, as we saw above in the expansion westward to Cirebon and Banten in

the 1520s. Already a few years after the fall of Melaka to the Portuguese, the

ruler of Tuban, Majapahit's only remaining coastal dependency, told Tome

Pires that Majapahit was 'always at war with the Moors on the sea coast, especially with the lord of Demak. 22 Muslims who had experienced the Indian

Ocean contest with the Portuguese identified Trenggana as the likeliest leader

of the political expansion of the dar al islam in Java. Sunan Gunung Jati, notably, is remembered as having bestowed on him the title sultan after his

return from Mecca, perhaps seeing it as a legitimation for military expansion.

Demak finally succeeded in taking the Hindu capital at Kediri around 1527, in a

campaign portrayed in Javanese sources as a holy war supported by several

Muslim port states and such spiritual leaders as the master of the sacred place

Kudus (al Quds), a little to the east of Demak.

The defeat of Majapahit did not lead direcdy to a Muslim kingdom taking its

place. In the power vacuum at the centre of Java Demak was now well placed,

but it remained a coastal metropolis long separated from the politics of the

21 Denys Lombard, Le carrefour javanais: Essai d'histoire ghbale (Paris, 1990), pp. 179 81, 378 n. 945.

22 Suma oriental of Tome Tires, p. 176.

444

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

interior, and still interested above all in its trade. The following decades saw

Sultan Trenggana sending the vital military and spiritual aid to one faction

of a succession dispute in Banjarmasin, in return for conversion. According to

the Banjarmasin chronicle, this intervention secured the Islamisation of Banjarmasin and enabled it to become the principal Muslim state of southern

Borneo, initially under Demak patronage. In the 1540s Trenggana led a military campaign eastwards, against the Hindu kingdom of Pasuruan. Mendes Pinto claims to have followed the campaign in 1546, and refers to

Turkish and Aceh assistance with artillery, and detachments of soldiers from

Banten, and from the 'Luzons' (Muslim Filipinos) exiled from the Manila area.

Pinto's account of this contest is free of the holy war rhetoric he used for Aceh's campaigns, however. Even though one side is Muslim, these contest

ants were both part of the same Javanese moral universe.

Sultan Trenggana was killed during this war against Pasuruan, and so it was

presumably his successor who in 1548 alarmed a visiting Jesuit with his aggressive plans to spread Islam around the neighbouring peoples, and 'become another Sultan of Turkey'. 23 On the contrary, however, Java after

Trenggana's death became again a patchwork of local chiefdoms. The com

mercial centrality his grandfather had built up had long passed to other centres

with better ports. References in the most reliable Javanese chronicle to wong

mati Selam (people who die for Islam, or martyrs), fighting furiously on the

winning side in battles for interior centres in the 1570s, 24 suggests that the

multiethnic Muslim shock troops who had fought for Islam under Demak's

banner continued to be decisive in the following decades. But all sources agree

that whatever unity there was on the Muslim side during Demak's heyday was

lost to a variety of newly Muslim contenders by the 1460s. Pajang, near contemporary Surakarta, claimed authority over much of central Java includ

ing Demak itself in the third quarter of the century, and hence a primacy over

the lords of Java.

According to the Javanese chronicles, it was a military commander of Pajang's forces who was given the fertile Mataram area around modern Yogyakarta as a fief. His son, Panembahan Senopati Ingalaga, emerges more

fully into history as a conquering king of Mataram from about 1584. As portrayed by an acute Dutch visitor in the following century, he was remem

bered as having used Islam to make a clean break with the old Hindu dynasty,

23 Mendes Pinto from Melaka, 7 December 1553, in Joseph Wicki (ed.), Documenta Indica II (Rome, 1950), p. 423.

24 Babad ing Sangkala, 1738, in M. C. Ricklefs, Modern Javanese historical tradition: A study of an original Kartasura chronicle and related materials (London, 1978), p. 24.

445

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

kill all potential rivals from that quarter and stake his claim to a new kind of

legitimacy based on upholding the new religion. After establishing an inde

pendent base in Mataram he 'made war until the end of his life', which came in

1601. 25 By then he had subdued the older centres of Pajang and Demak, and

taken possession of items of regalia held to confer legitimacy since the time of

Majapahit. He had also extended his power to Kediri and Madiun.

Senopati was remembered as the founder of the last strongjavanese state; a

great conqueror who returned power to the interior by mastering the

type of warfare introduced by Muslims, Portuguese and Chinese on the coast.

The Mataram he effectively founded laid claim to legitimacy in Islamic as well

as Javanese terms. Senopati sought to compensate for his lowly origins by

marrying various royal ladies, while subsequent historians saw him as succes

sor to Majapahit through Demak and Pajang. We know almost nothing about

the nature of his Islamic commitment, or the extent to which Islam was practised. Javanese legend has one of the coast based wall, Sunan Kalijaga

from the Demak holy place of Ngadilanggu, as his adviser, but no mosque is

attributed to him. Senopati's Mataram appears in fact to have been a pioneer

ing military camp in a fertile but underpopulated area, with most of its early

population forced to shift there as soldiers or captives from other areas.

Unlike its Muslim predecessors Mataram was not dependent on the Muslim

commercial communities of the Javanese pesisir (coast), though it needed their

support if it was to grow and flourish. The centres of the old Majapahit culture

were far away in east Java, and its leaders killed or fled to the remotest east at

Balambangan. The models both for Islamic learning and for the partially Islamised Javanese court culture were now in the pesisir. With the decline of

the central Java ports, the centre for both moved to Surabaya, including its

nearby port area of Gresik in which sat the Islamic 'holy hill' of Giri. If Mataram applied just as much Islam as its ruler saw fit, Surabaya inherited

from Demak the leading role of seeking to build a new civilisation which could reconcile the needs of international Muslims of the port communities

with those of Javanese aristocratic tradition.

Senopati failed in his attempts to incorporate the Surabaya area. This task

fell to his grandson, Sultan Agung (r. 1613 46), who defeated Surabaya in a

series of campaigns in 1620 5. It was the reign of this Javanese sun king that

created the synthesis between the old Java of Majapahit and the new Java of

the Muslim coastal cities. The eclipse of the Muslim coastal cities, under the

25 Rijklof van Goens, 1656, cited in Anthony Reid, Southeast Asia in the age of commerce

1450 1680, vol. II: Expansion and crisis (New Haven, 1993), p. 177.

446

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

military pressure of Mataram and the commercial inroads of the Dutch and

English into the formerly lucrative spice trade of the pesisir, brought an end to

a remarkable chapter in Javanese history. During the long sixteenth century

Java had been as exposed to the cosmopolitan and commercial influences of

the Muslim oecumene as had other parts of the Indian Ocean littoral. By the

end of Agung's reign those influences were limited and controlled, and a Javanese synthesis was in place that could bring even the most Hinduised elements of Javanese society along with it.

#### The spiritual synthesis

The story just told is one of kings and battles, and the way in which the old

order of Majapahit, centred 60 kilometres up the Brantas valley in east Iava,

was supplanted first by an avowedly commercial and cosmopolitan Islamic

order, and then in turn by an interior kingdom in south central Java. Another

story must be told, closer to that of the Javanese traditions, about a spiritual

transformation attributed to a number of miracle working holy men, mystic

saints as well as warriors.

The older religious order had comprised both a Hindu ritual in the courts.

intended to safeguard the supernatural legitimacy of kings, and a popular spirituality of holy men and holy places ascetics and hermits in their dhartna

or pertapaan (hermitages). The former was seemingly destroyed in the battles

of the long sixteenth century, so that no Brahmans survived to minister to the

needs of the court as they did in Buddhist Siam and Cambodia. The latter was

much more resilient. Tome Pires described how vigorously the older pattern

of ascetics itapa) survived the first stage of Islamisation even in the pesisir

ofjava:

There are about fifty thousand of these in Java. There are three or four orders

of them. Some of them do not eat rice nor drink wine: they are all virgins, they do not know women. They wear a certain headdress which is full a yard

long . . . And these men are also worshipped by the Moors, and they believe in

them greatly; they also give them alms; they rejoice when such men come to

their houses. 2

The popular success of the new doctrine in Java lay in its ability to penetrate

this ascetic world and gradually give it a more Islamic flavour, rather than

seeking to condemn and confront it directly. The wali beloved of Javanese Islamic tradition are depicted as men who through meditation and self denial

26 Suma oriental of Tome Pires, p. 177.

447

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

had penetrated to the inner unities of being, and could thereby demonstrate

superior spiritual powers. There are stories of their visiting the ancient mountain hermitages such as Mantingan near Demak, or Pulasari near Banten, and being accepted by the adepts (santri) there. The earliest Javanese guide to Islamic behaviour, from the pesisir of the sixteenth century,

itself adopted the same term tapa for its model Muslim. But 'the stronghold of

the tapa is to stay in the mosque, to perform the five daily prayers and to recite

the Quran'. The line was drawn against the tapa of the unbelievers and their

yogic practices. 27

This document certainly comes down to us from a Javanese urban milieu where Islam was still contested, even if supported by the local ruler. Muslims

had to be warned against honouring idols, praising the more generous behaviour of non Muslims and answering questions about religious identity

by denying one's Islam or suggesting it made no difference. Suggestive of the

upper hand of Muslims in the city, however, was the warning against killing a

non believer in order to take possession of his property, rather than for

religious motives. 2 The earliest Dutch expedition to Java, from 1597, also

received the impression that it was still only the coast that was predominantly

Muslim.

Legends about the spreading of the faith among the people of central Java

are associated with one of the best loved wall, Sunan Kalijaga, and his disciple,

Ki Pandan Arang. The latter was supposed to have come from the former rulers of Java, and in one version was in reality the last king of Majapahit.

Kalijaga converted him to the ascetic life through various miracles, however,

after which Ki Pandan Arang travelled about central Java performing his own

miracles and converting notable people as well as ruffians to the true faith. He

ended his life by teaching and meditating at the small hill of Tembayat, in the

Mataram area just south of modern Klaten. This appears to have been a pre

Muslim sacred place, judging from its architecture and inscriptions on the site.

In Muslim times however its sacredness was attributed to the tomb of Ki Pandan Arang there, known after his death as Sunan Tembayat. Islamic prayers and interpretations provided an added source of sacred power for

one of the holy places of the Mataram area. The former tapa became known as

santri, and their dharma as pesantren, autonomous centres of study, meditation

and often martial arts, both geographically and politically remote from the

27 G. W.J. Drewes (ed.), An early Javanese code of Muslim ethics (The Hague, 1978), pp. 15, 35.

28 Ibid., pp. 36 9.

Islam in South East Asia, 1500 1800

centres of royal power, and guaranteed immunity from taxes and levies like

their Hindu Buddhist predecessors. 29

Sunan Kalijaga is also attributed with the creation of the Javanese shadow

puppets (wayang kulit), despite the Hindu subject matter of their stories from

the Mahabharata and the Ramayana. Modern students of this most central and

semi sacred of Javanese arts tend to agree that it attained its modern form in

the Islamised pesisir around the sixteenth century, and was not part of the

older repertoire of theatrical forms. It may indeed have seemed a cultural compromise, depicting not human forms, exactly, but shadows. A Javanese

legend has Sunan Kalijaga telling the king of Demak that 'the wayang is indeed

a reflected image of the One, so to speak, the image of the Law. The wavang

represents all humanity, the dalang [puppeteer] corresponds to Allah, creator

of the universe.' 30 Some monist texts saw the dalang as absolute being, the

puppets as relative being and the screen as the outer world of essences where

formal religion had its place. The screen on which the shadows played thereby

represented the hiddenness of the ultimate reality of unity. 31 Yet the shadow

puppets were never used for the cycle of stories imenak) inspired by the Islamic tradition, which were played on wooden puppets also perhaps devel

oped in the coastal cities of the sixteenth century.

The aspect of the Islamic spiritual tradition which most appealed in Java, as

to a lesser extent throughout maritime Asia, was the monism of authors such

as al Hallaj and especially the Andalusian Sufi Ibn al 'Arab! (1165 1240). The

strain of Sufism that stressed a progression through seven layers of meaning,

towards the ultimate hidden one ness, appealed to the ascetic and meditative

strand of Hindu Buddhist Java. Many from the Javanese tapa tradition believed they saw in the Sufi ideas filtering to them through an Indian lens

another avenue of approaching this ultimate one ness. Of course more ortho

dox versions of mysticism propounded by the greatest of Arab theologians,

al Ghazali (1059 mi), also reached South East Asia and gradually established

the boundaries of orthodoxy there as elsewhere. The violent confrontation

between the two strands was well documented in Aceh (see below), but in

Java it is only through the wall legends that we know how a similar battle may

have been played out.

Many of these legends concern Siti Jenar, whose life and death suggest some influence from the Arabic stories about al Hallaj. At a famous meeting of

29 This argument is made most persuasively by Lombard, Catrefourjavanais, II, pp. 114 20.

30 D. A. Rinkes, Nine saints of Java, trans. H. M. Froger (Kuala Lumpur, 1996), p. 130.

31 P.J. Zoetmulder, Pantheism and monism in Javanese Suluk literature: Islamic and Indian

mysticism in an Indonesian setting, trans. M. C. Ricklefs (Leiden, 1995), pp. 163 5.

449

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

the wali in the mosque of Demak all gave their views about the true nature of

unity. They were concerned that Siti Jenar was growing very popular by teaching the secret knowledge which should not be publicly revealed, and that

in consequence his followers neglected the Friday prayer as unimportant. When they summoned Siti Jenar to join them he insisted that Siti Jenar did not

exist, only God existed. When they criticised his followers for not attending

Friday prayer he replied that 'there is no Friday, and there is no mosque'. Sunan Kalijaga, the warrior wali, then beheaded him with his sword, giving

rise to various miraculous stories about his disappearance. 31

We cannot know whether Siti Jenar had an existence in history as well as in

the abundant stories about his life and death. But the fact that these stories end

with his death, as do similar stories about four other popular radical monists,

two more placed in the sixteenth century, one in Agung's reign and one in the

eighteenth century, makes it very likely that the orthodox of the coastal cities

did seek to condemn to death those they identified as pantheist heretics. The

fact that they were all portrayed in the stories as miracle workers who had

attained ultimate knowledge, and erred if at all only in revealing it, shows the

popularity of this manner of thinking in Java's transition to Islam.

It appears that the battle over spiritual legitimacy in this critical period was

especially fought over sacred sites, and the charismatic spiritual eminences

associated with them. Each of the nine wali is associated with a sacred place

where they were thought to have taught, and where their tomb (if, unlike Siti

Jenar, they have one) is located (Fig. 4). The leader of the wali in some versions

was Sunan Giri, and the port complex of Gresik Surabaya over which Giri presided was sufficiently wealthy and well connected to ensure that Giri remained throughout the sixteenth and most of the seventeenth centuries the most prestigious Muslim site in Java. It became even more the spiritual

opposite pole to Mataram during the long resistance of the Surabaya complex

of cities to Sultan Agung's campaigns in the 1620s. Surabaya was eventually

starved into submission in 1625, and the cultivated heir to its throne, Pangeran

Pekik, was forced to become an ascetic at Surabaya's oldest mosque of Ampel.

But Giri continued to represent the greater centrality of Islamic norms and

leadership in the pesisir than in Mataram, and was therefore seen as an alternative and challenge by the king.

Sultan Agung's most explicit steps towards synthesis were coterminous with his campaign to incorporate Giri and co opt its legitimacy in the 1630s.

Reliance on military resources alone was not convincing after his armies had

32 Rinkes, Nine saints, pp. 15 48; Zoetmulder, Pantheism and monism, pp. 296 308.

450

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

4 The entrance to the tomb of Sunan Bonang, one of the nine semi legendary apostles (wali) of Java, located just outside Tuban. It is in the style

of the elevated entrances (gapura) to sacred places in Hindu Java and Bali, representing a syncretic phase in Muslim architecture (photo: Michael Feener)

met a spectacular defeat in attempting to expel the Dutch from Batavia in 1629.

Soon after this disaster the nearby sacred hill of Tembayat appeared to pose a

threat to the king, and he sent an army to conquer it. Whatever transpired

with the santri there persuaded him to make amends in the form of a personal

pilgrimage to the site in 1633, and the reconstruction of its massive gateway in

old Javanese style. At the same time he brought Pangeran Pekik to court from

his internal exile in Ampel, and co opted his charisma by royal marriages Pekik married Agung's sister while Pekik's daughter married the heir to the

Mataram throne. Pangeran Pekik was renowned not only for his heritage from

Surabaya and Ampel, but for his literary skills in incorporating the new Muslim knowledge into acceptable Javanese poetry. He is often credited with the 'civilising' of Mataram by bringing to it the best of court culture

45^

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

from the old Majapahit as filtered through the new pesisir centres. Perhaps

under his influence Sultan Agung established a uniquely complex Javanese

calendar, which incorporated the Islamic calendar with its weekly cycle and

lunar basis for establishing festivals, into the older Indian derived Saka calendar. 33

In 1635 Pangeran Pekik was placed in charge of the reconquest of Giri, which had presumably continued to see itself as an autonomous sacred place

as well as a haven for internationally connected l ulama\ The expedition was

successful and the Sunan Giri was brought to Mataram to make his obeisance

to the king, even if the wanderings of santri refugees from Giri became the

stuff of later legends. In the remainder of his reign Agung seemed determined

to ensure that he was the sole source of spiritual as well as political power. He

sent an embassy to Mecca that brought him back the title of sultan in 1641, a

step his rival in Banten had taken earlier. He began building his mausoleum at

Imogiri that explicitly evoked the kind of hybrid Javano Islamic shrine archi

tecture hitherto devoted to the tombs of the wall Later Javanese chronicles

gave him the title of king priest (prabu pandita) also bestowed on some of the

walis, and claimed that he had such spiritual power that 'each Friday the king

went to Mecca to pray'. 34 Dutch envoys are witness to his success in domes

ticating Islam effectively into a royal cult in which they 'consider their king so

proudly that they respect him as a god' even while insisting that they were

good Muslims 'and curse all others'. 35 Challenges from the more literal Islamic

world would return from time to time, most effectively in the twentieth century, but Sultan Agung had established a synthesis that allowed almost

all Javanese to become Muslims without sacrificing their rich heritage.

The boundaries of Islam in the eastern archipelagos

Prior to the sixteenth century Muslim influences had travelled to those trade

centres of the eastern islands best connected with trade routes to southern

China on the one hand and to the clove producing centres of northern Maluku

on the other. The undated genealogies of Sulu have been interpreted to mean

that a Muslim trader and adventurer from Sumatra began an Islamic lineage

there around 1400. Brunei, Sulu and Manila were the three easternmost tributaries of Ming China in the early 1400s, perhaps because Muslim traders

33 See further in following chapter.

34 Babad Tanah Djawi, Javaanse Rijkskwniek, ed. W. L. Olthof (Dordrecht, 1987), p. 122.

35 H.J. de Graaf (ed.), De Vijf Gezantschapsreizen van Rijkhfvan Goens naar het hof van

Mataram, 1648 1654 (The Hague, 1956), p. 263.

452

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

from Quanzhou had settled in each of them. In Maluku it appears that Javanese buyers of the precious clove crops of Ternate and Tidore, and the

nutmeg of Banda, began to establish stable Muslim communities there in the

late fifteenth century.

When the Portuguese reached Maluku in 1512, and the Spanish of Magellan

reached Cebu and Brunei in 1522, Islam had already begun to make converts

among those who dealt with the trade. Tome Pires explained that the great

majority even of key centres like Ternate were still animist, and the king of

Ternate seemed willing to switch from Muslim to Christian 'if it seemed good

to him'. 3 The five small islands of the Banda group were a kind of merchant

oligarchy where the Javanese and Malay Muslim merchants were held in great

respect. In Brunei Pigafetta described a flourishing sultanate seeking to dominate trade along the whole route from Manila to Melaka. In Cebu (central Philippines) a Muslim trader was on hand to warn the local raja against the aggressive 'Franks'.

In none of these sites, however, did Islam present an obstacle to the favourable reception of the Europeans. They were at first welcomed every

where as alternative buyers of the local spices, driving up the price and increasing the flow of Indian cloth into the region in exchange. Only as the

Europeans sought local domination or monopoly, or like Magellan tried to

impose Christianity at the first encounter, did the lines gradually become established between those who supported the Europeans and those who supported Islam.

As indicated above, the lines became more firmly drawn in mid century throughout the Indian Ocean region, and the numerous local conflicts in Maluku were rapidly drawn into this Christian Muslim dichotomy. The most useful chronicle of the events from the Muslim side, the Hikayat Tanah Hitu, portrayed the second half of the sixteenth century as one of continual holy war against the Portuguese, with those falling on the Muslim

side described as martyrs (shahM). The tenuous Portuguese alliance with the

nominally Muslim kings of Ternate, leaders of one side of age old rivalries

throughout Maluku, finally broke down completely in 1570. The Portuguese

murdered their supposed ally Sultan Hairun, and his son Baabullah led

effective Muslim alliance to throw the Portuguese out of Ternate and to impose Islam as the principal symbol of loyalty to Ternate rather than the Portuguese. He reigned until 1583, and the Europeans credited him with patronising numerous Arab and Persian preachers (muballigh), and with

36 Suma oriental of Tome Pires, pp. 213 15.

453

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

spreading the faith as far as Buton, Selayar (both in southern Sulawesi) and southern Mindanao.

The permanent Spanish presence in the Philippines, beginning with Legazpi's expedition of 1565, ultimately established the northern boundary

of Muslim expansion. Legazpi's seizure of Manila (1571) from the hands of an

incipient Muslim port state made of the city the opposite pole to Baabullah's

Ternate. Alarmed at the sending of Islamic teachers to Mindanao by Ternate

and the older Islamic trade centre of Brunei, Spanish Manila sent expeditions

to Mindanao and Sulu, and in 1578 succeeded in sacking Brunei and curbing

that city's role as a hub of trade and Islamisation for the Philippines. Henceforth the sultanates based in the island of Sulu and the Pulangi river

basin of Magindanao would be the primary political upholders of Islam and of

resistance to the Spanish in the Philippines. For both states the greatest strength was an intense pluralism, which made it impossible for the Spanish

to turn their military superiority and periodic victories into permanent influ

ence. Only the long reign of Sultan Qudrat in Magindanao (c. 1619 71) produced a strong political centre for Islam in this period, partly thanks to

Dutch commercial support.

In this eastern frontier of Muslim/ Christian competition, the Muslim side was far more successful in enrolling the support of local rulers. The port kings

who emerged as competition grew for spices and other products readily allied

with the Muslim traders, patronised them and gave them daughters in marriage, while drawing on the charisma of a new faith as a justification for

expanding their territories. Unlike the situation in Java, Bali, Siam or Cambodia, kingship had not in these regions embraced a specifically Hindu

pattern of legitimation. Yet power remained profoundly spiritual, and no king

could be strong who did not command supernatural support for his rule. Islam

is righdy seen as having brought individualist ('bourgeois') and rational elements into the world of Indie and animist religion. But it could not have

succeeded if it had directly subverted, as Iberian Catholicism did, the rulers'

need to be the pre eminent mediators with the supernatural. In Counter Reformation Catholicism the celibate clergy had a monopoly of sacramental

power, and hence there could be no successful Christian kings. Many rulers in

Sulawesi and Maluku were attracted to Christianity and Iberian assistance, but

misunderstandings put an end to every Christian kingdom after a few years.

By contrast, even the most orthodox of South East Asian sultans, Iskandar

Thani of Aceh (r. 1636 41, see below), claimed in his diplomatic letters to be a

supernaturally powerful world ruler endowed with magical regalia. The Malay language culture of kingship found an Islamic vocabulary to express

454

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

this royal transcendence. Arabic dawla (dynasty or state) became the term for

the profoundly mystical essence of Malay sovereignty, expressed in the self

abasing acknowledgement of royal charisma, 'Aaulat Tuankuf Persian nau bat

(nine drums) became not only the orchestra restricted to royal use, but the

term (nobat) for enthronement itself, by virtue of the sacred powers of the

music. Arabic wahy to express the divine inspiration of the Prophet, became

the magical power unique to kings (especially in Java).

The Islamisation of south Sulawesi, the populous, rice growing south western arm of the island, is a particularly interesting case. Although situated

in the east, beyond any substantial Brahmanic influences, the Bugis and Makassar peoples before their Islamisation in the early seventeenth century

had developed great reverence for their heaven descended royal lineages, a

written culture in an Indie script closest to those of Sumatra and the Philippines, and a priesthood of transsexual bissu as special mediators between

the kings and the upperworld of the gods, whose prehistory was elaborately

described in the La Galigo epic. Although not an essential part of the spice

trading route, south Sulawesi's ports could deliver a rice surplus helpful for

traders travelling to rice deficient Maluku, while the iron of the Lake Matano

area appears to have been important for both Java and Maluku. The abundant

Chinese, Vietnamese and Thai ceramics buried in grave sites of the fifteenth

and sixteenth centuries indicate that it was already integrated into a trading

world. At least by the 1540s, both Muslim and Portuguese traders began calling

in these ports, and encouraging converts. A few of the scores of local rulers

experimented with Christianity, while the Malay traders of the Makassar area

were permitted to build a mosque around 1580. But the major kings resisted

conversion to either faith if it would diminish their supernatural status, not to

mention interfering with their pattern of religious feasting with pork and palm wine.

In the short period 1603 11, on the other hand, all the Makassar and Bugis

kings accepted Islam. Local Muslim traditions associate these conversions

with three Minangkabau missionaries, seemingly linked with the rulers of Aceh and Johor. The consummate politician of Makassar, Karaeng Matoaya,

later told the Portuguese that he had adopted Islam out of largely political

motives, and after failing to get any response from Melaka to his request for

priests to be sent. The royal chronicles, however, suggest a pattern of consultation among the rulers with the greatest reputation for wisdom and

high birth. The most ancient lineage of Luwu was the first to accept Islam formally, and Karaeng Matoaya led Makassar into the new faith very quickly

thereafter (probably September 1605) to ensure that he would not be

#### Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

outflanked. After carefully securing the support of the Makassar nobles for the

new religion, Matoaya proceeded to attack those Bugis states that resisted his

request to follow him into Islam. The chronicles suggest that it was a mixture

of this forceful pressure and the generous terms on which the autonomy of

each state was guaranteed under Makassar's leadership that won them all over

within a few years. Although Makassar, like Aceh, Banten, Demak and Banjarmasin, profited from the expansion of trade and the new firearms to

rise to unprecedented prominence, it differed sharply from them in respecting

most traditional autonomies, and almost all of the older aristocratic culture.

Bissu remained to celebrate the enthronements, weddings and funerals of

courts of the Bugis and Makassar kings. Their lineages continued to be regarded as descended from the upperworld and surrounded with super natural mystique. While the elaborate death rituals still to be seen among the upland Toraja of south Sulawesi were wholly Islamised, and pork abol ished, other rituals of the life cycle, kingship and agriculture survived with an

Islamic addition. In each state a qadi and an imam for the state mosque were

appointed, though usually from among the aristocracy who could be relied

upon not to overturn the adat (custom). Some old palm leaf texts even developed a syncretic origin myth, in which the gods of the La Galigo cycle

were descended from Adam and Eve, and the hero of that cycle, Sawerigading, became a prophet foretelling the Qur'an. The story is probably

apocryphal, but is nevertheless suggestive, that Shaykh Yusuf (see below)

returned to Makassar in the 1660s, and appealed in vain to the rulers to impose

Islamic principles, but they 'were unwilling or unable to prohibit gambling,

cock fighting, arrack drinking, opium smoking and the like. They in fact promoted superstitious practices such as giving offerings to the spirit of ancestors in the hope that the latter would bring them prosperity/ 37

The cosmopolitan port and capital of Makassar was, until it fell to the Dutch

in 1669, a remarkable beacon of tolerance of all faiths, presenting itself in that

period as the free antithesis of the monopolistic Dutch. While Catholic wor

ship was forbidden in the Dutch settlements, there were three Catholic churches in mid century Makassar, and a well regarded Portuguese trading

community of several thousand.

South Sulawesi's most learned and revered c alim, Muhammad Yusuf al Maqassari (known today as Shaykh Yusuf, c. 162.7 99), left his homeland

37 Azyumardi Azra, The origins of Islamic reformism in Southeast Asia: Networks of Malay Indonesian and Middle Eastern 'ulama' in the seventeenth and eighteenth centuries (Sydney,

2004), p. 94.

456

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

for further studies in his late teens, and probably never returned. His life and

writings are more fully dealt with in the following chapter. He represents,

however, two points that should be noted here. First, he is the best documented South East Asian example of the political Sufi who returned from his studies in Arabia to become not only the charismatic populariser of

various tafiqas, but also the chief qddi upholding the sharfa and the soul of

armed resistance after the Dutch conquered Banten's capital in 1682, leading a

guerrilla force of perhaps 4,000 men. Second, he offers a refreshing corrective

to the presumption that Islamic knowledge and authority always flowed eastward, with the role of South East Asians only to adopt and adapt. His travels, sometimes involuntary, circled the Indian Ocean, and he left disciples

in Sri Lanka, Arabia and South Africa as well as Indonesia. 38

Further frontiers: Siam and Cambodia

The Asian maritime frontier of Islam expanded markedly in the sixteenth century, and in some sense reached its peak in the seventeenth before the

boundaries consolidated. The Muslim commercial oecumene in the time of

Ibn Battuta had stretched as far as China, but had little purchase on the littoral

beyond the enclave ports. In the sixteenth century contest with the Portuguese, important states became the champions of the Muslim side, but

the Chinese arm of the original occumene withered. Non Muslim Chinese were definitively in charge of their own commerce in the South China Sea

from at least 1567. By the mid seventeenth century Muslims had lost most of

the high points of maritime commerce, and even pilgrims from South East.

Asia to Mecca travelled most of the way in European ships. Yet as an alternative to the aggressive Europeans, Islam still had gains to make on distant frontiers.

One of these was the Theravada Buddhist world of mainland South East Asia. In this world the Cham ports along the major routes to China provided

the earliest converts to Islam, particularly in the Phan rang area left to the

Chams after their 1471 defeat. There was a Muslim commercial minority here

since the eleventh century, but they made rapid converts from the late sixteenth century until by 1670 the king and most of the coastal population

were declared to be Muslim. This community established commercial and religious links with the Malay states of the peninsula, and a new frontier for

Muslim commerce in Cambodia.

38 See the following chapter for a fuller account of Shaykh Yusuf.

457

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

Cambodia in the half century after 1594 was a battleground of foreign communities. Expanding Viet and Thai polities constantly threatened from

east and west respectively, while well armed Cham, Malay, Iberian, Chinese

and Japanese minorities sought to protect their commerce by holding the king

hostage in their mutual conflicts. By killing a group of Spanish and Portuguese

adventurers in 1598 and opposing the subsequent Siamese intervention, the

Malay and Cham commercial group positioned itself as one of the options for

greater Cambodian independence. In 1642 they supported a coup against an

unusually ruthless king, and the following year led a massacre of forty men of

the Dutch mission which had been asking for monopoly trading rights. The

new king, Cau Bana Chand, increasingly dependent on the Muslims to protect

him against Dutch and other retaliation, embraced Islam, imposed it on his

court, married a Malay woman and used the title Sultan Ibrahim when dealing

with foreigners. Although Cambodian memory has marginalised this figure,

his reign (1642 59) was one of the most stable of this turbulent century, and was only ended by a ruinous Vietnamese invasion that imposed a half Viet king.

Islamic influence in Siam also peaked in the mid seventeenth century, both

in Sunni and Shi'a forms. The Sunni were more numerous, at least in the

southernmost Malay dependencies and among the Malay, Makassar and Cham refugees who appreciated Siam's tolerance. But it was Shi'a Muslims

from Persia and India who were far more influential at the capital. Their annual Hasan Husayn procession was one of the highlights of the Siamese

calendar in the 1670s, with 2,000 Shi'ites reportedly participating. This festival

had provided cover for the Persian assisted coup that brought King Narai to

power in 1657, and in gratitude the king had paid for the annual festival thereafter. A cultivated Persian merchant, Aqa Muhammat Astarabadi, became Narai's chief adviser in commercial and foreign affairs, engineering

a Siamese embassy to Persia in 1668, and placing (mainly Shi'a) Muslims in

control of all the key ports Tenasserim, Mergui, Phuket and Bangkok. Narai

was an intellectually curious renaissance man, intrigued by Persian civilisation

as he later was by that of the Europeans, but was never likely to adopt either of

the foreign faiths that were urged upon him.

Muslim political influence declined with the death of Astarabadi in 1679, and the prominence of Constance Phaulcon at court in the 1680s. It ended

when a coup attempt by Makassar and Cham Muslim refugees was suppressed

with French help in 1686. The example of these Theravada Buddhist countries

reveals, however, both the strength of Islam in the maritime world at this time, and the factors ranged against its further expansion. The former

458

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

included an association with commerce, military prowess and a kind of cosmopolitan modernity at a time when local certainties were under threat;

the latter included even better armed antagonists from Europe and north east

Asia, an ever present anti foreign sentiment and the capacity of the Buddhist

monkhood (sangha) to create strong popular loyalties beyond anything known

to the Hindu influenced animist worlds of the islands.

# Sharfa and Sufi in the seventeenth century

In South East Asia, as in India, the carriers of the Islamic literary and philo

sophical tradition were primarily Sufi masters, who accepted to some degree a

lineage of esoteric and literary learning to their particular teacher and beyond

that to a chain of other masters of the tradition. Azyumardi Azra has at last

provided the first comprehensive survey of these Sufi networks linking Indonesia to the broader Indian Ocean world, making use of their own habit of establishing the legitimacy of their writings by describing the chain

of teachers before them.

In India these Sufi masters often showed an interest in the yogic mystical techniques long practised in the subcontinent, as in Java they could recognise

the strengths of the older ascetic tradition. As we have seen in the Java case,

the Sufi recognition of different stages of consciousness was in turn attractive

to ascetics accustomed to self denial and meditation to attain the inner essence

of knowledge beyond the surface of law and requirements. Some of the earlier

Sufis may indeed have seemed relatively indifferent to the legalistic tendency

ofshatfa. In the eyes of their later seventeenth century critics, the great Malay

poet Hamzah Fansuri (Hamza al Fansuri) and the possibly mythical Javanese

Siti Jenar crossed the line into heretical pantheism. Yet even Hamzah Fansuri

warned the faithful, in one of his favourite maritime metaphors, 'Uphold the

shaft 1 a ... If the rope of your anchor is attached to something other than the

skarVa, it will be difficult to reach the harbour of gnosis.' 39

Azyumardi has pointed out that in the seventeenth century, the leading Sufi

masters 'ardently believed that only by way of total commitment to the shari'a

could the extravagant features of earlier Sufism be controlled.' 40 He stresses

the harmony between the two trends, while earlier writers have perhaps excessively focused on the conflicts. The persecutions of al Ramri were indeed

39 The -poems of Hamzah Fansuri, ed. G.W.J. Drewes and Lode Brakel (Dordrecht, 1986), p. 92.

40 Azyumardi, The origins of Islamic reformism, p. 3.

459

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

of critical importance, but they are the only well documented case of using the

Islamic murtad (apostasy) laws to execute Sufis judged to have strayed too far

from sharVa. These occurred in the reign of South East Asia's greatest patron

of the shari L a, Sultan Iskandar Thani of Aceh (r. 1637 41). He excluded Chinese

traders from Aceh because of their pork eating habits, executed scores of Portuguese who refused to accept Islam (including their French priest, Pierre

Berthelot, subsequently beatified as a martyr by the Catholic Church) and

entrusted religious authority to the stern and prolific upholder of the centrality

of sharfa, Nur al Din al Raniri. Having failed to convince the previous ruler,

Iskandar Muda, to support his views, al Raniri now prevailed, and had the

books of Hamzah Fansuri and Shams al Dm al Sumatrani (d. 1630) burned in

front of the great mosque. Their disciples who refused to renounce the proscribed views were executed for apostasy, including the popular Shaykh

Jamal al Dm.

A consensus may be said to have developed in Aceh and elsewhere that, although al Raniri's numerous writings were extremely valuable in clarifying

for the Malay reading world the dangers of the wujuddiyya mysticism, and

the nature of shari c a and fiqh, his extremism was as unacceptable as the

excesses he condemned. After al Raniri's royal protector died in 1641, Sayf

al Rijal, a Minangkabau disciple of the executed shaykh, returned to Aceh from his studies in Arabia, and bitterly attacked al Raniri's views and actions.

As al Raniri himself put it,

Sayf al Rijal . . . held debates with us over the matters which had been discussed before. We ask: 'How could you approve of the people who assert

that "man is Allah and Allah is man"?' He answers: 'This is my belief and that

of the people of Mecca and Medina.' Then his words prevail, and many people return to the wrong belief. 41

In effect the crowd decided in favour of Sayf al Rijal, the Aceh establishment

accepted the popular view and in 1643 the learned Gujarati fled back to his

birthplace in Gujarat.

The Aceh elite had earlier spurned his advice by putting a woman on the throne, and were so pleased with the results that they enthroned three subsequent women, covering in all the period 1641 99. In this they emulated

the strategy of two other contemporary commercially inclined sultanates, Patani (from 1564) and the Maldives, who also showed a repeated preference

for female rule not previously known in the region. This raises the question

41 al Raniri, Fath al Mubin, as translated in ibid., pp. 60 1. 460

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

5 Evidence of Shafi'i penalties for theft being applied in Aceh, as sketched by Thomas Bowrey in the 1660s

whether the conventional disbarring of women from exercising religious authority was seen as an advantage for the queens by contrast with the pressures of office al Ramri had been able to impose on Iskandar Thani. It

may have been seen as a means to avoid pushing disagreements to the ultimate limit, and effectively legitimating, by default of a sole religious authority, the pluralism that was essential to stable commerce. Azyumardi

points out that the queen, Safiyyat al Din, 'wisely refused' to resolve the debate on the grounds that she had no authority on religious matters. 42,

42 Ibid., p. 61.

461

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Under the queens the Chinese returned, a Franciscan mission served the small

Christian community, commerce prospered and Aceh's most beloved Sufi master, Shaykh [ Abd al Ra'uf al Singkili, established a new and healing consensus.

Abd al Ra'uf was probably born about 1617 in Singkil, a west coast depend

ency of Aceh, and departed for study in Arabia in 1642, just after the Ramri

purges. As set out in the following chapter, he was inducted into the Shattariyya and Qadiriyya orders by Ahmad al Qushashi and studied philos

ophy, fiqh and sharfa with Ibrahim al Kurarii, the two great masters of his day.

He returned to Aceh in 1660 as the best connected and most authoritative of

any Indonesian l ulama\ and was quickly appointed chief religious authority as

Kadi Malikul Adil by the queen. In his own copious writings in Arabic and Malay he never condemned either Hamzah Fansuri or al Raniri, but clearly

sought a synthesis which would reconcile a commitment to sharVa with the

appreciation of the inner knowledge of Sufi masters. It seems clear that it was

he who appealed to the prominent Meccan shaykh Ibrahim al Kurani for a

ruling whether it was legitimate for a sultan to have executed a wujuddiya sufi,

accused of heresy by another l uiama\ when the sufi in question responded

that he could not repent as his argument had not been understood. He received the answer he no doubt anticipated, that such executions were very grave errors, and that a statement which could be interpreted in multiple

ways could not be held as evidence of heresy.

The conflict of the 1630s and 1640s was the most spectacular indication of a

peaking in the trend to a rigid scriptural interpretation of sharfa, after which a

more inclusive and indigenous synthesis was established. Regularly consti

tuted sharfa courts were set up at least in Aceh in the first half of the seventeenth century. In the 1630s there were two such courts functioning,

one to enforce the observance of fasting, prayer and religious orthodoxy, and

the other for issues of debt, marriage, divorce and inheritance. Although Iskandar Muda (r. 1607 36) frequently interfered arbitrarily in the working

of these courts, his successor Iskandar Thani supported the system devoutly,

and even decreed that the ancient South East Asian method of trial by ordeal

be replaced by Islamic requirements for witnesses. Under the early period of

female rule, at least, these courts continued to function. Foreign observers

were quick to notice also that the Shafi'i penalties for theft were applied in

seventeenth century Aceh as rigorously as anywhere in the world, with numerous people being seen on the streets with their hands or feet amputated

(Fig. 5). To a lesser extent, the same phenomenon was noted in Brunei in the

1580s, and Banten in the 1660s.

462

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

South-East Asian localisations

One may take the year 1629 as a striking military turning point, after which the

further expansion of Muslim political power was qualified by the ominous factor of superior European power at least by sea. In that year, coincidentally,

massive attempts were made by the strongest South East Asian Muslim powers to finally eject the Portuguese from their stronghold of Melaka, and

the Dutch from theirs in Batavia (Jakarta). Iskandar Muda of Aceh sent 236

ships and 20,000 men against Melaka, 'the finest fleet that had ever been seen

in Asia', 43 and the last Acehnese tour de force. It was largely destroyed by

superior Portuguese naval tactics and timely assistance from Aceh's Malay

rivals. The same year marked the last attempt by Java's most powerful ruler,

Sultan Agung, to take Batavia in a siege by a vast army poorly equipped with

modern siege techniques. After it too was destroyed, largely by hunger and

disease, Javanese rulers found ways to legitimise the Dutch as part of Javanese

history, working with them more often than against. Although it was much

too early to speak of European military superiority on land, from this point

Europeans held a naval advantage which was accepted as a fact of South East

Asian life.

The direct link between the archipelago and the Islamic heartland was also

broken, as the greater capacity of the English and Dutch companies to ship

spices and pepper around the Cape of Good Hope rendered the Muslim network uneconomic. By the 1620s the ships were no longer travelling directly

between Aceh and the Red Sea. Gujarati shippers, with their own relatively

direct links to the Holy Land, sailed to the archipelago in decreasing numbers,

securing the route to Mecca and Medina via Gujarat taken by Shaykh Yusuf in

1644. About eight Gujarati ships reached Aceh every year at the beginning of

the century, three in the 1630s, one or two after 1660 and none at all after

1690. 44 Thereafter it was Dutch and English ships that provided the most

comfortable passage to Mecca and Madina even by way of the main Gujarati

port of Surat. Muslim traffic remained dense across the Bay of Bengal, but the

chief Muslim connections outside South East Asia came again to be with south

India, and especially the Tamil coast, a world of similar localisations to those in

South East Asia.

43 Roque Carreiro 1630, trans. C. R. Boxer, 'The Achinese attack on Melaka in 1629, as

described in contemporary Portuguese sources', in Malayan and Indonesian studies:

Essays presented to Sir Richard Winstedt on his 8}th birthday, ed. John Bastin and

R. Roolving (Oxford, 1964), p. 113.

44 Reid, Age of commerce II, p. 28.

463

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

The result was a greater reliance on local resources and ideas, and a consensus that retreated from both extremes of the earlier debate.

## Diffusions of Muslim power

The major centres of Islamic learning, translation and propagation in seventeenth century South East Asia Aceh, Banten, Makassar, Ternate were also newly strong 'gunpowder empires' and centres of the spice trade.

The Dutch Company (VOC) at first allied with them in its attack on the Portuguese, but soon sought to dominate or defeat them in its quest for a monopoly of the supply of spices. The Muslim centres in Maluku (the Moluccas) were the first to fall under Dutch control. The sultan of Ternate

was effectively a Dutch client from the 1620s, and the Muslim hold out of Hitu

in Ambon was defeated in the 1640s. Makassar then became a goad to the

Dutch as the remaining free port of the eastern archipelago where the spices

which eluded Dutch controls were sold to English, Portuguese and Muslim

buyers. It was too strong for the Dutch alone, but they engineered an alliance

with a Bugis coalition led by Arung Palakka, resentful of the unprecedented

autocracy introduced by Makassar's Sultan Hasanuddin. Makassar fell in 1669.

Power in south Sulawesi was again dispersed under multiple small states, as in

the pre Islamic sixteenth century, but with the difference of a strong Dutch

naval presence in the fort of Makassar, able often to act as referee between

them.

Aceh under its queens was alone able to retain its complete independence.

The Dutch succeeded only in removing its productive pepper producing areas

on the west coast of Sumatra, and limiting its naval reach in the Straits of Malacca. Internally the sultans were never again as powerful as those of the

early seventeenth century had been. The military leaders rewarded with fiefdoms by Iskandar Muda became hereditary chiefs, small rajas, and united

with the capital only under religious exhortation or the threat from outside.

The substantial party opposing the queens, who lost the contest in the succession dispute of 1688, won the day in 1699 with the aid of afatwa from

Mecca condemning female rule. But the new Arab dynasty was even less successful than the queens had been in imposing its will on the country.

In the pepper sultanates of south Sumatra, the Dutch established a monop

oly in Palembang after sacking the city in 1659, though they continued to have

problems in neighbouring Jambi. Banten remained a strong competitor of Dutch Batavia until the 1680s, with English, French and Danish companies.

and a major Chinese presence, all using it as a base to take a share of the

464

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

pepper from the VOC. As explained in the following chapter, Islamic liter alism peaked in Banten under Sultan Abdulfatah Ageng (r. 1651 82), who patronised Shaykh Yusuf al Maqassari and sent the heir to the throne on a

pilgrimage to Mecca. Batavia's opportunity to crush this rival came in 1680,

when the more pro Dutch son, known as Sultan Haji, sought to take power

from the old sultan. The VOC intervened in the civil war in 1682, and the old

king capitulated a year later. The Banten sultanate became a kind of puppet

thereafter, though often disturbed by bitter individual attacks on Dutchmen.

The conflict between Islamic oriented port and agricultural hinterland, which played its part in these defeats for international Islam, had already been decided by Sultan Agung's Java in the 1620s in favour of a self sufficient

policy founded on rice growing. But the battle was rejoined under Agung's

less capable successors. The arbitrary cruelties of Amangkurat I (r. 1646 77)

managed to unite all his enemies under an Islamic banner. He had massacred

2,000 prominent c ulama' soon after his accession, and killed the king of Madura

after bringing him to court.

A son of this royal victim, Prince Trunajaya, obtained the blessing of Iava's

major Muslim holy places, Tembayat and Giri, for his rebellion in the 1670s

against Amangkurat. It was joined by a formidable group of Makassar refugees

from the loss of their capital, for whom Amangkurat appeared another compromiser with the hated Dutch. By February 1677 Amangkurat I had so

few supporters left that he signed a humiliating treaty with the VOC which

legitimated their seizure of Surabaya.

When the king died soon after, his son saw no better option than to become

a client of the Dutch, as Amangkurat II (r. 1677 1703). The better organised

Dutch forces managed to eliminate his chief rivals by 1680 not only Trunajaya himself but the Islamic leadership of both Giri and Tembayat. The VOC could in this way keep the king on his throne but not enforce his

will. The Javanese heartland knew little peace in the century between the death of Sultan Agung and the Dutch sponsored Giyanti Treaty of 1755 which

finally divided it into two kingdoms. The religious synthesis established under

Sultan Agung nevertheless withstood various challenges and largely defined

the way Javanese would face the new waves of Islamic reform with which they

had to deal in the nineteenth and especially twentieth centuries.

The specifically Malay type of polity, the Malay speaking kerajaan, had not

experienced the 'gunpowder empire' phase of power concentration in the sixteenth and seventeenth centuries. Arguably its genius was necessarily based

on a diffusion of power, with each raja occupying the lower reaches of a particular river, and mediating trade up the river to largely non Islamic food

465

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

producers and foragers whose forest products they exported. Relations between the different river systems were always unstable, with the primacy

of any one port, such as Sriwijaya, Melaka or Riau, always dependent on attracting a diversity of traders. The shifting capitals of Riau Johor in the Singapore area, and Patani in the Thai Malay borderland, were the most substantial Malay centres in the seventeenth century, and Riau continued in

the eighteenth.

Malay language Islamic scholarship was sustained in the sixteenth and seventeenth centuries primarily in strong port polities in which Malay was

not the vernacular Aceh, Banten and Makassar. The defeats suffered by these

states in the latter part of the seventeenth century opened the door to a different type of millenarian Islamic resistance, especially with the approach

of a new hijra century (AH noo began in 1688 CE). In this climate, states could

be imagined rather than defended. One self styled Sultan Ahmad Shah

Iskandar, a miracle working Minangkabau based on the island of Belitung,

claimed in 1685 that he was the rightful king of Minangkabau and descendant

of Alexander, commissioned by God to expel the Dutch from Muslim lands.

He gained the support of thousands of dispossessed warriors Makassarese,

Bantenese, Malays and Minangkabaus to threaten Dutch interests in south

Sumatra and the Malacca Straits. The kings of Jambi and Palembang appeared

to support him, and even Dutch ally Amangkurat II invited him to Java for the holy war. The Dutch sent numerous expeditions against him which regained control of the major commercial centres by 1690, though they never found him in the Sumatran interior. The most frightening moment for the Dutch came in August 1689, when they discovered evidence that the

Muslim Ambonese Captain Jonker, their most trusted Indonesian lieutenant

in numerous past military campaigns, had joined the cult and made prepara

tions to massacre the Europeans of Batavia. The Dutch were merciless in pursuing him and his men to Kartasura, where Amangkurat II at first gave

them refuge, and made Jonker's gruesome death an example to other poten

tial rebels.

# New networks of the eighteenth century

If the gunpowder empires had been the main proponents of Islam in the period 1550 1650, the eighteenth century was a time when Muslim devotional

and scholarly life depended more on networks. The Dutch had demonstrated

that they were the single strong power remaining in the archipelago, though

Islam in South East Asia, 1500 1800

not in a position to rule directly as the Spanish did in their comparatively underpopulated islands. Military technologies also shifted, with the key weap

ons no longer the royal cannons that had terrified the elephants and pikemen

of an older generation of opponents. Muskets and soon the flintlock rifle became generalised everywhere in the islands (the Malay term for rifle, senapang, being derived from Dutch for flintlock), not only widely sold by English and Portuguese but also manufactured at centres in Sumatra, Borneo

and Bali. With this the military balance shifted to smaller networks of armed

individuals, who could evade the pressures the Dutch could mobilise against

maritime states.

While the multiethnic followers of Trunajaya and Ahmad Shah had dem onstrated these new possibilities, it was the Bugis who proved most adept in

the long term at utilising the new conditions. In particularly the commercially

minded Bugis of Wajo, having seen their senior partner and trade centre Makassar humbled by a Dutch Bugis alliance, and the subsequent Bugis world dominated by neighbouring rival Bone, perceived little virtue in strong

states. They developed an individualistic ethos approaching a doctrine of personal freedom (to travel, to gather, to speak, to own property) in their homeland, yet cooperated effectively outside their borders to establish new

port states. They particularly sought commercial bases in the sparsely popu

lated but strategic Peninsula, settling in the Selangor area in the late seven

teenth century.

Johor Riau entered a period of crisis when the last scion of the old Melaka

royal line was murdered in 1699. Both Minangkabau and Bugis adventurers

moved in to support conflicting sides, but by 1721 the Bugis were clearly on

top. They installed one of the Malay contenders as senior ruler (Yangdipertuan Besar), but one of their own, Daeng Marewa, became the

first junior king' (Yangdipertuan Muda) and effective ruler of the most successful polity of the Straits area. Its headquarters were now on the island of Bintan, just south of Singapore, conveniently situated to become a

hub for Chinese, Malay and Bugis trade. The most formidable of the Bugis

junior kings, Raja Haji, took the fight to the Dutch in 1783 4 in a spirit of Islamic revival sparked by another imminent hijra century (AH 1200 began in

1785 CE). He laid siege to Dutch Melaka before being killed by a strong fleet sent out for the purpose from Holland. Riau thereafter was better known as a centre of Malay scholarship than as a serious challenger to Dutch power.

Among the other networks which became effective in the eighteenth century were those originating in China and India. Following the massacre

467

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

of Chinese in Batavia in 1740, and the exclusion of further Chinese migration

to Manila soon thereafter, Chinese trade showed more inclination to support

smaller ports not controlled by Europeans. Among the Muslim ports which

benefited from this shift were Riau itself, Trengganu on the east coast of the

peninsula, Brunei (before its own attacks on the Chinese) and especially Sulu.

Sulu, situated on an island chain at the margins of Spanish, Dutch, British and

Chinese spheres of influence, became the archetype of the anti state or pirate

lair. The Spanish occasionally punished the Sulu capital, but its sultan was but

one of the chiefs in a very plural polity, never susceptible to indirect rule. Sulu

was able to become in the period 1760 1820 not only the gathering place for

sea produce for the Chinese market, but the largest slave market in South East

Asia, financing slave raids by its Illanun allies throughout the central Philippines and as far as Sumatra to the west. In this period the 'Moro scourge'

became embedded in the Filipino psyche, with the heritage of Spanish plays

about the reconquista of the peninsula being transplanted and indigenised into

the Philippine locale.

Indian traders from Gujarat, the Tamil area and Bengal had all been bring

ing their cotton cloth to supply the South East Asian markets since at least the

fifteenth century. In the seventeenth century the English, Dutch and Danish

companies realised they too could only do well in the South East Asian spice

trade if they brought Indian cloth for sale. Hence they established their collecting centres in each of the three areas and gradually came to dominate

the supply. Gujarati and Bengali ships had virtually ceased to come to South

East Asia by 1700, as we noted above, though individual cloth traders and

financiers from these communities were still active. It was the Tamil Muslims,

known locally as Chulias, who became the chief Indian Muslim presence in

South East Asia in the eighteenth century, sailing out of Sao Tome, Porto Novo and Cuddalore. Many became influential advisers and ministers for the

rulers of Aceh and the Peninsula.

The following chapter explains the new prominence of Hadrami networks in the eighteenth century, and their links with a number of states outside Java.

The Hadramis came in European or Indian ships, not their own, but made their way as financiers, investors, small traders and religious teachers.

sayyids among them were especially honoured as descendants of the Prophet.

Many were able to intermarry with the ruling families of Sumatra, Borneo and

the Peninsula, and their descendants even to become rulers in Aceh (from

1799) and Siak in Sumatra, Pontianak and Mempawa in west Borneo. Although

the earliest census of them was only in 1859, this suggested that the biggest

concentrations of Arabs were in Aceh and Palembang (1,764 in 1859),

468

Cambridge Histories Online © Cambridge University Press, 201 1

Islam in South East Asia, 1500 1800

Pontianak (800 in 1859), Banjarmasin and the colonial centres of Batavia and  $\,$ 

later Singapore. 45

Though less direct and state centred than the contacts of the sixteenth and

seventeenth centuries, these Arab networks played their part in re establishing

dialogue between South East Asia and the Arab world. The Palembang authors discussed in the next chapter, such as 'Abd al Samad al Palimbam,

began a new phase of reformist thinking that would influence the following centuries.

45 L. W. C. van den Berg, Le Hadhramaut et les colonies Arabes dans l'Archipel Indien (Batavia, 1886), pp. 108 9.

469

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

South-East Asian localisations of

Islam and participation within a global

umma, c. 1500 1800

#### R. MICHAEL FEENER

Situated as it is in geographic distance from the so called 'central lands' of

Islamicate civilisation in the Middle East, South East Asia has often been regarded by modern scholarship as an 'exceptional' case, with discussions

tending to focus on issues such as 'syncretism'. 1 While some of the forms that

Islamic thought and practice take in various parts of the region may be distinc

tive, however, it would be mistaken to assume from this that somehow the

religious texts and traditions of the region are necessarily 'less Islamic' than those

of Muslim societies in the Middle East, or that Islam was merely a 'thin, flaking

veneer' upon more solid foundations of Indie and local cultures. Often implicit

in such views are ahistorical and essentialised understandings of 'Islam' con

ceptualised in relation to a rather limited range of modern reformist conceptions

that persist across various academic fields, as well as in popular perceptions.

There are rich traditions of Islamic religious thought and practice through

out South East Asia, comprising a diverse array of local expressions. Mainland

Muslim communities, including Cham, Malay and other ethnic minority populations in what are today the nation states of Vietnam, Cambodia, Thailand and the Philippines have complex histories in which the mutual interaction of Islamicate, Indie and indigenous cultural forms have been dynamically negotiated. However, due to constraints of space, this chapter

will focus on developments in the Indonesian archipelago. This choice of focus

has been determined by the fact that the islands and adjacent Malay peninsula

have historically been home to the vast majority of Muslims in South East Asia, and because the bulk of the textual documentation for the history of Islam during the period originates from, or relates to, this area.

1 I would like to thank Nico Kaptein, Henk Maier, Tony Reid, Azyumardi Azra, Geoffrey

Wade, Michael Pearson, Jon Miksic and Barbara Andaya for their helpful comments on

an earlier draft of this chapter.

470

Cambridge Histories Online © Cambridge University Press, 201 1

## South East Asian localisations of Islam

This chapter provides an overview of Islam in the Indonesian archipelago during the early modern period that presents a balance to prevalent under

standings of the extent of localisation involved in the centuries long processes

of 'Islamisation' in the region by also highlighting the ways in which local Muslim populations came to actively participate in developments within the

wider world of Islam. As a complement to the material presented by Anthony

Reid in the preceding chapter on political and economic aspects of these social

transformations, these pages will focus on the ways in which developments in

local intellectual and cultural histories between 1500 and 1800 reflect local

isations of Islam in the region as well as the engaged involvement of South

East Asian Muslims within a global, cosmopolitan community of Islamic religious scholarship.

Early developments of Islamic religious thought and culture in South-East Asia

Scattered references in Chinese court chronicles and epigraphic evidence from

the region hint at the presence of Muslims in the ports of the Indonesian archipelago from the first centuries of Islamic history. However, it is not until

the end of the thirteenth century that we have reports of quantitatively significant local conversions to Islam, and then apparently only among the

political and mercantile elites of select maritime entrepots. During this same

period, we also have the earliest surviving evidence for the involvement of a

Sufi shaykh associated with South East Asia in the cosmopolitan scholarly

circles active in the Middle East. This comes in an Arabic language work of

Sufi historiography containing notices of one Abu c Abd Allah Mas c ud b. 'Abd

Allah aljawi. Al Jawi was a teacher in the Yemeni port of Aden who was highly regarded by his famous Arabian pupil 'Abd Allah b. As'ad al Yafi'i (d.

1367), the author of the work in which historical data on al Jawi first appears,

and a pivotal figure in the early development of the Qadiriyya Sufi order. 2

The Qadiriyya tradition came to have a lasting impact on the development

of South East Asian Islam, and is clearly reflected in one of the oldest surviving

works of a Muslim author from this region, Hamza Fansuri. Hamza hailed from the west Sumatran port of Barus, and a recent epigraphic discovery

2 For a discussion of the relevance of this source for understanding medieval Sufi con

nections between the Arabian peninsula and the Indonesian archipelago, see R. Michael

Feener and Michael F. Laffan, 'Sufi scents across the Indian Ocean: Yemeni haqiography

and the earliest history of Southeast Asian Islam', Archipel, 70 (2005), pp. 185 208.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

suggests that he died at Mecca in 1527. 3 His surviving poetry demonstrates

remarkable accomplishment in translating aspects of Sufi thought that were

first developed in the Middle East into an evocative symbolic vocabulary forged in an Islamicised idiom of Malay and composed in a new genre that

came to be known as syair:

Listen, young reciter of the Qur'an,

Do not look too far afield

Passing by the water unwittingly . . .

The whale is casting about In the ocean in search of water. Yet the sea is clearly manifest To the pious and the profligate. 4

Like al Jawi's student al Yafi'i before him, Hamza combined affiliations with

the way of [ Abd al Qadir Jilani with an affinity for the cosmological concep

tions of the thirteenth century Andalusian mystic Ibn al 'Arab!. 5 Energetic

debates over the interpretation of the latter's writings were to comprise a

significant part of the broader developments in Islamic learning and literature

in South East Asia over the centuries that followed.

Following the Mongol conquest of Baghdad and the formal end of the 'Abbasid caliphate in the thirteenth century, Muslim trading networks across

the Indian Ocean linking the Middle East with South East Asia expanded

dramatically. By the fifteenth century, a number of the heretofore small and

often temporary populations of Muslim migrants from South Asia and the Middle East settled in various South East Asian ports were evolving into significant local Muslim communities. The processes through which such changes came about were complex and involved specific local considerations

on the part of both indigenous populations and immigrant Muslims, including

shared economic interests, the building of political alliances and patterns of

intermarriage. These developments led to the establishment of regional centres in which a range of local Muslim cultures emerged and from which

elements of their respective 'styles' of Islam spread to other areas of the archipelago. Some of the ways in which the acceptance of Islam was

3 Claude Guillot and Ludvik Kalus, 'La stele funeraire de Hamzah Fansuri', Archipel, 60 (2000), pp. 3 24.

4 G. W.J. Drewes and L. F. Brakel (eds.), The poems of Hamzah Fansuri (Dordrecht, 1986),

Malay text, p. 140. Unless otherwise credited all translations in this chapter are my own.

5 Alexander Knysh, Ibn 'Arabi in the later Islamic tradition: The making of a polemical image in medieval Islam (Albany, 1999), pp. 118 19.

472

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

conceptualised in such contexts can be traced through the development of

local traditions of Islamic learning during the sixteenth and seventeenth centuries.

For example, one text from the period of transition to Islam on Java demonstrates an extensive engagement with broader Islamic conversations

about the definition of confessional and communal boundaries:

It is unbelief when people involved in a lawsuit and invited to settle the dispute according to the law of Islam, refuse to do so and insist on taking it to

an infidel judge. Likewise it is unbelief to dress like an infidel and to speak

highly of these clothes ... It is unbelief to say, 'Which is the better religion,

Islam or the religion of the Javanese?' It is a pious act to give definite precepts

with regard to eating and drinking. It is unbelief to praise a particular idol,

maintaining that it is powerful; all this provided one was warned against it. 7

The dynamics of working out such redefinitions of religion and society has

been described by Marshall Hodgson as the 'naturalization of Islam' in South

East Asia. Such a vision of the complex, and by no means teleological, negotiations between broad ranges of imported religious ideas and practices

as well as myriad local traditions provides a useful heuristic for appreciating

the ways in which the Indonesian archipelago came to be one of the most populous and dynamic lands of Islam over the past six centuries.

One important factor in this was the role played by an evolving canon of Arabic texts that both linked local scholars to discussions current in the broader Muslim world and provided the basis for emerging bodies of vernac

ular Islamic scholarship. By at least the sixteenth century, Islamic religious

texts in Arabic were being translated and adapted into South East Asian languages, early examples of which in Malay appear to date from the late sixteenth century in the form of vernacular adaptations of the creed of al Nasafi (d. 1142), and the 'Mantle' poem (Burda) in praise of the Prophet by

al Busiri (d. 1296). The oldest surviving examples of analogous developments

in Javanese date from a few decades earlier in the sixteenth century and draw

considerably upon the works of al Ghazali (d. mi). The sharp critiques of

For richly illustrated introductions to local Islamicate manuscript traditions in the Arabic,

Malay, Javanese, Acehnese, Sundanese, Sasak, Bugis and Makassarese languages, see Ann

Kumar and John H. McGlynn (eds.), Illuminations: The writing traditions of Indonesia

(Jakarta, 1996).

G. W.J. Drewes (ed. and trans.), An early Javanese code of Muslim ethics (The Hague, 1978),

P-37-

Marshall G. S. Hodgson, The venture of Islam: Conscience and history in a world civilization

(Chicago, 1974), vol. II, p. 548.

473

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

established local practices elaborated in such texts point to the fact that during

this period Islam was by no means the dominant paradigm in all sectors of

society. At the same time, however, these works and other surviving examples

from early stages in the development of Islamic learning in the archipelago all

draw on the same scholarly and Sufi authorities recognised by Muslims all

across the Middle East, Africa and Asia during this period. This aspect of such

works attests to the extent to which a literate Muslim elite in South East Asia

had become participants in a broader Islamicate oecumene during that period.

The primary texts referenced in these far flung scholarly circles were in Arabic, the language of the Qur'an and the pre eminent medium of estab lished religious learning in medieval Islam. However, participation in such

discourses did not necessarily involve Arabisation' in the sense of non Arab

writers necessarily having to abandon vernacular languages and literary traditions upon their conversion to Islam. In fact, beginning with the Persian renaissance of the tenth century, the spread of Islam beyond the Arabian peninsula stimulated the reinvigoration of and new formulations of

a number of languages from vastly different linguistic families. By the early

modern period, for example, there is evidence of remarkable developments

in Islamicate forms of languages ranging from Bantu derived Swahili to Indo European Urdu, Dravidian Tamil, Altaic Turkic and a number of Austronesian languages in the Indonesian archipelago. Such transformations

of these diverse traditions often involved both the incorporation of a consid

erable body of Arabic vocabulary, and the adaptation of some modified form

of the Arabic script.

Tracking such developments in South East Asia from the sixteenth through

the eighteenth centuries opens up vistas on to a vivid mosaic of vernacular

styles of Muslim cultural expression, including those articulated in languages

including Malay, Javanese, Bugis and Makassarese. The pages that follow will

introduce aspects of these diverse forms of Muslim culture in discussions focused upon developments in different geographic areas, as well as in relation

to broader regional patterns associated with the diffusion of Malay Muslim

culture and Arabic textual traditions across the archipelago. In reading through them it should be kept in mind that these various 'styles' of Islamic

expression were by no means self contained systems and in fact interacted

with each other in dynamic ways over extended periods of time. Over the course of the seventeenth century, for example, a number of Javanese Islamic

texts were adapted from Malay models, and a renowned Makassarese Sufi

shaykh established himself as a prominent figure at the court of the sultanate

of Banten. The rubrics employed in the following sections are thus intended

474

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

only as one means of attempting to conceptualise the array of modalities through which Islam took root in the region. 9

Pesisir and palace developments of Javanese-Islamicate culture

Over the fifteenth and sixteenth centuries, a distinct style of regional Islamicate culture developed on the north Java coast (pesisir) in which ele

ments from the traditions of Muslim South Asia and the Middle East, as well as

from China and diverse areas of the Indonesian archipelago combined with

local traditions to form new, cosmopolitan cultural patterns among the merchant elite of what was at that time a dynamic maritime borderland of

Muslim expansion. The early history of translating in the most literal sense

Islamic teachings into a Javanese cultural milieu can be seen in surviving manuscripts that contain religious texts in Arabic, accompanied by interlinear

glosses in Javanese. 10 It is texts of this type that provide some of our best.

evidence for the early stages of the 'Islamisation' of Java, and the 'localisation

of Islam' there.

In popular understandings, the early Islamisation of Java is often attributed

to the work of nine saints, known in Javanese as the wali sanga. Reliable historical documentation of their lives and work remains elusive.

Nevertheless, local traditions circulating since at least the nineteenth century

are rich with narratives describing the ways in which the wali sanga were

believed to have won local populations over to Islam through their skilful manipulation of Javanese cultural forms. This appears all the more remarkable

given that in popular imaginings of the wali sanga only one of them Sunan

Kalijaga is regarded as being 'Javanese', the other eight being ascribed 'foreign' origins spanning the Muslim world from North Africa and Iran to Champa and China.

The Dutch scholar of Javanese literature Th. Pigeaud once suggested that the Islamicising agendas of the wali sanga 'loosened an ancient bond of

sacral secrecy and secularized several elements of pre Islamic religious ritual. In consequence some ancient religious texts may have developed into

9 The importance of examining 'modalities' of Islamisation in South East Asia was first

highlighted by A. H.Johns in 'Islam in Southeast Asia: Reflections and new directions',

Indonesia, 19 (1975), p. 34.

10 See T. E. Behrend, 'Textual gateways: The Javanese manuscript tradition', in Kumar and McGlynn (eds.), Illuminations, p. 165.

475

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

semi profane or popular literature.' 11 That is, he argues that as established

religious traditions gave way to Islam, the boundaries of esoteric exclusivism

constructed around cultural forms that may have once been the sacred preserve of a royal or religious elite crumbled. This in turn could make mass, rather than restricted, participation in or emulation of those forms of

aesthetic expression possible.

Popular histories of various Javanese cultural art forms would appear to corroborate such an impression, with legendary narratives telling, for exam

pie, of the carving of a set of wooden masks for the wayang topeng dance dramas by Sunan Kalijaga (one of the wait sanga), 12 and attributing stylistic

shifts in the appearance of wayang kulit shadow puppets to the work of another

of the walls, Sunan Giri. 13 Later Javanese literary works such as the early

nineteenth century Serat Centhini 14 emphasise the harmony of Islam with local

cultural expression through images such as the 'marriage' of the traditional

gamelan percussion orchestra with Islamic religious knowledge (ngebnu): 'the

sound of the dhikr prayer is analogous with the clanging of gamelan instru

ments'. 15 Elsewhere, the physical arrangement of a shadow puppet (wavang)

performance is used as an analogy to describe a form of Sufi cosmology:

Kidang Wiracapa spoke slowly, 'Younger brother Kulawirya, regarding per

fection of insight, the deeper meaning of the wayang, the inner reality: the

perfect person makes this into a symbol, an indication of God. He gives dalang

[puppeteer] and wayang their true place [meaning] as depictions of the various

ways in which God acts. He makes this comparison: "the screen is the visible

world. The wayang puppets which are set up to either side of the screen are

ii Th. Pigeaud, Literature of Java (The Hague, 1967), vol. I, p. 93.

12 Soedarsono, Wayang wong: The state ritual danee drama in tfte court of Yogyakarta (Yogyakarta, 1990), p. 13.

13 James R. Brandon (ed.), On thrones of gold: Three Javanese shadow plays (Honolulu, 1993), p. 6.

14 This encyclopaedic work is thought to have originated from east Javanese pesisir

tradition and consists of a series of religious instructions alternating with elaborate

accounts of the amorous adventures of wandering Muslim students descended from one

of the wali sanga. The current recension of the text dates from the early nineteenth

century, but appears to be based on an older, now lost, suluk. Pigeaud, Literature of Java,

vol. I, p. 229. For a condensed presentation of this work's contents in both Romanised

Javanese and a modern Indonesian translation, see Sumahatmaka, Ringkasan Centini

Suluk Tambanglaras (Jakarta, 1981). A very helpful Dutch summary of the work is also

available: Th. Pigeaud, 'De Serat Tjabolang en de Serat Tjentini: Inhoudsopgaven',

Verhandelingen van het Bataviaasch Genootschap, 72, 2 (1933). Some of its Islamic religious

content is discussed in Soebardi, 'Santri religious elements as reflected in the book of

Tjentini', Bijdragen tot de Taal , Land en Volkenkunde, 127 (1971), pp. 331 49.

15 Trans, in Sumarsam, Gamelan: Cultural interaction and musical development in central Java (Chicago, 1995), p. 24.

476

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

the categories of God's creatures. The banana trunk (into which the puppets

are stuck) is the earth. The blencong [oil lamp] is the lamp of life." 16

However, nearly all such texts are of comparatively recent provenance, and

tell us more about evolving local understandings of the role of Islam in Javanese society during the early modern period than they do of earlier historical developments.

Another popular genre of Muslim literature and performance in the archi pelago can be traced to significantly earlier: the Menak epic of narratives concerning the Prophet's kinsman Amir Hamza, and its related story cycles.

Its Javanese forms appear to combine characters and events apparently known

through Malay texts with established local literary forms such as that of Pafiji

tales. 17 Developing first on the north coast of Java in the sixteenth century, the

Menak later became known in Sundanese areas of west Java, where Menak

stories were performed with three dimensional rod puppets (wayang golek) in

a form of theatre whose invention has been popularly ascribed to another one

of the wall sanga, Sunan Kudus. As Javanese forms of Islam spread east to the

island of Lombok, analogous developments also took place there, with Menak

stories coming to serve as the foundation for the traditional repertoire of the

local form of shadow puppet theatre (wayang Sasak).

Other heroes from Islamic sacred history were also incorporated into Javanese literature in the seventeenth and eighteenth centuries. For example,

adaptations of Malay narratives themselves based on elements of the extensive Arabic and Persian literatures of 'stories of the prophets' (qisas al

anbiya) became popular in Javanese works referred to as Serat Anbiya and

Tapel Adam. 1 However, perhaps the most elaborate treatment in Javanese of

any Islamic prophet other than Muhammad can be found in textual traditions

associated with Yusuf (Joseph). Throughout the seventeenth, eighteenth and

early nineteenth centuries the courts of several Javanese sultans commis

sioned versions of the Serat Yusup, which was believed to be a work of particular supernatural potency. 19 These Javanese verse narratives of

16 P.J. Zoetmulder, Pantheism and monism in Javanese suluk literature: Islamic and Indian

mysticism in an Indonesian setting, ed. and trans. M. C. Ricklefs (Leiden, 1995), p. 245.

17 Pigeaud, Literature of Java, vol. I, p. 213. For a short introduction to the Pafiji tale genre,

see S. O. Robson, Wanban Wideya: A Javanese Pafiji romance (The Hague, 1971), pp. 11 15.

18 Pigeaud, Literature of Java, vol. I, pp. 130 1.

19 M. C. Ricklefs has called attention to the importance of these royal copies of Serat Yusup

and two other Javanese Islamic texts (the Carita Sultan Iskandar and the Kitab Usulbiyali)

for the perceived religious and political authority of Javanese rulers since the reign of

Sultan Agung. M. C. Ricklefs, Mystic synthesis in Java: A history of Islamization from the

fourteenth to tfte early nineteenth centuries (Norwalk, CT, 2005), passim.

477

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Joseph's near seduction and eventual vindication became incorporated into

elaborate contexts of ritual recitation in Java and Madura, some of which have

continued to be practised through the end of the twentieth century.

Alongside such literary narratives, however, Javanese textual production continued to adapt treatises in the technical Islamic religious sciences from

Arabic during this period. One of the most influential such adaptations in the

seventeenth century was based upon the work of the contemporary South Asian Sufi Muhammad b. Fadl Allah al Burhanpuri (d. 1620) entitled, al Tuhfa

al mursala ila ruh al nabi. This Arabic text was composed in Gujarat in 1590, and

soon thereafter began to make its impact in the Indonesian archipelago through a Javanese verse rendering, 2,0 as well as through the media of Malay

and Arabic language works produced by the Acehnese Sufi Shams al Dm Pasal. 21 Muslims across South East Asia were attracted to al Burhanpuri's

'seven grade' model of Sufi cosmology in the seventeenth century, and on the

island of Buton Sultan Dayanu Ihsan a'Din (r. 1598 1631) even used elements

of its symbolism to elaborate the ranking of official offices in the state structure of his realm.

Aside from systematic treatises, Javanese literary expressions of Sufism were also expressed in poetry, particularly in a verse genre known as suluk

composed in metres facilitating performative recitation. Suluk appear as an

increasingly popular literary form from the seventeenth century when these

mystical poems were apparently sung, sometimes perhaps even to the accom

paniment of music and dance. 22 Some suluk deal specifically with the wali

sanga and their teachings, or with other prominent Javanese mystical figures,

including controversial mystical teachers such as Seh Siti Jenar and Sunan

Panggung, who were executed by decree of religious councils in order to prevent (apparently unsuccessfully) the dissemination of their potentially disruptive doctrines. 23 Alongside such distinctively Javanese tropes, however,

other suluk texts reveal a deep involvement with systematic Arabic grammar

and its technical terminology. 24 Suluk were composed and performed in court

circles of some Javanese sultanates including Cirebon (west Java) in the eighteenth century, and became popular in the interior as well as on the

20 A. H. Johns, The gift addressed to the spirit of the Prophet (Canberra, 1964).

21 Published editions of some of these texts, along with critical apparatus and some partial

Dutch translations, can be found in C. A. O. van Nieuwenhuijze, Samsu'l Din van Pasai:

Bijdrage tot de Kennis der Sumatraansehe Mystiek (Leiden, 1945), pp. 245 406.

22 Pigeaud, Literature of Java, vol. I, p. 85.

23 G. W.J. Drewes, 'Het Document uit den Brandstapel', Djdwd, 2 (1927), pp. 97 109.

24 G.W.J. Drewes, 'Javanese poems dealing with or attributed to the saint of Bonan',

Bijdragen tot de Taal, Land en Volkenkunde, 124 (1968), pp. 209 40.

478

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

coast (pesisir). The move inland reflected a significant shift in Javanese Muslim

history following the decline of the coastal empire of Demak and the rise of

the Javanese agrarian Muslim kingdom of Mataram in the latter half of the

sixteenth century.

The construction of a Javanese Muslim identity for Mataram was most energetically developed during the reign of Agung (r. 1613 46). This arche

typical ruler of Muslim Java is most often referred to as Sultan Agung, the title

received in 1641 in response to a request that he had sent with a delegation to

Mecca. The taking of this Arabic title, however, is only one aspect of the ways

in which Agung pursued his agenda of Islamising Java (and Javanising Islam).

In 1633 he inaugurated the hybrid Saka calendrical system that continued the

established Indie Javanese practice of counting its 'year one ' from 78 CE;

however, from the year of Sultan Agung's decree forward each subsequent

year was reckoned according to the strictly lunar months of the Islamic hijri

calendar. 25 Another example of the ways in which Sultan Agung worked to

both Islamicise local traditions and to Javanise Islam can be seen in his mystical

'marriage' to Ratu Kidul, the 'Goddess of the Southern Ocean' from indige

nous Javanese tradition. As M. C. Ricklefs has recently argued, through his

deft manipulation of multiple symbolic idioms, Agung managed to cast a lasting image of himself as simultaneously, 'the lover of the distinctly non Islamic Javanese deity Ratu Kidul, as a monarch with supernatural powers,

and as a pious Muslim'. 2

Complex adjustments of universal Islamic religious ideas and traditional Javanese cultural institutions have been characteristic of Muslim history in the

region ever since. However, when trying to understand such long term processes of Islamisation it must be kept in the mind that the model is not

one of teleological progression towards some 'essential' perfection of Islam

imagined in terms of present dominant conceptions of orthodoxy. Rather, historical developments actually reveal more of a pattern of flux, as has been

evocatively demonstrated by Ricklefs in his history of Javanese Islam during

the reign of Pakubuwana II (1726 49). 27

In this way distinctly 'Javanese' expressions of Islam developed in dynamic

interaction with surrounding Muslim cultures. At different periods between

the sixteenth and eighteenth centuries, different forms of Javanese Muslim

25 H.J. de Graaf and Theodore G. Th. Pigeaud, Islamic states injava, yoo 1700 (The Hague, 1976), pp. 9 23, 45-

26 Ricklefs, Mystic synthesis injava, p. 35.

27 M. C. Ricklefs, Seen and unseen worlds injava: History, literature, and Islam in the court of Pakuhuwana II, 1726 1749 (Honolulu, 1998).

479

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

tradition had variously influenced, and been influenced by, the development

of other regional Islamicate cultures in surrounding areas, including the sultanate of Banten, the Muslim communities of Lombok and especially the

archipelagic networks of Malay Muslim culture. Even in such distant eastern

reaches of the archipelago as Maluku (the Moluccas), elements of Javanese

Muslim culture interacted with models of Malay practice, Middle Eastern influences and indigenous traditions in the formation of new local styles of

Islam at the courts of the sultanates of Ternate and Tidore. 2

# South Sulawesi styles of Islam

One of the other major modes of Islamicate cultural patterning that came to

be influential in the eastern half of the archipelago was that which was first

developed in Makassar, located on the south western tip of Sulawesi. There

the ruler of Gowa formally converted to Islam in the early seventeenth century, and soon thereafter launched a series of campaigns of military conquest and religious conversion towards the surrounding Bugis states long the most prominent local ethnic rivals of the Makassarese on the island. 29

In less than two decades, Makassar established itself as a powerful Muslim

sultanate in south Sulawesi and thence continued its campaigns of expansion

to other islands, most notably to Sumbawa. 30 The style of Islam that emerged

there in the sultanate of Bima over the centuries following these conquests

reflects Makassarese as well as Malay and Javanese models in matters ranging

from court regalia and literary traditions to the design of Muslim burial markers. 31

Local historiographic traditions credit three Malay Muslim preachers from

west Sumatra with the conversion of Gowa's king, but in south Sulawesi, as

elsewhere across the Muslim world, Islam came to take on its own distinctive

28 Leonard Y. Andaya, The world of Maluku: Eastern Indonesia in the early modern period (Honolulu, 1993).

 $29\ J.$  Noorduyn, 'De Islamisering van Makassar', Bijdragen tot de Taal , Land en

Volkenkunde, 112, 3 (1956), pp. 247 66.

30 J. Noorduyn, 'Makassar and the Islamization of Bima', Bijdragen tot de Taal Land en

Volkenkunde, 142, 23 (1987), pp. 31242.

31 Many other factors and cultural influences have been present in this eastern Indonesian

state since the seventeenth century, including Chinese and European. For a concise

overview of the cosmopolitan character of Bima, see Henri Chambert Loir, 'Etat, cite,

commerce: Le cas de Bima', Archivel, 37 (1989), pp. 83 105. Confluences of models from

Makassarese and Malay literary traditions can be found in one of Bima's distinctive

Malay language literary productions of the seventeenth and eighteenth centuries,

known as Kitab Bo'.

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

local forms. As local populations came to identify as Muslims, teachings based

upon the Qur'an and the sunna, as well as the works of Muslim scholars and

Sufis, were transmitted in verse forms that were adapted from poetic genres

with traditions of public performance well established before the Islamisation

of the Makassarese and Bugis cultural areas. Examples of this can be found in

works such as the Bugis poem Surek Pangngajakna Nabita Muhammad nennia

Abdul Ibadi, which opens:

This is advice for the wise man of learning,

Expert in the science offigh and

Master of the mystics.

A man of exemplary behaviour,

A man of pure heart,

Who implements the Shari'a and

Undertakes the discipline of the Sufi way. 32

This text was originally recorded in what is commonly referred to as the lontarak script, because it was used on palm leaves (bntarak). Before the

coming of Islam to this part of the archipelago, the two major languages of

south Sulawesi Makassarese and Bugis had well developed literary traditions, including texts in a number of genres written in local forms of a syllabic

script. 33 In the seventeenth and eighteenth centuries, this literature came to be

supplemented with works in the Islamic religious sciences including Qur'anic

translation and exegesis written in this script. However as with Javanese and

other South East Asian languages of this period, Islamic religious works and

other texts in the Makassarese and Bugis languages also came to be recorded

using a modified form of the Arabic script. In addition to this we find a rather

unusual development in south Sulawesi of an alternative 'cipher script', based

upon the forms of Arabic numerals, that was used to record some extant texts

of Bugis poetry. 34

Among Muslim scholarly circles in south Sulawesi, a more straightforward

adaptation of the Arabic script was more commonly used for certain kinds of

Bugis and Makassarese texts in the seventeenth century. William Cummings

has made a valuable contribution to our understandings of the symbolic, ritual

32 Abdul Kadir Mulya (ed. and trans.), Surek Pangngajakna Nabita Muhammad SAW nennia

Abdul lbadi (Jakarta, 1991), p. 1. This edition includes a translation of the Bugis poem into Indonesian.

33 Samples can be seen in B. F. Matthes (ed.), Makassaarsche Chrestomathie (Amsterdam, 1883).

34 B. F. Matthes, Eenige Proeven van Boegineesche en Makassaarsche Poezie (The Hague, 1883), p. 20.

# The New Cambridge History of Islam

and institutional significances of the outward forms of Arabic script texts in the

history of Makassarese Islam. 35 Aside from these important aspects relating to

their 'outsides' as artefacts, the actual contents of some such writings were

also significant in local understandings and implementations of Islamic reli

gious teachings in south Sulawesi.

This is evidenced, for example, during the reign of Sultan La Maddaremmeng in the Bugis state of Bone (r. 1631 44), who enacted a sweeping new legal order appealing to the sharfa in prohibiting pre Islamic

religious practices, attempting to abolish the traditional 'third gender' bissu

priesthood and emancipating slaves. 36 Alongside these sharfa oriented reforms, Sufi texts and practices also underwent a period of extensive develop

ment in south Sulawesi during the seventeenth century. Around 1620, an Arab

sayyid namedjalal al Din al 'Aydid settled in the Makassarese town of Cikoang

to begin teaching, alongside fiqh, a way of Sufism that became known locally

as the tariqa bahr al nurF Al Aydid's most famous student at Cikoang was an

associate of the royal house of Gowa who came to be known as Shaykh Yusuf

'Taj al Khalwati' al Magassari (d. 1699).

After completing his introductory studies in south Sulawesi, Yusuf pursued

more advanced studies of Islam in Banten, west Java (discussed below) and

thence on to major centres of learning in Yemen, the Hijaz and Syria. Much

of al Maqassari's studies were concentrated in Sufism as he was initiated into the Qadiriyya, Naqshbandiyya and Shattariyya tartqas. In Damascus he

was elevated to become a master of the Khalwatiyya Sufi order. 38 After two

decades of study in the Middle East, al Maqassari returned to the Indonesian

archipelago in 1664, settling not in his native south Sulawesi, but rather in

Banten, where he was attracted by the patronage of Sultan Ageng Tirtayasa.

There he composed the Sufi manual Zubdat al asrar ft tahqiq ba'A masharib

al akhyar and other works in Arabic. 39 However, his mode of Sufism was not that which is often imagined as typical of pre modern South East Asian

Islam no spiritualist syncretism facilitating concessions to indigenous or

35 William Cummings, 'Scripting Islamization: Arabic texts in early modern Makassar',

Ethnohistory, 48, 4 (2001), pp. 559 86.

36 Christian Pelras, 'Religion, tradition, and the dynamics of Islamization in south

Sulawesi', Archipel, 30 (1985), p. 124.

37 G. Harmonic, 'Le fete de grand Maulid a Cikoang: Traces d'influence SM'ite en Pays

Makassar', Papers from the III European Colloquium on Malay and Indonesian Studies

(Naples, 1988), pp. 95 107.

38 al Maqassari, Safrnat al naja in Tudjimah (ed.), Syekh Yusuf Makassar: Riwayat dan Ajarannya (Jakarta, 1997), pp. 194 204.

39 Nabilah Lubis, Syekh Yusuf Al Taj Al Makassari Menyingkap Intisari Segala Rahasia

(Bandung, 1996), Arabic text pp. 72 126.

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

Hindu Buddhist religious practices. As expressed in a letter attributed to al

Maqassari addressed to the sultan c Abd al Hamid Karaeng Karangreng of

Makassar, 'Our way is the tariqa of those Sufis who hold fast to the Qur ] an

and surma. Whoever does not adhere strictly to the Qur'an and surma have

strayed from the true and praiseworthy path.' 40

During the years al Maqassari spent in Banten, the Dutch East India Company (VOC) was growing increasingly wary of the potential for char ismatic teachers returning from the Middle East to disrupt Dutch designs for

control of the archipelago. In 1664 the VOC refused to allow the landing of

three returning Bugis 'Hajjis' and transported them to exile at the Cape of

Good Hope, arguing that they would become a disruptive influence among

the Muslims of the East Indies. 41 Eventually al Maqassari found himself in

conflict with the Dutch in Banten when he rallied to the support of Sultan Ageng Tirtayasa against the encroachments of the Dutch East India Company

in 1682. After leading a local resistance movement for nearly two years, al Maqassari was captured by the Dutch, and exiled to the VOC ougjost in Sri Lanka. Al Maqassari continued to compose Arabic works on Sufism there,

'in that place famous by the name of Sarandib, a foreign land and place of exile

for insurgents'. 42.

From his Sri Lankan exile al Maqassari also used his pen to continue advocating resistance against the Dutch via correspondence with the Muslim communities of the archipelago at a time when opposition to European incursion into the region was increasingly expressed in an Islamic

idiom. In 1685, the Minangkabau leader Ahmad Shah Ibn Iskandar was engaging his co religionists from other regions of Sumatra, the Malay pen

insula and even Makassar to join in his crusade against the 'un believing' Europeans. 43 Such developments drove the Dutch to an increasingly active

surveillance of communications between local Muslim communities, 44 and in

40 Tudjimah (ed.), Syekh Yusuf, p. 189. This Arabic document is preserved in an eighteenth century manuscript compilation from Makassar; however, the precise

dating of this

particular letter is problematic as it both purports to have been written in Banten, and

mentions Sri Lanka and one of the Sufi texts that al Maqassari is reported to have

written there (Sajmat al najd).

41 J. Vredenbregt, 'The Hadjdj: Some of its features and functions in Indonesia', Bijdragen

tot de Taal, Land en Volkenkunde, 118 (1962), p. 96.

42 al Minhat al Sayldniyya fi'l minhat al rahmaniyya, in Tudjimah (ed.), Syekh Yusuf, p. 205.

43 J. Kathirifhamby Wells, 'Ahmad Shah Ibn Iskandar and the late 17th century "holy war"

in Indonesia', Journal of the Malay Branch of the Royal Asiatic Society, 43, 1 (1970), pp. 54 5.

44 On the contemporary Dutch reactions to similar 'subversive messages' circulating

among Muslim courts in west Sumatra, see Jane Drakard, A kingdom of words:

Language and power in Sumatra (Selangor, 1999), pp. 182 92.

483

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

1693 some of al Maqassari's missives were intercepted by the VOC. In an attempt to remove him from the lines of communication maintained by Muslim scholars and pilgrims between Arabia and the Indonesian archipelago,

al Maqassari was re exiled to the Cape of Good Hope where he remained until

his death in 1699, becoming a founding figure of the Muslim community in

South Africa. 45

Banten: Islamic scholarship and state institutions

The career of Shaykh Yusuf al Maqassari provides a dramatic view of the interactions between various parts of the Indonesian archipelago and the wider Muslim world. References to teachers and places deployed throughout

his Arabic writings detail his links with prominent scholars all across the Muslim world, as well as with emerging regional centres of Muslim culture

in South East Asia such as the west Javanese sultanate of Banten. That area had

previously been under the control of the Hindu state of Pajajaran until its major port, Sunda Kelapa, was captured by Sunan Gunung Jati, who estab

lished his son Hasan al Dm as sultan in 1527. Over the sixteenth century this

western end of the Javanese coast was increasingly integrated into the rapidly

developing maritime Muslim culture of the region, emerging as an important

centre for trade, politics and religion.

The lucrative pepper trade passing through this port on the Sunda Straits provided revenues to support the patronage of Islamic learning and culture

Hasan al Din laid out a new capital alongjavanese lines, transforming a holy

site previously venerated by Hindus into a destination of Muslim pilgrimage

and the seat of his throne. He also used his resources to attract foreign Muslim scholars to his realm, increasing its prestige and strengthening connections between this South East Asian state and Muslim centres in the

Middle East.

In 1630, Banten sent an embassy to Mecca that carried copies of controver

sial Sufi texts written in Malay along with a request to the sharif that he send a

Meccan scholar to Banten in order to provide guidance on Islamic learning

there. 46 Over the decades that followed, Banten experimented with a range of

45 He has remained an important figure in the historical memory of Muslims on both ends

of the Indian Ocean littoral. For an overview of his importance in modern Indonesia, see

R. Michael Feener, 'Shaykh Yusuf and the appreciation of Muslim 'saints' in modern

Indonesia', Journal for Islamic Studies, 18 (1999), pp. 112 31.

46 Sejarah Banten, Canto 37. Cited in Drewes and Brakel (eds.), Poems ofHamzah Fansuri, p. 11.

484

Cambridge Histories Online © Cambridge University Press, 201 1

## South East Asian localisations of Islam

ideas and institutions as it sought to define itself in relation to a broader Muslim umma. Sultan Ageng Tirtayasa (r. 1651 82), friend and patron of al

Maqassari, encouraged the establishment of such formal indicators of Islamic

identity as the prohibition of opium and the adoption of what were considered

to be 'Arab' forms of dress. State sponsorship of Islam in the Banten sultanate

included the founding of the mosque school at Kasunyatan as well as the establishment of the office of Pakih Najmuddin which served as both the chief

qddi and a major political adviser to the sultan. 47 Such developments in Banten

can be seen as reflecting broader trends throughout the archipelago during

this period in which several local rulers made it a point of policy to cast local

rule in the idiom of the shaifa.

# Malay Muslim religious and literary cultures

The origins of a Malay 'style' of Islam stretch back to the late thirteenth century when the ruler of the north Sumatran port of Samudera Pasai con

verted to Islam. In the centuries that followed its influence spread to other

centres in the region and it continued to serve, symbolically at least, as a point

of authoritative reference for later Malay Muslim communities. 48 This was particularly the case for the 'Malay' port of Melaka whose rulers first accepted Islam during the fifteenth century. This cosmopolitan port city located at a key point on the straits between Sumatra and the Malay peninsula

became a thriving hub of commerce, in which Muslims from all around the Indian Ocean rim and beyond came together with non Muslims from all across Asia and Africa in exchanges of ideas and social practices, as well as commercial goods. Among the polyglot merchant population of the port in the early sixteenth century, the Portuguese Tome Pires listed:

Moors from Cairo, Mecca, Aden, Abyssinians, men of Kilwa, Malinidi, Ormuz, Parsees, Rumes, Turks, Turkomans, Christian Armenians, Gujeratees ... Merchants from Orissa, Ceylon, Bengal, Arakan, Pegu, Siamese, men of Kedah, Malays, men of Pahang, Patani, Cambodia, Champa, Cochin China, Chinese ... Moluccas, Banda, Bima, Timor, Madura, Java, Sunda, Palembang, Jambi . . . Pase, Pedir, [and the] Maldives. 49

47 Martin van Bruinessen, 'Shari'a court, tarekat and pesantren: Religious institutions in the Banten sultanate', Archipel, 50 (1995), pp. 165 200.

48 R. Roolvink, 'The Answer of Pasai', Journal of the Malay Branch of the Royal Asiatic Society, 38, 2 (1965), pp. 129 39-

49 Armando Cortesao (trans.), The Suma oriental of Tome Pires (London, 1944), p. 268.

485

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

A number of the male Muslim merchants in Melaka apparently married local

women in port, and the children of such unions were often polyglot pioneers

of Islamic expansion into other ports across the region. Elements from all these various streams of Islamicate civilisation came together with others from China and diverse local traditions of the archipelago in contributing to

the development of a new Malay Muslim culture.

This included not only the formation of a language of communication, study and trade, but also of evolving Malay Muslim styles of dress, diet, court

ceremonial, literary tastes and conceptions of gender roles in society. 50 The

new Malay Muslim cultural forms developed at Melaka spread throughout

large areas of South East Asia, and in the process the Malay language came to

serve as a medium of Muslim learning to a number of nascent Muslim communities across the region. In fact, many of the other Islamicate literary

traditions of the archipelago, ranging from Javanese to Makassarese, as well as

the Cham Muslim texts produced on the mainland, developed rich traditions

of adapting religious and literary works from Malay into local languages and genres.

The Malay Muslim religious and cultural superstratum tied such geograph

ically distant and ethnically distinct areas as northern Sumatra, Patani (now

southern Thailand), coastal Kalimantan (Borneo), Java and the 'Spice Islands'

of Maluku into a cosmopolitan network of trade, travel and religious scholar

ship. The spread and diffusion of Melaka's Malay Islamicate culture even accelerated after the Portuguese conquest of that important trading port in

1511, which scattered elements of its Muslim community throughout the region. Over the century that followed their ways of speaking, patterns of social behaviour, styles of dress and eating habits, court ceremonial and religious practices the building blocks of a Malay Islamicate culture were further dispersed to coastal centres around the archipelago, several of which

evolved into regional sultanates over the course of the seventeenth and eighteenth centuries.

Koster has characterised the common identity of 'Malayness' expressed in

these settings as predicated upon a constellation of shared political concepts,

customs and rituals, and the religion of Islam as well as a common language

and textual tradition that linked under a cultural rubric the disparate petty

50 For more on the last of these cultural transformations, see Barbara Waston Andaya,

'Delineating female space: Seclusion and the state in pre modern island Southeast Asia',

in Barbara Waston Andaya, Other pasts: Women, gender and history in early modem

Southeast Asia (Honolulu, 2000), pp. 231 53.

486

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

sultanates of the region. 51 Malay Muslim courts produced a wide range of

texts in forms of Malay that were loaded with Arabic and Persian vocabulary

and written almost exclusively in a modified form of the Arabic script (Jam).

These included literary chronicles such as the Sejarah Melayu and the Hikayat

Raja Pasai, as well as narratives involving important Islamic religious figures

in the Malay hikayat genre. 52. Prose texts of this latter type offer vivid, embellished accounts of the lives of Sufi saints like Ibrahim b. Adham, and episodes from Muhammad's life, ranging from the cutting of his hair to the delivery of his last words from his deathbed. Some of the earliest of

surviving Malay hikayat appear to have been adaptations from Persian originals, such as the Hikayat Muhammad Hanafiyya and the Hikayat Amir

#### HamzaP

Other Malay texts concerned with Islamic religious themes were composed

not in prose hikayat, but rather in the verse genre known as syair. These range

from poetic romances such as the Syair Bidasari to non narrative religious texts

such as the Syair Bahr al Nisa' produced by an anonymous poet at the court of

Aceh in the late sixteenth or early seventeenth century. Syair and hikayat,

however, comprise only a part of the textual history of Malay Islamicate literature. Among the other productive genres from the fifteenth through nineteenth centuries was that of the Malay legal digests known as undang

undang. These are digests of customary law that can include articles in which

rulings are stated in relation to both established local practice and more globalising sharta norms. For example, the Undang undang Melaka contains

the following ruling on a rather particular type of killing:

[If an adulterous woman's illicit lover] runs into someone's compound and

is pursued by the cuckold, who then becomes involved in a fight with the owner of the compound . . . and the pursuer is killed, the latter simply dies and

there shall be no legal penalty. This is the custom ('add) of the country, however according to the law of God (hukum Allah), he who kills shall also

be killed. This follows the directives of the Qur'an and is in accordance with

enjoining the right and forbidding the wrong (al amr bi'l ma'rufwa'l nahy 'an

al munkar). 54

51 G. L. Koster, Roaming through seductive gardens: Readings in Malay narrative (Leiden,

1997), P-15.

52 For an overview of these Malay narratives, see Teuku Iskandar, Kesusasteraan Klasik

Melayu Sepanjang Ahad (Jakarta, 1996), pp. 116 21.

53 See L. F. Brakel, The Hikayat Muhammad Hanafiah (The Hague, 1975), and Ph. S. van Ronkel, De Roman van Amir Hamzah (Leiden, 1895).

54 Liaw Yock Fang (ed.), Undang undang Melaka/The laws of Melaka (The Hague, 1976), Malay text p. 70.

487

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Alongside the undang undang texts, however, there were other Malay writings

on law that would be more recognisable to students of Islamic jurisprudence

elsewhere in the Muslim world.

One of the major characteristics of South East Asian history during the sixteenth and seventeenth centuries was the region's rapidly accelerating involvement with expanding networks of global commerce. Anthony Reid has called attention to the relationship between this increased economic interaction and the development of increasingly self conscious assertions of

Islamic identity in the politics of South East Asian societies. 55 In his ground

breaking survey of Muslim scholarly networks connecting South East Asia to

the Arabian peninsula, Azyumardi Azra has also characterised the period as

one of lively development involving new participants and new agendas among

Muslims from the Indonesian archipelago. 56

Over the course of the seventeenth century an increasing number of Muslim states across the archipelago were integrating emerging understand

ings of Islam into their most basic institutions, including the political, legal and

educational systems of a number of regional sultanates. This was manifest, for

example, in the staging of elaborate state rituals to mark Muslim religious

observances and in the interpretation of Sufi cosmological theories in ways

that developed local models of political power and cultural capital. The same

period also saw an Islamicising transformation in the legal systems of a number of South East Asian sultanates. Examples of this have been pointed

to even in areas such as the island of Muna in south east Sulawesi, where Raja

Sangia Latugho is reported to have 'implemented Islamic law' from 1671 to

1715. 57 However, the interpretation of just what this may have meant in such a

context still requires further research.

Local interpretations and implementations of 'Islamic law' differed from place to place in the Indonesian archipelago (as across the Muslim world as a

whole). However, despite considerable diversity of formal doctrines and structures, it is clear that during the seventeenth century a number of regional

polities established localised traditions of law and jurisprudence that were

55 Anthony Reid, 'Islam and the state in seventeenth century Southeast Asia', in Taufik

Abdullah (ed.), Proceedings of the international seminar on Islamic civilization in tfte Malay world (Istanbul, 1997), pp. 67 84.

56 Azyumardi Azra, The origins of Islamic reformism in Southeast Asia: Networks of Malay

Indonesian and Middle Eastern 'ulamd' in tfte seventeenth and eighteenth centuries (Crows Nest, NSW, 2004).

57 Laporan Hasil Penelitian Tentang Masuknya Islam di Sulawesi Tenggara, Departemen

Agama: Badan Penelitian dan Perkembangan Agama, Balai Penelitian Lektur

Kegamaan. Ujung Pandang, 1986/7, p. 59.

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

### South East Asian localisations of Islam

self assertively 'Muslim'. The very appeal to such external symbols of legal

order comprises a significant marker of the ongoing processes of the Islamisation of social institutions in the region.

# Islamic scholarship in the sultanate of Aceh

During the first half of the seventeenth century, and especially under the royal

patronage of Sultan Iskandar Muda (r. 1607 36), Aceh became the leading

regional centre of Islamic learning. Iskandar Muda launched campaigns for the

Islamisation of the neighbouring Gayo and Minangkabau regions of Sumatra,

and staged elaborate observances of Friday prayers and other Islamic religious

observances. He also appears to have adopted various symbols and institutions from the contemporary Mughal and Ottoman empires to bolster his authority as a ruler of Muslims, including official state seals and insignia 58

and even an institution reminiscent in some ways of the office of the Sehulislam. 59 Iskandar Muda and his successors devoted considerable patron

age to Islamic learning and literature as well, as attested to by both European

visitors' accounts of Aceh and the legacy of influential Muslim texts from the

seventeenth century produced there that have survived to this day.

The earliest surviving evidence for a tradition of Acehnese literature written in a modified Arabic script comes from the late seventeenth century:

however, most written texts in that language were produced in the eighteenth

and nineteenth centuries. Rather than Acehnese, the predominant language of

both the royal court and Islamic religious scholarship in the sultanate of Aceh

in the seventeenth and eighteenth centuries was Malay. In fact, the power and

prestige of the Acehnese court in the seventeenth century enabled it not only

to take up the mantle of Muslim Malay culture rooted in the earlier tradition

of Melaka, but also to significantly transform it. The extent to which this was

the case has been demonstrated by Leonard Andaya in arguing that, 'Aceh

came to offer new standards of Malayness based on Islamic models in literature and in court administration and behaviour.'

Nevertheless the Malay Muslim character of the sultanate of Aceh was, like

that of all other Islamicate cultures of the medieval and early modern period,

58 James Siegel, Shadow and sound: The historical thought of a Sumatran people (Chicago, 1979), PP- 24 5-

59 Takeshi Ito, 'The world of the Adat Aceh: A historical study of the sultanate of Aceh', (Ph.D. thesis, Australian National University (1984), pp. 259 62.

60 Leonard Y. Andaya, Aceh's contribution to standards of Malayness', Archipel, 61 (2001), P-45-

489

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

complex in its relationship to pre Islamic traditions. Thus the records of the

period reveal that a number of ideas and institutions rooted in the earlier history of the region were transmitted and transformed within the sultanate's

Islamicised idioms of symbolic power and social order. Perhaps the most striking example of this is a structure located in the inner precincts of the

sultan's palace known as the Gunongan (Fig. 6). This was an artificial mountain

located in the royal gardens, whose descriptions suggest that it resembled

replicas of Mt Meru known from other South East Asian courts, both Muslim

and non Muslim. The name of the garden in which this powerful Hindu Buddhist image was situated was Taman Ghayra, through which flowed a river

known as the Dar al Hshq, on the banks of which was a mosque called l Ishq

Mushahada. \* The Arabic terminology employed here is thick with Sufi valences, and points to the important role of tasawwuf in expressions of the

religious and political culture of the sultanate.

One of the most influential figures active in both the religious and political

spheres of life in Aceh during the reign of Sultan Iskandar Muda was the Sufi

shaykh Shams al Dm b. [ Abd Allah al Sumatram al Pasa'i (d. 1630), whose

presence is recorded in the works of European visitors to the court of Aceh,

and who has left behind a considerable corpus of writings in both Malay and

Arabic, some of which also contains quotations in Persian. In his work entitled

Nur al DaqaHq, which is transmitted in both Arabic and Malay recensions,

Shams al Din presents one of the earliest Malay expositions of the 'seven grade' emanationist cosmology developed by al Burhanpuri. However, court

tastes changed and eventually Shams al Din's models of Islamic mysticism lost

favour in the face of virulent critiques of the Sufi doctrine of the 'unity of Being' (wahdat al wujud) by a newcomer to the Acehnese court, Nur al Din al

Raniri.

Al Raniri was a Gujarati Muslim of south Arabian descent who was born into a family with far flung connections in the commercial and cultural net

works across the Indian Ocean littoral. His uncle had spent extended periods

of time in Aceh where he taught the Islamic religious sciences in the late

sixteenth century. z Al Raniri himself benefited from a rich Islamic education

under the direction of a number of highly mobile, ethnically hybrid teachers

from various countries along the Indian Ocean littoral. 3 In his own writings,

61 Robert Wessing, 'The Gunongan in Banda Aceh, Indonesia: Agni's fire in Allah's

paradise', Archipel, 35 (1988), pp. 157 94.

62 Azra, Origins of Islamic reformism, pp. 54 5.

63 Tudjimah (ed.), Asrdr al InsanfiMa'rifat al Riih wa'l Rahman Qakarta, 1961), p. 2; S. N. al

Attas, Raniri and the Wujudiyyah of lyth century Aceh (Singapore, 1966), pp. 13 14.

490

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

6 The artificial mountain (Gunongan) of Aceh, built as a centrepiece of a Sufi inspired royal garden (photo: Michael Feener)

al Ramri brought a good deal of these cosmopolitan traditions of Muslim scholarship into his Malay compositions. His dexterity in adapting techniques

and materials from global traditions of Arabic language scholarship comes

across clearly in the construction of his arguments in such works as the intra

Sufi polemics Hujjat al siddiq li dafal zindiq and the Tibyanfima^arifat'al adyan.

After he had established himself at the Acehnese court in 1637, al Ramri

initiated a radical campaign of religious reform that sought to discredit the

mystical cosmologies popularised in the region by Hamza Fansuri and more

recently Shams al Din to replace them with what he considered to be more

'orthodox' doctrine. Al Ramri's ambitious programme of reform was carried

491

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

out through the creation of a remarkable corpus of works written in Malay

that strove to redefine Aceh's Malay Muslim tradition in the fields of juris prudence, mysticism, theology, literature and history. His Malay works became the standard references for many South East Asian Muslim students

over the following centuries and were studied well beyond Aceh in places including the Malay peninsula and Kalimantan (Borneo), with translations and

adaptations made into Bugis and other regional vernaculars.

Of all his writings in these various fields, however, it has been al Raniri's work offigh that has proved of greatest longevity. The contents of this book.

entitled Sirat al Mustaqim, present striking images of the extent to which emerging traditions of Islamic religious scholarship in Malay during the seventeenth century had become engaged with contemporary conceptualisa

tions of a global Sunrii normativity. For instead of raising specific issues immediately relevant to the lives of South East Asian Muslims of that period,

this monumental Malay language work onfiqh includes rulings on such things

as the eating of camel (halal) and giraffe (karam). 64 That is, what is character

istic about a popular Malay teaching text such as this is not its exotic, local

vision of a distinctly South East Asian Islam, but rather its overwhelming

uniformity with analogous^IqJi manuals produced around the world in Arabic

during its day. Parallel developments can be found in seventeenth century

Malay works of other fields of Islamic religious scholarship as well, including

Qur'anic exegesis.

The most significant Malay work of this type was produced by a scholar active at the court of Aceh following al Raniri's abrupt fall from favour in 1643. 65 'Abd al Ra'uf al Singkeli's (d. 1693) Tarjuman al mustafid was the most

extensive and popular text of Malay language tafsvr extant for almost 300 years

and went through several print editions in the late nineteenth and early twentieth centuries. Through a painstaking study of this work Peter Riddell

has demonstrated the overwhelming extent to which the Tarjuman al mustafid

is based upon the Tafsvr jalalayn, which was composed by two Egyptian scholars in the sixteenth century, and ever since has served as a standard introductory text to the field.

The scholarly career of the author of the Tarjuman al mustafid, 'Abd al Ra'uf

al Singkeli, provides an illuminating contrast to that of his predecessor at the

court of Aceh, al Rariiri, in several respects. Most significantly, perhaps is the

64 Nur al Dm Muhammad JTlam b. 'All b. Hasanji b. Muhammad b. Humayd al Ramri,

Sirat al Mustaqim fijiqh madhliab al Shaji'i (Cairo, 1937), p. 336.

 $65\ Takeshi\ Ito,$  'Why did Nuruddin ar Raniri leave Aceh in  $1054\ AH?',$  Bijdragen tot de Taal ,

Land en Volkenkunde, 134, 4 (1978), pp. 489 91.

492

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

fact that 'Abd al Ra'uf was a locally born scholar who had returned to Aceh after

decades of study and scholarship in Duha, the Yemen and the Hijaz. Seen alongside the career paths of al Raniri others like him who came from South

Asia and the Middle East to teach Islam in the Indonesian archipelago, the

professional trajectories of 'Abd al Ra'uf and his contemporary colleague Yusuf

al Maqassari demonstrate that the movement of Muslim scholars and their

works between Arabia and South East Asia was by no means unidirectional.

A considerable amount of information about 'Abd al Ra'uf's period of study

in the Middle East (1641 61) can be gleaned from an autobiographical codicil

appended to his Sufi treatise entitled 'Umdat al MuhtdjTn. That section of the

text documents his position within the Muslim scholarly circles of his day through detailed listings of the teachers that he studied with, especially those

affiliated with the Qadiriyya and Shattariyya Sufi orders. Of all of these teachers, the most directly influential were the highly distinguished and influential shaykhs Ahmad al Qushashi (d. 1661) and Ibrahim al Kurani (d. 1690). 6? Among South East Asian Muslims this pair of Hijaz based Naqshbandi Sufi shaykhs became more popularly known as teachers of the

Shattariyya order, and their particular appeal for students from the Indonesian

archipelago seems to have been in part due to their combination of affinities

for the teaching of Ibn 'Arabi and the defence of the practice of vocalised dhikr

(jahf) according to the Shafi'i school of jurisprudence.

Educated in these prestigious Sufi circles of the Hijaz, c Abd al Ra'uf appears

to have considered Sufism to be a special preserve of a scholarly and spiritual

elite, rather than a phenomenon of popular syncretism. As he maintained in

his Malay treatise entitled DaqaHq al Huriif, 'those who do not understand the

technical language [of the Sufis] ... should leave discussions of such to them

[the Sufis]'. 69 Thus delimiting the sphere for such discussions, 'Abd al Ra'uf

was able to make more refined arguments and subtle distinctions in elaborat

ing his position on the controversial subject of wahdat al wujud, quoting appreciatively from Ibn 'Arabi but maintaining a careful ontological distinc

tion between God (al Hagg) and everything else in creation.

66 Peter Riddell, Transferring a tradition: 'AbdAl Ra'uf Al Singkili 's rendering into Malay of the Jalalayn commentary (Berkeley, 1990), pp. 223 38.

67 For more on his connection to Kurani, see A. H. Johns, 'Friends in grace: Ibrahim al

Kurani and 'Abd al Rauf al Singkeli', in S. Udin (ed.), Spectrum: Essays presented to Sutan

Takdir Alisjahbana on his seventieth birthday (Jakarta, 1978), pp. 469 85.

68 Dina Le Gall, A culture of Sufism: Naqshbandts in the Ottoman world, 1450 1700 (Albany, 2005), pp. 101 2.

69 A. H. Johns (ed.), 'Daka'ik alHuruf by Abd al Ra'uf of Singkel', Journal of the Royal Asiatic Society (1953), Malay text p. 59.

493

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

In addition to his works on Sufism and Qur'anic exegesis, Abd al Ra'uf composed books in a number of other fields, including haalth studies and jurisprudence. Much of this work was produced under the patronage of the

Acehnese court after his return from two decades of study in the Middle East.

Notable among these compositions is the Mifat al tullab fi tashil ma'rifat al

ahkam al SharHyya HI malik al wahhab, in which he advanced a sharfa based

argument for the legitimacy of a female to serve as the head of a Muslim state

(khalifa). 70 For Abd al Ra'uf, this was not an abstracted, hypothetical ruling,

but rather a concrete reference to the situation in Aceh during his day, as the

sultanate was ruled by a succession of four sultanas between 1641 and 1699.

Beyond his written work, 'Abd al Ra ] uf s lasting influence on the further development of Islamic thought in South East Asia has been exercised by the

legacy of his Sufi teachings passed down through his disciples hailing from

various parts of the archipelago. Some of the most important among them

were Shaykh Burhan al Din (d. 1692) of Ulakan in west Sumatra, Tok Pulau

Manis of Trengannu on the Malay peninsula (d. c. 1736), 'Abd al Muhyi of Banten in west Java and Baba Da'ud b. Isma'il al Rumi who is believed to have been a descendant of Ottoman gunsmiths who had come to Sumatra to

aid the Acehnese in their struggles with the Portuguese in the sixteenth century. Over the century that followed, the significance of such intersections

of trans regional Sufi lineages and opposition to European advances in

Indonesian archipelago were to become more pronounced.

New networks and European encroachment in the eighteenth century

In the early decades of the eighteenth century, attempts by the Dutch East

India Company (VOC) to strengthen its control over commerce and political

affairs in the Indonesian archipelago were challenged by various forms of local

resistance, a number of which were pursued or perceived as being advanced in

the name of Islam. In reaction to such challenges to their authority, real and

imagined, the Dutch took steps to disrupt the development of opposition movements, particularly those which they feared from native Muslim leaders.

In 1716 the VOC issued a prohibition on the use of Company ships to transport

Muslim pilgrims from the archipelago on their return voyages from Mecca. 71

70 Amirul Hadi, Islam and state in Sumatra: A study of seventeenth century Aceh (Leiden, 2004), p. 60.

71 Vredenbregt, 'The Hadjdj", p. 96.

494

Cambridge Histories Online © Cambridge University Press, 201 1

#### South East Asian localisations of Islam

Later in the same decade, the Dutch began to sense other religiously inspired

threats that originated not in Arabia, but in Java itself in the form of documents

circulating under the title of 'Predictions of Jayabaya'. 7i These predictions of

the overthrow of tyranny and the ascension to power of a messianic figure

(mahdT) or a just king' (ratu adit) were seen by some among both the colonisers and the colonised as supporting various millenarian movements

in the eighteenth century.

In 1721 these spectral menaces took on a new face for the Dutch population

of Batavia with the uncovering of an 'Islamic plot' allegedly engineered by a

baptised German Siamese Eurasian by the name of Pieter Erberveld. He was

arrested that December on charges of distributing Islamic religious amulets

containing Arabic script formulae (jimat) and plotting to put an end to VOC

control by slaughtering the Christian population of Batavia. Soon thereafter

he, along with a number of bis associates, was executed and his head was displayed on a pike. A gruesome monument to his fate with inscriptions in

Dutch and Javanese was set up as a constant reminder of the price to be paid

for threatening the colonial order.

Aside from polyglot, highly mobile and eclectic individuals like Erberveld, there were during the eighteenth century increasing numbers of people in

motion across the archipelago who could at various times identify themselves

as members of different ethnic groups. Engseng Ho has described this period

as one of expanding and interconnected diasporas impacting upon the histor

ies of a number of port polities in the archipelago. The two most influential

Muslim diasporas in the region during the eighteenth century were those of

the Bugis and Arabs from the Hadramawt in southern Arabia. While the Bugis

integrated themselves into the highest levels of Malay courts around the Straits, the Hadramis had an even wider range of influence. A Hadrami dynasty known as the Jamal al Layl established itself at Aceh at the expense

of the last sultana of Aceh in 1699, and in the decades that followed, other

Hadrami Creole migrants established themselves at Siak, Mempawa, Matan,

Kubu and Pontianak. 73

In many of these places, the ascendancy of 'Hadrami Arabs' within local religious and political elites contributed to the further incorporation of Islamic

72 H. J. de Graaf, 'South East Asian Islam to the eighteenth century', in P. M. Holt, Ann

K. S. Lambton and Bernard Lewis, Tfte Cambridge history of Islam (Cambridge, 1970), vol. II, p. 152.

73 Engseng Ho, 'Before parochialization: Diasporic Arabs cast in Creole waters', in Huub

de Jonge and Nico Kaptein (eds.), Transcending borders: Arabs, politics, trade, and Islam in Southeast Asia (Leiden, 2002), pp. 11 36.

495

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

elements in the symbols of political power in South East Asian states. In certain ways these developments mark the acceleration and proliferation of

processes that had been at work in the region for some time. As a result of

such collaborations, cosmopolitan Creole Arab Muslim immigrants came to

assume primary leadership roles in numerous communities stretching across

the archipelago.

Such patterns of close association between Arab immigrants and local elites

were reproduced with variations across the region in the eighteenth century.

For example, in 1711 two Arab sayyids arrived in Buton and were given permission by the sultan to establish two religious schools, one in the neigh

bourhood of the royal palace and one near the grand mosque at Bau Bau. 74 In

t737» ajavanese royal embassy to Batavia returned to the court of Pakubuwana

II, bringing with them an Arab shaykh named Sayyid Alwi. This new arrival at

the central Javanese capital quickly rose to prominence, being granted one of

the sultan's concubines for a wife and charge over religious affairs for the

realm.

Islam in eighteenth-century Java

Pakubuwana II's reign (1726 49) was marked by a series of dramatic trans

formations in the religious and cultural character of Java. His elderly grand

mother, Ratu Pakubuwana, had in the early years of his reign attempted to

strengthen the sultanate through the cultivation of Islam, particularly by means of sponsoring the production of Islamic religious and literary works

in Javanese. These texts included narratives of Alexander the Great (Carita

Sultan Iskandaf) and the prophet Yusuf (Carita Nabi Yusuf), as well as the Kitab

Usulbiyah, which details a mythic encounter between Jesus and Muhammad.

During the early years of his reign, Pakubuwana II appears to have embraced

trends towards the further Islamisation of Javanese court life, and attempted to

construct an image of himself as a crusading warrior of Islam against the 'Christian' Company of the Netherlands East Indies. However, after a dra matic reversal of military fortune in the joint Chinese Javanese campaign against the VOC, he abruptly dropped such pretence and sought reconcilia

tion with the Dutch. This decision was accompanied by radical reorientation

of the kraton elite towards Javanist modes of asceticism and court aesthetics,

and away from explicitly Islamic identifications. 75

74 La Ode Zaenu, Buton dalam Sejarah Kebudayaan (Surabaya, 1985), p. 89.

75 Ricklefs, Seen and unseen worlds in Java.

496

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

The complex negotiations of defining Islam in relation to Javanese culture

during this period are reflected in the literary as well as in the historical record.

For example, another episode in which issues of establishing particular, court

approved conceptualisations of Islam in Java is purportedly described in the

well known work of Javanese Sufi literature Serat Cabolek. This later text vividly

narrates the story of an unruly mystic who was reportedly brought before an

assembly of Muslim scholars in eighteenth century Java for divulging esoteric

doctrines to the uninitiated. While initially boasting of his 'superior' knowledge

of the faith gained under the tutelage of Yemeni teachers, Haji Amad Mutamakin is eventually humbled by the way in which one of the scholars

sitting in judgment over him is able to interpret the 'proper' Islamic mystical

meanings contained within Old Javanese 'Hindu' texts such as the Bhima Suci. 76

With more precise dating and historiographic reliability for the latter half of

the eighteenth century, we are fortunate enough to also be able to view some

other aspects of the continuing dynamics defining Islam in relation to the culture of the Javanese court through writings in an altogether different genre

than svA.uk and formal religious treatises. This is due to the survival of a manuscript written by a woman employed as a member of the sultan's elite

female guard (prajurit estri) that includes descriptions of a number of religious

rituals as they were observed at the court of Mangkunegara I from 1781 to 1791.

For example, we get a sense of the concrete ways in which Javanese aesthetic

and performance traditions were integrated into celebrations of the Muslim

feast day commemorating Abraham's near sacrifice of his son (Jv. Garebeg

Besar I Ar. c Id al adha):

In the evening and through the night before Friday

A vigil was kept by the army of the senior Pangeran Dipati who circled the courtvard.

They placed bets on their skills at archery, while the kaum [pious Muslim]

soldiers said their dikir in unison.

There was singing, and playing a gamelan

Of gongs and drums, and there was a meal at midnight.

Some performed a [dance performed by ornately costumed archers known as] tayungan.

In the morning they went to the prayer once again. 77

76 S. Soebardi, The hook of Caholek: A critical edition with introduction, translation and notes (The Hague, 1978).

77 Arm Kumar, 'Javanese court society and politics in the late eighteenth century: The record of a lady soldier, part 1 The religious, social, and economic life of

the court', Indonesia, 29 (1980), p. 14.

497

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

More formal works of Javanese Muslim literature were produced at about the same time by the celebrated court poet of Solo, Raden Ngabehi Yasadipura

I (d. 1803). Among his major works are modern Javanese verse renderings of

Menak stories, a guide for rulers entitled Taj al Saldtln and a collection of

narratives of the lives of the prophets from Adam to Muhammad. In his masterful survey of the history of Islam in early modern Java, M. C. Ricklefs

has demonstrated that by the time of Yasadipura I's death in the early nine

teenth century, a dominant mode of religious and cultural identity had formed

in Java out of a long developing 'mystic synthesis' incorporating elements of

indigenous, Indie and Islamic traditions/ 8 Yasadipura I's work, and that of the

court poets Yasadipura II and Ronggowarsito who followed him, helped to

create sophisticated works of local Muslim literature that reflected and further

influenced the changing religious culture of the courts of Java's sultans. These

latter works, however, are characteristic of a different era of the history of

Islam in Java, one beyond the scope of this essay.

## Malay Muslim scholarship in the eighteenth century

Outside Java, developments of religious and cultural dynamics in the region

were also vibrant in other parts of the archipelago during this period. For example, in the mid eighteenth century, a considerable number of Arab migrants came to be integrated into the political and cultural elite of the south Sumatran sultanate of Palembang, contributing to significant develop

ments in the history of Islam there. 79 Manuscript holdings preserve the work

of a number of local scholars active in Palembang at that time, including Shihab al Dm b. 'Abd Allah Muhammad and his younger contemporary Kemas Fakhr al Din (d. 1763). Shihab al Din's work is preserved in three surviving texts presenting simplified outlines of a Sufi theology that eschews

what he sees as the excesses of the 'seven grade' system of speculative emanationist cosmology that had been so popular in the archipelago since

the early seventeenth century. Kemas Fakhr al Din devoted a considerable

amount of his scholarly output to Malay translations of Arabic works, ranging

from an expanded treatment of Raslan al Dimashqi's (d. 1146) classic statement

of 'sober Sufism' Risala jTl tawhld, to selections from the Arabic historio graphical tradition dealing with the early Muslim conquest of Syria

78 Ricklefs, Mystic synthesis in Java, pp. 221 34.

79 Barbara Andaya, To live as brothers: Southeast Sumatra in the seventeenth and eighteenth centuries (Honolulu, 1993), pp. 220 1.

Cambridge Histories Online © Cambridge University Press, 201 1

#### South East Asian localisations of Islam

(ps. Waqidi's Mukhtasar Futiih al Sham). The rendering of such texts into Malay testifies to the increasing involvement of the South East Asian Muslim scholars in the world of Arabophone learning spanning the Indian Ocean during that period.

Within these contexts, the ongoing and deepening Islamisation of the archipelago underwent some remarkable developments during the eighteenth

century. In many ways these were related to broader trends making them selves felt across the Muslim world as a whole. For at this time a new surge in

internally oriented Islamic reform movements was sweeping across Africa and

Asia. Perhaps the one with the most name recognition today is that of 'Abd al

Wahhab which succeeded in becoming the 'official' form of Islam in Saudi Arabia. However, Wahhabism is only one manifestation, and a somewhat atypical one at that, of broader trends in Islamic religious reform in the eighteenth century. Many of the reform movements from this period combined a renewed emphasis on the study of hadith with a re evaluation of Sufi

tradition within various newly established or reformulated Sufi orders, such as

the Nagshbandiyya and the Shattariyya.

In the mid eighteenth century the Banten scholar 'Abd Allah b. 'Abd al Qahhar studied the Shattariyya and Naqshbandiyya Sufi orders in Mecca, and

returned carrying with him a manuscript of one of 'Abd al Ra'uf Singkeli's works. Later in the eighteenth century other tariqas began attracting adherents

in west Java, particularly the Rifa'iyya and Sammaniyya orders. ° Well beyond

the localities of the archipelago, however, South East Asian Sufis were deeply

involved with contemporary currents of Sufi reform, as can be seen from the

example of Shaykh Ahmad Khatib Sambas in the nineteenth century. Although born in Kalimantan, he spent most of his life at Mecca, where he

played a formative role in the systematisation of a new Sufi order combining

elements from the Qadiriyya and Nagshbandi traditions.

Before these developments, however, the most influential South East Asian

Sufi and Muslim scholar active in Arabia during the eighteenth century was

'Abd al Samad al Palimbani (al Jawi). Like a Fakhr al Din Kemas and Shihab al

Din, 'Abd al Samad hailed from Palembang. However, after coming to the Middle East to pursue his religious education, he never returned to South East

Asia, and died of old age in Ta'if after a lifetime of study, teaching and writing

in Yemen and the Hijaz. His writings were carried back to South East Asia by

his students where they had a tremendous impact on the evolving Islamic

van Bruinessen, 'Banten sultanate', pp.182 5.

499

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

intellectual history of the region. 'Abd al Samad is known to be the author of a

number of works in both Malay and Arabic on a broad range of topics.

'Abd al Samad wrote one of the earliest Malay works on the subject of perang sabil ('war in the way [of God]') against increasing European encroach

ment in the archipelago. This work draws on classical fiqh discussions of jihad

and came to be used as a source for the subsequent development of local literatures on the subject in poetry and prose genres of Malay and Acehnese.

Similar sentiments are reflected in letters 'Abd al Samad sent from Arabia to

Javanese leaders that were intercepted by the Dutch in 1772 J reminiscent of

episodes from the career of Yusuf al Maqassari a century earlier.

Today 'Abd al Samad is best known for his Malay adaptations of al Ghazali's works, entitled Hidayat al SalikTn and Sayr al Salikin. His role as a

teacher of Ghazali's 'Ihya 1 'ulum al dm was valued not only by readers of Malay

works, but also by Arab scholars, including such luminaries as Abd al Rahman

b. Sulayman al Ahdal (d. 1835), who studied under 'Abd al Samad in the Yemeni town of Zabid. Al 'Ahdal later wrote a biographical (tabaqat) entry

on 'Abd al Samad that provides a striking depiction of a South East Asian Muslim in the role of teacher to a prominent sayyid scholar in the Arabian

peninsula:

When our scholar arrived at Zabid, he continued to increase his exhortations

towards the study of Ghazali's y lhya\ and I read under him, thanks be to God.

the first quarter of every chapter. I asked him for an ijaza [document of certification] in this book to relate that which is good in it and to benefit from

its knowledge. He wrote for me in his own noble hand a very long ijaza, it being his way that if a student came to him asking detailed questions and he

saw something good in the student, he would lengthen his praise of the student in the ijaza. He would also explain to the student about law and literature to increase his adherence to it, and the student would see clearly

that which was presented to him. The shaykh continued to explain for me the

literature of legal decisions and the requirements of a mufti: it is not enough

only to inquire [into the facts of a certain case] but if he has knowledge of the

situation he must call attention to it in the writing of his decision. 82

These lines provide not only a sense of the respect that 'Abd al Samad

commanded from his Yemeni Arab colleagues, but also of the way in which

Sufism and the study of Islamic law were integrally related at the time.

81 G. Drewes, 'Further data concerning 'Abd al Samad al Palimbani', Bijdragen tot de Taal ,  $\,$ 

Land en Volkenkunde, 132, 2 3 (1976), pp. 267 92.

82 'Abd al Rahman b. Sulayman al 'Ahdal, al Nafas al yamanl (San'a', 1979), pp. 139 40.

500

Cambridge Histories Online © Cambridge University Press, 201 1

South East Asian localisations of Islam

At Zabid, 'Abd al Samad was fully integrated into the heart of a network of

Arabophone Muslim scholars that extended across the entire range of the Indian Ocean littoral and beyond, from West Africa to China. It is important to

note, however, that he was far from being the only South East Asian scholar in

Arabia during the eighteenth century. Others notably included 'Abd Allah al Rahman al Batawi al Masri, 'Abd al Wahhab al Bugisi and Muhammad Arshad b. 'Abd Allah al Banjari. 3 Upon returning to his native Kalimantan in

1773, Arshad al Banjari (d. 1812) served the sultan of Banjar as an authoritative

interpreter of what was considered legitimate Islamic teaching in the realm. 4 It

was in this position that he composed his most celebrated work, the Sabil al Muhtadin, which was commissioned in 1779 as a request to produce a Malay

text of Shafi'i fiqh in a style of language more accessible than al Raniri's Sirat

al Mustaqim. The close association of these two Malay fiqh works has persisted

to this day, with currently available editions of the SabU al Muhtadin having

al Raniri's text printed in its margins.

Another scholar of Banjar contemporary with Muhammad Arshad was Shaykh

Muhammad Nafis b. Idris b. Husayn al Banjari, whose al Durr al Nafis was

completed in 1785. This work of Sufi thought draws on a wide range of authori

ties and entertains speculative cosmological musings on the pre existent essence

of Muhammad while also acknowledging the importance of pursuing the Sufi

path within the parameters established by the shaifa. Texts like these written in

Arabic script Malay comprise the Malay kitab tradition often referred to in

modern Malay and Indonesian as kitab jawi or kitab kuning. These texts, and the

institutional settings of the schools in which they were taught (pesantren), played a

central role in the continuing development of Islamic thought and Muslim culture

in South East Asia throughout the nineteenth and twentieth centuries. 85

One of the most prolific early masters of the Malay kitab tradition who was

also to enjoy some of the most widespread and long lasting popularity in pesantren circles was Dawud b. 'Abd Allah al Fatam. He was a prolific author

83 Azra, Origins of Islamic reformism, pp. 118 19.

84 Azyumardi Azra, 'Opposition to Sufism in the East Indies in the seventeenth and

eighteenth centuries', in Frederick de Jong and Bernd Radtke (eds.), Islamic mysticism

contested: Thirteen centuries of controversies and polemics (Leiden, 1999), p. 685.

85 For an overview of these later developments, see: Martin van Bruinessen, 'Pesantren

and kitab kuning: Continuity and change in a tradition of religious learning', in

W. Marschall (ed.), Texts from the islands: Oral and written traditions of Indonesia and

tfte Malay world (Berne, 1994), pp. 121 46.

86 For more on this author and his place in the ongoing tradition of kitab scholarship in

Patani, see Virginia Matheson and M. B. Hooker, 'Jawi literature in Patani: The main

tenance of an Islamic tradition', Journal of the Malay Branch of the Royal Asiatic Society, 61, 1 (1988), pp. 1 86.

501

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

of Malay kitab who hailed from the region that is today southern Thailand, and

after a period of study in Aceh spent much of the rest of his long life in Arabia,

where he apparently died sometime in the 1840s. 87 He was a younger colleague of 'Abd al Samad and his cohort in Arabia, and from across the Indian Ocean he made remarkable contributions to Malay traditions of Islamic

scholarship, through his popular and oft printed works in the fields of figh,

tasawwuf and kalam, and other works such as his treatise on Muhammad's

'night journey' (mHraj) and ascension ('ism').

Recognising the remarkable degree to which religious developments in South East Asia were integrated into broader dynamics of intellectual and

cultural change in the Middle East and other Muslim societies can help us to

avoid the misperceptions that often accompany an overemphasising of the

'unique' nature of South East Asian Islam. The Indonesian archipelago is home to a number of distinctive forms and expressions of Islamicate civilisa

tion. However, the processes of 'naturalising' Islam in this region have not

been in any sense categorically different from those at work in the history of

other Muslim societies as they developed elsewhere, including in various

cultural subregions of the Arab Middle East. For over the past fourteen centuries, Muslims all across the world have engaged in complex cultural negotiations in their striving to root the eternal message of the Qur ] an within

the historical contingencies of their own day and age, and this has always involved the selective adaptation of traditional ideas and institutions to evolv

ing interpretations of Islamic religious and legal ideals. In his recent survey of

Muslim societies in African history, David Robinson has spoken of the com

plex and ongoing processes of Islamisation on that continent as 'making the

faith universal and local at the same time'. 88 A similar perspective on the

development of Islam in South East Asia can help us to recognise the fact that

its complex history involves the study of Arabic grammar as well as gamelan,

and waqf as well as wayang.

Over the course of the nineteenth century the situation in South East Asia

and other lands of Islam became even more complex with the development of

new dynamics of reform within Muslim communities, as well as the increas

ingly intense intrusions of modern European colonialism into various parts of

Africa and Asia. By the 1820s, for example while Dawud al Fatarii was composing his Malay works of traditionalist scholarship at Mecca the Indonesian archipelago was experiencing considerable upheavals in the form

87 Azra, Origins of Islamic reformism, pp. 114, 122 6. David Robinson. Muslim societies in African history (Cambridge, 2004), p. 201.

502

Cambridge Histories Online © Cambridge University Press, 201 1

## South East Asian localisations of Islam

of militant movements of resistance to European control expressed in the idiom of Islam. Foremost among them were the so called 'Diponegara war' in

central Java and the rise of the Padri movement in west Sumatra. These very

different campaigns can yet be seen as extensions of both the dynamics of

internal Islamic reformism and the advancement of Dutch economic and military dominance characteristic of the eighteenth century in South East Asian Muslim history. By the middle of the nineteenth century, however, changes were getting under way that were to dramatically transform Muslim

cultures across the archipelago and around the world. 89

89 I discuss major aspects of these transformations in Tfie new Cambridge history of Islam, vol. VI, Chapter 2.

503

Cambridge Histories Online © Cambridge University Press, 201 1

14

Transition: the end of the old order Iran in the eighteenth century

### G. R. GARTHWAITE

The nineteenth century in European history is often characterised as the 'long'

century, which probably holds true for Iran, too, with the reign of the Oaiars

from the late eighteenth century until 1925. Can the eighteenth century be

seen as the 'short' century in Iran's history? Very short, indeed, if the period

begins in 1722 with the Safavid collapse 1 and ends with Agha Muhammad Khan

Qajar's consolidation of power a half century later. Iran's eighteenth century

is easily characterised by its dynastic fragmentation, when no fewer than five

dynasties ruled Iran in that period: the Safavids, Afghans, Afshars, Zands and

Qajars. There are the larger historical questions, too: on what basis does one

era end and another begin? The Safavid era comes to its end in the eighteenth

century and the Qajar period begins, but what about that arbitrarily desig

nated period in between?

While there were dynastic changes, there was continuity in the eighteenth

century in terms of political culture. Short lived dynasties did result in weak

ened government institutions and in weakened, competing centres of power,

which in turn directly affected Iran's territorial integrity and debilitated Iran in

face of both internal and external threats. Internally and parallel with the decline of central government was not just its inability to maintain order, but

its administrative ineffectiveness and a corresponding strengthening of tribal

power 2 that further limited power at the centre.

Perhaps, the most significant change occurred in the increasing authority of

the religious institution, the 'ulama', a process begun late in the Safavid period

and that would be more fully realised in the Qajar period, including not only

new clerical roles but new identities for Iranian themselves as they responded

to the challenges of the nineteenth century. Consequently, the eighteenth

- 1 Andrew J. Newman, Safavid Iran: Rebirth of a Persian empire (London, 2006).
- 2 A. K. S. Lambton, 'The tribal resurgence and the decline of the bureaucracy in the

eighteenth century', in Thomas Naff and Roger Owen (eds.), Studies in eighteenth eentury

Islamic history, (Carbondale, IL, 1977), p. 108.

504

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

century 3 marks more than a conventional time period indicated merely by the

use of that date as a marker and more than simply a transition from the Safavids and to the Qajars, although the changes that occurred were incre

mental rather than sudden.

After Shah Sultan Husayn's reign (1694 1722) came to an end he was the last of the Safavids to rule two Safavid puppets in particular continued the

dynastic name, Tahmasp II (r. 1722 32) and 'Abbas III (r. 1732 49). Moreover,

there were some eight additional Safavid pretenders in the eighteenth century

that suggest the importance of Safavid descent as a legitimating principle;

consequently, dynastic descent did give that century a certain unity. 4 Moreover, at the end of the century, Agha Muhammad Khan Qajar (whether

his reign starts in 1779 or later) and Fath 'All Shah Qajar (r. 1797 1834) can be

characterised as Safavid successors, despite the fact that the Qajars claimed no

direct Safavid descent.

What is striking about the eighteenth century is not so much discontinuity

in dynasties and government despite the principle of Safavid descent, but continuity in Iran's political culture, 5 a political culture that long predated the

eighteenth century and provided for the essential transition in Iranian history

not only into the nineteenth century, but into the twentieth century, as well,

to the reign of Riza Shah Pahlavi (r. 1926 41). Iran and Central Asia's political

culture of the eighteenth century, and long before it, had been characterised

by weak centres of government and autonomy accorded to whole regions and, particularly, to tribal groups. In addition, dynastic power had always been

established from a tribal base until the Pahlavis. While the Safavids initially

emerged as leaders of a Sufi order, they utilised various Turkic tribes to achieve dynastic power and, initially, to maintain it.

An essential basis in Iran's political culture was geography and area, regardless of territorial borders, and geography was the critical determinant

to its economy that combined agriculture, pastoral nomadism and trade. While the vast majority of the population resided in the countryside and produced crops and animals for their own consumption, small agricultural

surpluses, other commodities and some handicraft production allowed for exchanges on a regional and international basis. Regional cities played key

roles here, and these urban centres were centres of government, culture and

learning. Increased trade with Europe, along with diplomatic contact, had

3 P. Avery, G. R. G. Hambly and C. Melville (eds.), The Cambridge history of Iran, vol. VII:

From Nadir Shah to rfie Islamic Republic (Cambridge, 1991).

4 John Perry, 'The last Safavids, 1722 1773', Iran, 9 (1971), pp. 59 69.

5 Gene R. Garthwaite, The Persians (Oxford, 2005), pp. 911.

505

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

emerged in the Safavid period as an increasingly important factor and con

tinued to grow in the eighteenth century. Notables were to be found in cities

including high ranking government officials, large landowners, religious lead

ers and merchants and from among the various tribal federations. That administration was traditionally embedded in bureaucratic families, and these

families provided for continuity despite eighteenth century decentralisation.

While taxes were imposed from the centre, given fragmentation of govern

ment, provincial capitals did not remit them: that in turn exacerbated decen

tralising forces. A new elite, foreigners, began to play political, diplomatic and

economic roles, especially at the end of the eighteenth century and increas

ingly in the nineteenth century.

Rulership was a critical component of Iran's political culture, and an important factor in continuity. The shah stood at the apex of Iran's traditional

political culture to rule on behalf of God, with the appropriate self affirming

titles. His role was to uphold and defend the community of believers and to

establish and maintain justice and order. While in practice his authority and

power were unchecked, his arbitrariness was checked by the ruler's reach,

which was directed largely at notables and limited by Iran's expanse and autonomy of its regions and groups. At the same time that arbitrariness affected all Iranians. Moreover, the eighteenth century was beset with political

fragmentation and fluidity that further limited the ruler's effectiveness and

that was compromised by rival claimants, typically from the same family, for

the throne.

Religion was an additional factor in continuity in political culture and rulership. Shi'ism as the state faith, and along with the development of the

Shi c i 'ulama\ continued in the eighteenth century despite a possible mid century attempt at change. Given fragmentation of power and government

discontinuity, the c ulamd' constituted one institution that not only provided

continuity but gradually asserted its role over and against royal authority, a

process begun in the late Safavid period, which constituted a change that resonated, and increased, through the nineteenth century down to the present.

There is a continuity, too, in terms of other key factors for change that so profoundly affected the nineteenth and the twentieth centuries, changes that

also began in the Safavid era and continued through the eighteenth century,

only to be compounded in the Qajar period. Those factors would include European political, economic and cultural impacts and corresponding

6 Ibid., pp. ii 21. 506

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

consequences and Iranian responses. Issues of the nature of government, national sovereignty, identity and economy become increasingly intertwined

and evident. While rulership, political culture and the European impact can be

separated out, in their historical contexts they were intertwined, and out of

necessity the political context will be emphasised here.

Perhaps because of the eighteenth century's dynastic discontinuity and because this century has been viewed as one of transition, the period has failed to attract recent attention and scholarship let alone the recent intense

interest in the Safavid era or that of the Qajars. 7 Even important eighteenth

century rulers such as Nadir Shah or Karim Khan Zand 9 have received little

attention in the past quarter century, with a very few exceptions. History in

any of its categories social, cultural, economic or political has been all

neglected for the eighteenth century, this thin filling of that short century

sandwiched between the Safavids and the Qajars.

Eighteenth century political history is commonly divided by dynasties and approximately by quarters: Safavids, 1501 1722, along with the subsequent,

seven year Afghan interlude; the Afshars, 1736 48, and to 1795 in Khurasan; the

Zands, 1750 81, or, in various regions, 1794; and the Qajars, 1779 1926. Notions

of the Safavid ideal continued throughout the century, and, significantly, both

the Afshars and the Qajars had played important roles from the beginning, and

throughout the Safavid era, and both conceived of their dynasties as Safavid

successors. Moreover, both the Afshars and Qajars eclipsed other important

Central Asian confederations, notably the Uzbeks, who now fade from Iranian

history. Capitals shifted with each dynasty from Isfahan, to Mashhad, to Shiraz

and finally to Tehran (see Map 5), where the centre of political power has continued to the present day.

The last Safavid rulers, Shah Sultan Husayn and especially the puppet Shah Tahmasp II (r. 1722 32), fall short in comparison with Shah 'Abbas (r. 1588 1629) who stood at the apogee of Safavid rule. Sultan Husayn sue

ceeded his father, who was known initially as Shah Safi II and then recrowned

as Sulayman (r. 1666 94). Already Sulayman had sought c ulamd' favour as a

means of shoring up his authority, which also further strengthened 'ulamff

7 For notable examples of recent scholarship on the Qajars see The new Cambridge history of Islam, vol. V.

8 Lawrence Lockhart, Nadir Shah: A critical study (London, 1938), has long stood as the

standard biography and is now replaced by Ernest Tucker, Nadir Shah's quest for

legitimacy in post Safavid Iran (Gainesville, FL, 2006) and Michael Axworthy, The sword

of Persia: Nader Shah from tribal warrior to conquering despot (London, 2006).

9 John Perry's Karim Khan Zand: A history of Iran, 1747 1779 (Chicago, 1979) remains the standard for the Zand period.

507

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

authority and power, particularly those 'ulamd' who were opposed to the Sufi

and philosophically inclined 'ulamd', the other leading school in the late Safavid period. While there was something akin to an official Shi'ism especially under the domination of Mulla Muhammad Baqir Majlisi, appointed Shaykh al Islam of Isfahan in 1686 Safavid shahs played a balancing

act between the competing schools. These ongoing religious disputes con tinued throughout the eighteenth century and would subsequently shape the

c ulama"s relationship with all subsequent governments.

Shah Sultan Husayn faced serious challenges to his sovereignty in the last

years of his reign with revolts in the Caucasus, Kurdistan, Khuzistan, the Persian Gulf, Kandahar and Khurasan. In addition, the Ottomans, and increas

ingly the Russians, posed an ongoing threat. There was also a potential coup

from within the Safavid family, not to mention disloyal factions among military and administrative leaders, particularly in Herat and Kandahar. Consequently, in 1722, Mahmud, a Ghilzai Afghan from Kandahar, formed a

confederation that defeated Safavid forces and then laid siege to Isfahan at

great human and economic cost to its population. During the seven months

before Isfahan capitulated, its population suffered great losses due to disease

and starvation.

Even though Tahmasp Mirza, the designated successor, escaped from the

capital to Qazvin to declare himself Shah Tahmasp II, Sultan Husayn abdi cated and named Mahmud Ghilzai as shah. The fall of the Safavids to the Afghans was as much a surprise to the Afghans as to the Safavids. The Afghans' initial, if limited, success was due to their political and tactical leadership. Safavid ineptitude, on the other hand, was the very absence of

political and military leadership despite dynastic legitimacy. Other critical

factors in the Safavid collapse were the decimation of Isfahan's population,

the Safavids' critical centre, and the political fragmentation and autonomy of

Safavid provinces. In similar circumstances earlier in Safavid history there had

been dynastic recovery, but such a recovery was not to be repeated at the end

of the first quarter of the eighteenth century. Even though the Safavid dynastic

principle still held, it would be usurped by successive tribal leaders only to

prove continuity in Iran and Central Asia's political culture.

The Afghans were to rule Iran, and then but a portion of it, for only seven years, and represented a transitional interlude from the Safavids to the Afshars, the second of the four eighteenth century dynasties. All of the subsequent rulers of eighteenth century Iran failed to solve the challenges of

contested power and legitimacy, which was exacerbated by weak support beyond the ruler's own provinces and by Ottoman and Russian power and

508

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

expansionism. Mahmud had attempted to assert Afghan control over central

Iran but when Qazvin successfully revolted, Mahmud feared that the Isfahanis

too would rebel, and he ordered the execution of key administrative and military leaders, and Safavid princes. After three short years, Mahmud himself

was overthrown in 1725 and killed by a kinsman, Ashraf Ghilzai.

Meanwhile, Tahmasp II had vainly sought a Safavid restoration with Ottoman support, yet a joint Ottoman Russian alliance for the division of north western Iran was averted only by Peter the Great's death in 1725. The

Ottomans, on the other hand, promised to restore Sultan Husayn to the throne, but he too was murdered by Ashraf. Tahmasp II rallied his forces when he won the support of two important tribal confederation leaders, first.

from Fath 'All Khan Qajar and then more critically from Nadir Quit Khan Afshar, and was able to inflict successive losses on Ashraf, who in 1729 attempted to return to Kandahar, only to be assassinated by a member of his own family. Descent in the Safavid family and the family itself fought each other for control over that legacy was still a prerequisite to rule Iran in

the first half of the eighteenth century. Nadir Quit Khan Afshar then entered

Isfahan to enthrone Tahmasp II in the Safavid capital. Only ten months later,

however, Nadir replaced Tahmasp with his infant son, c Abbas, as 'Abbas III.

and in 1736 Nadir freed himself from even a boy puppet to proclaim himself

shah. Nadir Shah's reign (1736 47), and that of the other Afshars, can be characterised as Safavid successors even though they, too, ruled over only a

portion of Safavid Iran, and from Khurasan rather than Isfahan.

Purportedly, Mirza c Abd al Husayn, the muMbdshi, was executed by the soon to be crowned Nadir, when he uttered: 'Everybody is in favour of the

Safavid dynasty.' 10 Nadir Quit's own base was centred on his role as an Afshar

tribal leader in northern Khurasan and on the initial idea as upholder of Safavid legitimacy. Often styled as the last of the great Central Asian conquer

ors, like his predecessors he commanded others through demonstrated mili

tary and political leadership skills to build a confederation and to achieve and

then maintain power. Nadir mastered his opponents through tactical and strategic alliances, including marriage. Like earlier leaders, he too seemed to

sweep across vast distances at great speed with mounted tribesmen to defeat

his opponents and to plunder their wealth. What legitimacy he possessed was

based initially in the province of Khurasan, fractious as a consequence of

Safavid instability, and the promise of booty and the restoration of Central

Asian trade. He represented himself under the mande not only of Safavid

10 Roger Savory, Iran under the Safavids (Cambridge, 1980), p. 253.

509

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

legitimacy but of the earlier Timurids. And he sought late in his reign to accommodate Shi'ism to Sunnism, possibly to broaden, or strengthen, his legitimacy, or as a means possibly to stifle any Shi'i radicalism or of a Safavid

revival, or to advance his own imperial ambitions.

Nadir Quli, while still nominally under the suzerainty of Tahmasp II, was entitled Tahmasp Quli (servant/ slave of Tahmasp). Tahmasp II then assigned

him the key governorships of Khurasan, Mazandaran, Kirman and Sistan on

the strategically important northern and eastern frontiers. Nadir's power increased, and he even minted coins in his own name, which undercut Tahmasp II's legitimacy as ruler. Nevertheless, Nadir continued to serve Tahmasp with both military and diplomatic victories. The Ottomans were forced from western Iran and Azerbaijan in 1730, and two years later Nadir's

army reached Baghdad, despite continuing Iranian anarchy and opposition.

After their Baghdad defeat, the Ottomans agreed to the boundary terms of the

earlier 1639 Treaty of Zuhab. Subsequently, Nadir forced the Russians to withdraw from parts of northern Iran. With such military success and it was

in 1732 that Nadir had deposed Tahmasp II for his infant son, 'Abbas III he

assembled tribal leaders, notables and 'ulam<P who proclaimed him shah in

1736 at a great assembly, quriltai, on the Mughan plain. This quriltai, that

hearkens back to Mongol practice, legitimised Nadir's rule and family that

lacked actual Safavid descent.

From 1737 to 1740, Nadir Shah gained his fame as an Asian conqueror. He

first campaigned to take Kandahar and then continued on deep into India with

its fabled wealth and infamously plundered Delhi in 1738, but seemingly without the intent of adding it to his realm. In 1740, however, he extended

Iran's boundary to the Amu Darya, which represented an extension of Khurasan. Importantly, after this defeat of the Uzbeks, they begin to disappear

from Iran's history, although not from Central Asia's. Isfahan, with its Safavid

past, was further marginalised when Nadir chose Mashhad, Khurasan's major

city and the location of the shrine of the imam Riza, the Ithna 'Ashari's eighth

imam, as his capital. In Safavid and time honoured practice, Nadir relocated

tribal populations such as the Kurds and Bakhtiyari in Khurasan and in the

other eastern provinces. For the last time, Iran's centre of power was shifted

east towards Central Asia, and as a consequence a significant Sunni population

was incorporated into what until then had been a largely Shi'i state. Moreover,

Nadir had potential rivals killed, including three Safavid pretenders, and in

1741 had his own heir, Riza Quli, blinded.

While Nadir's military exploits and his political skill in forming an effective

military force and in rallying his great quriltai are undoubted, yet his motives

510

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

and purpose continue to elude us. Even less explicable is the purpose behind

his religious proposals to bring ShTism more in accord with Sunnism. Nadir

called for acceptance of ShTism as a fifth Sunm school of law, to be called the

Ja'fari school, after the sixth imam, Ja'far al Sadiq. In addition, the ShTa would

abandon their practice of cursing the first three caliphs who had preceded 'All,

who, from the ShTi perspective, was the rightful first caliph, or successor to

the Prophet Muhammad following his death. Did Nadir's proposed change

represent some accommodation to the Sunms newly added to the empire that

now extended into Central Asia? Or accommodation to the Sunm Ottomans?

Or the contrary, to appeal to the religiously mixed population of eastern Anatolia? Or did this attempted change represent an expression of Nadir's own

broader religious views? Possibly, Nadir was attempting to strengthen his own

legitimacy, or to reassert government control over the 'ulama'.

Iran and Central Asia had a long, ancient tradition of universal, or simulta

neous, rulership 11 regardless of religious tradition, and Islamicised after the

Islamic conquests and conversions there as the basis for rulership; it was a

rulership in which the sovereign represented himself as the equipoise between

the cosmos and his realm. In this case, too, there were practical implications:

in representing himself as that universal ruler, Nadir provided a new basis by

appealing to Sunnls and as that universal ruler he was not only challenging

the Ottoman sultan in particular, but also the Mughals of India or in abandoning that position, he could appeal to the ShTa. In drawing back from his proposed changes, he was recreating new constituencies, the ^ulamd 1

and Iranians in general; Nadir Shah may have sought to placate the elites who

were becoming alienated as a consequence of his increasingly arbitrary and

oppressive rule.

Elite alienation had appeared as early as 1741, when Nadir's son, Riza Quit,

was implicated in an attempt to assassinate his father; as a result, he was blinded. Indeed, in 1747 Nadir's paranoia was borne out when he was assassi

nated by Afshar and Qajar leaders. Nadir was immediately succeeded by two

nephews, and then his grandson, Shah Rukh, who was able to maintain Afshar

rule, but only over Khurasan, from 1748 to 1796.

Nadir's legacy, if in the short term, consisted in reunifying Safavid Iran and providing some continuity in its institutions, and in successfully defending Iran from the Ottomans and the Russians. While he commanded

11 Garthwaite, The Persians, pp. 11 21; Pamela Kyle Crossley, 'The rulerships of China',

American Historical Review, orj (Dec. 1992), pp. 1468 83. In addition see Crossley, A trans

lucent mirror (Berkeley, 1999), pp. 929.

511

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Iran's political culture from his own tribal base, he was also its victim with

the continuing challenges to his legitimacy, disloyalty of those whom he had appointed to high positions, and widespread fragmentation and insta bility. He maintained his power through his military and political skills, ruthlessness and promise of booty from his many campaigns. His purpose,

aside from maintaining his own power, continues to be unresolved, and if it was to be the world conqueror, he lacked the means and resources to achieve, let alone maintain, it. Here the collapse of the Safavids, critically its economy, contributed to Nadir's problems, but these were exacerbated

by his own maladministration. And even the central institution of rulership

within his family would be short lived. Nadir's contemporaries may have feared his ruthlessness, but had expectations that with it he could establish

stability. His personality and even some of his idiosyncratic ideas and policies, including his notions regarding Shrism, were critical in shaping assessment of his rule. Emphasis on his failures and continuing instability

in Iran, however, would be recorded by those who valued order and continuity.

Nadir's immediate successors were two nephews, 'All Quli Khan, who reigned as 'Adil Shah (r. 1747) and then Ibrahim (r. 1748). All Quli, following

Nadir's death, raced to Mashhad and eliminated all possible Afshar claimants,

save for Shah Rukh, whose mother had descended from within the Safavid

family. In addition to problems in Kurdistan and Hasan Khan Qajar's rivalry,

c Adil Shah had to face an internecine challenge from his brother Ibrahim, who

had support from dissident Afshars. And when Ibrahim declared himself shah,

he was bested by Shah Rukh, who possessed greater legitimacy and power

from his base in Khurasan, and his supporters there included Hasan Khan

Qajar. Both 'Adil Shah and Ibrahim were executed in Mashhad in 1750. Shah

Rukh himself was deposed, blinded and then restored to a truncated kingdom

as a consequence of Ahmad Shah Durrani's need to protect his newly established Afghanistan formed immediately after Nadir's death from his eastern holdings from any potential changes that might emanate from central Iran.

Power and the capital of a continuingly fragmented Iran shifted from Khurasan back to the centre of the Iranian plateau under the leadership of

yet two other tribal leaders, Karim Khan Zand and All Mardan Khan Bakhtiyari. When this brief diarchy ended, another dynasty, the third in the

eighteenth century the Zand would emerge. While both Zands and Bakhtiyari shared the Turkic tribal title of khan, their respective tribal con 512

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

originated from Luristan in the west central Zagros, and the Bakhtiyari lived

further to the south west, in the central Zagros mountains and Khuzistan.

Notably, too, the pattern of Iran's political culture continued and the great

tribal confederations notably, of course, the Qajars, but also the Bakhtiyari,

QashqaT and Shahsavan 12, played roles that presaged their growing impor

tance in the nineteenth century. Some 3,000 Bakhtiyari families had been resettled in Khurasan by Nadir Shah for having threatened his rule other Bakhtiyari had participated in his Delhi campaign and after his death 2,000 of

these families are recorded as having returned to the Bakhtiyari. In the anarchy following Nadir's assassination, 'All Mardan Khan initially supported

'Adil Shah, but then gave his support to Ibrahim. Finally, along with Karim

Khan Zand, and in the face of Bakhtiyari factionalism, 'All Mardan Khan and

Karim Khan established joint suzerainty over central and western Iran in the

name of Isma'il III, yet another Safavid puppet.

The continuing importance of Safavid legitimacy for 'All Mardan Khan was

demonstrated in coins that were struck with 'bandah ye IsmcFU' ('slave /servant

of Isma'il') and in his use of the title, Vakil i Isma'il ('regent of Isma'il') that had

been used earlier by Nadir Quli before he had became shah. The diarchy ended in 1754 after only some four years when Karim Khan killed 'All Mardan

Khan, and defeated other former tribal commanders of Nadir's army, includ

ing Muhammad Hasan Khan Qajar and Azad Khan, a Ghilzai but whose power was now located in Azerbaijan. Then in 1759, Karim deposed Isma'il

III, but did not assume the title of shah; instead he first assumed 'All Mardan's

title Vakil i dawlat ('regent/ deputy of government'). Karim Khan moved his

capital to Shiraz where in 1765 he took the unusual title of Vakil i ra'aya ('regent/ deputy of the people'). 13 After this, Karim Khan is customarily known as Vakil, which suggests a kind of populism; moreover, Karim Khan

in so doing inverted the notion of universal rulership of Nadir Shah, the Safavids, and earlier Iranian and Central Asian rulers in which the shah as the

equipoise between the cosmos, or God, and their realm allowed for absolut

ism. Karim's rule, too, until his death in 1779 was more akin to earlier Islamic

notions of the just ruler than the monarchical and arbitrary universal ruler. His

period of rule was characterised by a kind of modesty that was reflected in the

buildings he had constructed in Shiraz and, importantly, he patronised Shi'ism

there, although by now the 'ulama 1 were increasingly independent of the ruler.

12 Lois Beck, Tfte Qashqa'i of Iran (New Haven, 1986); G. R. Garthwaite, Khans and shahs: A

documentary analysis of the Bakhtiyari in Iran (Cambridge, 1983); and Richard Tapper,

Frontier nomads of Iran: A political and social history of the shahsevan (Cambridge, 1997).

13 Perry, Karim Khan Zand, pp. 215 17. See also Lambton, 'Tribal resurgence', pp. 116 20.

513

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

## The New Cambridge History of Islam

Once Karim Khan had eliminated his rivals, atypically for an eighteenth century ruler he only once attacked the Ottomans and maintained a defensive

military posture rather than an offensive one. And in that one instance against Basra the Vakil may have sought to develop trade in the Persian Gulf

and to assure Bushire, with its close proximity to Shiraz, as its dominant port.

Following Karim Khan's death, the Zands competed among themselves for

succession. His immediate successor was Sadiq (r. 1779 81), the Vakil's young

est brother; Sadiq was succeeded by his grandson, Lutf 'All (r. 1789 94), the

most competent of the Zand successors. In turn, Lutf 'All was killed by Muhammad Khan Qajar, and with his death not only was the short lived Zand dynasty brought to its end, but with it the last link to Safavid Iran under

the guise of puppet shahs.

Until the advent of the Zands, the Qajars had been eclipsed by the Afshars,

but they still counted as a significant tribal power and not only in Gurgan and Mazandaran. And the shifting alliances and power among rival mid century tribal groups including Afshars, competing Qajar federations of the Develu and Quyunlu (Agha Muhammad's tribe), Zand, Bakhtiyari and the

Afghan Ghilzai and Durrani while often confusing, exemplify the nature of

Iran's political culture, especially in the absence of a strong centre. During the

short reign of Tahmasp II, Fath 'All Khan Qajar rivalled Nadir Khan Afshar

and had been given the title of Vakil i dawlat, the same title assumed next by

Nadir and then by 'All Mardan Khan. Fath 'All Khan Qajar was murdered in

1726, and his Qajar branch continued support for the Safavid pretender and for

Nadir. Qajar power shifted from the Quyunlu to the Develu's Muhammad Husayn Khan, who was challenged for dominance over the whole of the Qajar

confederation even before Nadir Shah's assassination, by Fath 'All's son Muhammad Hasan Khan Quyunlu.

Muhammad Hasan also fought against Nadir as the proponent of yet

another Safavid pretender, Sam Mirza, and, during the Afshar internecine

struggle for the throne, against 'All Quli Khan ('Adil Shah, Nadir's nephew). In

this mid century period, Muhammad Hasan was the dominant power in central and northern Iran, and played a role there, too, as a Safavid successor,

including political and cultural patronage. Meanwhile, Muhammad Hasan had

fathered (Agha) Muhammad in 1742, who was captured and castrated by 'Adil

Shah in c. 1748, but then returned to his family, where he participated in his

father's reconsolidation of Qajar power in the Caspian provinces during the

early Zand period and would later emulate his father's military and political

leadership roles and consolidation of power in the north. In 1755, Muhammad

Hasan Khan not only defeated the Abdali Afghans under Ahmad Khan,

514

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

subsequently Ahmad Shah Durrani, but continued south to occupy Isfahan

where coins were even struck in his name and went north again. During the

next two years, Muhammad Hasan re established control of Isfahan and proceeded to Shiraz to confront unsuccessfully Karim Khan, and in the ensuing aftermath lost the loyalty of key tribal allies and was killed in 1759.

Agha Muhammad was eventually seized and taken to Shiraz along with his

brother Husayn Quli Khan.

When Karim Khan Zand died in 1779, Agha Muhammad escaped from Shiraz to Mazandaran to begin the process of consolidation of Qajar power

hence the often cited date rather than his coronation date of 1796 for the

beginning of his reign from its northern base, which he accomplished by 1785, primarily against 'All Murad Khan Zand, Karim Khan's successor,

then against Ja c far Khan Zand.

Agha Muhammad's military and political achievement in re establishing Safavid Iran in terms of institutions and approximate borders is overshadowed

by his reputation for brutality and rapacity, but the shape of modern Iran

much to him. He was born into a turbulent and fragmented Iran, learned military and political survival skills campaigning with his father, and had mastered tribal and regional politics. Husayn Quli's appointment as

of Damghan by Karim Khan, his captor and rival, and then Agha Muhammad's ability to escape Shiraz were due to family alliances. Agha Muhammad established his always uneasy paramountcy within the Ouvunlu and then over the Develu federation to consolidate the Oajar confederation. From his strengthened position within Mazandaran, he encountered and outwitted the Russians, who were intent on establishing

base at the south eastern corner of the Caspian Sea, and established control of Gilan.

While Agha Muhammad was preoccupied in Gilan, an opposition

in Mazandaran, including a half brother who had thrown his support to c Ali

Murad Khan Zand, and Agha Muhammad's defeat of the Zands in Mazandaran in February 1785 opened west central Iran to him. He

Ja'far Khan, who fled Isfahan, and after taking that city, Agha Muhammad

turned north to seize Tehran, only to learn that Ja'far had reoccupied Isfahan.

A Qajar alliance with the Vali of Ardalan succeeded in forcing the Zands

to Shiraz, and this alliance would prove to be critical in maintaining

control over north western Iran, and during 1786 7 Zanjan and Gilan would

have to be rewon. Russia again was a destabilising factor here.

Throughout

the late 1780s tribal and regional leaders, often appointees, were able to

their autonomy over against both Zands and the Qajars, and Agha

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Muhammad was unable to establish Qajar control over the south even when Ja c far was assassinated in January 1789, to be succeeded by Lutf A.li

Zand (r. 1789 94).

Both the Zands and the Qajars, while competing with each other in the eighteenth century, also had to contend with challenges from within their respective families, which was especially acute for Agha Muhammad since he

had no direct heir, although he had favoured his nephew Fath 'All, even before

Agha Muhammad's brother, Husayn Quli Khan, died in 1779. In 1790, he had

ordered the execution of another brother, Ja'far Quli Khan. Had he expected

to accede to Qajar leadership, or did Agha Muhammad fear for an internecine

battle that might result in the loss of Qajar hegemony? Agha Muhammad Shah

appointed Fath Ali to important positions, and he co opted tribal leaders and

potential rivals to the succession by assigning them to a variety of governor

ships. Dynastic concern, issues of succession and legitimacy, and perhaps even

piety were factors in Agha Muhammad's decision to make pilgrimage to the

Safavid Ardabil shrine and burial place.

Lutf 'Ali took advantage of Agha Muhammad's absence in the north in 1790

and attacked Fath 'All in an attempt to retake Isfahan, but Lutf 'All lost Shiraz

in a coup to Hajji Ibrahim, of Fars, and faced insurrection in his own army.

The coup instigators proffered support to Agha Muhammad, and Hajji Ibrahim's willingness to hand over Shiraz allowed Agha Muhammad finally

to seize the Zand family, their property and Fars itself. Lutf 'All staged something of a comeback but in the end fled to Tabas. Agha Muhammad entered Shiraz in July 1792. Hajji Ibrahim was appointed beglerbegi (governor)

of Fars, hostages were taken including members of Hajji Ibrahim's family and Karim Khan Zand's body was disinterred and taken to Tehran. Given the

impregnable walls of Shiraz's Arg (fortress) and the many Qajar attempts to

breach them, Agha Muhammad had the outer ones destroyed along with the

Arg itself. Lutf 'All, from a base first in Tabas and then Kirman where he

coins struck as padishdh managed to elude Agha Muhammad for over two

years. He was finally captured and tortured, and died in Tehran; the Zand

threat to Qajar sovereignty was essentially ended. At the end of 1794/early

1795, Agha Muhammad designated Fath 'Ali beglerbegi of Fars and Kirman, for

he had helped establish Qajar authority there. Hajji Ibrahim was made vizier

and entitled I'timad al Dawla.

The borders of Safavid Iran, save for the Caucasus, were basically re established at this point in time, and with that precedent in mind Agha Muhammad set out in 1795 with a large army of some 60,000 to take the region

north of the Aras river, Qarabagh, Ganja, Shirwan and Georgia. Georgia was

516

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

not only a former Safavid dependency, but as Christian its reconquest allowed

for jihad and religious legitimacy in addition to the national one reportedly,

the Shah noma was recited at the siege of Tifiis.

The Caucasus, however, was a changing world and increasingly affected by

an expansionist Russia. Iran and the Qajars would be irrevocably challenged

by this powerful neighbour to the north. The Qajars had fruitlessly sought support from Georgia and Russia in the stand off against the Zands. Georgia,

which had become a protectorate of Russia in 1783, could only be apprehen

sive with Agha Muhammad's military success and consolidation of Qajar power, particularly after his 1791 subjection of Azerbaijan. In 1795, Russia did

not send support to Tifiis and dismissed the Qajar threat. Agha Muhammad

advanced towards Georgia and reminded its ruler of Safavid precedent for

Georgia's dependency status. After suffering serious damage, the besieged

Tifiis fell to Agha Muhammad's forces in September. The city was sacked and

its inhabitants were massacred, and some 15,000 Georgians were sent back to

Iran as slaves. After several days, Agha Muhammad returned south to the Mughan plain for the winter and then to Tehran. In the spring of 1796 the

other commonly accepted date for the beginning of his reign he accepted the

crown pressed upon him by notables.

From Hasan i FasaTs contemporary account, Agha Muhammad clearly possessed a historical consciousness and a sense of destiny. His court reminded him, in proposing his coronation, of his determination and success

in ridding Iran of all enemies and rebels save for Khurasan. He responded: 'If,

according to your desire, I put the crown on my head, this will cause you, in

the beginning, toil and hardship, as I take no pleasure in bearing the title of

king as long as I am not one of the greatest kings of Persia. This petition will

not be granted but by toil and fatigue.' 14 The Kryam crown was placed on his

head, the great diamond studded armbands clasped to his arms and pearl necklaces were draped around his neck. These jewels had been part of Nadir

Shah's booty and treasury, but even more important in the legitimating

coronation the Safavid sword 'with the blessing of the shrine of Shah Safi at

Ardabil' was girt around his waist. Similarly, the next day he wore the sword

once again at a banquet and as he distributed alms.

Agha Muhammad pressed on to take Khurasan, whose titular and long term ruler was Shah Rukh, Nadir's grandson. Power in this strategic province

was held by a variety of autonomous and rival tribal leaders and magnates,

14 Hasan i Fasa'i, History of Persia under Qajar rule (Farsnama ye Naseri), trans. Heribert Busse (New York, 1972), p. 68.

517

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

almost all of whom submitted, and Khurasan fell to the Qajars with almost no

bloodshed in May 1796. When the army reached Mashhad, Shah Rukh and the

leading mujtahid came to the Qajar camp to acknowledge Agha Muhammad's

suzerainty, and he himself entered this city of the shrine of the Imam Riza as a

humble pilgrim on foot following the precedent of Shah 'Abbas I:

with pious intention and in pure faith, he dismounted, and walking a distance

on foot entered the city . . . displaying signs of weakness, poverty, humility,

and submissiveness, and shedding tears, he walked to the shrine and kissed

the blessed soil. For a space of twenty three days he was engaged on this sanctified soil in serving God, acting obediently, and offering prayers. During

the time of his pilgrimage he served like a servant of the blessed shrine of the

venerable Emam. 15

As he had done in Shiraz with Karim Khan Zand's bones, Agha Muhammad

had Nadir Shah's bones disinterred to be reburied in Tehran. Shah Rukh died

as he was being escorted from Mashhad to Mazandaran. Consequently, the

primacy of the Qajar dynasty over the Afshars and the Zands was finally realised.

With Khurasan now under Qajar control, the borders of Safavid Iran were re established save for Herat, disregarding the short period that Baghdad had

been part of their realm. While in Mashhad, Agha Muhammad may have considered regaining Herat or even going further into Central Asia. Changes

in Russia and the Caucasus, however, intervened once again. Catherine the

Great died in November 1796, and her son and successor, Paul I, ended her

expansionist policy and withdrew Russian forces sent there at her behest. Agha Muhammad, nonetheless, turned to the Caucasus determined to lead his

troops into it, if, for nothing else, as a show offeree to forestall its governors

from closer Russian ties. Shusha capitulated to him and he entered the city;

while there, Agha Muhammad was assassinated on 16 June 1797 by two servants, whose execution had been postponed, and by a third.

Succession in the eighteenth century was always problematic, but espe daily so with assassination and without a designated successor, even though

Agha Muhammad had favoured Fath 'All. With the announcement of Agha Muhammad Khan Shah's death, family claimants and others along with their

supporters raced to Tehran to secure the capital, but its governor closed it off

to await Fath 'All from Shiraz. By the time of his arrival, he had won over most

rivals, but had his uncle c Ali Quli blinded, and then at Qazvin defeated Sadig

15 Ibid., pp. 69 70.

# Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

Khan Shaqaqi, who was pardoned in return for the royal regalia that he

acquired. Agha Muhammad's body was disinterred at Shusha, taken first to

Tehran and then to Najaf for final burial at the shrine of 'All, the first imam.

Agha Muhammad's contribution should not be underestimated nor should it be overshadowed by his brutality; the portrait of his beardless and wizened

face has become emblematic of that cruelty. That he emerged triumphant from internecine rivalry and from all of his family's enemies, especially the

Afshars and the Zands, including his own traumatic treatment by them, represents no small achievement. First and foremost, his triumph was based

on his ability to manoeuvre among and manipulate tribal and regional politics

to lead in the process of confederation building. Second, he possessed com

parable military skills and successfully dominated most of Iran. Out of neces

sity and the nature of eighteenth century Iranian political culture, Agha Muhammad was on a permanent military footing. Even after his coronation

and the institutionalisation of his rulership, Agha Muhammad's personal political and military qualities commanded awe, if not fear, rather than authority derived from legitimacy. Aside from mounted Qajar tribesmen personally loyal to him, and the Turkic tribes of Azerbaijan, 1 the key military

units were made up of cavalry from Gurgan and infantry from Mazandaran,

regions that supported Agha Muhammad throughout his life. Typically, too,

these two provinces provided their forces in lieu of taxes. His personal leadership style as well as his confidence in the loyalty of his troops are evident.

in the report that he slept among his troops at critical points.

At the height of his power in the Georgian campaigns, it is asserted that he

could muster some 50,000 regular troops, largely cavalry. His army also included a small number of cannons and light artillery. These numbers could be augmented by irregular levies and requisition of tribal levies, but

only when Agha Muhammad was successful. His military forces were most

effective in what we know as guerrilla tactics: he avoided confronting directly

troops of greater number, or better equipped, than his own. Above all his forces relied on mobility and speed and lived off the land. He exploited intertribal and regional rivalries in pursuit of particular military goals across

northern and western Iran, just as he did not hesitate to compromise or even

to entrust a specific responsibility to leaders whom he knew could not be trusted in the long run. Diplomatic skill and political and military judgement

can be seen in forming tribal and marriage alliances, and in retaining hostages

and removing whole peoples to new areas for strategic objectives. Agha

16 Lambton, 'Tribal resurgence', p. in.

519

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Muhammad's tactics reflected his careful and pragmatic assessment of the

capability of both his own forces and his enemies. His overall military strategy,

if he had one, was to maintain and expand his own power, and in Iran's political culture that was a zero sum game. After the defeat of the Zands, Agha

Muhammad's goal was the re establishment of Safavid Iran.

Safavid Iran was re established in terms of borders and rulership. The monarchy was once again instituted, but in the Qajar line. The Qajars lacked

spiritual descent from either Sufi leaders or the imams, but Agha Muhammad

was raised in a sayyid family and was outwardly pious and observant. His legitimacy as an Islamic ruler was further strengthened by titles and symbols

his name was linked with the imams on his coins. As an Islamic ruler and in the

Safavid tradition he patronised the l ulama\ constructed mosques, patronised

the arts and restored the shrine of the Imam Riza in Mashhad, where he demonstrated his piety after he secured its submission to him. That his body

was reinterred at Najaf suggests, too, his successors', and possibly even his own,

concern for traditional religious legitimacy. Furthermore, he led his troops in

jihad. And his national credentials were reinforced not just by the recreation of

borders but also by utilisation of the Shah noma to rally his troops again, on the

Safavid basis. Tehran replaced Isfahan and then Shiraz as the realm's capital.

Agha Muhammad initially relied on a most rudimentary bureaucracy of two

officials whose primary responsibilities were two: to collect revenues and to

dispense them for military maintenance. In the end, he re established a bureauc

racy utilising Zand officials, in particular, and maintained the loyalty of such

notables as HajjT Ibrahim Khan, I'timad alDawh, who functioned as prime

minister. Administration across Iran followed Safavid practice, including regional and administrative divisions, each with its historic autonomy.

After

the turbulence and misrule of the eighteenth century, responsible, if at times

ruthless, government was re established, which contributed to Qajar legiti

macy. Modern Iran is as much a Qajar construction as a Safavid one.

Agha Muhammad, of course, had no male issue. Even before the death of his only full brother, Husayn Qui! Khan, Agha Muhammad seems to have preferred his first son, Fath 'All, over him. Equally important and indicative of

Agha Muhammad's dynastic concern and for an unchallenged succession,

secured Fath 'All's marriage to a woman from the Develu clan, rivals of his

own Quyunlu one, in 1781. Similarly, in the next generation, another Develu

bride was arranged for 'Abbas Mirza. No sooner crowned, however, in March

1797, Fath 'Ali Shah (r. 1797 1834) was forced to deal with a challenge from his

own brother, Husayn Qui! Khan, beglerbegi of Fars, as well as another from the

troublesome Sadiq Khan and from Kurdish leaders.

520

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

While Fath c Ali maintained his hold on the throne from family claimants, his greatest challenge would be from Europe and then from his own subjects,

who would challenge his legitimacy as a consequence of lost territory and diminished sovereignty. The changed relationship with Europe was marked

not only by an asymmetry in military and economic power but by the Qajar's

seeming inability to recognise this imbalance. Iran's strategic location and its

decentralisation meant that British, French and Russian governments could

compete among themselves there at relatively low cost in terms of winning

imperial gains in the Middle East and India.

The impact of Europeans on Iran's economy had begun to be felt in the Safavid era, but the force of Europe's military and political power and rivalries,

combined with European economic interests, took on ever greater importance at the beginning of the nineteenth century. Despite eventual Russian

and then British support for succession within the Qajar ruling family, the

Qajars would be forced to relinquish claims over the Caucasus and eastern

Khurasan to suit Russian and British imperial aims. Moreover, Qajar impo

tence and misrule coupled with territorial losses resulted in the emergence of

a kind of cultural nationalism linked with Shi'i Islam that included a significant

role for religious leadership that had begun early in Fath c Ali Shah's reign and

would express itself throughout the nineteenth century.

The asymmetry in power and inability to recognise it and the reliance on irregular troops and tribal levies resulted not just in permanent territorial

losses but a crushing indemnity as a consequence of an ill conceived attempt

to recover them that Iran's economy could hardly afford. One significant and

long standing consequence of the indemnity and territorial losses was the emergence of anti foreign populism that was ^ulama' led and motivated by the

long standing tradition of jihad, or ghazd, in the Caucasus. Territorial losses,

the capitulations and increased European interference in Iranian domestic

affairs reinforced through direct experience the symbolic aspects of jihad and

added the new psychological ones of national and religious humiliation and a

role for the 'wkma 1 in rallying opposition to Iran's losses.

The roots for 'ulama' political activism go back to the Safavid era, 17 and

represented in their challenge to the shah, to Iran's historic tradition of ruler

ship, in which the ruler was God's representative and responsible for main

taining and protecting right religion Shi' 1 Islam, in the case of the Safavids

and subsequent rulers. The challenge operated both theoretically and

17 Andrew Newman, 'Toward a reconsideration of the Isfahan school of philosophy:

Shaykh Baha'i and the role of the Safawid ulama', Studia Islamica, 15, 2 (1986), pp. 165 99.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

theologically as well as in actuality in reaction to government failure and politics, or the loss of legitimacy to rule. The eighteenth century, once again,

provided for its transition.

The anarchy and fragmentation of late eighteenth century Iran recalls the

late fifteenth century, but Iran's reunification would then be brought about by

the Qajars, which would be the last dynasty in Iran's history to be formed from a tribal base. While the Qajars were one of the Qizilbash tribal confed

erations that early supported the Safavids, the Qajars, unlike the Safavids, had

neither claim to religious authority nor to Safavid descent. Descent within the

Qajar confederation and their political and military success were initially critical in establishing their dominance, but to rule the larger Iranian polity,

the Qajars had to legitimise themselves as Islamic rulers in the eyes of their

subjects, particularly the Shi 1! c ulama'. And it was the c ulama' that had under

gone a transformation in the Safavid period. Essentially, competing schools of

Shi'i thought had resulted in the domination of the Usuli, or Mujtahidi, school

that would increase its authority in the nineteenth century within the c ulama'

and with increasing tension with the monarch.

The issue of religious versus royal authority would result in a weakening of

the shah's legitimacy in both the eighteenth and the nineteenth centuries. In

the eighteenth century, however, royal authority was further weakened by

fragmentation and competition for power and authority, and incompetent

government. In the nineteenth century, these factors would be compounded

in the face of European domination, and the emergence of new ideas and identities.

Eighteenth century fragmentation mirrored the sixteenth, but without the

centralisation of government and institutionalisation of Shi' 1 'ulama' authority

that followed in the seventeenth century. Shi'ism, too, with its hierarchical

nature and organisation allows for competing leadership. In addition, that

leadership was further divided by legal, theological and philosophical differ

ences over the nature of L ulama' authority; such differences were accentuated

by Sufism and popular religion.

From the beginning of the sixteenth century, high ranking Shi'i 'ulamff enjoyed a mutually privileged position with the Safavids that reinforced their

legitimacy. Government appointments were important forms of state patron

age, a role not neglected by eighteenth century rulers, especially so since they

individually lacked the legitimacy of the Safavids. In the Safavid period, the

very basis of their rulership would even be questioned by some 'ulamd': that

the shah embodied both political and religious authority. Initially, too, in the

Safavid period, the shah was seen in popular religion as representing the

522

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

infallible imam. Some rulers linked their dynastic descent with descent from

the imams and with notions of just rule. c Ulamd\ too, took issue with popular

Islamic expressions. Safavid shahs periodically stepped back from aggravating

the c ulamd\ who played important stabilising roles, especially in urban society.

While ideas on authority were contested, the most significant theological legal dispute centred on sources and their interpretation between two emerg

ing schools of thought: the Akhbaris and the Usulis /Mujtahidis. Central were

the interpretation of two principles of jurisprudence (fiqh): taqBd and ijtihdd;

the former articulated the authority of those most learned in jurisprudence,

and the latter required the exercise of rational judgement, or disciplined reasoning, again of those most learned in jurisprudence. 1 Both principles

recognised the authority vested ultimately in those in the hierarchy who exercised ijtihdd, hence holders of the rank of mujtahid, or the most learned

of jurists.

The Akhbaris rejected the use of both principles and based their interpre tations and rulings only on the traditions akhbdr or hadith transmitted by the imams, and the Usulis usul, roots/principles (of jurisprudence) allowed

for reinterpretation of the traditions by mujtahids. Furthermore, the Akhbaris

argued that ijtihdd was restricted to the imams. The Usulis emerged as dominant in late Safavid history, and as an elite within the 'ulama' to reflect

a hierarchical view of authority and of society. And the Usulis are the ones to

challenge the shahs' authority, although like the Akhbaris they historically

acquiesced to the reality of the shah's de facto power. Usuli domination was

assured late in the Safavid period, although the role of the great mujtahid

Muhammad Baqir Majlisi (d. 1700) in this process has been challenged by

recent scholarship. 19 Majlisi's writings and power within the establishment

allowed for a frontal attack on the Akhbaris, philosophers, Sufis and popular

Islam in general.

A third 'ulamd' group emerged in the Safavid period as well, and these were

philosophers notably Mir Damad (d. 1631) and Mulla Sadra (d. 1640) whose

mystical and philosophical bases could put them at odds with the Usulis in

particular. Like the Akhbaris, the philosopher mystics were politically

18 Andrew Newman, 'The nature of the Akhbari/ Usuli dispute in late Safawid Iran. Part

One: 'Abdallah al Sahahiji's "Munyat al Mumirisin",' Bulletin of the School of Oriental and

African Studies, 55, 1 (1992), pp. 22 51; Newman, 'The nature of . . . Part Two: The conflict

reassessed', Bulletin of the School of Oriental and African Studies, 55, 2 (1992), pp. 250 61.

19 Juan Cole, 'Ideology, ethics and philosophical discourse in eighteenth century Iran',

Iranian Studies, 22, 1 (1989), pp. 7 34; Cole, 'The world as text: Cosmologies of Shaykh

Ahmad al Ahsa'i', Stadia Islamica, 80 (1994), pp. 123.

523

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

quiescent, but were also given high religious offices. A philosopher mystical

school in the mid eighteenth to early nineteenth century emerged as the result

of the teachings of Shaykh Ahmad Ahsa'i (1753 1826), 2  $^{\circ}$  who left Bahrayn to

study in Najaf and Karbala 1 and then travelled widely in Iran where he enjoyed

acclaim, including royal and notable patronage. His followers became known

as the Shaykhis, and during his lifetime he claimed direct communication with

the imams through his mystical practice; after his death, his followers became

increasingly radical in their dissent and activism.

A case for political activism, however, was advocated as early as the reign of Shah Tahmasp (1524 76), by the important mujtahid Shaykh 'All b.

Husayn b. [ Abd al All al Karaki (d. 1534), who was even given the authority to

make key clerical appointments. 21 This idea seems to have been expressed

when Isma'il II addressed the mujtahid at his coronation in 1576: 'This kingship

(saltanat) in truth belongs to the imam, the sahib al zaman [Lord of the Age] . . .

and you are the na'ib [deputy] appointed in his place ... to put into operation

the decrees of Islam and the shari'a. You spread the carpet for me and seat me

on the throne ... so that I may sit on the throne of government and rule by

your decision and will/ 22. And the mujtahid was quoted as muttering that he

was no one's servant; if so, this underscores the tension between competing

authorities. This tension was expressed by Sir John Chardin late in the seventeenth century: 'The highest throne of the universe is only fit for a mouchtehed [mujtahid], someone who possesses more holiness and knowledge

than common people. Since the mouchtehed is holy, and consequendy a peaceable person, a king is needed who can wield the sword to exercise justice, but he can only be his [the mujtahid's] minister and must be dependent

on him.' 23

Moreover, the emergence of increased 'ulam<P authority also meant greater

political, economic and social power for them within Iran and without. For

example, after the loss to the Ottomans of the shrine cities ('Atabat) of Irag,

notably Najaf and Karbala', they became vital centres of Shi 'i learning and

authority independent of Iranian governments. In addition, the collection of

21 Andrew Newman, 'The myth of the clerical migration to Safawid Iran: Arab Shi'ite

opposition to 'AM al Karaki and Safawid Shi'ism', Die Weltdes Mams, 33 (1993), pp. 66 112;

Said Amir Arjomand, 'Two decrees of Shah Tahmasp concerning statecraft and author

ity of Shaykh Ali al Karaki', in Said Amir Arjomand (ed.), Authority amipolitical culture in

SM'ism (Albany, 1988), pp. 250 62.

22 Ann K. S. Lambton, State and government in medieval Islam: An introduction to tfte study of

Islamic political theory: The jurists (Oxford, 1981), p. 277.

23 Cited in Heinz Halm, Shi'ism (Edinburgh, 1991), p. 95.

524

Cambridge Histories Online © Cambridge University Press, 201 1

Transition: Iran in the eighteenth century

khums (one fifth) by the 'ulamff helped to make them economically independ ent of government as well.

As the Safavid state withered in the eighteenth century, the one institution

that carried Iran into the nineteenth century was the 'ulamff, who had become

centralised and increasingly independent of government both in theory and  $% \left( x\right) =\left( x\right) +\left( x\right) +$ 

out of necessity under the mujtahids. ^Ulamd 1 continuity over that period was

typified by the lifespan of the great mujtahid Agha Muhammad Baqir Wahid

Bihbahani (c. 1705 91), who was responsible for the ultimate Usuli victory over

the Akhbaris in the 'Atabdt. The Akhbaris virtually disappeared; however, something of an amalgam of Akhbari thought with Safavid mystical philoso

phy would emerge in the early nineteenth century with the Shaykhis. Despite

the ^ulamff's disapproval of Sufism and popular religion, most Iranians found

comfort in their many forms. 24 While the martyrdoms of the early imams had

long been commemorated, dramatic expression of them, tcfziya? 5 emerged in

this period of transition from the Safavids to the Qajars. The use of the various

Safavid pretenders throughout most of the eighteenth century also repre sented the popular appeal of descent and of rulership legitimised by both religion and tradition. In this instance, too, Karim Khan Zand's appropriation

of the title, Vakil i ra l aya, 'representative of the people', possibly relates to the

government's inherent responsibility to its populace. At the beginning of the

nineteenth century, populism would express itself in religious terms, but at

the end of the century nationalism would indicate a new direction for Iranian

identities. In the end, continuity and transition in the eighteenth century were

to be found in the land of Iran and its peoples and political culture. In the nineteenth, Iran's political culture would undergo continuing change, but the

most profound change would come in the twentieth century with the emer

gence of the first non tribally based dynasty, the Pahlavis, who would ulti mately be confronted by revolution and by radical religious thought, whose

origin goes back to the late seventeenth and eighteenth centuries.

24 Juan Cole, 'Shi'i clerics in Iraq and Iran, 1722 1780: The Akhbari Usuli conflict recon

sidered', Iranian Studies, 18, 1 (Winter 1985), pp. 334.

25 Peter J. Chelkowski (ed.), Taz'iyeh, ritual and drama in Iran (New York, 1979).

Cambridge Histories Online © Cambridge University Press, 201 1

**PART IV** 

**THEMES** 

Cambridge Histories Online © Cambridge University Press, 201 1

15

Conversion to Islam

RICHARD W. BULLIET

### Introduction

Though it is self evident that over the centuries many millions of people have

changed their religious identity from non Muslim to Muslim, a majority of them

since the turn of the twelfth/sixth century in lands east of Iran, scholars under

stand the word 'conversion in a variety of ways and use differing approaches in

their studies of these changes. One person considers conversion to involve a

deeply felt personal change in religious belief; another simply counts the growth

over time in the number of people who consider themselves, or are considered by

others, to be Muslims and infers that conversion has taken place. One person

collects stories or legends about conversion experiences; another analyses social

and economic circumstances to explain the growth of the Muslim community.

The method chosen sets limits on the conclusions that can be reached. Just as

stories about individuals cannot be relied on to explain mass phenomena, eco

nomic data and quantitative modelling say nothing about spiritual experience.

Complicating the matter still further, studies of conversion often take it for

granted that converts to Islam move from one known entity to another, while

in fact both Islam and the religions from which new converts come change

over time and in response to their relative position in society. A person who is

among the first in a community to convert to Islam is in a very different position from the person who is the last in the community to change religions,

and almost certainly acts from a different motivation. Furthermore, Islam itself, even with an unchanging scripture and a fairly constant theology, appears different when it has newly arrived in a locality from the way it appears when it has been a common social identity for several centuries. In the

first instance, for example, it may be the religion of a conquering elite or of a

wandering holy man, whereas in the second it is considered part of tradition. 1

i Richard W. Bulliet, 'Process and status in conversion and continuity', in Michael Gervers

and Ramzijibran Bikhazi (eds.), Conversion and continuity: Indigenous Christian communities

in Islamic lands, eighth to eighteenth centuries (Toronto, 1990), pp. 112.

529

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Finally, studies of conversion often assume that the religious identities of individuals and groups are clear cut and that change from one identity to

another is as unambiguous as turning an electric switch on or off. Yet there is

ample evidence that some people waver between religions, adopting one identity in one situation or at one moment in time and another when the situation changes. And it is similarly apparent that there are halfway houses

between religions in which beliefs from more than one tradition mix together.

In addition to all of these complications, the study of conversion to Islam is

burdened by tales and assumptions that have little basis in fact. Fortunately,

the 'conversion by the sword' stereotype has largely died away. But the notion

that new converts are normally zealots, like the contradictory notion that new

converts are insincere and not really Muslim, is still encountered.

Given these problems, no general history of the whens, hows and whys of conversion is possible. In the place of such a history, an assessment of current

analytical approaches and of the types of conclusions that can be reached through different methods quantitative, economic, literary and institutional

must suffice.

# Quantitative analysis

Despite modern censuses, no one knows today how many Muslims there are

in the world, much less the demographic breakdown between Sunms and ShTites. How much more difficult it is for historians of earlier periods to find

reliable census data. Thus quantitative approaches usually depend on analyt

ical modelling rather than counting heads. Some models derive from patterns

of growth that have been observed in modern studies of innovation diffusion. 2

S shaped curves portray conversion as beginning slowly and then accelerating

into a bandwagon surge of conversion in the middle portion of the curve only

to taper off as the number of people left to convert diminishes. The logic behind this model assumes that each individual makes a decision to change religion based on access to convincing information or persuasion by an influential personal contact. Early growth proceeds slowly because, in the

absence of broad literacy and mass media, word of mouth is the primary source of information, and persuasion and informants are few. Language barriers slow diffusion yet further, a factor that accentuates the role of non

Muslim women, whether wives or concubines, who have children with

2 Richard W. Bulliet, Conversion to Islam in the medieval period (Cambridge, 1975) pioneered this approach.

530

Cambridge Histories Online © Cambridge University Press, 201 1

#### Conversion to Islam

Muslim men. The bilingual offspring of such unions are considered Muslim in

Islamic law and are often better equipped than their fathers to explain the faith

to potential converts.

Historians who take this innovation diffusion model as a hypothesis rely on

data that can be interpreted as fitting the slow early phase, the bandwagon middle

phase or the tapering off phase of the curve. 3 But data are seldom abundant or

systematic enough over a long period of time to demonstrate the validity of the

model directly. Moreover, the model's assumptions that people decide individ

ually on conversion, as opposed to changing religious identity as part of a community, and that conversion normally takes place in the definitive and

unambiguous fashion of an off on switch, may not be valid for many societies.

Another kind of diffusion model visualises conversion radiating outward

from nodes of initial Muslim presence, such as royal courts, military camps,

urban centres or Sufi shrines. 4 The assumption behind this model is that people who live close to such nodes feel pressure to convert, see opportunities

in conversion or gain access to information about the new faith sooner than

people who live in more remote locales. The growth of the convert com munity can thus be modelled as a series of chronologically sequenced con centric circles emanating from each node until the circles from different nodes

eventually overlap. Unfortunately, few bodies of data contain the chronolog

ical and geographical specificity needed to demonstrate the validity of this

model. Moreover, the model cannot easily accommodate collective change of

religious identity by an entire community. Thus it is generally more useful for

orienting the historian of conversion than for guiding empirical research.

## Economic analysis

Traditional approaches to the economic dimension of conversion involved either the idea that economic opportunities available to new converts induce

them to abandon their original faith, or that the head tax (jizya) collectible by

Muslim governments from people of the book primarily Jews and Christians, but sometimes including Zoroastrians, Hindus or others promp

ted conversion as a form of tax avoidance. Biographical accounts of govern

ment officials or military officers whose careers necessitated conversion to

3 See, for example, Anton Minkov, Conversion to Islam in the Balkans: Kisve bahasi petitions and Ottoman social life, i6yo 1730 (Leiden, 2004).

4 Richard W. Bulliet, 'Conversion based patronage and onomastic evidence in early

Islam', in M. Bernards and J. Nawas, Patronate and patronage in early and classical Islam

(Leiden, 2005), pp. 246 62.

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

Islam substantiate the first of these scenarios in particular cases, but it is difficult to prove a general link between conversion and economic opportu

nity. As for the second scenario, concrete evidence is generally lacking, and

there is no way of determining why some people remain steadfast in their ancestral religion while others in the same community are willing to renounce

it for economic gain. A third scenario, in which the Muslim government, or

local Muslim communities, offers financial rewards for conversion, does appear in the historical record; 5 but it seems to be uncommon.

A more sophisticated economic approach that has a strong foundation in quantifiable data involves the growth of the Muslim community in east Bengal. Richard M. Eaton has demonstrated a link between religious con version and the spread of rice farming in that area. Zamindars, Mughal govern

ment officials entitled to collect the revenues from specific tracts of land, engaged local religious figures to assemble workers, establish a village, clear

the land of jungle and plant rice. A few of these entrepreneurs were Hindus,

but most were Muslims, and they used religion to advance their activities. The

locally available labourers typically worshipped gods and goddesses from their

tribal traditions. Eaton found that the inhabitants of the new rice villages adopted the religion of the entrepreneur, even though their understanding of

that religion included many features of their previous cults, such as viewing

Muhammad as an incarnation of Vishnu. In this way, east Bengal became home to one of the largest populations of Muslims in India, but the content of

the Islam practised there was initially quite eclectic.

It is unlikely that east Bengal was the only place where agricultural develop

ment, or some economic activity associated with Muslims, correlated directly

with conversion to Islam; but examples of such developments cannot be expected to apply beyond specific subregions.

## Literary analysis

The Islamisation of the Turkic societies of Central Asia has long been a historical conundrum. However, a detailed folkloristic analysis by Devin DeWeese has reframed the question in a stimulating new way. 7 In 712/1313

Uzbek Khan became the ruler of the Golden Horde, a Mongol state

5 See for example the Ottoman practice of giving a sum of money (kisve haha) to new converts in Minkov. Conversion.

6 Richard M. Eaton, The rise of Islam and the Bengal frontier, 1204 1760 (Berkeley, 1996).

7 Devin DeWeese, Islamization and native religion in tfte Golden Horde: Baba Tiikles and conversion to Islam in historical and epic tradition (University Park, PA, 1994).

532

Cambridge Histories Online © Cambridge University Press, 201 1

#### Conversion to Islam

established in southern Russia by a grandson of Chinggis Khan. Tribal traditions among Central Asian peoples who trace their descent from the Golden Horde agree that Islamisation became common during Uzbek's reign,

even though the fourth Golden Horde ruler, Berke, had personally converted

half a century earlier. Early literary sources attribute Uzbek's conversion to a

Sufi named Sayyid Ata, just as they say that Berke converted at the hands of a

Sufi named Sayf al Dm Bakharzi. Nothing substantial is known of either of

these individuals, but their legends support the idea that Sufis were important

agents of conversion in the Turkic world. At the time these events took place,

Sufi brotherhoods had not yet formed, so these holy men, whose presence in

Mongol camps is attested to by European Christian travel accounts, were presumably acting individually.

DeWeese's work concentrates not on these early tales, but on a more detailed legend of a person named Baba Tiikles that gradually gained enough

popularity to become the dominant conversion story by the tenth/sixteenth

century. In that story, four Muslims who had been inspired by God to convert

Uzbek arrived at his coronation and disrupted the traditional rituals. Uzbek's

shamans and diviners urged him to kill the Muslim intruders, but he proposed a

test instead. Two ovens would be stoked. A Muslim would enter one, and one

of the diviners the other. Baba Tiikles volunteered for the test on the Muslim

side while the diviners simply tossed in one of their fellows, who was promptly

incinerated. Baba Tiikles put on his chain armour and entered the oven reciting

his Sufi chant (dhikf). Then, according to the tenth/ sixteenth century text:

When it was presumed that the sheep's flesh [suspended over the oven] was

fully cooked, they opened the mouth of the oven; and Baba, wiping the sweat

from his blessed face, came out of the oven, saying "Why did you hurry? If

you had held off for a time, my business [of reciting the dhikr] would have

been finished.' They saw that the armor was blowing red hot, but by the power of God most high not a hair of the Baba's body was burned. When all

the people, beginning with the Khan, saw this situation, they at once grasped

hold of the hems of the shaykhs' [Muslim holy men's] garments and became

Muslims; praise be to God for the religion of Islam!

DeWeese recognises that these (and other) conversion narratives preserved

in literary sources have little value as historical fact, but he finds them valuable

objects of study nonetheless:

We are thus not so much concerned with the extent to which the narrative

elements  $\dots$  'accurately' reflect historical events or practices  $\dots$  Rather, we will

8 Ibid., pp. 155 8.

533

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

assume that the themes evoked in the narrative reflect religious counterpoints

in the meeting of Islam and indigenous traditions, not 'as they were,' but as they

were imagined among later generations. It is in light of this assumption that we

may fully explore the religious meaning provided by the conversion narrative

for Islamic, or Islamizing, communities in Inner Asia, without being inordin

ately troubled by the lack of historical evidence ... In the final analysis, even

though we may find signs of the 'practical' encounter of Islam and indigenous

traditions, our chief concern is with the narrative response to that encounter. We

want to know how the communities most directly affected by the simultaneous

confrontation and assimilation of the two traditions talked about the process

and made sense out of it, ... this, after all, was a substantial, though too little

appreciated aspect of the 'practical' encounter of Islamic and Inner Asian traditions, with quite real historical consequences. 9

What this approach to conversion highlights is the importance of interaction, in areas of large scale conversion, between Muslim and non Muslim communities and traditions, and of the way that interaction became inscribed

in literary texts, sometimes long after the events. For eastern regions that

experienced such waves of conversion between the fifth/ eleventh and twelfth/ eighteenth centuries Central and Inner Asia, China, India, peninsu

lar and island South East Asia and the Philippines demographic and chrono

logical questions, some of them long debated, pale beside the question of the

way Islam accommodated local traditions, or vice versa. Thus this literary approach using manifestly legendary materials holds great promise for under

standing the texture of conversion and community building.

# Institutional analysis

Institutional analyses focus on networks of people who are believed to play a

role in conversion. Travelling merchants, Sufis or scholars are the groups most.

commonly mentioned. With respect to the latter two, the character of the Islam communicated plays a role in many analyses. Inasmuch as the particular

teachings or orientations of Sufi brotherhoods and scholarly networks are

often known, looking at them as agents for changing religious belief some

times involves the conversion of Muslims from one type of Islam to another,

rather than non Muslims to Islam. In the Muslim heartland of the Middle East.

and North Africa, this type of activity would be treated as part of the history of

sectarian development. But in more eastern lands where questions have been

9 Ibid., p. 162.

Cambridge Histories Online © Cambridge University Press, 201 1

#### Conversion to Islam

raised by both Muslims and non Muslims about the genuineness of the Islam

professed by new converts, the efforts of these networks to upgrade or purify

Islam can be woven into the history of conversion.

South East Asia serves as a microcosm for studying these approaches, though other regions offer parallel cases. Historians have speculated about

the coming of Islam to Indonesia, where there is no history of conquest or of

sharing a land border with a Muslim state. Scraps of information drawn from

narrative sources, tombstones and rulers' names, and inferences from the

dominant position of the Shafi'i law school, have been interpreted to pinpoint

Gujarat in north west India, Bengal in north east India or southern Arabia

the original source of Islam in the archipelago. But these scanty data do not

explain how and why Islam spread from a few coastal locales.

Since Muslim trade with South East Asia, like trade with southern China, is

attested from very early in Islamic history, some analysts surmise that travel

ling merchants spread Islam, persuading coastal rulers that their conversion to

Islam would benefit their seaports and even intermarrying with the rulers'

families. Unfortunately, for the period prior to the tenth /sixteenth century,

too litde is known about the organisation of trade to flesh out these surmises:

and there is little concrete evidence that Muslim merchants took a particular

interest in spreading the faith. The early Muslim merchants who took up residence in southern China, for example, seem not to have triggered a wave

of conversion, though they were part of the same commercial networks that

traded with Indonesia. In Central Asia, where merchants have also been suggested as agents for the spread of Islam, no one has produced concrete

evidence that proselytising was an important or systematic activity.

The case for Sufi brotherhoods proselytising in Indonesia and elsewhere is

much stronger because unlike merchants except when the merchants themselves were also Sufis the Sufis made religion their main calling and focused their efforts on building faith communities. However, fully devel oped Sufi brotherhoods did not appear in the Middle East until the seventh/

thirteenth century, and there must certainly have been a time lag before Sufi

networks reached lands as far away as Indonesia or China. Once they arrived,

their activities can sometimes be traced. But whether the followings they attracted were new converts to Islam, or people who already considered themselves Muslim, is difficult to determine. In the Muslim heartland, after

all, the great preponderance of those who were attracted to the Sufi way of

life were already Muslims, and in both China and Indonesia fragmentary evidence shows that some sort of Muslim community was already present several centuries before the eighth/ fourteenth century. In addition, Sufism

535

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

cannot be considered a uniform phenomenon, for the brotherhoods differed

substantially in their rituals, organisational complexity and interpretations of Islam.

In his overview of the history of Islam in China, Joseph Fletcher identified three tides, the first two of which are relevant here. 10 The first tide stretched

from the first/seventh to the eighth/fourteenth century and consisted of small, independent communities clustered around a mosque. These commun

ities descended from Muslim traders, military men and officials of various ethnicities, many of whom entered China during the Mongol Yuan dynasty in

the seventh /thirteenth century. The degree to which conversion of the local

population played a role in the establishment and survival of these commun

ities is indeterminable.

Fletcher's second tide began with the activities of Sufi brotherhoods, probably in the eighth/fourteenth century, but did not make a major impact

on Islam in China until the late eleventh/ seventeenth century. Sources are

available to study the spread of these Sufi networks from roots in the Middle

East, but, as in Indonesia, it is hard to distinguish their proselytising activities

from their reinvigoration of pre existing Muslim communities. Thus while the

general role of Sufis in spreading Islam is unquestioned, data for making direct

connections with conversion are seldom readily available.

Turning to the role of scholarly networks, the work of Azyumardi Azra on the spread of reformist Islam to Indonesia stands out. 11 Samudera Pasai, a

kingdom in northern Sumatra, became a centre for Muslim learning in the late

seventh/thirteenth century, some 200 years after the dates on the earliest

Muslim tombstones found in the archipelago. Despite the efforts of pious monarchs, however, formal religious learning did not spread widely. Azra demonstrates that Indonesia did not become fully integrated into the world of

Islamic scholarship until the eleventh/ seventeenth century when pilgrims

returning from several years of study in Mecca, often involving initiation into a Sufi order, set about teaching Islam in a more authoritative fashion. The

sources he draws upon are voluminous, but it is not clear how the activities of

this network should be interpreted from the standpoint of conversion. Just as

10 Joseph Fletcher, 'Les voies {turuq} soufites en Chines', in A. Popovic and G. Veinstein

(eds.), Ordres mystiques dans VIslam: Cheminements et situation actuelle (Paris, 1986). An

excellent discussion of Fletcher's work is contained in Dm C. Gladney, Muslim Chinese:

Ethnie nationalism in the People's Republic (Cambridge, MA, 1991), pp. 36 59.

n Azyumardi Azra, Tfte origins of Islamic reformism in Southeast Asia: Networks of Malay Indonesian and Middle Eastern 'ulama' in the seventeenth and eighteenth centuries (Crows Nest, NSW, 2004).

536

Cambridge Histories Online © Cambridge University Press, 201 1

#### Conversion to Islam

DeWeese argues that an analysis of how a community remembers the con version stories of bygone rulers can be used to diagnose the evolving relation

ship between Islam and non Islam, as cultural traditions, if not demonstrably

as faith communities, so Azra maintains that the propagation from Mecca of

this more authoritative 'reformist' version of Islam relates significantly to how

an earlier Islamic current that was more accommodating to local tradition

evolved over time.

### Conclusion

The original spread of Islam in the Middle East, North Africa and Andalusia

took four to five centuries. Those who became Muslim in the first/seventh

century clearly were joining a different religion from the one other converts

joined three centuries later. However, because the elaboration of Sunm and

Shi'ite Islam, the Sunm law schools and a variety of sects is normally treated as

a separate historical subject, it is usually taken for granted that the simple fact

of a change in religious identity is the central question in the history of conversion. By the sixth/twelfth century, when this first wave of conversion

had plateaued in the heartland, most of the major institutional and intellectual

developments within Islam had become manifest, though the elaboration of

Sufi mystical experiences into full blown brotherhoods was still on the hori

zon, as was the revival of neo Platonist philosophy in Iranian ShTism. Thus the

Islam that spread far to the east from the sixth/twelfth century onward was no

longer a 'work in progress' as it had been several centuries earlier.

The sense that Islam was a known and fully developed entity during this later period has obscured the fact that the same sort of accommodation with

local tradition that occurred when the legacy of Hellenistic culture entered

and altered Islam during the early Islamic centuries was bound to be mirrored

in the regions where Islam entered into its growth curve relatively late. The

types of analysis summarised above tacidy recognise this. Even if the sources

were available to determine the precise percentages of Muslims in the Central

Asian, Chinese, Indian or south eastern populations at any point in time, the

characteristics of the faith professed by those Muslims would be seen to change over time, to such an extent that modern observers sometimes disparage segments of the earlier (and even the present) Muslim communities

as merely 'nominal' adherents to Islam. (The term 'nominal' might well have

been applied to segments of the Middle Eastern, North African and

Andalusian Muslim communities in the ninth/fifteenth century.) One of the

537

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

values of the approaches of Eaton, DeWeese, Fletcher and Azra is that conversion is seen not just as a demographic matter, but as an accommodation

over time between Islam and the peoples it is drawing into its orbit. The process of accommodation, and the organisational forms by which accommodation comes about, represent the frontier of conversion studies in the lands of the east.

538

Cambridge Histories Online © Cambridge University Press, 201 1

16

Armies and their economic basis in Iran and the surrounding lands, c. iooo 1500

**REUVEN AMITAI** 

Who hath raised up one from the East,

At whose steps victory attendeth?

He giveth nations before him,

And maketh him rule over kings;

His sword maketh them as the dust,

His bow as the driven stubble. Isaiah, 41:2

One salient theme in the military, political and social history of the eastern

Islamic world of the late Middle Ages and early modern period is the alteration

and even tension between nomadic and standing armies. By the first men tioned, I am referring to armies that are based primarily on soldiers who normally live as pastoral nomads and can be called up to serve at need, as

opposed to the latter, armies based in cities, composed of more or less pro

fessional soldiers. The former mainly receive their livelihood from their pastoral occupations while the latter draw either salaries or revenues derived

directly from land allocations under their control. This chapter will revolve

around this alternating military situation in various regimes and territories,

looking also at the way armies were paid or otherwise supported.

Geographically, Iran more or less defined as the country within the boundaries of the present Islamic Republic, but also including a wide swathe

of northern modern Afghanistan and all of Turkmenistan is at the heart of our discussion. At the same time, the effective influence (and thus the arena

for the activities of the military) of these states based in Iran could extend

much further to the east, north or west. Thus under the Saljuqs and Mongols

we must include most of Anatolia, al c Iraq, al Jazira (Upper Mesopotamia) and

the southern Caucasus region as part of our canvas, and for the Timurids. we

cannot forget their original stomping grounds, Transoxania. With the Safavids, however, we approach a territory enjoying something like the modern borders of Iran (see Map 5).

539

# The New Cambridge History of Islam

Even a casual student of Islamic history will note that the Turkish involve ment with the region's history did not begin with the arrival of the Turcoman

tribes under Saljuq leadership in the early eleventh century. Already from the

first half of the ninth century the 'Abbasid caliphs had employed Turkish slave

troops, known generally then as ghilman (plural ofghuldm, literally a 'youth').

Modern scholars are far from holding a consensus about the origins and early

development of military slavery in the Islamic world, but there is no denying

its importance in the military, political, social and economic life of the caliph

ate, and its contribution to the increasing crisis in these areas from the mid

ninth century onward. Military slaves, again mostly Central Asian Turks (also

referred to as mamalik, plural of mamluk, an 'owned one'), also played an important role in the armies of the various successor 'states' to the united

caliphate, from Egypt to the east. Without denying their significance and even

prominence, however, mamluks (to which we will henceforth conveniently, if

at times anachronistically, refer to these slave troops) were never alone in any

army, composed also of other professional soldiers, civilian militias and other

volunteers, and nomadic auxiliaries. Yet, we can state that a clear trend can

already be discerned in the ninth and tenth centuries which would come to

fruition in the subsequent eras: the increasing status and then predominance

of troops of Central Asian provenance be they nomads or professional soldiers, the latter mostly of slave origin or status.

The title of this chapter should be noted. There can be no discussion of the

military without an examination of its financial basis: how were the officers

and soldiers equipped and paid? At the same time, we should remember that

probably the main recipient of the tax revenues of a pre modern state (and not

just in the Middle East) was the army. Often, as will be seen below, the officers

themselves directly managed the collection of taxes from land and elsewhere,

which went straight into their coffers for the upkeep of their households and

units. The subjects of military history and tax policy (and by extension the

system of land tenure) are therefore inextricably connected.

## The Saljugs

Under the aegis of the Saljuq family, relatively large numbers of Turkish tribal

groups crossed the Syr Darya (Jaxartes) river from the Eurasian steppe region

from the early eleventh century onward, then spreading into Iran and adjacent

regions. These tribal groups, mostly of the Oghuz (Arabic: Ghuzz) tribe, converted to Islam at some point (probably on the whole before entering the Muslim world), maintained their tribal framework and pastoral nomadic

540

Cambridge Histories Online © Cambridge University Press, 201 1

# Armies and their economic basis in Iran

lifestyle, and were known by the name of Turcoman (Arabic: turkuman; often

rendered in the plural tarakima; cf. modern Turkish: tiirktneri). 1 Like Inner

Asian invaders and raiders before and after them, the early successes of the

Saljuq princes were based on the use of disciplined masses of mounted archers, the hallmark of Inner Asian warfare for probably two millennia before

the advent of this dynasty. 2 Before proceeding to examining the early Saljuq

army, it would be instructive to cite one Muslim author who commented on

the military abilities, especially the archery, of the Turkish nomads (although

from almost two centuries before the arrival of the Turcomans in the Islamic

world). The Baghdadi belletrist aljahiz (d. 869) wrote in his essay on the 'Virtues of the Turks', where inter alia, the Turkish warrior is compared to the

Arab Kharijite rebel:

[The Turk] shoots [with his bow], while he lets his mount go at full gallop, riding backwards and forwards, right and left, going up and down. He lets off

ten arrows, before the Khariji can lift even one arrow [to his bow string]. The

Turk rides his mount down off the hill or down into the valley better than the

Khariji can do on flat ground. The Turk has four eyes: two in the front and

he does when he faces forward . . . The Turk on a raid has with him everything

that he will for himself, his armour, his beast and the apparatus of his beast

His endurance for riding and continuous travel, for night long journeys and

crossing the country are truly amazing . . . And if at the end of a Turk's life,

one were to calculate his days, one would find that he sat on the back of his

mount more than he had spent sitting on the earth. 3

Of course, we should remember that this is from a polemical text, part of the discussion in mid ninth century Iraq about the role of the Turks, and there

1 For the etymology of this term, see B. Kellner Heinkele, Turkmen', EI\*, vol. X, p. 682;

P. B. Golden, An introduction to tfte history of the Turkic peoples: Ethnogenesis and state

formation in medieval and early modern Eurasia and the Middle East (Wiesbaden, 1992),

pp. 212 13.

2 On the military abilities of the Turks, as well as the Eurasian Steppe nomads in general,

see D. Sinor, 'The Inner Asian warriors 'Journal of the American Oriental Society, 101 (1981),

pp. 133 44; P. B. Golden, 'War and warfare in the pre Cinggisid western steppes of

Eurasia', in N. Di Cosmo (ed.), Warfare in Inner Asian history (;00 1800) (Leiden, 2002),

pp. 105 72, as well as the editor's comments in the 'Introduction', pp. 1 12.

3 Abu 'Uthman b. Bahr aljahiz, Taldth rasa'il (Leiden, 1903), pp. 28 9; cf. the translation

in C. T. Harley Walker, 'Jahiz of Basra to al Fath ibn Khaqan on the "Exploits of the

Turks" and the army of the khalifate in general', Journal of the Royal Asiatic Society (1915),

pp. 666 7. See the discussion in M. V. McDonald, Al Gahiz and his analysis of the Turks',

in U. Vermeulen and J. M. F. van Reeth (eds.), Law, Christianity and modernism in Islamic

society (Leuven, 1998), pp. 27 38. The Khariji refers to a member of the revolutionary sect

in early Islam, mainly composed of Arab tribesmen, known collectively as Khawarij.

541

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

is no question of the pro Turkish perspective of the author. But although there

may have been questions about the contributions of the Turkish slave troops

to the political instability of the capital (as well as resentment from other military elements at their power and prestige), there is no doubting their military abilities. 4

Composed of such hardy mobile fighters possessing great 'firepower', the

Saljuq armies were able to advance virtually unimpeded, from the Oxus river

across Iran to Baghdad in 447/1055. We have few exact figures for the size of

these mostly Turcoman armies, but they probably numbered not much more

than 10,000 at a given time, since it is unlikely that significantly more than

several tens of thousands of nomadic families actually immigrated into the Muslim world in the first half of the eleventh century. At Dandaqan in 431/1040, the Saljuq army under the princes Toghnl Beg and Chagri Beg reportedly contained about 16,000 men, which was able to outmanoeuvre the

larger and better equipped (but exhausted) Ghaznavid force that included

over a hundred elephants. The Ghaznavid force was led into the dry plain north of Marv, where it met its demise, thus sealing the fate of the Ghaznavid

state in Khurasan. 5

Virtually nothing is known of the organisation of the early Saljuq army, although it probably remained arranged according to earlier tribal organisa

tion under traditional chiefs. The troops would have appeared to have main

tained themselves by their own herds, supplemented by booty resulting from

batde and raiding. There is no indication of any type of salary being paid to the

common troops, but chiefs and senior officers surely were awarded presents

of various types to tie them to the ruling house, and some of this wealth may

have percolated down the ranks. There appears at first to have been little thought given to siege warfare. '[T]he fortifications and walls of the towns of

Iran, like Ray and Isfahan did not have to be directly stormed by the Turkmen

For the positive characteristics of the Turks, as well as their perceived uncouthness and

barbarity, see U. Haarmann, 'Ideology and history, identity and alterity: The Arab image

of the Turk from the 'Abbasids to modern Egypt', International Journal of Middle Eastern

Studies, 20 (1988), pp. 175 96; Golden, 'War and warfare in the pre Cinggisid western

steppes of Eurasia', pp. 123 8; Y. Frenkel, 'The Turks of the Eurasian Steppes in medieval

Arabic writing', in R. Amitai and M. Biran (eds.), Mongols, Turks and others: Eurasian

nomads and the sedentary world (Leiden, 2005), pp. 201 41. See also the discussion on the Mongols, below.

For this battle and its importance, see D. S. Richards, The Annals of the Saljuq Turks:

Selections from alKdmilfi'l Ta'nkh of 'Izz alDin Von alAthir (London, 2002), pp. 39 40;

W. Barthold, Turkestan down to the Mongol invasion, 3rd edn (London, 1968), p. 303; C. E.

Bosworth, 'The political and dynastic history of the Iranian world', in J. A. Boyle (ed.),

The Cambridge history of Iran, vol. V (Cambridge, 1968), pp. 21 2.

542

Cambridge Histories Online © Cambridge University Press, 201 1

#### Armies and their economic basis in Iran

when the tramplings of their horses and the nibblings of their flocks could devastate the towns' agricultural hinterlands and hamstring their commerce.'

But what worked for the Saljuq rulers in their Drang nach Westen was to become increasingly inappropriate and unwieldy as they found themselves at

the head of a large, mainly sedentary empire. The Turcoman tribesmen

chiefs had increasingly different interests from the sovereign (perhaps as early

as 1040 known as sultan) and his inner circle. The tribesmen were interested in

pastureland, raids and booty, and did not take kindly to the restrictions placed

on these by the central government, now concerned about trade, revenues

from agriculture, and general political and economic stability. The growing

crisis can also be seen as a disagreement over the nature and extent of the

ruler's authority. What had been acceptable in the steppe milieu and the period of conquest, where the ruler (beg or khan) was basically the leader of a

war party with limited authority over other affairs, was seen to the chagrin

of the nomads as inappropriate for the situation in which the sultan and his

entourage found themselves, where a more centralised regime and powerful

ruler was called for. In order to head off tension and potential conflict, a modus

vivendi was worked out to the benefit of both sides: the majority of Turcoman

nomads moved to the area of Azerbaijan (comprising much of north western

Iran of today, the southern Caucasus and even some of eastern Turkey), where already some Turcoman had already taken up residence. There they

found ample pastureland, a climate appropriate for their lifestyle, distance

from the central authorities and ample opportunity to raid (against Georgians,

Armenians and, most importandy, the Byzantines) in the name of Islam. The

Saljuq authorities thus got their Turcomans out of their hair (but they were

not too far if they were needed for a campaign), without having to resort to

violence; they themselves, it should be remembered, were only a generation

or two out of the steppe, and thus would have wanted to preserve a civil relationship with their nomadic 'cousins'. 7

Of course, now that the Turcoman troops were somewhat far away, the Saljuqs needed a dependable force to preserve order from within, and wage

warfare against enemies from without. Their solution was to resort to the now

well entrenched institution in the Muslim world, military slavery. Thus a large

6 C. E. Bosworth, 'Army, ii. Islamic, to the Mongol period', EIr, vol. II, p. 501.

7 This is a summary of the discussion in C. Cahen, Pre Ottoman Turkey, trans. J. Jones

Williams (London, 1968), pp. 22 7. See also D. Morgan, Medieval Persia, 1040 1797

(London, 1988), pp. 28 9.

543

Cambridge Histories Online © Cambridge University Press, 201 1

## The New Cambridge History of Islam

formation of Turkish military slaves (usually still called ghilmari), was probably

created already around the time of the taking of Baghdad. When exactly this

force, which seemingly numbered between 10,000 and 15,000 troops, was

established is uncertain; it would seem that the immediate precedent for this initiative was the Ghaznavid army, although as the Saljuqs moved west

they would have encountered other Turkish slave units which should have

strengthened their resolve to create and maintain such a force. The role of

Persian speaking bureaucrats in conveying this long established military tra

dition and assisting in its re establishment under a Saljuq aegis should not be

underestimated. Perhaps the greatest, and certainly the most famous, of these

officials was Nizam al Mulk (d. 1092), the vizier of the sultans Alp Arslan and

Malik Shah, who left explicit instructions on the matter in his famous mirror

for princes, Siyasat ndma: military slaves (ghuldmdn, the Persian plural of

ghulam) were to be taken from the Turcomans, and they 'should be enrolled

and maintained in the same way as military slaves of the palace. When they

are in continuous employment they will learn the use of arms and become

trained in service. Then they will settle down with other people and with growing devotion serve as military slaves, and cease to feel that aversion [to

settled life] with which they are naturally imbued.' 9 Of course, there is always

the question when reading Nizam al Mulk's work whether he is being descriptive or merely prescriptive, reflecting his own views as a senior bureau

crat. But in this case, at least, his testimony is largely borne out by the historical record (see below). This author also states that the army should contain other ethnic elements (az har jins) besides Turks: Daylamis, Khurasanis, Georgians and Shabankarals (from Fars). This reflects the reality

of a mixed army of cavalry (predominandy Turcomans and Turkish ghilman)

and infantry, primarily of Persian provenance. Kurdish and Arab tribesmen

were also used as auxiliary forces; additional groups (Hindus, Rumis and others) were apparently found in smaller numbers. 10

8 Cahen, Pre Ottoman Turkey, pp. 22 7; Morgan, Medieval Persia, pp. 28 9; Bosworth, 'The

Iranian world', pp. 80 1; A. K. S. Lambton, 'The internal structure of the Saljuq empire',

in Cambridge history of Iran, vol. V, pp. 228 30 (with some details of weapons, logistics and tactics).

9 Nizam al Mulk (Abu All b. Hasan Tusi), Siyar al muluk ( Siyasat ndma), ed. H. Darke

(Tehran, 1962), p. 131; trans, taken, with some changes, from H. Darke, Tfte booh of

government or rules for kings, 2nd edn (London, 1978), p. 102. Darke mistranslates the term

ghulam as 'page', when it is clearly meant for military slave, i.e. mamluk. Nizam al Mulk

may well be mistaken when he states that the ghuldms were to be taken from among the

Turcoman tribes, as opposed to Turkish tribes still out on the steppe. See the discus

sions in the studies cited in the previous note, as well as Barthold, Turkestan, p. 309.

10 Nizam al Mulk, p. 128 (trans, pp. 1034).

Cambridge Histories Online © Cambridge University Press, 201 1

### Armies and their economic basis in Iran

The important role of Turkish military slaves in the Saljuq army is seen in the following citation from the chronicle of Sibt ibn al Jawzi (d. 654/1256), who

describes the victory of Alp Arslan over the Byzantines at the battle of Manzikert/Malazgird in 463/1071, as follows:

Alp Arslan's army deserted him. Those who stayed were 4000 ghulams.

army of 10,000 Kurds also joined him, but he relied, after his reliance on God,

may He be exalted, on those 4,000 who stayed with him. 11

The whole army was supervised, at least with regard to its income and equipment, by the diwdn i c ard ('military inspection office', also called diwdn i

jaysh: 'army office'), headed by a bureaucrat, sahib aljaysh or l drid. It is clear

that this civilian official could not hope to oversee effectively training or preparedness for war, even if theoretically he was in charge of organising

training sessions. The 'commander in chief was a Turkish officer known as

chief hdjib (chamberlain) or ispdhsaldr. The extent of his responsibility and

authority is unclear, since at least up to the time of Sultan Malik Shah usually

the ruler himself went out on major campaign at the head of his troops. 12

One important area overseen by the Army Office, which in modern terms would be understood as 'the office for military payments and supplies', was

the iqtd 1 system used to pay much of the army, certainly the ghuldm troops.

This system had been adopted most probably from the Buyids, who had ruled

previously in Iraq and western Iran, and had developed out of the attempts to

find solutions to pay the army in the chaotic times characterised by chronic

financial crises in Iraq in the late ninth and early tenth centuries. Here, at

least, the Saljuqs did not look to the Ghaznavids as their institutional model. 13

The key concept behind this institution was that a senior commander would

receive a large swathe of agricultural land over which he had the right to collect taxes, which he would use for the upkeep of himself, his household and

his troops (the border between the last two not always clear). In theory, at

least, the muqtcf (a possessor of an iqtcf) did not have any fundamental

11 Sibt ibn al Jawzi, Mir' at al zaman (Ankara, 1968), p. 148, cited and trans, (upon which this

is based) in D. Ayalon, 'The Mamluks of the Seljuks: Islam's military might at the

crossroads', Journal of the Royal Asiatic Society, 3rd ser., 6 (1996), p. 324. This article

(pp. 305 33) contains other important information on the mamluks of the Saljugs, as well

as a selection of citations regarding the appreciation in the Arabic sources of Turkish military qualities.

12 C. E. Bosworth, 'Recruitment, muster, review in medieval Islamic armies', in V.J. Parry

and M. E. Yapp (eds.), War, technology and society in the Middle East (London, 1975),

pp. 69, 75 7; Bosworth; Army', pp. 501 2; Lambton, 'Internal structure', p. 226.

13 See the comments by C. E. Bosworth, The Ghaznavids: Their empire in Afghanistan and eastern Iran 994 1040, 2nd edn (Beirut, 1973), pp. 66, 125.

545

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

administrative or governmental authority over this land, or the right to pass it

on to his heirs. It was not private property (milk), but, essentially, the right to

collect agricultural taxes (khardj) at source. As such, it certainly cannot be

confused with medieval European feudalism, and the use of the term 'fief' to

translate iqtd' should be eschewed. Where, as in earlier times, it had been

hoped that from the income that the muqta' received he would pay the 'ushr

('tithe') to the state treasury (this type of iqtd' being known as iqtd' tamlik, 'iqtd'

of possession'), in reality, in most cases the officer in question just kept all of

the revenues for his own uses. Eventually, this usage was recognised by the

bureaucrats, and received the name iqtd' istighdl ('iqtd' of usufruct'). This latter

form of the institution was that adopted in the Saljuq empire. 14 We also find

another form of the iqtd' institution, which became more pronounced with the

weakening of the authority of the Saljuq state (starting at the end of the twelfth

century, in the aftermath of the death of Nizam al Mulk and Malik Shah). This

was what has been referred to in modern scholarship as 'administrative' iqtd  $\mathbf{1}$  ,

whose holder received not only the right to collect taxes in a particular area

but also governing powers as a representative of the central government.

times of weakening central authority, these governorships could even be transferred by inheritance. In one Saljuq successor state, the Zangid princi

pality of Mosul and Aleppo, this right of inheritance was even institutionalised

(although this was short lived, and under their Ayyubid successors there was a

reversion to the non hereditary iqtd'). 15

The Mongol invasions and the Ilkhanate

With the advent of the Mongol period in Iran, we again encounter an army of

Inner Asian origin, with both similarities and differences between it and the

original Turcoman army of the Saljuqs. The main similarity would have been

the general character of the armies, based on masses of light horse archers. The

14 A. K. S. Lambton, 'Reflections on the iqtd'', in G. Makdisi (ed.), Arabic and Islamic studies

in honor of Hamilton A. R. Gibb (Leiden, 1965), pp. 358 76; Lambton, 'Eqta'', EIr, vol. VIII,

pp. 520 3; see Lambton, 'Internal structure', p. 234, for other albeit related uses of the

term iqtd' under the Saljuqs; C. Cahen, 'L'evolution de l'iqta' du IX e au XIII e siecle:

Contribution a une histoire compare des societes medievales', in C. Cahen, Les peuples

musulmans dans Vhistoire medievale (Damascus, 1977), pp. 231 69 (originally published in

Annales: Economies, Societes, Civilisations, 8 (1953), pp. 25 52); Cahen, 'Ikta'', EI 1, vol. Ill, pp. 1088 91.

15 Lambton, 'Reflections', pp. 369 73; Cahen, 'L'evolution de l'iqta'', pp. 247, 256 9;

R. Amitai, 'Turco Mongolian nomads and the iqtd' system in the Islamic Middle East',

in A. N. Khazanov and A. Wink (ed.), Nomads in the sedentary world (Richmond, 2001),

pp. 156, and notes 17 19.

546

Cambridge Histories Online © Cambridge University Press, 201 1

Armies and their economic basis in Iran

differences were the size of the armies (the Saljuq army numbering perhaps

several tens of thousands of horsemen, the Mongols probably more than a

hundred thousand), the superior discipline of the Mongol troops and their

obedience to the central authorities, and the greater destruction wrought by

the Mongols in the conquered lands, certainly during the campaigns of con

quest, and in specific areas in their aftermath. The Mongols introduced a larger

scale of armies and fighting, and this in turn influenced at least some of their

enemies, not the least the Mamluks of Egypt and Syria, who were one of their

main adversaries in the Middle East in the period after 1260.

Two main subjects will be investigated in this chapter: the Mongol army as

first formed in the Inner Asian steppes, 1 and the Mongol army in the post

Hiilegii period. 17 Brief comments will also be made regarding the size and

nature of Hiilegii's forces.

We can start by citing some passages from contemporary notices as to the

nature of the Mongol forces while still primarily an army of the steppe, although after a generation or two as a unified, conquering empire. Thus writes John of Piano Carpini, the papal envoy to the court of the Great Khan

Giiyiiq in 1246:

It should be known that when the [Mongols] come in sight of the enemy they

attack at once, each one shooting three or four arrows at their adversaries; if

they see that they are not going to be able to defeat them, they retire, going

back to their own line. They do this as a blind to make the enemy follow them

as far as the places where they have prepared ambushes . . . When however  $\protect\$ 

they are going to join battle, they draw up all the battle lines just as they are to

fight ... Other columns of stronger men they dispatch far off to the right and

the left so that they are not seen by the enemy and in this way they surround

them and close in and so the fight begins from all sides ... It should be known

that if they can avoid it, the Tartars [^Mongols] 1 do not like to fight hand to

hand but they wound and kill men and horses with their arrow; they only

16 See these previous studies: H. D. Martin, The rise of Chingis Khan and his conquest of north

China (repr. New York, 1971, of Baltimore, 1950), pp. 11 47; S. R. Turnbull, The Mongols,

Men at Arms Series, 105 (London, 1980); R. W. Reid, 'Mongolian weaponry in The secret

history of the Mongols', Mongolian Studies, 15 (1992), pp. 85 96; W. Swi^toslawski. Arms

and armour of the nomads of the great steppe in the times of the Mongol expansion (Lodz, 1999), pp. 103 10.

17 This topic has been explored systematically in B. Spuler, Die Mongolen in Iran: Politik,

Verwaltung und Kultur der Ilchanzeit 1220 ijjo, 4th edn (Leiden, 1985), pp. 30 48; D. O.

Morgan, 'The Mongol armies in Persia', Der Islam, 56 (1979), pp. 81 96. Other relevant

studies are mentioned below.

18 For the equivalence of the names Mongols and Tatars, in spite of the fact that the latter

were originally a separate tribe, see the comments of J. A. Boyle, in The history of the

world conqueror by 'Ala ad Din 'Ata Malik JuvainT (Manchester, 1958), vol. I, p. 20, n. 4.

547

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam come to close quarters when men and horses have been weakened by

The mass nature of the Mongol army is noted by the Persian historian Juwayni (d. 1283), who served the Mongols as governor of Baghdad. He writes:

'It is also a peasantry in the guise of an army, all of them, great and small,

noble and base, in time of battle becoming swordsmen, archers and lancers

and advancing in whatever manner the occasion requires.' 20 The discipline of

the Mongol soldiers is also vaunted: 'On the day of review, also, they display

their equipment, and if only a little be missing, those responsible are severely

punished . . . Their obedience and submissiveness is such that if there be a

commander of a hundred thousand between whom and the Khan there is a

distance of sunrise and sunset, and if he but commit some fault, the Khan dispatches a single horseman to punish him after the manner prescribed: if his

head has been demanded, he cuts it off, and if gold be required, he takes it.

from him/21

The vast majority of the Mongol army at this stage was clearly composed of

light cavalry, meaning horsemen who were lightly armoured (with armour

mainly composed of cloth and leather, but sometimes with iron components,

with partially metal helmets; some had iron armour), carrying bow and arrows and some basic weapons for hand to hand warfare, 22 and mounted

on small, but sturdy steppe ponies. 23 The Mongol trooper would set off on

campaign with a string of such ponies, apparently around five, in order to change mounts during both long distance travel and battle (and perhaps provide meat also for himself and his fellow soldiers). 24 The tactic of choice

was wave after wave of cavalrymen advancing while firing, and then wheeling

around to permit the advance of another wave of similar troops. 25 This might

19 John of Piano Carpini [Giovanni di Pian di Carpine], 'History of the Mongols', in

C. Dawson (ed.), The mission to Asia (London, 1980), pp. 36 7.

20 Juwayni, trans. Boyle, vol. I, p. 30.

21 Ibid., pp. 30 1. This information, derived from Juwayni, is also found in the section on

the Mongols by Ibn Fadl Allah al 'Umari, Das Mongolische Weltreich: Al 'Umaris

Darstellung der mongolischen Reiche in seinem Werk Masalik al absarfi 'I mamdlik al amsdr,

ed. and trans. K. Lech (Wiesbaden, 1968), pp. 10 11 (Arabic text), where there is more on

the army's discipline. See also Carpini, 'History of the Mongols', ed. Dawson, p. 33.

22 See Carpini, 'History of the Mongols', ed. Dawson, pp. 33 5, for their armour (and that of their horses) and weapons.

23 For these horses, see J. M. Smith, Jr, "Aynjalut: Mamluk success or Mongol failure", Harvard Journal of Asiatic Studies, 44 (1984), pp. 336 40.

24 Morgan, 'The Mongol armies in Persia', pp. 85 6.

 $25\ \mathrm{Timothy}\ \mathrm{May}\ \mathrm{usefully}\ \mathrm{compares}\ \mathrm{this}\ \mathrm{to}\ \mathrm{the}\ \mathrm{caracole}\ \mathrm{('charge}\ \mathrm{and}\ \mathrm{shoot')}\ \mathrm{manoeuvre}\ \mathrm{of}$ 

sixteenth century European pistol wielding cavalry; see his 'The training of an Inner

Asian nomad army in the pre modern period', Journal of Military History, 70 (2006), pp. 627 8.

548

Cambridge Histories Online © Cambridge University Press, 201 1

Armies and their economic basis in Iran

be accompanied by an attempt to encircle the enemy, facilitated by both the

large numbers and the mobility of the Mongols. 2, The aim was to break the

will and formation of the enemy by these repeated attacks, and only then to

engage in hand to hand combat or to chase after them if they fled, in either

case probably inflicting greater casualties than the previously mentioned barrages. Related to this technique was permitting encircled enemy troops

to 'escape' their predicament and then pursuing them to kill and capture. 27

Another favourite tactic was the feigned retreat, during which the Mongol

troops would turn around on their saddles, shooting behind them as they rode. Here the aim was to draw the enemy into an ambush, meanwhile exhausting their mounts and breaking up their formations. 2 There is nothing

especially Mongol in these formations, but just a use of classic Inner Asian

tactics, refined through practice, 29 efficient command and communications,

discipline and large numbers. In fact, the size of the Mongol armies is noted by

the sources, 30 and was certainly an important factor in their successes in the

Middle East and elsewhere. 31 Certainly in the aftermath of the Mongol invasion of the region, armies tended to get larger, surely to meet the challenge of the Mongols. The Mamluks of Egypt and Syria, in any event, had a significantly bigger army than their Ayyubid predecessors. 32

One adoption of a traditional Inner Asian military institution 33 was the decimal system of organisation, starting from units of 10, who were subsumed

in companies of ioo, which in turn were part of 'brigades' of 1,000 and these

finally were part of divisions of 10,000, known as a tilmen (in the singular). 34

26 See the passage from John of Piano Carpini, cited above.

27 The Mongols used this tactic at the siege of Bukhara in 1220; al Nasawi, Stmt al sultan

jalal al dm mankiibirti (Cairo, 1953), pp. 100 1; cf. Juwaym, trans. Boyle, vol. I, p. 103. For

this incident and additional similar ones, see May, 'Training', p. 620 and n. 5.

28 This was done at the batde of Kose Dagh in Anatolia against the Saljugs; C. Cahen,

'Kose Dagh', Ef, vol. V, p. 271.

29 Including the use of the massive, long distant hunting circle (nerge); see Juwayni, trans.

Boyle, vol. I, pp. 27 9; May, 'Training', pp. 620 1; D. Morgan, The Mongols, 2nd edn (Oxford, 2007), pp. 74 5.

30 See, e.g. al 'Umari, ed. Lech, p. 10.

31 See the comments in Smith, "Aynjaltit", p. 345; John M. Smith, Jr, 'Mongol manpower

and Persian population', Journal of the Economic and Social History of the Orient, 18 (1975),

pp. 271 99; also Morgan, 'The Mongol armies in Persia', pp. 82 8.

32 R. Amitai Preiss, Mongols and Mamluks: The Mamluk Hkhanid war, 1260 1281 (Cambridge, 1995), PP- 71 2.

33 See the comments in Smith, 'Mongol manpower', p. 298 n. 86; I. de Rachewiltz (trans, and ed.), The secret history of the Mongols (Leiden, 2004), vol. I, pp. 409 10, vol. II, pp. 689 90.

34 Carpini, 'History of the Mongols', ed. Dawson, pp. 32 3; Juwaym, trans. Boyle, p. 30; al

'Umari, ed. Lech, p. 11. See the discussion in Morgan, 'The Mongol armies in Persia', pp. 88 9.

549

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Unlike earlier Inner Asian states, however, in the case of the Mongols this

structure entailed the breaking up of many tribes, and men (and thus their

families) were moved hither and fro. The idea behind this reorganisation was

that the traditional system of loyalty and leadership was largely disrupted,

permitting the erection of a framework guaranteeing more obedience to Chinggis Khan, his family and his officers. 35 Here and there, however, some

tribes appear to have survived this exercise in social engineering, and con

tinued to exist both in the period of the united empire and even during the

rule of the successor states and beyond (the Oirats are the notable example, in

both East and West Asia). 36 The decimal organisation of course greatly facilitated logistics, communications, and the strategic and tactical control of

the troops. Whether the tilmens actually were able to maintain their strength

around 10,000 men over time remains an open question. 37 The attrition of a

long term campaign would certainly have taken its toll. Commanders of tilmens were known, at least from the mid thirteenth century, as noyad (plural

of noyari), 38 a term which in an earlier period appears to have referred to chiefs,

and later to princes.

An interesting and effective military institution of the Mongols, perhaps even their innovation, is the tamma system, which was used for both long term occupation duty and long distance campaigning. Basically, the idea was

to create expeditionary forces composed of contingents from the armies of the

different branches of the Chinggisid family. The concept behind this institu

tion was twofold: first, to provide sufficient manpower for the military needs

of the empire, and to spread this burden throughout the various princely appanages (uluses); and, second, to guarantee the unity of the imperial family

by involving princes and forces from all branches in these campaigns (and,

perhaps, these princes would function as would be hostages to forestall disloyalty in the future). 39 The forces in the Middle East commanded by the

36 De Rachewiltz, The secret history, vol. I, pp. 164 (sec. 239), 519; vol. II, pp. 849, 852. For the

later Oirats in the Ilkhanate, see D. Ayalon, 'The Wafidiyya in the Mamluk kingdom',

Islamic Culture (1951), pp. 99 101.

37 Smith, "Aynjahit", p. 310, believes so, but cf. Hsiao Ch'i ch'ing, The military establishment

of the Yuan dynasty (Cambridge, MA, 1978), pp. 170 1, n. 27, as well as the remark by de

Rachewiltz, in his commentary to The secret history, vol. I, p. 409.

38 This is the way that the term is defined by al 'Umari, ed. Lech, p. 93; see the discussion in

R. Amitai, 'An Arabic biographical notice of Kitbugha, the Mongol general defeated at

'Ayn Jalut', Jerusalem Studies in Arabic and Islam, 33 (2007), p. 227 n. 35.

39 Morgan, The Mongols, pp. 82 3; P. D. Buell, 'Kalmyk Tanggaci people: Thoughts on the

mechanics and impact of Mongol expansion', Mongolian Studies, 9 (1980), pp. 41 59; cf.

D. Ostrowski, 'The tamma and the dual administrative structure of the Mongol empire',

Bulletin of the School of Oriental and African Studies, 61 (1998), pp. 262 77.

550

Cambridge Histories Online © Cambridge University Press, 201 1

Armies and their economic basis in Iran

Mongol viceroys Chormaghun (1229 42) and Baiju (1242 c. 1256) are referred

to by the later pro Mongol historian (and vizier) Rashid al Din (d. 1318) as

tamma forces, both based in the environs of Azerbaijan. 40

Essentially such an army, albeit a much larger one, was sent by the Great Khan Mongke with his brother Hillegii to the lands of Islam in the early 1250s.

Juwaym writes that he was sent with two out of every ten Mongol soldiers, 41 a

statement which perhaps does not have to be taken literally but does clearly

imply a very big army and also hints at its composition from different parts of

the army. Rashid al Dm gives us the name of certain princes from various uluses, perhaps most importantly that of the Jochids (the so called Golden

Horde). 42 The army, which was probably composed also of many Turkish

nomads, may have included non nomadic troops such as Alans from the northern Caucasus, 43 as well as 1,000 households of Chinese military techni

cians. 44 No less important, the officers and troops were accompanied by their

families and herds. 45 Unlike Chinggis Khan's campaign of 1219 to Transoxania

and north east Iran, Hiilegii's march entailed the migration of a significant

section of the Mongols, as well as other steppe peoples.

Once Hiilegii crossed the Syr Darya, and began campaigning in the Muslim

world, first against the Nizari Isma'ilis (the so called Assassins), then against

40 W. M. Thackston (trans, and ed.), Rashiduddin Fazlullnh'sjami 'u't tawarikh (Compendium

of chronicles) (Cambridge, MA, 1999), vol. II, p. 478. Rashid al Din does not mention here

the command of Eljigidei (1248 51), who had replaced Baiju at the order of the Great

Khan Giiyiig (r. 1246 8) and continued into the following interregnum. With the arrival

of Hiilegu on the scene in the mid 1250s, Baiju and his troops vacated Azerbaijan and

moved into Anatolia; P. Jackson, 'Bayju', EIr, vol. IX, p. 1.

41 Juwaym, trans. Boyle, vol. II, p. 607; this information appears in Rashid al Dm, trans.

Thackston, p. 478. For a discussion of the size and composition of Hillegii's army, see

T. T. Allsen, Mongol imperialism: The policies of the Grand Qan Mongke in China, Russia,

and the Islamic lands, 1251 1259 (Berkeley, 1987), pp. 2037.

42 JuwanI, trans. Boyle, vol. II, p. 608; cf. Rashid al Din, trans. Thackston, pp. 487, 793; for the untimely end of these princes, see ibid., pp. 506, 511.

43 Allsen, Mongol imperialism, p. 208.

44 Juwaym, trans. Boyle, vol. II, p. 608: '[Mongke] sent to Cathay [khitay] to bring

mangonel [majaniq] experts and naphta [naff Greek fire] throwers.' A thousand of

these households (khana) of such specialists were dispatched. Cf. Rashid al Dm, trans.

Thackston, p. 478, who adds probably gratuitously 'crossbow men' to this list. See

the discussion in T. T. Allsen, 'The circulation of military technology in the Mongolian

empire', in Di Cosmo (ed.), Warfare in Inner Asian history, p. 278, for a discussion of this

passage. The 'Cathay' referred to here must be northern China and not the Khitan

people, its former rulers.

45 This statement has recently been called into question by J. M. Smith, Jr, 'Hillegii moves

west: High living and heartbreak on the road to Baghdad', in L. Komaroff (ed.), Beyond

the legacy of Genghis Khan (Leiden, 2006), pp. in 34, who sees a much smaller Mongol

army setting out with Hiilegii, without herds and families, some of whom joined up

with their menfolk at a later date.

551

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

the caliph in Baghdad as well as recalcitrant vassals and finally in Syria, his

army was swelled by the addition of two important elements: first, the Mongol troops who had already been serving in the area, be it in north eastern or north western Iran; and, second, by a substantial number of

auxiliaries from subservient rulers. These included Armenians, Georgians,

Iranians (tajik or al c ajam) and troops from aljazira (northern Mesopotamia)

and nearby Saljuq Rum (Anatolia). 46 Those from aljazira and Rum, at least, appear to have been largely professional soldiers of Turkish origin, i.e.

mamluks, and thus cavalrymen. The Armenians and Georgians, who usually

accompanied the Mongols in their campaigns into Syria, were probably a mixed

force of cavalry and infantry. 47 If not professional soldiers, they were certainly

highly trained militiamen. As for the 'Iranians', many of these were surely the

professional soldiers of the local vassal rulers but they may have included militiamen of some type. Tajik infantrymen were ordered to be used, at least

during the reign of Ghazan (1295 1304), in guarding mountain passes and

'difficult places on the frontiers'. 48

Some idea of the composition of the army is seen in two examples from the

campaigns against the Mamluks of Egypt and Syria, during the war which

began with the Mongol defeat at 'Ayn Jalut in 1260 and lasted for some sixty

years. 49 In 1281, the Mamluk sultan Qalawun received intelligence reports of

an advancing Mongol army that numbered 80,000 soldiers and was composed

of 50,000 Mongols (al mughul), the remainder being Georgians, Saljuq Rumi

troops, Armenians, Franks and renegades (al murtadda). 50 The Armenians,

from Cilicia, and the Georgians were led by their kings. The 'renegades' may well be Muslim troops from aljazira or elsewhere, even Iran (some

46 See the discussion in Allsen, Mongol imperialism, pp. 203 7.

47 For the role of the Armenian troops from Cilicia in Syria, sometimes even acting alone,

as well as Georgians, see Amitai Preiss, Mongols and Mamluks, pp. 26, 40, 54, 183, 189

(Saljuq and Iranian troops also mentioned in this campaign), pp.  $195\ 6$ . On the army of

Saljuq Rum, see the comments in Cahen, Pre Ottoman Turkey, pp. 230 4; for more on the

Armenians, see Allsen, Mongol imperialism, pp. 205 6.

48 Rashid al Dm, trans. Thackston, vol. II, p. 735; these troops were to be organised in units

of 100 and 1,000, and were supposedly to be supported by iqtd's. For a discussion of local

Iranian dynasties and their armies, see B. F. Manz, 'Military manpower in late Mongol

and Timurid Iran', in M. Szuppe (ed.), L'heritage timouride: Iran Asie eentrale Inde XVe

XVIIIe siecles, published as Cahiers d'Asie Centrale, 3 4 (1997), pp. 43 6. See also below.

49 See Amitai Preiss, Mongols and Mamluks, passim; Amitai Preiss, "Ayn Jalut revisited',

Tank, 2 (1992), pp. 119 50; R. Amitai, 'The resolution of the Mongol Mamluk war', in

R. Amitai and M. Biran (eds.), Mongols, Turks and others (Leiden, 2005), pp. 359 90.

50 Ibn al Furat, Ta'rikh, vol. VII, ed. Q. Zurayk (Beirut, 1942), p. 215; Baybars al Mansuri,

Zubdat alfikra, ed. D. S. Richards (Beirut, 1998), pp. 195 6. Rashid al Din, trans.

Thackston, vol. II, p. 544, does not mention any of these non Mongol forces, only the

names of several Mongol officers, evidently tilmen commanders.

552

Cambridge Histories Online © Cambridge University Press, 201 1

Armies and their economic basis in Iran

sources mention soldiers from al c ajam), who would have been traitors in the

Mamluks' mind. The Franks are of unknown provenance, but could have been mercenaries, or troops from the castles of the military orders in north

Syria and Cilicia. Unfortunately, there are no details of how these different

contingents were used on the battlefield or subsequently behaved. The impression from the sources is that the actual fighting was mainly, if not exclusively, a cavalry affair. 51

The second example is the battle of Wadi al Khaznadar north of Horns in Syria, in December 1299, the one major field battle in which the Mongols were

successful. We do not have here any information regarding non Mongol (or

rather, non Mongol or Turkish) contingents. Only the names of Mongol commanders (certainly of timens) are given by the contemporary Rashid al

Dm, who was present and provides a detailed order of battle. 52 In addition,

another contemporary, Wassaf, states that for this campaign, five out of every

ten Mongols had been ordered out, and each of them was required to bring

five mounts. 53 This is compelling testimony that the Mongols were still functioning as light cavalry, maintaining the fighting methods of their fore

fathers who had entered the Middle East two or three generations before. 54

Other information from this battle strengthens the view that there was a great

deal of continuity in Mongol fighting methods. Originally, the Mongol troops

in the centre had met the initial Mamluk attack dismounted, apparendy to

improve the accuracy of their archery, but also perhaps to take cover behind

their horses. Thereupon they remounted, and attacked the Mamluks 'in the

Turkish fashion' (bar \shan turk taz kardan), which should probably be under

stood to mean the traditional steppe tactic of a unified cavalry assault, with the

51 For the battle, which ended in a Mongol defeat, see Amitai Preiss, Mongols and Mamluks,

pp. 187 201; cf. Smith, 'Ayn Jalut', p. 329 n. 63; A. P. Martinez, 'Some notes on the II

Xanid army', Archivum Eurasiae Medii Aeivi, 6 (1986), pp. 159 65.

52 Rashid al Din, trans. Thackston, vol. II, pp. 645 6. This is, however, incomplete

evidence. As we have just seen above, Rashid al Dm provides no evidence on the

various non Mongol unit contingents that the Mamluk sources mention for the battle of Horns in 1281.

53 Wassaf, Ta'nkli (Bombay, 1269/1852 3), p. 373.

54 The battle is discussed, as are the implications for the nature of the Mongol army in Iran,

in R. Amitai, 'Whither the Ilkhanid army? Ghazan's first campaign into Syria (1299 1300)',

in Di Cosmo (ed.), Warfare in Inner Asian history, pp. 220 64. A different view, holding that

indeed the Mongols deliberately made a transition from 'light' to 'medium' cavalry in the

first decades of their rule, is presented in Martinez, 'Some notes,' pp. 129 242, esp. p. 176.

Morgan, 'The Mongol armies in Persia', pp. 90 6, also discusses the changing nature of

the Mongol army c. 1300. Smith, 'Ayn Jalut', tacidy assumes a continuity of the basic

nature of the Mongol and then Ilkhanid army, its equipment and fighting methods.

553

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

troops letting offbarrages of arrows. 55 Apparently at a later stage, when fresh

Mongol troops approached, archery was effectively employed against the Mamluk horses, 5 indicating the ongoing importance of this traditional noma

die weapon. We thus see that c. 1300, it appears on the whole that the Mongol

armies in Iran and the surrounding countries were still based on the tactics

derived from the preponderance of light cavalry. 57 While there is no explicit

evidence that this is the case in the following decades, there is also no clear

information that anything of substance had changed in the nature of the Mongol army. We can assume, therefore, that until the break up of the Ilkhanate state in the 1330s, the mainstay of its army was the light cavalryman

of Eurasian steppe provenance.

Originally, following the classical steppe pattern, the Mongol officers and troops in Iran did not receive salaries or other payments, except booty and

occasional gifts. Perhaps even more surprisingly to those used to standing

armies, the Mongol soldiers were expected to pay taxes; for the Mongol, military service was just another obligation towards the ruler. Juwayni writes:

'It is an army after the fashion of a peasantry, being liable to all manner of

contributions (mu'ari), and rendering without complaint whatever is enjoined

upon it, whether qubchur, occasional taxes QawciridM), the maintenance (ifeh

rdjdt) of travellers or the upkeep of the post system (yam) with the provisions

of mounts (ulagh) and fodder (\*ulufat).' 5S I will just note here that gubchur refers

to a yearly tax of a certain number of livestock that the Turco Mongolian nomad cum soldier would pay to the authorities. 59

Of course, the vast majority of the population was settled, and these continued to pay the land tax (khardj) as before. Apparently, at least as long

as the khans had yet to convert to Islam, the jizya tax paid by dhimmis was

abolished. ° In its place, however, was a bewildering array of taxes, duties and

payments, often demanded on a capricious schedule, exacerbated by different

55 Rashld al Din, Geschichte Gdzdn Han's aus dem Ta'rih i Mubarak i Gdzdnx ..., ed. K. Jahn

(London, 1940), p. 128; cf. the translation by Thackston, vol. II, p. 646, where this phrase is not rendered.

56 Baybars al Mansuri, Zubda, p. 331.

57 Certainly, this was what has been found for the Ilkhanid and Chaghadayid armies of a

generation before. See M. Biran, 'The battle of Herat (1270): A case of inter Mongol

warfare', in Di Cosmo (ed.), Warfare in Inner Asian history, pp. 175 219, esp. pp. 205 12.

58 Juwayni, trans. Boyle, vol. I, p. 30, with slight changes.

59 Morgan, The Mongols, p. 80; cf. Boyle, in his translation of Juwayni, vol. I, p. 30 n. 12.

Later on qubchur is used as a general term for tax or payment.

60 For the temporary reversal of this abolition during the short reign of Tegiider Ahmad,

see R. Amitai, 'The conversion of Tegiider Ilkhan to Islam', Jerusalem Studies in Arabic

and Islam, 25 (2001), pp. 26 7.

554

Cambridge Histories Online © Cambridge University Press, 201 1

Armies and their economic basis in Iran

authorities calling for various taxes. In general, it appears that the demands of

the Mongol administration were quite onerous, and contributed in many places to a decline in the economy, agricultural and urban.

For the Mongols, there is an often cited piece of evidence that appears to show that radical changes were in the offing towards the end of the thirteenth

century in the realm of payment and land tenure, indicative perhaps of the

substantial transformation of Mongol society and with significant implications

for the future. This is the passage found in the chapters devoted to the reforms

enacted by his patron, the Ilkhan Ghazan Rashid al Dm writes:

At this time [c. 1300], most of the soldiers had the desire for estates (amlak) and

[the practice of?] agriculture. Upon acquiring iqta' land (milktiqta'i), they will

have reached their goal.

Several scholars have accorded this passage much credence and seen it as

unequivocal evidence for the sedentarisation process of the Mongols. 63 It is my

opinion, however, that the evidence is problematic. 64 To start with, the edict

regarding the iqta c was promulgated late in Ghazan's reign, leading one to

wonder how much it was actually carried out by this khan and then by his successors. Second, the mention of actual iqtffat in the sources is few and far

between, to put it mildly. Third, this institution, which is somewhat different

from the iqta' of the Saljuqs (e.g. Ghazan's 'neo iqta 1 ' was to be allocated to

common soldiers, not only officers, and could be passed on by inheritance),

would not, even if implemented, have entailed the sedentarisation of the Mongols. Officers and soldiers could enjoy the fruits of agriculture without

settling down and practising it. One of the most important pieces of evidence

regarding land use by the Mongols and their continued practice of the pastoral

61 For Mongol taxation, see: A. K. S. Lambton, Continuity and change in medieval Persia

(New York, 1988), pp. 199 220; I. P. Petrushevsky, 'The socio economic condition of

Iran under the II Khans', in Cambridge history of Iran, vol. V, pp. 529 37.

62 Rashid al Dm, ed. Jahn, Geschichte Gazdn Han's, p. 302. The addition within the square

brackets is from Morgan, 'The Mongol armies in Persia', p. 93. Cf the translation in

Thackston, vol. HI, p. 731: 'since in this era most of the soldiers have a desire to own land

and farm, when they get land in fief, they will have what they want'. For the text of

Ghazan's farman (royal order), see ibid., pp. 731 5.

63 Morgan, 'The Mongol armies in Persia', pp. 91 6; but see Morgan, The Mongols, p. 148;

A. M. Khazanov, Nomads and tfte outside world, 2nd edn (Madison, WI, 1994), pp. 251 5;

J. Aubin, 'Le temoignage d'Ebn e Bazzaz sur la turquisation de l'Azerbaydjan', in C. H.

de Fouchecour and Ph. Gignoux (eds.), Etudes Irano Aryennes offertes a Gilbert hazard

(Paris, 1989), pp. 5 17 (esp. pp. 8 9).

64 The following paragraph is a summary of the argument in Amitai, 'Turco Mongolian nomads and the igta' system', pp. 156 65.

555

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

nomadic lifestyle is provided by al 'Umari, writing towards the middle of the

fourteenth century:

Every tribe has land to reside in and the descendants inherit it from the forefathers since Hulegii conquered the country. Their abodes (manaziluhum)

are in it. They have in it crops for their substance, but they do not live by tilling and sowing. 5

It appears, then, that there was nothing new in Mongol tribes having control

over large swathes of agricultural land, from which they enjoyed at least some

of its produce. This had thus nothing to do with a desire for agriculture, before, during or after Ghazan's time, and we should be wary of seeing a desire for sedentarisation in Rashid al Din's famous passage. The above parenthetical 'the desire for ... [practice of] agriculture' could probably be

better replaced by 'the desire for ... [the fruits and revenues of] agriculture'.

The corollary of this evidence is that if the Mongols remained nomads, there is

little reason to assume that they changed their methods of warfare which were

directly derived from their nomadic pastoral lifestyle. This conclusion fits the

evidence presented above to this effect.

Three issues related to the Mongols remain to be briefly discussed. The first

of these is the question of employment of gunpowder by the Mongols in the

Middle East. While there is some evidence that the Mongols had brought some

knowledge of gunpowder technology (probably as a means of causing a rapid

combustion, not so much as a way to send a projectile) with them into south

west Asia, it may be going too far to see this as an effective 'weapons system' at

this stage. 67 In fact, a careful analysis of a series of Mongol sieges against Mamluk

fortifications along the Euphrates and in Syria shows that there is absolutely no

evidence of anything resembling gunpowder being used, and the major siege

weapon of the Mongols was the manjamq, literally mangonel, but surely in this

context a trebuchet, both of the traction and counterweight variety.

A second matter relates to the logistic difficulties and limitations of the Ilkhanid army, a point independently raised and discussed by D. O. Morgan 68

and J. M. Smith, Jr, 69 in the framework of their analyses of the Mongol

65 al 'Umari, ed. Lech, p. 95.

66 Allsen, 'The circulation of military technology', p. 281.

67 Cf. Iqtadar Alam Khan, 'The coming of gunpowder to the Islamic world and India:

Spotlight on the role of the Mongols', Journal of Asian History, 30 (1996), pp. 27 45.

68 'The Mongols in Syria, 1260 1300', in P. W. Edbury (ed.), Crusade and settlement (Cardiff, 1985), pp. 229 35.

69 "Aynjalut", passim; John M. Smith, Jr, 'Nomads on ponies vs. slaves on horses', Journal

of the American Oriental Society, 118 (1998), pp. 154 62.

Cambridge Histories Online © Cambridge University Press, 201 1

#### Armies and their economic basis in Iran

invasions of Syria. The main thrust of their argument was that the Mongols

were repeatedly stymied by the difficulties of feeding and watering their large

number of horses whenever they entered Syria with a big army, particularly as

they drew close to the summer, and thus had no choice but withdraw most of

their forces after just a few months in the country. Related to this issue is Smith's suggestion that the Mongols were basically inferior soldiers (at least

compared to their Mamluk enemy), amateurs who made up for small horses,

home made weapons and haphazard training by mobility (facilitated by each

trooper having several mounts), 'firepower' and numbers. Thus, if Syria put

logistical limitations on the Mongols, they had no choice but to leave small

armies (composed of inferior troops) there, after withdrawing their larger forces. The Mongols were thus doomed in their war with the Mamluks over

control of Syria. This is a compelling argument, but I feel that it is too deterministic and reductionist. Without going here into a detailed comparison

of Mongols and Mamluks, one should note that it is doubtful that with mediocre soldiers Chinggis Khan and his descendants would have conquered

much of the known world. Second, logistical difficulties, while presenting real

problems, were not necessarily insurmountable: the grasslands and fields of

greater Syria were far from being exploited during any of the Mongol campaigns into Syria. Third, the Mongols kept coming back, so either they

were unaware of these logistical difficulties, or they thought that they could be

dealt with. Finally, the Mongols were not alone: the Mamluks themselves had

their own logistical problems, which could contribute as in the battle of Wadi al Khaznadar near Horns in 1299 to a Mongol victory. 70

Finally, it is worth noting that unlike the Saljuqs, and some other dynasties

of Eurasian nomadic provenance (what some have called 'post nomads'), the

Ilkhans never adopted the institution of military slavery, that is, they had no

regiments of mamluks or anything that resembled them. Rather, they pre ferred to maintain large armies of mounted horse archers (supplemented by

infantry and cavalry auxiliaries that included some mamluk units of local rulers). This military tradition was to be basically continued by the Turcoman federations that rose in north western Iran and the surrounding

regions and also by Temiir (Tamerlane) and his successors, to which we will

now briefly turn.

70 See Amitai Preiss, Mongols and Mamluks, pp. 214 29; R. Amitai, 'Some more thoughts on

the logistics of the Mongol Mamluk war (with special reference to the battle of Wadi al

Khaznadar)', in J. Pryor (ed.), Logistics of war in the age of the Crusades (Aldershot, 2006), pp. 25 42.

557

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Armies in post-Mongol Iran

The Qara Qoyunlu (1380 1468) and the Aq Qoyunlu (1378 1508) states were  $\,$ 

based on the masses of Turcoman tribesmen in Azerbaijan and the surround

ing areas. Many of these 'Turcomans' were probably Islamised and Turkified

Mongols. These tribesmen appear almost completely to have continued the

military traditions of the Mongols, that is, the army was composed primarily

of masses of disciplined light cavalry. Much more is known about the military

organisation of the Aq Qoyunlu. 71 There, the ongoing use of Mongol military

terminology appears to indicate that the institutions that they described also

continued, although the possibility exists of changes in the essence of these

structures. The Turcoman armies, however, were smaller than their Mongol

predecessors. 72 One difference, natural enough, was that the Aq Qoyunlu

rulers introduced firearms, which in the fifteenth century became increasingly

more available and acceptable (and thus desirable) in the eastern Mediterranean and further east. Towards the end of the fifteenth century the Aq Qoyunlu used captured Ottoman cannons, as well as having some locally cast ones for sieges. In addition, the Venetian allies of Uzun Hasan

(r. 1452 78) 'supplied him with cannons and arquebuses and artillerymen to

operate them and advise on their use'. 73 The ruler's personal guard also had

handguns of some type at this time. The overall impression is, however, that

Aq Qoyunlu gunpowder weapons (or their use) were inferior to those of their

Ottoman rivals to the west, and certainly did not bring about a breakthrough

on that front. Little is known about the payment of the Aq Qoyunlu army, beyond the granting to tribal leaders of lands over which they held fiscal and

administrative control. These lands were known as tiyiil or ulka, and this usage, or at least the terms, may have continued into the Safavid period. 74

71 This is due mainly to the excellent monograph by J. E. Woods, The Aqquyunlu: Clan,

confederation, empire, 2nd edn (Salt Lake City, 1999), as well as the important study by

V. Minorsky, 'A civil and military review in Fars in 881/1476', Bulletin of the School of

Oriental and African Studies, 10 (1940 2), pp. 141 78.

72 Morgan, Medieval Persia, p. 106, suggests that the Aq Qoyunlu army in total would have

numbered maybe 100,000 men, including a sizeable contingent of infantry. Of course, a

force of this size was never actually gathered, and thus a Turcoman army on a given

campaign would have been smaller than many of the armies that the Ilkhans sent (or

led) against the Mamluks.

73 Bosworth, 'Army', EIr, vol. II, p. 503. Cf the wording in Woods, Aqquyunlu, p. 114; see on

p. 138 for an example of the effectiveness of Aq Qoyunlu artillery.

74 Woods, Aqquyunlu, p. 12. The tiyiil seems to have been similar to the soyurghal of the

Jalayirids, another post Mongol state in Iraq and the surrounding areas that is not

discussed here, as well as that of the Timurids (see below). For these terms, see the

comments of A. K. S. Lambton, Landlord and peasant in Persia (London, 1953), pp. 101 3;

558

Cambridge Histories Online © Cambridge University Press, 201 1

Armies and their economic basis in Iran

The armies of Temiir and his successors also come under our purview, albeit briefly, since they were active in much of Iran for many years, and controlled parts of the country for generations. Here, too, we also see a general continuation of the Mongol military tradition, the primary importance

of masses of light cavalry, based on the Turco Mongolian nomadic population

of Chaghadayid Transoxania (Ma Wara ] al Nahr) and surrounding areas,

especially eastern Khurasan (including modern northern Afghanistan). As in Azerbaijan, in the eastern parts of the Iranian world the tribesmen had undergone the double transformation of conversion to Islam and Turkification. Temiir himself was an embodiment of these changes. Mongol

memories remained strong among the elite and tribesmen alike, and there is

evidence that he himself had the model of Chinggis Khan before him. The traditional tribal leadership of Transoxania was replaced by Temiir with men

that he himself could trust, but the tribal structure was left more or less in

place, unlike the example of Chinggis Khan. The unity of the state and discipline of the tribes were facilitated by their frequent campaigning outside

the Chaghadayid homeland and the resulting booty. There is ample evidence

for the importance of Iranian military and civilian elites and soldiers (including

infantry) during Timurid times, in the conflicts between the Timurid scions

and also involving local leaders, siege warfare and perhaps also on far flung

campaign (although the role of such formations in the campaign in Syria in

1400 is unclear). 75 Again with the Timurids, little is known of how their armies

were paid. On one hand, the nomads would have maintained themselves through their pastoral economy; on the other hand, commanders and tribal

leaders were granted soyurghals, similar to the above mentioned tiyuls, which

entailed administrative and financial control over a region. Few details are

available of how this actually worked/6

Lambton, Continuity and change in medieval Persia, p. 129 and n. 90; Petrushevsky. 'The

socio economic conditions of Iran', p. 520; see the examples and discussion in

G. Doerfer, Tiirkische und mongolische Elemente im Neupersischen (Wiesbaden, 1963 75),

vol. I, pp. 351 3 (no. 228); vol. II, pp. 667 9 (no. 1014). V. Minorsky, 'A soyurghal of Qasim

b. Jahangir Aq qoyunlu (903 / 1498)', Bulletin of the School of Oriental and African Studies, 9

(i939), PP- 927 60, esp. p. 960, suggests that there is a fundamental difference between

the tiyul and soyurghal, the former being temporary, and the latter for perpetuity.

75 For the Timurid army, see: Morgan, Medieval Persia, pp. 84 93; B. F. Manz, 'The ulus

Chaghatay before and after Temiir's rise to power: The transformation from tribal

confederation to army of conquest', Central Asiatic Journal, 27 (1983), pp. 79 100; Manz,

'Military manpower in late Mongol and Timurid Iran', pp. 43 55; Manz, 'Nomad and

settled in the Timurid military', in R. Amitai and M. Biran, Mongols, Turks and others

(Leiden, 2005), pp. 425 57.

76 B. F. Manz, Tfie rise and rule of Tamerlane (Cambridge, 1989), p. 140; H. R. Roemer,

'Tlmur in Iran', in P. Jackson and L. Lockhart (eds.), The Cambridge history of Iran, vol.

VI: The Timurid and Safavid periods (Cambridge, 1986), pp. 94 5.

559

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

In many ways, the Timurid armies represent another example for the continuing overall superiority of tribal armies based on masses of mounted

archers vis d vis traditional (i.e. pre gunpowder) standing armies with large

components of infantry. When Temiir met the Ottoman sultan Bayezid near

Ankara in 1402, the latter was completely defeated in spite of the general high

quality of his army. But this was in retrospect the swansong of Inner Asian

style warfare: a century later, the tables would be turned, as the resurgent

Ottomans would show at Chaldiran in 1514.

Cambridge Histories Online © Cambridge University Press, 201 1

u Commercial structures

SCOTT C. LEVI

From ancient times, the eastward movement of precious metals in exchange for merchandise has been a defining feature of the commercial structure of the eastern Islamic world. Sources suggest that this pattern was well established already in the first century of the Common Era, and that it continued even into the nineteenth century. For example, in his Natural History, the Roman author and adviser to the emperor Vespasian (r. 69 79), Pliny the Elder (23 79), complained that 'in no year does India drain our empire of less than five hundred and fifty millions of sesterces, giving back her own wares in exchange, which are sold among us at fully one hundred times their prime cost'. 1 Pliny may have been guilty of exaggerating the effluence of Roman specie to India for effect, but his assertion nevertheless suggests that Rome suffered a substantial deficit in

its eastward trade. Also writing in the first century, the anonymous author

of a handbook for Roman travellers in the Indian Ocean indicated that much Roman specie was exchanged for Indian textiles, available in abun dance in the port of Baryagaza, in modern Gujarat. 2

Numerous accounts report a similar pattern of trade in the early modern era. Focusing on the growing European trade with Mughal India in the seventeenth century, the Italian physician Niccolao Manucci (1639 1717) observed that the Indian export commodities in greatest demand at the time cotton textiles, indigo, opium and silk were all agricultural in nature.

Echoing his ancient Roman predecessor, Manucci concluded that, 'for the export of all this merchandise, European and other traders bring much silver

1 John Bostock and H. T. Riley (trans.), The natural history of Pliny, 2 vols. (London, 1855),

vol. II, p. 63. A difficulty in interpreting the notation Pliny used to identify the monetary

figure has resulted in discrepancies in the various translations of this passage. Rather than

550 million, some translators have interpreted it to mean either 100 million or 50 million.

The citation is found in Book 6, Chapter 26.

2 L. Casson (trans.), The Periplus Maris Erythraei (Princeton, 1989), p. 16.

561

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

to India'. 3 The French traveller François Bernier (1625 88) emphasised the

magnitude of this trade deficit even further, asserting that 'gold and silver.

after circulating in every other quarter of the globe, come at length to be swallowed up, lost in some measure, in Hindoustan . 4 And while there has

been a tendency to privilege the early modern maritime trade over that conducted along the caravan routes, more recent work has demonstrated considerable vitality in the overland trade as well. This is supported by the

report of the French monk Raphael du Mans (d. 1696), who compared Persia

to a great caravanserai with two doors: silver entered through one in the west.

only to exit through another in the east and pass into India, 'where all the money in the Universe is unloaded as if into an abyss'. 5

Much of the Indo Islamic commerce in the period under consideration represents a continuation of earlier trade patterns. Economic historians have

tended to agree that, in general, the value of India's exports has greatly exceeded the value of its imports; that merchant groups have made up for

this trade imbalance by importing significant amounts of precious metals,

especially silver, to Indian markets; and that the sustained Indian demand for

specie is at least partly attributable to a lack of significant precious metal reserves in Indian soil, a deficit that has provided foreign merchants equipped

with gold or silver increased purchasing power in Indian markets. This chapter will elaborate upon this defining feature with the aim of introducing

some of the more important factors that constituted the commercial relations

of the eastern Islamic world and investigating the ways in which the commer

rial structures in this region developed in the period from the eleventh through the eighteenth century. While some attention is directed to impor

tant developments in the oceanic trade, for the sake of expediency, and because the vicissitudes of the Indian Ocean commercial history receive sufficient attention elsewhere in this volume, the discussion here focuses on

the region consisting of India, Afghanistan, Iran and Central Asia.

Readers will note that the role of India looms large in the discussion below.

This can be attributed to three factors of primary importance. First is that India

was by far the most populous region under consideration. It boasted a considerably larger agrarian civilisation and, by comparison, a highly devel

oped commercial culture. This contributed to India's roles as both the largest

producer of many commodities that enjoyed high demand, and the largest

3 Niccolao Manucci, Storia do Mogor, or Mogul India 1653 lyoS, 4 vols., trans. W. Irvine (London, 1907 8), vol. II, p. 418.

4 Francois Bernier, Travels in tfte Mogul empire, AD 1656 1668 (Westminster, 1891), p. 202.

5 Raphael du Mans, Estat de la Perse en 1660 (Paris, 1890), p. 192.

562

#### Commercial structures

consumer of others. Second is that India was situated at the fulcrum of the

Indian Ocean trade, which was significant well before the eleventh century

and became substantially more active following the arrival of European commercial interests and their rise to a position of maritime dominance in

the sixteenth century. The role that Europeans played in the changing commercial structures of the eastern Islamic world through both their own trade and their injection of vast amounts of precious metals originally

extracted from the Americas is an important component of our discussion and it will be addressed below. Third, especially from the rise of Turco Afghan political authority in north India in the eleventh century, regional powers across the eastern Islamic world worked to encourage overland commerce and keep the trade routes secure and vibrant. Sustained efforts

under the Delhi sultanate (1206 1555) and the Mughal empire (1526 1707)

ensured that the considerably larger Indian economy remained connected to

the markets of Afghanistan, Central Asia and Iran, and, through those regions, to more distant markets in northern Eurasia, the Near East and Europe. This subject is central to an understanding of the general commer

rial structure of the eastern Islamic world and it merits our present consideration.

State investment in the maintenance and improvement of trade routes connecting India with its neighbours to the north and west was a cornerstone

of the Delhi sultans' economic policies. This is demonstrated quite early on by

the deliberate efforts of sultans Iltutmish (r. 1211 36) and Balaban (r. 1266 87)

to suppress frontier tribal groups that had been obstructing commercial traffic. 7 In northern India, state investment in trade routes involved such initiatives as building new roads by clearing paths through forests, improving

roads by widening them to enable the use of wheeled vehicles, planting trees

alongside roads to provide shade for travellers, digging wells, constructing

caravanserais at regular intervals, providing military patrols to offer travellers

protection from highway robbers and even forcing local government admin

istrators to provide restitution to caravan traders whose goods were stolen

See Michael Pearson's Chapter 9 in this volume. The literature on this subject is

abundant. For several recent studies, see esp. Michael Pearson, The Indian Ocean

(London, 2003); Sugata Bose, A hundred horizons: The Indian Ocean in the age of global

empire (Cambridge, MA, 2006); Om Prakash, Bullion for goods: European and Indian

merchants in the Indian Ocean trade, yoo 1800 (New Delhi, 2004); Prakash, European

commercial enterprise in pre colonial India (Cambridge, 1998); Ashin Das Gupta, The

world of the Indian Ocean merchant, yoo 1800 (New Delhi, 2001).

Andre Wink, Al Hind: The making of the Indo Islamic world, vol. II: The slave kings and the

Islamic conquest of India, nth rfih centuries (Leiden, 1997), p. 216.

563

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

under their watch. Successful merchants augmented state efforts by financing

the construction of bridges, wells, caravanserais and more. And Muslim rulers

in north India were not alone in these efforts; ruling administrators in Central

Asia and Persia also appreciated the benefits to be derived from maintaining

regular transregional trade with their neighbours. The high esteem for trans

regional traders in the fifteenth century Timurid era is perhaps most clearly

expressed by the celebrated poet, author and father of the modern Uzbek language, Alishir Nawal (1441 1501). In his work, Mahbiib al quliib ('The beloved of hearts'), Nawal differentiates merchants into three categories: first were the transregional traders, whom he respectfully designates 'real

men'; these were followed by retail merchants, whom he derogatorily char

acterises as 'housewives'; and finally were the market sellers, whom he dismisses as 'godless liars'.

There were, naturally, periods of marked decline in commercial relations. Transregional trade networks were dislocated for periods lasting even several

decades by such events as the early thirteenth century Mongol conquest of

Central Asia and Iran and the mid fourteenth century Eurasian plague pan

demic. The disruptive effects of such events cannot be overstated, and in some

cases they served as catalysts for permanent structural transformations. Still,

considered over the longue duree, such traumas appear as temporary dis ruptions followed by lengthy periods of recovery. Although it would have provided no solace to those unfortunate enough to have suffered such profound devastations, in the years following the Mongol conquests those areas of the eastern Islamic world under Mongol rule benefited from a dramatic increase in the movement of people and goods. 9 A century and

half later, the armies of the Central Asian conqueror Temiir (1336 1405)

proved to be an incredibly destructive force but, as had been the case under

the Mongols, trade flourished where there was peace. For example, Temiir's

campaigns against the Golden Horde dealt a crushing blow to the trans Eurasian trade routes of the north, but they added considerable value to Temiir's own commercial centres in the south, especially his capital of Samarqand. Thus, at the very beginning of the fifteenth century, the Spanish envoy Ruy Gonzales de Clavijo described Samarqand as a magnificent

8 AEsher Navoiy, Mahbub al quliib, ed. A. N. Kononov (Moscow, 1948), pp. 42 3. See also Roziia

G. Mukminova, Sotsial'naia dijferentsiatsiia naseleniia gorodov Uzbekistana v XV XVI w. (Tashkent, 1985), pp. 114 15.

9 See Thomas T. Allsen, Commodity and exchange in the Mongol empire: A cultural history of

Islamic textiles (Cambridge, 1997); George Lane, Early Mongol rule in thirteenth century Iran:

A Persian renaissance (London, 2003).

564

Cambridge Histories Online © Cambridge University Press, 201 1

## Commercial structures

city and vibrant commercial centre, overflowing with people, merchants and

merchandise from across Asia. 10

The evidence has generally been interpreted to suggest that the overland 'Silk Road' trade of Central Asia remained active and relatively stable through

the fifteenth century. The continuity of such patterns in subsequent centuries,

however, has been perceived as less certain. The interpretation most com monly embraced was summarised in a contribution to The Cambridge history of

Islam, published in 1970, in which Bertold Spuler argued that, from the early

sixteenth century, Central Asia became isolated 'and therefore led an existence

on the margin of world history'. Spuler concluded, as have others writing before him and since, that the Europeans' 'discovery of the sea route to East

Asia rendered the Silk Road increasingly superfluous [and] from the threshold

of modern times Central Asian history becomes provincial history'. 11

More recently, the relationship between the rising European activities in the Indian Ocean and the overland caravan trade in the eastern Islamic world

has received more attention and some much needed revision. An abundance

of evidence has been produced to support the argument that the Mughal,

Safavid and Uzbek rulers all exhibited a keen appreciation for the role of commerce in maintaining a healthy state. Throughout the early modern era,

transregional trade among these regions continued at an escalated level, and

even during times of military conflict government administrators attached to

states that were otherwise hostile welcomed caravans into their territory and

regularly communicated to each other information regarding commerce. 12

According to Muzaffar Alam, from the early Mughal era the overall successes

in these efforts contributed to a process of urbanisation in the Punjab, Multan,

Sind and the areas north of Delhi, which spurred agricultural and industrial

production and the emergence of a quite impressive commercial culture in

10 Ruy Gonzalez, Narrative of the embassy of Ruy Gonzalez de Clavijo to the court of Timour in

Samarcand, AD 1403 6, trans. Clements R. Markham (London, 1858), p. 171.

- 11 Bertold Spuler, 'Central Asia from the sixteenth century to the Russian conquests', in
- P. M. Holt, Ann K. S. Lambton and Bernard Lewis (eds.), The Cambridge history of Islam,
- vol. 1:, Tfte central Islamic lands (Cambridge, 1970), pp. 470, 483. For a critical analysis of

this scholarly trend, see Scott Levi, 'India, Russia and the eighteenth century trans

formation of the Central Asian caravan trade', Journal of the Social and Economic History of

the Orient, 42, 4 (1999), pp. 519 48.

12 Muzaffar Alam, 'Trade, state policy and regional change: Aspects of Mughal Uzbek

commercial relations, c.  $1500\ 1750$  , Journal of the Economic and Social History of the Orient,

37, 3 (i994), PP- 214 19; see also Audrey Burton, The Bukharans: A dynastic, diplomatic and

commercial history, yyo 1702 (New York, 1997); Rudolf Matthee, The politics of trade in

Safavid Iran: Silk for silver, 1600 1730 (Cambridge, 1999); Willem Floor, The economy of

Safavid Persia (Wiesbaden, 2000); and Scott C. Levi, The Indian diaspora in Central Asia and its trade, yio 1900 (Leiden, 2000).

565

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

north west India. 13 In an effort to explore the general structures of this trade,

the following discussion surveys a number of the more important commod

ities involved in the commercial exchanges across the eastern Islamic world in our period.

### Commodities and commercial flows

Countless goods have been transported along the Eurasian trade routes. Still.

it is possible to identify several commodities that, when considered together,

constituted the major part of this commercial exchange in markets across the

eastern Islamic world. Perhaps most notable are a select few agricultural products that for reasons having to do with climate and other ecological conditions were produced exclusively in India or South East Asia. Spices, including especially pepper, cloves, cinnamon, nutmeg and mace, represent

the most obvious examples. The structure of the spice trade is discussed in

sufficient detail elsewhere in these volumes. It is worth stressing, however,

that the European trade in spices represented only a small fraction of the commercial economy in the eastern Islamic world as a whole, and even under

the Portuguese the trade in spices appears to have been substantially less

valuable than the trade in other commodities, especially textiles. 14

The large scale exportation of Indian cotton textiles to the ancient Mediterranean has been mentioned above, and considerable evidence demonstrates that Indian textile production and its westward trade con tinued at considerable levels in later centuries. At least insofar as it relates

to Egyptian trade in Indian cotton, the continuity of this pattern is sup ported by S. D. Goitein's conclusion that, in the eleventh and twelfth centuries, Egyptian cotton production 'was of no great consequence' and much of the Egyptian supply was acquired from India. 15 K. N. Chaudhuri

emphasises the importance of the Indian textile trade even further, assert

ing that, 'before the discovery of machine spinning and weaving in Britain

in the second half of the eighteenth century, the Indian subcontinent was probably the world's greatest producer of cotton textiles'. 1

13 Alam, 'Trade, state policy and regional change', pp. 202 27.

14 James C. Boyajian, The Portuguese trade in Asia under the Habsburgs, isSo 1640 (Baltimore, 1992).

15 S. D. Goitein, A Mediterranean society: The Jewish communities of the Arab world as portrayed in the documents of the Cairo Geniza, 6 vols. (Berkeley and Los Angeles, 1967 93), vol. I, p. 105.

16 K. N. Chaudhuri, 'The structure of Indian textile industry in the seventeenth and eighteenth centuries', Tfte Indian Economic and Social History Review, n, 2 3 (1974), p. 127.

566

Cambridge Histories Online © Cambridge University Press, 201 1

# Commercial structures

India's cotton textile exports enjoyed a dominant position in many Eurasian

markets, and this appears to have become considerably more pronounced during the early modern era as several factors contributed to a general increase in India's textile production. These included technological improve

ments, a substantial increase in India's population and, especially, the delib

erate efforts on the part of the Mughal administration to promote the textile

industry by providing incentives to farmers who produced valuable 'cash crops' such as cotton. 17 This provided Indian textiles a significant commercial

advantage in foreign markets. Thus, although cotton had been grown since

antiquity in Iran and the sedentary stretches of Central Asia, and both of these

regions boasted their own cotton textile industries, neither could compete

with Indian producers in terms of quantity, quality, variety and price. In the

seventeenth century, the French traveller Jean Chardin reported that, although Iranians produced some cheap calico, they lacked the motivation

to invest in finer varieties as they would be unable to compete with Indian

suppliers. 18

European demand for Indian textiles grew significantly in the sixteenth century, and already from the early seventeenth century the Dutch and English East India Companies became increasingly active participants in the

textile trade. Still, the European share in this trade constituted only a small

fraction of the total exchange. In the seventeenth century, Dutch East India

Company employees estimated that annual Iranian imports of Indian cotton

textiles amounted to some 25 30,000 camel loads. 19 While a portion of this was

destined for the Iranian markets, much of it was a part of a long established

transit trade that moved Indian textiles to markets in Central Asia, Russia, the

Ottoman empire and other areas further afield. The magnitude of the Asian

trade is illustrated by John Richards's observation that, even as the Dutch and English demand for Indian textiles increased dramatically at the end of

the seventeenth century with English East India Company imports reaching

17 Irfan Habib, 'The technology and economy of Mughal India', The Indian Economic and

Social History Review, 17, 1 (1980), pp. 6 10; Tapan Raychaudhuri and Irfan Habib (eds.),

The Cambridge economic history of India, vol. 1: c.1200 C.1J30 (repr. Hyderabad, 1984),

pp. 167 9; John Richards, The Mughal empire (Cambridge, 1993), p. 190; B. R. Grover,

'An integrated pattern of commercial life in the rural society of north India during the

17th 18th centuries', in Indian historical records commission:

Proceedings of the thirty seventh

session (Delhi, 1966), pp. 129 30.

18 John Chardin, Sir John Chardin's travels in Persia (London, 1927), pp. 278 9.

19 Niels Steensgaard, The Asian trade revolution of the seventeenth century: The East India

Companies and the decline of the caravan trade (Chicago, 1974), p. 410.

567

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

employed less than  $10\ \mathrm{per}\ \mathrm{cent}\ \mathrm{of}\ \mathrm{the}$  'full time weavers and other workers in

the textile sector of Bengal'. 20 Indian cloth remained widely available in markets throughout East Africa and much of Eurasia even into the nineteenth

century, when global markets were flooded with the less expensive fabrics

produced in Europe's industrial factories. This trade was complemented by

the large scale production and exportation of other agricultural products, including dyes, especially indigo, and sugar. Much as they did with cotton,

the Mughal rulers deliberately encouraged sugar and indigo production, and

both were exported in bulk to Iran, Central Asia and other Asian markets.

Indian exports were not restricted to agricultural goods, as is evidenced by

the movement of large numbers of Indian slaves to markets in Afghanistan,

Iran and Central Asia. 21 The early Ghaznavid and Ghurid invasions of north

India are reported to have included the exportation of tens of thousands of

enslaved Indians, or more. 22 The Tarikh i Firishta, a later chronicle based on

earlier sources, reports that, following the Ghaznavid capture of the Indian

city of Thanesar in the year 1014, 'the army of Islam brought to Ghazna about

200,000 captives (qarib do sit hazar banda), and much wealth, so that the capital

appeared like an Indian city, no soldier of the camp being without wealth, or

without many slaves'. The same source also mentions that the Ghaznavid ruler Sultan Ibrahim (r. 1059 99) led a raid into Multan and returned to Ghazna with 100,000 captives. 23 While it is prudent to question the reliability

of such later sources, it is important to note that Firishta's assertions are supported by the reports of contemporary observers. For example, al c Utbi,

author of the early eleventh century Ghaznavid chronicle, the Tarikh al Yamirii, records that, following his raids of 1018 19, Mahmud of Ghazna (r. 998 1030) returned to his capital with such a large number of slaves that

their value plummeted to between just 2 and 10 dirhams each. This price was

apparently quite affordable and 'merchants came from distant cities to pur

chase them, so that the countries of Ma wara 1 al nahr (Central Asia), Iraq and

Khurasan were filled with them, and the fair and the dark, the rich and the

poor, mingled in one common slavery'. 24

20 Richards, The Mughal empire, pp. 198, 203.

21 See Scott C. Levi, 'Hindus beyond the Hindu Kush: Indians in the Central Asian slave

trade', Journal of the Royal Asiatic Society, 3rd ser., 12, 3 (2002), pp. 277 88.

22 Cf. Wink, Al Hind, vol. II, p. 126 and n. 76; Raychaudhuri and Habib (eds.), The

Cambridge economic history of India, vol. I, pp. 89 90.

23 Tarikh i Firishta (Lucknow, 1864), pp. 27 8, 48 9. Cited in Wink, Al Hind, vol. II, pp. 126 7 n. 76.

24 al 'Utbi, Tarikh al Yamini (Delhi, 1847), pp. 395 408. Cited in Wink, Al Hind, vol. II, p. 126 n. 76.

568

Cambridge Histories Online © Cambridge University Press, 201 1

### Commercial structures

Indian slaves in Afghanistan, Central Asia and Iran were used for a wide variety of purposes. These included housework, soldiering, maintaining irri

gation canals, working in brick factories, serving as concubines and labouring

on plantation style farms; many others were taken into slavery precisely because they had received valuable training as construction engineers. 25

Skilled slaves were especially valuable, accounting for the common practice

of conquering forces enslaving and relocating skilled artisans. 2. During Temiir's sack of Delhi, for example, several thousand skilled artisans were

reportedly put into bondage and taken to Central Asia. Many of these were

given away as gifts, but Temiir is reported to have reserved all of the Indian

masons for his own construction projects in his capital of Samarqand. 27

The exportation of enslaved Indians appears to have persisted throughout

the Mughal era. Indeed, the Mughal emperor Akbar (r. 1556 1605) attempted

to prohibit the practice, but his efforts met with only limited success. 2 Thus, a

survey of seventy seven entries in the Majmtfa yi watha'iq, the register of a

qddi in Samarqand dating from 1588 92, regarding the manumission or sale of

slaves reveals that slaves of Indian origin (Hindi al asl) accounted for over

58 per cent of those whose region of origin is mentioned. 29 Several decades

later, the Dutch traveller Francisco Pelsaert (d. 1630) observed that, while in

the process of suppressing a rebellion, Abdallah Khan Firuz Jang, an Uzbek

noble at the Mughal court during the 1620s and 1630s, 'beheaded the leaders

and enslaved their women, daughters and children, who were more than 2 lacks [200,000] in number 1 . 30 It was common practice to send such captives to

markets beyond India's north west frontier, far from their family support systems. Even accepting that the figures presented in the chronicles and other accounts are likely to be exaggerated, it seems reasonable to conclude

that, over the years, at least several hundred thousand slaves were exported to

markets in Afghanistan, Iran and, especially, Central Asia.

The Central Asian slave trade continued even to the late nineteenth century, although, during the course of the eighteenth century, Iranians

25 Mukminova, Sotsial'naia differentsiatsiia, pp. 123 4.

26 Ibid., p. 125.

27 Beatrice Manz, The rise and rule of Tamerlane (Cambridge, 1989), pp. 80, 90;

Raychaudhuri and Habib (eds.), The Cambridge economic history of India, vol. I, p. 91.

28 Abul Fazl Allami, The Akbar Nama of Abu IFazl, 3 vols., trans. H. Blochmann (repr.

Delhi, 1998), vol. II, pp. 246 7.

29 See Levi, 'Hindus beyond the Hindu Kush', p. 284.

30 Francisco Pelsaert, A Dutch chronicle of Mughal India, ed. and trans. Brij Narain and Sri Ram

Sharma (Lahore, 1978), p. 48. See also Dirk H. A. Kolff, Naukar, rajput and sepoy: The

ethnography of the military labour market in Hindustan, 1450 iSjo (Cambridge, 1990),

pp. 12 14; Richards, The Mughal empire, p. 128.

569

Cambridge Histories Online © Cambridge University Press, 201 1

# The New Cambridge History of Islam

appear to have replaced Indians as the dominant population. This transforma

tion in the structure of the slave trade seems to have been precipitated by a

dramatic decrease in the supply of Indian slaves from the early eighteenth

century, as the Mughal empire decentralised and considerably fewer

were exported to foreign markets under the Mughal successor states. The

general decline in the availability of Indian slaves motivated Central Asian

slave traders to look elsewhere for a viable source to satisfy the substantial

demand. From the early eighteenth century, this, along with the decline of

Safavid defensive capabilities, motivated the infamous Turkmen slave raiders

to look to the numerous comparatively close, and poorly defended, Iranian

cities and villages for their unfortunate victims.

It was noted above that India enjoyed a generally favourable trade balance,

receiving large amounts of precious metals in exchange for exports that included a vast surplus of agricultural products and other merchandise. Willem Floor's detailed analysis of the Safavid economy similarly recognises

that Iranians enjoyed bilateral commercial relations with virtually all of their

neighbours, but that Iran suffered a substantial trade deficit with India result

ing in a persistent effluence of silver from Safavid markets. 31 By and large, the

Iranians managed to offset this deficit by exporting the larger part of their

Indian imports and maintaining an overall positive trade balance with other

neighbours, including especially the Ottoman territories. It should also not be

overlooked that the Safavids made a concerted effort to bolster their economic

position vis a vis India by developing a sizeable silk industry, the products of

which were largely exported to foreign markets mostly to the west, but also in

India. 32

India did import Iranian silk and some other commodities, but, with the exception of precious metals, no commodity enjoyed greater sustained demand in Indian markets than horses. The magnitude of the horse trade was remarkable. Unless, that is, one considers that the Inner Asian steppe was

home to several million pastoral nomads whose primary economic activity

included the breeding and raising of horses and other livestock, both for their

own use and to trade with sedentary states in exchange for foodstuffs, manufactured goods and other necessities of life. Because of their availability

in large numbers and their reputation for strength and stamina, horses bred in

Inner Asia enjoyed widespread demand throughout much of Eurasia.

31 Floor, The economy of Safavid Persia, pp. 183 96.

32 Ibid., pp. 172 7. See also Matthee, The politics of trade in Safavid Iran, and Ina Baghdiantz

McCabe, The shah's silk for Europe's silver: The Eurasian trade of the Julfa Armenians in

Safavid Iran and India (1530 1750) (Atlanta, 1999).

# Commercial structures

The few first hand observations of the Indo Islamic horse trade provide some insight into the structures of this trade. In the mid fourteenth century,

the Moroccan traveller Ibn Battuta visited southern Russia, the territory of the

Mongol Golden Horde at the time, where he observed pastoral nomadic peoples who made their living by raising large numbers of horses, many of

which were transported to India. Although his account makes no mention of

the mediatory merchants responsible for moving the animals between the steppe and India, it does provide a sense of the value of this trade. According to

Ibn Battuta, horses were available for purchase in the steppe for 50 or 60 dirhams each, equal to about 1 Moroccan dinar. 33 He further reported that:

These horses are exported to India [in droves], each one numbering six thousand or more or less . . . When they reach the land of Sind with their horses, they feed them with forage, because the vegetation of the land of Sind

does not take the place of barley, and the greater part of the horses die or are

stolen. They are taxed on them in the land of Sind [at the rate of] seven silver

dinars a horse, at a place called Shashnaqar, and pay a further tax at Multan,

the capital of the land of Sind ... In spite of this, there remains a handsome

profit for the traders in these horses, for they sell the cheapest of them in the

land of India for a hundred silver dinars (the exchange value of which in Moroccan gold is twenty five dinars), and often sell them for twice or three

times as much. The good horses are worth five hundred [silver] dinars or

Inner Asian horses were in demand throughout the subcontinent, and they

reached South Asian markets both by overland routes traversing Afghanistan

and by the maritime routes of the Persian Gulf. Already in the thirteenth century, Marco Polo observed that each year the rulers of Malabar received as

many as 10,000 horses by sea, for which they reportedly spent some 2.2 million

dinars. Shedding some light on the reasons behind the sustained demand for

this commodity, Polo reported that, of the total number of horses that reached

Indian ports by sea, 'by the end of the year there shall not be one hundred of

them remaining, for they all die off. And this arises from mismanagement, for

those people do not know in the least how to treat a horse.' 35 Some two centuries later, in 1466, the Russian traveller Afanasi Nikitin made his way to

India by ship, embarking at the Persian Gulf port of Hormuz, which he

33 Ibn Battuta, The travels of Ibn Battuta, AD 1325 1354, trans. H.A. R. Gibb, 3 vols. (New Delhi, 1993), vol. II, p. 478.

34 Ibid., pp. 478 9 and n. 242.

35 Marco Polo, Thebook of Ser Marco Polo, 2 vols., ed. and trans. Sir Henry Yule (New York, 1903), vol. II, pp. 340, 348 9.

571

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

described as 'a vast emporium of all the world'. 36 Nikitin was in central India

for four years, much of which he spent in Bidar, the capital of the Bahmani

sultanate, where he was surprised to find that the markets of the Deccan were

full of horses, and that, although 'horses are not born in that country', they

were widely available, having been imported in large numbers from Arabia,

Khurasan and Turkistan. 37 These numbers must have been very large indeed

as Sultan Muhammad III (r. 1463 82) was reportedly able to raise military

forces that included half a million cavalry soldiers. 38 Again, even appreciating

that such figures may have been gross exaggerations, the evidence suggests a

lengthy commercial relationship that included: Indian consumers throughout

the subcontinent; pastoral nomadic horse breeders in Afghanistan, Iran and,

especially, the Inner Asian steppe; and mediatory pastoral nomadic tribesmen

who moved the herds between regions.

Later accounts suggest that India's demand for horses increased significantly

during the early modern period. Writing in the mid seventeenth century, Francois Bernier reported that over 25,000 horses were brought to India annually from Uzbek territory, with additional numbers coming overland from Iran through Kandahar and from Iran and Africa by sea. 39 Jean Baptiste

Tavernier and Jean de Thevenot both independently place the figure higher,

each suggesting that Uzbek mediatory merchants brought over 60,000 horses

per year to Kabul. 40 Writing in the second half of the seventeenth century,

Manucci asserted that every year over 100,000 horses were imported to India

from Balkh, Bukhara and Kabul, of which 12,000 went directly into the stables of

the Mughal emperor Aurangzeb (r. 1658 1707). 4I

Several factors contributed to India's apparently insatiable demand for this commodity. Most obviously, from the eleventh century Ghaznavid invasions to the nineteenth century British Raj, horses played an important

role in Indian warfare. 41 However, because of inadequate pasture land and India's tropical climate, efforts to breed horses in India were largely

36 Afanasi (Athanasius) Nikitin, The travels of Athanasius Nikitin of Twer, in R. H. Major

(ed.), India in the fifteenth century, Hakluyt Society, istser., 22, part 3 (London, 1857), p. 19.

37 Ibid., pp. 10, 12, 20.

38 Ibid., pp. 278.

39 Bernier, Travels in the Mogul empire, p. 203.

40 Jean Baptiste Tavernier, Les six voyages de Jean Baptiste Tavernier, Ecuyer Baron

d'Aubonne ..., 2 vols. (Utrecht, 1712), vol. II, p. 63; Surendranath Sen (ed.), Indian travels

of Thevenot and Careri (New Delhi, 1949), p. 80.

41 Manucci, Storia do Mogor, vol. II, pp. 390 1.

42 See the essay on the horse trade and the importance of cavalry in medieval Indian warfare

in Wink, Al Hind, vol. II, pp. 79 95. See also Jos J. L. Gommans and Dirk H. A. Kolff(eds.),

Warfare and weaponry in South Asia, 1000 1800 (New Delhi, 2001).

572

Cambridge Histories Online © Cambridge University Press, 201 1

### Commercial structures

unsuccessful. 43 Not only did horses suffer in the severe heat, but, instead of

hay or the nutritious broad leaf grasses found in the Inner Asian steppe, horses in India were fed mostly grains. The combination of poor diet, lack of

adequate pasture and insufficient exercise during India's hot season caused

Indian horse breeds to suffer dwarfing, and mares in India quickly became

infertile, further decreasing the ability of Indian breeders to maintain their

own stock. 44 The available evidence has led Jos Gommans to advance the

rather conservative estimate that, on average, during the eighteenth century

India's entire horse population of between 400,000 and 800,000 needed to be

replaced every seven to ten years, depending on the intensity of military conflict in the subcontinent. 45 Extrapolating from this, Gommans suggests

that the overland horse trade was valued at around 20 million rupees each

year, amounting to 'more than three times the total of Bengal exports to Europe by the English and Dutch East India Companies together'. 46

Shifting commercial structures from the sixteenth century

Focusing on the rising European commercial activities in the Indian Ocean has

led some scholars to conclude that certain organisational structures gave the

European companies an advantage over their Asian competitors. Many authors have presumed that, as European traders grew undeniably more active in the Indian Ocean commercial arena, the overland caravan trade operated by disadvantaged Asian pedlars fell into a corresponding decline,

leaving large parts of the eastern Islamic world disconnected from larger global economic processes. In recent years, these views have been contested

and substantially revised. Sushil Chaudhury and Michel Morineau have con

eluded that, during the 'Age of Competition' between European and Asian merchants (sixteenth to eighteenth centuries), neither enjoyed an inherent

advantage and the vast majority of Asian trade remained in the hands of Asian

merchants. 47 A considerable amount of evidence has been produced to sup

port this thesis and suggests that, throughout our period, indigenous com mercial enterprises across the eastern Islamic world remained substantially

43 Jos Gommans, The rise of the Indo Afghan empire, c.iyio lySo (Leiden, 1995), p. 17;

Richards, The Mughal empire, p. 64.

44 Gommans, The rise of the Indo Afghan empire, p. 73.

45 Ibid., p. 89.

46 Ibid.

47 Sushil Chaudhury and Michel Morineau (eds.), Merchants, companies and trade: Europe

and Asia in the early modem era (Cambridge, 1999), pp. 7 9, 300 20.

573

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

larger than European commercial interests in those markets. That is not to say

that the rise in European commercial activities was in any way irrelevant. Ouite

to the contrary, one might also argue that no single development exerted a

greater influence on commercial trends in the eastern Islamic world than the

Europeans' rising demand for commodities produced in Asia, and their ability to

purchase these goods with vast supplies of silver. 48 Recent scholarship indicates,

however, that the increase in Europeans' commercial activities contributed to a

corresponding rise in indigenous merchant networks as well.

The vast majority of the specie that European merchants brought to the Indian Ocean economy originated in the New World, where the Spanish colonisers aggressively accumulated the gold and silver that was in circulation

and established an elaborate network of mining settlements to extract more.

Even considering the superior value of gold, the total value of the silver was

monumentally higher. There is some debate regarding the amount of American silver put into circulation from the early sixteenth century, but even conservative estimates suggest that it totalled tens of thousands of tons. 49

Others place the figure much higher, suggesting that it reached even into the

tens of thousands of tons each year. 50 There is general agreement, however,

that as ships loaded with specie sailed both east and west from the Americas,

much of this wealth circulated around the globe and found its way into the

European, Chinese and Indian Ocean economies. Contrary to the assertions

by Manucci, Bernier and du Mans cited above, India was not the terminal destination for all of the specie in circulation around the globe. Indeed, the

Chinese economy appears to have absorbed at least as much as India, and

perhaps substantially more. But neither was the New World the sole source of

silver put in circulation during this period. Japan retained an earlier position as

a major silver producer and, from the early eighteenth century, the global

supply was augmented by a dramatic increase in the productivity of silver

mining in various locations across Russia. 51 The injection of vast amounts of

precious metals over an extended period beginning in the mid sixteenth century had profound ramifications for the economy of the eastern Islamic

world and the commercial structures connecting its various regions.

48 See Andre Gunder Frank, Reorient: Global economy in the Asian age (Berkeley, 1998), pp. 131 64.

49 See Stanley J. Stein and Barbara H. Stein, Silver, trade and war: Spain and America in the making of early modern Europe (Baltimore, 2000), pp. 21 6.

50 Robert Tignor, Jeremy Adelman, Stephen Aron et ah, Worlds together, worlds apart (New York, 2002), pp. 102 4.

51 Ian Blanchard, Russia's 'age of silver': Precious metal production and economic growth in the eighteenth century (London, 1989).

# Cambridge Histories Online © Cambridge University Press, 201 1

### Commercial structures

One product of the dramatic increase in the circulation of precious metals in

this era was the development in north India of what Sanjay Subrahmanyam

and C. A. Bayly have termed a 'portfolio capitalist' economy. 52. These authors

argue that, from the sixteenth century, Indian capitalists began to invest heavily in agricultural production, labour and trade and, functioning in con

junction with heavily capitalised Indian banking firms, these commercial organisations became more visible in state and military finance. 53 Other authors have argued alongside this notion, adding that the increased mone

tisation of the Indian economy in this period a direct product of European trade in the Indian Ocean contributed greatly to the growth of Indian commercial firms, their ability to diversify their portfolios by expanding into

new areas of the Indian economy and, from the mid sixteenth century, their

willingness to diversify geographically by seeking out lucrative commercial

opportunities in under exploited markets beyond the boundaries of the

continent. 54 It was noted above that the overland caravan trade appears to

have grown significantly from the eleventh century. Some five centuries later,

the emergence and development of several sizeable indigenous merchants

networks, or trading diasporas, represent an even greater strengthening of the

commercial structures of the eastern Islamic world. It should be stressed that,

contrary to triggering its decline, in some important ways the rise of European

commercial activities in the Indian Ocean appears to have actually spurred a

corresponding increase in the overland caravan trade as well.

During the second half of the sixteenth century, heavily capitalised, caste

based Indian firms established a commercial network with diversified interests

across this region. They were not, however, the only network in operation at

that time. Indians worked alongside, competed against and occasionally established partnerships with agents attached to Armenian, Iranian, Central

Asian, Chinese, Russian and other commercial organisations. Armenian mer

chants especially are known to have operated an impressive merchant dia

spora from their newly adopted (1604 5) home of Newjulfa, a suburb of the

52 Sanjay Subrahmanyam and C. A. Bayly, 'Portfolio capitalists and the political economy

of early modern India', The Indian Economic and Social History Review, 25, 4 (1988), pp. 401 24.

53 Ibid., p. 414.

54 Cf. Levi, The Indian diaspora; Stephen Dale, Indian merchants and Eurasian trade. 1600

1800 (Cambridge, 1994); Claude Markovits, The global world of Indian merchants. 1750 1947:

Traders of Sindfrom Bukhara to Panama (Cambridge, 2000); Markovits, 'Indian merchants

in Central Asia: the debate', in Scott C. Levi (ed.), India and Central Asia: Commerce and

culture, yoo 1800 (New Delhi, 2007), pp. 123 51.

575

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Safavid capital of Isfahan. 55 By the middle of the seventeenth century, however,

the Indian merchant diaspora had grown to become the most expansive

commercial network in the region, with some 35,000 merchants living in a

vast, interconnected network of communities that stretched across Afghanistan,

Central Asia, Iran and even into Russia. The largest Indian merchant commun

ity was by far the one in Isfahan, which numbered more than 10,000 Indian

merchants. Other sizeable Indian communities were located in Kabul and Kandahar in Afghanistan, Bandar 'Abbas in the Persian Gulf, Bukhara in Central Asia and the Russian port city of Astrakhan at the mouth of the Volga, on the Caspian Sea. In addition to being the largest merchant network

these merchants were also arguably the most influential ones of the region.

They were widely known for their large scale transregional trade in a number of

commodities, especially Indian textiles, and also for their deliberate and wide

spread moneylending activities in both urban and rural markets. A brief survey

of the Indians' commercial system provides some important insights into the

commercial structures that connected the various regional economies across

much of the eastern Islamic world.

Even before Indian firms began dispatching agents to markets in Afghanistan, Iran and Central Asia in the mid sixteenth century, north Indian portfolio capitalist firms had developed a reliable system to enlist agents (gumdshta) and prepare them to work in distant locations. Firm direc

tors enlisted agents and put them through a lengthy period of apprenticeship,

after which they advanced their agents a certain amount of capital, generally in

the form of a commodity for export. Because of their established role as creditors to farmers and weavers in the subcontinent, to whom they advanced

raw cotton in exchange for a portion of the finished cloth, cotton textiles were

available to the firms in large quantities at below market prices. For that reason, and because Indian cottons enjoyed considerable demand in foreign

markets, cloth constituted an especially important commodity in the Indians'

export trade. The agents then arranged to transport their merchandise by

caravan and, after a period of travel that might last even several months, they

would take up residence in a caravanserai, a hostel for merchants, where they

would begin to sell their goods.

During their time abroad, the agents were trained to put their capital to work by reinvesting it in other commercial activities, most commonly in

55 In addition to the works by Matthee and McCabe, cited above, see Edmund Herzig,

'The rise of the Julfa merchants in the late sixteenth century', in Charles Melville (ed.),

Safavid Persia: The history and politics of an Islamic society (London, 1996), pp. 305 23.

576

Cambridge Histories Online © Cambridge University Press, 201 1

### Commercial structures

interest earning moneylending ventures in both urban and rural markets. Because many farmers were dependent on credit to get their crops planted,

agricultural loans constituted an especially important and very lucrative venture. To be sure, Indian merchants operated alongside local institutions

that also provided rural credit to farmers. However, because of their training

and their access to substantial capital reserves, the Indians generally proved

quite competitive in rural markets. Indians also commonly purchased for cash

the remainder of the harvest and arranged for its sale in regional or urban

markets. The Indian merchants therefore operated at a critical juncture between urban and rural markets. They served their host societies by provid

ing investment capital to facilitate agricultural production even when local

peoples could not afford the initial investment, and also by extending a monetised economy into the countryside, which greatly facilitated the collec

tion of taxes in cash.

As was the case for many foreign merchant groups, Indian merchants provided a number of other valuable services to their host societies. Most obviously, they are known to have purchased and arranged for the export of

local production. It was observed already in the mid sixteenth century that.

rather than exporting Indian specie to Central Asia in order to purchase horses, it was common for Indian merchants to sell their Indian merchandise

in Central Asia and, after setding their accounts, transport their wealth back to

India in the form of horses, or another commodity (such as silver) available in

Central Asia and in demand in Indian markets. 56 In various locations, Indian

merchants are also known to have offered numerous other financial services

to the state. These include: collecting revenue, extending credit to the nobil

ity, financing military campaigns, managing trade routes and even serving in

high posts in the states' financial administrations. The combination of these

factors at least partly explains the motivation of Muslim administrators to protect the Indian merchants and ensure that they could conduct their busi

ness in a safe, predictable and reasonably agreeable social climate. For more

than three centuries, tens of thousands of Indian merchants employed the vast

resources of India's agrarian economy as an engine for investment in distant

markets and alongside their Bukharan, Armenian, Iranian and other merchant colleagues they served as a structural bond connecting various regional economies of the eastern Islamic world.

56 Anthony Jenkinson, Early voyages and travels to Russia and Persia ..., ed. E. Delmar

Morgan and C. H. Coote, Hakluyt Society 2 vols., 1st ser., 72 3 (London, 1886), vol. I, p. 88.

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

The eighteenth century

In the first decades of the eighteenth century, imperial authority rapidly deteriorated in both Safavid Iran and Mughal India. The factors behind the

series of invasions, rebellions and civil wars that precipitated the political decentralisation of these two empires lie beyond the parameters of our present discussion. The period of crisis itself is germane, however, insofar as

it had a significant impact on commercial structures across the region. This is

especially so as the turmoil was extended by the rise to leadership in Iran of

Nadir Shah Afshar (r. 1736 47), a Turkmen military commander who had earlier served under the Safavid emperor Shah Tahmasp II (r. 1722 32). During

his short reign as ruler of Iran, Nadir Shah extinguished the Safavid dynasty,

ran an extremely destructive campaign into India that culminated with

infamous sack of Delhi in 1739, and forced into submission the ruler of Bukhara, Abu'l Fayd Khan (r. 1711 47), directly contributing to the collapse

of his Ashtarkhanid dynasty (1599 1747) and the end of Chinggisid rule in the

region. These invasions resulted in the temporary economic dislocation of regional economies across Iran, north India and Central Asia. The economic

downturn was most severely felt in north India, as the Iranian victory over the

Mughal defenders brought an abrupt and acute reversal in monetary flows; in

addition to killing some 30,000 people, the Iranian invaders departed with an

amount of wealth estimated to have been between 500 million and 1 billion

rupees.

While terribly traumatic for the north Indian economy, these events appear

to have contributed to economic growth elsewhere. Upon his return to Iran,

Nadir Shah declared a three year tax moratorium, and de thesaurised rupees

were put in circulation across much of the eastern Islamic world. Within just a

few years, Central Asian traders are reported to have arrived at the newly

established Russian trading fortresses in the southern parts of the empire with

'bags full of Indian Rupees'. 57 And in 1750, a new regional market was opened

in Troitsk, located between the earlier markets at Orenburg and Omsk, at which prices were listed in both rubles and rupees. 58 Even in Iran, however,

economic growth was muted and perhaps even reversed by the shortsighted

and predatory policies that Nadir Shah imposed on foreign merchant communities in his territory, especially the Indians. Reports indicate that Nadir

Shah used the Hindus' unprotected status as a pretence to confiscate much of

57 Gommans, The rise of the Indo Afghan empire, p. 29.

58 E. la. Liusternik, Russko indiiskie ekonomicheskie sviazi v XIX v. (Moscow, 1958), p. 12.

578

Cambridge Histories Online © Cambridge University Press, 201 1

### Commercial structures

their wealth and property. By the time Nadir Shah was assassinated in 1747, the

Indian presence in Iran had dwindled almost out of existence.

Focusing their attention on India, Subrahmanyam and Bayly have argued that in the late eighteenth and early nineteenth centuries, the earlier portfolio

capitalist economy was 'swept away' by the imposition of a colonial economy.

Transformations in the commercial structures in Iran in the second half of the

eighteenth century suggest that much the same could be said for the larger

region. The revival of Indo Iranian commercial relations began under Muhammad Karim Khan Zand (r. 1751 79), who reinstated a policy of toler

ance towards foreign merchant communities in southern Iran. Soon thereafter

significant numbers of Indian merchants began to return to Iranian markets

and, along with Parsis and New Julfa Armenians, they resumed an active role

in the mediation of Indo Iranian transregional trade. But the most notable

development in this period was the rise of British commercial activity in the

Persian Gulf. British merchants benefited from their state's mercantilistic policies in both India and southern Iran, and, although they never established

a monopoly on the trade between these two regions, they did manage to coerce Asian merchants Indians, Armenians and Parsis to use British ships

to transport merchandise between the two countries. As this further devel

oped over the course of the nineteenth century, the overland caravan trade

through Afghanistan gave way to the maritime trade, fully under European

dominance.

Further to the north, the disruptive effects of Nadir Shah's invasions were

less pronounced than they had been in Iran and north India and, by and large,

earlier commercial structures continued unimpeded through the eighteenth

century. In fact, the rise of the Indo Afghan Durrani state in Afghanistan facilitated Indo Central Asian trade as the Durrani administration welcomed

Indian merchant communities, and encouraged caravan traffic and the horse

trade through Afghan territory. 59 Even as late as the 1770s, the French traveller

Comte de Modave reported that some 45,000 to 50,000 horses were still imported to India from Central Asia and Iran each year.  $^{\circ}$  During the eight

eenth century, Indians' commercial activities in Central Asia continued much

as they had during the previous two centuries, and they demonstrated con

siderable financial agility by expanding their activities into emerging markets,

such as those in the Farghana valley.

59 Gommans, Tfie rise of the Indo Afghan empire, passim.

60 Comte de Modave, Voyage en Inde du Comte de Modave, 1773 1776, ed. J. Deloche (Paris, 1971), P- 327-

579

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

In the eighteenth century, as European interests continued to expand in the

Indian Ocean and the Bukharan khanate weakened and toppled, the Central

Asian caravan trade remained active and in some ways grew along both latitudinal and longitudinal routes. It should be noted that this was a period of

transition and that economic growth was inconsistent. Thus, substantial and

irrefutable evidence suggests that some areas, such as Samarqand, suffered

economic hardship, de urbanisation and decline. But just as shifting commer

cial patterns pushed some parts of Central Asia to the periphery, other parts

became linked more closely to the larger economies of India, China and Russia, and these regions enjoyed growth in commercial activity, agricultural production, population size and military strength. This is perhaps most notable in the Farghana valley, which, from the early eighteenth century, began to benefit from its position on trade routes leading across the Tien Shan

mountains and on to the markets of Qing China (1644 1911). This position

became considerably more important after the Qing conquest of the province

later known as Xinjiang in 1758 9 brought the frontier of the Chinese empire

to the borders of the Farghana valley. J Soon thereafter, the Uzbek Ming ruler

of Khoqand, Irdana Biy (r. 1751 63), accepted a nominally subordinate position

to the Qian Long emperor (r. 1736 95), and the Farghana valley was poised to

become a crossroads of Eurasian trade.

Irdana Biy and his successors strategically exploited their relationship with

the Qing to improve Khoqand's access to Chinese markets and reap the benefits of taxing a more active commercial exchange between China and other Eurasian markets. Within a few decades, merchants from the Farghana

valley developed a sizeable network of commercial communities in urban centres across Xinjiang. 2 Rulers of Khoqand used the resources retrieved

from their eastward trade with China to improve their military power and political position in the Farghana valley, to expand their agricultural tax base

by sponsoring several sizeable irrigation projects, and also to challenge Bukhara's commercial and regional dominance. While some corners of Central Asia were suffering decline and de urbanisation, by the first decades

of the nineteenth century, the khanate of Khoqand, centred in the Farghana

valley, boasted a vibrant commercial economy and had grown to rival Bukhara in population and exceed it in size.

61 L.J. Newby, The empire and the khanate: A political history of Qing relations with Khoqand c. 1760 i860 (Leiden, 2005).

62 Ibid., pp. 45 50, 64 6; Saguchi Tom, 'The eastern trade of the Khoqand khanate',

Memoirs of the Research Department of the Toyo Bunko (The Oriental Library), 24 (1965),

580

Cambridge Histories Online © Cambridge University Press, 201 1

#### Commercial structures

These processes were greatly advanced as Tsarist Russia pushed its frontier

southward into the steppe and, from the late eighteenth century, emerged as

an even greater commercial presence in the region than China. Central Asian

merchant communities from Bukhara, Khiva, Khoqand and elsewhere were

eager to take advantage of the growing opportunities offered by the emerging

Russian markets in the north, the trade with which was mediated through a

network of frontier fortresses. Omsk was established in 1716 and followed by

Semipalatinsk, 'Ust Kamenogorsk, Orsk, Troitsk, Uralsk and others. Already

by 1743, this 'Orenburg Line' of militarised commercial outposts stretched

across the steppe, protecting Russian political and commercial interests from

nomadic tribes and significantly advancing Russia's trade. In the early nine

teenth century, as the merchants of Khoqand directed their attention to the

growing trade with Russia, rulers redirected their territorial ambitions to the

north and west, where they conquered Tashkent and reached even as far as Aq

Masjid (modern Kyzyl Orda, in Kazakhstan), a trading post settlement where,

a few years later, Khoqand would build a fortress to protect its quickly growing trade with Russia. Drawn by Russian silver, furs and manufactured

goods, merchants came from as far away as India and the Ottoman empire

leading hundreds of camels loaded with spices, bricks of tea, cotton and silk

textiles, Kashmiri shawls and other commodities in great demand in the markets of Moscow, St Petersburg and elsewhere in Europe. In some ways,

these commercial structures remained in place even to the end of the nine

teenth century, when the expansion of Russian colonial authority across Central Asia brought that region too under a colonial economy.

581

Cambridge Histories Online © Cambridge University Press, 201 1

i8

Transmitters of authority and ideas across

cultural boundaries, eleventh to

eighteenth centuries

MUHAMMAD QASIM ZAMAN

There is much that the c ulamd' of the eastern Islamic lands shared, in terms of

their conceptions of the scholarly tradition and of the practices constitutive of

it, with religious scholars elsewhere and, despite the transformations they

have undergone since the nineteenth century, many of these conceptions and

practices have continued to characterise their scholarly culture. 1 What are

these practices? In what directions did they evolve during the centuries and in

some of the regions with which this volume is concerned? How was the sense

of a tradition, and of religious authority, articulated through them? These are

among the questions this broad overview of the Islamic scholarly culture, and

of those contributing to it, seeks to address. 2

The 'ufamff's scholarly endeavours during much of the period which is the

subject of this volume have often been viewed as a 'sterile commentarial literature';

and it is not just Western scholars of an earlier generation but also Muslim

modernists and Islamists of colonial and post colonial Muslim societies who have

often concurred with this judgement. 3 The 'ulama''s own rhetoric during these

Cf. Muhammad Qasim Zaman, The ulama in contemporary Islam: Custodians of change (Princeton, 2002).

"Ulama" refers here, primarily though not exclusively, to scholars of hadith and law as

well as exegetes of the Qur'an, grammarians and lexicographers, and theologians. It was

common for the 'ulama' during these centuries to have Sufi affiliations but, though we

will touch upon this aspect of the 'ulama'' % culture, it is not central to the discussion here.

The primary focus of this chapter is, moreover, on the Sunni rather than the Shi'I

religious scholars.

The phrase quoted here is that of Fazlur Rahman (d. 1408/1988), one of the most

sophisticated Muslim modernists of the twentieth century and himself a scholar of

medieval Islamic philosophy and law. See his Islam and modernity: Transformation of an

intellectual tradition (Chicago, 1982), p. 63. And cf. Louis Gardet, 'Religion and culture', in

P. M. Holt, Ann K. S. Lambton and B. Lewis (eds)., The Cambridge history of Islam, 2 vols.

(Cambridge, 1970), vol. II, pp. 569 603, for an overview of the 'extremely rich and

### Cambridge Histories Online © Cambridge University Press, 201 1

### Transmitters of authority and ideas

centuries often did much to lend credence to the view that members of this

scholarly culture were but a pale reflection of incomparably superior predeces

sors. The comment of Mulla 'Ali al Qari (d. 1014/1605) a scholar ofhadiih and

law from Herat who later settled in Mecca concerning a famous hadith report

which promises a religious revival every hundred years was not atypical. 'Knowledge is continually in decline from year to year, just as ignorance is

constantly making progress,' he noted, and then went on to observe: 'indeed, the

advancement of the scholars of our time is only a function of the decline of

knowledge in our age'. 4

Not all 'ulama' were equally reticent, however, in denying that they might compare favourably with earlier figures. As Shah Wall Allah Dihlawi

(d. 1176/1762), one of the most important Indian thinkers of the twelfth/eight

eenth century, had remarked in concluding his best known book, Hujjat Allah al

baligha, the generality of people living in an earlier age, namely one closer to the

emergence of Islam, are better than those of later generations, but not all are

inferior to their forebears, whose generations were not lacking in their sinners

and their hypocrites; and, in any case, as the Prophet had said, his 'community is

like rain, whose first drops cannot be said to be better than its last'. 5 Even All al

Qari, in the same context in which he had made his caustic remarks about the

inadequacy of his contemporaries, had also observed that the periodic revival

promised by the Prophet did not necessarily refer to the work of a single

individual. As 'AE al Qari understood it, this renewal was a 'cumulative matter'

(amr ida.fi) and one that consisted of the activities of a group of people. 'Each

member of the group helps, in a particular land, to revive one or more of the

religious sciences through his speech and writing, thus becoming the cause of

their preservation, of saving them from extinction until God so decrees.'

Despite professions to the contrary, 'All al Qari's view does not signal any lack of confidence in the l ulama''s abilities to combat an allegedly chronic

decline. The period with which this volume is concerned and not just its earlier but also its later centuries was an age of rich scholarly activity, of the

emergence and diffusion of new institutions, of the expansion of Islam in, inter

complex collection of disciplines' in medieval Islam which concludes, however, with the

observation that '[fjrom the ninth/fifteenth century onwards, the "religious sciences"

scarcely developed at all' (ibid., pp. 600, 603).

4 Mulla 'Ali b. Sultan al Qari, Mirqat al mafafk shark Mishkat al masaWi, ed. S. M.J. al 'Attar,

10 vols. (Beirut, 1992), vol. I, p. 507. On the hadtth in question, see Ella Landau Tasseron, "The

"cyclical" reform: A study of the mujaddid tradition', Studia Islamica, 70 (1989), pp. 79 117.

5 Shah Wall Allah Dihlawi, Hujjat Allah al baligha, ed. S. Sabiq, 2 vols. (Cairo, 1964), vol. II,

pp. 885 6. On this hadtth, see A.J. Wensinck, Concordance et indices de la tradition musul

man, 8 vols., 2nd edn (Leiden, 1992), vol. VI, p. 241 (s.v. m t r).

6 'All al Qari, Mirgat, vol. I, p. 507.

583

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

alia, South and South East Asia, and of multifaceted interaction between these

new lands and older centres of Islamic learning. This chapter does not seek to

provide any comprehensive account of these developments, let alone to assess the

relative 'originality 1 of particular scholars or to evaluate their own or later claims

about a pervasive intellectual decline. And though the examples cited primarily

relate to the scholars of hadith and of law, this is not a survey of developments in

these areas either. 7 The concern here is, rather, to examine some of the discourses

and practices through which, and the contexts in which, the scholarly tradition

was cultivated in what c ulanuf like All al Qari clearly recognised as a 'cumulative'

endeavour. How religious authority was asserted through these discourses and

practices is among the central questions we would address in this chapter.

# Hadith scholarship in the eastern Islamic lands

All six of the collections of hadith that carry the greatest authority in Sunni

Islam were compiled by third fourth/ninth tenth century scholars from north east Iran and Central Asia. There were many paths along which scholarship in hadith had already developed by this time, and it would con

tinue to do so. It took several centuries for the works compiled by al Bukhari

(d. 256/870), Muslim (d. 261/875), Ibn Maja (d. 273/887), Abu Dawud (d. 275/889), al Tirmidhi (d. 279/892) and al Nasal (d. 303/915) to themselves

be recognised as the authoritative 'Six Books', 9 and other collections of hadith

continued to be produced long after they had come to be so accepted. In a

traditional scholarly culture, the very act of reordering well recognised and

authoritative materials was itself no small accomplishment, for the result, if

accepted, could signify new connections among well established themes, topics and disciplines, new foci of debate, changed emphases in scholarly

discourse and, not least, different ways of addressing new pedagogical needs

and styles; it also served, of course, to reaffirm and extend the authority of the

work(s) in which this new scholarship was anchored. The Mashariq al anwar of

7 For an overview of developments in the history of Islamic law, see The new Cambridge

history of Islam, vol. 4, Chapter 4.

8 Roy Mottahedeh, 'The transmission of learning: The role of the Islamic north east', in

N. Grandin and M. Gaborieau (eds.), Madrasa: La transmission du savoir dans le monde

musulman (Paris, 1997), pp. 63 72.

9 Ignaz Goldziher dates the general, though hardly unqualified, recognition of the Six

Books to the seventh /thirteenth century. See his Muslim studies, trans.

C. R. Barber and

S. M. Stern, 2 vols. (London, 1971), vol. II, pp. 240 3. The works of al Bukhari and Muslim

had come to be widely recognised as authoritative in Sunni circles by the beginning of

the fifth /eleventh century. See Jonathan Brown, The canonization of al Bukhari and

Muslim: The formation and function of the Sunni hadith canon (Leiden, 2007).

584

Cambridge Histories Online © Cambridge University Press, 201 1

Transmitters of authority and ideas

al Saghani (d. 650/1252) a scholar who was born in Lahore, in northern India, and

died in Baghdad is based, for instance, on hadith reports contained in the collections of al Bukhari and Muslim. Unlike these collections, it is a highly

concise work which would have lent itself to easy memorisation and would

have found its way in places where the larger collections might simply be inaccessible. The Hanafis had lagged far behind the Shafils in recognising the

canonical authority of al Bukhari and Muslim and, with his Mashariq al anwar, al

Saghani was among the first Hanafis to contribute significantly in that direction. 10

But al SaghanTs work performed other functions, too. He was an eminent lexicographer," and the Mashariq al anwar is a veritable manual of instruction in

the Arabic linguistic sciences, illustrated with well chosen examples from the two

authoritative collections of hadith. 12 'These linguistic sciences occupied an impor

tant place in the pedagogical concerns of the madrasas that had begun to emerge

in Muslim societies from the late fourth/tenth century; and it is not difficult to

understand the tremendous popularity of this work in the milieu of the madrasa,

to which the numerous commentaries on it bear ample testimony. 13

For all their skill in straddling several disciplines and their assistance in the

acquisition of an essential grounding in key disciplines, compendia like al SaghanTs would, however, have done little to satisfy those who saw the study

of hadith as more than a crucial milestone on the path to a juristic training, and

who sought, rather, to anchor their scholarly endeavours, their piety and their

authority in hadith itself. Their scholarship, in turn, produced new and, in some cases, extremely large collections of hadith, new commentaries on standard collections and, not least, further contributions to well worn genres

concerned with evaluating the credentials of the transmitters of hadith. There

were times when such multifaceted hadith scholarship was especially vibrant.

Some modern observers have examined instances of a renewed attention to

hadith, especially in scholarly circles in the Hijaz, during the eleventh/ seven

teenth and twelfth/ eighteenth centuries, and have professed to see in them

the early origins of modern and global Islamic 'reform' and 'revival'. 14 Our

- 10 Brown, Canonization, p. 226.
- 11 El 2 'al Saghani' (R. Baalbakki).
- 12 RacE al din al Hasan b. Muhammad al Saghani, Mashariq al anwar (Constantinople, AH 1329).
- 13 Hajji Khalifa, Kashf al zunun, ed. §. Yaltkaya and R. Bilge, 2 vols. (Istanbul, 1972), pp. 1688 90.
- 14 See, for example, John O. Voll, 'Hadith scholars and tariqahs: An ulama group in the 18th

century Haramayn and their impact in the Islamic world', Journal of Asian and African Studies,

25 (1980), pp. 264 73; Voll, "Abdallah ibn Salim al Basri and 18th century hadith scholarship",

Die Welt des Islams, 42 (2002), pp. 356 72; Azyumardi Azra, The origins of Islamic reformism in

Southeast Asia: Networks of Malay Indonesian and Middle Eastern 'ulama' in the seventeenth and

eighteenth centuries (Honolulu, 2004). For a critique of the hypothesis that posits the shared

585

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

interest here is not in the genealogy of such revivalism, however, but rather in

considering how hadlth scholarship was a major site on which religious authority was constituted and put on display. This is best illustrated, as are

changing orientations within such scholarship, with reference to the work of a

number of South Asian scholars.

Among the figures who came to exercise a major influence on the development of hadlth studies in India was Shaykh 'All al Muttaqi (d. 975/

1567), a Chishti Sufi from Burhanpur in the Deccan who had grown up in Gujarat in western India but spent much of his scholarly career in Mecca. 15

Chishti Sufis of India were often viewed with considerable misgivings for certain practices notably a pronounced attachment to devotional music (sama^) that some other Sufis and many jurists saw as only tenuously sanctioned by Islamic norms. Al Muttaqi never relinquished the Sufi path, but he devoted considerable energy to firmly anchoring Sufi thought and practice in what he viewed as authoritative sharfa norms. Hadlth scholarship

was, to him, the principal means of doing so. His best known work is the Kanz al 'ummal, a monumental collection of hadlth reports that condenses

and reorganises three collections of hadlth produced by the famous Egyptian

scholar al Suyuti (d. 911/1505). T Unlike al Suyuti's alphabetical listing of

hadlth, but like the compilers of the Six Books, al Muttaqi compiled his hadlth reports by juridical topic, 17 subsequently producing an abridged version of this collection to further facilitate its use. 1 The larger concern in all this was to reinvigorate the study of hadlth in both Sufi and juristic circles, and thereby to reorient both towards a firmer grounding in hadlth.

The normative example of the Prophet was the yardstick by which the claims and practices of the Sufis were to be measured; and Sufi practices such as sama\ as well as the extravagant claims of not a few of his Sufi contemporaries, were found unacceptable by this measure. 19

origins of modern Islamic revivalism in twelfth /eighteenth century Hijazi study circles, cf.

Ahmad Dallal, 'The origins and objectives of Islamic revivalist thought, 1750 1850', Journal of

the American Oriental Society, 113, 3 (1993), pp. 341 59.

15 For a detailed discussion of the life and thought of 'All al Muttaqi, see Scott Kugle, 'In

search of the centre: Authenticity, reform and critique in early modern Islamic saint

hood', Ph.D. dissertation (Duke University, 2000), esp. pp. 336 584.

16 The three collections are: Jam' aljawami'; aljami' al saghlr; and Zawa'id aljami' al saghlr.

All three are included in Jalal al dm al Suyuti, Jdmi' al ahadlth, ed. 'A. A. Saqr and A. 'Abd

al Jawwad, 21 vols. (Beirut, 1994).

17 See 'Ala' al din 'All al Muttaqi, Kanz al 'ummal fi sunan al aqwal wa'l afal, 18 vols.

(Aleppo, 1969), vol. I, p. 3.

18 'All al Muttagi, Muntakhab Kanz al 'ummal, 8 vols. (Beirut, 1990).

19 On al Muttaqi's rejection of sama', see Kugle, 'In search of the centre', pp. 415 19; for

daring efforts to counter the claims of other Sufis, see ibid., pp. 467 501.

586

Cambridge Histories Online © Cambridge University Press, 201 1

## Transmitters of authority and ideas

But there were other targets as well. Al Muttaqi lived at a time when the Islamic calendar was close to completing its first millennium, and this had given

rise to messianic expectations in India and elsewhere and to those claiming to

fulfil them. It was hadtth scholarship that offered him the resources with which

to deflate such claims, for instance by showing that they were either entirely

lacking a basis in the reported teachings of the Prophet or, at least, that reports

to that effect failed to withstand critical scrutiny. 20 Significantly, however, such

sober scholarship did not deny him opportunities for his own, alternative, claims to authority; and these claims, like those of al Suyuti before him, were

not modest. Al Muttaqi argued, for instance, that, unlike the jurists, scholars of

Judith could plausibly claim to have improved upon the work of otherwise authoritative predecessors. 21 He is also reported to have seen Muhammad in a

dream, in which the Prophet informed him that he al Muttaqi was, in fact, the most virtuous person of his age. 22

'Ali al Muttaqi's circle of students and disciples counted many distinguished

figures. He was himself a student of the noted Egyptian hadtth scholar Ibn Hajar

al Haytami (d. 974/1567), though the latter acknowledged al Muttaqi as his own

Sufi master. 23 The aforementioned All al Qari was also a student of al Muttaqi, as

was Muhammad b. Tahir Patani (d. 986/1578) of Gujarat, the 'king of the scholars

oihadtth' best known for works on transmitters oihadtth reports and especially on

fabrications in hadtth. 24 So far as hadxth scholarship in India is concerned, however,

the most prominent scholar to emerge from this circle was Abd al Haqq Muhaddith (d. 1052/1642), a student of one of al Muttaqi's disciples in Mecca.

Among many other works, Abd al Haqq is the author of two commentaries

on the Mishkat al masabih, a highly popular collection ofhadith compiled by Wall

al dm of Tabriz (d. 737/1336). The Preface to the Arabic commentary illustrates

well some of the many overlapping ways in which religious authority might be

articulated through hadith and especially through the discursive medium of the

commentary. 'Abd al Haqq notes at the outset that the most noble of the religious sciences are Qur'anic exegesis and hadxth 'for they are ends in them

selves, whereas all other forms of knowledge are only means to them'. 25 This

20 Ibid., esp. pp. 343 6, 517 59.

21 Ibid., p. 549.

22 'Abd al Qadir al Aydarus, al Nur al sdfir 'an akhbar al qarn al 'dshir, ed. A. Haiti, M. al

Arna'ut and A. al Bushi (Beirut, 2001), pp. 4212.

23 Kugle, 'In search of the centre', pp. 381 2,385 6.

24 On Muhammad Tahir, see al 'Aydarus, al Nur al sdfir, pp. 475 6; Kugle, 'In search of the centre', pp. 561 73.

25 'Abd al Haqq Dihlawi, lama'dt al tanqihfi shark Mishkat al masabih, ed. M. 'Ubayd Allah, 4 vols. (Lahore, 1970), vol. I, p. 12.

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

would seem to be an unproblematic assertion, given that the Qur'an and the

hadtih are the foundational sources of Islamic law. In the Indian context, however,

the systematic study of hadtth was anything but well established in Islamic higher

learning. It was Islamic law and the rational sciences (al 'ulum al l aqliyya) that held

pride of place there (on this, see below). The importance of the study of haalth

needed to be argued rather than taken for granted, and Abd al Haqq saw it as his

calling to do so. Indeed, as he notes in this Preface, he had been sent back to India

by his teacher in Mecca, Abd al Wahhab al Makkl (himself a student of 'All

al Muttagi), precisely 'to serve this noble science [sc. haalth]'. 2 ' 7

Once back in India, 'Abd al Haqq embarked on a commentary on the Mishkdt al masdbih in the Persian language in order to make this work broadly

accessible. 2 He soon realised, he says, that many topics were unsuited to

being expressed in a Persian commentary, and therefore simultaneously began an Arabic commentary on the Mishkdt for a more select audience:

The two proceeded parallel to each other, but also in competition with each

other. At times, the Persian [commentary] would lead because it had been

commenced earlier; but at others, the Arabic [commentary] would catch up

by virtue of [its importance as] encompassing principles of legal theory and

matters of substantive law (al usul wa'lfuru'). At yet other times, [the Arabic

commentary] would dominate [the Persian] on account of its exalted status.

and because of my own partiality towards it in view of its suitability to the

intellect of many among [my] companions. 29

Needless to say, this is not merely an explanation of why he needed to write

two commentaries or why the Arabic commentary was completed before its

Persian counterpart; it also illustrates the importance of language to articu

lations of authority. Arabic and Persian were both cosmopolitan languages, of

course, and major works of religious scholarship were produced not just in

Arabic but also in Persian. During the centuries with which this volume is concerned, mystical, literary, ethical and scientific works had increasingly

come to be written in Persian. 30 Yet even when particular works showed

26 Cf. 'Abd al Hayy al Hasam, al Thaqdfa al Islamiyyaf'l Hind (Damascus, 1958), pp. 11 17.

27 'Abd al Haqq, Lama'at al tanqih, vol. I, p. 13. On 'Abd al Haqq and his relationship with

'Abd al Wahhab, see Scott Kugle, ''Abd al Haqq Dihlawi, an accidental revivalist:

Knowledge and power in the passage from Delhi to Makka', Journal of Islamic Studies,

19 (2008), pp. 196 246.

28 'Abd al Haqq Dihlawi, Ashi"at al lama'at, 4 vols. (Sukkar, Pakistan, 1976).

29 'Abd al Hagg, Lama'at al tangih, vol. I, p. 14.

30 On scientific writings in Persian, cf. Ekmeleddin Ihsanoglu, 'Ottoman science: The last

episode in Islamic scientific tradition and the beginning of European scientific tradition',

in Ekmeleddin Ihsanoglu, Science, technology and learning in the Ottoman empire

(Aldershot, 2004 [repr. as article no. 3, original pagination]), pp. 11 48, at 20 7; on the

# Transmitters of authority and ideas

unmistakable signs of having been produced in the eastern Islamic lands, 31

Arabic remained (and, among the 'ulamff of South Asia and Iran, has often

continued to be) the language through which one's scholarly credentials were

established, the language that offered as it clearly did to Abd al Haqq the best prospects for recognition beyond one's own region and for participation

in the trans cultural scholarly tradition. Conversely, the Persian commentary

was a means not only of trying to reach a larger audience within the Indian

Muslim circles, but also of making a work like the Mishkat part of local Islamic

knowledge in India. 32

A century later, Shah Wall Allah of Delhi would continue to build on earlier

advances in the study ofhadith; like 'Abd al Haqq, he, too, had acquired some

of his scholarly learning in the Hijaz and he, too, wrote his major works in

both Arabic and Persian. But if he shared much with Abd al Haqq and, indeed, with 'All al Muttaqi in his scholarly orientation and in the effort to anchor legal norms and Sufi doctrines in the study of hadith, his work again

reveals distinctive emphases. These are of interest, of course, for what they tell

us about Wall Allah's thought, but their primary significance in the present

context lies in illustrating continuing shifts in otherwise highly formalised styles of discourse and constructions of authority attached to such shifts.

Abd al Haqq had sought not only to promote the study of haalth in India but

also to defend the norms of the Hanafi school of law (madhhab) in its terms. 33

Wan" Allah, for his part, was unusual among the north Indian scholars of his age

in the lack of his attachment to the Hanafi school of law and, indeed for what

might be characterised as a juristic ecumenism. He continued to adhere to the

Hanafi madhhab, but he expressed great admiration for the norms of the Shafi'i

school for what he saw as their close concordance with hadlth, and he was an

avid admirer of the Muwatta' of Malik b. Anas (d. 179/795), the eponymous

founder of the Maliki madhhab. To Wall Allah, hadlth scholarship was a means

not of defending a particular madhhab, but of trying to reconcile their sometimes

importance of Persian as the language of ethical discourses and of administration in

Mughal India, see Muzaffar Alam, The languages of political Islam: India, 1200 1800 (Chicago, 2004).

31 For instance, references to the scholars of Samarqand, Balkh and Bukhara are ubiquitous

in the Fatdwa 'Alamgiriyya commonly known as al Fatdwa al Hindiyya a monumental

juridical work produced under royal patronage in India in the seventeenth century.

Words and sentences in Persian are also liberally strewn throughout the work. Yet the

language of this work remains Arabic. See al Fatdwa al Hindiyya fi madhhab al imam al

a'zam AKHanifa al Nu'mdn, 6 vols. (Beirut, n.d. (1973; repr. of the Bulaq edn, AH 1310)).

32 For a similar point, though in the context of Islamic scholarship in seventeenth century

eastern China, see Zvi Ben Dor Benite, The Dao of Muhammad: A cultural history of

Muslims in late imperial China (Cambridge, MA, 2005), pp. 7982.

33 'Abd al Hagg, Lama'dt al tangih, vol. I, pp. 17 18.

589

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

# The New Cambridge History of Islam

acrimonious differences. And it was in the Muwattff, a collection of legal reports

predating the Six Books and reflecting the views and practices of the early jurists

of the Prophet's adopted home, Medina, that he found the best prospects for

doing so. Wall Allah considered the Muwattff on which he wrote commen taries in both Arabic and Persian as the single most authoritative work after

the Qur'an, 34 as well as the earliest extant work with a continuous chain of

transmission. 35 The Six Books of hadith were, to him, in the nature of commen

taries on the Muwattff 36 and the same was true of the four Sunrii schools of

law. 37 Indeed, to the degree that particular forms of ijtihad in the sense of

'ascertaining the rulings of the sharfa from its detailed proofs and the deriving

and rearranging of these rulings ... if only according to the instructions of the

founder of [one's own] school of law' were still possible in his day, the resources of the Muwattff were the means of undertaking them. 38

Neither Wall Allah's concern to keep paths to ijtihad open nor his juristic ecumenism suffices as an explanation of his devotion to the Muwattff For the

viability of ijtihad was scarcely contingent upon this, or any other, work in

particular, as Wall Allah's own discussion of ijtihad elsewhere makes clear; 39

and privileging the authority of Malik's famous work in a land where few Malikis were to be found would not have struck his Indian contemporaries as

an ecumenical gesture. 40 The Muwattff, however, is the foundational text of a

madhhab which accords especial importance to considerations of public inter

est or the common good (maslaha). It is likely that such considerations, which

are central to Wall Allah's religious thought, had drawn him to Malik's work. 41 But Wali Allah's invocation of the authority of the Muwattff in a non Maliki, Indian, context may also be seen as an assertion of his own authority. He was not content to rearrange the contents of an earlier work,

or to write elaborate commentaries on it, as he did in the case of the

34 Wall Allah al Dihlawl, Musawwd Musajja, shark Muwatta' imam Malik, 2 vols. (Karachi,

n.d.; repr. of the Delhi AH 1346 edn), p. 6. The top section of each page in this edition

contains Wali Allah's Arabic commentary, al Musawwd, and the bottom page comprises

the more expansive Persian commentary, Musajja. All references are to the Musajja

unless otherwise noted.

35 Ibid., p. 8.

36 Ibid., p. 7.

37 Ibid., p. 8 (al Musawwd).

38 Ibid., pp. 10 11.

39 Cf. Shah Wall Allah, 'Iqd aljidfiahkam al ijtihad wa'l taqlid (Cairo, AH 1385).

40 There was a renewed interest in the Muwatta' in the Hijaz as well, where Wall Allah had

continued his studies. Cf. Voll, ''Abdallah ibn Salim al Basri', p. 361. But even this does

not quite explain his zealous invocation of the Muwatta'' in the Indian context.

41 See, in particular, Wali Allah, Hujjat Allah al baligha; also cf. Marcia K. Hermansen, The conclusive argument from God (Leiden, 1996), pp. xvi xvii.

590

Cambridge Histories Online © Cambridge University Press, 201 1

Transmitters of authority and ideas

Muwattff. 42 In a move that would have astonished the more conservative among

his fellow 'idamff in India, Wall Allah sought, in effect, to go beyond the Six

Books, and thereby to transcend the long history of commentary and debate tied

to them as well as to the school of law dominant in India. The task of reorienting

legal norms in the light of the Prophet's normative example required a new

beginning, with the MuwattS both as resource and as an example of how hadrth

and law ought to work in tandem. That Wall Allah continued to profess his

devotion to the Hanafi school of law meant that his was an internal challenge to

the other Hanafi scholars. 43 Yet his project sought more than a reorientation of

law in terms of hadith; it was also a venture in the reorientation of hadtth scholar

ship itself. This, in turn, was accompanied by an effort to train a new generation of

scholars along lines, and in texts, different from those most commonly encoun

tered in Indian madrasas of Wall Allah's times. The study of the Muwatta' never

really caught on in Indian madrasas. But it did allow WaE Allah the opportunity to

base his own claims to authority on a new and distinctive basis, as other facets of

had&h scholarship had allowed his predecessors to do as well.

Constructions of authority in the discourses of the jurists

As in the study of hadith, compendia of legal doctrines, agreements and disagreements as well as commentaries on such works were central to the

articulation, preservation and transmission of the ^ulamff's discursive tradi

tion. Here, too, certain texts gradually came to be invested with compelling

authority within particular madhhabs, giving coherence and stability to the

legal tradition and guiding the further evolution of legal thought. 44

There is much creativity that continued to find expression in scholarly engagement with authoritative texts, in law as in other areas. Yet the authority

42 Wall Allah, Musawwd Musaffa. He also wrote on the SahTh of al Bukhari: see Wall Allah,

Risdla shark ahwab sahih al Bukhari, 3rd edn (Haydarabad, 1949).

43 For his criticism of his fellow scholars, see Wall Allah, Musawwd Musaffa, pp. 11, 21; also

cf. Dallal, 'Origins and objectives', pp. 347, 349.

44 See Baber Johansen, Contingency in a sacred law: Legal and ethical norms in the Muslim figh

(Leiden, 1999); Wael B. Hallaq, Authority, continuity and change in Islamic law (Cambridge,

2001). Some of the issues relating to juristic authority that I touch upon in this section are

also considered in Wael B. Hallaq's review of the history of Islamic law in The new Cambridge

history of Islam, vol. 4, Chapter 4. The focus of the relevant sections of that chapter is,

however, on the construction of the authority of the classical Sunni schools of law, as

embodied in their eponymous founders and the legal doctrines attributed to them; my

concern here is with the opportunities and the techniques a well developed legal system as

it existed during the centuries with which this volume is concerned afforded to its jurists,

as well as to other scholars, for continuing articulations of their authority.

591

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

of a commentator, or of the compiler of a collection of legal opinions and doctrines, did not necessarily depend only on what was 'innovative' about his

enterprise. To transmit learning in accordance with recognised scholarly standards, to write in the established genres and styles, and to train students

in them was to continue an ongoing conversation with forebears and con

temporaries. The skill with which one was seen to do so was a sufficient marker of one's scholarly eminence, though this hardly precluded critical engagement with the texts and traditions being passed on. Such critical engagement could create the space within which the authoritative positions

handed down by forebears could be adapted to new or newly felt needs, received opinions might be supplemented with other, more recent views, and

the latter put into circulation.

It was not just the credentials of the individual scholar writing the commentary or preparing a new compendium of law that were affirmed through

such works; so, too, was the continuing tradition of the school as a whole. Mahmud b. Ahmad b. Abd al Aziz al Bukhari's (d. 616/1219) Preface to his

compendium of Hanafi law, al Muhit al Burhani fi'l fiqh al Nu^marii, illustrates

some of these concerns:

Knowledge of the rulings of religion is among the noblest and highest of ranks, and understanding religion is the most beneficial, and the purest, of

activities. It is to the scholars and the jurists that things taking place among the

[ordinary] servants of God are best directed, in order to ascertain their thoughts

on these matters. As God has said, ' $\dots$  if they had referred it to the Messenger

and those in authority among them, those seeking its meaning would have

found it out from them' [Q 4.83] . . . The Companions of the Prophet of God had

persevered in seeking the knowledge and understanding of religion, and they

had thereby become models to be emulated by everyone . . . After the gener

ation of the Companions and their Followers had become extinct, the great

imam . . . Abu Harufa, and his companions stood up to aid this religion. They are

the ones who have delineated the preamble of the sharTa and set forth the

principles of this radiant religion . . . After them, the scholars of this religion have

done their utmost in explicating difficulties, . . . knowledge being . . . transmitted

from one elder to another until it reached the seven ancestors [of this author.

These ancestors have, in turn,] ... expounded on what had still remained condensed in the law and opened what had hitherto been left locked.

Their

writings circulate among the people, and are relied on injudicial decisions and

fatwds ... It occurred to me to become like them by compiling a work that brings together matters to which legal rulings pertain ... so that such a work

assists me during my lifetime and results in [divine] recompense after my death . . . The idea [of compiling such a work] was strengthened by the request  $\frac{1}{2}$ 

of some brothers, which I have answered by gathering legal problems (masffil)

592

Cambridge Histories Online © Cambridge University Press, 201 1

### Transmitters of authority and ideas

from al Mabsut, the two Jdmi's, the Siyar and the Ziyadat [all by Muhammad

b. al Hasan al Shaybani (d. 189/805)]. To these [sources of the school's author

itative doctrine], I added the less authoritative legal problems (al nawadir) and

the fatwas ..., further adding to these the useful lessons I had received from my

father . . . and the subde matters I had committed to memory from the scholars  $% \left( 1\right) =\left( 1\right) \left( 1\right) +\left( 1\right) \left( 1\right) \left( 1\right) +\left( 1\right) \left( 1\right)$ 

of my own time. I have written a detailed work, explicated the problems in it to

the full, and supplied them with proofs relied upon by the ancients as well as

those of the latter day scholars (al muttfakhkhiruri). 45

This is as good an illustration as any of the self conscious sense of an ongoing, discursive tradition from which the scholars derived their identity

and their authority while striving to preserve, adapt and further develop it in

their local contexts. Some of the authority in question came not only from

inserting oneself into a long standing genealogy of learning, but also from the

ability acquired on the path to a scholarly career to navigate through the multiplicity of discourse, the variety of texts and their frequently competing

claims and implications. That jurists often professed strict adherence to the

established doctrines of their school of law (taqlid), rather than presuming to

engage in efforts towards arriving at new legal rulings (ijtihad), had little bearing on such authority, for the very effort to sort out the complexities of

a rich, multi layered tradition as it existed at a particular time and place was

itself not a small measure of legal acumen and of the recognition that went

with it.

The range of doctrines that the Fatdwa 'Alamgiriyya (produced in eleventh/ seventeenth century India at the instance of the Mughal emperor Aurungzeb (r. 1069 1118/1658 1707)) presents in its 'Book of the Judge's Etiquette' (Kitab adab al qad.1) 46 leaves no doubt, for instance, that some of

the options are only for a judge who is a mujtahid, one qualified to undertake

ijtihad. But while most jurists of the age in which this compilation was produced would have insisted that their qualifications entitled them only to taqlid, the latter is hardly the 'blind imitation' that many modern commentators have often taken it to be. 47 Important efforts to adjust legal

45 Mahmud b. Ahmad b. 'Abd al Aziz al Bukhari, al Muhit al Burhaniji'ljiqh al Nu'mdm, ed.

A. 'A. 'Inaya, 11 vols. (Beirut, 2003), vol. I, pp. 21 3. On the author of this work, see

Muhammad 'Abd al Hayy al Laknawi, al FawSid al oahiyya fi tarajim al Hanafiyya

(Karachi, AH 1393), pp. 205 7.

46 al Fatdwa al Hindiyya, vol. Ill, pp. 306 450.

47 For recent re evaluations of taqlid, see Sherman Jackson, Islamic law and the state: The

constitutional jurisprudence of Shihah al Din al Qarafi (Leiden, 1996); Hallag, Authority,

continuity and change; Mohammad Fadel, 'The social logic of taqlid and the rise of the

Mukhtasar', Islamic Law and Society, 3 (1996), pp. 193 233.

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

doctrine to changing needs long continued to take place within the overall

framework of taqlid, and the rhetoric of taqlid sometimes also served to mask

and, in a largely conservative society, thereby to justify important depar tures from traditional norms and practices. Taqlid, like ijtihdd itself, admitted

of many degrees, moreover, which means that the manner in which a learned judge or jurist might adhere to the doctrines of the school could scarcely be the same as that of a less sophisticated colleague. For all the proliferation of madrasas in medieval Muslim societies, the transmission of

learning was characterised by considerable informality (see below), so that

deciding what sort of taqlid a particular judge was bound to in view of his specific intellectual accomplishments could not have been a matter of objective assessment. Merely to decide which of the existing legal doctrines

to follow in a particular case required considerable skill, just as the very availability of this range of positions could allow considerable manoeuvrabil

ity even to judges otherwise bound to taqlid. The Fatawa l Alamgiriyya had, in

fact, been envisioned as a way of limiting some of this manoeuvrability, of rationalising judicial practice in India, 48 though it is unlikely that it did much

to curb the range of choices the tradition itself had made available to the judges. 49

Debates among the Shi'i 'ulama' in the eleventh twelfth/ seventeenth eighteenth centuries likewise demonstrate that a disavowal of ijtihdd scarcely

signified relinquishing strong claims to religious authority. It has often been

supposed that the 'Akhbari' 'ulama\ who insisted on firmly adhering to the

reported teachings (akhbar) of their ShTi imams rather than undertaking ijtihdd

on the basis of the foundational texts, were thereby abandoning their own

claims to authority. But, as Robert Gleave has observed, opposition to ijtihdd

does not compromise claims to authority; it merely relocates those claims. 50

The 'Usuli' ShTi jurists claimed the prerogative of ijtihdd and argued that,

48 al Fatawa al Hindiyya, vol. I, pp. 2 3; also cf. Saqi Musta'idd Khan, Md'athir i 'Alamgiri,

ed. A. A. 'All (Osnabriick, 1985; repr. of the Calcutta 1870 3 edn), pp. 529 30.

49 Nor was taqlid itself unrelenting in all instances. In a discussion of the 'sequence of

proofs according to which [the judge is] to act', the Fatawa 'Alamgiriyya stipulates

recourse to the views of Abu Hanifa and his principal disciples, Abu Yusuf and

Muhammad al Shaybani. Should no guidance be available in their teachings, and if

latter day scholars are themselves in disagreement on the matter, the judge was to

choose from among the variant views of these scholars. But 'in case even the latter day

scholars have nothing to say on the matter, [the judge] exercises ijtihdd in accordance

with his considered opinion, provided that he understands the precepts of the law and

has consulted on the matter with [other] jurists', al Fatawa al Hindiyya, vol. Ill, p. 312.

50 My understanding of the Akhbari position and of the Akhbari claims to religious

authority is based on Robert Gleave, Inevitable doubt: Two theories of ShfT jurisprudence

(Leiden, 2000), esp. pp. 220 53. For another insightful discussion, see Etan Kohlberg,

594

# Transmitters of authority and ideas

while the results of this ijtihad were at best probable (zannT) rather than certain

(qat c T), the probable nature of these results need not have any bearing on the

authority they ought to carry for the lay believer following the guidance of the

master jurist, the mujtahid. The Akhbaris, on the other hand, located authority

not in the person of the mujtahid but rather in the textual tradition comprising

the teachings of the imams. These teachings led to certainty rather than to

mere conjecture and probability, and they obviated the need for ijtihad. But it

is the scholars who arrived at an authoritative understanding of these teach

ings, articulated the legal norms on their basis and guided their followers accordingly. And a formal disavowal of ijtihad did not undermine their religious authority or their claims to it.

### The cosmopolitanism of the 'ulama'

Debates about ijtihad and taqlid, the writing of commentaries and the issuing of

fatwas were all constitutive of religious authority in the eastern Islamic lands just

as they were elsewhere in the Muslim world. These were activities of the distinguished scholars, however, and many of those who had acquired only a

modicum of religious learning would not have had very much of a share in

them. Yet the significance of this learning consisted not only in sustaining and

developing a scholarly tradition but also in helping create the conditions for an

Islamic cosmopolitanism. There were important limits to this cosmopolitanism,

as we would observe later. Even so, and for all the differences of the natural

languages people spoke, the geographical and cultural distances that separated

them, the different schools of law to which they adhered and the varied societies

they inhabited, there was a language of discourse that those schooled in the

religious sciences could, with some plausibility, claim to share.

There is no better illustration of this cosmopolitanism than the famous North African traveller Ibn Battuta (d. 770/1368?.) who, by the end of his travels, had 'visited territories equivalent to about 44 modern countries'. 51

Besides major cities in the Arab Middle East, he travelled to Anatolia, India,

the Maldive islands in the Indian Ocean, the island of Sumatra and possibly

also to China. 52 Ibn Battuta's account of his travels is of interest not only for

'Aspects of Akhbari thought in the seventeenth and eighteenth centuries', in Nehemia

Levtzion and John O. Voll, (eds.), Eighteenth century renewal and reform in Islam

(Syracuse, 1987), pp. 133 60.

51 Ross E. Dunn, The adventures of Ibn Battuta: A Muslim traveler of the 14th century (Berkeley, 1986), pp. 3, 12 n. 2.

52 On doubts about whether he did, in fact, go to China, cf. D. O. Morgan, 'Ibn Battuta and the Mongols', Journal of the Royal Asiatic Society, 3rd ser., 11 (2001), pp. 1 11.

595

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

what he tells us about the places he visited, however, but also for the company

he kept. He had acquired a religious and specifically a juristic training in his

native North Africa, though, by all accounts, his scholarly credentials were at

best modest. Even so, he was never oblivious of these credentials, and it is to

the presence of the religious scholars and Sufis in the lands he visited that he

remained most attentive.

Ibn Battuta was clearly a most unusual figure. Scholars did travel considerable

distances in search of knowledge (talab al Him) but not on the scale he did, nor

was he primarily travelling in search of knowledge. And as his Rihla makes clear,

he was exceptionally fortunate both in finding patrons almost everywhere

went and in eluding the mishaps that accompanied the not always predictable

relations of patronage. Yet, such as they were, it is his scholarly claims that

facilitated his entry into circles of scholars and into royal courts where religious

scholarship was ostentatiously celebrated. Muhammad b. Tughluq, the sultan of

Delhi (r. 724 52/1324 51), made him a judge in the imperial city, for all that Ibn

Battuta did not know the local languages and in fact belonged to the Malik!

school of law when most inhabitants of northern India were Hanafis. Nor was

Muhammad b. Tughluq deterred, some years later, from sending Ibn Battuta as

his ambassador to China. Some of the scholars and Sufis he came across for

instance the pious jurist from Mogadishu [whom he met on the Malabar coast

of India] . . . who had studied at Mecca fourteen years and for the same length of  $% \left\{ 1,2,...,n\right\}$ 

time at Medina ... and had travelled in [northern] India and China' were comparable to him in their cosmopolitanism. 53 The latter may, indeed, have had

a better grasp of the religious sciences, but Ibn Battuta clearly had sufficient

grounding in a shared language of discourse to find himself at home in scholarly

circles everywhere he went, and to feel entitled to the sort of positions and

patronage often reserved for religious scholars. Indeed, he professes an inability

to remain inconspicuous even when he had wanted to, as when he was appointed as a qddl while passing through the Maldives. 54 Whether this appoint

ment owed itself to the prestige, in local circles, of being an Arab scholar or to

the fact that he was travelling at this time as an emissary of the Delhi sultan, a

sense exaggerated, perhaps of shared norms in otherwise disparate Muslim

communities may also have had something to do with it. Four centuries later,

53 Ibn Battuta, Voyages d'Ibn Batoutah, ed. C. Defremery and B. R. Sanguinetti, 2nd edn, 4

vols. (Paris, 1877 9), vol. IV, p. 82; trans. H. A. R. Gibb, The travels of Ibn Battuta, AD 132s

1354, 5 vols. (Cambridge, 1958 2000), vol. IV, p. 809.

54 Ibn Battuta, Voyages, vol. IV, pp. 137, 150 2; Gibb, Travels, vol. IV, pp. 834 5, 840. His

public rebuke of the incumbent judge who 'did nothing right' could scarcely have

helped his desire for anonymity on this occasion. On this, see below, p. 599.

596

Cambridge Histories Online © Cambridge University Press, 201 1

Transmitters of authority and ideas

Muhammad 'All Hazin Lahlji (d. 1180/1766), an Iranian scholar who had fled

to India to escape a period of great political turmoil in Iran, likewise complained and no more convincingly of not being able to maintain his anonymity when he arrived in the town of Thatta, in Sind, in 1146/1734: 'I

did not wish that any person should know me in that country. But it was almost impossible for it to be so; and the very same day that I arrived ... a company of merchants of that town, who had seen me in Fars, become

informed of my visit. A number of Persians were also residing there, most of

whom were among my acquaintance. In short, this idea of remaining incognito was not realized in any city of that empire/ 55

The Iranians living in Thatta when Hazin arrived in that town were, no doubt, part and product of a long standing movement of merchants and scholars from Iran who had sought their fortunes in South Asia, with not a

few also coming to play some role in local Indian politics. 56 Networks of Iranian merchants and scholars were not the only ones facilitating the move

ment of people, merchandise and ideas, however. One of the most remarkable

networks during the centuries with which this volume is concerned was that

of the Hadramis tracing their origins to Hadramawt in Yemen which had a

major presence in Gujarat and elsewhere on the western coast of India and

which extended from East Africa to the Malay Indonesian archipelago. 57 Besides a shared origin, the Hadramis were tied to one another as transmitters

of hadith, jurists, Sufis and, not least, as merchants. Local elites across the

Indian Ocean saw the Hadramis as the carriers of an uninterrupted Islamic

scholarly tradition and were often eager to offer rich patronage to them. And

as the Nur al safir, a biographical dictionary composed by c Abd al Qadir al

'Aydarus (d. 1038 / 1638) a Hadrami Sufi living in Ahmadabad in Gujarat and

devoted to the scholars and notables of the tenth/ sixteenth century amply

attests, the Hadramis were not reticent in putting their scholarly claims and

accomplishments on display. 58

55 Muhammad 'All Hazm Lahiji, Ta'rikh wa safarnama i Hazin, ed. 'A. Dawwani (n.p.,

AH 1375), p. 259; trans, as in The life of Sheikh Mohammad 'All Hazin, written by himself,

trans. F. C. Belfour (London, 1830), p. 252. On him, see Muzaffar Alam and Sanjay

Subrahmanyam, Indo Persian travels in the age of discoveries, 1400 1800 (Cambridge, 2007),

pp. 229 40.

56 Cf. Sanjay Subrahmanyam, 'Iranians abroad: Intra Asian elite migration and early

modern state formation', Journal of Asian Studies, 51, 2 (1992), pp. 340 63.

57 Engseng Ho, The graves of Tarim: Genealogy and mobility across the Indian Ocean (Berkeley, 2006).

58 See al 'Aydarus, al Nural safir, pp. 444 53, for the author's account of his own career and accomplishments. On this work, see Ho, Graves of Tarim, pp. 118 37.

597

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Like the Iranians, Hadramis of the diaspora rose, on occasion, to political prominence and some, like Nur al din al Raniri (d. c. 1068/1658), left a major

impact on religious developments in their host communities. 59 Nur al din, a

student and disciple of Abu Hafs 'Umar Ba Shayban al Hadrami a prominent

member of the Aydarus clan in India and the nephew of the author of al Nur al

safir was born in Ranir (present day Rander) in Gujarat and educated in Gujarat and Hadramawt. Al Raniri's uncle had taught in Aceh in the late tenth/ sixteenth century; c and, in 1047/1637, al Raniri came not only to live in

Aceh but soon also to occupy a position of great influence there, that of the

Shaykh al Islam, with close ties to the Acehnese court. He remained in this

position for seven years, before being forced to retire in 1054/ 1644 to his native

Ranir, but not before he had played a highly prominent, but also polarising, role

in trying to suppress what he regarded as wayward mystical ideas associated

with the teachings of the Andalusian mystic Ibn al Arab! (d. 638/1240).

Al Raniri's career illustrates something about the scope but also about the limits of the 'ulamff's cosmopolitanism. For scholars like him, it was evidently possible to move freely between South Asia, the Arab Middle East and South East Asia in what they would have seen as an intercon nected world of fellow scholars and their revered forebears. But this cosmopolitanism also had its limits, and al Raniri seems to have reached them after seven years in Aceh. He apparently lost his influential position in Aceh in competition with a rival with deeper local roots, one Sayf al Rijal, who professed precisely the sort of beliefs that al Raniri had all along

been branding as heretical. Milder expressions of the views al Raniri had tried to implement in Aceh did not lose influence or proponents after his departure, however; and the Malay Indonesian archipelago long remained

a fertile territory for scholars from elsewhere, not least for subsequent generations of Hadramis. z It is also worth noting that the rival mystical beliefs, associated with the teachings of Ibn al 'Arabi, that al Raniri wanted

to see erased were themselves an expression of a cosmopolitan world; and

Sayf al Rijal, a Minangkabau, had travelled to Surat in Gujarat to establish

his own scholarly credentials before returning to challenge al Raniri. Conversely, al Raniri's roots in Aceh were by no means shallow: he wrote

59 For an informative overview of al Raniri's career, on which I draw here, see Azra,

Islamic reformism, pp. 52 69.

60 Azra, Islamic reformism, pp. 55 6.

61 Cf. ibid., p. 112.

62 Ibid., pp. 60 2; Takeshi Ito, 'Why did Nuruddin ar Raniri leave Aceh in 1054 AH?',

Bijdragen tot de Taal, Land en Volkenkunde, 1344, (1978), pp. 489 91.

# Transmitters of authority and ideas

not only in Arabic but also in Malay and, indeed, some of his most influential works were written in the latter language. 63 Even so, contem poraries would not have mistaken al Raniri's cosmopolitan orientation, the paradox of which was, of course, that it could bring influence and prestige just as easily as it might become a liability for the cosmopolitan and for his local hosts.

In a different context, and with much less of a grounding in the local cultures, Ibn Battuta too had also come up against the limits of his cosmopolitanism. Having publicly rebuked a local qddi in the Maldives for doing 'nothing right' he had assumed the position in his stead and proceeded to make his presence felt:

When I was appointed, I strove my utmost to establish the prescriptions of

the Sacred Law. Lawsuits there are not like those in our land. The first bad

custom I changed was the practice of divorced wives of staying in the houses

of their former husbands. I put a stop to that. About twenty five men who had

acted thus were brought before me; I had them beaten and paraded in the

bazaars, and the women put away from them. Afterwards I gave strict injunctions that the prayers were to be observed, and ordered men to go swiftly to the streets and bazaars after the Friday service; anyone whom they

found not having prayed I had beaten and paraded. 64

The local people professed to belong to the same, Maliki, school of law as Ibn

Battuta did, but the manner in which he proceeded to implement his under

standing of the legal norms was clearly foreign to them. Elsewhere, Ibn Battuta speaks of how people in his presence fainted when he once ordered

the hand of a thief to be cut off. He attributes this reaction to the physical

weakness' of the people, 65 but it may have had more to do with the fact that.

local customary practices were not quite what he wanted to see implemented.

There is no indication in his account that he made any effort to bridge this

distance. Qadis were, by definition, required to uphold shafCa norms, but they

also needed to be attentive to local social and religious configurations. The

qddi who 'did nothing right' may yet have had a firmer grasp of these local

norms than did Ibn Battuta, whose tenure in this position was, in any case,

soon terminated on account of the political rivalries in which he found himself entangled.

63 Azra, Islamic reformism, pp. 66 9.

64 Ibn Battuta, Voyages, vol. IV, pp. 151 2; Gibb, Travels, vol. IV, pp. 840 1.

65 Ibn Battuta, Voyages, vol. IV, pp. 114 15; Gibb, Travels, vol. IV, p. 824.

599

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

Educational institutions and practices

Medieval cosmopolitanism had its constraints, but scholarly learning remained,

by far, its most important basis. This learning was typically transmitted from

one person to another, with the particular site where such activity took place

being incidental to it. Ibn al Najjar (d. 643/1245), the author of a biographical

dictionary devoted to the scholars who had some connection with Baghdad, 67 is

said to have travelled, inter alia, in the Hijaz, Syria, Mesopotamia and Khurasan

for twenty eight years before returning to Baghdad with a list of 3,000 men and

400 women from whom he claimed to have acquired his knowledge. It usually

did not take either that long or this many people to establish one's scholarly

credentials. But Ibn al Najjar's claim to do so, despite its hyperbole, suggests at

least that there were varied and often informal ways in which learning was

transmitted from one person to another. Yet his was also an age of major developments in the institutionalisation of Islamic education. Debates about the

origins and diffusion of the madrasas, and the purposes they may have been

meant to serve, need not occupy us here, 69 though it is worth noting that this

institution first emerged in Khurasan in the fourth/tenth century and that madrasas had begun to spread elsewhere in the Muslim world, in both the

east and the west, from the late fifth /eleventh century. 70 The most famous of

the early madrasas were the Nizamiyyas, founded in more than ten cities in Iran

and Iraq under the patronage of the Saljuq vizier Nizam al Mulk (d. 485/1092). 71

Later madrasas had their own claims to distinction. The Mustansiriyya, estab

lished by the 'Abbasid caliph al Mustansir in Baghdad in 631/1234, was, for

instance, the first to be endowed by a caliph and the first to have professorships

 $66\ Cf.$  Carl F. Petry, 'Travel patterns of medieval notables in the Near East', Studia

Islamica, 63 (1985), pp. 53 87, esp. 75.

- 67 This large work, itself a sequel to the History of Baghdad by al Khatib al Baghdad!
- (d. 463/1072), was abridged by Shihab al din al Dimyati (d. 749/1348) as al Mustajad

min dhayl ta'rikh Baghdad, ed. M. M. Khalaf (Beirut, 1986).

68 Kitab al hawddith, ed. B. C A. Ma'ruf and 'I. 'Abd al Salam Ra'uf (Beirut, 1997), pp. 245 6.

69 On madrasas in Iran and the Arab Middle East, see, inter alia, George Makdisi, The rise of

colleges (Edinburgh, 1981); Jonathan Berkey, The transmission of learning in medieval Cairo

(Princeton, 1992); Michael Chamberlain, Knowledge and practice in medieval Damascus,

1190 1350 (Cambridge, 1994); Richard W. Bulliet, Islam: The view from rite edge (New York,

1994); Said Amir Arjomand, 'The law, agency, and policy in medieval Islamic society:

Development of the institutions of learning from the tenth to the fifteenth century',

Comparative Studies in Society and History, 41 (1999), pp. 263 93. On madrasas in medieval

India, see Abu'l Hasanat Nadwi, Hindustan hi qddim Isldmi darsgdhen (A'zamgarh, 1971);

Iqtidar Husain Siddiqui, 'Muslim intellectual life in India', in Iqtidar Husain Siddiqui (ed.),

Medieval India: Essays in intellectual thought and culture (Delhi, 2003), vol. I, pp. 81 94.

70 Cf. Bulliet, Islam, pp. 148 51.

71 Arjomand, 'Law', p. 270.

600

Cambridge Histories Online © Cambridge University Press, 201 1

# Transmitters of authority and ideas

in all four of the Sunrii schools of law that had emerged as pre eminent by that

time. 72 And madrasas established in Iran in the age of the Ilkhanids (c. 658 735/

 $1260\ 1335$ ) and the Timurids (771  $913/1370\ 1507$ ) were often part of what Said

Amir Arjomand has characterised as 'educational charitable complexes' that

included not only mosques but also Sufi convents and hospitals and, as such,

represented a vast increase in scope and function over even the grandest of the

Madrasas, large and small, were supported through pious endowments (awqaf, singular: waqf), specifically allocated, and in perpetuity, by the founder

for the upkeep of the institution and the maintenance of all those the founder

envisioned as being associated with it. The endowment often also specified the

subjects that were to be taught, the madhhab(s) to which the professors and the

students were to belong, and the other pious activities (e.g. the recitation of

the Qur'an) that were to be financed through the endowment. Ideally, the endowment was created from the resources belonging to the individual in question. Yet, as Arjomand has argued, it is not clear that the sultans, viziers

and other members of the ruling elite who created lavish madrasas through

out Muslim societies made any firm distinctions between their 'private' property and the resources of the state that they controlled, any more than

they did between founding madrasas as a matter of personal piety and doing

so as a facet of public policy. 74

The study of law was typically at the centre of a madrasa's concerns, as the

work of George Makdisi has demonstrated, 75 and the rich history of Islamic

law no doubt has much to do with the financial resources made available for

its study through the madrasa and its endowments. But law was scarcely the only concern of the madrasas. Expertise in the other 'transmitted' or sharfa sciences (al 'ulum. al naqliyya) 76 was essential to the training of a jurist,

though many of these sciences were also studied for their intrinsic interest.

72 Ef 'al Mustansir bi'llah', (C. Hillenbrand). For an account of the founding of this madrasa, see Kitab al hawddith, pp. 80 6.

madrasa, see Kitab ai nawddith, pp. 80 6.

73 Arjomand, 'Law', pp. 271 6, esp. 272.

74 Ibid., pp. 281 5, 290. On the legal manoeuvres whereby state land was converted into

private property as a prelude to being turned into waqf endowments, see Maria

E. Subtelny, Timurids in transition: Turko Persian politics and acculturation in medieval Iran (Leiden, 2007), pp. 220 7.

75 See, especially, Makdisi, Colleges.

76 It is common to render al 'ulum al naqliyya ('the transmitted sciences') as the 'religious

sciences'. But the 'rational sciences' (al 'ulum al 'aqliyya), from which they are distin

guished were, arguably, also 'religious' sciences. I therefore prefer 'sharfa sciences' as

the characterisation for al 'ulum al naqliyya a characterisation that is occasionally used

by the 'ulanuV themselves. Cf. 'Abd al Hayy al Laknawi, al FawcVid, pp. 209, 213, 228, etc.

601

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

The Mustansiriyya's deed of endowment provided, for instance, for a Dar al

hadtth, headed by a scholar with a 'superior [literally: 'high'] chain of trans

mission' linking him to earlier transmitters ofhadith. It was to this position that

the aforementioned Ibn al Najjar had been appointed on returning from his

long travels. 77 The rational sciences including not just philosophy but also

astronomy, mathematics and medicine were also taught in many madrasas,

however. 78 The Mustansiriyya's endowment deed itself provided for a physi

cian not only for the wellbeing of others attached to the madrasa but also to

train medical students. 79 Nor was it unusual for royal patrons of madrasas for

example those founded by the Ottoman sultan Mehmed II (r. 848 50/1444  $\,$ 

and  $855\ 86/1451\ 81)$  as part of his educational complex in Istanbul to specifically require competence in the rational sciences as part of the profes

sors' qualifications. ° And the madrasa founded in Samarqand by the Timurid

prince Ulugh Beg (d. 853/1449) was headed by a distinguished mathematician,

and drew many others to it. J

That madrasas could serve as sites for the pursuit of various transmitted and

rational sciences was due not only to the interests and commitments of those

founding these institutions (Ulugh Beg, for instance, was himself an accom

plished mathematician), but also to the fact that a scholar's work often encompassed varied disciplines. Sonja Brentjes has shown that the rational

and the sharfa sciences had begun to draw increasingly close to one another

from the fifth/ eleventh century onwards: works on law also contained discussions on logic, for instance, and biographical dictionaries routinely praise

the same scholar as a master of the rational and the sharfa sciences even

they testify to their training of students in each. 2 Indeed, the rational sciences

had gradually themselves come to be studied in the manner of the sharfa sciences: 'the same modes of writing epitomes, paraphrases, commentaries

and supercommentaries applied to all of the [rational and transmitted] scien

ces, as did the same modes of learning, whether by heart, with a tutor, through serving a master, or by reading authoritative texts'. 83 Brentjes has

argued that these practices may have contributed to the decline of the rational

77 Kitdb al hawddith, p. 246.

78 Sonja Brentjes, 'On the location of the ancient or "rational" sciences in Muslim educa

tional landscapes (AH 500 1100)', Bulletin of the Royal Institute for Inter Faith Studies, 4 (2002), pp. 47 71.

79 Kitdb al hawddith, p. 85.

80 Ihsanoglu, 'Ottoman science', p. 16. The same was true of the madrasas established by sultan Siileyman the Magnificent: cf. ibid., p. 17.

81 Cf. Ef 'Ulugh Beg' (B. F. Manz); Arjomand, 'Law', p. 275.

82 Brentjes, 'On the location'.

83 Ibid., p. 65.

602

Cambridge Histories Online © Cambridge University Press, 201 1

## Transmitters of authority and ideas

sciences in the later Middle Ages, for these sciences were not always amenable

to such modes of discourse. The case for any such decline has come to appear

increasingly tenuous, however, in the light of recent scholarship on late medieval and early modern Islamic societies. 84 The overlap and fluidity of

genres are nonetheless readily discernible in the scholarly culture of the period, which means that no firm barriers separated the scholars rooted in

the sharfa sciences from those excelling in other disciplines.

Yet, for all this interpenetration of genres, there remained important differ

ences of emphasis within this scholarly universe. Some of these surely had to

do with individual predilections. Muhammad b. Tughluq, the Delhi sultan who had patronised Ibn Battuta, was known for an especially keen interest in

the rational sciences, with Diya 1 al dm Barani (d. c. 758/1357), a contemporary

historian, going so far as to attribute the much dreaded brutality of this sultan

to the hard heartedness that came with these rational sciences. 85 Emphasis on

particular disciplines also varied from one time or place to another. Hadith and

law were at the forefront of scholarly learning during the 'Sunm revival' in the

reign of the Timurid ruler Shah Rukh (r. 807 50/1405 47). Conversely, and

for all the overlap between the transmitted and the rational sciences, the latter

would long remain a primary focus of scholarly interest in India. Important

advances were made in tenth/ sixteenth century Gujarat and eleventh twelfth/seventeenth eighteenth century Delhi in the study of hadith, to which, as observed earlier, the authority of several generations of scholars

was intimately tied. Yet it would have been difficult to find many madrasas in

India whose 'curriculum' included a dozen works in the genre of Qur'anic exegesis (tafsif) and another twelve relating to hadith as was apparently the

case with a curriculum for advanced studies in Ottoman madrasas, issued in

973/1565 on the authority of the Ottoman sultan Siileyman the Magnificent

(r. 926 74/1520 66). 8y

Scholars were mobile, as we have seen, and it was typically through their movement that new trends, new topics and new books were introduced into a

84 Khaled El Rouayheb, 'Opening the gate of verification: The forgotten Arab Islamic

florescence of the 17th Century', International Journal of Middle East Studies, 38 (2006), pp. 263 81.

85 Diya' al din Barani, Ta'fikh i Firuzshahi, ed. Sayyid Ahmad Khan (Calcutta, 1862), pp. 464 7-

86 Maria Eva Subtelny and Anas B. Khalidov, 'The curriculum of Islamic higher learning in

Timurid Iran in the light of the Sunni revival under Shah Rukh', journal of the American

Oriental Society, 115 (1995), pp. 210 36.

87 See Shahab Ahmed and Nenad Filipovic, 'The sultan's syllabus: A curriculum for the

Ottoman imperial medreses prescribed in a ferman of Qanum I Siileyman, dated 973

(1565), Studia Islamica, 98 9 (2004), pp. 183 218.

603

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

community's intellectual circles. 88 Mir Fath Allah (d. 977/1569), a distinguished rationalist scholar from Shiraz who eventually came to serve as head of the religious establishment isadr al sudur) under the Mughal emperor

Akbar (r. 963 1014/1556 1605), is credited with having introduced the works of

Jalal al din Dawani (d. 908/1502) and Mulla Sadra (d. 1050/ 1640) into north

Indian study circles and to have further strengthened the rationalist tradition

in India. 9 Contemporary observers likewise credited Kurdish and Persian

scholars with having introduced new books into seventeenth century study

circles in the Arab Middle East along with new methods of critically examining

texts (tahqiq). 9 ° As al Muhibbi (d. 1111/1699) wrote of one such scholar, Mulla

Mahmud al Kurd! (d. 1074/1663^, 'he mostly taught the books of the non Arabs (kutub al a c ajitri), and he was the first to acquaint the Syrian students

with these books ... It is with him that the gate of tahqiq in Damascus was

opened/91

Commentaries and glosses on well established earlier works assured their

longevity and helped launch the career of new generations of scholars even as

new works and new discursive methods continued to be introduced into particular scholarly circles. Needless to say, many books also regularly con

tinued to fall out of circulation. The vicissitudes of a manuscript culture had as

much to do with this as, of course, did the competition with new books. Some

jurists specifically required that the texts a mufti relied upon in issuing his

fatwas ought to be in broad circulation for his legal pronouncements to be

credible. 91 Thus a scholar who might, in one locale, have easily drawn on a

well recognised work would not be able to invoke it in his fatwas in another,

88 Cf. the stories about the introduction of particular texts in the Muslim scholarly circles

of eastern China in the seventeenth century: Ben Dor Benite, The Dao of Muhammad, pp. 82 8.

89 Ghulam 'All Azad Bilgrami, Ma'athir al kiram, ed. Muhammad 'Abduh Lyallpuri (Lahore, 1971), pp. 228 9.

90 El Rouayheb, 'Opening the gate of verification'.

91 Muhammad Amin al Muhibbi, Khulasat al atharfi a'yan al qam al hadx 'ashar (Beirut, n.d.),

vol. IV, pp. 329 30; quoted (with some changes) from El Rouayheb, 'Opening the gate of

verification', p. 265. For an explication of how a teacher ought to elucidate a text in all its

complexity to his students, see Shah Wall Allah, 'Risala i danishmandT', published

together with Shah Raff al din, TakmH al adhhan, ed. Abd al Hamid al Sawati

(Gujaranwala, n.d.), pp. 179 83. What Wall Allah characterises as 'danishmandi' in this

work seems similar to what al Muhibbi means by 'tahqiq' here. Note also that the isnad

Wall Allah gives for his reception of this discursive method from his father includes many

rationalist luminaries, including Mir Muhammad Zahid Harawi (d. 1111/1699), the afore

mentioned Jalal al din Dawani, and Sa'd al din Taftazani (d. 793/1390) (ibid., p. 179).

92 Cf. Ibn al Humam, Shark fath al qadir, 10 vols. (Cairo, 1970), vol. VII, p. 256; Wall Allah, Tqd aljid, p. 35.

604

Cambridge Histories Online © Cambridge University Press, 201 1

Transmitters of authority and ideas

where it might simply be unavailable. 93 It would be recalled that the Central

Asian compiler of the Muhit al Burhdnihad noted in the Preface to his own

work that the legal writings of his ancestors were all in circulation, that they were relied upon by judges and muftis and that he had compiled his Muhit in order to join their scholarly company. Ironically, however, the Muhit itself fell out of circulation, and some scholars notably the Egyptian

HanafI jurist Ibn Nujaym (d. 970/1563) disallowed/atwas with reference to it. 94 The late nineteenth century Indian scholar Muhammad 'Abd al Hayy (d. 1304/1886) notes that, like some others before him, he had assumed the disallowing of fatwds on the basis of the Muhit to have been a function of the book's poor quality. But, having chanced upon a copy of the manuscript, he found it to be a generally sound work. 'It then became clear to me,' he writes, 'that [Ibn Nujaym's] interdiction of fatwds on its basis had to do, not with the intrinsic qualities of this work or [the credentials] of its author, but only with the fact that the book had become

inaccessible. This is a matter that varies from one age or region to another.

Many a book is extinct in one place but available in another, hard to find at

one time and plentiful at another.' 95

This is a sensible view of the matter, though it may also reflect an age when the technology of print was making long forgotten works available afresh to scholars. Applied to an earlier age, however, 'Abd al Hayy's comment may suggest yet another limit on the cosmopolitanism of the 'ultima': an acquaintance with scholarly modes of discourse allowed entry into the circles of the c ulamd' and could open doors to the patronage of the

ruling elite, but further recognition would have required deeper immer

sion in the scholarly culture of the local community a mastery of the texts available, and authoritative, in that community. Even the 'authorisation' (ijdza) 'to teach and issue fatwds', which some have taken to be the equivalent of a medieval 'doctorate in Islamic law', would probably have

93 They could always be introduced by him there, of course, but it is unlikely that they

would acquire sufficient currency rapidly enough for him to then base his juristic

responsa on them. Being in possession of a chain of transmission through which one

claimed to have acquired the right to teach and transmit a text was likewise an accept

able way of putting it to use, but even this may have worked better with, say, hadith

reports than with large works of substantive law in a milieu where they were previously unknown.

94 Ibn Nujaym, 'Fi sura waqfiyya ikhtalafat al ajwiba fiha', in Ibn Nujaym, Rasa'ti Ibn

Nujaym al iqtisadiyya, al musammat al RasaHl al Zayniyya fi madhhab al Hanafiyya, ed.

M. A. Siraj and 'A.J. Muhammad (Beirut, 1998), pp. 287 93, at 291.

95 'Abd al Hayy al Laknawi, al Fawd'id, p. 206.

605

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

resonated most in circles where the scholars issuing it were themselves well known. 9

The ^v&amtf and the state

Many of the scholars we have encountered in the preceding pages were the

beneficiaries, in one form or another, of royal patronage. Al Saghanl, the celebrated lexicographer and compiler of the Mashdriq al anwar, was sent on

caliphal missions from Baghdad, his adopted home, to his native India by the

Abbasid caliphs al Nasir (r. 575 622/1180 1225) and al Mustansir (r. 623 40/1226

42); and he was later appointed by the caliph al Musta'sim (r. 64056/124258) to

the Tutushiyya madrasa in Baghdad. 97 Though the purpose of al Sagharii's trips

to India remains uncertain, they may have had to do with al Nasir's innovative

efforts to extend the caliphate's moral authority over other Muslim rulers and,

specifically perhaps, with the investiture of the Delhi sultans as the deputies of

the caliphs in Baghdad a highly symbolic but politically not insignificant initiative that promised a much cherished facet of legitimacy to the sultans in

exchange for a formal recognition of their subservience to the caliph. 98 Even the

usually reclusive Gujarati scholar All al Muttaqi, who spent much of his later

life in Mecca, briefly returned to Gujarat in 955/1548 to oversee the implemen

tation of the sharfa in the polity of the young sultan Mahmud II (d. 961/1554). "

The networks of Hadrami scholars were, for their part, made possible not only

by their dexterously orchestrated scholarly credentials but also by the patronage

of local rulers around the Indian Ocean which these credentials helped secure.

And as long as it lasted, al Ramri's campaign against wayward beliefs had the full

force of the Acehnese royal court behind it. If Abd al Haqq Dihlawi had misgivings about the Mughal emperor Shah Jahan (r. 1037 68/1628 57), to

whom he presented his Arabic commentary on the Mishkat al masatrih, he did

not express them in his preface to this work. Instead, he characterised the

96 Devin Stewart, 'The doctorate of Islamic law in Mamluk Egypt and Syria', in J. E.

Lowry, D.J. Stewart and S. M. Toorawa (eds.), Law and education in medieval Islam:

Studies in memory of Professor George Makdisi (Chippenham, 2004), pp. 45 90. Makdisi

too, on occasion, acknowledged the limits of geography on a scholar's ijaza. Cf. Colleges,

p. 152: 'the disputation was the final test a candidate had to pass in order to obtain his

license. He then was eligible for a teaching position in the locality in which he had proved

himself a disputant' (emphasis added).

97 Kitab al hawadith, pp. 306 7; Ef 'al Saghani'.

98 Cf. Aziz Ahmad, Studies in Islamic culture in the Indian environment (Oxford, 1964), pp. 3 11.

On al Nasir's efforts to revive and extend the authority of the caliphate, cf. Ef 'al Nasir li

din Allah' (A. Hartmann).

99 Kugle, 'In search of the centre', pp. 438 57.

606

Cambridge Histories Online © Cambridge University Press, 201 1

Transmitters of authority and ideas

emperor as 'the manifestation of the virtues of religion, the devoted adherent of

the firm sharfa, oriented towards God and His prophet in all basic and subsidiary matters'. 100 All this is stylised rhetoric, of course, yet it illustrates a

scholar's vision of what a ruler should be like even as it testifies to his own

willingness to associate with him.

It was royal patronage that enabled many scholars to not only pursue well

trodden paths but also areas of enquiry that were unpopular in some circles.

Fakhr al Din Razi (d. 606/1210), the noted exegete and Ash'ari theologian,

enjoyed the favour of both the Khwarazm Shahs and the Ghurids, for all that

these dynasties were engaged in a bitter conflict with each other. Ghiyath al

Din Muhammad (r. 558 99/1163 i202f), his Ghurid patron, had built a madrasa for him in Herat as a way of 'shielding] Fakhr al Din's teaching activity from the criticism of his peers inside and outside the Ash'ari school'. 101

As Frank Griffel has argued, such patronage seems to have played an impor

tant role in the development and spread of the rational sciences in the eastern

Islamic lands. 102

Mughal emperors in India tended to allocate revenue grants (madad i ma' ash) to scholars and Sufis more often than they established pious endow

ments (waqfs). 103 But the patronage of the ruling elite was crucial just the same

for the continuation of scholarly endeavours and for attracting streams of scholars from outside India, as well as from different parts of India to the royal

court. A monumental work such as the Fatawa 'Alamgiriyya, compiled during

the reign of the Mughal emperor Aurungzeb 'Alamglr and named after him, likewise underscores the significance of royal patronage: the project,

on which a team of leading Hanafl jurists worked, is said to have cost a large sum, and it was the scholarly resources of the imperial library that had made this venture possible in the first place. 104

100 'Abd al Haqq Dihlawi, Lama'at al tanqih, vol. I, pp. 201. Earlier, Dihlawi had presented

another work of his to Shah Jahan's father, the Mughal emperor Jahangir. See Jahangirnama: Memoirs of Jahangir, emperor of India, ed. and trans. Wheeler

M. Thackston (New York, 1999), p. 316.

101 Frank Griffel, 'On Fakhr al Din al Razl's life and the patronage he received', Journal of Islamic Studies, 18 (2007), p. 343.

102 Ibid., pp. 341 3 and passim.

103 Gregory C. Kozlowski, 'Imperial authority, benefactions and endowments (awqaf) in

Mughal India', Journal of the Economic and Social History of the Orient, 38, 3 (1995), pp. 355 70;

Rafat M. Bilgrami, Religious and quasi religious departments of the Mughal period (i%6 1707J (Delhi, 1984), pp. 59 98.

104 On the cost of producing this work and the use of the imperial library for it, see

Musta'idd Khan, Ma'athir i 'Alamgiri, pp. 529 30.

607

Cambridge Histories Online © Cambridge University Press, 201 1

### The New Cambridge History of Islam

Illustrations such as these are not meant to deny that some scholars and Sufis

would have been far more eager to keep their distance from the governing elite

than to frequent their circles. The existence of such scholars should not, however, lead us to reify what some medieval observers rhetorically charac

terised as the 'worldly' and the 'otherworldly' c ulama $\ m5$  As Sunil Kumar has

argued, the discourses of Sufis like the much revered Nizam al dm Awliya'

(d. 725/1325) point, instead, to a considerably more fluid distinction between, on

the one hand, those 'worldly' figures who were prone to using their religious

and scholarly pretensions to curry favour with the rulers and, on the other,

those whose piety and learning entitled them to a share in the royal patronage,

which they were able to use for the good of others. It was the former sort of

people who were most likely to be objects of derision in scholarly and Sufi

circles. 10 It is worth noting, finally, that the ruling elite were crucial to the

scholarly culture even when many of those who were part of that culture

wished to have no personal contact with the rulers. More important than any

direct patronage of scholarly circles was, after all, the creation and maintenance

of the conditions in which scholars could travel and engage in the pursuit and

transmission of learning and in which they could hope to see the fundamental

norms of the sharta at least publicly affirmed. The legitimacy of the rulers itself

depended on the creation and preservation of such conditions; 107 and few

among the religious and the political elite disputed that their institutions were, in fact, interdependent.

### Tradition, identity and authority

The period with which this volume is concerned saw major developments in

law, Qur'anic exegesis and the study of hadith, as well as in the rational sciences. Scholars, texts and ideas moved not just eastward, from the Arab

Middle East and Iran to India and South East Asia, but also in the other direction, with Kurdish and Iranian scholars introducing seventeenth century

Damascene study circles to new texts and approaches, as we have observed,

and eighteenth century figures like the north Indian Murtada al Zabidi (d. 1205/1791) achieving great recognition in the Arab Middle East and

105 For such reified formulations in modern scholarship, cf. Khaliq Ahmad Nizami, Some

aspects of religion and politics in India during the thirteenth century (Bombay, 1961), 152; for

a critique, see Sunil Kumar, The emergence of the Delhi sultanate (Delhi, 2007), pp. 219 24,

esp. 219 20 n. 61.

106 See Kumar, Emergence, pp. 219 24.

107 Cf. Petry, 'Travel patterns', pp. 81 5.

# Transmitters of authority and ideas

beyond. 108 Many, though by no means all, scholars of the later Middle Ages

were reluctant to claim that their ideas diverged significantly from those of

their forebears. Yet, as we have observed, such rhetoric, and the well worn

genres in which they typically chose to express themselves, should not obscure the ingenuity of these scholars and their resourcefulness in adapting

earlier ideas to changing needs.

Nor, however, should we place a premium only on what appears to us novel in the scholarly culture of the 'ulamd'. For even when it was largely a

matter of the transmission, translation and repackaging of an existing body of

knowledge, it continued to serve important purposes. As Zvi Ben Dor Benite

has shown with reference to eastern China during the eleventh twelfth/

teenth eighteenth centuries, Muslim scholarly practices in this region usually

consisted in the translation into Chinese of Arabic and Persian texts, the dissemination of such texts as well as of many others produced in dialogue

with them in the scholarly circles inhabited by Muslims of eastern China, the

establishment of a vast but closely knit network of schools, and discursive

techniques informed not only by a sense of affinity with scholars elsewhere in

the Muslim world but also with China's Confucian literati. 109 In the eleventh

twelfth/ seventeenth eighteenth centuries, 'Chinese Muslims, like their non

Muslim Confucian counterparts, were active producers of bibliographies, cata

logues, genealogies, anthologies, and the like,' 110 all of which both helped

constitute a distinctive Chinese Islamic scholarly tradition and came to be

among its most characteristic expressions. Even when not viewing Chinese

Islam as peripheral to a history of Muslim intellectual practices, it might be

tempting to consider such cultural production and the practices that made it

possible as illustrative, above all, of an age of intellectual decline in the history of

Islam an age dominated by 'mere' genealogies and commentaries. But as Ben

Dor Benite has persuasively demonstrated, it was precisely through a painstak

ing preservation and memorialising of the work of their forebears and contem

poraries that the sense of a self conscious and closely knit scholarly community

was fostered which, in turn, was central to the construction and the preservation

of a distinctive Muslim identity in China.

Whether particular L ulama' made claims to reshaping facets of the scholarly

tradition, to reviving the path of the forebears, or simply to continuing inherited practices and passing them on through their books and their

108 Stefan Reichmuth, 'Murtada az Zabidi (d. 1791) in biographical and autobiographical accounts', Die Welt des Islams, 39 (1999), pp. 64 102.

109 Ben Dor Benite, Dao of Muhammad. no Ibid., p. 121.

609

Cambridge Histories Online © Cambridge University Press, 201 1

The New Cambridge History of Islam

students, their discursive practices were crucial as much to the articulation of

their own authority as they were to the preservation of their scholarly tradition. As the Chinese example suggests, the 'ulamd , 's scholarly practices

were equally central to the sense of a stable Islamic identity in the larger community they inhabited. The contexts in which the ^ulamd 1 have lived and

worked in the modern world have often been radically different from those

with which this volume, and this chapter, are concerned. Yet the sense of a

stable religious identity has not ceased to be intertwined with their scholarly

tradition, which has continued to be an important site both for new articu lations of authority and for ongoing explorations of ways to adapt their practices to change.

610

Cambridge Histories Online © Cambridge University Press, 201 1

Glossary

All terms are Arabic except where designated as Bg = Bugis; Ch = Chinese; H =

Hindi/Urdu; I = modern Indonesian; J = Javanese; M = Malay; Mg = Mongolian;

P = Persian; Po = Portuguese; S = Sanskrit; T = Turkish

c ada, adat (M/I, from Ar 'adat) ahl al kitab

ajam Akhbari

'Alawiyya

```
'Alids
c alim, pi. 'ulama'
amir
amir al mu'minin
anda (Mg)
Ash'arism
'Ashurff
atabeg (T)
custom
'People of the Book', i.e. Jews and
Christians (extended de facto to
Zoroastrians)
non Arabs, usually referring to Persians
Shi'i theological school, opposed to the
use ofijtihad
The most influential brotherhood in
the colonial period whose main shrine
was at Inat
descendants of All b. Abi Talib,
notably the Shi'i imams
religious scholar
commander, ruler
Commander of the Faithful, a tide of
```

```
the caliph
sworn brother, in Mongol society
school of theology, the foundation of
which is attributed to al Ash'ari (d. 935)
ShTi religious festival on the tenth day
of Muharram, commemorating the
death of the third imam Husayn at
Karbala 3 in 680
'father of the prince'; guardian of a
Saljuq prince; later a ruler of a Saljuq
successor state
611
Cambridge Histories Online © Cambridge University Press, 201 1
Glossary
ba'in
Bania (H)
baraka
batin
bafa
```

beg (T)

bid'a

berhala (M)

```
BUM al fulfill
bismilldh
bissu (Bg)
blencong (J)
caciz (Po)
caliph (Ar khalifa)
Chettyars (H)
da'l
dalang (J)
dar al barb
dar al islam
da c wa (M. dakwah)
dawla
dhartna (J)
dharma (S)
dhikr
dhimmT
dhow (Anglo Indian)
tank
Commercially oriented caste, chiefly
in northern India
prestige, blessing
hidden, esoteric meaning of the
```

Qur] an

oath of allegiance

```
prince, chieftain
```

idols, idolatry

doctrinal innovation

Malabar, lit. 'land of pepper'

expression of faith in the supremacy of

Allah

priest of old Bugis religion

oil lamp

Muslim religious specialists (from

qadT)

'successor', 'representative' of the

Prophet Muhammad, title of the head

of the Sunni community and other

rulers

Hindu commercial caste

missionary, propagandist

puppeteer

'abode of war', lands not yet under

Muslim rule and Islamic law

'abode of Islam', lands under Muslim

rule and Islamic law

the court

mission, proselytisation

dynasty, state

pre Muslim hermitages

```
right behaviour
'remembrance' of God, often in the
form of a ritual recitation
protected person, member of the ahl
al kitab
Asian ships sailing in the Indian Ocean
612
Cambridge Histories Online © Cambridge University Press, 201 1
Glossary
din
dinar
din i ildhi
diwan
fanke (Ch)
faqih, pi. fuqaha'
faqir
fatwa
fiqh
firman
fitna
gamelan (J)
```

```
gedimu (Ch)
ghayba
ghazi
ghulam
ghulat
hadith
hafiz
hajj
halal
Han (Ch)
Hanafi
Hanbali
haram
religion, especially of Islam
unit of coinage
eclectic religious movement created
by the Mughal emperor Akbar
(r. 1556 1605)
'register', administration, esp.
financial; department of government
foreign guests
jurist
poor; a religious mendicant
opinion on a legal matter provided by a
mufti
```

```
jurisprudence
```

decree

disorder, anarchy: used as a term for

civil war

Javanese orchestra

lit. old teachings (from Ar qadim);

traditionalist Muslims

'occultation', of the twelfth Shi'i imam,

who disappeared in 874

fighter in the holy war (jihad)

military slave (see also mamluk)

'extremist' Shi'is

a tradition attributed to the

Prophet Muhammad or his

Companions

one who knows the Qur'an by heart

the pilgrimage to Mecca

permitted, in Islamic law

'Chinese', though in pre modern usage

including Koreans and others and

excluding many southerners

one of the four schools (madhhab) of

Sunni Islamic law

one of the four schools of Sunni

```
Islamic law
forbidden, in Islamic law
613
Cambridge Histories Online @ Cambridge University Press, 201 1
Glossary
hijra
hikayat (M, from Ar)
Hui, Huihui (Ch)
hujiao (Ch)
ijaza
ijmti
ijtihad
ilchi (Mg)
Him (M ilmu), pi. Hilum
imam
imam
iqtiF
Isma'ilis
isra
```

#### Ithna 'Ashan

```
jahr
jam? masjid
jihad
```

jimat (M) jinn

the emigration of the Prophet

Muhammad from Mecca to Medina in
622 CE, which marks the beginning of
the Muslim era and calendar
chronicle

Muslim

hui teaching: Islam
document certifying one's authority to
teach classical Islamic texts
consensus of the Muslim community
on a matter of Islamic law
use of individual reasoning in
interpreting Islamic law
envoy (from the Mongol period)
'science', esp. of religion

prayer leader

title of the heads of Shi c i Islam

following 'All

an assignment of land or its revenue;

provincial government; held by a

muqta'

Shi'i sect founded in 765, which split off

from what was to become the

**Twelvers** 

Muhammad's ascension through the

various levels of Heaven

'Twelver', the largest Shi c i sect, which

believed in the succession of twelve

imams: made the official religion of

Iran under the Safavids

vocal dhikr

'congregational' or Friday mosque

'struggle', either internal, against one's


own faults, or external, warfare against


the infidel; holy war


talisman, often in form of sacred formula


airy or fiery being(s), the third intelligent

form of life beside humans and angels











```
mihrab
mila (Swahili)
minbar
mi'rtij
mu l allim (M. mualim)
mufti
mujtahid
mulld (P)
mufid
murshid
murtad
mustawp
Nan (Ch)
nass
ngehnu (J)
nisba
Nizaris
nobat (M)
noker (Mg)
Pardesi (H)
pleat tanda (J)
peranakan (M)
perang sabil (I)
pertapaan (J)
pesantren (J)
pesisir (J)
p tr (P)
court exercising jurisdiction
```

supplementary to that of the qddx, for

the redress of grievances

niche in a mosque to indicate the

direction (qibla) of Mecca and therefore

of prayer

custom

pulpit in a mosque

Muhammad's 'night journey'

expert, especially in mysticism;

navigator

jurist with authority to issue legal

opinions (fatwa)

c dlim competent to exercise ijtihad

Muslim cleric

disciple of a Sufi master

Sufi master

apostasy

revenue accountant

southern (people)

designation of a Shi'i imam by his

predecessor

(esoteric) knowledge (cf. Him)

Arabic name affixations indicating

relation to place, tribe or person


Isma'ili sect, esp. in Persia, from 1094


drums used in installing rulers;

```
enthronement
comrade, follower, in Mongol society
Malabar Muslims of Arab ancestry
head of the market
locally born persons, usually of foreign
descent
war in the way (of God)
hermitages
Islamic school (for santri)
coast, shoreline
master of a Sufi brotherhood
616
Cambridge Histories Online © Cambridge University Press, 201 1
Glossary
prabu pandita (J)
king priest
prajurit estri (J)
sultan's elite female guard
qddi
```

```
judge of Islamic law
Qadiriyya
Sufi brotherhood following tradition of
c Abd al Qadir
qaldn (Mg)
a Mongol tax
qanat
underground irrigation channel
qiyama
the Resurrection
Qizilbdsh (T)
'red heads', the Turkmen tribal
followers of the Safavid order
qubchur (Mg)
tax on flocks and herds; poll tax
```

```
qullar (P)
members of the Safavid ghu ]dm cavalry
qurchi (P)
members of the permanent military
force of the early Safavids
quriltai (Mg)
Mongol assembly of notables
ram adi! (J/M)
just king
rifrat
fortress on the frontiers of the ddr
al islam; a Sufi monastery
5ahib diwdn
minister of finance; chief minister in
```





```
shahna
military governor
617
Cambridge Histories Online © Cambridge University Press, 201 1
Glossary
sharfa
sharif
shaykh
Shi'a
Sufi
sultan (sultan)
suluk (J)
surma
Sunm
suyurghal
syair (M)
tabaqat
tafslr
tamgha (T)
tapa (J)
taqiyya
```

```
ta'rikh
Tcfrikh
tafiqa
tayungan (J)
```

tcfziya

tian (Ch) Tian Fang (Ch) tiyul

God's law, interpreted by the fuqaha' of noble lineage, especially from the Prophet

'old man'; leader of a tribe; head of a

Sufi fraternity

one of the two main branches of Islam,

the other being the Sunni

a Muslim mystic

power'; title used by Muslim rulers,

Saljuq period and after

verse genre, of Sufi literature in

Javanese

the example of the Prophet

Muhammad: one of the sources of

Islamic law

one of the two main branches of Islam,

the other being the Shi'a

an assignment of land or its revenue, a

form of iqta 1

verse form of traditional Malay

literature

an Arabic genre of biographical

dictionary

Qur'anic exegesis

tax on commercial transactions

ascetic /mystic

tactical dissimulation, esp. among the

Shi'a

history, date

Maldivian state chronicle

Sufi fraternity

dance performed by ornately

costumed archers

Shi c i passion play, commemorating the

death of the Imam Husayn

Heaven

Mecca; the Ka'ba

a form of iqtff


618

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

```
Glossary
tusheng fanke (Ch)
autochthonous or native born foreign
guests
'ulama 1
plural of c ah'm; more commonly used
(Malay ulama) than the singular to
designate a religious scholar in
South East Asia
umma
the Muslim community
undang undang (M)
digest of customary law
```

```
l urf
customary law
Usui!
Shi'i theological school which
favoured the use ofijtihad
Vanias (H)
Hindu commercial caste
vizier
minister, often chief minister
wahdat al wujud
Sufi doctrine of 'the oneness of Being'
wahy (M/J wahyu)
divine revelation; in Java, the divine
charisma of kings
wali (J)
```

```
apostle, holy man (from Ar wall, saint)
wali sanga (J)
'nine saints' to whom Islamisation of
Java is attributed
waqf (pi. awqdf)
Muslim religious endowment
wayang (J)
theatre, especially of shadow puppetry
wayang golek (J)
three dimensional rod puppets
wayang kulit (J/M)
shadow puppet theatre (lit. leather
theatre)
wayang topeng (J)
masked theatre
```



# **Bibliography**

i The steppe peoples in the Islamic world Edmund Bosworth

Practical suggestions for farther reading

Barthold, W., Turkestan down to the Mongol invasion, Gibb Memorial Series, n.s. vol. V, 3rd

edn., London, 1968.

Bosworth, C. E., 'The political and dynastic history of the Iranian world (AD 1000 1217)', in

J. A. Boyle (ed.), The Cambridge history of Iran, vol. V: The Saljuq and Mongol periods

Cambridge, 1968, pp. 1 202.

Grousset, R., The empire of the steppes: A history of Central Asia, Eng. trans. Naomi Walford,

New Brunswick, NJ, 1970.

Morgan, David O., Medieval Persia, 1040 1797, London and New York, 1988.

Safi, Omid, The polities of knowledge in premodern Islam: Negotiating ideology and religious

enquiry, Chapel Hill, NC, 2006.

Soucek, Svat, A history of Inner Asia, Cambridge, 2000.

UNESCO, History of civilizations of Central Asia, 8 parts in 7 vols., Paris, 1992 2005.

Primary sources

Barhebraeus, Chronography, Eng. trans. E. A. Wallis Budge, London, 1932.

Bayhaqi, Abu '1 Fadl, Tarxkh i Mas'udi, ed. A. A. Fayyad, Tehran, 1350/1971.

Bundan, al Fath b. Ah, Zubdat al nusra wa nukhhat al 'usra, ed. M. T. Houtsma in Recueil de

textes relatifs a l'histoire des Seljoucides, vol. II, Leiden, 1889.

Gardizi, Abd al Hayy b. al Dahhak, Kitab Zayn al akhbar, ed. Muhammad Nazim, Berlin

Steglitz, 1928.

al Husaym, Sadr al Din Ah, Akhbar al dawla al saljuqiyya, ed. Muhammad Iqbal, Lahore, 1933.

Ibn al Athir, 'Izz al Dm, al Kamilfi 'I ta'rikh, 13 vols., Beirut, 1385 7/1965

Ibn al Balkhi, Tars nama, ed. G. Le Strange and R. A. Nicholson, Gibb Memorial Series, n.s.

vol. I, London, 1921.

Ibn Fadlan, Ahmad, Rihla, ed. and Ger. trans. A. Z. V. Togan, Ibn Fadlans Reisebericht,

Abhandlungen für die Kunde des Morgenlandes, XXIV/3 (Leipzig, 1939); Fr. trans.

Marius Canard, 'La relation du voyage d'Ibn Fadlan chez les Bulgares de la Volga', in

Annales de l'Etudes Orientales de la Faculte des Lettres d'Alger, 14 (1956), pp. 41 146;

Eng. trans. R. N. Frye, Ibn Fadhn's journey to Russia: A tenth century traveler from Baghdad

to the Volga river, Princeton, 2005.

620

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Juwaym, Ata' Malik, Tankh i Julian gusha, Eng. trans. J. A. Boyle, The history of the World

Conqueror, 2 vols., Manchester, 1958. Juzjam, Minhaj al Dm, Tabaqat i nasin, ed. 'Abdal Hayy Habibi, 2 vols. (Kabul, 1342 3/1963 4), Eng. trans. H. G. Raverty, Tabakat i nasin: A general history of the Muhammadan dynasties

of Asia, including Hindustan, 2 vols., London, 1881 99. Kashghan, Mahmud, Diwan lughat al turk, Eng. trans. Robert Dankoff and James Kelly,

Compendium of the Turkic dialects (Diwan luyat at Turk), 3 vols., Cambridge, MA, 1982 5.

Muhammad b. Ibrahim, Tarxkh i Saljuqiyan i Kirman, ed. M. T. Houtsma, in Recueil de textes

relatifs a Vhistoire des Seljoucides, vol. I, Leiden, 1886.

Narshakhi, Abu Bakr Muhammad, Tarxkh i Bukhara, ed. Mudarris Ridawi (Tehran, n.d.

[i939])> Eng. trans. R. N. Frye, The history of Bukhara, Cambridge, MA, 1954.

Nizam al Mulk, Abu Ah Hasan Tusi, Siyasat noma, ed. H. Darke, Tehran, 1340/1962, 2nd

edn 1347/1968, Eng. trans. Darke, The book of government or rules for kings, London,

i960, 2nd edn 1978.

Pseudo Zahir al Dm Nishapun, Saljuq noma, Eng. trans. K A. Luther, The history of the

Seljuq Turks from the Jami' al tawarikh: An Ilkhanid adaption [sic] of the Saljuq nama of

Zahir al Dm Nishapun, Richmond, 2001.

Rawandi, Muhammad b. All, Rahat al sudur wa ayat al surur, ed. Muhammad Igbal, Gibb

Memorial Series, n.s. vol. II, London, 1921.

Secondary sources

Barthold, W., ZwblfVorlesungen iiber die Geschichte der Tiirken Mittelasiens , trans. Th. Menzel,

Berlin, 1935.

History of tfte Semirechye, in Four studies on the history of Central Asia, trans. V. and

T. Minorsky, vol. I, Leiden, 1962, pp. 73 165. Biran, Michal, The empire of the Qara Khitai in Eurasian history: Between China and the Islamic world, Cambridge, 2005.

Bosworth, C. Edmund, The Ghaznavids: Their empire in Afghanistan and eastern Iran, 994 1040,

Edinburgh, 1963.

'Dailamis in central Iran; the Kakuyids of Jibal and Yazd', Iran, Journal of the British

Institute of Persian Studies, 7 (1969), pp. 73 95.

'Barbarian invasions: The coming of the Turks into the Islamic world', in Islamic

civilisation 950 1150, Papers on Islamic History III, ed. D. S. Richards, Oxford, 1973,

pp. 1 16.

The later Ghaznavids: Splendour and decay: The dynasty in Afghanistan and northern India,

1040 1186, Edinburgh, 1977.

The New Islamic dynasties: A chronological and genealogical manual, Edinburgh, 1996.

'The Seljuqs and the Khwarazm Shahs. Part 3. The eastern Seljuq sultanate (1118 57) and

the rise and florescence of the Khwarazm Shahs of Anushtegin's line up to the

appearance of the Mongols (1097 1219)', in UNESCO, History of the civilizations of

Central Asia, vol. IV: The age of achievement: AD y\$0 to the end of the fifteenth century.

Part 1, the historical, social and economic setting, Paris, 1998, pp. 161 75.

Bregel, Yuri, 'Turko Mongol influences in Central Asia', in Robert L. Canfield (ed.), Turko

Persia in historical perspective, School of American Research Advanced Seminar Series,

Cambridge, 1991, pp. 53 77.

# Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Busse, Heribert, Chalifund Grosskonig. Die Buyiden im Iraq (94J 1055), Beiruter Texte und

Studien 6, Beirut and Wiesbaden, 1969. Cahen, Claude, 'La campagne de Mantzikert d'apres les sources musulmanes', Byzantion, 9

(1934), PP-613 42.

'La premiere penetration turque en Asie Mineure (seconde moitie du XI e siecle)',

Byzantion, 18 (1948), pp. 5 67.

'Les tribus turques d'Asie occidentale pendant la periode seljukide', Wiener Zeitschrift fiir

die Kunde des Morgenlandes, 51 (1948 52), pp. 178 87. 'Le Malik Nameh et les origines seljukides', Oriens, 2 (1949), pp. 31 65. Pre Ottoman Turkey: A general survey of the material and spiritual culture and history c, 1071 1330,

trans. J. Jones Williams, London, 1968.

The formation of Turkey: The Seljukid sultanate of Rum: eleventh to fourteenth century, trans.

## P. M. Holt, Harlow, 2001.

Daftary, Farhad, The Isma'ilis: Their history and doctrines, Cambridge, 1990, 2nd edn, 2007.

Davidovich, E. A., 'The Karakhanids', in UNESCO, History of civilizations of Central Asia,

vol. IV: The age of achievement: AD J50 to the end of the fifteenth century, Part 1, The

historical, social and economic setting, Paris, 1998, pp. 119 43. Frye, Richard N., Bukhara, the medieval achievement, Bibliotheca Iranica Reprint Series no. 3,

Costa Mesa, CA, 1997.

Gibb, H. A. R., The Arab conquests in Central Asia, London, 1923. Golden, B., Peter, 'The Karakhanids and early Islam', in Denis Sinor (ed.), The Cambridge history of early Inner Asia, Cambridge, 1990, pp. 343 70.

An introduction to the history of the Turkic peoples, Turcologica 9, Wiesbaden, 1992.

Gordon, MatthewS., The breaking of a thousand swords: A history of the Turkish military of

Samarra (AH 200 2J5/815 889 CE), Albany, 2001.

Hartmann, Angelika, An Nasir li Dm Allah (1180 1225). Politik, Religion, Kultur in der spaten

'Abbasidenzeit, Studien zur Sprache, Geschichte und Kultur des islamischen Orients, n.s. 8,

Berlin and New York, 1975.

Hillenbrand, Carole, Turkish myth and Muslim symbol: The battle ofManzikert, Edinburgh, 2007.

Hodgson, Marshall G. S., The order of Assassins: The struggle of the early Nizdri Isma'ilis against

the Islamic world, The Hague, 1955.

Kafesoglu, Ibrahim, Sultan Meliksah devrinde Biiyiik Selcuklu imparatorlugu, Istanbul, 1953.

Harezmsahlar devleti tarihi (48) 617/1092 1229J, Ankara, 1956. Klausner, CarlaL., The Seljuk vezirate: A study of civil administration iojj 1194, Harvard

Middle Eastern Monograph Series XXII, Cambridge, MA, 1973. Kochnev, Boris D., 'Les frontieres du royaume des Karakhanides', in Vincent Fourniau

(ed.), Etudes karakhanides, Cahiers dAsie centrale, 9, Tashkent and Aix en Provence,

2001, pp. 41 8.

'La chronologie et la genealogie des Karakhanides du point de vue de la numismatique',

in Etudes karakhanides, pp. 49 75.

Kopriilu, Mehmed Fu'ad, Early mystics in Turkish literature, ed. and Eng. trans. Gary Leiser

and Robert Dankoff, Routledge Sufi Series, London and New York, 2006. Koymen, Mehmad Altay, Biiyiik Selcuklu imparatorlugu tarihi, vol. II: Ikinci impartorluk devri,

Ankara, 1954.

Lambton, A. K. S., Landlord and peasant in Persia: A study of land tenure and land revenue

administration, London, 1953; expanded edn., 1991.

622

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

'The administration of Sanjar's empire as illustrated in the 'Atabat al kataba , Bulletin of the

School of Oriental and African Studies, 20 (1957), pp. 367 88. 'The internal structure of the Saljuq empire', in The Cambridge history of Iran, vol. V,

pp. 203 82.

State and government in medieval Islam: An introduction to the study of Islamic political theory:

The jurists, London Oriental Series, 36, Oxford, 1981.

Mercil, Erdogan, Kirman Selcuklan, Istanbul, 1980.

Minorsky, Vladimir F., Studies in Caucasian history. I. New light cm the Shaddadids of Ganja.

II. The Shaddadids of Ani. III. The prehistory of Saladin, London, 1953. Nazim, Muhammad, The life and times of Sultan Mahmud of Ghazna, Cambridge, 1931.

Pritsak, Omeljan, 'Von den Karluk zu den Karachaniden', Zeitschrift der Deutschen

Morgenldndischen Gesellschaft, 101 (1951), pp. 270 300.

'Der Untergang des Reiches des Oguzischen Yabgu', in 60. dogum ydx miinasebetiyle Fuad

Koprulii armagan/ Melanges Fuad Koprulii, Istanbul, 1953, pp. 397 410. 'Die Karachaniden', Der Islam, 31 (1953), pp. 17 68.

Sanaullah, Mawlawi Fadil, The decline of the Saljuqid empire, Calcutta, 1938.

Sevim, Ali, and C. Edmund Bosworth, 'The Seljuqs and the Khwarazm Shahs', in

UNESCO, History of civilizations of Central Asia, vol. IV, part 1, Paris, 1998.

pp. 145 75-

2 The early expansion of Islam in India Andre Wink

Practical suggestions for further reading

Arab conquests, rule and economic life in Zabul, Kabul, Makran and Sind; early trade in the Indian Ocean

Watson, A., Agricultural innovation in the early Islamic world: The diffusion of crops and farming

techniques, 700 1100, Cambridge, 1983.

Wink, A., Al Hind: The making of the Indo Islamic world, vol. I: Early medieval India and the

expansion of Islam, jth nth centuries, Leiden, 1990.

India and Central Asia; post nomadic empires Gommans, J.J. L., 'The silent frontier of South Asia, c. AD 1000 1800', Journal of World

History, 9, 1 (1998), pp. 123.

Wink, A., Al Hind: The making of the Indo Islamic world, vol. Ill: Indo Islamic society, 14th 15th

centuries, Leiden, 2004; and Wink, vol. II.

Ghaznavids in India

Bosworth, C. E., The Ghaznavids: Their empire in Afghanistan and eastern Iran, 994 1040,

Edinburgh, 1963.

The later Ghaznavids: Splendour and decay: The dynasty in Afghanistan and northern India,

iojo 1186, Edinburgh, 1977.

Wink, A., Al Hind: The making of the Indo Islamic world, vol. II: The slave kings and the Islamic

conquest of India, nth 13th centuries, Leiden, 1997.

623

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

## **Bibliography**

#### Ghurids

Wink, A., Al Hind: The making of the Indo Islamic world, vol. II: The slave kings and the Islamic

conquest of India, uth 13th centuries, Leiden, 1997.

### Primary sources

Arab conquests, rule and economic life in Zabul, Kabul, Makran and Sind;

early trade in the Indian Ocean

al Baladhun, Futuh al buldan, Cairo, 1932.

Daudpota, U. M. (ed.), Chachnama, Hyderabad, 1939.

al Mas'udi, Muruj al dhahab, 2 vols., Cairo, 1948.

al Mugaddasi, Descriptio imperii moslemici, Leiden, 1906.

#### Ghaznavids

Morley, W. H. (ed.), Ta'rikh i Baihaqi, Calcutta, 1862. al 'Utbi, Tarxkh al Yammi, Delhi, 1847.

### Ghurids

Lees, N. (ed.), Tabaqat i Nasin of Abu 'Umar aljuzjani, Calcutta, 1894; ed. 'A. Habibi.

Tabagat i Nasin, 2 vols., 2nd edn, Kabul, 1964 5.

### Secondary sources

Arab conquests, rule and economic life in Zabul, Kabul, Makran and Sind;

early trade in the Indian Ocean

Mishra, Y., The Hindu Sahis of Afghanistan and the Punjab, AD 865 1026, Patna, 1972.

Misra, S. C., Muslim communities in Gujarat, Baroda, 1964.

3 Muslim India: The Delhi sultanate Peter Jackson

Practical suggestions for further reading

Eaton, Richard M., The rise of Islam, and the Bengal frontier, 1204 ij6o, Berkeley and Los

Angeles, 1993.

Habib, Mohammad and Nizami, Khaliq Ahmad (eds.), A comprehensive history of India,

vol. V: The Delhi Sultanate AD 1206 1526, New Delhi, 1970.

Habibullah, A. B. M., The foundation of Muslim rule in India, 2nd edn, Allahabad, 1961.

Hardy, Peter, Historians of medieval India: Studies in Indo Muslim historical writing, London,

i960, repr., with new preface, New Delhi, 1997. Husain, Agha Mahdi, Tughluq dynasty, Calcutta, 1963.

Jackson, Peter, The Delhi sultanate: A political and military history, Cambridge, 1999.

Khan, Iqtidar Alam, Gunpowder and firearms: Warfare in medieval India, Oxford and Delhi,

#### 2004.

Lai, Kishori Saran, A history of the Khaljis AD 1290 1320, 3rd edn, Delhi, 1980

Twilight of the sultanate, 3rd edn, New Delhi, 1980.

624

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Wink, Andre, Al Hind: The making of the Indo Islamic world, vol. II: The slave kings and the

Islamic conquest of India, uth ytfi centuries, Leiden, 1997.

Al Hind: The making of the Indo Islamic world, vol. Ill: Indo Islamic society, 14th iflh centuries, Leiden, 2004.

Primary sources (including epigraphy and numismatics)

'Afif, Shams i Siraj, Tarxkh i Firuzshahi, ed. Maulavi Vilayat Hosain, Calcutta, 1891.

Amir Hasan Dihlawi, Fawa'id alfu'ad, ed. Muhammad Latif Malik, Lahore, AH 1386.

Amir Khusraw Dihlawi, Rasd'il al i'jaz, lithograph edn, 5 vols, in 2, Lucknow, 1876.

Tughlua nama, ed. Sayyid Hashimi Fandabadi, Aurangabad, 1933.

Nuh sipihr, ed. Muhammad Wahid Mirza, London, 1950.

KhazaHn alfutuh, ed. Muhammad Wahid Mirza, Calcutta, 1953.

Miftah alfutuh, ed. Shaikh Abdur Rashid, Aligarh, 1954.

Diwal Ram yi Khadir Khan, ed. Rashid Ahmad Salim Ansan, Aligarh, AH 1336.

Qiran al sa'dayn, ed. Maulavi Muhammad Isma'il and Sayyid Hasan Baram, Aligarh, AH 1337.

Babur, Zahir al Dm Muhammad, Babur nama, trans. Annette S. Beveridge, The Babur nama

in English, 2 vols., London, 1921 2; repr. in 1 vol., 1969. Baram, Diya yi, Tarxkh i Firuzshahi, ed. Saiyid Ahmad Khan, Calcutta, 1861 2.

Fatawa yijdhandan, ed. Afsar Saleem Khan, Lahore, 1972. Bihamadkham, Muhammad, Tarikh i Muhammadi, British Library ms. Or. 137; partial trans.

by Muhammad Zaki, Aligarh, 1972.

Desai, Ziyaud din A. (ed.), A topographical list of Arabic, Persian and Urdu inscriptions of south

India, New Delhi, 1989.

(ed.), Arabic, Persian and Urdu inscriptions of west India: A topographical list, New Delhi,

1999-

Fakhr i Mudabbir, Shajarat [or Bahr] al ansab, partial edn by Sir E. Denison Ross as Ta'rikh

[sic] i Fakhr al Din Mubdrakshdh, London, 1927.

Firishta (Muhammad Qasim Hindushah Astarabadi), Gulshan i Ibrahimi, lithograph edn,

2 vols., Bombay, AH 1247.

Firuz Shah (Sultan), Futuhat Firuzshahi, ed. Shaikh Abdur Rashid, Aligarh, 1954.

Hafiz i Abru, Zubdat al tawarikh, ed. Sayyid Kamal Haj Sayyid Jawadi, 2 vols., Tehran, AH

solar 1372.

Hamid Qalandar, Khayr al majalis, ed. Khaliq Ahmad Nizami, Aligarh, [1959].

Hasan i Nizami, Taj al ma'athir, India Office ms. 15 (Ethe, Catalogue, no. 210).

Ibn Battuta, Tuhfat al nuzzar, ed. Ch. Defremery and B. R. Sanguinetti, 4 vols. Paris, 1853 8;

trans. H. A. R. Gibb and C. F. Beckingham, The travels of Ibn Battuta AD 132} 1354,

5 vols., Hakluyt Society, Cambridge and London, 1958 2000. Ibn Fadl allah al 'Uman, Masalik al absarfi mamalik al amsar, partial edn by Otto Spies, Ibn

Fadlallah al 'Oman's Bericht iiber Indien, Leipzig, 1943, and trans. Iqtidar Husain Siddiqi

and Qazi Muhammad Ahmad, A fourteenth century Arab account of India under Sultan

Muhammad bin Tughlaq, Aligarh, [1975]; partial edn by Klaus Lech, Das mongolische

Weltreich, Asiatische Forschungen, 22, Wiesbaden, 1968. Ibn Mahru, Ayn al Mulk Abd allah b. Muhammad, Insha yi Mahru, ed. Shaikh Abdur

Rashid, Lahore, 1965.

625

Cambridge Histories Online © Cambridge University Press, 201 1

# Bibliography

'Isami, Futuk al salatin, ed. A. S. Usha, Madras, 1948; trans. A. M. Husain, 3 vols., Aligarh,

1967 77-

Jazan, Shams al Din Muhammad, Hawadith al zaman, ed. Abd al Salam Tadmun, 3 vols.,

Beirut AH 1419.

Juwayni, Ala' al Dm Ata Malik, Tarikh i jahan gusha, ed. Mirza Muhammad Qazwim,

3 vols., Gibb Memorial Series XVI, Leiden, 1912 37; trans. John Andrew Boyle, The

history of the world conqueror, 2 vols., Manchester, 1958, repr. in 1 vol., 1997.

Juzjani, Minhaj i Siraj, Tabaqat i Nasin, ed. Abd al Hayy Habibi, 2nd edn, 2 vols., Kabul,

AH solar 1342 3.

Kuf 1, 'All b. Hamid b. Abi Bakr, Chach nama, ed. N. A. Baloch as Fathnamah i Sind,

Islamabad, AH 1403.

Mir i Khwurd (Muhammad b. Mubarak Kirmam), Siyar al awliya', lithograph edn, Delhi,

AH 1302.

Prasad, Pushpa (ed.), Sanskrit inscriptions of Delhi sultanate 1191 1526, Oxford and Delhi, 1990.

Rashid al Din Fadl allah al Hamadam, Jami' al tawankh, partial edn and trans, by Karl Jahn,

Die Indiengeschichte des Rasid ad Din, 2nd edn, Vienna, 1980. Shabankara'i, Muhammad b. 'All, Majma' al ansab, ed. Mir Hashim Muhaddith, Tehran,

AH solar 1363.

Shami, Nizam i, Zafar nama, ed. Felix Tauer, Histoire des conquetes de Tamerlan, 2 vols.,

Monografie Archivu Orientalniho, 5, Prague, 1937 58. Shokoohy, Mehrdad (ed.), Rajasthan I, Corpus inscriptionum Iranicarum, part IV: Persian

inscriptions down to the early Safavid period, 49, London, 1986. (ed.), Haryana I, Corpus inscriptionum Iranicarum, part IV: Persian inscriptions down to

the early Safavid period, 47, London, 1988.

Sirat i Firuzshahi, School of Oriental and African Studies ms. 283116 (copy of ms. in

Bankipore Library, Patna).

Sirhindi, Yahya' ibn Ahmad, Tarikh i Mubarakshahi, ed. S. M. Hidayat Hosain, Calcutta, 1931.

Thomas, Edward, Chronicles of the Pathan kings of Delhi, Delhi, 1871. Willis, Michael D. (ed.), Inscriptions of Gopaksetra: Materials for the history of central India,

London, 1996.

Wright, H. Nelson, The coinage and metrology of the Sultans of Delhi, Delhi, 1936; repr.

New Delhi, 1974.

Yazdi, Ghiyath al Dm All, Ruz nama yi ghazawat i Hindustan, trans. A. A. Semenov,

Dnevnik pokhoda Timura v Indiiu, Moscow, 1958.

Secondary sources

Ahmad, Aziz, 'The early Turkish nucleus in India', Turcica, 9 (1977), pp. 99 109.

Aubin, Jean, 'L'ethnogenese des Qaraunas', Turcica, 1 (1969), pp. 65 94.

Biran, Michal, Qaidu and the rise of the independent Mongol state in Central Asia, Richmond,

1997.

Chakravarti, Ranabir, 'Horse trade and piracy at Tana (Thana, Maharashtra, India):

Gleanings from Marco Polo', Journal of the Economic and Social History of the Orient,

34 (1991), PP- 159 82.

Chattopadhyaya, Brajadulal, Representing the Other? Sanskrit sources and the Muslims (eighth

to fourteenth century), New Delhi, 1998.

626

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

Conermann, Stephan, Die Beschreibung Indiens in der 'Rihla' des Ibn Battuta: Aspekte einer

herrschaftssoziohgischen Einordnung des Delhi Sidtanates unter Muhammad Ibn Tugluq,

Islamkundliche Untersuchungen, 165, Berlin, 1993. Dani, Ahmad Hasan, 'Shamsuddin Ilyas Shah, Shah i Bangalah', in Hari Ram Gupta et al. (eds.), Essays presented to Sirjadunath Sarkar, 2 vols., Hoshiarpur, 1958, vol. II, pp. 50 8.

Day, U. N., The government of the sultanate, 2nd edn, New Delhi, 1993. Deyell, John S., Living without silver: The monetary history of early medieval north India, Oxford

and Delhi, 1990.

Digby, Simon, War horse and elephant in the Delhi sultanate: A study of military supplies,

Oxford and Delhi, 1971.

'The currency system', in Raychaudhuri and Habib (eds.), The Cambridge economic history

of India, vol. I, pp. 93 101.

'The sufi shaykh and the sultan: A conflict of claims to authority in medieval India', Iran,

28 (1990), pp. 71 81.

'Before Timur came: Provincialization of the Delhi sultanate through the fourteenth

century', Journal of the Economic and Social History of the Orient, 47 (2004), pp. 298 356.

Eaton, Richard Maxwell, Sufis of Bijapur 1300 1700: Social roles of sufis in medieval India.

Princeton, 1978.

'Temple desecration and Indo Muslim states', Journal of Islamic Studies, 11 (2000),

pp. 283 319; repr. in Gilmartin and Lawrence (eds.), Beyond Turk and Hindu, pp. 246 81.

Ernst, Carl W., Eternal garden: Mysticism, history and politics at a South Asian Sufi center,

Albany, 1992.

Frykenberg, Robert E. (ed.), Delhi through the ages: Essays in urban history, culture and society,

Oxford and Delhi, 1986.

Gilmartin, David and Lawrence, Bruce B. (eds.), Beyond Turk and Hindu: Rethinking religious

identities in Islamicate South Asia, Gainesville, FL, 2000. Gommans, Jos, 'The silent frontier of South Asia, c. AD 1100 1800', Journal of World History,

9 (1998), pp. 123.

'Warhorse and gunpowder in India c. 1000 1850', in Jeremy Black (ed.), War in the early

modern world, London, 1999, pp. 105 27.

Habib, Irfan, 'Economic history of the Delhi sultanate an essay in interpretation', Indian

Historical Review, 4 (1977), pp. 287 303.

'Baram's theory of the history of the Delhi sultanate', Indian Historical Review, 7 (1980 1),

pp. 99 ii5-

'Agrarian economy', in Raychaudhuri and Habib (eds.), The Cambridge economic history of

India, vol. I, pp. 48 76.

'The price regulations of 'Ala'uddm Khalji a defence of Zia' Baram', Indian Economic

and Social History Review, 21 (1984), pp. 393 414.

'Formation of the sultanate ruling class of the thirteenth century', in Irfan Habib (ed.),

Medieval India 1: Researches in the history of India 1200 iy;o, Oxford and Delhi, 1992,

pp. 121.

Hambly, Gavin R. G., 'Twilight of Tughluqid Delhi', in Frykenberg, Delhi through the ages,

pp. 47 56-

Hardy, Peter, 'The growth of authority over a conquered political elite: The early Delhi

sultanate as a possible case study', in John S. Richards (ed.), Kingship and authority in

South Asia, Madison, WI, 1978, pp. 192 214.

627

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

## **Bibliography**

'The authority of mediaeval Muslim kings in South Asia', in Marc Gaborieau (ed.), Islam

et societe en Asie du Sud, Collection Purusarthe, 9, Paris, 1986, pp. 37 55.

Hodivala, S. H., Studies in Indo Muslim history, 2 vols., Bombay, 1939 57.

Husain, Agha Mahdi, The rise and fall of Muhammad bin Tughluq, Calcutta, 1938.

Islam, Zafarul, 'The Fatawa Firuz Shahi as a source for the socio economic history of the

sultanate period', Islamic Culture, 60 (1986), part 2, pp. 97 117.

'Firuz Shah's attitude towards non Muslims a reappraisal', Islamic Culture, 64 (1990),

part 4, pp. 65 79-

Jackson, Peter, 'The Mongols and the Delhi sultanate in the reign of Muhammad Tughlug

(1325 1351)', Central Asiatic Journal, 19 (1975), pp. 118 57.

'Delhi: The problem of a vast military encampment', in Frykenberg, Delhi through the

ages, pp. 18 33-

'Jalal al Dm, the Mongols and the Khwarazmian conquest of the Panjab and Sind', Iran,

28 (1990), pp. 45 54-

'The Mamluk institution in early Muslim India', Journal of the Royal Asiatic Society (1990),

pp. 340 58.

'The fall of the Ghurid dynasty', in Carole Hillenbrand (ed.), Studies in honour of Clifford

Edmund Bosworth, vol. II: The sultan's turret: Studies in Persian and Turkish culture,

Leiden, 2000, pp. 207 37.

Jahn, Karl, 'Zum Problem der mongolischen Eroberungen in Indien (13. 14. Jahrhundert)'.

in Akten des XXIV. internationalen Orientalisten Kongresses

Miinchen . . . 195J, Wiesbaden,

1959, PP-617 19-

Khan, IqtidarAlam, 'Origin and development of gunpowder technology in India: AD

1250 1500', Indian Historical Review, 4 (1977 8), pp. 20 9.

'The coming of gunpowder to the Islamic world and north India: Spotlight on the role of

the Mongols', Journal of Asian History, 30 (1996), pp. 27 45.

'The role of the Mongols in the introduction of gunpowder and firearms in South Asia',

in Brenda J. Buchanan (ed.), Gunpowder: The history of an international technology, Bath,

1996, pp. 33 44-

Khuhro, Hamida (ed.), Sind through the centuries, Oxford and Karachi, 1981.

Moreland, W. H., The agrarian system of Moslem India, Cambridge, 1929.

Naqvi, Hamida Khatoon, Agricultural, industrial and urban dynamism under the sultans of Delhi

1206 1555, New Delhi, 1986.

Nizami, Khaliq Ahmad, Some aspects of religion and politics in India in the thirteenth century,

Aligarh, 1961.

On history and historians of medieval India, New Delhi, 1983.

Raychaudhuri, Tapan and Habib, Irfan (eds.), The Cambridge economic history of India, vol. I:

c.1200 C.IJ50, Cambridge, 1982.

Siddiqi, Iqtidar Husain, Some aspects of Afghan despotism in India, Aligarh, 1969.

'Wajh i Ma'ash grants under the Afghan kings (1451 1555)', Medieval India: A Miscellany,

2 (1972), PP- 19 44-

'The Qarlugh kingdom in northwestern India during the thirteenth century', Islamic

Culture, 54 (1980), pp. 75 91.

'The Afghans and their emergence in India as ruling elite during the Delhi sultanate

period', Central Asiatic Journal, 26 (1982), pp. 241 61.

628

Cambridge Histories Online © Cambridge University Press, 201 1

**Bibliography** 

'Politics and conditions in the territories under the occupation of Central Asian rulers in

north western India 13th and 14th centuries', Central Asiatic Journal, 27 (1983), pp. 288 306.

'Sultan Muhammad bin Tughluq's foreign policy: A reappraisal', Islamic Culture, 62

(1988), part 4, pp. 1 22.

Perso Arabic sources of information on the lives and conditions in the sultanate of Delhi,

New Delhi, 1992.

(ed.), Medieval India I: Essays in intellectual thought and culture, New Delhi, 2003.

Talbot, Cynthia, 'Inscribing the Other, inscribing the self: Hindu Muslim identities in pre

colonial India', Comparative Studies in Society and History, 37 (1995), pp. 692 722.

Venkata Ramanayya, N., 'The date of the rebellions of Tilang and Kampila against Sultan

Muhammad bin Tughlaq', Indian Culture, 5 (1938 9), pp. 135 46, 261 9. Venkataramanyya, N., The early Muslim expansion in south India, Madras, 1942.

Verma, H. C, Dynamics of urban life in pre Mughal India, New Delhi, 1986.

Welch, Anthony and Crane, Howard, 'The Tughluqs: Master builders of the Delhi

sultanate', Mugarnas, 1 (1983), pp. 123 66.

4 The rule of the infidels: the Mongols and the Islamic world Beatrice Forbes Manz

Practical suggestions for further reading

Aigle, Denise, he Fars sous la domination mongole: Politique etfiscalite (Xllle XlVe s.), Paris,

2005.

Allsen, Thomas, Mongol imperialism: The policies of the Grand Qan Mongke in China, Russia

and the Islamic lands, 1251 1259, Berkeley, 1987.

Culture and conquest in Mongol Eurasia, Cambridge, 2001.

Amitai Preiss, Reuven and Morgan, David O. (eds.), The Mongol empire and its legacy,

Leiden, 1999.

Carboni, Stefano and Komaroff, Linda (eds.), The legacy of Genghis Khan: Courtly art and

culture in western Asia, 1256 1353, New York, 2002.

Jackson, Peter, The Mongols and the West, 1221 1410, Harlow, 2005. Komaroff, Linda (ed.), Beyond the legacy of Genghis Khan, Leiden, 2006. Lane, George, Early Mongol rule in thirteenth century Iran, London, 2003.

Morgan, David, The Mongols, Oxford, 1986; 2nd edn 2007. Raby, Julian and Fitzherbert, Teresa, eds., The court of the II khans 1290 1340, Oxford, 1996.

### Primary sources

Bar Hebraeus, Gregorius Abu'l Faraj, trans. E. A. Wallis Budge, The chronography of

Gregory Abu'l Faraj ... commonly known as Bar Hebraeus, 2 vols., Oxford and London,

1932.

Fasih Khwaf 1, Ahmad b. Jalal al Din, Mujmal i fasxhx, ed. Muhammad Farrukh, 3 vols.,

Mashhad, AH solar 1339.

Hafiz i Abru, Dhayl ijami' al tawarxkh, ed. K. Bayani, Tehran, 1971. al Harawi, Sayf b. Muhammad b. Ya'qub (Sayf 1), Tarikh nama i Harat, ed. Muhammad

Zubayr al Siddigi, Calcutta, 1944.

629

Cambridge Histories Online © Cambridge University Press, 201 1

#### Bibliography

Ibn Battuta, Shams al Din, The travels of Ibn Battuta, AD 1325 1354, trans. H. A. R. Gibb,

3 vols., Hakluyt Society, 5 vols., Cambridge, 1958 2000.

Juwayni, 'Ala' al Dm 'Ata Malik, Tankh i jahan gusha, ed. Mirza Muhammad Qazwmi,

3 vols., Gibb Memorial Series XVI, Leiden, 1912 37.

The history of the world conqueror, trans. John A. Boyle, 2 vols., Manchester, 1958.

Men da Bei hi ('Polnoe opisanie Mongolo Tatar'), ed. and trans. N. Ts. Munkuev, Moscow,

1975-

Mustawf 1 Qazwim, Hamd Allah, The geographical part of the Nuzhat al qulub composed by

Hamd Allah Mustawf \ of Qazwvn in 140 (1340), ed. and trans. G. Le Strange, Gibb

Memorial Series, London, 1915 18.

Qasham, Abu'l Qasim, Tarikh i Uljaytu, ed. Mahin Hambly, Tehran, 1969. Rashid al Din Hamadam, Jami' al tawarikh, ed. A. Ali zade, 3 vols., Moscow, 1968 80.

trans. J. A. Boyle, The successors of Genghis Khan, New York, 1971. Jami' al tawankh: Compendium of chronicles: A history of the Mongols, trans. Wheeler

Thackston, 3 vols., Sources of Oriental Languages and Literatures, Harvard

University, Cambridge, MA, 1998 9.

ed. Muhammad Rawshan, Mustafa Musawi, 4 vols., Tehran, AH solar 1373.

al 'Umari, Das mongolische WeUreich. Al 'Umans Darstellung der mongolischen Reiche in seinem

Werk Masalik al absarfi mamalik al amsar, ed. and trans. K. Lech, Wiesbaden, 1968.

Wassaf Abd Allah b. Fadl Allah, Tajziyat al amsar wa tazjiyat al a'sar (Tarxkh i Wassaf,

Bombay, 1852 3, repr. Tehran, AH 1338.

## Secondary sources

Aigle, Denise, (ed.), L'Iranface a la domination mongole, Biblioteque Iranienne 45, Tehran, 1997.

'Le grand jasaq de Gengis Khan, l'empire, la culture mongole et la shan 'a ', Journal of the

Economic and Social History of the Orient, 47, 1 (2004), pp. 31 79.

Allsen, Thomas T., 'Mongolian princes and their merchant partners, 1200 1260', Asia Major,

3rd ser., 2 (1989), pp. 83 126.

'Changing forms of legitimation in Mongol Iran', in Gary Seaman and Daniel Marks

(eds.), Rulers from the steppe: State formation and the Eurasian periphery, Ethnographies

Monograph Series, 2, Los Angeles, 1991, pp. 223 41.

'Notes on Chinese titles in Mongol Iran', Mongolian Studies, 14 (1991), pp. 27 39.

'The rise of the Mongolian empire and Mongolian rule in north China', in Herbert

Franke and Denis Twitchett (eds.), Cambridge history of China, vol. VI, Cambridge,

1994, PP- 321 413-

'Biography of a cultural broker, Bolad Ch'eng Hsiang in China and Iran', in Raby and

Fitzherbert (eds.), The court of the II khans, pp. 7 22.

'Spiritual geography and political legitimacy in the eastern steppe', in Henri

J. M. Claessen and Jarich G. Oosten (eds.), Ideology and the formation of early states,

Leiden, 1996, pp. 116 35.

Commodity and exchange in the Mongol empire: A cultural history of Islamic textiles,

Cambridge, 1997.

'Ever closer encounters: The appropriation of culture and the apportionment of peoples

in the Mongol empire', Journal of Early Modern History, 1, 1 (1997), pp. 2 23.

630

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

'Sharing out the empire: Apportioned lands under the Mongols,' in A. Wink and

A. Khazanov (eds.), Nomads in the sedentary world, Richmond, 2001, pp. 172 90.

Amitai, Reuven, 'Ghazan, Islam and Mongol tradition: A view from the Mamluk

sultanate', Bulletin of rfie School of Oriental and African Studies, 59, 1 (1996),

pp. 1 10.

'Sufis and shamans: Some remarks on the Islamization of the Mongols in the Ilkhanate',

Journal of the Economic and Social History of the Orient, 42 (1999), pp. 27 46.

Amitai, Reuven and Biran, Michal (eds.), Mongols, Turks, and others: Eurasian nomads and the

sedentary world, Leiden, 2005.

Amitai Preiss, Reuven, Mongols and Mamluks: The Mamluk Ilkhanid war, 1260 1281

Cambridge, 1995.

Aubin, Jean, 'Les princes d'Ormuz du XHIe au XVe siecle', Journal Asiatique, 241 (1953), pp. 77 137.

'L'ethnogenese des Qaraunas', Turcica, 1 (1969), pp. 65 94.

'Reseau pastoral et reseau caravanier: Les grand' routes du Khurassan a l'epoque mon

gole', he Monde Iranien et ITslam, 1 (1971), pp. 105 30.

'Le khanat de Cagatai et le Khorassan (1334 1380)', Turcica, 8, 2 (1976), pp. 16 60.

'La propriete fonciere en Azerbaydjan sous les Mongols', Le Monde Iranien et ITslam,

4 (1976 7), pp. 79 132.

'Le quriltai de Sultan Maydan (1336)', Journal Asiatique, 279 (1991), pp. 175 97.

Emirs mongols et vizirs persans dans les remous de I 'acculturation, Cahiers de Studia Iranica,

Paris, 1995.

Ayalon, David, 'The great Yasa of Chingiz Khan: A reexamination', A, Studia Islamica, 33 (1971),

pp. 97 140, B, 34 (1971), pp. 151 80, C(i), 36 (1972), pp. 113 58, C(2), 38 (1973), pp. 107 56-

Barthold, W., Turkestan down to the Mongol invasion, London, 1968.

Biran, Michal, Qaidu and the rise of the independent Mongol state in Central Asia, Richmond, 1997-

'The battle of Herat (1270): A case of inter Mongol warfare', in Nicola Di Cosmo (ed.),

Warfare in Inner Asian history (yoo 1800), Leiden, 2002, pp. 175 219. 'The Chaghadaids and Islam: The conversion of Tarmashirin Khan (1331 34)', Journal of

the American Oriental Society, 122, 4 (2002), pp. 742 52.

Blair, Sheila S., 'Calligraphers, illuminators, and painters in the Ilkhanid scriptorium', in

Komaroff (ed.), Beyond the legacy, pp. 167 82.

Boyle, John A., 'Dynastic and political history of the 11 Khans', in Cambridge history of Iran,

vol. V, Cambridge, 1968, pp. 303 421.

Buell, Paul D., 'Tribe, "Qan" and "ulus" in early Mongol China: Some prolegomena to Yuan

history', Ph.D. thesis, University of Washington, 1977.

'Sino Khitan administration in Mongol Bukhara', Journal of Asian History, 13, 2 (1979),

pp. 121 47.

Early Mongol expansion in western Siberia and Turkestan (1207 1219): A reconstruc

tion', Central Asiatic Journal, 36, 12 (1992), pp. 132.

Cahen, Claude, The formation of Turkey: The Seljukid Sultanate of Rum: Eleventh to fourteenth

century, trans. P. M. Holt, Harlow 2001.

Carboni, Stefano, 'Synthesis: Continuity and innovation in Ilkhanid art', in Carboni and

Kamaroff (eds.), Legacy, pp. 196 225.

631

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

DeWeese, Devin, Islamization and native religion in the Golden Horde: Baba Tiikles and

conversion to Islam in historical and epic tradition, University Park, PA, 1994.

Dillon, Michael, China's Muslim Hui community: Migration, settlement and sects,

Richmond, 1999.

Endicott West, Elizabeth, 'Merchant associations in Yuan China: The ortogh', Asia Major,

3rd ser., 2 (1989), pp. 127 54.

Fedorov Davydov, G. A., Obshchestvennyi strox Zolotox Ordy, Moscow, 1973.

Fletcher, Joseph, 'The Mongols: Ecological and social perspectives', Harvard Journal of

Asiatic Studies, 46 (1986), pp. 11 50.

Fragner, Bert, 'Ilkhanid rule and its contributions to Iranian political culture', in Komaroff

(ed.), Beyond the legacy, pp. 68 80.

Hillenbrand, Robert, 'The arts of the book in Ilkhanid Iran', in Carboni and Komaroff

(eds.), Legacy, pp. 134 67.

Hoffmann, Birgitt, 'The gates of piety and charity: Rasid al Din Fadl Allah as founder of

pious endowments', in Aigle (ed.), L'Iran, pp. 189 201.

Waqf im mongolischen Iran. Rasxduddxns Sorge um Nachruhm und Seelenheil, Freiburger

Islamstudien, 20, Stuttgart, 2000.

Hsiao, Ch'i ch'ing, The military establishment of the Yuan dynasty, Harvard East Asian

Monographs, 77, Cambridge, MA, 1978.

Jackson, Peter, 'The Mongols and the Delhi sultanate in the reign of Muhammad Tughluq

(1325 1351)', Central Asiatic Journal, 19, 1 2 (1975), pp. 118 57.

'The dissolution of the Mongol empire', Central Asiatic Journal, 22 (1978), pp. 186 243.

'From ulus to khanate: The making of the Mongol states c. 1220 c. 1290', in Amitai Preiss

and Morgan (eds.), Mongol empire, pp. 12 38.

Kato, Kazuhide, 'Kebek and Yasawr: The establishment of the Chaghatai Khanate', Memoirs

of the Research Department of the Toyo Bunko, 49 (1991), pp. 97 118. Kempiners, Russell G., 'Vassafs Tajziyat alamsar wa tazjiyat ala'sar as a source for the

history of the Chaghadayid khanate', Journal of Asian History, 22, 2 (1988), pp. 160 87.

Kim, Ho Dong, 'The early history of the Moghul nomads: The legacy of the Chaghatai

khanate', in Amitai Preiss and Morgan (eds.), Mongol empire, pp. 290 318.

A reappraisal of Gtiytig Khan', in Amitai and Biran, Mongols, Turks, and others,

pp. 309 38.

Krawulsky, Dorothea, Iran Das Reich der Ilhane. Eine topographisch historische Studie,

Beihefte zum Tiibinger Atlas des vorderen Orients, ser. B 17, Wiesbaden, 1978.

Mongolen und Rkhdne Ideologic und Geschichte: 5 Studien, Beirut, 1989. Lambton, Ann K. S., 'Mongol fiscal administration in Persia', part I, Studia Islamica, 64

(1986), pp. 79 99, part II, Studia Islamica, 65 (1987), pp. 97 123. Continuity and change in medieval Persia: Aspects of administrative, economic and social

history, 11th 14th century, Columbia Lectures on Iranian Studies, 2, Albany, 1988.

Lane, George, Arghun Aqa: Mongol bureaucrat', Iranian Studies, 32, 4 (1999), pp. 459 82.

Leslie, Donald D., Islam in traditional China: A short history to 1800, Belconnen, 1986.

Liu, Yingsheng, 'War and peace between the Yuan dynasty and the Chaghadaid khanate

(1312 1323)', in Amitai and Biran (eds.), Mongols, Turks, and others, pp. 339 58.

Masuya, Tomoko, 'Ilkhanid courdy life', in Carboni and Komaroff (eds.), Legacy, pp. 74 103.

May, Timothy, A Mongol Isma'ili alliance?: Thoughts on the Mongols and Assassins',

Journal of the Royal Asiatic Society, ser. 3, 14, 3 (2004), pp. 231 9.

Cambridge Histories Online © Cambridge University Press, 201 1

## Bibliography

Melikian Chirvani, Assadullah Souren, 'Conscience du passe et resistance culturelle dans

l'Iran mongol', in Aigle (ed.), L'Iran, pp. 135 77.

Melville, Charles, 'Padshah i Islam: The conversion of Sultan Mahmud Ghazan Khan',

Pembroke Papers, 1 (1990), pp. 159 77.

"The year of the elephant": Mamluk Mongol rivalry in the Hejaz in the reign of

Abu Sa'id (1317 1335)', Studia Iranica, 21, 2 (1992), pp. 197 214. The fall of Amir Chupan and the decline of the Ilkhanate 1327 1337: A decade of discord in Iran,

Bloomington, IN, 1999.

'The Ilkhan Oljeitii's conquest of Gilan (1307): Rumour and reality', in Amitai Preiss and

Morgan (eds.), Mongol empire, pp. 73 125.

'The keshig in Iran: The survival of the royal Mongol household', in Komaroff (ed.),

Beyond the legacy, pp. 135 64.

Morgan, David O., 'Mongol or Persian: The government of Ilkhanid Iran', Harvard Middle

Eastern and Islamic Review, 3, 2 (1996), pp. 62 76.

'Rasid al Din and Gazan Khan', in Aigle (ed.), L'Iran, pp. 179 88.

'Reflections on Mongol communications in the Ilkhanate', in Carole Hillenbrand (ed.),

Studies in honour of Clifford Edmund Bosworth, vol. II: The sultan's turret: Studies in

Persian and Turkish culture, Leiden, 2000, pp. 375 85.

'The "Great yasa of Chinggis Khan" revisited', in Amitai and Biran (eds.), Mongols, Turks

and others, pp. 291 308.

Morton, A. H., 'The letters of Rashid al Din: Ilkhanid fact or Timurid fiction?', in Amitai

Preiss and Morgan (eds.), Mongol empire, pp. 155 99. O'Kane, Bernard, 'Persian poetry on Ilkhanid art and architecture', in Komaroff (ed.),

Beyond the legacy, pp. 346 54.

Paul, Jtirgen, 'L'invasion mongole comme "revelateur" de la societe iranienne', in Aigle

(ed.), L'Iran, pp. 37 53.

Paviot, Jacques, 'Les marchands italiens dans l'Iran mongol', in Aigle (ed.), L'Iran, pp. 71 86.

Petrushevskii, I. P., Zemledelie i agramye otnosheniia v Irane XIII XIV vekov, Moscow and

Leningrad, i960.

'The socio economic condition of Iran under the Ilkhans', in The Cambridge history of Iran,

vol. V, Cambridge, 1968, pp. 483 537.

'Pokhod mongol'skikh voisk v Sredniuiu Aziiu v 1219 1224 gg. i ego posledstviia', in

S. L. Tikhvinskii (ed.), Tataro Mongoly v Azii i Evrope, Moscow, 1970, pp. 100 33.

Pfeiffer, Judith, 'Conversion to Islam among the Ilkhans in Muslim narrative traditions: The

case of Ahmad Tegiider', Ph.D. dissertation, University of Chicago, 2003. Potter, Lawrence G., 'The Kart dynasty of Herat: Religion and politics in medieval Iran',

Ph.D. thesis, Columbia University, 1992.

Quade Reutter, Karin, '... denn sie haben einen unvollkommenen Verstand'. Herrschaftliche

Damen im Grossraum Iran in der Mongolen und Timuridenzeit (ca. 1250 i;oy), Aachen,

2003.

Rachewiltz, Igorde, 'The title Cinggis Qan/Qa'an re examined', in W. Heissig and Klaus

Sagaster (eds.), Gedanke und Wirking. Festschrift zum go. Geburtstag von Nikolaus Poppe,

Asiatische Forschungen, 108, Wiesbaden, 1989, pp. 281 98. Rachewiltz, Igorde, Hoklam Chan, Hsiao Ch'i ch'ing and Geier, Peter W. (eds.), In

tfie service of the khan: Eminent personalities of the early Mongol Yuan period,

Wiesbaden, 1993.

633

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Ratchnevsky, Paul, Genghis Khan, his life and legacy, trans, and ed. Thomas N. Haining,

Oxford, 1992.

Remler, Philip, 'New light on economic history from Ilkhanid accounting manuals', Studia

Iraniea 14, 2 (1985), pp. 157 77.

Richard, Jean, 'D'Aljigidai a Gazan: La continuite d'une politique franque chez les Mongols

d'Iran', in Aigle (ed.), L'Iran, pp. 57 69.

Rossabi, Morris, 'The Muslims in the early Yuan dynasty', in John D. Langlois (ed.), China

under Mongol rule, Princeton, 1981, pp. 257 95. Khubilai Khan: His life and times, London, 1988.

'The Mongols and their legacy', in Carboni and Komaroff (eds.), Legacy, pp. 12 35.

Togan, Isenbike, Flexibility and limitation in steppe formations: The Kerait khanate and Chinggis

Khan, Leiden, 1998.

Vasary, Istvan, "History and legend" in Berke Khan's conversion to Islam', in Aspects of

Altaic civilization III: Proceedings of the thirtieth meeting of the Permanent International

Altaistic Conference, Indiana University, Bloomington, Indiana, June 19 2j, 198J,

Bloomington, IN, 1990, pp. 230 52. Zerjal, Tatiana, Xue, Yali et ah, 'The genetic legacy of the Mongols', American Journal of

Human Genetics, 72 (2003), pp. 717 21.

5 Tamerlane and his descendants: from paladins

to patrons

Maria E. Subtelny

Practical suggestions for farther reading

Barthold, V. V., Four studies on the history of Central Asia, trans. V. Minorsky and T. Minorsky,

vol. II, Ulugh Beg; vol. Ill, Mir Ah Shir and A history of the Turkman people, Leiden, 1958 62.

Golombek, Lisa and Subtelny, Maria (eds.), Timurid art and culture: Iran and Central Asia in

the fifteenth century, Leiden, 1992.

Hodgson, Marshall G. S., The venture of Islam: Conscience and history in a world civilization,

vol. II: The expansion of Islam in the Middle Periods, Chicago, 1974. Jackson, Peter and Lockhart, Laurence (eds.), The Cambridge history of Iran. vol. VI: The

Timurid and Safavid periods, Cambridge, 1986. Lentz, Thomas W. andLowry, GlennD., Timur and the princely vision:

Lentz, Thomas W. andLowry, GlennD., Timur and the princely vision Persian art and culture

in the fifteenth century, Los Angeles, 1989. Manz, Beatrice Forbes, The rise and rule of Tamerlane, Cambridge, 1989.

Power, politics and religion in Timurid Iran, Cambridge, 2007. Morgan, David, Medieval Persia, 1040 1797, London, 1988.

Subtelny, Maria E., Timurids in transition: Turko Persian politics and acculturation in medieval

Iran, Leiden, 2007.

Primary sources

Album, Stephen, Sylloge of Islamic coins in the Ashmolean, vol. IX: Iran after the Mongol

invasion, Oxford, 2001.

Alisher Navoii, Mazholisun nafois, ed. Suiima Ghanieva, Tashkent, 1961. Asarlar, 15 vols., Tashkent, 1963 8.

634

Cambridge Histories Online © Cambridge University Press, 201 1

#### Bibliography

Mukammal asarlar tuplami, ed. K. Yashin et ah, 20 vols., Tashkent, 1987 2003.

'Ahshir Nawa'i, Majalis al nafa'is dar tadhkira i shu'ara' i qarn i nuhum i hijn, trans. Sultan

Muhammad Fakhri Harati and Hakim Shah Muhammad Qazwim, ed. 'All Asghar

Hikmat, Tehran, 1323, repr. 1363.

Babur, Zahir al Dm Muhammad, Baburnama (Vaqayi'), ed. Eiji Mano, 2 vols., Kyoto,

1995 6.

Clavijo, [Ruy Gonzalez de], Embassy to Tamerlane, 1403 1406, trans. Guy Le Strange,

London, 1928, repr. 2005.

Dawlatshah Samarqandi, Tadhkirat al shu'ara', ed. Edward G. Browne, London, 1901.

Fischel, WalterJ., Ibn Khaldun and Tamerlane: Their historic meeting in Damascus, 1401 AD

(803 AH): A study based on Arabic manuscripts of Ibn Khaldun's Autobiography', Berkeley

and Los Angeles, 1952.

Gross, Jo Ann and Urunbaev, Asom (eds. and trans.), The letters of Khwaja 'Ubayd Allah Ahrar

and his associates, Leiden, 2002.

Hafiz i Abru, Zubdat al tawarikh, ed. Sayyid Kamal Hajj Sayyidjawadi, 2 vols., Tehran, 1372.

Ibn Arabshah, Ahmad b. Muhammad, Aja'ib al maqdurfi nawa'ib Taymur, ed. Ahmad Fa'iz

al Himsi, Beirut, 1407.

Isfizan, Mu'in al Din Muhammad Zamchi, Rawdat aljannat ft awsaf madmat Harat, ed.

Sayyid Muhammad Kazim Imam, 2 vols., Tehran, 1338 9.

Jami, Nur al Dm Abd al Rahman b. Ahmad, Nafahat al uns min hadarat al guds, ed.

Mahmud Abidi, Tehran, 1370.

Diwan ijarm, ed. Ala Khan Afsahzad, 2 vols., Tehran, 1378.

Mathnawi i Haft awrang, ed. Jabilqadad Alishah et al., 2 vols., Tehran, 1378.

Khwandamir, Ghiyath al Din b. Humam al Dm, Dastur al wuzara', ed. Sa'id Naf isi,

Tehran, 1317, repr. 2535/1976.

Habib al siyarfi akhbar afrad i bashar, ed. Jalal al Dm Huma'i, 4 vols., Tehran, 1333, 3rd

repr. 1362.

Habibu's siyar: Tome three, trans. W. M. Thackston, Sources of Oriental Languages and

Literatures, 24, 2 parts, Cambridge, MA, 1994.

Krawulsky, Dorothea (ed. and trans.), Horasan zur Timuridenzeit nach dem Tarxh e Hafez e

Abru (verf. 817 823 h.), 2 vols., Wiesbaden, 1982 4.

Mu'izz alansabfi shajarat alansab, ms. Bibliotheque nationale de France, Ancien fonds

persan 67.

Mu'izz al ansab (Proslavliaiushchee genealogii), ed. and trans. Sh. Kh. Vokhidov, Alma Ata, 2006.

Natanzi, Mu'in ad Dm, Muntakhab al tawarikh i mu'mi, ed. Jean Aubin, Tehran, 1336.

Nawa'i, Abd al Husayn, Asnad wa mukatabat i tarxkhx i Iran: Az Timur ta Shah Isma'il,

Tehran, 2536/1977.

Qasim b. Yusuf Abu Nasn Harawi, Irshad al zira'a, ed. Muhammad Mushin, Tehran, 1346.

Roemer, Hans Robert, (ed. and trans.), Staatsschreiben der Timuridenzeit. Das Sarafnama des

Abdallah Marwand in kritischer Auswertung, Wiesbaden, 1952. (ed. and trans.), Sams al husn. Eine Chronik vom Tode Timurs bis zumjahre 1409 von Tag

as Salmanx, Wiesbaden, 1956.

Samarqandi, Kamal al Din Abd al Razzaq, Matla' i sa'dayn wa majma' i bahrayn, ed.

Muhammad Shafi', vol. II in 3 parts, Lahore, 1365 8. Sanders, J. H. (trans.), Tamerlane or Timur the Great Amir: From the Arabic life by Ahmed Ibn

Arabshah, London, 1936.

635

Cambridge Histories Online © Cambridge University Press, 201 1

#### Bibliography

Tauer, Felix, 'Continuation du Zafarnama de Nizamuddin Sami par Hafiz i Abru', Archiv

Orientdlni, 6 (1934), pp. 429 65.

(ed.)i Histoire des completes de Tamerlan, intitulee Zafarnama par Nizamuddin Sami, avec des

additions empruntees au Zubdatu t tawarih i Baysungun de Hafiz i Abru, 2 vols., Prague,

1937 56.

(ed.), Cinq opuscules de Hafiz i Abru concernant I'histoire de I'Iran au temps de Tamerlan,

Prague, 1959.

Thackston, Wheeler M. (trans, and ed.), The Babumama: Memoirs of Babur, prince and

emperor, New York, 1996.

'Uqayh, Sayfal DinHajji b. Nizam, Athar al wuzara', ed. Mir Jalal al Dm Husayni Urmawi

'Muhaddith', Tehran, 1337.

Urunbaev, A. (ed. and trans.), Pis'ma avtografy Abdarrakhmana Dzhami iz 'Al'boma Navoi',

Tashkent, 1982.

Yazdi, Sharaf al Dm 'All, Zafar natna: Tarikh i 'umumi mufassil i Iran dar dawra i Timuriyan,

ed. Muhammad 'Abbasi, 2 vols., [Tehran], 1336.

Secondary sources

Akimushkin, Oleg, etal., The arts of the book in Central Asia, 14th 16th centuries, ed. Basil Gray,

London, 1979.

Ando, Shiro, Titnuridische Emire nach dem Mu'izz al ansab.

Untersuchung zur Stamtnesaristokratie

Zentralasiens im 14. und 13. Jahrhundert, Berlin, 1992.

'Die timuridische Historiographie II. Saraf al dm 'All Yazdi', Studia Iranica, 24, 2 (1995),

pp. 219 46.

Aubin, Jean, 'Le mecenat timouride a Chiraz', Studia Islamica, 8 (1957), pp. 7188.

'Tamerlan a Bagdad', Arabica, 9 (1962), pp. 303 9.

'Comment Tamerlan prenait les villes', Studia Islamica, 19 (1963), pp. 83 122.

Barry, Michael, Figurative art in medieval Islam and the riddle of Bihzdd of Herat (1463 1535),

Paris, 2004.

Barthold, W., An historical geography of Iran, trans. Svat Soucek, ed. C. E. Bosworth,

Princeton, 1984.

Bartol'd, V. V., 'Mir Ali Shir i politicheskaia zhizn', in V. V. Bartol'd, Sochineniia, vol. II,

part 2, ed. Iu. E. Bregel, Moscow, 1964, pp. 199 260.

'O pogrebenii Timura', in V. V. Bartol'd, Sochineniia, vol. II, part 2, ed. Iu. E. Bregel',

Moscow, 1964, pp. 423 54.

'Ulugbek i ego vremia', in V. V. Bartol'd, Sochineniia, vol. II, part 2, ed. Iu. E. Bregel',

Moscow, 1964, pp. 25 196.

Bernardini, Michele (ed.), 'La civilta timuride come fenomeno internazionale', 2 vols.,

special issue, Oriente Moderno, n.s. 15, 2 (1996). Bertel's, Evgenii Eduardovich, Navoi i Dzhami, Moscow, 1965.

Birnbaum, Eleazar, 'The Ottomans and Chagatay literature: An early 16th century manuscript

of Nava'i's Dzvan in Ottoman orthography', Central Asiatic Journal, 20, 3 (1976), pp. 157 90.

Dale, Stephen F. 'The legacy of the Timurids', Journal of the Royal Asiatic Society, 3rd ser., 8, 1

(1998), PP- 43 58.

The garden of the eight paradises: Babur and the culture of empire in Central Asia, Afghanistan

and India (1483 1530), Leiden, 2004.

636

Cambridge Histories Online © Cambridge University Press, 201 1

# Bibliography

Doerfer, Gerhard, Tiirkische und mongolische Elemente im Neupersischen. Unter besonderer

Beriicksichtigung alterer neupersischer Geschichtsquellen, vox allem der Mongolen und

Timuridenzeit, 4 vols., Wiesbaden, 1963 75.

Fragner, Bert, 'Social and internal economic affairs', in The Cambridge history of Iran, vol. VI,

pp. 491 567-

Gabain, Annemarie von, 'Kasakentum, eine soziologisch philologische Studie', Acta Orientalia

Academiae Scientiarum Hungaricae, 11, 13 (i960), pp. 1617.

Golombek, Lisa, 'The gardens of Timur: New perspectives', Muqarnas, 12 (1995), pp. 137 47.

Golombek, Lisa, Mason, Robert B. and Bailey, Gauvin A., Tamerlane's tableware: A new approach

to the chinoiserie ceramics of fifteenth and sixteenth century Iran, Costa Mesa, CA, 1996.

Golombek, Lisa and Wilber, Donald, The Timurid architecture of Iran and Turan, 2 vols.,

Princeton, 1988.

Grupper, S. M., 'A Barillas family narrative in the Yuan Shih: Some neglected prosopo

graphical and institutional sources on Timurid origins', Archivum Eurasiae Medii Aevi, 8

(1992 4), pp- 11 97-

Kauz, Ralph, Politik und Handel zwischen Ming und Timuriden. China, Iran und Zentralasien im

Spatmittelalter, Wiesbaden, 2005.

Kennedy, E. S., 'The exact sciences in Timurid Iran', in The Cambridge history of Iran, vol. VI,

pp. 568 80.

Komaroff Linda, The golden disk of heaven: Metalwork of Timurid Iran, Costa Mesa, CA, 1992.

Levend, Agah Sirn, Ali Sir Nevai, 4 vols., Ankara, 1965 8.

McChesney, RobertD., Waqfin Central Asia: Four hundred years in the history of a Muslim

shrine, 1480 1889, Princeton, 1991.

Timur's tomb: Politics and commemoration, Central Eurasian Studies Lectures, 3,

Bloomington, IN, 2003.

'A note on the life and works of Ibn 'Arabshah', in Judith Pfeiffer and Sholeh A. Quinn

(eds.), History and historiography of post Mongol Central Asia and the Middle East: Studies

in honor of Professor John E. Woods, in collaboration with Ernest Tucker, Wiesbaden,

2006, pp. 205 49.

Mason, Robert B., 'The response I: Petrography and provenance of Timurid ceramics', in

Lisa Golombek, Robert B. Mason and Gauvin A. Bailey, Tamerlane's tableware: A new

approach to the chinoiserie ceramics of fifteenth and sixteenth century Iran, Costa Mesa,

CA, 1996, pp. 1646.

Misugi, T., Chinese porcelain collections in the Near East: Topkapi and Ardebil, 3 vols., Hong

Kong, 1981.

Mitchell, Colin Paul, 'To preserve and protect: Husayn Va'iz i Kashifi and Perso Islamic

chancellery culture', Iranian Studies, 36, 4 (2003), pp. 485 507. Necipoglu, Giilru, The Topkapi scroll geometry and ornament in Islamic architecture, Santa

Monica, 1995.

O'Kane, Bernard, Timurid architecture in Khurasan, Costa Mesa, CA, 1987.

'Poetry, geometry and the arabesque: Notes on Timurid aesthetics', Annales

Islamologiques, 26 (1992), pp. 63 78.

'From tents to pavilions: Royal mobility and Persian palace design', Ars Orientalis, 23

(i993), PP- 249 68.

Paul, Jiirgen, Die politische und soziale Bedeutung der Naqsbandiyya in Mittelasien im y.

Jahrhundert, Berlin, 1991.

637

Cambridge Histories Online © Cambridge University Press, 201 1

### Bibliography

Richard, Francis, 'Un temoignage inexploite concernant le mecenat d'Eskandar Soltan a

Esfahan', Oriente Moderno, n.s. 15, 2 (1996), vol. I, pp. 45 72. Roemer, H. R., 'The successors of Timur', in The Cambridge history of Iran, vol. VI, pp. 98 146.

'Timur in Iran', in The Cambridge history of Iran, vol. VI, pp. 42 97. Roxburgh, David J., The Persian album, 1400 1600: From dispersal to collection, New Haven,

2005.

Rypka, Jan, History of Iranian literature, ed. Karljahn, trans. P. van Popta Hope, Dordrecht,

1968.

Seguy, Marie Rose (ed.), The miraculous journey of Mahomet: 'Mirdj ndmeh', Bibliotheque

Nationale, Paris (Manuscrit Supplement Turc 190), trans. Richard Pevear, New York,

1977-

Soudavar, Abolala, Art of the Persian courts: Selections from the Art and History Trust collection,

New York, 1992.

Stori, Ch. A. [Storey, C. A.], Persidskaia literatura: Bio bibliograficheskii obzor, trans, and rev.

Iu. E. Bregel', 3 vols, Moscow, 1972.

Subtelny, Maria Eva, Ah Shir Nava'i: Bakhshi and beg, Harvard Ukrainian Studies, 3 4

(1979 80), part 2, pp. 797 807.

'Scenes from the literary life of Timurid Herat', in Logos islamikos: Studia islamica in

honorem Georgii Michaelis Wickens, ed. Roger M. Savory and Dionisius A. Agius,

Toronto, 1984, pp. 137 55.

'A taste for the intricate: The Persian poetry of the late Timurid period', Zeitschrift der

Deutschen Morgenlandischen Gesellschaft, 136, 1 (1986), pp. 56 79.

'Centralizing reform and its opponents in the late Timurid period', Iranian Studies, 21, 1 2

(1988), pp. 123 51.

'Socioeconomic bases of cultural patronage under the later Timurids', International

Journal of Middle East Studies, 20, 4 (1988), pp. 479 505.

'A Timurid educational and charitable foundation: The Ikhlasiyya complex of Ah Shir

Nava'i in 15th century Herat and its endowment', Journal of the American Oriental

Society, in, 1 (1991), pp. 38 61.

'The Vaqfiya of Mir Ah Sir Nava'i as apologia', Journal of Turkish Studies, 15 (1991), vol. II,

pp. 257 86.

A medieval Persian agricultural manual in context: The Irshad al zira'a in late Timurid

and early Safavid Khorasan', Studia Iranica, 22, 2 (1993), pp. 167 217. 'The cult of Abdullah Ansan under the Timurids', in Alma Giese and J. Christoph

Biirgel, (eds.), Gott ist schbn und Er liebt die Schonheit/God is beautiful and He loves beauty:

Festschrift in honour of Annemarie Schimmel, Bern, 1994, pp. 377 406. 'Mirak i Sayyid Ghiyas and the Timurid tradition of landscape architecture: Further

notes to "A medieval Persian agricultural manual in context", Studia Iranica, 24, 1

(i995), PP- 19 60.

Agriculture and the Timurid chaharbagh: The evidence from a medieval Persian agricul

tural manual', in Attilio Petruccioli (ed.), Gardens in the time of the great Muslim empires:

Theory and design, Leiden, 1997, pp. no 28.

'The Timurid legacy: A reaffirmation and a reassessment', Cahiers d'Asie Centrale, 3 4

(i997), PP- 9 19-

Le monde est unjardin: Aspects de Vhistoire culturelle de ITran medieval, Cahiers de Studia Iranica, 28, Paris, 2002.

638

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

'Husayn Va'iz i Kashifi: Polymath, popularizer, and preserver', Iranian Studies,  $36,\,4$ 

(2003), pp. 463 7.

Subtelny, Maria Eva, and Khalidov, AnasB., 'The curriculum of Islamic higher learning in

Timurid Iran in the light of the Sunni revival under Shah Rukh', Journal of the American

Oriental Society, 115, 2 (1995), pp. 210 36. Sulaimon, Hamid and Sulaimonova, Fozila, Alisher Navoii asarlariga ishlangan rasmlar, XV XIX

asrlar/Miniatiury k proizvedeniiam Alishera Navoi XV XIX vekov/ Miniatures illustrations of

Alisher Navoi's works of the XV XlXth centuries, Tashkent, 1982. Szuppe, Maria, 'The female intellectual milieu in Timurid and post Timurid Herat: Faxri

Heravi's biography of poetesses, Javaher al 'ajayeb', Oriente Modemo, n.s. 15, 2 (1996),

vol. I, pp. 119 37.

(ed.), 'L'heritage timouride: Iran Asie centrale Inde, XVe XVIIIe siecles', special

issue, Cahiers dAsie Centrale, 3 4 (1997).

Woods, John E., 'The rise of Timurid historiography', Journal of Near Eastern Studies, 46, 2

(1987), pp. 81 108.

The Timurid dynasty, Papers on Central Asia, 14, Bloomington, IN, 1990. 'Timur's genealogy', in Michel M. Mazzaoui and Vera B. Moreen (eds.), Intellectual studies

on Islam: Essays written in honor of Martin B. Dickson, Salt Lake City, 1990, pp. 85 125.

Wright, Owen, 'On the concept of a "Timurid music'", Oriente Modemo, n.s. 15, 2 (1996),

vol. II, pp. 665 81.

Yarshater, Ehsan, 'Persian poetry in the Timurid and Safavid periods', in The Cambridge

history of Iran, vol. VI, pp. 965 85.

6 Iran under Safavid rule Sholeh A. Ouinn

Practical suggestions for further reading

Aubin, Jean, 'La politique religieuse des Safavides', in Jean Aubin, he Shi'ism Imamate, Paris,

1970, pp. 235 44.

'Revolution Chiite et conservatisme: Les Soufis de Lahejan, 1500 1514 (Etudes Safavides

II)', Moyen Orient &r Ocean Indien, 1 (1984), pp. 140.

'L'avenement des Safavides reconsidere (Etudes Safavides III)', Moyen Orient & Ocean

Indien, 5 (1988), pp. 1 130.

'Chroniques persanes et relations italiennes: Notes sur les sources narratives du regne de

Sah Esma'il Ier', Studia Iranica, 24 (1995), pp. 247 59.

Babayan, Kathryn, 'The Safavid synthesis: From Qizilbash Islam to Imamite Shi'ism'.

Iranian Studies, 27 (1994), pp. 135 61.

Bashir, Shahzad, 'Shah Isma'il and the Qizilbash: Cannibalism in the religious history of

early Safavid Iran', Religion, 45 (2006), pp. 234 56.

Browne, E. G., 'Note on an apparently unique manuscript history of the Safawi dynasty of

Persia', Journal of the Royal Asiatic Society (1921), pp. 395 418.

A Literary history of Persia, vol. IV: Modem times (1500 1924),

Cambridge, 1924.

Calmard, Jean, Ali Asghar Mossadegh, and Parizi, M. Bastani, 'Notes sur des historiogra

phes de l'epoque Safavide', Studia Iranica, 16 (1987), pp. 123 35. Canby, Sheila R. (ed.), Safavid art and architecture, London, 2002.

639

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Dale, Stephen Frederic, 'The legacy of the Timurids', Journal of the Royal Asiatic Society, 8

(1998), pp. 43 58.

Dickson, Martin B., 'The fall of the Safavi dynasty' Journal of the American Oriental Society, 82

(1962), pp. 503 17.

Dickson, Martin B. and Welch, Stuart Cary, The Houghton Shahnameh, 2 vols., Cambridge,

MA, 1981.

Farhad, Massumeh, 'The art of Mu'in Musawir: A mirror of his times', in Sheila R. Canby

(ed.), Persian masters: Five centuries of painting, Bombay, 1990. Floor, Willem M., Safavid government institutions, Costa Mesa, CA, 2001. Fragner, BertG., Repertorium persischer herrscherurkunden. Publizierte originalurkunden

(his 1848), Freiburg, 1980.

Gholsorkhi, Shohreh, 'Ismail II and Mirza Makhdum Sharifi: An interlude in Safavid

history', International Journal of Middle East Studies, 26 (1994), pp. 477 88.

Haneda, Masashi, 'L' evolution de la garde royal des Safavides', Moyen Orient ir Ocean

Indien, 1 (1984), pp. 41 64.

he chah et les Qizilbash: he systeme militaire Safavide, Berlin, 1987. 'La famille Huzani d'Isfahan (ye i7e siecles)', Studia Iranica, 18 (1989), pp. 77 92. Hodgson, Marshall G. S., The venture of Islam: Conscience and history in a world civilization,

3 vols., Chicago, 1974.

Jacobs, Adam, 'Sunni and Shi'i perceptions, boundaries and affiliations in late Timurid and

early Safawid Persia: An examination of historical and quasi historical narratives',

Ph.D. dissertation, University of London, 1999.

Kafadar, Cemal, Between two worlds: The construction of the Ottoman state, Berkeley, 1995.

Kasravi, Ahmad, Shaykh Soft va tabarash, Tehran, 2535 [1976].

LeStrange, Guy, The bands of the eastern caliphate: Mesopotamia, Persia and Central Asia from

the Muslim conquest to the time of Timur, Cambridge, 1905, repr. New York, 1976.

Lockhart, Laurence, Nadir Shah, London, 1938.

McCabe, Ina Baghdiantz, The shah's silk for Europe's silver: The Eurasian trade of the Julfa

Armenians in Safavid Iran and India (i%o tyyo), Atlanta, 1999. Mazzaoui, Michel, 'From Tabriz to Qazvin to Isfahan: Three phases of Safavid history',

Deutschen Orientalistentag, 19 (1977), pp. 514 22.

'The siege of Herat during the first year of Shah Abbas' reign according to Iskandar

Munshi', Zeitschrift da Deutschen Morgenldndeschen Gesellschaft, Suppl. 4 (1980), pp. 233 4.

Safavid Iran and her neighbors, Salt Lake City, 2003.

Melville, Charles, A lost source for the reign of Shah Abbas: The Afdal al Tawarikh of Fazli

Khuzani Isfahani', Iranian Studies, 31 (1998), pp. 263 5. 'New light on the reign of Shah Abbas: Volume III of the Afdal al Tavarikh', in

Andrew J. Newman (ed.), Society and culture in the early modern Middle East: Studies

on Iran in the Safavid period, Leiden, 2003, pp. 63 97.

Minorsky, Vladimir, 'The poetry of Shah Isma'il I', Bulletin of the School of Oriental and

African Studies, 10 (1942), pp. 1006 53.

Morgan, David, Medieval Persia, 1040 1797, London and New York, 1988.

Morton, A. H, 'The Ardabil shrine in the reign of Shah Tahmasp I', Iran: Journal of the

British Institute of Persian Studies, 12 (1974), pp. 31 64; 13 (1975), pp. 39 58.

'The chub i tariq and qizilbash ritual in Safavid Persia', in Etudes Safavides, ed. Jean

Calmard, Paris and Tehran, 1993, pp. 225 45.

640

Cambridge Histories Online © Cambridge University Press, 201 1

## Bibliography

Newman, Andrew J. (ed), Society and culture in the early modern Middle East: Studies on Iran

in the Safavid period, Leiden, 2003.

Safavid Iran: Rebirth of a Persian empire, London, 2006.

Nikitine, B., 'Essai d' analyse du Safvat us Safa', Journal Asiatique, 245 (1957), pp. 385 94.

Perry, John R., Karim Khan Zand, Chicago, 1977.

Porter, Y., 'Notes sur le "Golestan e honar" de Qazi Ahmad Qomi', Studia Iranica, 17 (1988),

pp. 207 23.

Quinn, Sholeh A., 'The dreams of Shaykh Safi al Din and Safavid historical writing', Iranian

Studies, 29 (1996), pp. 127 42.

'The historiography of Safavid prefaces', in Charles Melville (ed.), Safavid Persia: The

history and politics of an Islamic society, London, 1996, pp. 1 25. 'Rewriting Ni'matullahi history in Safavid chronicles', in Leonard Lewisohn and

David Morgan (eds.), Late classical Persianate Sufism (1501 1750J, Oxford, 1999.

Rahimi, Babak, 'The rebound theater state: The politics of the Safavid camel sacrifice

rituals, 1598 1695 CE', Iranian Studies, 37 (2004), pp. 451 78. Riazul Islam, Indo Persian relations: A study of the political and diplomatic relations between the

Mughul empire and Iran, Tehran, 1970.

A calendar of documents on Indo Persian relations (yoo 17J0J, 2 vols., Tehran and Karachi, 1979.

Roemer, Hans R., 'The Qizilbash Turcomans: Founders and victims of the Safavid theoc

racy', in Michel M. Mazzaoui and Vera B. Moreen (eds.), Intellectual studies on Islam:

Essays written in honor of Martin B. Dickson, Salt Lake City, 1990, pp. 27 39.

Rota, Giorgio, 'Three little known Persian sources of the seventeenth century', Iranian

Studies, 31 (1998), pp. 159 76.

Roxburgh, DavidJ., Prefacing the image: The writing of art history in sixteenth century Iran,

Leiden, 2001.

Rypka, Jan, History of Iranian literature, ed. Karljahn, Dordrecht, 1968. Safa, Z., 'Persian literature in the Safavid period', in Peter Jackson and Laurence Lockhart

(eds.), The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods,

Cambridge, 1986, pp. 948 64.

Sarwar, Ghulam, History of Shah Isma'il Safawi, Aligarh, 1939, repr. New York, 1975.

Savory, Roger, A 15th century Safavid propagandist at Harat', in D. Sinor (ed.), American

Oriental Society, Middle West Branch, semi centennial volume: A collection of original essays,

Bloomington, IN, 1969.

"Very dull and arduous reading": A reappraisal of the history of Shah Abbas the great by

Iskandar Beg Munshi', Hamdard Islamicus, in (1980), pp. 19 37. Schimkoreit, Renate, Regesten publizierter safawidischer herrscherurkunden. Erlasse und staatss

chreiben derfruhen neuzeit Irans, Berlin, 1982. Simsar, Muhammad Hasan, 'Farman nivisi dar dawra yi Safaviyah', Barrasihayi tarikhi, 2

(1346 [1967 8]), pp. 127 52.

Streusand, Douglas E., The formation of the Mughal empire, Delhi, 1989. Szuppe, Maria, Entre Timourides, Uzbeks et Safavides: Questions d'histoire politique et sociale de

Herat dans la premiere moitie du XVIe siecle, Paris, 1992. 'L' evolution de l'image de Timour et des Timourides dans l'historiographie Safavide du

XVIe au XVIIIe siecle', Cahiers dAsie Centrale, 3 4 (1997), pp. 313 31. Tapper, Richard, 'Shahsevan in Safavid Persia', Bulletin of the School of Oriental and African

Studies, 37 (1974), PP- 321 54-

641

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Tauer, Felix, 'Persian learned literature from its beginnings up to the end of the 18th

century', in Karl Jahn (ed.)» History of Iranian literature, Dordrecht, 1968, pp. 438 59.

Togan, A. Z. V., 'Sur l'origine des Safavides', in Melanges Louis Massignon III, 3 vols.,

Damascus, 1957, pp. 345 57.

Tucker, Ernest, 'Explaining Nadir Shah: Kingship and royal legitimacy in Muhammad

Kazim Marvi's Tarikh i 'alam ara yi Nadiri', Iranian Studies, 26 (1993), pp. 95 117.

Nadir Shah's quest for legitimacy in post Safavid Iran, Gainesville, FL, 2006.

Von Erdman, F., 'Iskender Munschi und sein werk', Zeitschrift der Deutschen

Morgenldndeschen Gesellschaft, 15 (1861), pp. 457 501. Walsh, J. R., 'The historiography of Ottoman Safavid relations in the sixteenth and

seventeenth centuries', in Bernard Lewis and P. M. Holt (eds.), Historians of the

Middle East, London, 1962, pp. 197 211.

Wood, Barry D., 'The Tarikh i Jahanara in the Chester Beatty Library: An illustrated

manuscript of the "Anonymous Histories of Shah Isma'il'", Iranian Studies, 37

(2004), pp. 89 107.

Woods, John E., The Aqquyunlu: Clan, confederation, empire, rev. and exp. edn, Salt Lake City, 1999.

Yar Shater, E., 'Safavid literature: Progress or decline?', Iranian Studies, 7 (1974), pp. 217 70.

# Primary sources

Abdi Beg Shirazi, Zayn al 'Abidm 'All, Takmilat al akhbar, ed. Abd al Husayn Nava'i,

Tehran, 1369 [1990].

Afushta yi Natanzi, Mahmud ibn Hidayat Allah, Naqavat al athar f\ dhikr al akhyar, ed.

Ihsan Ishraqi, Tehran, 1350 [1971].

Ahmad Razi, Amin, Haft iqhm, ed. Javad Fazil, 3 vols., [Tehran], n.d. 'Alam ara yi Safavi, ed. Yad Allah Shukri, [Tehran], 1350 [1971]. 'Alam ara yi Shah Tahmasb, ed. Iraj Afshar, [Tehran], 1370 [1991]. Ammi Harawi, Sadr al Dm Sultan Ibrahim, 'Futuhat i shahi', ms. Kitakhana yi Vazin yi

Yazd 5774; ms., Dushanbe I.

Amir Mahmud ibn Khvandamir, Iran dar ruzgar i Shah Isma'il va Shah Tahmasb Safavi, ed.

Ghulam Riza Tabataba'i, Tehran, 1370 [1991]. Ghaffan Qazvim Kasham, Qazi Ahmad, Tarikh ijahan ara, ed. Hasan Naraqi, Tehran, 1342 [1963].

Hasan Beg Rumlu, Ahsan al tavarikh, ed. Abd al Husayn Nava'i, Tehran, 1349 [1970].

Kitab i ahsan al tavarikh, ed. Charles Norman Seedon, Tehran, n.d. Husayni Qazvim, Yahya ibn 'Abd al Latif, Lubb al tavarikh, ed. Jalal al Din Tihrani,

[Tehran], 1314 [1937].

Ibn Bazzaz Tavakkul ibn Isma'il Safvat al safa, ed. Ghulam Riza Tabataba'i Majd, Ardabil,

[1373] 1994; lith. Ahmad ibn Kanm Tabnzi, Bombay, 1329 [1911]; trans, and ed. Heidi

Zirke as Ein hagiographisches zeugnis zur persicschen geschichte aus der mitte des 14

jahrhunderts. Das achte kapitel des Safwat as safa in kritischer bearbeitung, Berlin, 1987.

Iskandar Beg Munshi, Tarikh i 'alam arayi 'Abbasi, 2 vols., ed. Iraj Afshar, Tehran, 1350 [1971].

Tarikh i 'alam ara yi 'Abbasi, trans. Roger Savory as History of Shah 'Abbas the great (Tarik e

'alamaraye 'Abbasi), 3 vols., Boulder, CO, 1978. Juan de Persia, Don Juan of Persia: A Shiah Catholic 1560 1604, trans, and ed. G. LeStrange,

London, 1926.

642

Cambridge Histories Online © Cambridge University Press, 201 1

## Bibliography

Junabadi, Mirza Beg, Rawzat al safaviyya, ed. Ghulam Riza Tabataba'i majd, Tehran, 1378

[1999].

Khatunabadi, Sayyid Abd al Husayn al Husaym, Waqayi' al sinin wa al a'wam, ed.

Muhammad Bagir Bihbudi, Tehran, 1352 [1973].

Khunji, Fazl Allah ibn Ruzbihan, Tarikh i 'alum ara yi Amim, trans, and abr. V. Minorsky as

Persia in AD 147S 1490: An abridged translation of Fadlullah b. Ruzbihan Khunji's tarikh i

'alam'ara yi Amini, London, 1957; rev. and aug. by John E. Woods, London, 1992.

Khvandamir, Ghiyath al Din ibn Humam al Din, Tarikh i habib alsiyar, ed Jalal al Dm

Huma'i, 4 vols., [Tehran], 1333 [1954]; trans. Wheeler Thackston as Habibu's siyar,

2 vols., Cambridge, MA, 1994.

Membre, Michele, Mission to the Lord Sophy of Persia (1539 1542), trans. A. H. Morton,

London, 1993.

Mirkhwand, Muhammad ibn Khwavandshah, Tarikh i rawzat al sofa, ed. Abbas Parviz,

7 vols., [Tehran], 1338 [1959]; trans. E. Rehatsek as Rauzat us sofa or, garden of purity, ed.

F. F. Arbuthnot, 3 vols., London, 1891.

Muhammad Ma'sum ibn Khwajagi Isfaham, Khulasat al siyar: Tarikh i ruzgar i Shah Safi i

Safavi, ed. Iraj Afshar, Tehran, 1368 [1989]. Qazi Ahmad Munshi Qummi, Gulistan i hunar, ed. Ahmad Suhayli Khwansan, [Tehran],

n.d.; trans. V. Minorsky as Calligraphers and painters, Washington, 1959. Khulasat al tavarikh, ed. Ihsan Ishraqi, 2 vols., Tehran, 1363 [1984]; trans, and ed. Erika

Glassen as Diefruhen Safawiden nach Qazi Ahmad Qumi, Freiburg, 1970; trans, and ed.

Hans Muller as Die chronik Hulasat at tawarih des Qazi Ahmad Qumi. Der abschnitt uber

Schah 'Abbas I, Wiesbaden, 1964.

Sam Mirza Safavi, Tadhkira yi tuhfa yi Sami, ed. Rukn al Dm Humayun Farrukh, n.p., n.d.

Shah Isma'il, II Canzoniere di Sah Isma'il Hatah, ed. Tourkhan Gandjei, Naples, 1959, trans.

Robert Dankoff in 'Readings in Islamic civilization: From the rise of Islam to the

beginning of the ioth/i6th century', Robert Dankoff, gen. ed., unpublished ms.

Shah Tahmasb Safavi, 'Tadhkira yi Shah Tahmasb', ed. P. Horn, Zeitsehrift des Deutschen

Morgenldndischen GeseUschaft 44 (1890), pp. 563 649; 45 (1891), pp. 245 91.

Siyaqi Nizam, Futuhat i humayun, ed., trans, and arm. Chahryar Adle as 'Fotuhat e homayun:

Les victoires augustes, 1007/1598', Ph.D. dissertation., University of Paris, 1976.

Tadhkirat al muluk, trans, and ed. V. Minorsky, London, 1943. Tarikh i Qizilbashan, ed. Mir Hashim Muhaddith, Tehran, 1361 [1982]. Yazdi, Mulla Jalal al Dm Munajjim, Tarikh i 'Abbasi ya ruznama yi Mulla Jalal, ed. Sayf Allah

Vahid Niya, [Tehran], 1366 [1987].

Zahidi, Shaykh Husayn Pirzada, Sihilat al nasab i Safaviyah, ed. Kazimzada, Berlin, 1924.

#### Secondary sources

Abisaab, Rula Jurdi, Converting Persia: Religion and power in the Safavid empire, London, 2004.

Arjomand, Said Amir, The shadow of God and the hidden imam: Religion, political order, and

societal change in Shi'ite Iran from the beginning to 1S90, Chicago, 1984.

Aubin, Jean, 'Etudes Safavides I Sah Isma'il et les notables de l'Iraq Persan', Journal of

Economic and Social History of the Orient, 2 (1959), pp. 37-81. Babaie, Sussan, Babayan, K., Baghdiantz McCabe, I. and Farhad, M., Slaves of the shah: New

elites of Safavid Iran, London, 2004.

## Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Babayan, Kathryn, Mystics, monarchs, and messiahs: Cultural landscapes of early modern Iran,

Cambridge, MA, 2002.

Calmard, Jean, 'Shi'i rituals and power II: The consolidation of Safavid Shi'ism: Folklore

and popular religion', in Charles Melville, (ed.), Safavid Persia: The history and politics of

an Islamic society, London, 1996, pp. 139 90.

Dale, Stephen Frederic, 'A Safavid poet in the heart of darkness', in Stephen Frederic Dale,

Safavid Iran and her neighbors, Salt Lake City, 2003. Dickson, Martin B., 'Shah Tahmasb and the Uzbeks: The duel for Khurasan with 'Ubayd

Khan (930 946/1524 1540)', Ph.D. dissertation, Princeton University, 1958.

Gurney, J. D., 'Pietro della Valle: The limits of perception', Bulletin of the School of Oriental

and African Studies, 49 (1986), pp. 103 16.

Hillenbrand, Robert, 'Safavid architecture', in Peter Jackson and Laurence Lockhart (eds.),

The Cambridge history of Iran, vol. VI: The Timurid and Safavid periods, Cambridge, 1986,

pp. 759 842.

Horst, Heribert, Timur und Hogd 'Ali. Ein beitrag zur geschichte der Safawiden, Mainz, 1958.

Hourani, Albert, 'From Jabal 'Amil to Persia', Bulletin of the School of Oriental and African

Studies, 49 (1986), pp. 133 40.

Jackson, Peter and Lockhart, Laurence (eds.), The Cambridge history of Iran, vol. VI: The

Timurid and Safavid periods, Cambridge, 1986.

Lockhart, Laurence, 'European contacts with Persia, 1350 1736', in Peter Jackson and

Laurence Lockhart (eds.), The Cambridge history of Iran, vol. VI: The Timurid and

Safavid periods, Cambridge, 1986.

Losensky, Paul E., '"The allusive field of drunkenness': Three Safavid Moghul responses to

a lyric by Baba Fighani', in Suzanne P. Stetkevych (ed.), Reorientations / Arabic and

Persian poetry, Bloomington, IN, 1994, pp. 227 62.

Welcoming Fighani: Imitation and poetic individuality in the Safavid Mughal Ghazal (Costa

Mesa, CA, 1998).

McChesney, Robert D., 'A note on Iskandar Beg's chronology', Journal of Near Eastern

Studies, 39 (1980), pp. 53 63.

'Four sources on Shah Abbas's building of Isfahan', Muqarnas, 5 (1988), pp. 103 34.

'The conquest of Herat 995 6/1587 8: Sources for the study of Safavid /Qizilbash

Shibanid/Uzbak relations', in Jean Calmard (ed.), Etudes Safavides, Paris and Tehran,

1993, PP- 69 107.

McNeill, William H. and Waldman, Marilyn Robinson (eds.), The Islamic world, Chicago,

1973-

Marshall, D. N., Mughals in India: A bibliographical survey of manuscripts, London, 1967, repr.

New York, 1985.

Matthee, Rudolph P., Administrative stability and change in late 17th century Iran: The

case of Shaykh Ali Khan Zanganah (1669 89)', International Journal of Middle East

Studies, 26 (1994), pp. 77 98.

The politics of trade in Safavid Iran: Silk for silver, 1600 1730, New York, 1999.

Mazzaoui, Michel, The origins of the Safawids: Si'ism, Sufism, and the Gulat, Wiesbaden, 1972.

Melville, Charles, 'Shah Abbas and the pilgrimage to Mashhad', in Charles Melville, (ed.),

Safavid Persia: The history and politics of an Islamic society, London, 1996, pp. 191 229.

Mirjafari, Hossein, 'The Haydari Ni'mati conflicts in Iran', trans, and adapt. J. R. Perry,

Iranian Studies, 12 (1979), pp. 135 62.

644

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Momen, Moojan, An introduction to ShiH Islam, New Haven, 1985.

Morton, A. H., 'The date and attribution of the Ross Anonymous: Notes on a Persian history of

Shah Isma'il I', in Charles Melville (ed.), Pembroke papers I, Cambridge, 1990. pp. 179 212.

'The early years of Shah Isma'il in the Afzal al tavarikh and elsewhere', in

Charles Melville (ed.), Safavid Persia: The history and politics of an Islamic society,

London, 1996, pp. 27 51.

Nasr, S. H., 'Spiritual movements, philosophy and theology in the Safavid period', in

Peter Jackson and Laurence Lockhart (eds.), The Cambridge history of Iran, vol. VI:

The Timurid and Safavid periods, Cambridge, 1986, pp. 656 97. Newman, AndrewJ., 'The myth of the clerical migration to Safawid Iran: Arab Shiite

opposition to Ali al Karaki and Safawid Shiism', Die Welt des Islams, 33 (1993), pp. 66 112.

'Baqir al Majlisi and Islamicate medicine', in AndrewJ. Newman (ed.), Society and culture in

the early modem Middle East: Studies on Iran in the Safavid period, Leiden, 2003, pp. 381 96.

Nizami, Khaliq Ahmad, On history and historians of medieval India, New Delhi, 1982.

Perry, JohnR., 'The last Safavids (1722 73)', Iran: Journal of the British Institute of Persian

Studies, 9 (1971), pp. 59 71.

Quinn, SholehA., Historical writing during the reign of Shah 'Abbas: Ideology, imitation and

legitimacy in Safavid chronicles, Salt Lake City, 2000.

Roemer, Hans R., 'The Safavid period', in Peter Jackson and Laurence Lockhart (eds.), The

Cambridge history of Iran, vol. VI: The Timurid and Safavid periods, Cambridge, 1986,

pp. 189 350.

Savory, Roger, Iran under the Safavids, Cambridge and New York, 1980. Sims, Eleanor, A dispersed late Safavid copy of the Tarikh ijahangusha yi Khaqan Sahibairan,

in Sheila R. Canby (ed.), Safavid art and architecture, London, 2002, pp. 54 7.

Stanfield Johnson, Rosemary, 'The Tabarra'iyan and the early Safavids', Iranian Studies, 37

(2004), pp. 47 71.

Stewart, DevinJ., 'Notes on the migration of 'Amili scholars to Safavid Iran', Journal of Near

Eastern Studies, 55 (1996), pp. 81 103.

Storey, C. A., Persian literature: A bio bibliographical survey, 3 vols., London, 1927.

Persidskaya literatura: Bio bibliograficheskii obzor, rev. and trans. Yu. E. Bregel, 3 vols.,

Moscow, 1972.

Szuppe, Maria, 'Kinship ties between the Safavids and the Qizilbash amirs in late sixteenth

century Iran: A case study of the political career of members of the Sharaf al Din Ogli

Tekelu family', in Charles Melville (ed.), Safavid Persia: The history and politics of an

Islamic society, ed. London, 1996, pp. 79 104. Welch, Stuart Cary, A king's book of kings: The Shah nameh of Shah Tahmasp, New York, 1972.

7 Islamic culture and the Chinggisid restoration: Central Asia

in the sixteenth and seventeenth centuries

R. D. McChesney

Practical suggestions for further reading

Zahir al Din Muhammad Babur Padshah Ghazi, The Babur noma in English (Memoirs of Babur), trans, from the original Turki text by Annette Susannah Beveridge, London, 1969, repr. of London, 1922 edn.

645

Cambridge Histories Online © Cambridge University Press, 201 1

#### Bibliography

Mirza Muhammad Haidar Dughlat, A history of the Moghuh of Central Asia being the Tarikh i

Rashidi of Mirza Muhammad Haidar, Dughlat, ed. N. Elias, trans. E. Denison Ross,

New York, 1972, repr. of London 1898 ed; Tarikh i Rashidi: A history of the khans of

Moghulistan, Eng. trans, and arm. W. M. Thackston, Cambridge, MA, 1996.

#### Primary sources

Abu'l Ghazi Bahadur Khan, Rodoslovnaya Turkmen (Shajarah i Tarakimah), ed. and trans.

(into Russian), A. N. Kononov, Moscow and Leningrad, 1958.

Shajara i Turk, ed. and trans. Petr I. Desmaisons as Histoire des Mongols et des Tatares par

Aboul Ghazi Behddour Khan, St Leonards and Amsterdam 1970 repr. of St Petersburg

1 871 4 edn.

Babadjanov, Baxtiyor, Muminov, Ashirbek, and Paul, Jtirgen, Schaibanidische Grabinshriften,

Wiesbaden, 1997.

Babajanov, Bakhtyar and Szuppe, Maria, Les inscriptions persanes de Char Bakr, necropole

familiale des khwajajuybfln pres de Boukhara, Corpus inscriptionum iranicarum, Part IV:

Persian inscriptions down to the early Safavid period, vol. XXXI: Uzbekistan, London,

2002.

Bertel's, E. [and Rostopchin, F. B.,] (eds.), Iz arkhiva Dzhuibari, Leningrad, 1938. Summarily

translated by Fedor Borisovich Rostopchin with later review of translation by Iu.

P. Verkhovsky and an introductory essay by P. P. Ivanov and published as Khoziaistvo

Dzhuibarskikh Sheikhov, Moscow, 1954.

Kamal al Din Banna'i (Bina'i), Shaybam nama, ed. Kazuyuki Kubo, in A synthetical study on

Central Asian culture in the Turco Islamic period, Kyoto, 1997 (Japanese and English).

Davidovich, E. A., Istoriia monetnogo dela Srednei Azii XVII XVIII w. (Zolotye i serebrianye

monety Dzhanidov), Dushanbe, 1964.

Istoriia deneszhnogo obrashcheniia srednevekovoi Srednei Azii, Moscow, 1983.

Korpus zolotykh i serebrianykh monet Sheibaniudov, XVI vek, Moscow, 1992.

Fazlallah b. Ruzbihan i Khunji Isfaham, Tarikh i 'Alamarayi Ammi, Persian text ed.

JohnE. Woods, ms.

Mihman nama i Bukhara, ed. M. Sutudah, Tehran, 1341/1963.

Hafiz i Tamsh, Sharafnama i Shahi (also known as 'Abdallah nama), ed. and trans.

M. A. Salakhetdinova (vols. 1 and 2 only of four projected), Moscow 1983 9; India

Office Library ms. 574 for the remainder of the work. Fakhn Harawi, Tazkirah i Rawzat al Salatm, Tabriz, 1345/1966. Inayat Khan, The Shahjahan Nama, trans. A. R. Fuller, ed. and completed W. E. Begley and

Z. A. Desai, Delhi and New York, 1990.

Islam, Riazul, A calendar of documents on Indo Persian relations (1500 1750], 2 vols., Karachi,

1979 82.

Badr al Dm Kashmiri, Rawzat al rizwanfi hadiqat alghilman, Inv. no. 2094 (Sharqshinosliq

Institut, formerly Institut Vostokovedeniia), Tashkent. Khwaja Baha' al Dm Hasan Nithan Bukhan, Mudhakkir al ahbab, ed. S. M. Fazlullah,

New Delhi, 1969.

Lowick, N. M., 'Shaybanid silver coins', Numismatic Chronicle, ser. 7, 1966, pp. 251 330.

Mahmud b. Amir Wall, Bahr al asrarfi manaqib al akhyar, vol. VI, part (rukn) 4, India Office

Library ms. 575.

646

Cambridge Histories Online © Cambridge University Press, 201 1

### **Bibliography**

More tain otnositel'no doblestei blagorodnykh (Geografiia) (Geographical portion of the Bahr

al asrar), ed. and trans. B. A. Akhmedov, Tashkent, 1977. Bahr al asrar fix ma'rifat al akhyar, vol. 1, part 1, ed. Hakim Mohammed Said, S. Moinul Haq and Ansar Zahid Khan, Karachi, 1984. Minorsky, V. M., Persia in AD 1478 1490: An abridged translation of FadluUah b. Ruzbihan

Khunji's Tarikh i 'alam ara yi Amvni, London, 1957. Muhammad Badi' Samarqandi (Maltha), Muzakkir al ashab, Tashkent, Biruni Institute of

Oriental Studies, ms. 4270; Dushanbe, Institute of Oriental Studies, ms. 610.

Mukminova, R[oziya] G[alievna], K istorii agrarnykh otnoshenii v Uzbekistane XVI v. : Vakf

name, Tashkent, 1966.

Munis Khorezmi, Shir Muhammad Mirab Munis and Muhammad Riza Mirab Agahi, Firdaws

al iqbal: History ofKhorezm, ed. (1988) and trans. (1999) Yuri Bregel, Leiden, 1988, 1999.

Mutribi al Asamm al Samarqandi, Nuskhah i ziba yijahangir, ed. Isma'il Bikjanuf and Sayyid

Ah Mujam, Qum, 1377/1998.

Tazkirat al shu'ara\ ed. Asghar Janfada and Ah Rafi'i, Tehran, 1377/1998. Zayn al Dm Wasif 1, Bada'i' al vvaqaH', ed. Aleksandr Boldyrev, 2 vols., Moscow, 1961.

Secondary sources

Akhmedov, B. A., Istoria Balkha, Tashkent, 1982.

Babajanov, Bakhtyar, 'La naqshbaniyya sous les premiers Sheybanides', L'heritage

Timouride: Iran Asie centrale Inde XV e XVIIIe siecles; Cahiers dAsie Centrale, 3 4

(i997), PP- 69 90.

'Datation de la mosquee Valida ye Abd al Aziz Xan a Boukhara', Studia Iranica, 28

(i999), PP- 227 34.

Bregel, Yuri, An historical atlas of Central Asia, Leiden, 2002, pp. 48 60. Burton, Audrey, The Bukharans: A dynastic, diplomatic and commercial history, 1550 1702,

Richmond, 1997.

DeWeese, Devin, 'The eclipse of the Kubraviya in Central Asia', Iranian Studies, 21 (1988),

PP-4583.

Islamization and native religion in the Golden Horde Bab Tiikles and conversion to Islam in

historical and epic tradition, University Park, PA, 1994. Dickson, Martin B., 'Shah Tahmasb and the Uzbeks', Ph.D. dissertation, Princeton

University, 1958.

Digby, Simon, (trans.), Sufis and soldiers in Awrangzeb's Deccan: Malfuzdt i Nagshbandiyya,

New Delhi, 2001.

Fraser, James B., Narrative of a journey into Khorasan in the years 1821 and 1823, 1984 repr. of

London 1825 edn.

Galerkina, Olympiada, Mawarannahr book painting, Leningrad, 1980. Haneda, Masashi, 'Emigration of Iranian elites to India during the 16th 18th centuries',

L'heritage Timouride: Iran Asie centrale Inde XVe XVIIIe siecles; Cahiers d'Asie Centrale,

3 4 (1997) PP- 129 43-

Hofman, H., Turkish literature: A bio bibliographical survey, Section III: Part 1 (Authors)

2 vols., Utrecht, 1969.

Isogai, Ken'ichi, Yasa and Shariah in early 16th century Central Asia', L'heritage Timouride:

Iran Asie centrale Inde XVe XVIIIe siecles; Cahiers d'Asie Centrale, 3 4 (1997), pp. 91 103.

647

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

McChesney, R. D., 'Economic and social aspects of the public architecture of Bukhara in

the 1560s and 1570s', Islamic Art, 2 (1987), pp. 217 42. Waqf in Central Asia: Four hundred years in the history of a Muslim shrine, 1480 1889,

Princeton, 1991.

Central Asia: Foundations of Change, Princeton, 1996.

'Some observations on "garden" and its meanings in the property transactions of the

Juyban family in Bukhara, 1544 77', in Attilio Petruccioli (ed.), Gardens in the time of the

great Muslim empires, Leiden, 1997, pp. 97 109.

'Bukhara's suburban villages: Juzmandun in the sixteenth century', in Attilio Petruccioli

(ed.), Bukhara: The myth and the architecture, Cambridge, MA, 1999, pp. 93 119.

'Reconstructing Balkh: The Vaqfiya of 947/1540', in Devin DeWeese (ed.), Studies on

Central Asian history in honor of Yuri Bregel, Bloomington, IN, 2001, pp. 187 243.

Architecture and narrative: The Khwaja Abu Nasr Parsa shrine', (in two parts)

Mugarnas, 18 (2001), pp. 94 119; 19 (2002), pp. 78 108.

Mukminova, R. G., Ocherki po istorii remesla v Samarkande i Bukhare v XVI veke, Tashkent, 1976.

O'Kane, Bernard, 'The Uzbek architecture of Afghanistan', La memoire et ses supports en Asie

centrale; Cahiers dAsie Centrale, 8 (2000), pp. 123 60.

Paul, Jtirgen, 'La propriete fonciere des cheikhs Juybari', L'heritage Timouride: Iran Asie

centrale Inde XVe XVIIIe sticks; Cahiers dAsie Centrale, 3 4 (1997), pp. 183 202.

Porter, Yves, 'Farhad le peintre: A propos des ateliers de peinture de Boukhara a l'epoque

de 'Abd al 'Aziz Khan (1645 1680)', L'heritage Timouride: Iran Asie centrale Inde

XVe XVIIIe sticks; Cahiers dAsie Centrale, 3 4 (1997), pp. 267 78.

'Remarques sur la peinture a Boukhara au XVIe siecle', Boukhara La Nobk; Cahiers d'Asie

Centrale, 5 6 (1998), pp. 147 67.

'Le kitdb khdna de 'Abd al 'Aziz Khan (1645 1680) et le mecenat de la peinture a

Boukhara', Patrimoine manuscrit et vie intellectuelle de I'Asie centrale islamique; Cahiers

dAsie Centrale, 7 (1999), pp. 117 36.

Schimmel, Annemarie, 'Some notes on the cultural activity of the first Uzbek rulers',

Journal of the Pakistan Historical Society, 8 (i960), pp. 149 66. Schwarz, Florian, 'Bukhara and its hinterland: The oasis of Bukhara in the sixteenth century

in light of the Juybari Codex', in Attilio Petruccioli (ed.), Bukhara: The myth and the

architecture, Cambridge, 1999.

'Unser Weg schlieft tausend Wege ein': Derwische und Gesellschaft im islamischen Mittelasien

im 16. Jahrhundert, Berlin, 2000.

Sylloge Numorom Arabicorum Tubingen: Balh und Die Landschaften am oberen Oxus XIV c

Hurasan III, Berlin, 2002.

Storey, C. A., Persidskaya literatura: Bio bibliograficheskii obzor, vev., trans, and updated Yuriv

E. Bregel, 3 vols., Moscow, 1972.

Maria Eva Subtelny, Art and politics in early 16th century Central Asia', Central Asiatic

Journal, 27 (1983), pp. 121 48.

'Socio economic bases of cultural patronage under the later Timurids', International

Journal of Middle Eastern Studies, 20, 4 (1988), pp. 479 505.

'A medieval Persian agricultural manual in context: The Irshad al zira'a in late Timurid

and early Safavid Khorasan', Studia Iranica 22, 2 (1993), pp. 167 217. 'Miraki Sayyid Ghiyas and the Timurid tradition of landscape architecture', Studia

Iranica, 24 (1995), pp. 1960.

648

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

The making of Bukhara yi Sharif. Scholars and libraries in medieval Bukhara (The library

of Khwaja Muhammad Parsa)', in Devin DeWeese (ed.), Studies on Central Asian

history in honor of Yuri Bregel, Bloomington, IN, 2001, pp. 79 in.

he monde est unjardin: Aspects de l'histoire culturelle de l'Iran medieval, Paris, 2002.

Subtelny, Maria Eva and Khalidov, Anas B., 'The curriculum of Islamic higher learning in

Timurid Iran in the light of the Sunni revival under Shah Rukh', Journal of the American

Oriental Society, 115 (1995), pp. 210 36.

Sukhareva, O. A., Kvartal'naia obshchina pozdnefeodal'nogo goroda Bukhary, Moscow, 1976.

Szuppe, Maria, Entre Timourides, Uzbeks, et Safavides: Questions d'histoire politique et sociale de

Herat dans la premiere moitie du XVIe siecle, Paris, 1992.

'Lettres, patrons, libraires: L'apport des recueils biographiques sur le role du livre en

Asie centrale aux xvie et xvue siecles', Cahiers d'Asie Centrale, 7 (1999), pp. 99 115.

'Circulation des lettres et circles litteraires entre Asie centrale, Iran et Inde du Nord

(XVe XVIIIe siecles), Annales: Histoire, Sciences Sociales, 59 (2004), pp. 997 1018.

8 India under Mughal rule Stephen Dale

Practical suggestions for further reading

Alam, Muzaffar, The crises of empire in Mughal north India, Delhi, 1986.

Alam, Muzaffar, Delvoye, Francois 'Nalini' and Gaborieau, Marc, The making oflndo Persian

culture, New Delhi, 2000.

Asher, Catherine B., Architecture of Mughal India, The new Cambridge history of India,

Cambridge, 1992.

Berinstain, Valerie, India and the Mughal dynasty, New York, 1998.

Gascoigne, Bamber, The great Mughals, London, 1971.

Gham, Muhammad Abdu'l, A history of Persian language and literature at the Mughal court,

2 vols., Allahabad, 1930.

Koch, Ebba, Mughal architecture, Munich, 1991.

Losensky, Paul E., Welcoming Fighdni: Imitation and poetic individuality in the Safavid Mughal

ghazal, Costa Mesa, CA, 1998.

Mukhia, Harbans, The Mughals of India, Oxford, 2004.

Okada, Amina, Indian miniatures of the Mughal court, trans. D.

Dusinberre, New York, 1992.

Richards, John F., The Mughal empire, Cambridge, 1993.

Schimmel, Annemarie, Islamic literatures of India, Wiesbaden, 1973.

The empire of the great Mughals, London, 2004.

Welch, S. C, Imperial Mughal painting, London, 1978.

Ziad, Zeenut, The magnificent Mughals, Karachi, 2002.

Primary sources

Abu'l Fadl 'Allami, A'm i Akban, trans. H. Beveridge, 3 vols., Delhi, repr. 1987.

Akbar nama, trans. H Blochmann, 3 vols., Delhi, repr. 1988.

Bacque Grammont, Jean Louis, Le livre de Babur, Paris, 1980.

al Badaum, Abd al Qadir b. Muluk Shah, Muntakhabu 't Tawarikh, trans. W. H. Lowe,

3 vols., Patna, repr. 1973.

# Cambridge Histories Online © Cambridge University Press, 201 1

# Bibliography

Begam, Gul Badan, The history of Humayun (Humayun nama), trans, and ed. Annette

S. Beveridge, Delhi, repr. 1972.

Begley, W. E. and Desai, Z. A. (eds.), The Shahjahan nama of Inayat Khan, Delhi and New

York, 1990.

Bernier, Francis, Travels in the Moghul empire 1656 1658, Delhi, repr. 1968.

Beveridge, Annette Susannah, The Babur nama in English, London, repr. 1969.

Dughlat, Haydar Mirza, Tarikh i Rashidi, Persian text ed. W. M. Thackston, Sources of

Oriental Languages and Literatures. 37 and 38, Cambridge, MA, 1996. Haq, Moinul, Kha.fi Khan's history ofAlamgir, Karachi, 1975. Jahangir, The Jahangirnama: Memoirs ofi Jahangir, emperor of India, ed. and trans.

Wheeler M. Thackston (Washington, DC, 1999).

Kazim, Muhammad, 'Alamgvr Nama, ed. Abd al Hayy and Ahmad Ali, Calcutta, 1865.

Khan, 'Aqil, The Waqi'at i 'Alamgin, trans. Zafar Hasan, Delhi, 1946. Lahawn, Abd al Hamid, The Badshahnamah, Persian text ed. M. Kabir al Din Ahmad and

M. Abd al Rahim, Calcutta, 1867 72.

Mano, Eiji, Babur nama (Vaqayi'), Kyoto, 1995 6.

Manrique, Sebastian, Travels of Fray Sebastian Manrique 1629 1643, Cambridge, 1927.

Manucci, N., Storia do Mogor or Moghul India, 4 vols., Calcutta, 1907 8. Roe, Thomas, The embassy of Sir Thomas Roe to India 1615 1619, ed. William Foster, London, 1926.

Sarkar, J. N., History of Aurangzeb, based mainly on Persian sources, 5 vols., Calcutta, 1912 30.

Tavernier, Jean Baptiste, Travels in India, trans. V. Ball, 2 vols., London, 1989.

## Secondary sources

Alam, Muzaffar and Subrahmanyam, Sanjay, The Mughal state 1526 1750, New Delhi, 1998.

Ali, M. Athar, 'The passing of empire: The Mughal case', Modern Asian Studies, 9, 3 (1975),

pp. 385 96.

The apparatus of empire, Delhi, 1985.

The Mughal nobility under Aurungzeb, Delhi, 1985.

Alvi, Sajida Sultana, Advice on the art of governance: An Indo Islamic mirror for princes, Albany,

1989.

Balabanlilar, Lisa, 'Lords of the auspicious conjunction: Turco Mongol imperial identity on

the subcontinent', Journal of World History, 18, 1 (2007), pp. 1 39. Blake, Stephen P., 'The patrimonial bureaucratic empire of the Mughals', journal of Asian

Studies, 39, 1 (November 1979), pp. 77 94.

Shahjahanabad: The sovereign city in Mughal India, Cambridge, 1993. Chaudhuri, K. N., The European trading world of Asia and the English East India Company,

Cambridge, 1978.

Dale, Stephen F., Indian merchants and Eurasian trade 1600 1750, Cambridge, 1994.

The garden of the eight paradises: Babur and the culture of empire in Central Asia, Afghanistan

and India (1483 1530), Leiden and Boston, 2004.

Gommans, JosJ. L. and Kolff, Dirk, Warfare and weaponry in South Asia, 1000 1800,

Delhi, 2001.

Gordon, Stewart, The Marathas 1600 1818, Cambridge, 1993. Grewal, J. S., The Sikhs of the Punjab, The new Cambridge history of India, Cambridge,

1990.

## Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Habib, Irfan The agrarian system of Mughal India, London, 1963.

An atlas of the Mughal empire, Delhi, 1982.

(ed), Akbar and his India, New Delhi, 1997.

Irvine, William, Later Mughals, New Delhi, repr. 1971.

Khan, Shah Nawaz, The Maathir ul Umara, trans. H. Beveridge and B. Prashad, New Delhi,

repr. 1979.

Koch, Ebba, The complete Taj Mahal, London, 2006.

Kolff, Dirk, Naukar, Rajput and Sepoy: The ethnohistory of the military labour market in

Hindustan 1450 1830, Cambridge, 1990.

Lai, Ruby, Domesticity and power in the early Mughal world, Cambridge, 2005.

Marek, Jan, 'Persian literature in India', in Jan Rypka (ed.), History of Iranian literature,

Dordrecht, 1968, pp. 713 34.

Moosvi, Shireen, 'The silver influx, money supply, prices and revenue extraction in

Mughal India', Journal of the Economic and Social History of the Orient, 30, 1 (1987),

PP-4794-

The Economy of the Mughal empire c. ygy, Delhi, 1987.

Nathan, Mirza, Bahdristan i Gaybi, Gauhati, India, 1936.

Nizami, K. A., Akbar and religion, Delhi, 1989.

Pradhan, Mahesh Chandra, The political system of the fats of northern India, Bombay, 1966.

Prakash, Om, European commercial enterprise in pre colonial India, The new Cambridge

History of India, Cambridge, 1998.

Prasad, Beni, History ofjahangir, London, 1922.

Prasad, Ishwari, The life and times of Humayun, Calcutta, 1955.

Raychaudhuri, Tapan and Habib, Irfan (ed.), The Cambridge economic history of India,

Cambridge, 1982, vol. I.

Richards, John F., Mughal administration in Golconda, Oxford, 1975.

'The formation of imperial authority under Akbar and Jahangir', in J. F. Richards (ed.),

Kingship and authority in South Asia, Madison, WI, 1978.

(ed.), The imperial monetary system of Mughal India, Delhi, 1987.

Rizvi, S. A. A., Religious and intellectual history of Muslims in Akbar's reign, Delhi, 1975.

Robinson, Francis, 'Ottomans Safavids Mughals: Shared knowledge and connective

systems' Journal of Islamic Studies 8, 2 (1997), pp. 151 84.

The 'ulama of the Farangi Mahall and Islamic culture in South Asia, London, 2001.

Sadiq, Muhammad, A history of Urdu literature, London, 1964.

Saksena, Banarsi Prasad, History of Shah Jahan of Dihli, Allahabad, repr. 1973.

Siddiqi, N., Land revenue administration under the Mughals ijoo 17/0, Aligarh, 1970.

9 Islamic trade, shipping, port-states and merchant communities

in the Indian Ocean, seventh to sixteenth centuries

Michael Pearson

Practical suggestions for further reading

Muslim trade and navigation: port cities Bouchon, Genevieve, 'Les Musulmans du Kerala a l'epoque de la decouverte portugaise', Mare Luso Indicum, 2 (1973), pp. 3 59.

651

Cambridge Histories Online © Cambridge University Press, 201 1

#### **Bibliography**

L'Asie du Sud a Vepoque des grandes decouvertes, London, 1985. Hourani, George F., rev. and expanded by John Carswell, Arab seafaring in the Indian Ocean in ancient and medieval times, Princeton, 1951, 1995. Pearson, Michael, 'Gateways to Africa: The Indian Ocean and the Red

Sea', in Randall

Pouwels and Nehemia Levtzion (eds.), History of Islam in Africa, Athens, OH, 2000,

PP-3759-

The Indian Ocean, London, 2003.

Risso, Patricia, Merchants and faith: Muslim commerce and culture in the Indian Ocean, Boulder,

CO, 1995.

Wink, Andre, Al Hind: The making of the Indo Islamic World, 3 vols., Leiden, 1990 2004.

Wright, H. T., 'Trade and politics on the eastern littoral of Africa, AD 800 1300', in

Thurstan Shaw (ed.), The archeology of Africa: Food, metals and towns, London, 1993,

pp. 658 72-

The Swahili coast

Horton, Mark and Middleton, John, The Swahili: The social landscape of a mercantile society,

Oxford, 2000.

Martin, B. G., Arab migration to East Africa in medieval times', International Journal of

African Historical Studies, 7 (1975), pp. 367 90.

Pearson, Michael, Port cities and intruders: The Swahili Coast, India, and Portugal in the early

modern era, Baltimore, 1998.

The Maldives

Forbes, Andrew D. W., 'Southern Arabia and the Islamicisation of the central Indian Ocean

archipelagos', Archipel, 21 (1981), pp. 55 92.

Gabriel, Theodore, 'Islamic mystics of the Lakshadweep islands, India', in Theodore

P. Gabriel and C. H. Partridge (eds.), Mysticisms east and west, Carlisle, 2003,

PP-4453-

Maloney, Clarence, People of the Maldive islands, Bombay, 1980.

Malabar

Bouchon, G., 'Quelques aspects de l'islamisation des regions maritimes de l'Inde a l'epoque

medievale (Xlle XVIe s.), Purusartha, 9 (1986), pp. 29 36.

'Regent of the sea': Cannanore's response to Portuguese expansion, 1507 1528, Delhi, 1988.

Dale, Stephen Frederic, Islamic society on the South Asian frontier: The Mappilas of Malabar,

1498 1922, Oxford, 1980.

Engineer, Asghar Ali (ed.), Kerala Muslims: A historical perspective, Delhi, 1995.

Miller, R. E., Mappila Muslims of Kerala, Madras, 1976.

Sri Lanka

Gunawardana, R. A. L. H., 'Changing patterns of navigation in the Indian Ocean and their

impact on pre colonial Sri Lanka', in Satish Chandra (ed.), The Indian Ocean:

Explorations in history, commerce and politics, New Delhi, 1987, pp. 5489.

Mohan, Vasundhara, Muslims in Sri Lanka, Jaipur, 1985.

652

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Wink, Andre, Al Hind: The making of the Indo Islamic World, 3 vols., Leiden, 1990 2004.

#### Coromandel

Arasaratnam, Sinnappah, 'The Chulia Muslim merchants in Southeast Asia, 1650 1800', in

Sanjay Subrahmanyam (ed.), Merchant networks in the early modern world, Aldershot,

1996, pp. 159 77-

Bayly, Susan, 'Islam in southern India: "Purist" or "syncretic"?', in C. A. Bayly and

D. H. A. Kolff (eds.), Two colonial empires: Comparative essays on the history of India

and Indonesia in the nineteenth century, Leiden, 1986, pp. 35-73. More, J. B. P., Muslim identity, print culture and the Dravidian factor in Tamil Nadu,

New Delhi, 2004.

Uwise, M. M., Muslim contribution to Tamil literature, Madras, 1990.

Primary sources

Barbosa, Duarte, A description of the coasts of East Africa and Malabar in the beginning of the 16th

century, trans. Henry E.J. Stanley, Hakluyt Society, 35, London, 1866. The book of Duarte Barbosa: An account of the countries bordering on the Indian Ocean and their

inhabitants, trans, and ed. Mansel Longworth Dames, Hakluyt Society, ser. 2, nos. 44,

49, 2 vols., London, 1918 21.

Ibn Battuta, The travels oflbn Battuta, trans. H. A. R. Gibb, Hakluyt Society, ser. 2, nos. no,

117, 141, 178, 4 vols., London, 1958 94.

Ibn Muhammad Ibrahim, The ship of Sulaiman, trans. John O'Kane, Persian Heritage Series,

n, London, 1972.

Major, R. H. (ed.), India in the fifteenth century: Being a collection of narratives of voyages to India

in the century preceding the Portuguese discovery of the Cape of Good Hope; from Latin,

Persian, Russian, and Italian sources, now first translated into English, Hakluyt Society, 22,

London, 1857.

Pires, Tome, The Suma oriental of Tome Pires, trans, and ed. A. Cortesao, Hakluyt Society,

ser. 2, nos. 89 and 90, 2 vols., London, 1944.

Pyrard, Francois, The voyage of Francois Pyrard of Laval to the East Indies, the Maldives, the

Moluccas and Brazil, trans, and ed. Albert Gray, Hakluyt Society, nos. 76, 77, 80, 2 vols.,

London, 1887 9.

Tibbetts, G. R., Arab navigation in the Indian Ocean before the coming of the Portuguese: Being a

translation of Kitab al Faw 'id fi uSul al bahr wa'l qawa'id of Ahmad b. Majid al Najdi;

together with an introduction on the history of Arab navigation, notes on the navigational

techniques and on the topography of the Indian Ocean and a glossary of navigational terms,

London, 1971.

Zayn al Dm, Tohfut ul Mujahideen, trans. M.J. Rowlandson, London, 1833.

Secondary sources

Ahmad, Rizwan A., 'The state and national foundation in the Maldives', Cultural Dynamics,

13 (2001), pp. 293 315.

Asghar Ali Engineer, 'Kerala Muslims in historical perspective: An introduction', in Asghar

Ali Engineer (ed.), Kerala Muslims: A historical perspective, Delhi, 1995, pp. 116.

653

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

## **Bibliography**

Bayly, Susan, Saints, goddesses and kings: Muslims and Christians in south Indian society

lyoo 1900, Cambridge, 1989.

Bhattacharya, Bhaswati, 'The Chulia merchants of southern Coromandel in the eighteenth

century: A case for continuity', in Om Prakash and Denys Lombard (eds.), Commerce

and culture in the Bay of Bengal, 1500 1S00, Delhi, 1999. Dale, Stephen F., 'Trade, conversion and the growth of the Islamic community of Kerala,

south India', Studia Islamica, 71 (1990), pp. 155-75. Fanselow, Franks., 'Muslim society in Tamil Nadu (India): An historical perspective',

Journal of the Institute of Minority Muslim Affairs, 10 (1989), pp. 264-89. Forbes, Andrew, 'Sources towards a history of the Laccadive islands', South Asia, 2 (1979),

pp. 130 50.

Gabriel, Theodore P. C, Hindu Muslim relations in north Malabar, 1498 1947, Lewiston, NY,

1996.

Iwata, K., Religions and cultures of Sri Lanka and south India, Osaka, 1984.

John, K. J., 'The Muslim Arabs and mosque architecture in Malabar', in Asghar Ali Engineer

(ed.), Kerala Muslims: A historical perspective, Delhi, 1995, pp. 47 55. Kunju, A. P. Ibrahim, 'Origin and spread of Islam in Kerala', in Asghar Ali Engineer (ed.),

Kerala Muslims: A historical perspective, Delhi, 1995, pp. 17-23. McPherson, Kenneth, 'Chulias and Klings: Indigenous trade diasporas and European

penetration of the Indian Ocean littoral', in Giorgio Borsa (ed.), Trade and politics in

tfte Indian Ocean: Historical and contemporary perspectives, Delhi, 1990, pp. 33 46.

Mines, Mattison, Muslim merchants: The economic behaviour of a Muslim Indian community,

New Delhi, 1972.

Nainar, S. Muhammad Husayn, Arab geographers' knowledge of southern India, Madras, 1942.

Shulman, David and Subrahmanyam, Sanjay, 'Prince of poets and ports: Citakkati, the

Maraikkayars and Ramnad, ca 1690 1710', in Anna Libera Dallapiccola and Stephanie

Zingel Ave Lallaemant (eds.), Islam and the Indian regions, vol. I, Stuttgart, 1993,

PP-497 535-

Subrahmanyam, Sanjay, 'Noble harvest from the sea: Managing the pearl fishery of

Mannar, 1500 1925', in Burton Stein and Sanjay Subrahmanyam (eds.), Institutions

and economic change in South Asia, Delhi, 1996, pp. 134 72. 'Diversity in South Asian Islam', Akhbar, 5 (2002), www.indowindow.com/akhbar/

article.php?article=i32&category=4&issue=i9. Vitharana, V., Sri Lankan Maldivian cultural affinities, Polgasovita, 1997.

10 Early Muslim expansion in South-East Asia, eighth

to fifteenth centuries

Geoff Wade

Practical suggestions for further reading

Islam in South East Asia to the fifth/ eleventh century Ferrand, Gabriel, Relations de voyages et textes geographiques, arabes, persans et turks relatifs a

VExtreme Orient du VIII au XVIII siecles, Paris, 1912. Freeman Grenville, G. S. P., The East African coast: Select documents from the first to the earlier

nineteenth century, Oxford, 1962.

# Cambridge Histories Online © Cambridge University Press, 201 1

# **Bibliography**

Hourani, George, Arab seafaring in the Indian Ocean in ancient and early medieval times.

Princeton, 1951.

Laffan, Michael, Finding Java: Muslim nomenclature of insular Southeast Asia from Srivijaya to

Snouk Hurgronje, Asia Research Institute Working Paper Series, 52, Singapore,

Nov. 2005.

Tibbetts, G. R., A study of the Arabic texts containing material on South East Asia, Leiden, 1979.

Islam in South East Asia from the fifth /eleventh to the seventh/thirteenth centuries

Chen Da sheng (chief ed.), Quan zhou Yi si Ian jiao shi fee (Islamic stone inscriptions from Quan zhou), Quan zhou, 1984.

Hirth, Friedrich and Rockhill, W. W., Chauju Kua: His work on the Chinese and Arab trade in the

twelfth and thirteenth centuries, entitled Chufan ch'i, St Petersburg, 1911, repr. Taipei, 1970.

Kuwabara, Jitsuzo, 'On P'u Shou keng: A man of the Western regions, who was the

superintendent of the trading ships' office in Ch'iian chou towards the end of the

Sung dynasty, together with a general sketch of trade of the Arabs in China during

the T'ang and Sung eras', Memoirs of the Research Department of the Toyo Bunko, 2 (1928),

pp. 1 79, and 7 (i935), PP- 1 104-

Lo Hsiang lin, 'Islam in Canton in the Sung period: Some fragmentary records', in F. S. Drake

and Wolfram Eberhard (eds.), Symposium on historical, archaeological and linguistic studies

on southern China, South east Asia and the Hong Kong region, Hong Kong, 1967.

Salmon, Claudine, 'Srivijaya, la Chine et les marchands chinois, X e XII e : Quelques

reflexions sur la societe de l'empire sumatranais', Archipel, 63 (2002), pp. 57 78.

Islam in South East Asia from the eighth/fourteenth to

the ninth/fifteenth centuries

Cortesao, Armando, The Suma oriental of Tome Pires: An account of the East, from the Red Sea to

Japan, written in Malacca and India in 1512 15, Hakluyt Society, 2 vols., London, 1944.

Damais, Louis Charles, 'Etudes javanaises: Les tombes musulmans datees de Tralaya',

Bulletin de VEcole Francaise d'Extreme Orient, 48 (1956), pp. 353 415. 'L'epigraphie musulmane dans le Sud Est Asiatique', Bulletin de VEcole Francaise

d'Extreme Orient, 56 (1968), pp. 567 604.

Gibb, H. A. R., The travels oflbn Battuta AD 1325 1354, trans, with revisions and notes from the

Arabic text, ed. C. Defremery and B. R. Sanguinetti, Hakluyt Society, 4 vols., London,

1958 1994.

Graaf, H.J. de and Pigeaud, G.Th. (trans.), Chinese Muslims in Java in the tyth and 16th

centuries: The Malay Annals of Semarang and Cerbon, ed. M. C. Ricklefs, Monash Papers

on Southeast Asia, 12, Melbourne, 1984.

Guillot, Claude and Kalus, Ludvik, Les monuments funeraires et I'histoire du sultanat de Pasai a

Sumatra, Cahier d' Archipel, 37, Paris, 2008.

Mills, J. V. G. (trans, andannot.), MaHuan: Yingyai Sheng Ian: The overall survey of the ocean's

shores, Cambridge, 1970.

Reid, Anthony, Southeast Asia in the age of commerce 1450 1680, vol. II: Expansion and crisis,

New Haven, 1993.

Wink, Andre, Al Hind: The making of the Indo Islamic world, 3 vols., Leiden, 1990 2004.

655

Cambridge Histories Online © Cambridge University Press, 201 1

**Bibliography** 

Primary sources

Brakel, L. F., The hikayat Muhammad Hanafiyyah: A medieval Muslim Malay romance,

Bibliotheca Indonesica, 12, The Hague, 1975.

Chen Da Sheng, 'A Brunei sultan in the early 14th century: Study of an Arabic gravestone',

Journal of Southeast Asian Studies, 23, 1 (1992), pp. 1 13. Chen Da sheng and Kalus, Ludvik, Corpus d'inscriptions arahes etpersanes en Chine, 1. Province

de Fujian (Quan zhou, Fu zhou, Xia men), Paris, 1991. Chen Da sheng and Salmon, Claudine, 'Rapport preliminaire sur la decouverte de tombes

musulmanes dans l'lle de Hainan', Archipel, 38 (1989), pp. 75 106. Hill, A. H., 'Hikayat Raja raja Pasai', Journal of the Malaysian Branch of the Royal Asiatic

Society, 33, 2 (June i960).

Kalus, Ludvik, 'Le plus ancienne inscription islamique du monde malais?', Archipel, 59

(2000), pp. 23 4.

'Reinterpretation des plus anciennes steles funeraires islamiques nousantariennes: I. Les

deux inscriptions du "Champa", Archipel, 66 (2003). Kalus, Ludvik and Guillot, Claude, 'Reinterpretation des plus anciennes steles funeraires islamiques nousantariennes: II. La stele de Leran (Java) datee de 475/1082 et les steles

associees', Archipel, 67 (2004), pp. 17 36.

Mills, J. V. G. and Ptak, Roderich, Using ch'a Sheng Ian: The overall survey of the Star Raft by

Fei Hsin, South China and Maritime Asia Series, 4, Wiesbaden, 1996. Montana, Suwedi, 'Nouvelles donnees sur les royaumes de Lamuri et Barat', Archipel, 53

(i997), PP- 85 96-

Tibbetts, G. R., Arab navigation in the Indian Ocean before the coming of the Portuguese, Royal

Asiatic Society Oriental Translation Fund, N. S. XLIII, London, 1971. Wade, Geoff, 'Melaka in Ming dynasty texts', Journal of the Malaysian Branch of the Royal

Asiatic Society, 70, 1 (1997), pp. 31 69.

Wang Gungwu, 'The Nanhai trade: A study of the early history of Chinese trade in

South China Sea', Journal of the Royal Asiatic Society; Malaysian Branch, 31 (1958),

pp. 1 135.

Wu Wen liang \$J3t S. and Wu You xiong 'jki)]f\$E, Quan zhou zongjiao shi fee TfcjH'fe'lit

-fl Sll (Religious Inscriptions in Quan zhou), Beijing, 2005. Yule, Henry (trans, and ed.), The book of Ser Marco Polo the Venetian concerning the kingdoms

and marvels of the Fast, 2 vols., 3rd edn, London, 1929.

Secondary sources

al Attas, Syed Naquib, Preliminary statement on a general theory of the Islamization of the Malay

Indonesian Archipelago, Kuala Lumpur, 1963.

Bousquet, Georges Henri, Introduction a Vetude de ITslam indonesien, Paris, 1938.

'Islam and local traditions: Syncretic ideas and practices', Indonesia and the Malay World,

32, 92 (2004), pp. 5 20.

Casparis, J. G. de, 'Historical writing on Indonesia (early period)', in D. G. E. Hall (ed.),

Historians of South East Asia, London, 1961, pp. 121 63. Chafee, John, 'Diasporic identities in the historical development of the maritime Muslim

communities of Song Yuan China', Journal of Economic and Social History of the Orient,

49, 4 (2006), pp. 395 420.

656

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Chang Pin tsun, 'The first Chinese diaspora in Southeast Asia in the fifteenth century', in

Roderich Ptak and Dietmar Rothermund (eds.), Emporia, commodities and entrepreneurs

in Asian maritime trade, c. 1400 rj%o, Stuttgart, 1991, pp. 13 28. Coatalen, Paul, 'The coming of Islam to SE Asia: A critical review of some extant theories',

Islamic Quarterly, 25, 34 (1981), pp. 00 21.

Di Meglio, Rita Rose, Arab trade with Indonesia and the Malay peninsula from the th to the

16th century', in D. S. Richards (ed.), Islam and the trade of Asia: A colloquium, Oxford,

1970.

Drewes, G. W.J., 'New light on the coming of Islam to Indonesia?', Bijdragen tot de Taal,

Land en Volkenkunde, 124 (1968), pp. 433 59. Eaton, Richard M., The rise of Islam and the Bengal frontier, 1204 1760, Berkeley and Los Angeles, 1993.

India's Islamic traditions, 711 1750, New Delhi, 2005.

Evans, IvorH.N., A grave and megaliths in Negri Sembilan with an account of some

excavations', Journal of the Federated Malay States Museums, 9, 3 (1921), pp. 155 73.

Fan Ke, 'Maritime Muslims and Hui identity: A south Fujian case', Journal of Muslim

Minority Affairs, 21, 2 (2001), pp. 309 32.

Fatimi, S. Q., Islam comes to Malaysia, Singapore, 1963.

Feener, R.Michael and Laffan, Michael F., 'Sufi scents across the Indian Ocean: Yemeni

hagiography as a source for the earliest history of Southeast Asian Islam', Archipel, 70

(2005), pp. 185 208.

Flecker, Michael, A ninth century AD Arab or Indian shipwreck in Indonesia: First

evidence for direct trade with China', World Archaeology, 32, 3 (Feb. 2001),

pp. 335 54-

Freeman Grenville, G. S. P., The Swahili coast, 2nd to 19th centuries: Islam, Christianity and

commerce in eastern Africa, London, 1988.

Gommans, Jos and Leider, Jacques (eds.), The maritime frontier of Burma: Exploring political,

cultural and commerial interaction in the Indian Ocean world, 1200 1800, Leiden, 2002.

Gonda, J., Sanskrit in Indonesia, New Delhi, 1973.

Gordon, Alijah (ed.), The propagation of Islam in the Indonesian Malay archipelago, Kuala

Lumpur, 2001.

Graaf, H.J. de, 'South East Asian Islam to the eighteenth century', in P.M. Holt, Ann

K. S. Lambton and Bernard Lewis (eds.), The Cambridge history of Islam, vol. II: The

further Islamic lands, Islamic society and civilization, Cambridge, 1970, pp. 123 54.

Hooker, M. B. (ed.), Islam in South East Asia, Leiden, 1983. Ibrahim, Ahmad, Siddique, Sharon and Hussain, Yasmin (eds.), Readings on Islam in

Southeast Asia, Singapore, 1986.

Ibrahim Kunju, A.P., 'Origin and spread of Islam in Kerala', in Ashgar Ali Engineer (ed.),

Kerala Muslims: A historical perspective, New Delhi, 1995, pp. 1734. Israeli, Raphael and Johns, Anthony H. (eds.), Islam in Asia, vol. II: Southeast and East Asia,

Boulder, CO, 1984.

Johns, A. H, 'Sufism as a category in Indonesian literature and history', Journal of Southeast

Asian History, 2, 2 (July 1961), pp. 1023.

'Modes of Islamization in Southeast Asia', in David N. Lorenzen (ed.), Religious change

and cultural domination, 30th international congress of human sciences in Asia and North

Africa, Mexico City, 1981, pp. 60 77.

657

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Islam in the Malay world: An exploratory survey with some reference to Quranic

exegesis', in Raphael Israeli and A. H. Johns (eds.), Islam in Asia, vol. II: Southeast

and East Asia, Boulder, CO, 1984, pp. 37 49. Kern, R. A., De Islam in Indonesie, The Hague, 1947.

'The propagation of Islam in the Indonesian Malay archipelago', in Alijah Gordon (ed.),

The propagation of Islam in the Indonesian Malay archipelago, Kuala Lumpur, 2001,

pp. 23 124.

Kumar, AnnL., 'Islam, the Chinese and Indonesian historiography a review article',

Journal of Asian Studies, 46, 3 (Aug. 1987), pp. 603 16. Lambourn, Elizabeth, 'From Cambay to Pasai and Gresik the export of Gujarati grave

memorials to Sumatra and Java in the 15th century AD', Indonesia and the Malay World,

31, 90 (2003), pp. 221 89.

'La production de marbre sculpte a Cambaye au Gujarat et son exportation dans l'Ocean

Indien (XHIe XVe siecles Ap.J. C.)', in J. M. dos Santos Alves, C. Guillot and R. Ptak

(eds.), Mirabilia Asiatica: Produtos raros no comercio maritimo. Produits rares dans le

commerce maritime. Seltene Waren im Seehandel, Wiesbaden and Lisbon, 2003,

pp. 209 52.

'The formation of the batu Aceh tradition in fifteenth century Samudera Pasai', Indonesia

and the Malay World, 32 (2004), pp. 211 48.

Leslie, Donald Daniel, Islam in traditional China: A short history to 1800, Canberra, 1986.

Lombard, Denys and Salmon, Claudine, 'Islam and Chineseness', Indonesia, 57 (April 1994),

pp. 115 32, repr. in Alijah Gordon (ed.), The propagation of Islam in the Indonesian Malay

archipelago, Kuala Lumpur, 2001, pp. 181 208. Maejima Shinji, 'The Muslims in Ch'tian chou at the end of the Yuan dynasty' (I & II),

Memoirs of the Research Department of the Toyo Bunko, 31 (1973), pp. 27 52 and 32 (1974),

pp. 47 72.

Manguin, Pierre Yves, 'The introduction of Islam into Champa', Journal of the Malaysian

Branch of the Royal Asiatic Society, 58, 1 (1985), pp. 1 28; repr. in Alijah Gordon (ed.), The

propagation of Islam in the Indonesian Malay archipelago, Kuala Lumpur, 2001, pp. 288 328.

Marrison, G. E., 'The coming of Islam to the East Indies', Journal of the Malaysian Branch of

the Royal Asiatic Society, 24, 1 (Feb. 1951), pp. 28 37.

'Persian influences in Malay life', Journal of the Malaysian Branch of the Royal Asiatic

Society, 28, 1 (1955), pp. 52 69.

Miksic, John, 'From megaliths to tombstones: The transition from prehistory to the early

Islamic period in highland west Sumatra', Indonesia and the Malay World, 32, 93 (July

2004), pp. 191 210.

Moquette, J. P., 'De datum op den grafsteen van Malik Ibrahim te Grisse', Tijdschrift voor

Indische Taal, Land en Volkenkunde, 54 (1912), pp. 208-14. Pigeaud, Theodore G. Th. and de Graff, H.J., Islamic states in Java 1500-1700, The Hague,

1976.

Ray, Haraprasad, Trade and diplomacy in India China relations: A study of Bengal during the

fifteenth century, New Delhi 1993.

Reid, Anthony, Southeast Asia in the age of commerce 1450 1680, vol. I: The lands below the

winds, New Haven and London, 1988.

'The rise and fall of Sino Javanese shipping', in V.J. H. Houben, H.M.J. Maier and

W. van der Molen (eds.), Looking in odd mirrors: The Java Sea, Leiden, 1992, pp. 177 211.

# Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

'The Islamization of Southeast Asia', in Anthony Reid (ed.), Charting the shape of early

modern Southeast Asia, Chiang Mai, 2000, pp. 15 38.

Ricklefs, M. C,, 'Islamization in Java: An overview and some philosophical considerations',

in R. Israeli and A. H. Johns (eds.), Islam in Asia, vol. II: Southeast and East Asia,

Boulder, CO, 1984, pp. 11 24.

A history of modern Indonesia since c. 1200, 3rd edn, Basingstoke, 2001. Rinkes, D. A., Nine saints of Java, trans. H.M. Froger, ed. Alijah Gordon, Kuala Lumpur,

1996.

Risso, Patricia, Merchants and faith: Muslim commerce and culture in the Indian Ocean, Boulder,

CO, 1995.

Seiji, Imanaga, Islam in Southeast Asia, Hiroshima, 2000.

Slamet Muljana, Runtuhnja keradjaan Hindu Djawa dan timbulnja negara negara Islam di

Nusantara, Jakarta, 1968.

'Islam before the foundation of the Islamic state of Demak', Journal of the South Seas

Society, 27, 1 and 2 (1972), pp. 41 83.

So, Billy K. L., Prosperity, region, and institutions in maritime China: The south Fukien pattern,

946 1368, Cambridge, MA, 2000.

Tan Yeok Seong, 'Chinese element in the Islamisation of Southeast Asia: A study of the

story of Njai Gede Pinatih, the Great Lady of Gresik', Journal of the South Seas Society,

30, 1 and 2 (1975).

Teeuw, A., 'The history of the Malay language: A preliminary survey', Bijdragen tot de Taal,

Land en Volkenkunde, 115 (1959), pp. 138 61.

Tibbetts, G. R., 'Early Muslim traders in South East Asia', Journal of the Malaysian Branch of

the Royal Asiatic Society, 30 (1957), pp. 145.

Wake, Christopher, 'Malacca's early kings and the reception of Islam', Journal of Southeast

Asian History, 5, 2 (Sept. 1964), pp. 104 28.

'Melaka in the fifteenth century: Malay historical traditions and the politics of

Islamization', in Kernial Singh Sandhu and Paul Wheatley (eds.), Melaka: The trans

formation of a Malay capital c. 1400 19S0, Kuala Lumpur, 1983, vol. I, pp. 128 61.

Wang Gungwu, 'The opening of relations between China and Malacca 1403 05', in

J. S. Bastin and R. Roolvink (eds.), Malayan and Indonesian studies: Essays presented to

Sir Richard Windstedt, London, 1964.

'Early Ming relations with Southeast Asia: A background essay', in John K. Fairbank

(ed.), The Chinese world order, Cambridge, MA, 1968, pp. 34 62. 'The first three rulers of Malacca', Journal of the Malaysian Branch of the Royal Asiatic

Society, 41, 1 (1968), pp. 11 22.

Wilkinson, R.J., 'The Pengkalan Kempas "saint"', Journal of the Malayan Branch Royal Asiatic

Society, 9, 1 (1931), pp. 134 5-

11 Follow the white camel: Islam in China to 1800 Zvi Ben-Dor Benite

Practical sugggestions for further reading

Ben Dor Benite, Zvi, The Dao of Muhammad: A cultural history of Muslims in late imperial

China, Harvard East Asian Monographs, 248, Cambridge, MA, 2005.

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Chang, JingQi, 'Islamic architecture in China', in Brian Brace Taylor (ed.), The changing

rural habitat, vol II: Background papers, Singapore, 1982. Clark, Hugh, Community, trade and networks: Southern Fujian province from the third to the

thirteenth century, Cambridge, 2002.

Fletcher, Joseph, Studies on Chinese and Islamic Inner Asia, ed. Beatrice Forbes Manz,

London, 1995.

Forbes, Andrew D. W., Warlords and Muslims in Chinese Central Asia, Cambridge, 1986.

Franke, Herbert and Twitchett, Denis, The Cambridge history of China, vol. VI: Alien regimes

and border states, yw 1368, Cambridge, 1994.

Gladney, DruC, Muslim Chinese: Ethnic nationalism in the People's Republic, 2nd edn,

Cambridge, MA, 1996.

Israeli, Raphael, and Gorman, Lyn, Islam in China: a critical bibliography, Bibliographies and

Indexes in Religious Studies, 29, Westport, CT. Leslie, Donald, Daye, Yang, and Yousef, Ahmed, Islam in traditional China: A bibliographical

guide, Monumenta Serica Monograph Series, 54, Sankt Augustin. Li Xinghua, Huibin Qin, Jinyuan Feng and Qiuzhen Sha, Zhongguo Yisilanjiao shi = History

of Islam in China, Beijing, 1998.

Lipman, Jonathan N., Familiar strangers: A history of Muslims in north west China, Seattle, 1997.

Millward, James A., Eurasian crossroads: A history of Xinjiang, New York, 2007.

Perdue, Peter C, China marches west: The Qing conquest of central Eurasia, Cambridge, MA, 2005.

Qiu Shusen, China's Muslim nationality history, Yinchuan Shi, 1996 (in Chinese).

Rossabi, Morris, China and Inner Asia from 1368 to the present day, London, 1981.

Rudelson, Justin Jon, Oasis identities: Uyghur nationalism along China's Silk Road, New York,

#### 1998.

Sinor, Denis (ed.), The Cambridge history of early Inner Asia, Cambridge, 1990.

Tazaka Kodo, Islam in China: Its introduction and development, Tokyo, 1964 (in Japanese).

#### Primary sources

Chen Dasheng (ed.), Islamic inscriptions in Quanzhou, trans. Chen Enming, Yinchuan and

Quanzhou, 1984.

Dunn, Ross E., The adventures of Von Battuta: A Muslim traveler of the 14th century, Berkeley, 1986,

2nd edn 2005.

Ferrand, Gabriel, Relations de voyages et textes geographiques, Arabes, Persans et Turks relatifs a

I'Extreme Orient du VIII au XVIII siecles, Paris, 1912.

Hafiz Abru (Shihabu'd Din Abdullah bin Lutfullah Al Khwafi), trans. K. M. Maitra,

A Persian embassy to China: Being an extract from Zubdat t tawarikh of Hafiz Abru,

New York, 1970 (1st edn, Lahore, 1934).

Hirth, Friedrich and Rockhill, W. W., Chauju Kua: His work on the Chinese and Arab trade in the

twelfth and thirteenth centuries, entitled Chufan chi, St Petersburg, 1911, repr. Taipei, 1970.

Ma Sai bei (chief ed.), Qing shi hi Mu si lin zi liaoji lu [Collection of references to Muslims in

the Qing shi lu], 4 vols., Lanzhou and Ningxia, 1988.

Mills, J. V. G. (ed.), Ma Huan: YingyaiSheng Ian: 'The overall survey of the ocean's shores' (1433),

Cambridge, 1970.

Murata, Sachiko, Chinese gleams of Sufi light: Wang Tai yii's Great learning of the pure and real

and Liu Chih's Displaying the concealment of the real realm; with a new translation of jami's

Lawa'ihfrom the Persian by William C. Chittick, Albany, NY, 2000.

660

Cambridge Histories Online © Cambridge University Press, 201 1

# Bibliography

Murata, Sachiko, Chittick, William C. and Weiming, Tu, The sage learning of Liu Zhi: Islamic

thought in Confucian terms, Cambridge, MA, 2009. Sulayman al Tajir and Abu Zayd Hasan ibn Yazid, Ancient accounts of India and China, by two

Mohammedan travellers. Who went to those parts in the 9th century; translated from the

Arabic, by the late learned Eusebius Renaudot, London, 1733.

#### Secondary sources

Alles, Elisabeth, Musulmans de Chine: Une anthropologic des Hui du Henan, Recherches

d'histoire et de sciences sociales, 89, Paris, 2000. Allsen, Thomas T., 'The Yuan dynasty and the Uighurs of Turfan in the thirteenth century',

in Morris Rossabi (ed.), China among equals, Berkeley, 1983, pp. 243 80. Atwill, David, The Chinese sultanate: Islam, violence, and the Panthay rebellion, 1856 1873,

Stanford, 2005.

Aubin, Francoise, 'En Islam Chinois: Quels Naqshbandis?' [In Chinese Islam, which

Naqshbandis?], in M. Gaborieau, A. Popovic and T. Zarcone (eds.), Naqshbandis:

Cheminements et situation actuelle d'un ordre mystique musulman, Istanbul and Paris,

1990, pp. 49i 572.

Ben Dor Benite, Zvi, '"Even unto China": Displacement and Chinese Muslim myths of

origin', Bulletin of the Royal Institute for Inter Faith Studies, Winter (2003), pp. 93 114.

'The Marrano emperor: The mysterious bond between Zhu Yuanzhang and the Chinese

Muslims', in Sarah Schneewind (ed.), Long live the emperor!: Uses of the Ming founder

across six centuries of East Asian history, Ming Studies Research Series, 4, Minneapolis,

2008, pp. 275 308.

Chen, Dasheng and Lombard, Denis, 'Foreign merchants in maritime trade in Quanzhou

("Zaitun"): Thirteenth and fourteenth centuries', in Denis Lombard and Jean Aubin

(eds.), Asian merchants and businessmen in the Indian Ocean and China Sea, Oxford, 2000,

pp. 19 23.

Di Cosmo, Nicola, Ancient China and its enemies: The rise of nomadic power in East Asian

history, Cambridge, 2002.

Fan, Ke, 'Maritime Muslims and Hui identity: A South Fujian case', journal of Muslim

Minority Affairs, 11, 2 (2001), pp. 309 32.

Franke, Wolfgang, A note on the ancient Chinese mosques at Xian and Quanzhou, Kuala

Lumpur, 1980.

Gillette, Maris Boyd, Between Mecca and Beijing: Modernization and consumption among urban

Chinese Muslims, Stanford, 2002.

Gladney, Dru C, 'Muslim tombs and ethnic folklore: Charters for Hui identity', Journal of

Asian Studies, 46, 3 (1987), pp. 495 532.

Gladney, DruC. and Ma Shouqian, 'Interpretations of Islam in China: A Hui scholar's

perspective', Journal of Institute for Muslim Minority Affairs, 10, 2 (1989), pp. 475 86.

Haneda, Akira, 'Introduction: The problems of Turkicization and Islamicization of

Turkestan', Acta Asiatica, 34 (1978), pp. 121.

Jaschok, Maria, and Shui, Jingjun, The history of women's mosques in Chinese Islam: A mosque of

their own, London, 2001.

Kim Hodong, Holy war in China: The Muslim rebellion and state in Chinese Central Asia,

1866 i8yy, Stanford, 2003.

661

Cambridge Histories Online © Cambridge University Press, 201 1

#### Bibliography

Kuwabara, Jitsuzo, 'On P'u Shou keng', Memoirs of the Research Department of the Toyo

Bunko, 2 (1928), pp. 1 79, and 7 (1935), pp. 1 104. Mackerras, Colin, The Uighur empire according to the Tang dynastic

histories: A study in

Sino Uighur relations, 744 840, Columbia, SC, 1972. Millward, James A., Beyond the pass: Economy, ethnicity, and empire in Qing Central Asia,

1J59 1864, Stanford, 1998.

Millward, James A. and Perdue, Peter C, 'Political and cultural history of the Xinjiang

region through the late nineteenth century', in Fredericks. Starr (ed.), Xinjiang:

China's Muslim borderland, Armonk, NY, pp. 27 62. Quanzhou Foreign Maritime Museum, (ed.), Symposium on Quanzhou Islam, Quanzhou

1983.

Rossabi, Morris, Khubilai Khan: His life and times, Berkeley, 1988. Sen, Tansen, 'The formation of Chinese maritime networks to southern Asia, 1200 1450',

Journal of the Economic and Social History of the Orient, 49, 4 (2006), pp. 421 53.

Sun Dazhang, Ancient Chinese architecture: Islamic buildings, New York, 2003.

Voll, John O., "Muslim minority alternatives: Implications of Muslim experiences in China

and the Soviet Union', Journal, Institute for Muslim Minority Affairs, 6, 2 (1985), pp. 332 53.

Yang Hongxun, 'A preliminary discussion on the building year of Quanzhou holy tomb and

the authenticity of its legend', in Committee for Protecting Islamic Historical Relics in

Quanzhou and the Research Centre for the Historical Relics of Chinese Culture (eds.),

The Islamic historic relics in Quanzhou, Quanzhou, 1985. Zhang, Jing qui, Mosques of northern China, MIMAR 3: Architecture in Development,

Singapore, 1982.

12 Islam in South-East Asia and the Indian Ocean littoral,

1500-1800: expansion, polarisation, synthesis

Anthony Reid

Practical suggestions for further reading

Andaya, Barbara and Ishii, Yoneo, 'Religious developments in Southeast Asia, c.1500 1800', in

Nicholas Tarling (ed.), Cambridge history of Southeast Asia, Cambridge, 1992, pp. 508 71.

Azra, Azyumardi, The origins of Islamic reformism in Southeast Asia: Networks of Malay

Indonesian and Middle Eastern 'ulama' in the seventeenth and eighteenth centuries,

Sydney, 2004.

Graaf, H.J. de and Pigeaud, Theodore G. Th., Islamic states in Java, 1500 1700, The Hague,

1976-

Ibrahim, Ahmad, Siddique, Sharon, and Hussain, Yasmin (eds.), Readings on Islam in

Southeast Asia, Singapore, 1986.

Lombard, Denys, he carrefour javanais: Essai d'histoire ghbale, Paris, 1990.

Reid, Anthony, Southeast Asia in the age of commerce 1450 1680, vol. II: Expansion and crisis,

New Haven, 1993.

(ed.), Southeast Asia in the early modern era: Trade, power and belief, Ithaca, 1993.

(ed.), The making of an Islamic political discourse in Southeast Asia, Melbourne, 1993.

Ricklefs, M. C,, 'Six centuries of Islamization in Java', in Nehemia Levtzion (ed.), Conversion

to Islam, New York, 1979, pp. 100 28.

662

Cambridge Histories Online © Cambridge University Press, 201 1

#### **Bibliography**

Mystic synthesis in Java: A history of Islamization from the fourteenth to the early nineteenth

centuries, Norwalk, CT, 2005.

Riddell, Peter, Islam and the Malay Indonesian world, Honolulu, 2001.

# Primary sources

Adat Aceh dari Satu manuscript India Office Library, Romanised by Teungku Anzib Lamnyong,

Banda Aceh, 1976.

al Attas, S. M. Naquib, The mysticism of Hamzah Fansuri, Kuala Lumpur, 1970.

Babad Tanah Djawi, Javaanse Rijkskroniek. W. L. Olthofs Vertaling van de prozaversie van

J.J. Meinsma lopende tot hetjaar 1721, rev. ed. J.J. Ras, Dordrecht, 1987. Brown, C. C. (trans.), 'Sejarah Melayu or "Malay Annals'", Journal of the Malaysian Branch of

the Royal Asiatic Society, 25, parts 2 and 3 (1952).

Drewes, G. W.J. (ed. and trans.), Ben Javaanse Primbon uit de Zestiende Eeuw, Leiden, 1945.

(ed. and trans.), The admonitions of Seh Bari: A 16th century Javanese Muslim text attributed to

the Saint ofBonan, The Hague, 1969.

(ed.), An early Javanese code of Muslim ethics, The Hague, 1978. Drewes, G.W.J, and Brakel, L. F. (eds. and trans.), The poems of Hamzah Fansuri,

Dordrecht, 1986.

Fang, Liaw Yock (ed.), Undang undang Melaka/The laws of Melaka, The Hague, 1976.

Galvao, Antonio, A treatise on the Moluccas (c.1344), probably the preliminary version of Antonio

Galvao's lost Historia das Molucas, ed. and trans. Hubert Jacobs, Rome, 1971.

Graaf, H.J. de (ed.), De Vijf Gezantschapsreizen van Rijklof van Goens naar het hof van

Mataram, 1648 1654, The Hague, 1956.

Hikayat Patani: The story of Patani, ed. A. Teeuw and D. K. Wyatt, 2 vols., The Hague, 1970.

Hill, A. H. (ed and trans.), 'The Hikayat Raja raja Pasai', Journal of the Malaysian Branch of the

Royal Asiatic Society, 33, 2 (i960).

Jacobs, Hubert (ed.), Documenta Malucensia, I, 1542 ljjy, Rome, 1974.

(ed.), The Jesuit Makasar documents, 1613 1682, Rome, 1980.

Johns, A. H. (ed. and trans.), The gift addressed to the spirit of the Prophet, Canberra, 1964.

Ma Huan, Ying Yai ShengLan: The overall survey of the ocean's shores, trans. J. V. G. Mills,

Hakluyt Society, Cambridge, 1970.

Major, R. H. (ed.), India in the fifteenth century, being a collection of narratives of voyages to

India, Hakluyt Society, London, 1857.

Nieuwenhuijze, C. A. O. van (ed. and trans.), Samsu'l din van Pasai: Bijdrage tot de Kennis der

Sumatraansche mystiek, Leiden, 1945.

Pinto, Mendes, The travels of Mendes Pinto, ed. Rebecca Catz, Chicago and London, 1989.

Pires, Tome, The Suma oriental of Tome Pires: An account of the east, from the Red Sea to Japan,

written in Malacca and India in 1312 y, ed. Armando Cortesao, Hakluyt Society, 2 vols.,

London, 1944.

Raniri, Nuru'd din ar , Bustanu's Salatan, Bab II, Fasal 13, ed. T. Iskandar, Kuala Lumpur, 1966.

Ras, J. J., The Hikayat Bandjar: A study in Malay historiography, The Hague, 1968.

Ricklefs, M. C., Modern Javanese historical tradition: A study of an original Kartasura chronicle

and related materials, London, 1978.

Riddell, Peter, Transferring a tradition: 'Abd al Ra'ufal Singkili's rendering into Malay of the

Jalalayn commentary, Berkeley, 1990.

663

Cambridge Histories Online © Cambridge University Press, 201 1

**Bibliography** 

Rinkes, D. A., Nine saints of Java, trans. H. M. Froger, ed. Alijah Gordon, Kuala

Lumpur, 1996.

Serjeant, R. B., The Portuguese off the South Arabian coast, Hadhrami chronicles, Oxford,

1963.

Tibbetts, G.R., A study of the Arabic texts containing material on South East Asia,

Leiden, 1979.

Secondary sources

al Attas, Syed Naquib, Preliminary statement on a general theory of the Islamization of the

Malay Indonesian archipelago, Kuala Lumpur, 1963.

Dames, M. Longworth, 'The Portuguese and Turks in the Indian Ocean in the sixteenth

century', Journal of the Royal Asiatic Society (1921).

Fatimi, S. Q., Islam comes to Malaysia, Singapore, 1963.

Gordon, Alijah (ed.), The propagation of Islam in the Indonesian Malay archipelago, Kuala

Lumpur, 2001.

Graaf, H.J. de, De regering van Panembahan Senapati Ingalaga, The Hague, 1954.

De Regering van Sultan Agung, vorst van Mataram, 1613 164% en die van zijn voorganger

Panembahan Seda ingKrapjak, 1601 1613, The Hague, 1958. De regering van Sunan Mangkurat I Tegal Wangi, vorst van Mataram, 1646 1677, The Hague,

1961.

'South East Asian Islam to the eighteenth century', in P. M. Holt, Ann K S. Lambton and

Bernard Lewis (eds.), The Cambridge history of Islam, vol. II: The further Islamic lands,

Islamic society and civilization, Cambridge, 1970, pp. 123 54. Guillot, Claude and Kalus, Ludvik, 'La stele funeraire de Hamzah Fansuri', Archipel,

60 (2000), pp. 3 24.

Hadi, Amirul, Islam and state in Sumatra: A study of seventeenth century Aceh, Leiden, 2004.

Hooker, M. B. (ed.), Islam in South East Asia, Leiden, 1983.

Israeli, Raphael and Johns, Anthony H. (eds.), Islam in Asia, vol. II: Southeast and East Asia,

Boulder, CO, 1984.

Ito, Takeshi, 'The world of the Adat Aceh: A historical study of the sultanate of Aceh',

Ph.D. thesis, Australian National University, 1984.

Lombard, Denys, Le sultanat d'Atjeh au temps d'Iskandar Muda i6oy 1636, Paris, 1967.

Naimur Rahman Farooqi, 'Mughal Ottoman relations: A study of political and diplomatic

relations between Mughal India and the Ottoman empire, 1556 1748', Ph.D. disserta

tion, University of Wisconsin, 1986.

Reid, Anthony, Southeast Asia in the age of commerce 1450 1680, vol. I: The lands below the

winds, New Haven and London, 1988.

'The Islamization of Southeast Asia', in Anthony Reid (ed.), Charting the shape of early

modern Southeast Asia, Chiang Mai, 2000, pp. 15 38.

An Indonesian frontier: Acehnese and other histories of Sumatra, Singapore, 2004.

Ricklefs, M. C, Seen and unseen worlds in Java: History, literature, and Islam in the court of

Pakubuwana II, 1726 1749, Honolulu, 1998.

A history of modern Indonesia since c. 1200, 3rd edn, Basingstoke, 2001. Zoetmulder, P. J., Pantheism and monism in Javanese Suluk literature: Islamic and Indian

mysticism in an Indonesian setting, trans. M. C. Ricklefs, Leiden, 1995.

664

Cambridge Histories Online © Cambridge University Press, 201 1

**Bibliography** 

13 South-East Asian localisations of Islam and participation

within a global umma, c. 1500-1800

R. Michael Feener

Practical suggestions for further reading

Azra, Azyumardi, The origins of Islamic reformism in Southeast Asia: Networks of Malay

Indonesian and Middle Eastern 'ulama^ in the seventeenth and eighteenth centuries, Crows

Nest, NSW, 2004.

Ricklefs, M. C, Mystic synthesis injava: A history oflslatnization from the fourteenth to the early

nineteenth centuries, Norwalk, CT, 2005.

Riddell, Peter, Islam in the Malay Indonesian world: Transmission and responses, Honolulu,

2001.

Primary sources

#### Arabic

al 'Ahdal, 'Abd al Rahman b. Sulayman, al Nafas al yamam, San'a', 1979. Fathurahman, Oman (ed. and trans.), Tanbih al Masyi: Menyoal Wahdatul Wujud, Kasus

Abdurrauf Singkel di Aceh Abad ly, Bandung, 1999. Johns, A. H. (ed. and trans.), The gift addressed to the Spirit of the Prophet, Canberra,

1964.

Lubis, Nabilah (ed. and trans.), Syekh Yusuf al Taj al Makasari Menyingkap Intisari Segala

Rahasia, Bandung, 1996.

van Nieuwenhuijze, C. A. O. (ed. and trans.), Samsu'l Dm van Pasai: Bijdrage tot de Kennis der

Sumatraansche Mystiek, Leiden, 1945.

Tudjimah (ed.), Syekh Yusuf Makasar: Riwayat dan Ajarannya, Jakarta, 1997.

al Yafi'i [al Yamam al Makki], Abu Muhammad Abd Allah b. As'ad b. Ah b. Sulayman

Af if al Dm, Mifat aljinan wa 'ibrat al yaqzan, Haydarabad, 1919 20.

South East Asian languages

Aad, Janson, Tol, Roger and Witkam, Jan Just, Mystical illustrations from the teachings

of Syaikh Ahmad Al Qusyasyi: A facsimile edition on paper and CD ROM of a

manuscript from Aceh (Cod. Or. 2222) in the Library of Leiden University, Leiden,

1995-

al Attas, Syed Muhammad Naquib (ed.), The oldest known Malay manuscript: A 16th century

Malay translation of the 'Aqa'id of al Nasafi, Kuala Lumpur, 1988. al Banjan, Muhammad Arshad b. Abd Allah, Sabil al Muhtadin, Singapore, n.d.

al Banjan, Muhammad Naf is b. Idns b. Husayn, al Durr al Nafis, Singapore, n.d.

Braginsky, V. I. (ed.), Tasawuf dan Sastera Melayu: Kajian dan Teks teks, Jakarta, 1993.

Brakel, L. F. (ed.), The Hikayat Muhammad Hanafiah, The Hague, 1975. Brown, C. C. (ed. and trans.), Sejarah Melayu, or Malay Annals, Kuala Lumpur. 1970.

Chambert Loir, Henri and Salahuddin, Siti Maryam R. (eds.), Bo' Sangaji Kai: Catatan

Kerajaan Bima, Jakarta, 1999.

665

Cambridge Histories Online © Cambridge University Press, 201 1

**Bibliography** 

Drewes, G.W.J, (ed. and trans.), 'Het Document uit den Brandstapel', Djawa, 2 (1927),

pp. 97 109-

(ed. and trans.), Eenjavaanse Primbon uit de Zestiende Eeuw, Leiden, 1945.

(ed. and trans.), Een i6de Eeuwse Maleise Vertaling van de Burda van al Busin, The Hague,

1955-

(ed. and trans.), 'Javanese poems dealing with or attributed to the saint of Bonan',

Bijdragen tot de Taal, Land en Volkenkunde, 124 (1968), pp. 209 40. (ed. and trans.), The admonitions of Seh Bari: A 16th century Javanese Muslim text attributed to

the saint of Bonan, The Hague, 1969.

(ed. and trans.), 'Further data concerning 'Abd al Samad al Palimbani', Bijdragen tot de

Taal, Land en Volkenkunde, 132, 23 (1976), pp. 267 92.

(ed. and trans.), Directions for travelers on the mystic path: Zakariyya al Ansan's Kitab Eath

al Rahman and its Indonesian adaptations, The Hague, 1977.

(ed. and trans.), An early Javanese code of Muslim ethics, The Hague, 1978.

Drewes, G.W.J, and Brakel, L. F. (eds. and trans.), The poems of Hamzah Fansuri,

Dordrecht, 1986.

Fang, Liaw Yock (ed.), Undang undang Melaka/The Laws of Melaka, The Hague, 1976.

al Fatam, Dawud b. 'Abd Allah, al Durr al thamin, Cairo, 1923.

Kifayat al muhtaj, Patani, n.d.

Minhaj al 'abidin, Singapore, n.d.

Johns, A. H. (ed.), 'Daka'ik al Hurufby Abd al Ra'uf of Singkel', Journal of the Royal Asiatic

Society (1953), pp. 55 73, 137 50.

(ed.), 'Nur al Daka'ik by the Sumatran mystic Shamsu'l Din ibn Abdullah', Journal of

the Royal Asiatic Society (1953), pp. 137 51.

Jones, Russell (ed. and trans.), Hikayat Sultan Ibrahim Ibn Adham: An edition of an anonymous

Malay text with translation and notes, Berkeley, 1985.

(ed. and trans.), Hikayat Raja Pasai, Selangor, 1987.

Matthes, B. F. (ed.), Eenige Proeven van Boegineesche en

Makassaarsche Poezie, The Hague, 1883.

(ed.), Makassaarsche Chrestomathie, Amsterdam, 1883.

Millie, Julian (ed. and trans.), Bidasari: Jewel of Malay Muslim culture, Leiden, 2004.

Millies, H. C. (ed.), 'Proeven eener Makassarsche vertaling des Korans ...', Bijdragen tot de

Taal , Land en Volkenkunde, 3 (1856), pp. 89 106. Mulya, Abdul Kadir (ed. and trans.), Surek Pangngajakna Nabita Muhammad SAW nennia

Abdul Ibadi, Jakarta, 1991. al Palimbani, 'Abd al Samad, Hidayat al salikm, Cairo, 1922.

Abd al Samad, Sayr al Salikm, Jakarta, n.d. al Ramri, Nur al Dm Muhammad Jilani b. All b. Hasanji b. Muhammad b. Humayd, Sirat

al Mustaqim f\ fiqh madhhab al Shafi'i, Cairo, 1937. van Ronkel, Ph. S., De Roman van Amir Hamzah, Leiden, 1895. [Singkeli], Abd al Ra'uf b. 'All al Fansuri al Jawi, Tarjuman al mustafid, Cairo, 1951.

Soebardi, S. (ed. and trans.), The book of Cabolek: A critical edition with introduction, translation

and notes, The Hague, 1978.

Tudjimah (ed.), Asrar al Insanfi Ma'rifat al Rub. wa'l Rahman, Jakarta, 1961.

Voorhoeve, P., Twee Maleise Geschriften van Nuruddin arRaniri in facsimile uitgegeven met Aantekeningen, Leiden, 1955.

666

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

Secondary sources

South East Asian history writing Andaya, Barbara Waston, 'Delineating female space: Seclusion and the state in pre modern island Southeast Asia', in Barbara Waston Andaya, Other pasts: Women, gender and

history in early modern Southeast Asia, Honolulu, 2000, pp. 231 53. Andaya, Leonard Y., 'Aceh's contribution to standards of Malayness', Archipel, 61 (2001),

pp. 26 68.

Azra, Azyumardi, 'Opposition to Sufism in the East Indies in the seventeenth and eight

eenth centuries', in Frederick de Jong and Bernd Radtke (eds.), Islamic mysticism

contested: Thirteen centuries of controversies and polemics, Leiden, 1999, pp. 665 86.

van Bruinessen, Martin, 'Shari'a court, tarekat and pesantren: Religious institutions in the

Banten sultanate', Archipel, 50 (1995), pp. 165 200.

Cortesao, Armando (trans.), The Suma oriental of Tome Pires, London, 1944.

Cummings, William, 'Scripting Islamization: Arabic texts in early modern Makassar',

Ethnohistory, 48, 4 (2001), pp. 559 86.

Graaf, H.J. de and Pigeaud, Theodore G. Th., Islamic states injava, you 1700, The Hague, 1976.

Hadi, Amirul, Islam and state in Sumatra: A study of seventeenth century Aceh, Leiden, 2004.

Ho, Engseng, 'Before parochialization: Diasporic Arabs cast in Creole waters', in

Huub de Jonge and Nico Kaptein (eds.), Transcending borders: Arabs, politics, trade,

and Islam in Southeast Asia, Leiden, 2002.

Ito, Takeshi, The world of the Adat Aceh: A historical study of the sultanate of Aceh, Canberra, 1984.

Johns, A. H., 'Islam in Southeast Asia: Reflections and new directions', Indonesia, 19 (1975),

PP- 33 55-

Lombard, Denys, he sultanat d'Atjeh au temps d'Iskandar Muda i6oy 1636, Paris, 1967.

Reid, Anthony, 'Islam and the state in seventeenth century Southeast Asia', in

Taufik Abdullah (ed.), Proceedings of the international seminar on Islamic civilization in

the Malay world, Istanbul, 1997.

Ricklefs, M. C, Seen and unseen worlds injava: History, literature, and Islam in the court of

Pakubuwana II, 1726 1749, Honolulu, 1998.

Islamicate literatures of South East Asia

al Attas, S. N., Raniri and the Wujudiyyah cfiyth century Aceh, Singapore, 1966.

van Bruinessen, Martin, Kitab Kuning, Pesantren, dan Tarekat: Tradisi tradisi Islam di

Indonesia, Bandung, 1995.

Feener, R. Michael and Laffan, Michael F., 'Sufi scents across the Indian Ocean: Yemeni hagiog

raphy and the earliest history of Southeast Asian Islam', Archipel, 70 (2005), pp. 185 208.

Iskandar, Teuku, Kesusasteraan Ylasik Melayu Sepanjang Abad, Jakarta, 1996.

Kumar, Ann and McGlynn, JohnH. (eds.), Illuminations: The writing traditions of Indonesia,

Jakarta, 1996.

Pigeaud, Th., Literature of Java, The Hague, 1967.

Riddell, Peter, Transferring a tradition: 'Abd al Ra'ufal Singkili's rendering into Malay of the

Jalalayn commentary, Berkeley, 1990.

Zoetmulder, P. J., Pantheism and monism in Javanese suluk literature: Islamic and Indian

mysticism in an Indonesian setting, ed. and trans. M. C. Ricklefs, Leiden, 1995.

667

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

14 Transition: the end of the old order -

Iran in the eighteenth century

#### G. R. Garthwaite

Practical suggestions for farther reading

Axworthy, Michael, The sword of Persia: Nader Shah from tribal warrior to conquering despot,

London, 2006.

Halm, Heinz, Shi'ism, Edinburgh, 1991.

Newman, AndrewJ., Safavid Iran: Rebirth of a Persian empire, London, 2006.

Perry, John R., Karim Khan Zand: A history of Iran, 1747 1779, Chicago, 1979.

Tucker, Ernest, Nadir Shah's quest for legitimacy in post Safavid Iran, Gainesville, FL, 2006.

## Primary sources

Abu'l Hasan b. Muhammad Amm Gulistana, Mujmal al Tavankh Afshariya va Zandiya, ed.

Mudaris Razavi, Tehran, 1344/1966.

Chardin, Sir John, The travels of Sir John Chardin into Persia and riie East Indies, London, 1686.

A chronicle of the Carmelites in Persia and the papal missions of the XVIIth and XVIIIth centuries,

London, 1939.

Fasa'i, Hasan e, History of Persia under Qajar rule (Farsnama ye Naseri), trans. Heribert Busse,

New York, 1972.

Fraser, James, The history of Nadir Shah, London, 1742.

Hanaway, Jonas, An historical account of the British trade over tfte Caspian Sea, London, 1753.

The revolutions of Persia, London, 1754.

Kazim, Muhammad, Namah yi Alam Ara yi 'Nadiri, facsimile, 3 vols., Moscow, i960 6.

Kitab i Nadiri, Leningrad, n.d.

Krusinski, Father Judasz Tadeusz, The history of the revolution of Persia, London, 1728.

Malcolm, Sir John, The history of Persia from the most early period to the present time, London,

1815.

Rabino di Borgomale, H. L., Coins, medals and seals of the shahs of Iran, yoo 1941, Algiers (?), 1945.

Album of coins, medals, and seals of the shahs of Iran, Oxford, 1951.

Secondary sources

Algar, Hamid, Religion and state in Iran ijSk 1906: The role of the ulama in the Qajar period,

Berkeley, 1969.

'Religious forces in eighteenth and nineteenth century Iran', in Peter Avery,

Gavin Hambly and Charles Melville (eds.), The Cambridge history of Iran, vol. VII:

From Nadir Shah to the Islamic Republic, Cambridge, 1991, pp. 705-31. Arjomand, Said Amir, The shadow of God and the hidden imam: Religion, political order, and

societal change in Shi'ite Iran from the beginning to 1&90, Chicago, 1984.

Avery, Peter, 'Nadir Shah and the Afsharid legacy', in Avery, Hambly and Melville (eds.),

Cambridge history of Iran, vol. VII, pp. 3 62.

Babayan, Kathryn, Mystics, monarchs, and messiahs: Cultural landscapes of early modern Iran,

Cambridge, MA, 2002.

Bayat, Mangol, Mysticism and dissent: Socioreligious thought in Qajar Iran, Syracuse, 1982.

668

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

Beck, Lois, The Qashaa'i of Iran, New Haven, 1986.

Black, Antony, The history of Islamic political thought: From the Prophet to tfte present,

Edinburgh, 2001.

Bloom, Jonathan and Blair, Sheila, Islamic arts, London, 1997.

Chelkowski, Peter J. (ed.), Taz'iyeh, ritual and drama in Iran, New York, 1979.

Cole, Juan, Sacred space and holy war: The politics, culture and history of Shi'ite Islam, London,

2002.

Floor, Willem, The Afghan invasion of Safavid Persia, rjn 29, Paris, 1998. Garthwaite, GeneR., Khans and shahs: A documentary analysis of the Bakhtiyari in Iran,

Cambridge, 1983.

The Persians, Oxford, 2005.

Greaves, Rose, 'Iranian relations with the European trading companies, to 1798', in

Avery, Hambly and Melville (eds.), Cambridge history of Iran, vol. VII, pp. 350 73.

Hambly, Gavin, 'Agha Muhammad Khan and the establishment of the Qajar dynasty', in

Avery, Hambly and Melville (eds.), Cambridge history of Iran, vol. VII, pp. 104 43.

'Iran during the reigns of Fath 'All Shah and Muhammad Shah', in Avery, Hambly and

Melville (eds.), Cambridge history of Iran, vol. VII, pp. 144 73.

Kazemzadeh, Firuz, 'Iranian relations with Russia and the Soviet Union, to 1921', in

Avery, Hambly and Melville (eds.), Cambridge history of Iran, vol. VII, pp. 314 49.

Lambton, A. K. S., 'Persia: The breakdown of society', in P. M. Holt, AnnK. S. Lambton

and Bernard Lewis (eds.), The Cambridge history of Islam, vol. I: The central Islamic lands,

Cambridge, 1970.

'The tribal resurgence and the decline of the bureaucracy in the eighteenth century', in

Thomas Naff and Roger Owen (eds.), Studies in eighteenth century Islamic history,

Carbondale, IL, 1977.

State and government in medieval Islam: An introduction to the study of Islamic political theory:

The jurists, Oxford, 1981.

'Concepts of authority in Persia: Eleventh to Nineteenth centuries AD', Iran, 26 (1988),

pp. 102 3.

Continuity and change in medieval Persia, London, 1988. Lockhart, Laurence, Nadir Shah: A critical study, London, 1938.

The fall of the Safavi dynasty and the Afghan occupation of Persia, Cambridge, 1958.

Matthee, Rudolph P., The politics of trade in Safavid Iran: Silk for silver, 1600 1730, Cambridge, 1999.

Iran and the surrounding world: Interactions in culture and cultural politics, Seattle, 2002.

Perry, John R., 'The last Safavids, 1722 1773', Iran, 9 (1971), pp. 59 69.

'Forced migration in Iran during the seventeenth and eighteenth centuries', Iranian

Studies, 8 (1975), pp. 199 215.

'The Zand dynasty', in Avery, Hambly and Melville (eds.), Cambridge history of Iran, vol.

VII, pp. 63 103.

Savory, Roger M., Iran under the Safavids, Cambridge, 1980.

Shaw, Stanford, 'Iranian relations with the Ottoman empire in the eighteenth and nine

teenth centuries', in Avery, Hambly and Melville (eds.), Cambridge history of Iran, vol.

VII, pp. 297 313.

Tapper, Richard, 'The tribes in eighteenth and nineteenth century Iran', in Avery, Hambly

and Melville (eds.), Cambridge history of Iran, vol. VII, pp. 506 41.

669

Cambridge Histories Online  $\ \ \, \mathbb C$  Cambridge University Press, 201 1

# **Bibliography**

Frontier nomads of Iran: A political and social history of the Shahsevan, Cambridge, 1997.

Walbridge, Linda S. (ed.) The most learned of the Shi'a: The institution of the Marja' Taqlid, Oxford, 2001.

15 Conversion to Islam Richard W. Bulliet

Practical suggestions for farther reading

Bulliet, Richard W., Conversion to Islam in the medieval period, Cambridge, 1975.

DeWeese, Devin, Islamization and native religion in the Golden Horde: Baba Tiikles and

conversion to Islam in historical and epic tradition, University Park, PA, 1994.

Eaton, Richard M., The rise of Islam and the Bengal frontier, 1204 1760, Berkeley, 1996.

Levtzion, Nehemia (ed.), Conversion to Islam, New York, 1979.

Minkov, Anton, Conversion to Islam in the Balkans: Kisve bahasi petitions and Ottoman social

life, 1670 1730, Leiden, 2004.

#### Primary sources

Compilation of Hui and Islamic Chinese classical documents, 9 vols., Yinchuan City, n.d.

Ibn Battuta, The travels oflbn Battuta, AD 1325 1354, trans. H. A. R. Gibb, vol. II, Cambridge, 1962.

## Secondary sources

al Attas, S.M. N., Preliminary statement on a general theory of the Islamization of the

Malay Indonesian archipelago, Kuala Lumpur, 1969. Azra, Azyumardi, The origins of Islamic reformism in Southeast Asia: Networks of

Malay Indonesian and Middle Eastern 'ulama' in the seventeenth and eighteenth

centuries, Crows Nest, NSW, 2004.

Bulliet, Richard W., 'Process and status in conversion and continuity', in Michael Gervers

and Ramzi Jibran Bikhazi (eds.), Conversion and continuity: Indigenous Christian com

munities in Islamic lands, eighth to eighteenth centuries, Toronto, 1990, pp. 1 12.

Eaton, Richard M., Approaches to the study of conversion to Islam in India', in Richard

C. Martin (ed.), Approaches to Islam in religious studies, Tucson, 1985, pp. 106 23.

Fatimi, S. Q., Islam comes to Malaysia, Singapore, 1963.

Fletcher, Joseph, 'Les voies (turuq) soufites en Chines', in A. Popovic and G. Veinstein

(eds.), Ordres mystiques dans ITslam: Cheminements et situation actuelle, Paris, 1986.

Gladney, Dru C, Muslim Chinese: Ethnic nationalism in the People's Republic, Cambridge, MA,

1991.

Lawrence, Bruce B., 'Islam in India: The function of institutional Sufism in the Islamization

of Rajasthan, Gujarat, and Kashmir', in Richard C. Martin (ed.), Islam in local contexts,

Leiden, 1982, pp. 2743.

'Early Indo Muslim saints and conversion', in Yohanan Friedmann (ed.), Islam in Asia,

vol. I: South Asia, Boulder, CO, 1984, pp. 109 45.

Leslie, Donald Daniel, Islam in traditional China: A short history to 1800, Canberra, 1982.

Majul, C. A., Muslims in the Philippines, Quezon City, 1979.

670

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

Pillsbury, Barbara, 'Muslim history in China: A 1300 year chronology', in Morris Rossabi

(ed.), China and Inner Asia from 1368 to the present day, London, 1981.

Winstedt, R. O., 'The advent of Muhammadanism in the Malay peninsula and archipelago',

Journal of Malaysian Branch of the Royal Asiatic Society, 77 (1917), pp. 1713.

16 Armies and their economic basis in Iran

and the surrounding lands, c. 1000-1500

Reuven Amitai

Primary sources

Anon., The secret history of the Mongols, trans, and ed. Igor de Rachewiltz, 2 vols., Leiden, 2004.

Baybars al Mansun, Zubdat alfikra, ed. D. S. Richards, Beirut, 1998.

Ibn al Athir, al Kamilfi 'I ta'rxkh, trans, in Donald S. Richards, The Annals of the Saljuq Turks:

Selections from al Kamilfi'l Ta'nkh of'Izz al Dm Ibn al Athir, London, 2002.

Ibn al Furat, Ta'rxkh, vol. VII, ed. Q. Zurayk, Beirut, 1942.

aljahiz, Abu 'Uthmanb. Bahr, Talath rasa'il, ed. G. Van Vloten, Leiden, 1903.

John of Piano Carpini [Giovanni di Pian di Carpine], 'History of the Mongols', in

C. Dawson (ed.), The mission to Asia [repr. of The Mongol mission], London, 1980.

Juwayni, 'Ala' al Dm, Ta'rxkh ijahangusha, trans, in John A. Boyle, The history of the world

conqueror by 'Ala ad Dxn 'Ata Malik Juvainx, 2 vols., Manchester, 1958. al Nasawi al Munshi, Sxrat al sultan jalal al dxn mankubirtx, Cairo, 1953. Nizam al Mulk, Abu Ah b. Hasan Tusi, Siyar al muluk {—Siyasat nama), ed. Hubert Darke,

Tehran, 1962.

Siyar al muluk (=Siyasat nama), trans, in Hubert Darke, The book of government or rules for

kings, 2nd edn, London, 1978.

Rashid al Din al Hamadam, Jami' al tawarxkh, in Karl Jahn (ed.), Geschichte Gazan Han's aus

dem Ta'rxh i Mubarak i Gazanx ..., London, 1940. Jami' al tawarxkh, trans, in W. M. Thackston (trans, and ed.), Rashiduddin Fazhdlah's

Jami'u't tawarikh (Compendium of chronicles), 3 vols., Cambridge, MA, 1999.

Sibt ibn al Jawzi, Mir' at al zaman, Ankara, 1968.

al 'Umari, Ibn Fadl Allah, Masalik al absar, in Klaus Lech (ed. and trans.), Das Mongolische

Weltreich: Al 'Umarxs Darstellung der mongolischen Reiche in seinem Werk Masalik al absar

fx 1 mamalik al amsar, Wiesbaden, 1968. Wassaf, Ta'rxkh, Bombay, 1269 /1852 3.

Secondary sources

Allsen, Thomas T., Mongol imperialism: The policies of the Grand Qan Mbngke in China, Russia,

and the Islamic lands, 1251 1259, Berkeley, 1987.

'The circulation of military technology in the Mongolian empire', in Nicola Di Cosmo

(ed.), Warfare in Inner Asian history (500 1800), Leiden, 2002, pp. 265 94.

Amitai, Reuven, 'The conversion of Tegtider Ilkhan to Islam', Jerusalem Studies in Arabic and

Islam, 25 (2001), pp. 15 43.

'Turco Mongolian nomads and the iqta' system in the Islamic Middle East', in

Anatoly N. Khazanov and Andre Wink (ed.), Nomads in the sedentary world,

Richmond, 2001, pp. 152 71.

671

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

'Whither the Ilkhanid army? Ghazan's first campaign into Syria (1299 1300)', in

Nicola Di Cosmo (ed.), Warfare in Inner Asian history (500 1800), Leiden, 2002.

pp. 220 64.

'The resolution of the Mongol Mamluk war', in Reuven Amitai and Michal Biran (eds.),

Mongols, Turks and others, Leiden, 2005, pp. 359 90.

'The Mamluk institution: 1000 years of military slavery in the Islamic world', in

Christopher L. Brown and Philip D. Morgan (eds.), Arming slaves: From classical

times to riie modern age, New Haven, 2006, pp. 40 78.

'Some more thoughts on the logistics of the Mongol Mamluk war (with special refer

ence to the battle of Wadi al Khaznadar)', in John Pryor (ed.), Logistics of war in the age

of the Crusades, Aldershot, 2006, pp. 25 42.

'An Arabic biographical notice of Kitbugha, the Mongol general defeated at Aynjalut',

Jerusalem Studies in Arabic and Islam, 33 (2007), pp. 219 34.

Amitai Preiss, Reuven, 'Aynjalut revisited', Tarih, 2 (1992), pp. 119 50.

Mongols and Mamluks: The Mamluk Ilkhanid war, 1260 1281, Cambridge, 1995.

Aubin, Jean, 'Le temoignage d'Ebn e Bazzaz sur la turquisation de l'Azerbaydjan', in C. H.

de Fouchecour and Ph. Gignoux (eds.), Etudes Irano Aryennes offertes a Gilbert hazard,

Paris, 1989, pp. 517.

Ayalon, David, Gunpowder and firearms in the Mamluk kingdom: A challenge to a mediaeval

society, London, 1956.

'The Wafidiyya in the Mamluk kingdom', Islamic Culture (1951), pp. 89 104 (reprinted in

D. Ayalon, Studies on the Mamluks of Egypt (1255 1517), London, 1977, art. II).

'The Mamluks of the Seljuks: Islam's military might at the crossroads', fournal of the Royal

Asiatic Society, 3rd ser., 6 (1996), pp. 305 33.

Barthold, W., Turkestan down to the Mongol invasion, 3rd edn, London, 1968.

Biran, Michal, 'The battle of Herat (1270): A case of inter Mongol warfare', in Nicola Di

Cosmo (ed.), Warfare in Inner Asian history (po 1S00), Leiden, 2002, pp. 175 219.

Bosworth, C. Edward, 'The political and dynastic history of the Iranian world', in

JohnA. Boyle (ed.), The Cambridge history of Iran, vol. V, Cambridge, 1968, pp. 1 202.

The Ghaznavids: Their empire in Afghanistan and eastern Iran 994 1040, 2nd edn, Beirut,

1973-

'Recruitment, muster, review in medieval Islamic armies', in Vernon J. Parry and

Malcolm E. Yapp (eds.), War, technology and society in the Middle East, London, 1975,

PP- 159 77-

Buell, PaulD., 'Kalmyk Tanggaci people: Thoughts on the mechanics and impact of

Mongol expansion', Mongolian Studies, 9 (1980), pp. 41 59. Cahen, Claude, 'L'evolution de l'iqta' du IX e au XIH e siecle: Contribution a une histoire

comparee des societes medievales', in C. Cahen, Les peuples musulmans dans Vhistoire

medievale, Damascus, 1977, pp. 231 69 (originally published in Annales: Economies.

Societes, Civilisations, 8 (1953), pp. 25 52). Pre Ottoman Turkey, trans. J. Jones Williams, London, 1968. Doerfer, Gerhard, Turkische und mongolische Elemente im Neupersischen, 4 vols., Wiesbaden,

1963 75-

Frenkel, Yehoshua, 'The Turks of the Eurasian Steppes in medieval Arabic writing', in

Reuven Amitai and Michal Biran (eds.), Mongols, Turks and others: Eurasian nomads and

the sedentary world, Leiden, 2005, pp. 201 41.

672

Cambridge Histories Online © Cambridge University Press, 201 1

# **Bibliography**

Golden, Peter B., An introduction to the history of the Turkic peoples: Ethnogenesis and

state formation in medieval and early modern Eurasia and the Middle East,

Wiesbaden, 1992.

'War and warfare in the pre Cinggisid western steppes of Eurasia', in Nicola Di Cosmo

(ed.), Warfare in Inner Asian history (500 1800), Leiden, 2002, pp. 105

Haarmann, Ulrich, 'Ideology and history, identity and alterity: The Arab image of the Turk

from the 'Abbasids to modern Egypt', International journal of Middle Eastern Studies, 20

(1988), pp. 175 96-

Hsiao Ch'i ch'ing, The military establishment of the Yuan dynasty, Cambridge, MA, 1978.

Kennedy, Hugh, The Prophet and the age of the caliphates: The Islamic Near East from the sixth to

the eleventh century, London, 1986; 2nd edn, 2004.

The armies of the caliphs: Military and society in the early Islamic state, London. 2001.

Khan, Iqtadar Alam, 'The coming of gunpowder to the Islamic world and India: Spotlight

on the role of the Mongols', Journal of Asian History, 30 (1996), pp. 2745.

Khazanov, Anatoly M., Nomads and the outside world, 2nd edn, Madison, WI. 1994.

Lambton, Ann K. S., 'Reflections on the iqta'', in G. Makdisi (ed.), Arabic and Islamic studies

in honor of Hamilton A, R, Gibb, Leiden, 1965, pp. 358 76.

'The internal structure of the Saljuq empire', in John A. Boyle (ed.), The Cambridge history

of Iran, vol. V, Cambridge, 1968, pp. 203 82.

Continuity and change in medieval Persia, New York, 1988.

Lindner, Rudi, Nomads and Ottomans in medieval Anatolia, Bloomington, IN, 1983.

Lockhart, Laurence, 'The Persian army in the Safavid period', Der Islam, 34 (1959),

pp. 89 98.

McDonald, M. V., Al Gahiz and his analysis of the Turks', in Urbain Vermeulen and

J. M. F. van Reeth (eds.), Law, Christianity and modernism in Islamic society, Leuven,

1998, pp. 27 38.

Manz, Beatrice F., 'The ulus Chaghatay before and after Temtir's rise to power: The

transformation from tribal confederation to army of conquest', Central Asiatic

Journal, 27 (1983), pp. 79 100.

The rise and rule of Tamerlane, Cambridge, 1989.

'Military manpower in late Mongol and Timurid Iran', in Maria Szuppe (ed.), 'L'heritage

timouride: Iran Asie centrale Inde XV e XVIIIe siecle, published as Cahiers d'Asie

Centrale, 3 4 (1997), PP- 43 55-

'Nomad and settled in the Timurid military', in Reuven Amitai and Michal Biran,

Mongols, Turks and others, Leiden, 2005, pp. 425 57. Martin, Henry D., The rise cfChingis Khan and his conquest of north China, repr. New York,

1971, of Baltimore, 1950.

Martinez, ArsenioP., 'Some notes on the 11 Xanid army', Archivum Eurasiae Medii Aeivi,

6 (1986), pp. 129 242.

May, Timothy, 'The training of an Inner Asian nomad army in the pre modern period',

Journal of Military History, 70 (2006), pp. 617 35.

Minorsky, Vladimir, 'A soyurgal of Qasim b. Jahangir Aq qoyunlu (903 / 1498)', Bulletin of the

School of Oriental and African Studies, 9 (1939), pp. 927 60. 'A civil and military review in Fars in 881 / 1476', Bulletin of the School of Oriental and African

Studies, 10 (1940 2), pp. 141 78.

Morgan, David O., 'The Mongol armies in Persia', Der Islam, 56 (1979), pp. 81 96.

673

Cambridge Histories Online © Cambridge University Press, 201 1

# **Bibliography**

'The Mongols in Syria, 1260 1300', in Peter W. Edbury (ed.), Crusade and settlement,

Cardiff, 1985, pp. 229 35.

Medieval Persia, 1040 1797, London, 1988.

The Mongols, 2nd edn, Oxford, 2007.

Ostrowski, Donald, 'The tamma and the dual administrative structure of the Mongol

empire', Bulletin of the School of Oriental and African Studies, 61 (1998), pp. 262 77.

Paul, Jiirgen, 'The state and the military: The Samanid case', Papers on Inner Asia, 26,

Bloomington, IN, 1994.

Petrushevsky, I. P., 'The socio economic condition of Iran under the 11 Khans', in

John A. Boyle (ed.), The Cambridge history of Iran, vol. V, Cambridge, 1968, pp. 483 537.

Reid, Robert W., 'Mongolian weaponry in The secret history of the Mongols', Mongolian

Studies, 15 (1992), pp. 85 96.

Roemer, HansR., 'Timur in Iran', in Peter Jackson and Laurence Lockhart (eds.), The

Cambridge history of Iran, vol. VI: The Timurid and Safavid periods, Cambridge, 1986,

pp. 42 97.

Sinor, Denis, 'The Inner Asian warriors', Journal of the American Oriental Society, 101 (1981),

pp. 133 44-

Smith, John M., Jr, 'Mongol manpower and Persian population', Journal of the Economic and

Social History of the Orient, 18 (1975), pp. 271 99.

'Ayn Jalut: Mamluk success or Mongol failure', Harvard Journal of Asiatic Studies,

44 (1984), pp. 307 45-

'Nomads on ponies vs. slaves on horses', Journal of the American Oriental Society,

118 (1998), pp. 154 62.

'Htilegii moves west: High living and heartbreak on the road to Baghdad', in

Linda Komaroff (ed.), Beyond the legacy of Genghis Khan, Leiden, 2006, pp. in 34.

Spuler, Bertold, Die Mongolen in Iran: Politik, VerwaUung und Kultur der Ilchanzeit 1220 1350,

4th edn, Leiden, 1985.

Swietoslawski, Witold, Arms and armour of the nomads of the great steppe in the times of the

Mongol expansion, Lodz, 1999.

Turnbull, Stephan R., The Mongols, Men at Arms Series, 105, London, 1980.

de la Vaissiere, Etienne, 'Chakars d'Asie centrale: A propos d'ouvrages recents'. Studia

Iranica, 34 (2005), pp. 139 49.

Walker, C. T. Harley, Jahiz of Basra to al Fath ibn Khaqan on the "Exploits of the Turks"

and the army of the khalifate in general', Journal of the Royal Asiatic Society (1915),

pp. 631 97-

Woods, John E., The Aqquyunlu: Clan, confederation, empire, 2nd edn, Salt Lake City, 1999.

17 Commercial structures

Scott C. Levi

Practical suggestions for further reading

Alam, Muzaffar, 'Trade, state policy and regional change: Aspects of Mughal Uzbek

commercial relations, c.  $1500\ 1750^{\circ}$  , Journal of the Economic and Social History of the

Orient, 37, 3 (1994), pp. 202 27.

Allsen, Thomas T., Commodity and exchange in the Mongol empire: A cultural history of Islamic

textiles, Cambridge, 1997.

674

Cambridge Histories Online © Cambridge University Press, 201 1

### Bibliography

Blanchard, Ian, Russia's 'age of silver': Precious metal production and economic growth in the

eighteenth century, London, 1989.

Burton, Audrey, The Bukharans: A dynastic, diplomatic and commercial history, 1550 1702,

New York, 1997.

Calmard, Jean, 'Les marchands iraniens: Formation et montee d'un groupe de pression,

i6e i9e siecles', in Denys Lombard and Jean Aubin (eds.), Marchands et hommes

d'affaires asiatiqu.es, Paris, 1988, pp. 91 107.

Chaudhuri, K. N. , Trade and civilisation in the Indian Ocean: An economic history from the rise of

Islam to 1750, Cambridge, 1985.

Chaudhury, Sushil and Morineau, Michel (eds.), Merchants, companies and trade: Europe and

Asia in the early modern era, Cambridge, 1999.

Dale, Stephen, Indian merchants and Eurasian trade, 1600 1800, Cambridge, 1994.

Das Gupta, Ashin, The world of the Indian Ocean merchant, you 1800, New Delhi, 2001.

Ferrier, R. W., 'The Armenians and the East India Company in Persia in the seventeenth

and early eighteenth centuries', The Economic History Review 2nd ser., 26, 1 (1973),

pp. 38 62.

Floor, Willem, The economy of Safavid Persia, Wiesbaden, 2000.

Frank, Andre Gunder, Reorient: Global economy in the Asian age, Berkeley, 1998.

Gommans, Jos, The rise of the Indo Afghan empire, c.iyio 1780, Leiden, 1995.

Jackson, Peter, The Delhi sultanate: A political and military history, Cambridge, 1999.

Levi, Scott C, 'India, Russia and the eighteenth century transformation of the Central

Asian caravan trade', Journal of the Social and Economic History of the Orient, 42, 4 (1999),

pp. 519 48.

The Indian diaspora in Central Asia and its trade, yyo 1900, Leiden, 2000.

(ed.), India and Central Asia: Commerce and culture, 1500 1800, New Delhi, 2007.

McCabe, Ina Baghdiantz, The shah's silk for Europe's silver: The Eurasian trade of the Julfa

Armenians in Safavid Iran and India (1530 17J0J, Atlanta, 1999. McChesney, R. D., Central Asia: Foundations of change, Princeton, 1996. Markovits, Claude, The global world of Indian merchants, 17JO 1947: Traders of Sind from

Bukhara to Panama, Cambridge, 2000.

'Indian merchants in Central Asia: The debate', in Scott C. Levi (ed.), India and Central

Asia: Commerce and culture, 1500 1800, New Delhi, 2007, pp. 123 51. Matthee, Rudolf, The politics of trade in Safavid Iran: Silk for silver, 1600 1730, Cambridge,

1999.

Pearson, Michael, The Indian Ocean, London, 2003.

Prakash, Om., European commercial enterprise in pre colonial India, Cambridge, 1998.

Bullion for goods: European and Indian merchants in the Indian Ocean trade, 1500 1800, New

Delhi, 2004.

Raychaudhuri, Tapan and Habib, Irfan (eds.), The Cambridge economic history of India, vol. 1:

c.1200 c.iyyo, repr. Hyderabad, 1984.

Richards, John, The Mughal empire, Cambridge, 1993.

Steensgaard, Niels, The Asian trade revolution of the seventeenth century: The East India

Companies and the decline of the caravan trade, Chicago, 1974. Subrahmanyam, Sanjay and Bayly, C. A., 'Portfolio capitalists and the political economy of

early modern India', The Indian Economic and Social History Review, 25, 4 (1988),

pp. 401 24.

675

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Tracy, James D. (ed.), The rise of merchant empires: Long distance trade in the early modern

world, lyo 17/0, Cambridge, 1990.

(ed.), The political economy of merchant empires: State power and world trade, 1350 1750,

Cambridge, 1991.

Tripathi, Dwijendra (ed.), Business communities of India: A historical perspective, New Delhi,

1984.

Wink, Andre, Al Hind: The making of the Indo Islamic world, vol. II, The slave kings and the

Islamic conquest of India, nth 13th centuries, Leiden, 1997; vol. Ill: Indo Islamic society,

14th 15th centuries, Leiden, 2004.

Primary sources

Abul Fazl Allami, The Akbar Nama of Abu I Fazl, 3 vols., trans. H. Blochmann, repr. Delhi,

1998.

Bernier, Francois, Travels in the Mogul empire, AD 1656 1668, Westminster, 1891.

Chardin, John, Sir John Chardin's travels in Persia, London, 1927. Gonzalez, Ruy, Narrative of the embassy of Ruy Gonzalez de Clavijo to the court of Timour in

Samarcand, AD 1403 6, trans. Clements R. Markham, London, 1858. Ibn Battuta, The Travels oflbn Battuta, AD 1325 1354, trans. H. A. R. Gibb, 3 vols., New Delhi,

1993-

Jenkinson, Anthony, Early voyages and travels to Russia and Persia ..., ed. E. Delmar Morgan

and C. H. Coote, Hakluyt Society, 2 vols., 1st ser., 72 3, London, 1886. du Mans, Raphael, Estat de la Perse en 1660, Paris, 1890. Manucci, Niccolao, Storia do Mogor, or Mogul India 1653 1708, 4 vols., trans. W. Irvine,

London, 1907 8.

de Modave, Comte, Voyage en Inde du Comte de Modave, 1773 1776, ed. J. Deloche, Paris, 1971.

Navoiy, Alisher, Mahbub al qulub, ed. A. N. Kononov, Moscow, 1948. Nikitin, Afanasi (Athanasius), The travels of Athanasius Nikitin of Twer, in R. H. Major (ed.),

India in the fifteenth century, Hakluyt Society, 1st ser., 22, part 3, London, 1857.

Pelsaert, Francisco, A Dutch chronicle of Mughal India, ed. and trans. Brij Narain and

Sri Ram Sharma, Lahore, 1978.

Polo, Marco, The book of Ser Marco Polo, 2 vols., ed. and trans. Sir Henry Yule, New York, 1903.

Sen, Surendranath (ed.), Indian travels of Thevenot and Careri, New Delhi, 1949.

Tarikh i Firishta, Lucknow, 1864.

Tavernier, Jean Baptiste, Les six voyages dejean Baptiste Tavernier, Ecuyer Baron d'Aubonne ...,

2 vols., Utrecht, 1712. al 'Utbi, Tarikh al Yamvm, Delhi, 1847. 18 Transmitters of authority and ideas across cultural

boundaries, eleventh to eighteenth centuries

Muhammad Qasim Zaman

Practical suggestions for further reading

Alam, Muzaffar, The languages of political Islam: India, 1200 1800, Chicago, 2004.

Alam, Muzaffar and Subrahmanyam, Sanjay, Indo Persian travels in the age of discoveries,

1400 1800, Cambridge, 2007.

676

Cambridge Histories Online © Cambridge University Press, 201 1

# **Bibliography**

Arjomand, Said Amir, 'The law, agency, and policy in medieval Islamic society:

Development of the institutions of learning from the tenth to the fifteenth century',

Comparative Studies in Society and History, 41 (1999), pp. 263-93. Azra, Azyumardi, The origins of Islamic reformism in Southeast Asia: Networks of Malay Indonesian

and Middle Eastern 'ulamd in the seventeenth and eighteenth centuries, Honolulu. 2004.

Ben Dor Benite, Zvi, The Dao of Muhammad: A cultural history of Muslims in late imperial

China, Cambridge, MA, 2005.

Dallal, Ahmad, 'The origins and objectives of Islamic revivalist thought, 1750 1850', Journal

of the American Oriental Society, 113, 3 (1993), pp. 341 59. Dunn, Ross E., The adventures oflbn Battuta: A Muslim traveler of the 14th century, Berkeley,

1986, 2nd edn, 2005.

Ho, Engseng, The graves of Tarim: Genealogy and mobility across the Indian Ocean, Berkeley, 2006.

Johansen, Baber, Contingency in a sacred law: Legal and ethical norms in the Muslim fiqh,

Leiden, 1999.

Rosenthal, Franz, The technique and approach of Muslim scholarship, Rome, 1947.

Primary sources

Abd al Haqq Dihlawi, Lama' at al tanqihfi sharh Mishkat al masabih, ed. M. 'Ubayd Allah, 4

vols., Lahore, 1970.

Ashi"at al lama'at, 4 vols., Sukkar, Pakistan, 1976.

Abd al Qadir al 'Aydarus, al Nur al safir 'an akhbar al qarn al 'ashir, ed. A. Halu,

M. al Arna'ud and A. al Bushi, Beirut, 2001.

Ali al Muttaqi, 'Ala' al din, Kanz al 'ummalfi sunan al aqwal wa'l afal, 18 vols., Aleppo, 1969.

Muntakhab Kanz al 'ummal, 8 vols., Beirut, 1990.

'All b. Sultan al Qan, Mirqat al mafatih sharh Mishkat al mafatih, ed. S. M.J. al Attar, 10 vols.,

Beirut, 1992.

Baram, Diya' al din, Td'rikh i Firuzshahi, ed. Sayyid Ahmad Khan, Calcutta, 1862.

Bilgrami, Ghulam 'All Azad, Mahathir al kiram, ed. Muhammad 'Abduh Lyallpun, Lahore,

1971.

al Bukhan, Mahmudb. Ahmad b. 'Abd al Aziz, al Muhit al Burhamfi'lfiqh al Nu'mam, ed.

A. A. 'Inaya, 11 vols., Beirut, 2003.

al Fatawa al Hindiyyafi madhhab al imam al a'zam Abi Hamfa al Nu'man, 6 vols., Beirut, n.d.

((1973); repr. of the Bulaq edn, AH 1310).

Hajji Khalifa, Kashf al zunun, ed. §. Yaltkaya and R. Bilge, 2 vols., Istanbul, 1972.

Hazm Lahiji, Muhammad 'Ah, Ta'rikh wa safarnama i Hazm, ed. A. Dawwam, n.p., AH

solar 1375, trans. F. C. Belfour, The life of Sheikh Mohammad Ali Hazin, written by himself,

London, 1830.

Ibn Battuta, Voyages d'Ibn Batoutah, ed. C. Defremery and B. R. Sanguinetti, 2nd edn, 4 vols.,

Paris, 1877 9. trans. H.A. R. Gibb, The travels oflbn Battuta, AD 1325 1354, 5 vols.,

Cambridge, 1958 2000.

Ibn al Humam, Sharh fath al qadvr, 10 vols., Cairo, 1970. Ibn Nujaym, RasaHl Ibn Nujaym al iqtisadiyya, al musammat al RasaHl al Zayniyyafi madhhab

al Hanafiyya, ed. M. A. Siraj and 'A.J. Muhammad, Beirut, 1998. Jahangir, The Jahangirnama: Memoirs of Jahangir, emperor of India, ed. and trans. Wheeler

M. Thackston, New York, 1999.

677

Cambridge Histories Online © Cambridge University Press, 201 1

# Bibliography

Kitab al hawadith, ed. B. 'A. Ma'ruf and 'I. Abd al Salam, Beirut, 1997.

al Muhibbi, Muhammad Amm, Khulasat al atharji a'yan al qarn al hadx 'ashar, Beirut, n.d.

Musta'idd Khan, Saqi, Ma'athir i 'Alamgin, ed. A. A. Ah, Osnabriick, 1985 (repr. of the

Calcutta 1870 3 edn).

al Saghani, Radi al dm al Hasan b. Muhammad, Mashariq al anwar, Constantinople, AH

1329.

al Suyuti, Jalal al dm, Jami' al ahadith, ed. A. A. Saqr and A. 'Abd al Jawwad, 21 vols., Beirut,

1994.

Wall Allah al Dihlawi, Risala shark abwab sahih al Bukhan, 3rd edn, Haydarabad, 1949.

Hujjat Allah al baligha, ed. S. Sabiq, 2 vols., Cairo, 1964. Partial trans, by Marcia K. Hermansen, The conclusive argument from God, Leiden, 1996. 'Iqd aljidfi ahkam al ijtihad wa'l taqhd, Cairo, AH 1385.

Musawwa Musaffa, sharh MuwattcC imam Malik, 2 vols., Karachi, n.d. (repr. of the Delhi

AH 1346 edn).

'Risala i danishmandi'. Published together with Shah Rafi' al dm, Takmil al adhhan, ed.

'Abd al Hamid al Sawati, Gujaranwala, n.d.

Secondary sources

Abd al Hayy al Hasani, Al Thagafa al Islamiyya fi'l Hind, Damascus, 1958.

Abd al Hayy al Laknawi, Muhammad, Al FawaHd al bahiyya fi tarajim al Hanafiyya,

Karachi, AH 1393.

Ahmad, Aziz, Studies in Islamic culture in the Indian environment, Oxford, 1964.

Ahmed, Shahab and Filipovic, Nenad, 'The sultan's syllabus: A curriculum for the Ottoman

imperial medreses prescribed in aferman of Qanum I Siileyman, dated 973 (1565)', Studia

Islamica, 98 9 (2004), pp. 183 218.

Berkey, Jonathan P., The transmission of learning in medieval Cairo, Princeton, 1992.

Bilgrami, RafatM., Religious and quasi religious departments of the Mughal period (1556 1707),

Delhi, 1984.

Brentjes, Sonja, 'On the location of the ancient or "rational" sciences in Muslim educational

landscapes (AH 500 1100)', Bulletin of the Royal Institute for Inter Faith Studies, 4 (2002),

pp. 47 71.

Brown, Jonathan, The canonization of al Bukhan and Muslim: The formation of the Sunni hadith

canon, Leiden, 2007.

Bulliet, Richard W., Islam: The view from the edge, New York, 1994.

Chamberlain, Michael, Knowledge and practice in medieval Damascus, 1190 lyo, Cambridge,

1994.

El Rouayheb, Khaled, 'Opening the gate of verification: The forgotten Arab Islamic flor

escence of the 17th century', International Journal of Middle East Studies, 38 (2006),

pp. 263 81.

Ephrat, Daphna, A learned society in a period of transition: The Sunni 'ulama' of eleventh century

Baghdad, Albany, 2000.

Fadel, Mohammad, 'The social logic of taqlid and the rise of the Mukhtasar', Islamic Law

and Society, 3 (1996), pp. 193 233.

Gardet, Louis, 'Religion and culture', in P. M. Holt, Ann K. S. Lambton and B. Lewis (eds.),

The Cambridge history of Islam, 2 vols., Cambridge, 1970, vol. II, pp. 569 603.

678

Cambridge Histories Online © Cambridge University Press, 201 1

## **Bibliography**

Gleave, Robert, Inevitable doubt: Two theories of Shi'i jurisprudence, Leiden, 2000.

Goldziher, Ignaz, Muslim studies, trans. C. R. Barber and S. M. Stern, 2 vols., London, 1971.

Griffel, Frank, 'On Fakhr al Dm al Razi's life and the patronage he received', Journal of

Islamic Studies, 18 (2007), pp. 313 44.

Hallaq, WaelB., Authority, continuity and change in Islamic law, Cambridge, 2001.

Ihsanoglu, Ekmeleddin, Science, technology and learning in the Ottoman empire, Aldershot,

2004.

Ito, Takeshi, 'Why did Nuruddin ar Raniri leave Aceh in 1054 AH?', Bijdragen tot de Taal,

Land en Volkenkunde, 134, 4 (1978), pp. 489 91. Jackson, Sherman, Islamic law and the state: The constitutional jurisprudence of Shihab al Din al

Qarafi, Leiden, 1996.

Kohlberg, Etan, Aspects of Akhbari thought in the seventeenth and eighteenth centuries',

in Nehemia Levtzion and John O. Voll (eds.), Eighteenth century renewal and reform in

Islam, Syracuse, 1987, pp. 133 60.

Kozlowski, Gregory C, 'Imperial authority, benefactions and endowments (awqafi in

Mughal India', Journal of the Economic and Social History of the Orient, 38 (1995),

PP-35570.

Kugle, Scott, 'In search of the center: Authenticity, reform and critique in early modern

Islamic sainthood', Ph.D. dissertation, Duke University, 2000. ''Abd al Haqq Dihlawi, an accidental revivalist: Knowledge and power in the passage

from Delhi to Makka', Journal of Islamic Studies, 19 (2008), pp. 196 246. Kumar, Sunil, The emergence of the Delhi sultanate, Delhi, 2007. Landau Tasseron, Ella, 'The "cyclical" reform: A study of the mujaddid tradition', Studia

Islamica, 70 (1989), pp. 79 117.

Levtzion, Nehemia and Voll, John O. (eds.), Eighteenth century renewal and reform in Islam,

Syracuse, 1987.

Makdisi, George, The rise of colleges, Edinburgh, 1981.

Morgan, D. O., Tbn Battuta and the Mongols', Journal of the Royal Asiatic Society, 3rd ser., 11

(2001), pp. 111.

Mottahedeh, Roy, 'The transmission of learning: The role of the Islamic northeast', in

Nicole Grandin and Marc Gaborieau, (eds.), Madrasa: La transmission du savoir dans le

monde musulman, Paris, 1997, pp. 63 72.

Nadwi, Abu'l Hasanat, Hindustan ki qadim Islamx darsgahen, A'zamgarh, 1971.

Nizami, Khaliq Ahmad, Some aspects of religion and politics in India during the thirteenth

century, Bombay, 1961.

Petry, Carl F., 'Travel patterns of medieval notables in the Near East', Studia Islamica,

63 (1985), PP- 53 87.

Rahman, Fazlur, Islam and modernity: Transformation of an intellectual tradition, Chicago,

1982.

Reichmuth, Stefan, 'Murtada az Zabidi (d. 1791) in biographical and autobiographical

accounts', Die Welt des Islams, 39 (1999), pp. 64 102. Siddiqui, Iqtidar Husain, 'Muslim intellectual life in India', in (ed.), Iqtidar Husain Siddiqui,

Medieval India: Essays in intellectual thought and culture, Delhi, 2003, vol. I, pp. 81 94.

Stewart, Devin, 'The doctorate of Islamic law in Mamluk Egypt and Syria', in J. E. Lowry,

D.J. Stewart and S. M. Toorawa, (eds.), Law and education in medieval Islam: Studies in

memory of Professor George Makdisi, Chippenham, 2004, pp. 45 90.

679

Cambridge Histories Online © Cambridge University Press, 201 1

Bibliography

Subrahmanyam, Sanjay, 'Iranians abroad: Intra Asian elite migration and early modern

state formation', Journal of Asian Studies, 51, 2 (1992), pp. 340 63. Subtelny, Maria Eva and Khalidov, Anas B., 'The curriculum of Islamic higher learning in

Timurid Iran in the light of the Sunni revival under Shah Rukh', Journal of the American

Oriental Society, 115 (1995), pp. 210 36.

Voll, John O., 'Hadith scholars and tariqahs: An ulama group in the 18th century Haramayn

and their impact in the Islamic world', Journal of Asian and African Studies, 25 (1980),

pp. 264 73-

'Abdallah ibn Salim al Basri and 18th century hadith scholarship', Die Welt des Islams,

42 (2002), pp. 356 72.

Wensinck, A. J., Concordance et indices de la tradition musulman, 8 vols., 2nd edn, Leiden,

1992.

Zaman, Muhammad Qasim, The ulama in contemporary Islam: Custodians of change,

Princeton, 2002.

680

Cambridge Histories Online © Cambridge University Press, 201 1

.